



Portsmouth, NH City Council

Eileen Dondero Foley Council Chambers

City Hall Complex, 1 Junkins Avenue, Portsmouth, NH

Monday, October 26, 2026, at 7:00 pm

Register to participate via Zoom. A unique meeting ID and password are provided once you register. To register, click on the link below or copy and paste into your web browser:

https://us06web.zoom.us/webinar/register/WN_PMKWVXCQRfqkPUkFODC6Uw

Anticipated Non-Public Session

5:30 pm – Anticipated Non-Public Session is being held in Conference Room A in accordance with RSA 91-A:3, II (a), (d), (l) and (m)

Agenda

- | | Page |
|--|------|
| 1. Rolling Stock Work Session 6:00 pm | |
| 2. Public Dialogue Session (when applicable) | |
| 3. Call to Order (7:00 pm or thereafter) | |
| 4. Roll Call | |
| 5. Invocation | |
| 6. Pledge of Allegiance | |
| 7. Acceptance of Minutes | |
| A. Minutes and Actions of the October 13, 2026, City Council meeting | 6 |
| DRAFT City Council minutes and actions of October 13, 2026.pdf  | |
| <i>(Sample motion - move to accept and approve the minutes of the October 13, 2026, City Council meeting)</i> | |
| 8. Recognitions and Volunteer Committee Reports | |
| A. Proclamation | 16 |
| • Domestic Violence Awareness Month | |
| Proclamation Domestic Violence Awareness.pdf  | |

9. Public Comment Session

This session shall not exceed 45 minutes; participation may be in person or via Zoom

10. Public Hearings and Vote On Ordinances and/or Resolutions

- A. Third and Final Reading to Amend Chapter 10, Zoning Ordinance, which will remove most parking regulations from the Zoning Ordinance to the Site Plan Review Regulations (except one and two-family dwellings) 17

[Third Reading Ordinance Removing Parking Chapter 10 Art 2.pdf](#) 

[SitePlanReviewRegs_09172026.pdf](#) 

(Sample motion - move to pass third and final reading as presented)

- B. Adoption of Resolution #15-2026 authorizing a Bond Issue and/or Notes of the City under the Municiple Finance Act of up to Six Hundred Thousand Dollars (\$600,000) for costs related to the purchase of fire apparatus 116

[Legal Notice Resolution 15-2026 Fire Apparatus.pdf](#) 

(Sample motion - move to adopt Resolution #15-2026 as presented)

11. City Manager's Items Which Require Action 121

[CM Report 10_26_2026.pdf](#) 

- A. *Request for Solid Waste Ordinance Work Session
(Sample motion - move to schedule a Solid Waste Ordinance Work Session on December 7, 2026, at 6:00 pm to allow staff to provide additional details on solid waste collection challenges and receive City Council and public input)

- B. Request for First Reading on Sewer Ordinance 129

[CM Action Item Regarding Sewer Ordinance First Reading.pdf](#) 

(Sample motion - move to schedule first reading on November 16, 2026, regarding an amendment to the Sewer Use Ordinance which will delete in its entirety the existing ordinance in Chapter 11, Article II, and replace it with a new ordinance in Chapter 16, Utilities, Article III, Sewers)

- C. Friends of Lafayette House PILOT Agreement for FY2027 190

[CM Action Item Regarding Friends of Lafayette House PILOT Agreement.pdf](#) 

(Sample motion - move to authorize the City Manager to enter into a PILOT Agreement with Friends of Lafayette House in the amount of \$3,500 for FY2027)

- D. Betty's Dream Foundation PILOT Agreement for FY2027 195

[CM Action Item Regarding Bettys Dream Foundation PILOT Agreement.pdf](#) 

(Sample motion - move to authorize the City Manager to enter into a PILOT Agreement with Betty's Dream Foundation in the amount of \$3,000 for FY2027)

- E. Planning Board Recommendation Regarding Licenses and a Sidewalk Easement for 361 Hanover Street 200

[CM Action Item Regarding 361 Hanover Street Easements.pdf](#) 

(Sample motion - move to authorize the City Manager to accept and record a Sidewalk Easement, a Landscape License, and a Pole License from 361 Hanover Steam Factory, LLC for 361 Hanover Street in a form acceptable to the City Attorney, subject to the recommendations in the enclosed memorandum from Assistant Planning Director Stith)

- F. Memorandum of Agreement - Portsmouth Professional Fire Officers Association, 203
Local #4039

[CM Action Item Regarding Fire Officers MOA.pdf](#) 

(Sample motion - move to approve the Memorandum of Agreement with the Portsmouth Professional Fire Officers Association, Local #4039 as presented)

- G. Planning Board Recommendation on Cornwall Street 204

[CM Action Item Regarding Cornwall Street.pdf](#) 

(Sample motion - move to schedule a public hearing on the discontinuance of the identified portion of Cornwall Street at the November 16, 2026, City Council Meeting)

- H. Planning Board Recommendation on Taft Road 233

[CM Action Item Regarding Taft Road.pdf](#) 

(Sample motion - move to approve the discontinuance of the identified portion of Taft Road, subject to the recording of a Municipal Utility Easement over the existing water line in a form acceptable to the City Attorney)

- I. Planning Board Recommendation on 0 Elm Street 236

[CM Action Item Regarding 0 Elm Street.pdf](#) 

(Sample motion - move to authorize the issuance of a building permit for 0 Elm Street contingent on the applicant obtaining all other required variances, approvals, and permits, and on construction of a driveway adequate for emergency vehicle access as approved by the Department of Public Works and the Fire Department; this authorization confers no private right of access over Forrest Street or any other private property)

Or

(Sample motion - move to deny the request on the ground that the lot has no frontage and does not abut any constructed private road or other street)

- J. Sidewalk Easement for Property Located at 48-50 Langdon Street 251

[CM Action Item Regarding Langdon Street.pdf](#) 

(Sample motion - move to authorize the City Manager to accept and record a Sidewalk Easement Deed from Martin Husslage)

12. Consent Agenda

Consent Action - No items for this meeting

13. Presentations and Written Communications

- A. Email Correspondence 252
[Email Correspondence Packet 10.26.26.pdf](#) 
[Email Appendix 10.26.26.pdf](#) 

(Sample motion - move to accept and place on file)

14. Mayor McEachern

- A. Appointments to be Considered 274
• Peter Weeks reappointment to the Trustees of the Trust Funds
[Peter Weeks - Trustees Reappointment.pdf](#) 
- B. Appointments to be Voted
• Zachary (Zach) Dombrowski to full member to the Economic Development Commission
• Matthew Jeffers to alternate member to the Economic Development Commission

(Sample motion - move to appoint as presented)

15. City Council Members

- A. Councilor Bagley
Sealed Minutes of the Monday, September 28, 2026, Non-public Session
(Sample motion - move to release the sealed minutes of the Monday, September 28, 2026, non-public session, held under RSA 91-A:3 II(l) as the circumstances warranting their sealing no longer apply)
- B. Councilor Hopkins 275
• Parking & Traffic Safety Committee Action Sheet and Minutes of the October 1, 2026 meeting
[PTS Action Sheet FINAL 10.01.26 CC.pdf](#) 
[10.01.26 PTS Minutes - CC.pdf](#) 

(Sample motion - move to approve and accept the action sheet and minutes of the October 1, 2026, Parking & Traffic Safety Committee Meeting)

16. Approval of Grants/Donations

- A. Point of Graves Cemetery Donations 279
[Donation Point of Graves Packet.pdf](#) 
(Sample motion - move to accept with thanks donations for the Point of Graves Cemetery Wall Replacement from an anonymous resident, Charles & Barbara Bickford, and Michael Pennington, in the amounts as presented in the attached Gift and Donation Submission Forms)
- B. FY26 Byrne Discretionary Community Projects Grant in the amount of \$1,000,000 282
from the Office of Justice Programs to fund NH Internet Crimes Against Children Task Force's COPS and Enhanced Capacity Program
[FY26 Byrne Discretionary Community Projects Grant.pdf](#) 

(Sample motion - move to accept the FY26 Byrne Discretionary Community Projects Grant in the amount of \$1,000,000 and its terms and conditions from the Office of Justice Programs to fund NH Internet Crimes Against Children Task Force's COPS and Enhanced Capacity Program)

- C. FY26 COPS Technology and Equipment Program Grant in the amount of 300
\$1,031,000, from the Office of Community Oriented Policing Service for the
Portsmouth Police Department

[FY26 COPS Technology and Equipment Program Grant.pdf](#) 

(Sample motion - move to accept the FY26 COPS Technology and Equipment Program Grant in the amount of \$1,031,000 and its terms and conditions from the Office of Community Oriented Policing Service for the Portsmouth Police Department)

17. City Manager's Informational Items

- A. Annual Food and Liquor Permit Renewals 318

[CM Info Item Regarding Food and Liquor Permits.pdf](#) 

- B. *Pease Development Authority Board Meeting Update

- C. Resident Access Parking Program (RAPP) Q1 Report Back 320

[CM Info Item Regarding RAPP Quarterly Check in October 26 2026.pdf](#) 

- D. *Off-Peak/Workweek Parking for Downtown Businesses Report Back

- E. *General Fund Revenues Update

- F. *Offsite Water and Sewer Improvements - Borthwick Avenue and Sherburne Property

- G. *Mechanic Street Pump Station 2nd Public Meeting - November 9, 2026, in Council
Chambers at 6:30 pm

18. Miscellaneous Business Including Business Remaining Unfinished At Previous Meeting

19. Adjournment (At 10:30 pm or earlier)

*Indicates verbal report with no attachments

Sally A. Kellar
City Clerk



Portsmouth, NH City Council Regular Meeting October 13, 2026

Eileen Dondero Foley Council Chambers

Tuesday, October 13, 2026, at 7:00 PM

Minutes

1. Non-Public Session

Assistant Mayor Kelley moved to close non-public session and to seal the meeting minutes. Seconded by Councilor Moreau.

Motion passed unanimously.

2. Work Session (when applicable)

3. Public Dialogue Session (when applicable)

4. Call to Order (7:00 p.m. or thereafter)

Mayor McEachern called the meeting to order at 7:09 p.m.

5. Roll Call

Present: Mayor McEachern, Assistant Mayor Kelley, Councilors Cook, Tabor, Blalock, Bagley, Moreau, Flynn and Hopkins

6. Invocation

7. Pledge of Allegiance

Mayor McEachern led the Pledge of Allegiance.

8. Acceptance of Minutes

A. Minutes and Actions of September 28, 2026, City Council Meeting

Assistant Mayor Kelley moved to accept and approve the minutes of the September 28, 2026, City Council meeting. Seconded by Councilor Cook.

Motion passed unanimously.

9. Recognitions and Volunteer Committee Reports

10. Public Comment Session

There were 5 speakers:

Sue Polidura presented the request of a Paul Revere Plaque to commemorate a midday ride of Paul Revere in Portsmouth during the American Revolution. Funding is not being requested.

Peter Coddington is in support of a Paul Revere Plaque especially as we celebrate the 250th Anniversary of the United States. He would like to see Portsmouth take credit for happenings before Paul Revere's infamous midnight ride. He thanked the Council for their service.

Tony Keating, Newcastle, NH, shared his perspective on the Paul Revere plaque initiative. The request is well documented in the presented proposal. He thanked Mike Geanoulis, Sr. for researching and documenting this historic event.

Tyler Garza, on Zoom, is in support of Agenda Item 15.C, ADU tax exemption

Mike Geanoulis, Sr., Newcastle, NH, spoke about the event the plaque will commemorate. He is donating, as a gift to the Portsmouth Public library, the historical account of this event.

Councilor Moreau moved to take Agenda item 13.B out of order - Letter from Curtis Hermann from the New Hampshire Sons of the American Revolution, Sue Polidura and Michael J. Geanoulis, Sr., Historians, requesting permission to donate and install a new Paul Revere Marker in Market Square. Seconded by Councilor Bagley.

Motion passed unanimously.

Agenda item 13.B taken out of order - Letter from Curtis Hermann from the New Hampshire Sons of the American Revolution, Sue Polidura and Michael J. Geanoulis, Sr., Historians, requesting permission to donate and install a new Paul Revere Marker in Market Square.

Councilor Bagley commented on Portsmouth's involvement in the American Revolution and thanked those involved in this proposal.

Councilors Cook and Blalock echoed Councilor Bagley's comments and shared their favorite American Revolution stories.

Mayor McEachern also supports the placement of this plaque and the importance of documenting Portsmouth history throughout the city.

Sue Polidura asked for permission to share Mr. Geanoulis 's poem, "Shots Not Heard Round the World", about this event, and asked if Mr. Geanoulis could read his poem aloud.

Councilor Tabor moved to refer to the City Manager with authority to act. Seconded by Councilor Moreau.

Motion passed unanimously

Councilor Bagley moved to suspend the rules and allow Michael Geanoulis, Sr. to read his poem aloud. Seconded by Councilor Moreau.

Motion passed unanimously.

[Shots Not Heard Round the World.pdf](#) 

Assistant Mayor Kelley moved to suspend the rules and bring Agenda item 15.A out of order - Municipal Building Blue Ribbon Committee Recommendation. Seconded by Councilor Moreau.

Motion passed unanimously.

Agenda Item 15.A taken out of order - Councilors Cook and Tabor

- Municipal Building Blue Ribbon Committee Recommendation

Councilor Bagley feels this is a solid municipal building plan and he supports it. It is a phased project. All the bonding will not be done all at once.

Councilor Cook was originally skeptical about this plan because she thought the scope was too large, and the cost was too great. Overtime she learned the committee worked hard to limit the scope, so what is needed gets done. She explained that the money would come from the existing CIP budget.

Councilor Tabor commented that this project will last many years and serve the City well. He believes this project can be done as efficiently as possible without having to look at a new location to meet the needs of the Police Department. He feels this is a tremendous value for the money. City Hall will be rehabilitated and enhanced in a better way to serve the public. He is in support of this project.

Councilor Moreau thanked the building committee for the work that has been done. The space has been used wisely. She is in support of this project.

Councilor Blalock commented that this project has been discussed for over 10 years. He asked what is going to happen to the rock room?

Councilor Cook talked about increasing storage through basement space being added to additions.

Mayor McEachern thanked key players who worked on this project. He also thanked Councilors Tabor, Cook and Bagley for their work serving on this committee. He appreciates the efforts to find savings for this project.

Councilor Bagley also thanked Joe Almeida for his work on this committee and keeping an old building running.

Councilor Cook moved to accept the recommendation of the Municipal Building Blue Ribbon Committee regarding Final Concept C, including the revised third and fourth-floor and HVAC and electrical upgrades, as the preferred design concept for the Municipal Complex Upgrade, consistent with the revised project cost estimate and phasing plan, for a total project cost estimate of \$58.6 million, and update the existing CIP element sheet in the FY28-33 CIP. Seconded by Councilor Tabor.

Motion passed unanimously.**11. Public Hearings and Vote On Ordinances and/or Resolutions**

- A. Public Hearing and Second Reading to amend Chapter 10, Zoning Ordinance, City of Portsmouth Zoning Map, be amended to change to the district boundary of the Historic District

- **PRESENTATION**

Assistant Planning Director, Peter Stith, explained the proposed amendments, the reasons to change the boundary, the proposed boundary, parcels that will be affected, Historic District Amendments and the implementation plan.

- **CITY COUNCIL QUESTIONS**

Councilor Moreau gave some context to the boundary.

Councilor Blalock asked if property owners have been notified. All 74 properties have been notified via certified mail.

- **PUBLIC HEARING SPEAKERS**

Mayor McEachern opened the public hearing.

Brad Landon's questions were explained through the presentation.

Councilor Bagley said his neighbors are in favor of the changed boundary.

Councilor Moreau mentioned other areas will be assessed at a later date.

Councilor Cook explained this ordinance brings Middle Street in line with Historic District Rules. It mirrors what had been done on Islington Street.

Councilor Blalock would like to see the historic district celebrate the historic buildings for Portsmouth.

Mayor McEachern closed the public hearing.

Councilor Tabor moved to pass second reading and schedule a third and final reading as presented for the October 26, 2026, City Council meeting. Seconded by Councilor Blalock.

Motion passed unanimously.

Councilor Moreau moved to suspend the rules and bring forth third and final reading. Seconded by Councilor Blalock.

Motion passed unanimously.

Councilor Moreau moved to pass third and final reading as presented. Seconded by Councilor Cook.

Motion passed unanimously.

- B. Public Hearing and Second Reading amendments to Chapter 10, Zoning Ordinance, which will remove most parking regulations from the Zoning Ordinance to the Site Plan Review Regulation (except one and two-family dwellings)

- **PRESENTATION**

Assistant Planning Director, Peter Stith, explained the proposed zoning amendments regarding parking regulations, a history of parking, changes to site plan review regulations, parking flexibility, changes not being made, and implementation.

- **CITY COUNCIL QUESTIONS**

Councilor Cook asked about the site planning regulations. How does this procedure work? Peter Stith explained that the Planning Board has simplified the process in line with site plan regulations. Councilor Moreau echoed his answer. Councilor Tabor commented on the site review parking standards in the packet. It is much simpler.

Mayor McEachern asked questions about parking and conditional use permits. Will parking be a part of the site plan and come before the Planning Board with every

application? It changes from a conditional use permit to a site plan review through the Planning Board.

Councilor Bagley feels we should be eliminating parking requirements. He feels we are taking a complicated thing and making it more complicated.

Councilor Moreau explained we are making things less complicated by putting it into site plan review.

Councilor Tabor thinks looking at parking requirements over time and putting it as a part of the site plan to be presented in front of the Planning Board is a step in the right direction.

Councilor Cooks feels this is a step in the right direction in order to approve housing.

Mayor McEachern added how this relates to the City's zoning ordinances. He is in support of these amendments.

Councilor Moreau requested redline site plan regulations in the ordinance in advance of third and final reading.

- **PUBLIC HEARING SPEAKERS**

Tyler Garza, on Zoom, is in support of these changes and the efforts to bring this forward.

Mayor McEachern closed the public hearing.

Councilor Moreau moved to pass second reading and schedule third and final reading as presented for the October 26, 2026, City Council meeting. Seconded by Councilor Bagley.

Motion passed unanimously.

12. City Manager's Items Which Require Action

- A. Acceptance of Drainage and Turnaround Easements and Additional Right-of-Way and Approval of McMaster Drive as New Street Name for Property Located at 86 Farm Lane
City Manager Conard explained the background of this request.

Councilor Flynn moved to authorize the City Manager to accept and record the drainage easement, turnaround easement, and conveyance of the additional right-of-way in substantially the same form as the documents contained in the agenda packet and approve McMaster Drive as the name of the new public street. Seconded by Councilor Hopkins.

Motion passed unanimously.

13. Consent Agenda

Consent Action - No items for this meeting

14. Presentations and Written Communications

- A. Request from Attorney John Bosen on behalf of property owners at 107 Ledgewood Drive for a Zoning Map Amendment

Assistant Mayor Kelley moved to refer to the Planning Board for recommendation and report back. Seconded by Councilor Cook.

Motion passed unanimously.

- B. Agenda Item 13.B taken out of order - Letter from Curtis Hermann from the New Hampshire Sons of the American Revolution, Sue Polidura and Michael J. Geanoulis, Sr., Historians, requesting permission to donate and install a new Paul Revere Marker in Market Square
- C. Email Correspondence

Assistant Mayor Kelley moved to accept and place on file. Seconded by Councilor Bagley.

Motion passed unanimously.**15. Mayor McEachern**

- A. Acceptance of Resignation
 - MC (Mary Claire) Rodriguez-Abbot from the Portsmouth Energy Advisory Committee

Councilor Flynn moved to accept with regret the resignation of MC (Mary Claire) Rodriguez-Abbot from the Portsmouth Energy Advisory Committee and send a letter thanking MC for her service to the City. Seconded by Councilor Hopkins.

Motion passed unanimously.

- B. Appointments to be Considered
 - Zachary (Zach) Dombrowski for full member to the Economic Development Commission
 - Matthew Jeffers for alternate member to the Economic Development Commission
- C. Appointments to be Voted
 - Alanna Lang appointment to the Behavioral Health Task Force
 - Meganne Fabrega reappointment to the Library Board of Trustees
 - Alice Carey reappointment to the Conservation Commission

Assistant Mayor Kelley moved to appoint as presented. Seconded by Councilor Cook.

Motion passed unanimously.**16. City Council Members**

- A. Agenda Item 15.A taken out of order - Councilors Cook and Tabor
 - Municipal Building Blue Ribbon Committee Recommendation
- B. *Councilors Tabor, Blalock, and Moreau

- CIP Citizen Request Subcommittee Report Out

Councilor Moreau gave an overview of the CIP Citizen requests. There are 27 requests this year. Seven they acted on. 14 requests are existing projects. There are five that are better off in another process. There was one request where the committee asked for more information and a report back from the Recreation Board before moving forward. She highlighted a tree project. There is a request for a Banfield Road sidewalk.

Councilor Blalock thanked the citizens for their requests. He highlighted a sidewalk request on Jones Avenue. There was a request for a disc golf course as well as a request

for a hockey ball court.

Councilor Tabor mentioned a bicycle path and fixing the intersection at Dennett Avenue. There was also a request to research a zero-waste plant.

C. Councilor Bagley

- ADU Property Tax Exemption

Councilor Bagley moved to request that Portsmouth's Delegation to the General Court file legislation for the 2027 session authorizing cities and towns to adopt a local option property tax exemption on the added assessed value of newly created accessory dwelling units, for a period of up to 20 years, as outlined below. Seconded by Councilor Moreau.

Councilor Bagley explained why he likes this proposal.

Mayor McEachern discussed how this request relates to the Housing Action Plan. It also has the potential to create more senior housing.

Councilor Cook hopes this is something that can pass at the State level. She feels this should apply to RSA 79-E.

Assistant Mayor Kelley would like to have an understanding from the City Assessors as it relates to tax exemption. There are a limited number of lots that can be converted to accessory dwelling units. She would like the maximum sized ADUs allowed on lots. She would like to have a report back from the Assessing Department.

Councilor Bagley would like to know how many accessory dwelling units have been built since 2017.

Councilor Moreau mentioned the last Housing Committee meeting reviewed the first draft of the proposed changes to RSA 79-E. Feedback was given about changes they would like to see and have should have more information towards the end of this year or the beginning of next year.

Councilor Cook mentioned the deadline for filing.

Motion passed unanimously.

Councilor Bagley moved to request that the City Attorney report to the Council on whether tax relief under RSA 79-E:4-c, as amended in 2026, could apply to newly created accessory dwelling units. Seconded by Councilor Moreau.

Motion passed unanimously.

D. Councilor Hopkins

- Parking & Traffic Safety Committee Action Sheet and Minutes of September 3, 2026

Councilor Hopkins moved to approve annual renewal of Valet License Agreement with LAZ Parking Limited, LLC for Portwalk HI, LLC as presented. Seconded by Councilor Blalock.

Motion passed unanimously.

Councilor Hopkins moved to approve annual renewal of Valet License Agreement with LAZ Parking Limited, LLC for Parade Residence Hotel, LLC as presented. Seconded by Councilor Cook.

Motion passed unanimously.

Councilor Hopkins moved to approve and accept the action sheet and minutes of the September 3, 2026, Parking & Traffic Safety Committee Meeting Seconded by Assistant Mayor Kelley.

Motion passed unanimously.

17. Approval of Grants/Donations

- A. Donation to the Senior Activity Center Luncheon Fund - \$1000 from Charlotte Dura and Robbin DiPierre

Assistant Mayor Kelley moved to accept with thanks a donation to the Senior Activity Center Luncheon Fund from Charlotte Dura and Robbin DiPierre in the amount as presented in the attached Gift and Donation Submission Form. Seconded by Councilor Blalock.

Motion passed unanimously.

- B. Granite United Way Opioid Abatement Responsive Grant Round 4 Award - \$13,000

Councilor Moreau moved to accept a \$13,000 Round 4 Opioid Abatement Response Grant from Granite United Way and authorize the City Manager to execute the Grant Agreement as presented. Seconded by Councilor Flynn.

Motion passed unanimously.

- C. Point of Graves Cemetery Donations

Councilor Cook moved to accept with thanks donations for the Point of Graves Cemetery Wall Replacement from Sharon Fulton, Patricia & Richard Bagley, Dan Corcoran, and Kathryn Lynch, in the amounts as presented in the attached Gift and Donation Submission Forms. Seconded by Councilor Tabor.

Motion passed unanimously.

18. City Manager's Informational Items

- A. Amended Resident Access Parking Pilot (RAPP) Program Policy

City Manager Conard noted that a Q1 update on the RAPP program will be presented at the October 26, 2026, City Council Meeting.

19. Miscellaneous Business Including Business Remaining Unfinished At Previous Meeting

Assistant Mayor Kelley mentioned the postponed New England BIPOC Festival, due to the recent Nor'easter, has been rescheduled to October 25, 2026, at Strawberry Banke, from 12:00 p.m. - 4:00 p.m.

20. Adjournment (At 10:30 pm or earlier)

Councilor Moreau moved to adjourn at 9:06 p.m. Seconded by Councilor Blalock.

Motion passed unanimously.

SHOTS NOT HEARD ROUND THE WORLD

By Michael James Geanoulis, Sr.

Listen my children, and be aware,
The sins of King George were everywhere.
He sought to enslave and tax beyond reason,
To seize powder and arms in a snow-driven season.
But the spirit of patriots was all that George wrought.
For it's true, they then knew, a war must be fought.

It mattered not, to Liberty's Sons and Paul Revere,
That problems could rise and prove quite severe.
That ye olde Portsmouth and New Castle's fort,
Were three score miles distant from ye Boston port.
And they but least cared, that travel on horse,
In the snows of December, was risky of course.

Most vital it was, if freedom be got,
New Hampshire be told, about the King's plot.
They should if they could, preempt the King's dash,
And seize for their own, that New Castle stash.

Not long after the arrival of Paul,
With his call for all to rise and stand tall,
Drummers drummed and runners ran,
To spread the news of his honorable plan.

From Kittery and Rye, from Dover and Brentwood,
By the hundreds they came, to help where they could.
They schemed and contrived to befuddle the Master,
Who sought to control those barrels of powder.
To ensure that instead, they'd be able to fight,
The upcoming war they thought proper and right.

So too, they knew, with gunpowder needed,
And knowing King George will likely advance,
To Fort William and Mary, they quickly proceeded.
Their future success they would not leave to chance.

It was freezing and snowing, that day in December,
When three hundred and more, rose as a member.
At first, they began with a subtle demand,
But the fort's captain rejected the plan,
Firing braces of balls as his deadly rejoinder.

At that signal they came, like bees in a swarm,
Some wading ashore in waters not warm,
To face cannon and musket as possible fodder,
But since no one was hurt, 'twas trivial bother.

That all escaped death, seemed like a clue,
Divine intervention came out of the blue.
To be candid and honest and perfectly frank,
Cannons and muskets fired at them point blank.
But the creator of lights was supportive, they said,
When the Crown was unable to paint the ground red.

Return fire came not from the rebels who saw,
Brute force would suffice though substantially raw.
They demanded and failed to get keys to the store,
But access was gained with the leverage they bore.

One hundred barrels of gunpowder they won,
With more arms next day for another ton.
From two days of raids at His Majesty's fort,
Their quest for freedom had much more support.
This initial assault on the much-hated Crown,
Gave birth to America, a place of renown.

And so it is, we're proud to remember,
And ever be glad to repeat this report,
That on two snowy days of '74 December,
The people had taken His Majesty's fort.

*Mike
Geanoulis*

Copyright © 2022 Michael J. Geanoulis, Sr.
All Rights Reserved
Exception: Non-Commercial Use by residents of Maine,
Massachusetts & New Hampshire.
Rev 4, 02/18/2023

**The Council Chambers
City Hall
Portsmouth, New Hampshire**

A Proclamation

- Whereas:** October was declared National Domestic Violence Awareness Month in 1987 because domestic violence is prevalent in every community and affects all people regardless of age, socio-economic status, sexual orientation, gender, race, religion or nationality; and
- Whereas:** We know that one in every three women and one in every four men are victims of domestic violence in their lifetimes; and that millions of Americans live in daily, silent fear within their own homes; and
- Whereas:** All domestic violence incidents affect every person within a home with long-lasting negative effects, particularly on children's emotional well-being and their social and academic functioning; and
- Whereas:** Between 2009 and 2024 there were 234 homicides in the State of New Hampshire of which 128, approximately 55%, were domestic violence related. In 2024, the State had 10 homicides, 9 of which were domestic violence related; and
- Whereas:** Since 1999, the City of Portsmouth has employed a Victim Witness Advocate, funded through the Violence Against Women Act, who works with the Portsmouth Police Department to support domestic violence victims under RSA 173-B, New Hampshire's Protection of Persons from Domestic Violence statute; and
- Whereas:** The City's Victim Witness Advocate serves on the State's Domestic Violence Fatality Review Committee, a multi-disciplinary team that reviews domestic violence fatalities in New Hampshire and identifies gaps in system responses, services, and points of intervention — gaps that, if addressed, could improve the State's response to domestic violence; and
- Whereas:** The City works with HAVEN, one of twelve crisis centers across the State, to provide 24/7 support to victims of sexual assault, domestic violence, sexual harassment and stalking. We remind everyone that confidential, local help is available, 24 hours a day, at the HAVEN Violence Prevention and Support Hotline: 603-994-SAFE; and
- Whereas:** The City of Portsmouth stands with all New Hampshire prosecutors as sentries on the front lines, advocating on behalf of victims of domestic violence; and


Now, therefore, I, Deaglan McEachern, Mayor of the City of Portsmouth, on behalf of the members of the City Council and citizens of Portsmouth, do hereby proclaim October 2026 in Portsmouth as

Domestic Violence Awareness Month

And call on our citizens to come together to reaffirm our commitment to ending domestic violence and supporting survivors.



Given with my hand and the
Seal of the City of Portsmouth,
on this 26th day of October 2026


Deaglan McEachern, Mayor of Portsmouth

ORDINANCE #0 -26
THE CITY OF PORTSMOUTH ORDAINS

That Chapter 10, ZONING ORDINANCE, be amended by removing most parking regulations from the Zoning Ordinance to the Site Plan Review Regulations (except one and two-family dwellings) by amending: Article 2, ADMINISTRATION AND ENFORCEMENT, Section 10.240, Conditional Use Permits; Article 5A, CHARACTER-BASED ZONING, Section 10.5A44, Off-Street Parking and Loading Requirements, Section 10.5A44.20, Number of Required Spaces; Article 5B, GATEWAY NEIGHBORHOOD MIXED USE DISTRICTS, Section 10.5B80, Parking and Loading Requirements and Standards, Section 10.5B82, Number of Required Spaces, Section 10.5B83, Location of Motor Vehicle Parking Facilities; Article 6, OVERLAY DISTRICTS, Section 10.685, Parking; Article 8, SUPPLEMENTAL STANDARDS, Section 10.815.30, Parking Requirements; Article 11, SITE DEVELOPMENT STANDARDS, Section 10.1110, Off-Street Parking, Section 10.1112, Number of Required Spaces, Section 10.1113, Location of Vehicular Use Facilities, Section 10.1114, Design of Off-Street Parking Facilities, Section 10.1115, Off-Street Parking Provisions in the Downtown Overlay District, Section 10.1116, Bicycle Parking and Section 10.1120, Off-Street Loading, be amended as follows (deletions from existing language ~~stricken~~; additions to existing language **bolded**; remaining language unchanged from existing):

ARTICLE 2 ADMINISTRATION AND ENFORCEMENT

Section 10.240 Conditional Use Permits

10.241 General

- 10.241.10 A conditional **use** is a use of land or **buildings** within a zoning district that may be authorized by this Ordinance subject to additional requirements. A conditional use permit allows the Planning Board or other such or person as may have jurisdiction to consider **uses** which may be desirable or appropriate in particular cases, but which are not allowed as a matter of right within a zoning district.
- 10.241.20 This Ordinance authorizes the following general types of conditional **use** permits:
- 10.241.21 Conditional **use** approval is required for any **use** designated “CU” in Section 10.440 – Table of Uses.
- 10.241.22 Conditional **use** approval is required for most **uses**, activities and alterations in a **wetland** or **wetland buffer** (Article 10, Section 10.1010 – Wetlands Protection).
- 10.241.23 Conditional **use** approval may be granted to allow flexibility of site or **building** design where specifically authorized by

the Ordinance but not listed in Section 10.440. These include the following provisions:

(a) Character Districts (Article 5A)

- Increase in allowed **building** footprint subject to specified **development** standards;
- Provision of required **community space** on a different **lot** than the **development**;
- Crediting or assignment of excess **community space** in an Incentive Overlay District.

(b) Gateway Districts (Article 5B)

- More than 24 **dwelling units** in a **building**;
- More than one **principal building** or building type on a **development** site;
- Increased housing density, **building height**, or footprint.

~~(c) Off Street Parking (Article 11)~~

- ~~• Less than the minimum number of required spaces or more than the maximum number of allowed spaces;~~
- ~~• Shared parking.~~

~~(cd)~~ Highway Noise Overlay District (Article 6)

- **Noise sensitive land uses**

ARTICLE 5A CHARACTER-BASED ZONING

10.5A44 Off-Street Parking and Loading Requirements

10.5A44.10 General

10.5A44.11 ~~Except as otherwise provided in this Section, all **building**, **structures** and **uses** in the Character districts and Civic districts shall comply with the **off-street parking** requirements set forth in Section 10.1110.~~ The number of required parking spaces shall be provided in accordance with the Site Plan Review Regulations.

10.5A44.12 **Buildings, structures** and **uses** in the Character districts and Civic districts that are also within the Downtown Overlay District shall comply with the additional standards in Section 10.643.

10.5A44.20 Number of Required Spaces

10.5A44.21 **Uses** in the Character districts and Civic districts that are not located in the Downtown Overlay District shall provide **off-street parking** in accordance with ~~the Site Plan Review Regulations Section 10.1112.~~

10.5A44.22 **Uses** in the Character districts and Civic districts that are included in the Downtown Overlay District shall comply with the **off-street parking** requirements for the Downtown Overlay District in accordance with ~~the Site Plan Review Regulations Section 10.1115.~~

10.5A44.23 Subject to approval by the Planning Board, any portion of the required **off-street parking** spaces may be dedicated to public use.

ARTICLE 5B GATEWAY NEIGHBORHOOD MIXED USE DISTRICTS

Section 10.5B80 Parking and Loading Requirements and Standards

10.5B81 General

10.5B81.10 ~~Except as otherwise provided in this Section, all **building**, **structures**, **uses**, and **development sites** in the Gateway Neighborhood Mixed Use Districts shall comply with the **off-street parking** and loading requirements set forth in Section 10.1110 and Section 10.1120.~~ Required parking shall be provided in accordance with the Site Plan Review Regulations.

10.5B82 Number of Required Spaces

10.5B82.10 Uses in the Gateway Neighborhood Mixed Use Districts shall provide **off-street parking** in accordance with ~~the Site Plan Review Regulations, Section 10.1112,~~ except as follows:

- a) For **developments** located on a public transit route with year-round, 5-days-per-week, fixed-route service and where at least 50% of the **building(s)** are within ¼ mile of a transit stop, the minimum **off-street parking** required for motor vehicles shall be reduced by 20% of the total required for all **uses**.

10.5B83 Location of Motor Vehicle Parking Facilities

10.5B83.10 Required **off-street parking** spaces shall not be located between a **principal building** and a **street** or within any required perimeter buffer area.

10.5B83.20 **Development sites** that include multiple **lots** shall not be subject to ~~the requirements of 10.1113.10~~ requiring **off-street parking** spaces to be located on the same **lot** as the principal **use**. **Off-street parking** spaces shall be located within the same **development site** for the principal **use** they are intended to serve.

ARTICLE 6 OVERLAY DISTRICTS

10.685 Parking

In the GNOD, the shared parking provisions of Section ~~4.4 of the Site Plan Review Regulations 10.1112.62~~ shall apply, and shared parking shall be permitted on separate **lots**, whether in common ownership or separate ownership ~~without the requirement of a conditional use permit~~. The provisions of Section ~~4.6 10.1113~~ of the Site Plan Review Regulations (Location of Vehicular Use Facilities) shall not apply to a GNOD development.

ARTICLE 8 SUPPLEMENTAL USE STANDARDS

~~10.815.30~~ **Parking Requirements**

~~10.815.31~~ Motor vehicle parking shall be required for **Coliving Facilities** as follows:

~~1. If any part of the **Coliving Facility** is located within 600 feet (approximately a 2.5 minute walk) of a public parking garage, No parking required.~~

~~2. If no part of the **Coliving Facility** is located within 600 feet (approximately a 2.5 minute walk) of a public parking garage,~~

~~off-street parking is required at the rate of 1 space per every 4
Coliving Unit.~~

ARTICLE 11 SITE DEVELOPMENT STANDARDS

Section 10.1110 Off-Street Parking

10.1111 General

- 10.1111.10 ~~The purpose of this Article, as amended, is to (a) retain off-street parking requirements for single-family and two-family dwellings; (b) delegate all other off-street parking requirements to the Site Plan Review Regulations. The purposes of Section 10.1110 are to manage parking supply to serve development needs without compromising community character or contributing to increased housing development costs. These purposes will be achieved by calibrating off-street parking requirements to demands, promoting shared parking arrangements for complementary uses, and providing for flexibility in the administration of off-street parking standards.~~
- 10.1111.20 All new **buildings** and **structures**, as well as additions to or changes in **use** or intensification of **use** in existing **buildings** and **structures**, shall be provided with **off-street parking** spaces in accordance with this Section.
- 10.1111.30 A **use** that is **nonconforming** as to the requirements for **off-street parking** shall not be enlarged or altered unless **off-street parking** is provided for the original **building**, **structure** or **uses** and all expansions, intensifications or additions sufficient to satisfy the requirements of this Section.
- 10.1111.40 ~~For all other uses including multifamily, nonresidential, and mixed-use development, or a change of use, the number of required off-street parking spaces and all related provisions (including shared/off-site parking, reserve parking, bicycle parking, and electric-vehicle parking) are established and administered under the Site Plan Review Regulations.~~

10.1112 Number of Required Parking Spaces

~~10.1112.10 General Requirements and Interpretation~~

- ~~10.1112.11 The number of required off-street parking spaces shall be based on the uses on the lot, as specified in Section 10.1112.30.~~
- ~~10.1112.12 For any permitted use not covered by Section 10.1112.30, the Code Official shall determine the closest similar use listed in that table and require off-street parking accordingly.~~
- ~~10.1112.13 Specially designated parking spaces for the physically disabled shall be provided in compliance with the Building Code (see International Building Code, Section 1106).~~

~~10.1112.14—The Planning Board may grant a conditional use permit to allow a **building** or **use** to provide less than the minimum number of **off-street parking** spaces required by Section 10.1112.30, Section 10.1112.61 or Section 10.1115.20, as applicable, or to exceed the maximum number of **off-street parking** spaces allowed by Section 10.1112.51.~~

~~10.1112.141—An application for a conditional use permit under this section shall include a parking demand analysis, which shall be reviewed by the City's Technical Advisory Committee prior to submission to the Planning Board, demonstrating that the proposed number of **off-street parking spaces** is sufficient for the proposed **use**.~~

~~10.1112.142—An application for a conditional use permit under this section shall identify permanent evidence-based measures to reduce parking demand, including but not limited to provision of rideshare/microtransit services or bikeshare station(s) servicing the property, proximity to public transit, car/van pool incentives, alternative transit subsidies, provisions for teleworking, and shared parking on a separate **lot** subject to the requirements of 10.1112.62.~~

~~10.1112.143—The Planning Board may grant a conditional use permit only if it finds that the number of **off-street parking** spaces required or allowed by the permit will be adequate and appropriate for the proposed **use** of the property. In making this determination, the Board may accept, modify or reject the findings of the applicant's parking demand analysis.~~

~~10.1112.144—At its discretion, the Planning Board may require more **off-street parking** spaces than the minimum number requested by the applicant, or may allow fewer spaces than the maximum number requested by the applicant.~~

10.1112.20—Calculation of Number of Required Spaces

~~10.1112.21—The number of required **off-street parking** spaces shall be the sum of the requirements for the various individual **uses** on a **lot** computed separately.~~

~~10.1112.22—Where the computation of required **off-street parking** spaces results in a fractional number, the computation shall be rounded up to the next whole number.~~

~~10.1112.23—Parking spaces occupied by **EV** chargers and supporting equipment may count towards minimum parking requirements.~~

10.1112.1030 Off-Street Parking Requirements

~~10.1112.31—Parking Requirements for Residential Uses~~

~~10.1112.311~~ The required minimum number of **off-street parking** spaces for **single- and two-family dwellings uses 1.10 through 1.90, including dwelling units in mixed-use developments,** shall be based on the gross floor area of each **dwelling unit**, as follows:

Dwelling Unit Floor Area	Required Parking Spaces
500 Sq. ft. or less	0.5 spaces per unit
Over 500 sq. ft.	1.0 space per unit

~~10.1112.312~~ In addition to the **off-street parking** spaces provided in accordance with Sec. 10.1112.311, any **dwelling** or group of **dwellings** on a **lot** containing more than 4 **dwelling units** shall provide one visitor parking space for every 5 **dwelling units** or portion thereof.

~~10.1112.20—Parking Compliance for Change of Use~~

~~Any change of use that does not require Site Plan Review shall be subject to the following:~~

~~a) comply with the parking requirements in the Site Plan Review Regulations.~~

~~b) The Planning Director may require submission of documentation, including a parking plan or existing and proposed parking counts, sufficient to demonstrate compliance.~~

~~A change of use shall not create a new nonconformity or increase an existing nonconformity related to parking.~~

~~10.1112.32—Parking Requirements for Nonresidential Uses~~

~~10.1112.321~~ The required minimum number of **off-street parking** spaces for **uses** other than 1.10 through 1.90 shall be based on the following table.

Table of Minimum Off-Street Parking Requirements for Nonresidential Uses

Use No.	Use	Requirement
2. Institutional Residence or Care Facilities		
2.10-2.20	Assisted living facility or Residential care facility	0.5 per bed or resident
3. Educational, Religious, Charitable, Cultural and Public Uses		
3.10	Place of assembly	0.4 per seat (fixed seating); or 1 per 4 persons maximum occupancy of assembly area; or Parking demand analysis
3.20	School	Parking demand analysis
3.30	Historic preservation building	No requirement

Use No.	Use	Requirement
3.40	Museum	Parking demand analysis
3.50	Performance facility	0.4 per seat (fixed seating), or Parking demand analysis
3.60	Cemetery	No requirement
3.70	Club, fraternal or service organization	Greater of: —1 per 4 persons maximum occupancy —1 per 200-sf GFA
3.80	Municipally operated park and related activities	No requirement
4. Recreational Uses		
4.10	Religious, sectarian or private non-profit recreational use	Parking demand analysis
4.20	Cinema or similar indoor amusement use with no live performance	0.4 per seat, or Parking demand analysis
4.30	Indoor recreation use , such as bowling alley or arcade	1 per 4 persons maximum occupancy
4.40	Health club, yoga studio, martial arts school, or similar use	1 per 250-sf GFA
4.50	Outdoor recreation use	Parking demand analysis
4.60	Amusement park, water park or theme park	NA—Prohibited Use
5. Office Uses, Non-Medical		
5.10-5.30	Professional, business and financial services	1 per 350-sf GFA
5.40	Social service campus	Apply standards for component uses
5.50	Media studio	1 per 1,000-sf GFA
5.60	Publishing facility or similar electronic production operation	1 per 1,000-sf GFA
5.70	Call Center	1 per 250-sf GFA
6. Medical Services and Health Care		
6.10	Hospital	Parking demand analysis
6.20	Medical offices and clinics (outpatient only)	1 per 250-sf GFA
6.30	Clinics with inpatient care	Greater of: —2 per bed —1 per 250-sf GFA
6.40	Ambulatory surgical center	1 per 250-sf GFA

Use No.	Use	Requirement
6.50	Substance abuse treatment facility	Parking demand analysis
6.60	Psychiatric hospital for the criminally insane	NA—Prohibited Use
7. Services, Other Than Health Care		
7.11	Family day care facility	4 spaces (including 2 for the single-family dwelling)
7.12	Group day care facility including private preschool and kindergarten	0.5 per client or student based on licensed enrollment capacity
7.20-7.40	Personal services , Consumer services, and Trade, craft and general services	1 per 400-sf GFA
7.50-7.60	Veterinary care and Laundry and dry cleaning establishments	1 per 500-sf GFA
7.70	Undertaking establishment , funeral parlor or mortuary chapel, excluding crematorium	1 per 25-sf of floor area for public occupancy
8. Retail Trade		
8.10-8.90	All retail trade uses	1 per 300-sf GFA
9. Eating and Drinking Places		
9.10-9.50	All eating and drinking places	1 per 100-sf GFA
10. Lodging Establishments		
10.10-10.20	Boarding house or Bed and breakfast	2 + 1 per room for rent
10.30-10.40	Inn, hotel or motel	1.25 per guest room + 1 per 100-sf of lounge or restaurant area + 1 per 25-sf of conference or banquet facilities
10.50-10.60	Conference hotel or Conference center	Parking demand analysis
11. Motor Vehicle-Related Uses		
11.10, 11.30	Sales, renting or leasing of vehicles, marine craft, power equipment, etc.	1 per 600-sf GFA + 1 per 2000-sf outside display or storage area
11.20	Motor vehicle service station, motor vehicle repair or washing facility for passenger cars and light trucks	2 + 1 per 400-sf GFA EV fueling spaces A and B may count towards minimum parking requirements.
11.40	Impound lot (principal or accessory use)	No requirement
11.50	Truck fueling facility	4 spaces
11.60	Truck terminal	1 per 2000-sf GFA +

Use No.	Use	Requirement
		3 per loading dock
12. Marine Craft Related Uses		
12.11	Non-commercial boat landings, boat docks, boathouses, etc.	No requirement
12.12	Fishing boat landing 1	4 spaces
12.13	Fishing boat landing 2	Parking demand analysis
12.20-12.40	Marina , repair of commercial marine craft and marine-related structures , or landside support facility for commercial passenger vessel	Parking demand analysis
13. Wholesale Trade, Warehousing and Distribution		
13.10	Wholesale use	1 per 2000-sf GFA
13.20	Wholesale sales devoted to, and in the same establishment as, a permitted retail use	1 per 2000-sf area devoted to wholesale
13.30	Wholesale lumber yards, lumber and contractor sales	No requirement
13.40	Warehousing or distribution of non-flammable, non-hazardous materials, not classified as a high hazard use	1 per 2000-sf GFA
14. Industrial Uses		
14.10-14.20	Light industry or Research and development	1 per 500-sf GFA
14.30-14.50	Food processing , Electronics manufacturing , General manufacturing	1 per 1000-sf GFA
14.60	Biological or chemical laboratory	1 per 500-sf GFA
14.70	Recycling facility or recycling plant	No requirement
14.80	High hazard use , including other uses listed in this section but not including uses described in 14.90	Parking demand analysis
14.90	Storage (other than normal accessory use), processing, disposal, or transfer of petroleum, petrochemicals, natural gas and liquid petroleum products, coal, alcohol, wood pulp, solid or liquid waste, junk or hazardous waste as classified by Federal or State law	NA—Prohibited Use

Use No.	Use	Requirement
15. Transportation and Utilities		
15.10	Public or private transformer station, substation, pumping station or automatic telephone exchange, not including any business office, storage yard or storage building	No requirement
15.20	Heliport or helipad	No requirement
16. Wireless Telecommunications Facilities		
16.10-16.40	All wireless telecommunications facilities	No requirement
17. Agricultural Uses		
17.10-17.20	All agricultural use	No requirement
18. Temporary Uses		
18.10	Construction trailer	No requirement
18.20	Temporary structure	No requirement
18.30	Manufactured housing not on a foundation, as temporary replacement housing for a dwelling on the same lot destroyed by natural causes	2 spaces (single-family dwelling)
18.40	Carts or trailers, including outdoor display area, used for the seasonal sale of dry goods, Christmas trees, flowers, fruits, vegetables, seasonal products and prepared food	No requirement
19. Accessory Uses		
19.10	Accessory use to a permitted principal use (not otherwise specified in this section), but not including any outdoor storage	No requirement
19.20	Home occupation	No minimum requirement (maximum 1 space for the home occupation)
19.30	Concessions and services located within the principal building	No requirement
19.40	Drive-through facility, as accessory use to a permitted principal use	No requirement
20. Accessory Storage		
20.10— 20.60	All accessory storage uses	No requirement

~~10.1112.322—Where the table lists a general **use** category without the subcategories, the parking ratio shall apply to all subcategories within that category (for example, the parking ratio shown for **use** number 2.10 applies to **uses** 2.11 and 2.22).~~

~~10.1112.323—Where the table indicates that the minimum required number of **off-street parking** spaces shall be based on a parking demand analysis, the applicant shall submit such analysis for review by the Planning Board. Where the table indicates that a parking demand analysis is an alternative to a specified ratio, the applicant may submit such analysis to justify a ratio different from that listed in the table. In either case, the Planning Board may approve the number of parking spaces proposed by the analysis, or may approve a greater or lesser minimum number of parking spaces based on its review.~~

~~10.1112.324—Where the minimum number of **off-street parking** spaces is based on **maximum occupancy**, the applicant shall submit a code analysis showing the occupant load for the proposed **use** determined in accordance with the Building Code.~~

10.1112.40—Reserve Parking Area

When Section 10.1112.30 requires the provision of 20 or more **off-street parking** spaces, the Planning Board may approve the construction of fewer **off-street parking** spaces than required, subject to the following:

~~10.1112.41—A “Reserve Parking Area” shall be designated that is sufficient to accommodate the difference between the number of spaces required and the lesser number actually provided.~~

~~10.1112.42—The site plan shall clearly delineate the Reserve Parking Area and shall demonstrate that it is sufficient to accommodate the additional parking spaces in accordance with the requirements of this Section.~~

~~10.1112.43—The Reserve Parking Area shall be landscaped with grass, ground covers and/or other plant materials, but shall not be counted toward any minimum **open space** requirement.~~

~~10.1112.44—The Reserve Parking Area shall not be used as snow storage area and shall not contain any **structure** or mechanical equipment.~~

10.1112.50—Maximum and Minimum Number of Parking Spaces

~~10.1112.51—The number of **off-street parking** spaces for any **building** or **use** shall not exceed the following amounts:~~

Minimum Number of Spaces Required by Section 10.1112.30	Maximum Number of Spaces Allowed
0-20	No maximum
21 or more	120 percent of minimum

~~10.1112.60 — Shared Parking~~

~~10.1112.61 — Methodology~~

~~Developments that contain a mix of uses on the same parcel shall reduce the number of **off-street parking** spaces in accordance with the following methodology:~~

- ~~(1) Determine the minimum number of **off-street parking** spaces for each land **use** within the development in accordance with Sections 10.1112.10 through 10.1112.50.~~
- ~~(2) Multiply the minimum parking requirement for each land use by the corresponding parking occupancy rates for each of the five time periods set forth in Columns (B) through (F) of the Parking Occupancy Rates table below.~~

Parking Occupancy Rates

(A) Land Use	Weekday		Weekend		(F) Nighttime (Midnight– 6:00 AM)
	(B) Daytime (8:00 AM– 5:00 PM)	(C) Evening (6:00 PM– Midnight)	(D) Daytime (8:00 AM– 5:00 PM)	(E) Evening (6:00 PM– Midnight)	
Residential	60%	100%	80%	100%	100%
Office/ Industrial	100%	20%	10%	5%	5%
Retail/Service	60%	90%	100%	70%	5%
Hotel/Motel	70%	100%	75%	100%	100%
Restaurant	70%	100%	80%	100%	10%
Entertainment	40%	100%	80%	100%	10%
Conference/ Convention	100%	100%	100%	100%	5%
Place of Worship*	10%	5%	100%	50%	5%
Other Institutional	100%	20%	10%	10%	5%

~~* For a religious use that holds its principal services on a weekday, the weekday and weekend ratios shall be reversed.~~

- ~~(3) Add the resulting shared parking requirements for each time period to determine the minimum parking requirement for that period.~~

~~The required minimum number of parking spaces for the development shall be the highest of the five time period totals.~~

~~10.1112.62 — Shared Parking on Separate Lots~~

~~The Planning Board may grant a conditional use permit to allow a reduction in the number of required **off-street parking** spaces for uses on separate **lots**, whether in common or separate ownership, subject to the following:~~

- (1) ~~The shared parking requirement may be determined using the methodology in Section 10.1112.61, or by another method approved or required by the Planning Board.~~
- (2) ~~The shared parking arrangement shall be secured by a covenant acceptable to the City and recorded at the Rockingham County Registry of Deeds.~~

10.1113 Location of Vehicular Use Facilities

~~10.1113.10~~ Proximity to Principal Use

~~10.1113.11 All required off-street parking spaces shall be located on the same lot as the principal use they are required to serve except as follows:~~

~~10.1113.111 Required parking spaces may be located on a separate lot from the principal use which they serve where a municipally owned or operated covered parking facility is constructed as part of the overall development.~~

~~10.1113.112 The Board of Adjustment may authorize a special exception for the provision of required parking on another lot in the same ownership as the lot in question and within 300 feet of the property line of the lot in question.~~

~~10.1113.12 In no case shall parking be permitted within any Residential or Mixed Residential District other than that which is accessory to a principal use allowed within the district.~~

10.1113.120 Location of Parking Facilities on a Lot

Required off-street parking spaces ~~shall not~~ may be located in any required front yard, or between a principal building and a street (including on a corner lot). ~~This restriction shall not apply to required off-street parking for a single-family dwelling (including the combination of a single-family dwelling and an accessory dwelling unit) or two-family dwelling.~~

~~10.1113.30~~ Minimum Distance from Residential and Mixed Residential Zoning Districts

~~10.1113.31 Off-street parking areas, accessways, maneuvering areas and traffic aisles serving uses in a Business or Industrial district shall be set back from all Residential and Mixed Residential districts as follows:~~

District	Minimum Distance from Residential or
	Mixed Residential District
B	50 feet
GB, GW	100 feet
I, OR, WI	100 feet

~~10.1113.32 Off-street parking areas, accessways, maneuvering areas and traffic aisles serving a nonresidential use on a lot in a Mixed Residential district that abuts a Residential district shall be set back at least 10 feet from the~~

~~Residential district boundary and shall be screened in accordance with the screening standards of the Planning Board's Site Plan Review Regulations.~~

~~10.1113.40 — Setback from Lot Lines~~

~~10.1113.41 — Off-street parking areas, accessways, maneuvering areas and traffic aisles serving uses in a Business or Industrial district shall be set back from front lot lines as follows:~~

District	Minimum Setback from Front Lot Line
B	20 feet
GB, GW	40 feet
I, OR, WI	50 feet

~~10.1113.42 — In a Residential zoning district, off-street parking spaces for a home occupation use, including family day care and group day care, shall be set back at least 10 feet from side and rear property lines and shall be screened in accordance with the screening standards of the Planning Board's Site Plan Review Regulations.~~

~~10.1113.43 — All required setbacks of off-street parking areas from front property lines shall be landscaped in accordance with the landscaping and screening standards of the Planning Board's Site Plan Review Regulations.~~

10.1114 Design of Off-Street Parking Facilities

~~10.1114.10 — Applicability~~

~~The provisions of this Section 10.1114 shall apply to all off-street parking facilities, whether in parking structures or surface lots, and whether or not the parking spaces are required or in excess of the requirements for a use, except as specifically exempted herein.~~

~~10.1114.20 — Stall Layout~~


~~10.1114.21 — Parking spaces and maneuvering aisles shall be laid out in compliance with the minimum dimensions set forth in the Table of Off-Street Parking Dimensions.~~

Table of Off-Street Parking Dimensions

A Angle of Parking (degrees)	B Width of Parking Space	C Depth of Parking Space	D Width of Maneuvering Aisle *	
			1-way traffie	2-way traffie
0°	8.5'	20'	14'	24'
45°	8.5'	19'	16'	24'
60°	8.5'	19'	18'	24'
90°	8.5'	19'	24'	24'

* The minimum width of a **maneuvering aisle** shall be 22 feet for (a) an aisle for 2-way traffic providing access to fewer than 7 parking spaces, or (b) an aisle in a parking structure for 2-way traffic, or (c) an aisle in a parking structure for 1-way traffic with 90-degree parking.

Key to Table of Off-Street Parking Dimensions



- 10.1114.22 — ~~Parking areas shall include parking spaces for the physically disabled in compliance with the **Building Code** and *Accessible and Usable Buildings and Facilities* (ICC/ANSI A117.1 latest edition).~~
- 10.1114.23 — ~~Parking spaces located within four feet of an abutting **structure, sidewalk,** or public **street** shall be designed with suitable bumper stops.~~
- 10.1114.24 — ~~Parking areas and access drives shall be surfaced with a durable surface that meets the load bearing **maximum occupancy** of the project; minimizes dust, material tracking and erosion; and facilitates snow removal. Examples of such materials include, but are not limited to, bituminous binder, concrete, asphalt, compacted gravel and crushed stone. Pervious surfaces may be used provided that they meet the above objectives and provide equivalent protection of surface and groundwater resources.~~

~~10.1114.25 — Except for **one-family** and **two-family dwellings**, all **off-street parking** spaces shall be marked and maintained to provide delineation between parking stalls and aisles.~~

10.1114.1030 Vehicular Circulation

10.1114.1131 Access to and egress from all parking areas shall be only via **driveways** which meet the standards for “General Accessway and Driveway Design” in the Site Plan Review Regulations.

10.1114.1232 ~~Except for Off-street parking for **one-family** and **two-family dwellings**, all **off-street parking** areas shall be designed so that:~~

- (a) Vehicles can enter and leave each parking space without passing over any other parking space or requiring the moving of any other vehicle, and
- (b) Vehicles can enter and leave the parking area without backing into or from a public **street** or way.

~~10.1114.33 — Notwithstanding the previous provision, tandem parking spaces may be provided for required **off-street parking** spaces serving **dwelling units** in residential and mixed-use developments, subject to the following requirements:~~

- ~~(a) Tandem spaces shall be assigned to the same **dwelling unit**.~~
- ~~(b) Tandem parking shall not be used to provide guest parking.~~
- ~~(c) Two parking spaces in tandem shall have a combined minimum dimension of 9 feet in width by 38 feet in length.~~

10.1114.40 — Pedestrian Circulation

~~Except for **one-family** and **two-family dwellings**, all **off-street parking** areas shall incorporate the following provisions for pedestrian circulation:~~

~~10.1114.41 — A minimum 5-foot wide pedestrian path shall be provided throughout the site, connecting **adjacent streets**, **accessways**, **sidewalks** and parking areas to the entrances of all **structures**.~~

~~10.1114.42 — Pedestrian areas shall be clearly distinguished from vehicular and bicycle traffic areas through the use of paving materials, **landscaping** buffers, or other means.~~

~~10.1114.43 — Continuous off-**street** vehicle routes shall be no more than 200 feet in length before interruption by pedestrian crosswalks over speed tables, T-intersections or other design elements to calm vehicle movement on-site.~~

10.1115 — Off-Street Parking Provisions in the Downtown Overlay District

10.1115.10 — Purpose

~~10.1115.11 — This Section 10.1115 establishes modified **off-street parking** standards for **lots** in the Downtown Overlay District in recognition of the availability of municipal on-**street** and **off-street parking** facilities, private shared parking facilities, and public transit, and the pedestrian-oriented pattern of **lots and uses**.~~

~~10.1115.12 — Except as specifically modified by this Section 10.1115, **lots** in the Downtown Overlay District shall comply with all other provisions of Section 10.1110.~~

~~10.1115.20 — Number of Required Off-Street Parking Spaces~~

~~10.1115.21 — The following requirements shall apply in the Downtown Overlay District in lieu of the requirements in Section 10.1112.30:~~

Use	Required Parking Spaces
Residential use (dwelling)	Same as Section 10.1112.30
Hotel or motel	0.75 space per guest room, plus 1 space per 25 sf of conference or banquet facilities
Other nonresidential use	No requirement

~~10.1115.22 — The requirements in Section 10.1115.21 shall be applied to all **uses** on a **lot**, and not to individual **uses**.~~

~~10.1115.23 — For any **lot**, the number of **off-street parking** spaces that would be required by applying the ratios in Section 10.1115.21 shall be reduced by 4 spaces. (Therefore, any **lot** that would be required to provide 4 or fewer **off-street parking** spaces shall not be required to provide any spaces.)~~

~~10.1115.24 — The provisions of Section 10.1112.50, Maximum Number of Parking Facilities, shall not apply to **buildings** and **uses** within the Downtown Overlay District.~~

~~10.1116 — Bicycle Parking~~

~~10.1116.10 — Number of Bicycle Parking Spaces Required~~

~~10.1116.11 — Off street parking of bicycles shall be provided as follows, up to a maximum of 30 bicycle spaces:~~

Multifamily dwellings	1 bicycle space for each 5 dwelling units or portion thereof
Elementary, middle and high schools	1 bicycle space for each 4 students
All other uses, except as exempted in Section 10.1116.14	1 bicycle space for each 10 automobile parking spaces or fraction thereof required by Section 10.1112.30 or Section 10.1115.21, as applicable

~~10.1116.12 — When the Planning Board approves the construction of fewer **off-street parking** spaces than would normally be required under Section 10.1112.30 or Section 10.1115.21 (for example, when a Reserve Parking Area is provided under Section 10.1112.40), or when Board of Adjustment grants a variance from the required number of **off-street parking** spaces, the required number of bicycle parking spaces shall be based on the number of such spaces that would be required without such reduction or variance.~~

~~10.1116.13 — In addition to the number of bicycle parking spaces required under Section 10.1116.11 and 10.1116.12, any nonresidential use may substitute bicycle parking spaces for up to 5 percent of the required automobile parking spaces at the following ratios: 1 required automobile space may be replaced by 6 bicycle spaces or by 2 bicycle lockers.~~

~~10.1116.14 — The following uses are exempt from providing bicycle parking spaces:~~

Use No.	Use
1.10	Single-family dwelling
1.20, 1.21, 1.22	Accessory dwelling unit
1.30	Two-family dwelling
2.10	Assisted living facility
2.20	Residential care facility
7.10	Day care
7.70	Undertaking establishment
11.10-11.60	Motor vehicle related uses
12.10-12.40	Marine craft related uses
13.10-13.40	Wholesale trade, warehousing and distribution
14.70	Recycling facility or recycling plant
14.80	High hazard use
17.10-17.20	Agricultural uses
19.10-19.40	Accessory uses

~~10.1116.15 — Bicycle parking spaces shall be designed in accordance with standards set forth in the Site Plan Review Regulations.~~

~~Section 10.1120 Off-Street Loading~~

~~10.1121 — General Requirements~~

~~10.1121.10 — All new **structures**, additions to existing **structures**, and changes and intensification of **use** in existing **structures** shall be provided with off-street loading areas in accordance with this Section, except in Character Districts 4-W, 4 and 5 (CD4-W, CD4 and CD5) and the Downtown Overlay District.~~

~~10.1121.20 — No loading areas shall be required in Character Districts 4-W, 4 and 5 (CD4-W, CD4 and CD5) and the Downtown Overlay District.~~

~~10.1122 — Number of Loading Areas~~

~~10.1122.10 — Off-street loading spaces shall be provided according to the following ratios:~~

Use	Gross Floor Area (sf)	Required Spaces
Industrial	Up to 10,000 sq. ft.	0
	10,001–40,000 sq. ft.	1
	40,001–100,000 sq. ft.	2
	100,001–200,000 sq. ft.	3
	Each additional 200,000 sq. ft.	1
Office-/	Up to 10,000 sq. ft.	0
Professional Service	10,001–100,000 sq. ft.	1

Use	Gross Floor Area (sf)	Required Spaces
	100,001—350,000 sq. ft.	2
	Each additional 350,000 sq. ft.	1
Retail	Up to 10,000 sq. ft.	0
	10,001—25,000 sq. ft.	1
	25,001—60,000 sq. ft.	2
	60,001—120,000 sq. ft.	3
	Each additional 100,000 sq. ft.	1
Other Non-Residential	Up to 10,000 sq. ft.	0
	10,001—40,000 sq. ft.	1
	Each additional 60,000 sq. ft.	1

~~10.1122.20—In case of mixed **uses**, the loading areas required shall be the sum of all requirements computed on the basis of the above table.~~

~~10.1123—~~ Loading Area Dimensions

~~All required loading areas shall conform to the following dimensional standards:~~

Minimum vertical clearance:	14 feet
Minimum width of loading area:	12 feet
Minimum length of loading area:	
 First required loading area:	20 feet
 Additional required loading areas:	45 feet

10.111524 Location of Loading Areas

10.111524.10 Loading areas shall not be located between the front property line and any building or structure nor in a required side yard or rear yard.

~~10.1124.20—No off-street loading or maneuvering areas shall be nearer than 100 feet to any adjoining Residential or Mixed Residential Districts and shall be screened in accord with Section 10.1130 and the Planning Board's Site Plan Regulations.~~

~~10.1124.30—No off-street loading areas shall be a part of an area used to satisfy the **off-street parking** requirements of this Ordinance.~~

The City Clerk shall properly alphabetize and/or re-number the ordinances as necessary in accordance with this amendment.

All ordinances or parts of ordinances inconsistent herewith are hereby deleted. This ordinance shall take effect upon its passage.

APPROVED:

Deaglan McEachern, Mayor

ADOPTED BY COUNCIL:

Sally Kellar, City Clerk

CITY OF PORTSMOUTH, NEW HAMPSHIRE

SITE PLAN REVIEW REGULATIONS



Adopted by Planning Board: December 17, 2009
Amended: November 19, 2020

SITE PLAN REVIEW REGULATIONS

ARTICLE 1	PURPOSE AND APPLICABILITY	1
SECTION 1.1	PURPOSE	1
SECTION 1.2	APPLICABILITY	1
ARTICLE 2	APPLICATION AND REVIEW PROCESS	4
SECTION 2.1	PLANNING BOARD RESPONSIBILITIES	4
SECTION 2.2	SITE PLAN REVIEW TECHNICAL ADVISORY COMMITTEE	4
SECTION 2.3	TECHNICAL REVIEW AND ASSISTANCE	5
SECTION 2.4	PREAPPLICATION REVIEW	5
SECTION 2.5	APPLICATION REQUIREMENTS	7
SECTION 2.6	REFERRALS TO CITY DEPARTMENTS	14
SECTION 2.7	PUBLIC HEARING	14
SECTION 2.8	DETERMINATION OF APPLICATION COMPLETENESS	15
SECTION 2.9	EVALUATION CRITERIA	16
SECTION 2.10	WAIVER REQUESTS	17
SECTION 2.11	APPROVAL PROCEDURES	17
SECTION 2.12	SITE PLAN REVIEW AGREEMENT	18
SECTION 2.13	RECORDING OF SITE PLANS	18
SECTION 2.14	APPROVAL EXPIRATION AND EXTENSION	19
SECTION 2.15	POST APPROVAL PROCEDURES	20
SECTION 2.16	PROJECT INSPECTION AND COMPLETION	21
SECTION 2.17	EXEMPTION OF APPROVED SITE PLAN FROM CHANGES IN LAND USE REGULATIONS	22
ARTICLE 3	VEHICULAR CIRCULATION STANDARDS	24
SECTION 3.1	GENERAL PROVISIONS	24
SECTION 3.2	OFF-SITE IMPACTS	24
SECTION 3.3	GENERAL ACCESSWAY AND DRIVEWAY DESIGN	25
SECTION 3.4	CURBING	26
SECTION 3.5	TRAFFIC CALMING AND CONNECTIONS	26
SECTION 3.6	DRIVE-THROUGH FACILITIES	26
SECTION 3.7	LOADING AND SERVICE AREAS	28
SECTION 3.8	FIRE LANES	29
SECTION 3.9	MASS TRANSIT FACILITIES	30

ARTICLE 4	PARKING AREA STANDARDS	31
SECTION 4.1	PARKING PROVISION	31
SECTION 4.1	GENERAL PROVISIONS.....	31
SECTION 4.2	NUMBER OF REQUIRED PARKING SPACES.....	31
SECTION 4.3	CALCULATION OF NUMBER OF REQUIRED SPACES PARKING FLEXIBILITY	32
SECTION 4.4	RESERVE PARKING AREA.....	ERROR! BOOKMARK NOT DEFINED.
SECTION 4.5	SHARED PARKING.....	ERROR! BOOKMARK NOT DEFINED.
SECTION 4.6	SHARED PARKING ON SEPARATE LOTS	ERROR! BOOKMARK NOT DEFINED.
SECTION 4.7	LOCATION OF VEHICULAR USE FACILITIES.....	36
SECTION 4.8	DESIGN OF OFF-STREET PARKING FACILITIES.....	37
SECTION 4.9	OFF-STREET PARKING PROVISIONS IN THE DOWNTOWN OVERLAY DISTRICT	40
SECTION 4.210	REQUIREMENTS FOR ACCESSIBLE PARKING FOR THE PHYSICALLY DISABLED.....	40
SECTION 4.113	OFF-STREET PARKING SPACE DESIGN AND LAYOUT	40
ARTICLE 5	PEDESTRIAN AND BICYCLE CIRCULATION	42
SECTION 5.1	GENERAL PROVISIONS.....	42
SECTION 5.2	SIDEWALKS AND PEDESTRIAN PATHWAYS.....	42
SECTION 5.3	BICYCLE FACILITIES	43
ARTICLE 6	LANDSCAPING AND SCREENING STANDARDS	45
SECTION 6.1	GENERAL PROVISIONS.....	45
SECTION 6.2	LANDSCAPING PLAN.....	45
SECTION 6.3	GENERAL REQUIREMENTS	46
SECTION 6.4	PLANTING REQUIREMENTS.....	47
SECTION 6.5	PLANT SELECTION	49
SECTION 6.6	LANDSCAPED AREAS	49
SECTION 6.7	LANDSCAPING ALONG PUBLIC RIGHTS OF WAY	50
SECTION 6.8	PERIMETER LANDSCAPING	51
SECTION 6.9	SCREENING.....	51
SECTION 6.10	MAINTENANCE AND REPLACEMENT OF LANDSCAPING AND SCREENING.....	52
SECTION 6.11	IRRIGATION	52
SECTION 6.12	INNOVATIVE LANDSCAPING PRACTICES	53
ARTICLE 7	WATER RESOURCES STANDARDS	54
SECTION 7.1	LOW IMPACT DEVELOPMENT (LID).....	54
SECTION 7.2	GENERAL WATER QUALITY AND STORMWATER MANAGEMENT PROVISIONS.....	54
SECTION 7.3	WELLHEAD PROTECTION AREAS.....	55

SECTION 7.4	STORMWATER MANAGEMENT AND EROSION CONTROL PLAN (SMECP)	55
SECTION 7.5	CONSTRUCTION EROSION CONTROL DESIGN STANDARDS	57
SECTION 7.6	POST-CONSTRUCTION STORMWATER MANAGEMENT DESIGN STANDARDS	59
ARTICLE 8 UTILITIES STANDARDS		65
SECTION 8.1	GENERAL PROVISIONS	65
SECTION 8.2	WATER SUPPLY AND DISTRIBUTION SYSTEM	65
SECTION 8.3	SANITARY SEWERS	66
SECTION 8.4	OTHER UTILITIES	66
SECTION 8.5	OVERSIZE AND OFF-SITE IMPROVEMENTS	67
ARTICLE 9 ON-SITE WASTE STORAGE AND DISPOSAL STANDARDS		68
SECTION 9.1	WASTE ACCUMULATION	68
SECTION 9.2	STORAGE CONTAINERS	68
SECTION 9.3	LOCATION AND DISPOSAL	68
SECTION 9.4	FLAMMABLE AND COMBUSTIBLE LIQUIDS	69
SECTION 9.5	SCREENING	69
ARTICLE 10 OUTDOOR LIGHTING		70
SECTION 10.1	GENERAL PROVISIONS	70
SECTION 10.2	COMPLIANCE WITH ZONING ORDINANCE	70
SECTION 10.3	LIGHTING PLAN	70
SECTION 10.4	LAMPS	71
ARTICLE 11 RADIO COMMUNICATIONS STANDARDS		72
SECTION 11.1	SITE SURVEY	72
ATTACHMENT A: DIGITAL AS-BUILT PLAN REQUIREMENTS		73
ATTACHMENT B: TOPSOIL SPECIFICATIONS		74

Article 1 Purpose and Applicability

Section 1.1 Purpose

The purposes of these Regulations are to:

- (a) Further the safe and orderly development of the City;
- (b) Promote sustainable design and development that supports long-term economic vitality and ecologic integrity;
- (c) Achieve a high-quality and sustainable site appearance that conserves and protects natural resource systems, helps to reduce infrastructure costs, and conserves energy;
- (d) Encourage site design techniques that protect water quality and natural hydrology, prevent increases in the quantity of stormwater runoff, and manage stormwater runoff at the source;
- (e) Protect abutters against hazards, unsightliness, and nuisances detrimental to property values;
- (f) Insure that development of land is appropriate for the public and private services and facilities available;
- (g) Insure that pedestrian, bicycle, and vehicular circulation can be accommodated in a safe manner;
- (h) Preserve and enhance the historic and cultural character of the community.

Section 1.2 Applicability

1.2.1 Uses Requiring Site Plan Approval

Site Plans shall be submitted for Site Plan Review for any development or redevelopment of land within the municipal boundaries that includes one or more of the following:

- (a) Development or change or expansion of use of tracts for nonresidential uses or for multi-family dwelling units, which are defined as any structures containing more than 2 dwelling units, whether or not such development includes a subdivision or resubdivision of the site.

- (b) Residential development or redevelopment which, when completed, will have three (3) or more dwelling units regardless of whether the development involves a subdivision of land;
- (~~cb~~) Nonresidential development or redevelopment including alterations, additions or extensions (including the addition of a drive-through facility), ~~or new nonresidential uses that increase the amount of required off-street parking by five (5) or more spaces;~~
- (~~ed~~) The ~~proposed~~ addition of five (5) or more parking spaces.

1.2.2 Exemption of Small Projects

The Planning & Sustainability Director may determine that a proposed development is exempt from Site Plan Review if it meets all of the following three criteria:

- (a) There is no increase in building height or gross floor area; and
- (b) There is no reduction in the setback of any structure or vehicular service area from any property line; and
- (c) Lot coverage by impervious surfaces does not increase by more than 500 square feet.

1.2.3 Determination of Developments of Regional Impact

1. The Planning Board shall make a determination as to whether the proposed development has the potential for regional impact.
2. In determining whether a project has regional impact, the Planning Board may consider, but is not limited to the consideration of, such factors as: the relative size or number of dwelling units compared to the existing housing stock, the proximity to the borders of a neighboring community, transportation networks, anticipated emissions or environmental impacts such as light, noise, smoke, odors, or particles, the proximity to aquifers or surface waters which transcend municipal boundaries, water demand, and shared facilities such as schools, wastewater treatment plants, and solid waste disposal facilities or other criteria as allowed under NH State Law.

1.2.4 Other Local, State, and Federal Requirements

1. These Site Plan Review Regulations in no way relieve a developer, agent or individual from compliance with the Zoning Ordinance, Subdivision Rules and Regulations, Building Codes, Historic District Commission, standard construction plans and specifications of the Department of Public Works, or

any other federal, state and local ordinance, regulation, or code that pertains to the proposed development.

2. The Site Plan Review Agreement shall not be executed until all other required municipal approvals have been granted.

Article 2 Application and Review Process

Section 2.1 Planning Board Responsibilities

The Planning Board and the Site Plan Review Technical Advisory Committee (TAC) are responsible for the review of all Site Plan Review applications.

Section 2.2 Site Plan Review Technical Advisory Committee

2.2.1 Committee Composition

A Site Plan Review Technical Advisory Committee (TAC) is hereby established to assist and advise the Planning Board in reviewing Site Plan Review applications. The TAC shall consist of nine (9) members as follows:

- (a) The Planning & Sustainability Director or a representative of the Planning Department as designated by the Director (either of whom shall act as Chair);
- (b) Two (2) representatives of the Planning Department as designated by the Director;
- (c) The Director of Public Works or a representative of the Department of Public Works as designated by the Director;
- (d) Two (2) representatives from the Divisions of the Department of Public Works as designated by the Director of Public Works;
- (e) The Chief Building Inspector or a representative of the Inspection Department as designated by the Chief Building Inspector;
- (f) A representative of the Fire Department as designated by the Fire Chief;
- (g) A representative of the Police Department as designated by the Police Chief.

2.2.2 Technical Advisory Committee Responsibilities

The Site Plan Review Technical Advisory Committee (TAC) shall make recommendations to the Planning Board for approval or disapproval of all Site Plan Review applications.

Section 2.3 Technical Review and Assistance

1. The TAC or the Planning Board may request any additional information it deems necessary in order to find that the application satisfies the review standards.
2. The TAC or the Planning Board may request information or technical assistance from City staff, Boards, or Commissions, or from independent experts in any field. If the TAC or the Planning Board determines that it requires the assistance of independent consultants, the applicant shall agree in advance to fund or reimburse the City for all costs of engaging such consultants.
3. When the TAC or the Planning Board notifies the applicant of the need for technical assistance or additional information, then the time periods for review and approval of a Site Plan Review application shall be waived only upon written request by the applicant. In the event that such a request is not forthcoming, the Planning Board may deny the application.

Section 2.4 Preapplication Review

2.4.1 Preapplication Review – General

1. An applicant may request to meet with the Planning Board for preliminary nonbinding discussions of a proposal as provided herein. An applicant may request to meet with the Board for either Preliminary Conceptual Consultation or Design Review, or both. The preliminary conceptual consultation phase is mandatory for certain applications as stated in Section 2.4.2 below.
2. Discussions in the Preliminary Conceptual Consultation and Design Review Phases shall not bind either the applicant or the Board. Statements made by Planning Board members during either phase shall not be a basis for disqualifying said members or invalidating any action subsequently taken by the Board.
3. Preliminary review shall be separate and apart from formal consideration of an application for Site Plan Review, and the time limits for acting on a proposal shall not apply until a formal application has been submitted and has been determined by the Planning Board to be complete.

2.4.2 Preliminary Conceptual Consultation Phase

1. The applicant may request a meeting with the Planning Board to discuss a proposal in conceptual form. The preliminary conceptual consultation phase is mandatory for a site plan that meets any of the following criteria:

- (a) Includes the construction of 30,000 square feet or more gross floor area;
 - (b) Includes the creation of 20 or more dwelling units;
 - (c) Includes the construction of more than one principal structure on a single parcel.
- 2. A request for preliminary conceptual consultation accompanied by all plans and exhibits shall be submitted to the Planning Department at least 14 days prior to the date of a scheduled meeting of the Board via the City's online permitting system and in hard copy. The total number of hard copies required shall be determined by the Planning & Sustainability Director.
- 3. Preliminary conceptual consultation may occur only at formal meetings of the Planning Board. However, such discussions shall not be the subject of a public hearing, and formal notice of abutters and the public shall not be required.
- 4. Preliminary conceptual consultation shall be directed at review of the basic concept of the proposal and suggestions that might be of assistance in resolving problems with meeting requirements during final consideration. The Board and the applicant may discuss proposals in conceptual form only and in general terms such as the desirability of the proposed development type, scale, intensity and layout under the Master Plan.

2.4.3 Design Review Phase

- 1. The applicant may request to meet with the Board for nonbinding discussions of a potential application that involve more specific design and engineering details than in the preliminary conceptual consultation phase.
- 2. A request for design review accompanied by all plans and exhibits shall be submitted to the Planning Department at least 14 days prior to the date of a scheduled meeting of the Board via the City's online permitting system as well as in hard copy. The total number of hard copies required shall be determined by the Planning & Sustainability Director.
- 3. The request for design review shall include enough of the information listed in Section 2.5.3(1) and plans displaying enough of the information listed in Section 2.5.4(3) so that the Board is able to review the project. Detailed engineering of infrastructure and utilities are not required at the design review phase, but the information listed in Section 2.5.4(3) should be displayed in sufficient detail to enable the Board to understand the proposed project and identify potential issues and concerns.
- 4. At a regular meeting of the Planning Board, the Board shall determine if the request for design review includes sufficient information to allow the Board

to understand the project and identify potential issues and concerns, and shall vote on whether to accept the request for design review and to schedule a public hearing. If the Board determines that the request does not describe the proposed project in sufficient detail, it shall notify the applicant of the specific deficiencies that need to be addressed **before consideration of the application can continue.**

5. Design review discussions shall take place in a public hearing at a regularly scheduled meeting of the Planning Board, after notice to abutters, holders of conservation, preservation, or agricultural preservation restrictions, and the general public as required by State statute.
6. At any public meeting of the Planning Board, the Board may determine that the design review process of an application has ended and shall inform the applicant in writing within 10 days of such determination.

Section 2.5 Application Requirements

2.5.1 Applicant

An application for Site Plan Review shall be submitted by the owner or lessee of the parcel or parcels, or by the holder of an option or other contract for purchase or lease of the property. If the applicant is not the current owner, the application shall include a copy of the lease, option or other contract, and a written letter from the current property owner.

2.5.2 Applicant Responsibilities

The applicant shall be responsible for fulfilling the following responsibilities before a Site Plan Review Agreement will be executed.

1. The applicant shall submit a completed application via the City's online permitting system to the Planning Department along with the application fee, the Site Plan (see section 2.5.4 for plan specifications) and supporting documents and studies for review by the TAC. The number of hard copies required to be submitted shall be determined by the Planning & Sustainability Director.
2. After review of the application by the TAC, the applicant shall submit one (1) ~~twelve (12) hard copies~~ **and 1 digital copy** of the Site Plan (see section 2.5.4 for plan specifications) to the Planning Department including any revisions as requested by the TAC and supporting documents and studies.
3. The application shall be fully executed and signed, and shall provide evidence of ownership or legal authorization to represent the landowner.

4. The application shall be complete as submitted and provide adequate information for evaluation of the proposed site development.
5. The applicant shall pay any application fees and costs of advertising and providing notice to abutters.
6. The applicant shall appear and present the Site Plan before the TAC and also at the public hearing before the Planning Board.
7. The applicant shall provide technical information and expertise sufficient for evaluation of the application.
8. All application documents, plans, supporting documentation and other materials shall also be provided in digital Portable Document Format (PDF). Digital files shall be complete and exact copies of the corresponding paper submittals (e.g., ~~digital plans files~~ shall be ~~submitted to facilitate printing~~ at the same scale and sheet size as the paper copies). Applicants may submit additional digital files to assist in presentations at public hearings.

2.5.3 Site Plan Review Application Required Information

1. The following information shall be submitted with the Site Plan Review application:
 - (a) Complete form entitled “Site Plan Application Checklist”.
 - (b) Detailed statement that lists and describes “green” building components and systems, including, but not limited to, whether the project is certifiable as demonstrated by a completed LEED (Leadership in Energy and Environmental Design) checklist. For example, building orientation, HVAC efficiencies, reductions in water usage, landscaping, source of building materials, production of on-site electricity, on-site rainwater recovery systems, energy efficient lighting, “cool” roof products, “green” refrigerant and plumbing systems, and energy efficient windows.
 - (c) Existing and proposed gross floor area and dimensions of all buildings and statement of uses and floor area for each floor.
 - (d) Tax map and lot number, and current zoning of all parcels under Site Plan Review.
 - (e) Owner’s name, address, telephone number, and signature. Name, address, and telephone number of applicant if different from owner.

- (f) Names and addresses (including Tax Map and Lot number and zoning districts) of all direct abutting property owners (including properties located across abutting streets) and holders of existing conservation, preservation or agricultural preservation restrictions affecting the subject property.
 - (g) Names, addresses and telephone numbers of all professionals involved in the site plan design.
 - (h) List of reference plans.
 - (i) List of names and contact information of all public or private utilities servicing the site.
2. As part of final approval of the site plan by the Planning Board, the applicant shall submit the following.
- (a) All local approvals, permits, easements and licenses required, including but not limited to:
 - Waivers;
 - Driveway permits;
 - Special exceptions;
 - Variances granted;
 - Easements;
 - Licenses.
 - (b) Any exhibits, data, reports or studies that may have been required as part of the approval process, including but not limited to:
 - Calculations relating to stormwater runoff;
 - Information on composition and quantity of water demand and wastewater generated;
 - Information on air, water or land pollutants to be discharged, including standards, quantity, treatment and/or controls;
 - Estimates of traffic generation and counts pre- and post-construction;
 - Estimates of noise generation;
 - A Stormwater Management and Erosion Control Plan;
 - Endangered species and archaeological / historical studies;
 - Wetland and water body (coastal and inland) delineations;
 - Environmental impact studies.
 - (c) Amendments and any conditions for final Site Plan approval as modified from the original Site Plan Review application submittal.

These should be annotated and highlighted on the final site plan in the index and on each affected plan sheet.

- (d) A document from each of the required private utility service providers indicating approval of the proposed site plan and indicating an ability to provide all required private utilities to the site.
- (e) A list of any required state and federal permit applications required for the project and the status of same.
- (f) For site plans that involve land designated as "Special Flood Hazard Areas" (SFHA) by the National Flood Insurance Program (NFIP) confirmation that all necessary permits have been received from those governmental agencies from which approval is required by Federal or State law, including Section 404 of the Federal Water Pollution Control Act Amendments of 1972, 33 U.S.C. 1334.

2.5.4 Site Plan Specifications and Required Exhibits and Data

1. Plan sheets submitted as part of the Site Plan Review application process shall meet the following specifications:
 - (a) Full size plans shall not be larger than ~~11 22~~ inches by ~~17 34~~ inches with match lines as required, unless approved by the Planning & Sustainability Director;
 - (b) Scale: Not less than 1 inch = 60 feet and a graphic bar scale shall be included on all plans;
 - (c) GIS data should be referenced to the coordinate system New Hampshire State Plane, NAD83 (1996), with units in feet;
 - (d) Plans ~~depicting all required information~~ shall be drawn to scale and shall be prepared and stamped by a NH licensed civil engineer, ~~÷with boundary and related information prepared and stamped by a NH licensed land surveyor~~;
 - (e) Wetlands shall be delineated by a NH certified wetlands scientist and so stamped.
2. The following information is required on all sheets of the plan set submitted as part of the application process:
 - (a) Title (name of development project), north point, scale, legend;
 - (b) Date plans first submitted and the date and explanation of all revisions;

- (c) Individual plan sheet title that clearly describes the information that is displayed;
 - (d) Source and date of data displayed on the plan;
 - (e) A note shall be provided on the Site Plan stating: “All conditions on this Plan shall remain in effect in perpetuity pursuant to the requirements of the Site Plan Review Regulations.”
3. Plans displaying the following information shall be submitted as part of the Site Plan Review application process. Where possible, the information on each plan should be grouped according to the review standards outlined in Articles 3 through 11 of these regulations.
- (a) Existing Conditions
 - Surveyed plan of the site showing existing natural and built features.
 - Existing building footprints and gross floor area.
 - Existing parking areas and number of parking spaces provided.
 - Zoning district boundaries.
 - Existing, required, and proposed dimensional zoning requirements including building and open space coverage, yards and/or setbacks, and dwelling units per acre.
 - Existing impervious and disturbed areas.
 - Limits and type of existing vegetation.
 - Wetland delineation, wetland function and value assessment (including vernal pools).
 - Special Flood Hazard Areas (SFHA), the 100-year flood elevation line, and Base Flood Elevation (BFE) data, as required.
 - (b) Buildings and Structures
 - Plan view of all buildings and/or structures indicating their use, size, dimensions, location and first floor elevation, footings, overhangs and snow dams.
 - Elevations of building(s) indicating their height, massing, placement, materials, lighting and façade treatments.
 - Total floor area.
 - Number of usable floors.
 - Gross floor area by floor and use.
 - (c) Access and Circulation
 - The location and width of accessways within the site.

- The location of curbing, rights-of-way, edge of pavement and sidewalks.
- The location, type, size and design of proposed traffic signing and traffic signal equipment including conduits and pavement markings on and off-site.
- Names and layout of existing abutting streets (including paper streets).
- Driveway curb cuts for abutting properties and for any adjacent properties that front on public roads that provide access to the site.
- If a subdivision, then right-of-way lines and names of all proposed streets, accessways, lanes, right-of-ways or easements and licenses intended to be dedicated for public use.
- Use current AASHTO truck turning templates descriptions with the minimum vehicle allowed being a WB-50, unless otherwise approved by the TAC.

(d) Parking and Loading

- The location of off-street parking and loading areas with the layout of the parking spaces and landscaped areas and buffers.
- Parking calculations showing number required and number provided.

(e) Water Infrastructure

- The size, type, and proposed location of water mains, shut-offs, hydrants, gate boxes, valves, and other water facilities with all necessary engineering data.
- Location of water wells and monitoring wells including protective radii and reserve areas and distance to seasonal high water.

(f) Sewer Infrastructure

- The size, type and proposed location of sanitary sewage facilities with all necessary engineering data including any onsite temporary facilities during construction period.

(g) Utilities

- The size, type, and location of all above ground and underground public service connections and private service connections; including gas lines, power lines, telephone lines, other communication lines and fire alarm connections.
- Size, type, and location of generator pads, transformers, pad mounted condensers, and other electrical or mechanical bases or fixtures.

(h) Solid Waste Facilities

- The size, type, and location of solid waste disposal facilities.
- (i) Stormwater Management
- The location, elevation, and layout of surface and subsurface stormwater drainage system features including design and sizing details for proposed stormwater treatment measures.
 - Location of any onsite snow storage areas and/or proposed off-site snow removal provisions.
 - Locations and containment measures for any salt storage facilities, if applicable.
 - Location of proposed temporary and permanent material storage locations and distance from wetlands, water bodies, and stormwater structures.
- (j) Outdoor Lighting
- The type and placement of outdoor lighting fixtures for the exterior of the buildings, parking areas, and any other areas of the site, and photometric plan.
- (k) Landscaping
- Landscaping plan identifying dimensions of the undisturbed area, existing vegetation, all vegetation to be retained, and measures used to protect natural features to be retained.
 - Location of any landscaping irrigation systems and water source.
- (l) Contours and Elevations
- Existing and proposed contours (2-foot minimum) and finished grade elevations.
- (m) Open Space
- Type, extent, and location of existing and proposed open space.
- (n) All easements, deed restrictions and non-public rights of ways.
- (o) Any other information that the TAC or the Planning Board may require in order to adequately evaluate the proposed development.
- (p) For sites within a Character District or Civic District, the following additional information shall be included in the plan set:
- Applicable building height standards (Zoning Ordinance, Sec. 10.5A21.20 and 10.5A43.30, and Regulating Plan) and proposed building height.
 - Applicable special requirements (Zoning Ordinance, Sec. 10.5A21.30 and Regulating Plan), if any, and demonstration of compliance.

- Proposed building form and building type (Zoning Ordinance, Sec. 10.5A43).
 - Proposed community space, if applicable (Zoning Ordinance, Sec. 10.5A46).
- (q) For sites that involve land designated as “Special Flood Hazard Areas” (SFHA) by the National Flood Insurance Program (NFIP), the site plan set shall include sufficient evidence (construction drawings, grading and land treatment plans) so as to allow a determination that:
- (i) The proposed development is consistent with the need to minimize flood damage;
 - (ii) All public utilities and facilities, such as sewer, gas, electrical and water systems, are located and construction to minimize or eliminate flood damage; and
 - (iii) Adequate drainage is provided so as to reduce exposure to flood hazards.
4. For any of the Site Plan Review requirements listed above or as detailed in Articles 3 through 11 of these regulations, the applicant shall submit either the requested information or request a waiver from the Planning Board according to the requirements of Section 2.10 of these regulations.

Section 2.6 Referrals to City Departments

The Planning & Sustainability Director shall refer applications to other City departments as follows:

1. Applications that involve proposed food service establishments shall be referred to the Health Department.
2. Applications that involve the creation of new dwelling units shall be referred to the School Department

Section 2.7 Public Hearing

1. A public hearing by the TAC will be held for all Site Plan Review applications.
2. Within thirty (30) days of receipt of a recommendation from the TAC, the Planning Board shall place the application on its agenda for a public hearing.
3. In accordance with NH State Law, the following parties shall be given at least ten (10) days’ notice of the public hearing at which Site Plan Review will occur:

- (a) Direct abutters;
 - (b) Holders of conservation, preservation or agricultural preservation restrictions on the property.
- 4. The general public shall be notified by posting a copy of the written notice at least ten (10) days in advance of the public hearing at two public places and by printing a notice in a newspaper of general circulation.
 - 5. Notices shall include a general description of the proposed development, the name of the applicant, the location of the property which is to be developed and the time, date and place of the meeting or public hearing.
 - 6. When computing the period for notification, the day of mailing, posting or publication and the day of the meeting shall not be counted.
 - 7. All costs of notice, whether mailed, posted or published, shall be paid by the applicant.
 - 8. At the public hearing, any applicant, abutter, or individual may testify in person or in writing.
 - 9. The Planning Board may deny an application for Site Plan Review without a public hearing, based upon failure of the applicant to supply information required by these regulations, failure to meet deadlines established by the Planning Board, or failure to pay costs of the notice or other fees required by the Planning Board.

Section 2.8 Determination of Application Completeness

- 1. Upon submission of a formal application for Site Plan Review, the Planning Board shall hold a public hearing on the application, with notice to abutters and the public as required by State statute, and shall determine if the application is complete according to these Regulations and shall vote upon its acceptance.
- 2. If the Board determines that a submitted application is incomplete according to these Regulations, the Board shall notify the applicant of the determination in accordance with RSA 676:3, which shall describe the information, procedure, or other requirement necessary for the application to be complete.
- 3. Upon determination by the Board that a submitted application is complete according to these Regulations, the Board shall begin formal consideration

and shall act to approve, conditionally approve, or disapprove within 65 days, subject to extension or waiver as provided by State statute.

Section 2.9 Evaluation Criteria

In order to grant site plan review approval, the TAC and the Planning Board shall find that the application satisfies evaluation criteria pursuant to NH State Law and listed herein. In making a finding, the TAC and the Planning Board shall consider all standards provided in Articles 3 through 11 of these regulations.

1. Compliance with all City Ordinances and Codes and these regulations.
2. Provision for the safe development, change or expansion of use of the site.
3. Adequate erosion control and stormwater management practices and other mitigative measures, if needed, to prevent adverse effects on downstream water quality and flooding of the property or that of another.
4. Adequate protection for the quality of groundwater.
5. Adequate and reliable water supply sources.
6. Adequate and reliable sewage disposal facilities, lines, and connections.
7. Absence of undesirable and preventable elements of pollution such as smoke, soot, particulates, odor, wastewater, stormwater, sedimentation or any other discharge into the environment which might prove harmful to persons, structures, or adjacent properties.
8. Adequate provision for fire safety, prevention and control.
9. Adequate protection of natural features such as, but not limited to, wetlands.
10. Adequate protection of historical features on the site.
11. Adequate management of the volume and flow of traffic on the site and adequate traffic controls to protect public safety and prevent traffic congestion.
12. Adequate traffic controls and traffic management measures to prevent an unacceptable increase in safety hazards and traffic congestion off-site.
13. Adequate insulation from external noise sources.

14. Existing municipal solid waste disposal, police, emergency medical, and other municipal services and facilities adequate to handle any new demands on infrastructure or services created by the project.
15. Provision of usable and functional open spaces of adequate proportions, including needed recreational facilities that can reasonably be provided on the site.
16. Adequate layout and coordination of on-site accessways and sidewalks in relationship to off-site existing or planned streets, accessways, bicycle paths, and sidewalks.
17. Demonstration that the land indicated on plans submitted with the application shall be of such character that it can be used for building purposes without danger to health.
18. Adequate quantities, type or arrangement of landscaping and open space for the provision of visual, noise and air pollution buffers.
19. Compliance with applicable City approved design standards.

Section 2.10 Waiver Requests

1. When the Planning Board finds by a vote of six members that a waiver will not have the effect of nullifying the spirit and intent of the City's Master Plan or these regulations, it may grant a waiver following a written request by the Applicant.
2. In granting waivers the Planning Board may require such conditions as will in its judgment secure the objectives of the regulations.

Section 2.11 Approval Procedures

1. Recommendations of the TAC for approval shall require a majority of those present and voting. Five voting members shall constitute a quorum for the transaction of business.
2. Once the TAC has made a recommendation to the Planning Board and a public hearing has been held, final approval shall require a vote by the majority of those Planning Board members present and voting.
3. If the TAC or the Planning Board determines that the proposed site plan does not meet all of the applicable requirements, the TAC or the Planning Board shall vote to disapprove the plan.

4. The reasons for disapproval will be clearly stated in the Planning Board's records and shall be communicated to the applicant in writing.
5. Approval of the site plan shall not be effective until a site plan agreement has been signed (see Section 2.12) and the applicable sheets of the site plan have been recorded at the Rockingham County Registry of Deeds (see Section 2.13).

Section 2.12 Site Plan Review Agreement

1. A Site Plan Review Agreement to ensure the site is developed in accordance with the approved plan shall be drafted for all approved site plans. Terms and conditions of the Site Plan Review Agreement shall indicate any stipulation or condition which may be necessary to secure the public health, safety, and welfare and insure compliance with all of the ordinances of the City of Portsmouth, all applicable state and local regulations, and requirements of the Building Code to insure that all site development and construction is completed according to the Plan approved. A security shall be provided in a form and amount approved by the City.
2. The Site Plan Review Agreement shall be considered fully executed when the Agreement has been endorsed by the owner of the property and the Planning & Sustainability Director, and when the security has been approved by the City Attorney and placed on file with the Planning Department.

Section 2.13 Recording of Site Plans

1. An approved site plan shall be signed by the Planning Board Chairperson (or designee) and shall be recorded at the Rockingham County Registry of Deeds (RCRD). Site plans are not valid until recorded at the Registry of Deeds.
 - (a) For the purpose of this requirement, only those sheets in the approved plan set which are intended to show the layout and arrangement of on-site vehicular and pedestrian circulation, off-street parking, and/or landscaping and screening shall typically be required to be recorded.
 - (b) Notwithstanding the above, the Planning Board may require the recording of additional plan sheets or supporting documentation if the Board determines that such recording is necessary to ensure continued compliance with the conditions shown on the plans. Examples include plans showing specific measures designed to protect wetlands or manage stormwater.
2. The applicant shall submit to the Planning Department the following:

- (a) One (1) hard copy and one (1) electronic file uploaded to the City's online permitting system of the final site plan incorporating any changes that have been required as a condition of the Planning Board vote;
 - (b) One original Mylar of the sheets from the final site plan that are required to be recorded at the RCRD.
- 3. The plan sheet(s) submitted for recording shall include the following notes:
 - “1. This Site Plan shall be recorded in the Rockingham County Registry of Deeds.
 - 2. All improvements shown on this Site Plan shall be constructed and maintained in accordance with the Plan by the property owner and all future property owners. No changes shall be made to this Site Plan without the express approval of the Portsmouth Planning & Sustainability Director.”
- 4. An amended site plan shall be recorded at the RCRD as above, provided that in the case of a plan amendment that is granted approval by the Planning & Sustainability Director or TAC without a hearing before the Planning Board, the recording of a notice of approval shall be sufficient unless otherwise determined by the Planning & Sustainability Director.
- 5. The applicant shall have the required site plans pre-approved by the Registry of Deeds prior to submitting mylars to the Planning Department for signature and recording.

Section 2.14 Approval Expiration and Extension

- 1. Site plan approval by the Planning Board shall expire unless used (obtain a Building Permit) within a period of one (1) year from the date granted.
- 2. The Planning Board may, for good cause shown, extend such period by as much as one (1) year if requested and acted upon prior to the expiration date.
- 3. If additional one (1) year extensions are requested, the owner will be required to have the previously approved plans reviewed by the TAC and the Planning Board. For this review the owner shall provide to the Planning Department the previously approved plans and supporting data.
- 4. Upon review of a request for an extension, the Planning Board shall have the authority to amend or deny a previously approved application. This review shall not require an application fee; however, the Planning Board

and/or TAC may, if deemed necessary by either chair, conduct a public hearing at the owner's expense.

5. A time extension shall be granted if determined that no change has taken place that would materially affect the currently approved site plan in regard to:
 - (a) Traffic flow, volume, or congestion;
 - (b) Pedestrian safety;
 - (c) Drainage;
 - (d) Water availability;
 - (e) Sewer capacity;
 - (f) Design standards;
 - (g) Landscape elements; and
 - (h) Zoning compliance.
6. The Planning Board shall not deny a request for an extension without first having held a public hearing.

Section 2.15 Post Approval Procedures

2.15.1 Amendments

After approval of the site plan the owner may request, in writing, approval of minor amendments. The Planning & Sustainability Director may approve the amendment in writing or may require review by the TAC or the Planning Board.

2.15.2 Landscape Markings

Once a site plan has been approved and prior to the signing of the Site Plan Review Agreement, the applicant shall tag or otherwise identify at the site all vegetation and natural features to be retained as shown on the approved site plan.

2.15.3 Construction Management and Mitigation Plan

1. The Planning Board, as a condition of approval, may require a Construction Management and Mitigation Plan (CMMP). If such a plan is required, no site work is authorized nor shall work commence before the Plan has been accepted and approved as to content and form by the City.
2. If the Planning Board requires completion of a CMMP all activities on the site shall be in full compliance with the CMMP.

2.15.4 Recording of Plans and Documents

Once a site plan has been approved and prior to the signing of the Site Plan Review Agreement, owner shall submit to the Planning & Sustainability Director documents showing all easements, licenses, rights-of-way, and maintenance agreements in a recordable format.

2.15.5 Submittal of a Land Use Development Tracking Form

The Applicant or its engineer shall submit a copy of a completed Land Use Development Tracking Form using the Pollutant Tracking and Accounting Program (PTAP) online portal currently managed by the UNH Stormwater Center or similar form approved by the City.

Section 2.16 Project Inspection and Completion

2.16.1 Compliance and Enforcement

During construction and upon completion of the project, the Planning Board may require routine inspections to insure compliance with the approved site plan. Such inspections shall be performed by an oversight engineer or other licensed or certified professional at the expense of the applicant.

2.16.2 Final Inspection

1. Prior to the completion of the project, the applicant shall notify the Planning & Sustainability Director that the project is ready for final inspection.
2. All stormwater detention and/or treatment devices constructed onsite shall be certified by a qualified engineer as being built in accordance with approved site plans with a letter of certification submitted to the City Engineer.

2.16.3 As-Built Plan

1. At the completion of the project, the applicant shall submit to the Planning & Sustainability Director an “as-built plan” which shall include all surface and subsurface features, easements, licenses, rights-of-way, and maintenance agreements. The plan shall be prepared and stamped by a New Hampshire licensed land surveyor.
2. The applicant shall provide a digital version of the as-built plan. The purpose of the digital plan is to aid in updating the City’s geographic information system (GIS). The City respects the copyright interests of the applicant’s representatives and requires only factual, not expressive, data. The digital plan shall meet the requirements outlined in Attachment A.
3. The Planning & Sustainability Director may waive the requirement for an as-built plan.

2.16.4 Release of Performance Security

1. The Planning & Sustainability Director and City Attorney may order release of the performance security only after receipt of the Building Inspector's Certificate of Occupancy, the as-built plan, final inspections and completion of all required conditions of approval as required by the Planning Board.
2. If necessary, the Planning & Sustainability Director and City Attorney may order a partial release of the performance security, but no more than one partial release shall be permitted.

2.16.5 Long-Term Maintenance

The property owner shall maintain the property to comply with the approved site plan and shall fulfill all reporting requirements stipulated in the site plan review approval.

Section 2.17 Exemption of Approved Site Plan from Changes in Land Use Regulations

1. Under State statute (RSA 674:39), approved site plans are protected from future changes in regulations and ordinances as follows:
 - (a) A site plan that has been approved by the Planning Board shall be exempt from all subsequent changes in site plan regulations and zoning ordinances (except those regulations and ordinances which expressly protect public health standards, such as water quality and sewage treatment requirements) for a period of 4 years after the date of approval of the site plan by the Planning Board, provided that:
 - (1) Active and substantial development or building has begun on the site by the owner or the owner's successor in interest in accordance with the approved plans within 12 months after the date of approval, or in accordance with the terms of the approval, and any required site plan security is provided to the City at the time of commencement of such development; and
 - (2) The development remains in full compliance with the public health regulations and ordinances of the City of Portsmouth; and
 - (3) At the time of approval, the site plan conforms to the site plan regulations and zoning ordinances then in effect at the site of such plan.

- (b) Once substantial completion of the improvements as shown on the site plans has occurred in compliance with the approved site plans or the terms of said approval, or unless otherwise stipulated by the Planning Board, no subsequent changes in these Site Plan Review Regulations or the Zoning Ordinance shall operate to affect such improvements.
- 2. In the absence of a specific finding by the Planning Board, the following terms are defined for the purpose of determining exempting a project from subsequent amendments to local land use regulations:
 - (a) “Active and substantial development or building” shall mean the completion of all of the following in accordance with the approved plans:
 - (1) Installation and maintenance of erosion control measures; and
 - (2) Construction of all drainage improvements to service the development, including all detention/retention basins, treatment swales, pipes, underdrains, catch basins, etc.; and
 - (3) Construction of all roadways, accessways, etc. to a minimum of gravel base; and
 - (4) Construction and/or installation of all utilities ready for connection to proposed buildings and structures; and
 - (5) Construction of at least one building foundation or 20% of the total building foundations on the site, whichever is greater; and
 - (6) Review and approval of items (1) through (5) by the Department of Public Works or designated agent.

Site clearing, excavation or earth movement without completion of items (1) through (6) above shall not be considered “active and substantial development.” A plan approved in phases shall be subject to this definition only for the phase currently being developed.

- 2. “Substantial completion of the improvements as shown on the site plan” is defined as the establishment of all on-site and off-site improvements specified in the site plan approval, except for those improvements which are specifically deferred by recorded vote of the Planning Board prior to the expiration of the four (4) year period specified in RSA 674:39. To the extent that the Planning Board calls a bond or other security for such improvements and the funds are paid to the City, substantial completion of the improvements in the subdivision shall be deemed to have occurred.

Article 3 Vehicular Circulation Standards

Section 3.1 General Provisions

1. All site development shall be designed and constructed to consider the safety, interests and convenience of all users – drivers, bicyclists, transit users and pedestrians of all ages and abilities.
2. All site plans shall portray the design of every element of vehicular circulation that provides access in and around the site, unless otherwise specified. The Planning Board may require that work involving areas of special sensitivity or significance be conducted by a traffic engineer licensed in New Hampshire.

Section 3.2 Off-Site Impacts

1. The applicant is responsible for assessing the impact of the proposed development on traffic patterns and vehicular circulation systems. The TAC and/or the Planning Board may require that a traffic study be performed and that a technical expert may be hired to review any traffic analysis performed by the applicant.
2. A traffic impact analysis shall be prepared by a professional engineer licensed in New Hampshire and experienced and qualified in traffic engineering, and shall contain the following information:
 - (a) Existing traffic conditions on streets and intersections adjacent to the site, including daily and peak-hour traffic volumes, seasonally adjusted as determined by the TAC;
 - (b) Projected traffic conditions on adjacent streets for the design year of occupancy and for the tenth year following occupancy or such longer period as the TAC or Planning Board determines applicable based on the scale of the project;
 - (c) Projected impacts of the proposed development including:
 - total daily and peak-hour traffic entering and exiting the site
 - turning movements
 - estimates of induced vs. pass-by trips;
 - (d) A proposed plan to mitigate the projected impacts of the development.
3. Projects shall be designed to maintain, and where possible enhance, the quality of vehicular, bicycle and pedestrian circulation and safety on affected public streets.

4. The applicant shall provide traffic signal equipment, traffic signs, travel lanes, pavement widening, markings, sidewalks, and other improvements to existing streets upon determination by the Planning Board that the specific improvements are necessary for safe handling of traffic generated by the proposed development.
5. Projects having access onto congested public streets may be required to eliminate certain turning movements as determined necessary and practical by the Planning Board.

Section 3.3 General Accessway and Driveway Design

3.3.1 General Requirements

1. The internal network of accessways and driveways shall:
 - (a) Provide for the safe, efficient and orderly movement of all modes of transportation, including vehicles, public transit, bikes and pedestrians;
 - (b) Be designed to meet, but not exceed, the needs of the present and projected population served by the site, and;
 - (c) Be designed to respect natural features and topography.
2. Accessways shall be designed based on the anticipated role within the project site of the accessway as defined by AASHTO road classifications and/or approved by the Planning Board.
3. A driveway permit from the Department of Public Works shall be required for all existing and new driveways accessing a street.

3.3.2 Accessway and Driveway Design and Location

1. Accessways and driveways shall, where practical, have an all-season safe sight distance (according to AASHTO standards) in both directions along the public street. Where only a lesser sight distance is obtainable, no more than one accessway per single parcel shall be allowed.
2. Accessways and driveways shall be located no closer than fifty (50) feet to the curb line of an intersecting street.
3. Driveways shall be limited to one per lot.

3.3.3 Travel Lanes

Where multiple travel lanes are required, planted medians (designed in accordance with the landscaping standards in Article 6 herein) may be required at the discretion of the Planning Board to reduce the visual impact of pavement.

3.3.4 Shared Access

Shared driveways are encouraged and may be permitted between adjacent lots. In such cases, a joint access easement between the property owners may be required.

Section 3.4 Curbing

Granite curbing shall be installed per the Department of Public Works specifications in all of the following situations:

- (a) Where accessways and driveways meet public streets;
- (b) Where curbing is necessary to channelize surface drainage; and
- (c) Where otherwise required by the Planning Board.

Section 3.5 Traffic Calming and Connections

- 1. Internal accessway networks shall be designed to optimize public safety.
- 2. Traffic measures shall be implemented to support the overall interconnectedness and coherence of the City's public street system.

Section 3.6 Drive-Through Facilities

3.6.1 Site Access and Circulation Standards

- 1. The internal entrance into the drive-through lane shall not conflict with the general access to the site.
- 2. The distance from any transaction window to the site exit shall be a minimum of sixty (60) feet.
- 3. Where a turn in the drive-through lane is required between a transaction window and the site exit, the distance from the transaction window to the beginning of the turn shall be a minimum of forty (40) feet with an internal minimum turning radius of seventeen (17) feet.

3.6.2 Stacking Lanes and Spaces

1. Stacking lanes shall be provided to prevent circulation congestion and conflicts, both within the site and on adjacent public streets. Stacking lanes shall be designed to separate drive-through traffic from other vehicular and pedestrian circulation.
2. Stacking lanes shall not conflict with or impede vehicular or pedestrian circulation within the site, access into or out of parking spaces, or access into buildings; and shall not interfere with required loading and trash storage areas.
3. Stacking lanes shall be at least 10 feet wide and stacking spaces shall be at least 20 feet in length.
4. The applicant must demonstrate that the number of stacking lanes and spaces proposed are sufficient for the intended use.
5. A bypass lane at least 11 feet wide shall be provided in order to permit vehicles to exit the site without using the drive-through lane(s).
6. Stacking lanes (not including bypass lanes) shall be set back 15 feet from the property line fronting on any public way, 15 feet from any side or rear property lines which abut non-residential properties, and 20 feet from any side or rear property lines which abut residential property.
7. Stacking lanes shall be integrated with the onsite circulation pattern, and shall not enter directly from a public right-of-way.
8. Stacking lanes shall be distinguished from traffic aisles, other stacking lanes and parking areas with striping, curbing, landscaping or the use of alternative paving materials or medians.
9. The intersection of stacking lanes and walk-in customer access shall be a minimum of fifty (50) feet from site entrances and exits and from transaction windows. Said intersections shall be provided with crosswalks delineated by patterned or contrasting paving and striping and shall include warning signage aimed at both the pedestrian and vehicle.

3.6.3 Traffic Impact Study

A traffic impact analysis conforming to the standards in Section 3.2 shall be submitted with any site plan review application containing a drive-through facility.

3.6.4 Noise Reduction

Sound pressure levels created by devices in the drive-through facility, including but not limited to speakers, shall comply with the standards for noise control in the Zoning Ordinance. Methods of communicating to patrons that do not require the use of speakers shall be used where feasible or where required by the Planning Board.

3.6.5 Screening

1. Drive-through lanes, stacking spaces and bypass lanes that would be visible from a public right-of-way or from land in a Residential or Mixed Residential zoning district shall be screened from view to at least three feet above grade.
2. Screening shall be with brick or stone walls, berms, or equivalent structures approved by the Planning Board. Walls, berms and other screening structures shall be supplemented by plantings such as shrubs and trees.
3. Notwithstanding the above, drive-through facilities need not be screened from a public right-of-way if (a) the right-of-way is more than 100 feet from the drive-through facility and (b) the Planning Board determines that existing or proposed topography or landscaping will provide adequate visual relief and prevention of glare.

Section 3.7 Loading and Service Areas

3.7.1 Location

1. Loading and services areas shall not be located between the front property line and any building or structure nor in the required side yard or rear yard areas.
2. No off-street loading or maneuvering areas shall be nearer than 100 feet to any adjoining Residential or Mixed Residential Zoning Districts.
3. All such areas shall be screened in accordance with Article 6 of these regulations.
4. No off-street loading areas shall be a part of an area used to satisfy the off-street parking requirements of the Zoning Ordinance.

3.7.2 Design Standards

Loading areas and accessways to loading areas shall have a durable surface (whether pervious or impervious) that meets the load bearing capacity of the project, minimizes dust, material tracking and erosion, and facilitates snow removal.

3.7.3 Required Loading Areas

The Planning Board may require one or more loading areas where the scale or nature of the proposed use is expected to generate regular delivery, moving, service, or freight activity.

In determining the need for loading facilities, consideration shall be given to:

1. Building size;
2. Nature of the proposed use;
3. Frequency and type of deliveries;
4. Availability of on-street loading opportunities;
5. Internal circulation and site constraints; and
6. Potential impacts on neighboring properties and public streets.

Section 3.8 Fire Lanes

1. Fire lanes shall be provided in accordance with the City's Emergency Lanes Ordinance.
2. Fire lanes may be required to be within 30 feet of a building if deemed necessary by the TAC. A minimum of 5 foot wide unobstructed pathway shall be provided through all barriers, including rows of parked cars.
3. Fire lane and access easements shall be provided to serve all buildings and any areas deemed necessary for emergency vehicle access.
4. Required "NO PARKING FIRE LANE" signs shall be 12 inches wide and 18 inches high. Signs shall be painted on a white background with letters and borders in red, using not less than 2 inches lettering. Signs shall be permanently affixed to a stationary post and the bottom of the sign shall be six (6) feet, six (6) inches above finished grade. Signs shall be spaced not more than one hundred (100) feet apart. Signs may be installed on permanent buildings or walls or as approved by the TAC.
5. Pavement marking lines shall be painted in red traffic paint, six (6) inches in width to show the boundaries of the fire lane. The words "NO PARKING FIRE LANE" shall appear in four (4) inch white letters at 25 foot intervals on the red border markings along both sides of the fire lanes.

6. Curb marking shall be painted in red traffic paint from the top seam of the curb to a point even with the driving surface. The words “NO PARKING FIRE LANE” shall appear in four (4) inch white letters at 25 feet intervals along the curb(s).
7. All fire lanes shall be maintained and kept in a good state of repair at all times by the owner.

Section 3.9 Mass Transit Facilities

Mass transit facilities shall be incorporated at the discretion of the Planning Board based on future transit system needs. Transit routes, access points and shelter locations shall be addressed along major streets or accessways within and on the perimeter of such projects. Transit facilities shall be provided in a manner to make transit an attractive mode of travel for both employees and patrons.

Article 4 Parking Area Standards

Section 4.1 ~~Parking Provision~~

~~The number of parking spaces required, parking facility setbacks, and location of parking facilities shall be in accordance with the off-street parking standards in the Zoning Ordinance.~~

Section 4.1 General Provisions

1. This Article establishes the number of required and allowed off-street parking spaces for development subject to these Regulations, together with provisions for shared/off-site parking, reserve parking, bicycle parking, electric-vehicle parking, maximum parking, and alternative compliance mechanisms.
2. All new buildings and structures, as well as additions to or changes in use or intensification of use in existing buildings and structures, shall be provided with off-street parking spaces in accordance with this Section.
3. A use that is nonconforming as to the requirements for off-street parking shall not be enlarged or altered unless off-street parking is provided for the original building, structure or uses and all expansions, intensifications or additions sufficient to satisfy the requirements of this Section.

Section 4.2 Number of Required Parking Spaces

1. The number of required off-street parking spaces shall be the sum of the requirements for the various individual uses on a lot computed separately.
2. Where the computation of required off-street parking spaces results in a fractional number, the computation shall be rounded up to the next whole number.
3. Parking spaces occupied by EV chargers and supporting equipment may count towards minimum parking requirements.

4.2.1 Residential Uses

Use	Minimum Parking Requirement
Dwelling unit 500 sq. ft. or less	0.5 spaces per unit
Dwelling unit greater than 500 sq. ft.	1.0 space per unit
Coliving Facility within 600 feet of a public parking garage	No parking required
Coliving Facility not within 600 feet of a public parking garage	1 space per 4 coliving units

4.2.2 Nonresidential Uses

Use Category	Examples	Minimum Parking Requirement
Office and Professional Services	Offices, financial services, government offices, business services	1 space per 350 sq. ft. GFA
Medical Uses	Medical offices, dental offices, outpatient clinics	1 space per 250 sq. ft. GFA
Retail Sales and Consumer Services	Retail stores, personal services, salons, pharmacies	1 space per 300 sq. ft. GFA
Restaurants and Drinking Establishments	Restaurants, cafes, taverns, breweries, bars	1 space per 100 sq. ft. GFA
Child Care and Educational Uses	Day care centers, nursery schools, educational facilities, tutoring centers	1 space per employee on the largest shift
Recreation, Entertainment and Assembly Uses	Fitness centers, theaters, clubs, museums, recreation facilities	1 space per 250 sq. ft. GFA, or parking demand analysis
Lodging Uses	Hotels, inns, motels, bed and breakfasts	1.25 spaces per guest room
Industrial, Research and Production Uses	Manufacturing, research and development, laboratories	1 space per 750 sq. ft. GFA
Warehouse, Distribution and Wholesale Uses	Warehousing, distribution, storage, wholesale operations	1 space per 2,000 sq. ft. GFA
Residential Care and Assisted Living Facilities	Assisted living facilities, nursing homes, rehabilitation facilities, congregate care facilities	1 space per 3 beds, plus 1 space per employee on the largest shift

4.2.3 Unlisted Uses

1. Uses not specifically listed shall be assigned to the most similar parking category by the Planning & Sustainability Director based upon the nature of the proposed use and anticipated parking demand. Where a use is not reasonably comparable to an identified category, the Planning & Sustainability Director or the Planning Board may require a parking demand analysis.

4.2.4 Parking Demand Analysis

1. A parking demand analysis may be required for unlisted uses, mixed-use developments utilizing shared parking, requests for parking reductions or increases, or developments where the Planning Board determines that the minimum parking requirements may not accurately reflect anticipated demand.

4.2.5 Maximum Parking

1. For developments requiring more than twenty (20) parking spaces, the total number of spaces provided shall not exceed 120 percent of the minimum requirement unless otherwise approved by the Planning Board based upon a parking demand analysis.

4.2.6 Change of Use

1. Any change of use, change in occupancy, or intensification of use that increases the minimum parking requirement established by this Article shall require a parking compliance determination by the Planning & Sustainability Director.
2. Where the Planning & Sustainability Director determines that the proposed use does not comply with the parking requirements of this Article, the applicant may:
 1. Provide additional parking.
 2. Obtain approval of a parking modification pursuant to Section 4.3.
3. A change of use that does not increase the minimum parking requirement shall not require additional parking.

Section 4.3 Parking Flexibility

1. The purpose of this Section is to provide flexibility in the application of the parking requirements of this Article where strict compliance is not necessary to accommodate anticipated parking demand.

2. The Planning & Sustainability Director or Planning Board, as applicable, may approve modifications to the parking requirements of this Article, including:
 - a. Reduced parking requirements;
 - b. Shared parking;
 - c. Off-site parking;
 - d. Phased parking construction; and
 - e. Reserve parking areas.
3. Any request under this Section shall be supported by information demonstrating that parking demand will be adequately accommodated.
4. In evaluating a request for a parking modification, consideration may be given to:
 1. The characteristics of the proposed use;
 2. Existing parking supply;
 3. Availability of public parking facilities;
 4. Availability of on-street parking;
 5. Proximity to public transportation facilities;
 6. Walkability and accessibility of the site;
 7. Shared parking opportunities;
 8. Existing or historic parking utilization;
 9. Parking demand studies or other supporting information; and
 10. Any other site-specific factors affecting parking demand.

Section 4.3.1 Administrative Parking Modifications

1. The Planning & Sustainability Director may approve a parking modification associated with a change of use, change in occupancy, or intensification of use where no exterior site modifications are proposed.
2. In considering a request under this Section, the Planning & Sustainability Director may consider the factors identified above and any additional information submitted by the applicant regarding anticipated parking demand.
3. The Planning & Sustainability Director may approve, approve with conditions, or deny a parking modification upon a finding that:
 - a. The proposed parking supply will adequately accommodate anticipated parking demand; and
 - b. The proposed use will not create unreasonable parking impacts on adjacent properties or the public right-of-way.

4. The Planning & Sustainability Director may approve a reduction of up to four (4) parking spaces from the minimum parking requirement established by this Article. Parking modifications resulting in a reduction of five (5) or more spaces shall require Planning Board approval pursuant to Section 4.3.2.
5. The Planning & Sustainability Director may refer any application to the Planning Board where, in the Planning & Sustainability Director's judgment, the nature, scale, or anticipated parking impacts of the proposed use warrant Planning Board review.

4.3.2 Planning Board Approval

1. Parking modifications associated with applications requiring Site Plan Review shall be reviewed and approved by the Planning Board.

Section 4.4 Shared and Off-Site Parking

1. Shared parking may be approved where the applicant demonstrates that peak parking demand for the uses served will occur at different times or that the combined parking demand of multiple uses will be less than the sum of the individual parking requirements.
2. The Planning & Sustainability Director or Planning Board may require a parking demand analysis or other supporting documentation demonstrating that adequate parking will be available to serve the proposed uses.
3. Any off-site parking or shared parking arrangement involving separate properties shall be secured through a recorded agreement acceptable to the City.

Section 4.5 Reserve Parking

The Planning Board may permit construction of fewer parking spaces than otherwise required where sufficient land is reserved for future parking expansion.

The reserve parking area shall:

- a. Be shown on an approved site plan;
- b. Remain available for future parking use; and
- c. Not contain buildings or permanent site improvements that would prevent future parking construction.

Section 4.6 Location of Vehicular Use Facilities

4.6.1 General Standards

1. Required off-street parking spaces shall generally be located on the same lot as the principal use they are intended to serve.
2. The Planning Board may authorize required parking on a separate lot in accordance with Section 4.3.
3. In no case shall parking be permitted within a Residential or Mixed Residential District other than that which is accessory to a permitted principal use within the district.

4.6.2 Relationship to Buildings and Streets

1. Off-street parking areas, accessways, maneuvering areas, and traffic aisles shall be located and configured to:
 - a. Promote safe and efficient vehicular circulation;
 - b. Minimize conflicts between vehicles, pedestrians, and bicyclists;
 - c. Minimize visual impacts from public streets and adjacent properties;
 - d. Preserve opportunities for landscaping, stormwater management, and open space; and
 - e. Support the character and design objectives of the surrounding area.
2. Required off-street parking spaces shall not be located between a principal building and a public street, including on corner lots.
3. Parking areas shall be designed to maintain safe and convenient pedestrian connections between public sidewalks, parking areas, and building entrances.

4.6.3 Screening

1. Parking areas, accessways, maneuvering areas, and traffic aisles adjacent to residential properties shall be screened in accordance with Article 6.
2. Required landscaped setbacks and landscaped buffer areas shall not be used to satisfy required parking.

4.6.4 Modifications

The Planning & Sustainability Director or Planning Board may require modifications to the location, configuration, or design of parking areas, accessways, maneuvering areas, and traffic aisles where necessary to improve safety, circulation, pedestrian access, site design, or compatibility with surrounding development.

Section 4.7 Design of Off-Street Parking Facilities


1. The provisions of this Section shall apply to all off-street parking facilities, whether in parking structures or surface lots, and whether or not the parking spaces are required or in excess of the requirements for a use, except as specifically exempted herein.
2. Parking spaces and maneuvering aisles shall be laid out in compliance with the minimum dimensions set forth in the Table of Off-Street Parking Dimensions.

Table of Off-Street Parking Dimensions

A Angle of Parking (degrees)	B Width of Parking Space	C Depth of Parking Space	D Width of Maneuvering Aisle *	
			1-way traffic	2-way traffic
0°	8.5'	20'	14'	24'
45°	8.5'	19'	16'	24'
60°	8.5'	19'	18'	24'
90°	8.5'	19'	24'	24'

* The minimum width of a maneuvering aisle shall be 22 feet for (a) an aisle for 2-way traffic providing access to fewer than 7 parking spaces, or (b) an aisle in a parking structure for 2-way traffic, or (c) an aisle in a parking structure for 1-way traffic with 90-degree parking.

Key to Table of Off-Street Parking Dimensions



- Parking areas shall include parking spaces for the physically disabled in compliance with the Building Code and *Accessible and Usable Buildings and Facilities* (ICC/ANSI A117.1 latest edition).
- Parking spaces located within four feet of an abutting structure, sidewalk, or public street shall be designed with suitable bumper stops.
- Parking areas and access drives shall be surfaced with a durable surface that meets the load bearing maximum occupancy of the project;

minimizes dust, material tracking and erosion; and facilitates snow removal. Examples of such materials include, but are not limited to, bituminous binder, concrete, asphalt, compacted gravel and crushed stone. Pervious surfaces may be used provided that they meet the above objectives and provide equivalent protection of surface and groundwater resources.

6. All off-street parking spaces shall be marked and maintained to provide delineation between parking stalls and aisles.
7. All off-street parking areas shall be designed so that:
 - (a) Vehicles can enter and leave each parking space without passing over any other parking space or requiring the moving of any other vehicle, and
 - (b) Vehicles can enter and leave the parking area without backing into or from a public street or way.
8. Notwithstanding the previous provision, tandem parking spaces may be provided for required off-street parking spaces serving dwelling units in residential and mixed-use developments, subject to the following requirements:
 - a. Tandem spaces are assigned to the same dwelling unit;
 - b. Tandem parking is not used for visitor parking; and
 - c. Tandem spaces have minimum dimensions of 9 feet by 38 feet.
9. All off-street parking areas shall incorporate the following provisions for pedestrian circulation:
 - (a) A minimum 5-foot-wide pedestrian path shall be provided throughout the site, connecting adjacent streets, accessways, sidewalks and parking areas to the entrances of all structures.
 - (b) Pedestrian areas shall be clearly distinguished from vehicular and bicycle traffic areas through the use of paving materials, landscaping buffers, or other means.
 - (c) Continuous off-street vehicle routes shall be no more than 200 feet in length before interruption by pedestrian crosswalks over speed tables, T-intersections or other design elements to calm vehicle movement on site.

Section 4.8 Off-Street Parking Provisions in the Downtown Overlay District

1. The provisions of this Section recognize the availability of municipal parking facilities, on-street parking, and walkable development patterns within the Downtown Overlay District.
2. Residential uses shall comply with Section 4.2.
3. Hotels, inns, and motels shall provide:
 - a. 0.75 parking spaces per guest room; and
 - b. 1 parking space per 25 square feet of conference or banquet facilities.
4. No minimum parking requirement shall apply to other nonresidential uses within the Downtown Overlay District.
5. For uses within the Downtown Overlay District that are subject to a minimum parking requirement under this Section, the number of required off-street parking spaces shall be reduced by four (4) spaces.

Section 4.29 Requirements for Accessible Parking for the Physically Disabled

1. Specially designated parking spaces for the physically disabled shall be located closest to the designated accessible primary entrance(s).
2. If possible, these shall be located so that physically disabled persons do not have to cross vehicular travel lanes.
3. Ramps required as a means of egress leading from specially designated parking spaces for the physically disabled in parking lots shall be in conformity with Building Code.
4. Parking for the physically disabled shall comply at a minimum with the standards provided by *Accessible and Usable Buildings & Facilities* (ICC/ANSI A117.1 latest edition).

Section 4.310 Off-Street Parking Space Design and Layout

~~In addition to the requirements of the Zoning Ordinance, the following design standards shall apply.~~

1. Every effort shall be made to use pervious parking and pathway surfaces as an alternative to impervious asphalt or concrete for overflow parking areas, except in cases where it is determined that a traditional impervious parking lot with engineered stormwater systems renders greater protection of surface and groundwater resources than pervious pavement.
2. When provided, motorcycle parking pads shall be concrete.

Article 5 Pedestrian and Bicycle Circulation

Section 5.1 General Provisions

1. The site plan shall provide for a system of pedestrian or bicycle paths, or a combination of both, as appropriate to the type and scale of development. This system shall connect the major building entrances/exits, parking areas and any existing or proposed sidewalks within or adjacent to the project.
2. Any paths shall be located within the lot lines of the site, unless it is determined by the Planning Board that it would be more appropriate to locate these in the public right of way.
3. The system shall also be designed to link the project with residential, recreational, commercial facilities, schools, bus stops and existing bicycle or pedestrian facilities in the neighborhood.
4. The system shall minimize conflicts between pedestrians, bicycles and motor vehicles.

Section 5.2 Sidewalks and Pedestrian Pathways

5.2.1 Accessibility

Sidewalks and pedestrian pathways shall be easily accessible to all users, whatever their level of physical ability, and comply at a minimum with the standards provided by *Accessible and Usable Buildings & Facilities* (ICC/ANSI A117.1, latest edition).

5.2.2 Travel Width

The sidewalk or pedestrian pathway shall be at least five (5) feet wide. If anticipated pedestrian volumes warrant, the Planning Board may require a wider pathway.

5.2.3 Continuity

1. A sidewalk or pedestrian pathway shall connect destinations and shall not require pedestrians to travel out of their way unnecessarily.
2. Pedestrian areas shall be clearly distinguished from vehicular and bicycle traffic areas through the use of paving materials, landscaping buffers, or other means.

5.2.4 Location

At a minimum, sidewalks shall be located along the front of the site, along the front of buildings, and shall connect to building entrances.

5.2.5 Pedestrian Amenities

1. Sidewalks and pedestrian pathways longer than 500 feet shall provide areas for standing and sitting and may include pedestrian amenities such as benches, tables, shade trees or grassy areas.
2. Such pedestrian areas shall be a minimum of 100 square feet in area and shall be provided at regular intervals of 300 feet along the sidewalk or pedestrian pathway.

5.2.6 Surfacing Materials

Any off-site improvements to public sidewalks that are required as part of the project shall use surfacing materials specified by the Planning Board.

Section 5.3 Bicycle Facilities

5.3.1 General

1. Bicycle facilities (including routes and racks) may be combined with pedestrian facilities when designed according to shared path standards of AASHTO, but not on City sidewalks.
2. Bicycle facilities shall be designed in accordance with AASHTO, Guide for the Development of Bicycle Facilities, as amended.

5.3.2 Bicycle Routes

Bicycle routes may be required by the Planning Board in the form of a separate off-street path or on-street marked bicycle lanes.

5.3.3 Bicycle Racks

Bicycle racks, when required by the Planning Board, shall meet the following requirements:

- (a) All racks shall be located in a convenient and secure location.
- (b) Where bicycle racks are placed near trees, trees shall be protected with tree guards to prevent the securing of bicycles to trees.

- (c) All racks shall be designed to allow the frame and one wheel to be locked to the rack with a high security, U-shaped shackle lock if both wheels are left on the bicycle.
- (d) All racks shall be securely anchored to a durable, hard paved (preferably concrete) permanent surface.

5.3.4 Bicycle Parking

1. Off-street parking of bicycles shall be provided as follows, up to a maximum of 30 bicycle spaces:

Multifamily dwellings	1 bicycle space for each 5 dwelling units or portion thereof
Elementary, middle and high schools	1 bicycle space for each 4 students
All other uses	1 bicycle space for each 10 automobile parking spaces required under these regulations or fraction thereof

2. When the Planning Board approves the construction of fewer off-street parking spaces than would normally be required, the required number of bicycle parking spaces shall be based on the number of such spaces that would be required.
3. In addition to the number of bicycle parking spaces required above, any nonresidential use may substitute bicycle parking spaces for up to 5 percent of the required automobile parking spaces at the following ratios: 1 required automobile space may be replaced by 6 bicycle spaces or by 2 bicycle lockers.
4. The following uses are exempt from providing bicycle parking spaces:
 - a. One-family and two-family dwellings;
 - b. Accessory dwelling units;
 - c. Assisted living facilities and residential care facilities;
 - d. Agricultural uses;
 - e. Warehousing, distribution, and similar industrial uses where bicycle parking demand is expected to be minimal; and
 - f. Other uses determined by the Planning Director to have minimal bicycle parking demand due to the nature of the use, anticipated occupancy, or operational characteristics.

Article 6 Landscaping and Screening Standards

Section 6.1 General Provisions

Landscaping shall be provided that:

- (a) Defines areas for pedestrian and vehicular circulation;
- (b) Breaks up the mass of buildings and impervious areas;
- (c) Incorporates existing native vegetation and other natural features into the site design;
- (d) Micromanages and controls stormwater at its source to minimize off-site impacts;
- (e) Conserves water and reduces outside water use on the site;
- (f) Provides buffers between incompatible land-uses or sites;
- (g) Softens architectural and structural materials;
- (h) Minimizes the need for fertilizer and pesticide usage and the introduction of pollutants to the environment.

Section 6.2 Landscaping Plan

1. A landscaping plan shall be submitted with each application for Site Plan Review showing:
 - (a) Existing and proposed vegetation including trees, shrubs and plant beds including all vegetation that shall be retained as required by the Planning Board;
 - (b) Dimensions of undisturbed areas and measures that shall be used to protect during construction existing natural features that are to be retained;
 - (c) Location of all utilities above ground and below ground and related easements;
 - (d) Required front, side, and rear yards.

2. A plant schedule shall accompany the plan that includes the following information:
 - (a) Botanical and common names;
 - (b) Planting size and size at maturity;
 - (c) Quantity;
 - (d) Growth habits (branching, crown spread, root spread);
 - (e) Tolerance to urban conditions including road salt, soil; compaction, drought, heat, and air pollution;
 - (f) Planting requirements.

Section 6.3 General Requirements

1. Areas not occupied by buildings or other structures, parking, loading, and accessways shall be landscaped to provide visual relief from expanses of paving and buildings while providing shade and stormwater management benefits.
2. At a minimum, all yards, setbacks, and areas of open space as required by the Zoning Ordinance shall retain existing natural features or be landscaped as required herein.
3. Landscaped areas shall consist of a combination of grass, flowers, vines, groundcovers, trees and/or shrubs. All planting areas shall be landscaped with a combination of climate tolerant plant material and protective groundcover. Bare soil is not permitted. Managed lawn areas should be kept to a minimum to the extent practical especially areas that will not be accessed and where alternative options are available.
4. Natural features, existing healthy mature trees, and other existing vegetation shall be identified on the landscaping plan and shall be retained when required by the Planning Board.
5. Existing invasive plant species shall be removed and destroyed if required by the Planning Board. Applicants shall refer to the *Prohibited Invasive Plant Species List* maintained by the NH Department of Agriculture.
6. No loam or other topsoil shall be removed from the site as part of site development. Topsoil shall be appropriately stockpiled and stabilized for redistribution within new planting areas.

7. Existing topography shall be maintained unless otherwise permitted by the Planning Board.
8. Any areas disturbed during construction that will not be occupied by buildings or other structures, parking, loading, and accessways shall be replaced with a minimum of 6 inches of suitable topsoil that meets the specifications of the City of Portsmouth DPW and then shall be replanted according to the requirements herein.
9. Plant material and landscape maintenance procedures that incorporate water conservation techniques are preferred.
10. All local and state requirements for yards and sight distance shall take precedence for selection and placement of landscaping features, as applicable.
11. No plantings shall be placed where they may impede or interfere with existing or proposed sewer, water, natural gas lines, or power lines.
12. The front yard landscaping area may contain any of the following:
 - (a) Public utility easements and open surface drainage easements that do not occupy more than thirty (30) percent of the required landscaped area. Such areas should be planted with perennials or groundcover so as not to interfere with utility connections;
 - (b) Underground utility connections and transformers, provided that they do not encroach more than five (5) feet into the required landscaped area. Such equipment shall be landscaped to soften the visual impact.
13. Wherever appropriate, applicants shall incorporate Low Impact Development (LID) design practices and technologies in all aspects of the site's landscaping.
14. Topsoil applied on the site shall be a mixture of $\frac{3}{4}$ loam and $\frac{1}{4}$ compost and shall comply with the specifications of the City of Portsmouth DPW as provided in Attachment B of these Site Plan Review Regulations (as amended).

Section 6.4 Planting Requirements

The purpose of planting requirements is to enhance the long-term survival prospects of the plant materials used in site landscaping. These standards are also meant to ensure that the benefits of site landscaping (buffering, aesthetic enhancement, erosion control, etc.) are realized as early after planting as possible.

At a minimum, all plantings shall be planted consistent with the *ANSI A300 Part 6 Standard Practices for Planting and Transplanting* (as amended).

In addition, the following planting standards shall apply:

- (a). All planting holes shall be dug by hand. The only exceptions are for new construction where new planting pits, planting beds with granite curbing, and planting sites with Silva Cells (or equivalent) are being created. If a machine is used to dig in any of these situations and planting depth needs to be raised, the material in the bottom of the planting hole must be firmed with machine to prevent sinking of the root ball.
- (b). Wire and burlap coverings shall be removed from the root ball and planting hole prior to planting.
- (c). The root ball of the tree shall be worked so that the root collar of the tree is visible and no girdling roots are present.
- (d). The root collar of the tree shall be 2"-3" above grade of planting hole for finished depth.
- (e). All plantings shall be backfilled with soil from the site and amended no more than 20% with organic compost. The only exceptions are new construction where engineered soil is being used in conjunction with Silva Cells (or equivalent) and where new planting beds are being created.
- (f). All plantings shall be backfilled in three lifts and all lifts shall be watered so the planting will be set and free of air pockets.
- (g). An earth berm shall be placed around the perimeter of the planting hole except where curbed planting beds or pits are being used.
- (h). 2"-3" of mulch shall be placed over the planting area.
- (i). At the time the planting is complete the planting shall receive additional water to ensure complete hydration of the roots, backfill material and mulch layer.
- (j). Stakes and guys shall be used where appropriate and/or necessary. Guy material shall be non-damaging to the tree.
- (k). All planting stock shall be specimen quality, free of defects, and disease or injury. The City reserves the right to refuse/reject any plant material or planting action that fails to meet the standards and practices contained herein.

- (l) When appropriate for trees placed within sidewalks, tree grates shall be used to prevent excessive soil compaction and to add interest to the pavement. Tree grates shall be fabricated of a strong, durable material, installed flush with grade, and provide an expandable center opening to allow for continued tree growth.
- (m) Where applicable, tree guards shall be installed to protect the base of the tree from street activity.
- (n) Tree wells over 6 inches deep or other landscape features that have the potential to present a falling hazard to the public shall have grates, fences or other protective measures installed.
- (o) All trees where required shall be welled and protected against change of grade.
- (p) Where appropriate a tree protection plan meeting the specifications of the City of Portsmouth may be required by the City to protect trees at risk from damage during construction.

Section 6.5 Plant Selection

- 1. All proposed plantings shall be appropriate for the soils, weather and environmental conditions of the site. Particular attention shall be paid to tolerance to potential road salt and other deicing treatments.
- 2. Plant materials shall be of specimen quality conforming to the American Standards for Nursery Stock and shall be guaranteed for at least two growing seasons.
- 3. Plants on the *Prohibited Invasive Plant Species List* maintained by the NH Department of Agriculture shall not be planted.
- 4. Trees shall be selected for growing habits that are appropriate for the location. Consideration shall be given to crown height and canopy spread at maturity so as not to interfere with buildings, structures, pedestrian and bicycle facilities, or other site features.

Section 6.6 Landscaped Areas

- 1. Side slopes for all landscaped areas shall not exceed thirty-three (33) percent (3:1 slope), and shall be appropriately stabilized with vegetation.

2. Within parking areas, landscaped islands shall be provided between adjacent rows of parking and between groups of parking spaces with the goal of breaking up large contiguously paved areas.
3. Landscaped islands shall be a minimum of nine (9) feet wide or as necessary to provide adequate room for growth and so as not to interfere with access to vehicles, lines of sight, pedestrian travel, or the long-term health of the vegetation.
4. Landscaped areas shall consist of a combination of large and small trees, shrubs, perennial and/or annual flowers, and groundcover. Managed turf areas should be kept to a minimum to reduce mowing and fertilizer needs.
5. Landscaped areas shall be designed with a variety of plant species that provide seasonal variety.
6. Landscaping around building entrances, near parking spaces, and along pedestrian and bicycle ways shall not interfere or block line of sight, restrict travel, or present a hazard to personal property.
7. Any landscaping located within the safe site distance of a driveway entryway, as defined by AASHTO standards, shall be no more than 3 feet at mature height.
8. Areas between trees and shrubs shall be planted with groundcover spaced to cover the area within 3 years. Areas of exposed bare soil shall be avoided. Mulch shall not be considered a groundcover.
9. Pedestrian pathways made of permeable materials are encouraged where landscaping areas are of a size and shape to accommodate pedestrian passage.
10. Low Impact Development techniques such as rain gardens, bioretention areas, and tree boxes and other stormwater management landscaping techniques may be incorporated into landscaped areas and may replace required landscaping components as approved by the Planning Board.

Section 6.7 Landscaping Along Public Rights of Way

1. Where feasible or as required by the Planning Board, street trees may be planted along public rights-of-way with the goal of providing a tree-lined street.
2. Trees shall be spaced at a minimum of 1 tree per 30 lineal feet or farther apart if necessary to accommodate the mature crown spread of the tree.

Trees shall not interfere with buildings, overhead utilities, pedestrian travel, or access to on-street parking spaces.

3. In the Gateway District, the front yard shall include a landscaped buffer strip with a depth of at least one-third of the distance between the street right-of-way and any building, and extending across the width of the lot except for driveways, sidewalks and bicycle paths. The buffer strip shall be in addition to the street trees required herein, and shall include a combination of trees and lower-level elements such as shrubs, hedges, fences, planted berms, or brick or stone walls.

Section 6.8 Perimeter Landscaping

1. Parking areas shall be landscaped on the perimeter in order to soften the visual impact of the parking area while maintaining clear sight lines.
2. Landscaping between nonresidential uses is intended to provide visual relief from pavement. It may, however, encourage passage between nonresidential properties by (a) providing five (5) foot wide pedestrian pathways through landscaping elements at locations suitable for safe pedestrian circulation and (b) using landscaping materials that allow a clear sight line between properties at a height of three (3) feet.
3. A minimum nine (9) foot-wide landscaped buffer, including shade trees, between the street or accessway pavement and the sidewalk or pedestrian pathway shall be provided where adequate public right of way exists.

Section 6.9 Screening

1. Where nonresidential uses and/or off-street parking facilities abut a residential zone the perimeter shall be screened to provide physical and visual separation between uses.
2. Natural screening shall consist of evergreen shrubs/trees planted in a line to form a continuous screen and growing to a height of 6 feet within 3 years. The remaining portion of the screening area shall consist of large and small trees, grass, flower beds, or other vegetative groundcover planted to fully cover the ground surface of the area within 3 years.
3. A 6-foot high fence or masonry wall may be substituted for natural screening if approved by the Planning Board. The wall or fence shall be placed on the exterior side of any landscaping.
4. All sites shall incorporate screening measures to prevent the headlights of vehicles from shining on adjoining residential areas.

5. All mechanical installations and equipment, solid waste collection equipment, pump stations, and outdoor storage shall be screened or softened with landscaping that is appropriate for the location.

Section 6.10 Maintenance and Replacement of Landscaping and Screening

1. The property owner shall be responsible for the maintenance, repair, and replacement of all required screening and landscaping materials.
2. All required plant materials shall be tended and maintained in a healthy growing condition, replaced when necessary, and kept free of refuse and debris. All required fences and walls shall be maintained in good repair.
3. The property owner will remove and replace dead or diseased plant materials immediately with the same type, size and quantity of plant materials as originally installed, unless alternative plantings are requested, justified, and approved by the Planning Board.

Section 6.11 Irrigation

1. Irrigation should be minimized to the extent possible through use of native drought tolerant species and the use of landscaping that does not require permanent irrigation systems.
2. When irrigation is necessary to support the establishment and/or maintenance of landscaped areas smart controllers shall be used that limit irrigation during the day and during rain events.
3. Where appropriate, additional water conservation features including trickle and drip lines, rain barrels, cisterns or other water harvesting elements shall be incorporated into the site design to help maintain plantings.
4. Applicants are encouraged to use recycled water for irrigation provided the harvesting and circulation systems and water quality meet the requirements of the City's Utility Ordinance and state standards.
5. Irrigation systems shall be installed and operated in accordance with the City's Utility Ordinance.

Section 6.12 Innovative Landscaping Practices

6.12.1 Green Roofs

Applicants are encouraged to use roofing materials that have a Solar Reflective Index (SRI) of at least 29 (greater for roofs with a slope of 2:12 or more) and to install vegetated roofs to minimize the runoff volume generated by the roof.

6.12.2 Solar Orientation

Applicants are encouraged to incorporate landscaping techniques that help reduce energy consumption for heating and cooling of buildings on the site. Trees should be planted in order to provide shade on buildings and parking lots in the warm seasons and to allow solar heat during the cool seasons.

Article 7 Water Resources Standards

Section 7.1 Low Impact Development (LID)

Applicants shall incorporate Low Impact Development (LID) site planning and design practices to the maximum extent practical (MEP) to reduce stormwater runoff volumes, maintain predevelopment site hydrology, and protect water quality in receiving waters. LID practices may include site design techniques (e.g., maintenance of vegetated buffers, minimizing of disturbance footprint) and structural measures to promote infiltration such as porous pavement, rain gardens or the capture / reuse of stormwater to reduce the stormwater volume discharged from the site. If LID practices are not proposed, the applicant shall fully demonstrate in writing why these practices are not feasible.

Section 7.2 General Water Quality and Stormwater Management Provisions

1. Water bodies, watercourses, and wetlands shall be preserved in their existing condition whenever possible.
2. All regulated substances shall be stored, transported, disposed or transferred in accordance with the rules for Best Management Practices for Groundwater Protection of the New Hampshire Department of Environmental Services (NH DES).
3. The proposed site development and use shall not adversely impact either the quality or quantity of groundwater available to surrounding properties or to public water supply systems or adjacent or downstream surface waters used for aquatic habitat support, aesthetic and/or recreational purposes.
4. For any on-site water system supplying 20,000 gallons per day (gpd) or more, evidence presented by a qualified hydrologist shall be sufficient to reasonably conclude that there will be no adverse effect on other public or private groundwater sources.
5. The development shall meet all applicable federal, state, and City regulations, statutes, ordinances, and standards regarding protection of water quality and stormwater management.
6. Stormwater treatment BMPs shall be designed to optimize nitrogen removal based on currently approved design standards and removal efficiencies listed in either the NH Stormwater Manual, as amended, Appendix F of the EPA NH MS4 Permit or as published by the UNH Stormwater Center.

7. Projects that involve replacement or adding new conveyance infrastructure that will connect to City infrastructure and/or are located on City property with a design life beyond 2050 (e.g. closed drainage pipes, bridges, culverts, etc.), shall incorporate applicable recommended flood protection measures and sizing design guidance contained in the *NH Coastal Flood Risk Summary: Part II: Guidance for Using Scientific Projections 2020* (as amended). The determination of applicability for such measures and design considerations shall be based on review by the City Engineer.

Section 7.3 Wellhead Protection Areas

1. The application for Site Plan Review shall indicate whether the proposed development is located in a wellhead protection or aquifer protection area, and such determination shall be approved by the Director of the Department of Public Works.
2. If the proposed development is determined to be located in a wellhead or aquifer protection area, the Planning Board may:
 - (a) Require upgradient and downgradient U.S. EPA-type monitoring wells that are installed under the direction of a NH certified professional hydrogeologist;
 - (b) Require that a first round of pre-construction samples be collected and analyzed and the results submitted to the Department of Public Works;
 - (c) Determine that continued monitoring is necessary per the recommendation of the Department of Public Works;
 - (d) Require an easement to access the monitoring wells in order to take future samples;
 - (e) Require annual sampling of constituents of concern as determined by the Department of Public Works.
3. Within a wellhead protection area no more than twenty percent (20%) of a single lot or building site shall be rendered impervious to groundwater infiltration.

Section 7.4 Stormwater Management and Erosion Control Plan (SMECP)

The applicant shall submit a Stormwater Management and Erosion Control Plan.

The Planning Board shall approve the Stormwater Management and Erosion Control Plan if it complies with the requirements and objectives of these

regulations. Such approval shall be a component of the overall subdivision or site plan approval. If disapproved, the Planning Board shall furnish the applicant with a list of plan deficiencies and procedures for filing a revised plan.

The Planning Board may require a third-party review by a qualified professional consultant of any Stormwater Management and Erosion Control Plan prepared under these regulations at the applicant's expense.

The SMECP shall, at a minimum, contain the following information, however, additional information may be requested by the Planning Board depending on the proposed project, water quality issues and third-party review recommendations.

1. Narrative that describes the proposed development activity, the proposed changes in land use, land cover and impervious areas, the anticipated construction period and timing, project start and completion dates, sequence and duration of grading and construction activities, sequence and timing of installation and/or application of soil erosion and sediment control measures as well as sequence for final stabilization of the project site.
2. Description of onsite and adjacent wetlands, streams and other water bodies or natural resources and the methods used to identify these resources.
3. Description of Low Impact Development (LID) practices and other protective measures to limit impacts to adjacent natural resources and water bodies.
4. Description of any applicable buffer setbacks, steep slopes, existing mature vegetation, unique habitat conditions, 100-year floodplain limits, manmade and natural drainage conveyances and constraints and known water quality concerns based on local data or the NHDES 303(d) list.
5. Description of existing drainage patterns, receiving waterbodies or drainage infrastructure and soil types for recharge potential.
6. Methods and assumptions used to calculate pre-and post-development runoff volume, peak discharge, and discharge velocity for the specified design storms.
7. Description of the procedures that will be used to store and/or dispose of solid waste during construction such as demolition materials, concrete washout material litter, hazardous liquids such as equipment fuel, as well as sanitary waste that have the potential to cause adverse impacts to water quality.
8. Where proposed changes are anticipated within mapped limits of the 100-year floodplain, provide hydrologic and hydraulic analysis to show no net increase in flood elevations for the 100-year flood.
9. Description of the proposed erosion control and stormwater treatment measures, dewatering methods, including calculations of stormwater runoff rates and volumes and BMP sizing, a demonstration of no downstream impacts, inspection and maintenance procedures including discussion of roles and responsibilities and contingency measures for extreme precipitation events during construction.

10. Calculations for any proposed infiltration measures, including estimated infiltration rates based on test pit information and an estimate of the seasonal high-water table elevation. The calculations should account for frozen ground conditions, or when the devices may not function at their optimal design.
11. Any other specific study, calculation, or investigation as requested by the Planning Board (e.g. sea level rise estimates per other Regulations).
12. The SMECP and drainage plans shall be certified by a licensed professional engineer, registered in the State of New Hampshire.
13. Description of the proposed erosion control inspection and maintenance procedures including planned frequency, reporting, roles and responsibilities, contact information and contingency plans for extreme weather events.
14. A long-term post-construction stormwater BMP maintenance plan that describes inspection and maintenance procedures for all post-construction stormwater control measures including a description of the responsible party that will perform the long-term maintenance, reporting procedures and process for corrective actions.
15. Description of the procedures for removing temporary erosion control measures and removal of accumulated sediment captured by such measures.
16. For projects draining to inland wetlands and water bodies, the SMECP shall include a description of winter maintenance practices including any onsite salt storage and handling practices, snow storage and Best Management Practices that will be deployed to minimize the use of road salt.

Section 7.5 Construction Erosion Control Design Standards

The following standards shall be applied in selecting and designing appropriate stormwater management and erosion control measures during the construction phase. If a Stormwater Pollution Prevention Plan (SWPPP) has been prepared to comply with the EPA Construction General Permit (CGP), relevant portions of the SWPPP can also be utilized to satisfy the required SMECP contents, provided the listed required elements are included in the SWPPP.

1. The selection, sizing, installation and maintenance of all erosion and sediment control measures shall be consistent with the design guidance set forth in the NH Stormwater Manual, Volume 3 (as amended).
2. Whenever practical, natural vegetation (not included invasive species) shall be retained, protected and/or supplemented. Clearing of any vegetation shall be done in a manner that minimizes soil erosion. Vegetated areas to be retained should be clearly marked and protected using construction fencing or similar means.
3. Soil disturbance shall be avoided within established buffer setbacks as established by the City Wetland Protection section of the Zoning Ordinance.
4. The area of disturbance shall be kept to a minimum through innovative site

design and treatment methods that preserve and protect existing onsite and adjacent natural resources to the greatest extent practical.

5. Construction site disturbance should be phased to disturb only the amount of area needed to accommodate each phase of development and limit the amount of exposed soil area especially during winter months.
6. Adequate temporary solid waste and sanitary waste disposal facilities shall be maintained onsite during the construction period.
7. Adequate construction stone access pads shall be installed and maintained at the site entrance and exit locations to prevent mud and sediment from being tracked on to pavement.
8. An onsite pre-construction meeting shall be held with the City Engineer or designated representative prior to initiating earth moving activities and after perimeter erosion control measures, protective fencing, waste disposal and construction access pads have been installed.
9. Disturbed areas shall be either temporarily or permanently stabilized by measures consistent with the guidelines included in the NH Stormwater Manual. In areas where final grading has not occurred, temporary stabilization measures shall be implemented as soon as practicable but no later than (7) calendar days from the initial disturbance or as requested by the City Engineer. Disturbed soil areas that have achieved final grading shall be permanently stabilized within (3) calendar days after final grading.
10. Upgradient surface runoff from undisturbed areas shall be diverted away from disturbed areas where feasible or carried non-erosively through the project area. Integrity of downstream drainage systems shall be maintained.
11. Natural drainage patterns and conveyances, including intermittent streams, swales, and drainage ditches shall be maintained to the extent practical to convey runoff from the project area. Perimeter controls shall not be placed within wetland buffer areas or intermittent and perennial stream channels.
12. Winter stabilization measures shall be deployed on disturbed areas that will remain idle over the winter period as described in the NH Stormwater Manual, as amended.
13. All erosion and sediment control measures shall be designed and installed in accordance with guidelines including in the NH Stormwater Manual, as amended.
14. All erosion control measures and related drainage ways shall be routinely inspected and maintained by a qualified professional to ensure measures remain in functioning condition until final site stabilization is accomplished.
15. All temporary erosion and sediment control measures shall be removed after final site stabilization.

Section 7.6 Post-Construction Stormwater Management Design Standards

7.6.1 Post-Construction Stormwater Management Standards

All development and redevelopment projects that are subject to Site Plan Review shall use an array of best management practices to reduce and treat stormwater runoff prior to discharging from the development. The Applicant will prepare and submit a Stormwater Management and Erosion Control Plan (SMECP) to the Planning Board that describes relevant details on the various best management practices that will be used to protect water quality and prevent flooding and, at a minimum, meets the following design standards:

1. Adequate provisions shall be made to retain natural and existing flow patterns and maintain existing groundwater recharge volumes to the maximum extent feasible, where appropriate, and/or retain, treat and/or potentially reuse the stormwater generated on the site.
2. Efforts shall be made to utilize methods that disconnect and/or reduce the amount of effective impervious area including, but not limited to, infiltration trenches, dry wells, bioretention areas, filter strips, permeable pavement, and cisterns.
3. Applicants shall demonstrate why on-site infiltration approaches are not possible or adequate before proposing the use of conventional systems that rely on collection and conveyance to remove runoff from the site.
4. All proposed stormwater treatment practices shall be adequately sized to treat the Water Quality Volume (WQV) or Water Quality Flow (WQF) in order to minimize pollutant discharges and be properly maintained in accordance with NH Administrative Code PART Env-Wq 1507.03 “Pollutant Discharge Minimization Requirements” and PART Env-Wq, 1707.03, respectively (or as revised / renumbered).
5. Where vegetated areas are used to control and treat stormwater, such areas shall be planted with appropriate non-invasive groundcover, shrubs and/or other plantings sufficient to prevent soil erosion and to promote proper treatment of stormwater.
6. Measures shall be taken to control the post-development peak rate of runoff so that it does not exceed pre-development runoff for the 2, 10, 25, and 50-year, 24-hour storm event. Rainfall amounts for these events shall be based on local rainfall data using the extreme precipitation table provided by the Northeast Regional Climate Center or as otherwise required by the NHDES Alteration of Terrain requirements, if applicable. Where stormwater will

discharge directly to tidal waters, the Planning Board may waive peak flow control requirements provided the Applicant can demonstrate minimal risk of flooding or increased erosion as result of the discharge, adequate onsite stormwater treatment is provided for water quality purposes and the City Engineer concurs with the waiver request.

7. Site development shall comply with the requirements of the Flood Plain District as regulated by the Zoning Ordinance.
8. BMP designs shall include appropriate separation distances from the seasonal high-water table elevations, where appropriate, and as specified in the *New Hampshire Stormwater Manual* (as amended).
9. Salt storage areas shall be covered using permanent or semi-permanent measures and loading/offloading areas shall be located and designed to not drain directly to receiving waters and be maintained with good housekeeping measures in accordance with NHDES guidance documents.
10. Snow storage areas shall be located such that no direct discharges to receiving waters are possible from the storage site. Runoff from snow storage areas shall enter treatment areas to remove suspended solids and other contaminants before being discharged to receiving waters or preferably be allowed to infiltrate into the groundwater.
11. The applicant shall demonstrate that there is sufficient on- and off-site downstream channel or system capacity to carry the stormwater run-off volume and flow without adverse effects, such as flooding and erosion of stream banks and shoreland areas.
12. Stormwater treatment BMPs involving excavation or other site alterations shall be located outside of protected wetland buffer areas as defined in the City's Zoning Ordinance Article 10 -- Environmental Protection Standards unless approved under a Conditional Use Permit as outlined Article 10, as amended.
13. In addition to the requirements of this Article, all developments subject to Site Plan Review shall comply with the City's Regulation of Discharges into the Stormwater Drainage System Ordinance.
14. The applicant shall submit documentation demonstrating how and who will maintain stormwater treatment devices post-development.
15. Property owners of new development projects that will add new paved areas shall minimize their salt use through appropriate measures including hiring Green SnowPro certified operators for winter maintenance.

7.6.2 Enhanced Stormwater Treatment Standards for New and Redevelopment Disturbing More than 15,000 square feet of Area

1. New Development

In addition to the Basic Stormwater Management Design Standards listed above, all new development projects that will disturb more than 15,000 square feet of area and are subject to Site Plan Review shall meet the enhanced stormwater treatment standards to minimize the discharge of pollutants consistent with the NH MS4 Stormwater Permit and N.H. Code Admin. R. Part Env-Wq 1507.03, and shall include but not limited to the following:

- (a) Retain or treat stormwater runoff before discharged to a surface water or the MS4 system by one of the following:
 - i. Adequately size and install BMPs that are designed to retain the Water Quality Volume from the total post-construction impervious area calculated in accordance with N.H. Code Administrative Rules Part Env-Wq 1504.10, OR
 - ii. Include BMPs designed to remove 80% of the average annual Total Suspended Solids (TSS) load and 50% of the average annual Total Nitrogen (TN) load generated from the total post-construction impervious area.
- (b) Applicants shall provide details on the proposed BMPs in the SMECP including type, location, sizing and related calculations that demonstrate both the Basic and Enhanced Stormwater treatment standards will be met and the export of TSS and nutrients from the site have been minimized to the maximum extent practical given the proposed use and the characteristics of the site.
- (c) Runoff from new development shall meet the anti-degradation provisions of the state water quality standards (Env-Wq 1700) that require that no additional pollutant loads shall contribute to existing water body impairments.
- (d) Proposed projects that will drain to inland wetlands and water bodies and will create additional roadway or ten (10) or more additional parking spaces, the Applicant shall develop a winter maintenance plan that describes any onsite storage and handling of road salt, anticipated snow storage areas, and efficient deicing practices that will limit the amount of road salt used including the use of Green SnowPro Certified Operators

2. Redevelopment Projects: Redevelopment refers to any proposed development activity subject to Site Plan Review on an existing parcel where 40% or more of its developable land is comprised of impervious surfaces. Stormwater from the disturbed portion of the redevelopment site shall be treated by one of the following techniques, listed in order of preference:
 - (a) Implement LID or stormwater treatment BMPs that will disconnect and/or treat at least 30% of the existing impervious cover and 100% of any additional proposed impervious surfaces or paved areas preferably using filtration and/or infiltration practices; or
 - (b) Implement LID or stormwater treatment measures to disconnect or treat at least 60% of the entire developed area.

7.6.3 Additional Pollutant Tracking and Accounting Program (PTAP) Submittal Requirements

All applicants shall submit, as part of the Final Post Approval Procedures (See Section 2.15), relevant PTAP information using the most recent online data portal currently managed by the UNH Stormwater Center and included on their website. The Planning Department shall be notified and copied of the PTAP data submittal. This may include, but not be limited to, the following information which will be submitted as part of the site plan application:

1. Property address, parcel map no., parcel size, property owner and contact information, Applicant's Engineer contact information.
2. Current property use, amount of existing developed area, impervious area and vegetated area draining to each receiving water body.
3. Proposed property use, amount of disturbed area, impervious area and vegetated area draining to each receiving water body.
4. Description of existing and proposed stormwater drainage conveyances and treatment BMPs and amount of impervious area expected to be treated before discharging to specific water bodies.
5. Direct Receiving Water Body, NHDES HUC Assessment Unit No. and any listed water quality impairments.
6. Maximum effective impervious surface cover that contributes to stormwater leaving the site shall be minimized to the maximum extent feasible. Applicants shall provide a calculation of the maximum effective impervious surface as a percentage of the site.
7. For purposes of these regulations, the total impervious area of a lot or site is defined as the total area of impervious parking lots, accessways, driveways, roof area, decks, paved walkways, sidewalks, and any concrete, stone, brick, asphalt or compacted gravel surface.
8. Impervious surfaces may be disconnected from the stormwater drainage network to reduce the total effective impervious surface cover through such techniques as infiltration or sheet flow over pervious area.

9. Estimates of pollutant load reductions or pollutant removal efficiencies provided by the proposed BMPs based on the impervious area and expected WQV volume treated and removal efficiencies provided in Appendix F or the NH MS4 Permit, published data reported by the UNH Stormwater Center or Appendix E of the NH Stormwater Manual, as amended.
10. Information on the long-term maintenance plan for the proposed BMP(s) including identifying the responsible party, inspection frequency and the reporting procedures consistent with the details identified in Sec. 7.4.6 below.

7.6.4 Responsibility for Installation and Construction

1. The applicant shall bear final responsibility for the installation, construction, inspection and disposition of all stormwater management and erosion control measures required by the provisions of these regulations.
2. Installation of stormwater management and erosion control measures shall be overseen by a qualified engineer and the Planning Board may require independent review and oversight.
3. The Applicant shall provide the City with an emergency contact name and number for stormwater management emergency incidents. The contact name and number shall remain current during the life of the permit and shall be able to respond to emergencies as soon as possible within no more than four (4) hours at any given time.

7.6.5 Inspection and Maintenance Plans.

1. Long-term Inspection and Maintenance (I&M) Plan

The applicant shall develop and execute an enforceable inspection and maintenance plan for both erosion control measures and permanent stormwater treatment measures to maintain their effectiveness for the duration of their useful life. The I&M Plan shall contain relevant protective covenants or land preservation commitments with a long-term agreement that specifies who will be responsible for inspecting and maintaining the long-term integrity and the stormwater BMP functions and protected area. The I&M Plan shall be provided to the Planning Board as part of the application review process prior to issuance of any local permits for land disturbance and construction activities. The Plan shall include the following items at a minimum:

- (a) This agreement will identify the Owner/ Operator and their successor that will be responsible for perform the inspections and maintenance and the ability to access these BMPs including all maintenance easements required to access and inspect the stormwater treatment practices, and to perform routine maintenance as necessary to ensure proper functioning of the stormwater system.
- (b) During the construction period, inspections shall be conducted at least once every seven (7) calendar days or once every 14 calendar days and

within 24 hours of the end of a storm event of 0.5 inch or greater.

- (c) Permanent Stormwater BMPs shall be inspected annually following post-construction
 - (d) The operations and maintenance plan shall specify the parties responsible for the proper maintenance of all stormwater treatment practices.
 - (e) The approved plan shall be incorporated into the agreement of the property on which such measures are located and recorded at the Rockingham County Registry of Deeds. The narrative shall be in the form of a typical Development agreement, or as otherwise set forth by the Planning Board.
- 2. Inspection reports are to be filed on-site in a location easily accessible to a City Engineer.
 - 3. If the Applicant is unable to adequately provide the required inspection and maintenance activities during construction, the City may require additional escrow funding to be used by either the Applicant or the City solely to repair, replace and/or maintain the required measures.
 - 4. As a condition of Planning Board approval, the owner, their successor and assigns shall consent to inspections by the Planning Board or its designee for compliance with these regulations.

Article 8 Utilities Standards

Section 8.1 General Provisions.

1. The development shall be provided with all utilities to adequately meet the anticipated use of the project.
2. All new and relocated wires, conduits, and cables shall be located underground.
3. All electrical and mechanical devices including transformers, telecommunications devices, equipment switching boxes, generators, and other utility cabinets shall be located within buildings when possible or hidden from street and pedestrian areas with landscaping or architectural screens when located outside according to the requirements of Article 6.
4. Temporary overhead power and telephone lines are permitted during construction only.
5. Utility equipment for private development shall not be built in public rights of way.

Section 8.2 Water Supply and Distribution System

1. Where a public water supply is reasonably accessible or required because of groundwater pollution problems, the development shall be provided with a complete water distribution system, including a connection for each legally subdivided lot in accordance with the City Utility Ordinance.
2. Adequacy of public water supply will be determined using existing DPW hydraulic models and studies.
3. Fire hydrants shall be located within five hundred (500) feet of a building (distance measured as usable, not as straight line).
4. Fire hydrants shall be served by a minimum 8 inch main.
5. Fire hydrant flow tests shall yield flow determined adequate for the project by the TAC.
6. The size, flow rate, and pressure of water mains serving the project shall comply with the City Utility Ordinance.

Section 8.3 Sanitary Sewers

All sewage disposal systems shall be designed, constructed and operated in conformance with the NH DES requirements in a manner that will prevent the spread of disease and illness; prevent the pollution of the municipality's brooks, streams, ponds, lakes, and groundwater table; and assure an adequate supply of potable and palatable water for human consumption.

8.3.1 Sewerage System

Existing sewer mains or lines into which the project will connect shall be capable of transporting estimated sewage generated in accordance with the City's Sewer Use Ordinance.

8.3.2 On-site Sewage Disposal System Design

In cases where connection to City sewer systems is not required, on-site sewage disposal systems shall meet NH DES rules and regulations. If required, the City may also conduct an independent review of the on-site disposal system design.

8.3.3 Design and Installation

1. All waste disposal systems shall be designed and installed in accordance with the rules, regulations and design criteria adopted by the NH DES and with the City's Utility Construction Manual.
2. Where an on-site sewage disposal system is proposed, the application shall list the types of uses for which the proposed system is designed.

8.3.4 Fats, Oil and Grease Controls

Measures for the treatment and disposal of fats, oils and greases shall conform to the City's Sewer Use Ordinance.

Section 8.4 Other Utilities

Preliminary approval from the applicable utility company for all other utility services including but not limited to electric, telephone, cable TV, and gas shall be secured prior to approval by TAC. Approvals shall be documented on site plans as appropriate.

Section 8.5 Oversize and Off-Site Improvements

The Planning Board may require that utilities for the proposed site plan be designed oversized, and/or with additional conduits or extensions provided within the public right-of-way, to serve nearby land that is an integral part of the neighborhood service or drainage area.

Article 9 On-Site Waste Storage and Disposal Standards

Section 9.1 Waste Accumulation

Except as otherwise allowed by City ordinances, owners and managers of every property shall be responsible for maintaining all open areas free of improperly stored solid or liquid waste accumulations.

Section 9.2 Storage Containers

1. Every property shall be supplied with adequate solid, semi-liquid, and liquid waste storage containers. These containers shall be provided by the owner of the property, construction company or by contract with a commercial hauler.
2. All solid waste storage containers shall be resistant to insect or animal entry. Liquid waste may only be stored in tanks designed for the particular waste type.
3. Containers will be constructed with rust and impact resistant materials and will be equipped with tight-fitting covers. Containers shall have an appropriate child safe design and be secure from unauthorized access after business hours (locked). The property owner is responsible for maintaining containers in a neat, clean, sanitary, and leak-free condition.
4. All containers for regulated substances shall meet all applicable federal, state, and local standards.

Section 9.3 Location and Disposal

1. The owner of a property shall insure that the contents of all waste containers are to be emptied or removed for disposal as necessary to prevent nuisance odors and public safety hazards.
2. An appropriate location shall be provided for permanent placement of waste and recycling containers.
3. An appropriate location for temporary placement of waste and recycling containers for collection purposes shall be indicated on all site plans. Such locations shall provide for the safe, accessible and convenient placement of storage containers that do not interfere or impede daily operations and uses on the site or neighboring properties. Such locations shall provide adequate accommodation for access by waste collection and disposal vehicles so as not to damage sidewalks or other City property.

4. Dumpsters and other large exterior waste containers shall be located at service entrances and at the rear of buildings.
5. Dumpster or other waste container pads shall be a minimum of 20 feet from any property line or yard.
6. Dumpster or other waste container pads shall be a minimum of 20 feet from any inlet for stormwater collection.
7. The effluent from any stormwater pipe that drains the area where a dumpster or other waste storage container is located shall traverse a minimum of 50 feet of vegetated area before reaching the banks of the watercourse itself.
8. When a dumpster or other waste storage container pad is adjacent to a watercourse, a minimum landscaped area of 50 feet shall be maintained between the pad and the bank of the watercourse.
9. Recycling shall comply with the City's Solid Waste, Yard Waste and Recycling Ordinance.
10. Permanent and temporary storage locations for all waste and recycling containers shall provide access for waste removal vehicles without damage to sidewalks or other City property.

Section 9.4 Flammable and Combustible Liquids.

All flammable and combustible liquids shall be contained and stored in accordance with the National Fire Protection Association's standards and the International Fire Code. Location of all flammable, combustible and hazardous material storage shall be provided to the Fire Department along with a copy of all required Material Safety Data Sheets (MSDS) prior to Fire Department approval.

Section 9.5 Screening

Screening of on-site waste storage and disposal equipment shall be provided as required in Article 6, of these regulations.

Article 10 Outdoor Lighting

Section 10.1 General Provisions

All projects submitted for Site Plan Review shall provide dark sky friendly outdoor lighting according to these regulations in order to:

- (a) Permit reasonable uses of outdoor lighting for night-time safety, utility, security, productivity, enjoyment and commerce;
- (b) Minimize glare, obtrusive light, and artificial sky glow by limiting outdoor lighting that is misdirected, excessive, or unnecessary;
- (c) Conserve energy and resources to the greatest extent possible.

Section 10.2 Compliance with Zoning Ordinance

All projects shall comply with the outdoor lighting dark sky friendly standards provided in the Zoning Ordinance.

Section 10.3 Lighting Plan

- 1. When a proposed project includes outdoor lighting, the Site Plan shall include a lighting plan which shall show:
 - (a) The location on the site where outdoor lighting fixtures (both pole and mounted) will be installed.
 - (b) Scaled plans indicating the location of outdoor lighting fixtures on the site, the height of each fixture, the types of outdoor lighting proposed, and the level of wattage and initial lumens for all light sources.
 - (c) A description of the outdoor lighting fixtures including but not limited to manufacturer's catalog descriptions and drawings. The required plans and descriptions shall be sufficiently complete to enable the Planning Board to readily determine compliance with the requirements of this regulation.
 - (d) A photometric (iso-lux) plan indicating levels of illumination, in foot candles, at ground level.
- 2. The maintained horizontal illuminance standards set by the Illuminating Engineering Society of North America (IESNA) shall be observed.

3. Should any outdoor light fixture, or the type of light source therein, be changed after the building permit has been issued an amended site plan approval shall be required.

Section 10.4 Lamps

1. Lamp types shall be selected for optimum color rendering as measured by their color rendering index (CRI), as listed by the lamp manufacturer.
2. Lamps with a color rendering index lower than 50 are not permitted. This requirement shall not apply to decorative lighting which may include colored lamps, such as holiday lighting.
3. Commercial lighting shall meet minimum IESNA illumination levels while not exceeding IESNA uniformity ratios and average illuminance recommendations.

Article 11 Radio Communications Standards

Section 11.1 Site Survey

1. When necessary to provide emergency response communication to the site and at the request of the police or fire department, the applicant shall have a site survey conducted by a radio communications carrier approved by the City's Communications Division. The radio communications carrier must be familiar and conversant with the police and fire radio configuration.
2. If the site survey indicates that it is necessary to install a signal repeater either on or near the proposed project, those costs shall be the responsibility of the property owner.
3. The property owner shall be responsible to pay for the site survey whether or not the survey indicates a repeater is necessary.
4. The owner shall coordinate with the supervisor of radio communications for the City.

Attachment A: Digital As-Built Plan Requirements

1. The digital plan must show the same features as the hardcopy plan, including, but not limited to, structures, utilities, property lines, and survey monuments. Text items, such as titles and dimensions, are allowed but not required.
2. The file format must be either AutoCAD DWG, AutoCAD DXF, or an ESRI format. The plan must be in a single digital file with no external reference (“XREF”).
3. The plan must be created in model space, with drawing units of U.S. survey feet. The north rotation must be 0°. New Hampshire state plane coordinates, NAD83 (1996), are preferred.
4. The features must be in the CAD layers and a list of layers shall be provided. Features that do not have a layer specified in this list must be in a separate, unique layer and identified in accompanying documentation. The City will provide a template CAD file upon request.
5. When creating line features that would represent polygons in a GIS, such as property lines and building footprints, the CAD user must snap end points of lines together and must make sure polygons close. All line features must be of a continuous line-type, such that each individual line/pipe feature (i.e. each segment) is only broken at the ends where a node/structure is located. Straight lines must be represented by only the beginning and ending x- and y-coordinate points.
6. All point features shall be entered using standard point/node symbols.
7. When choosing reference features, the applicant must begin at the top of the list. For example, manhole covers may only be used if no hydrants or valves are available. The reference features should be as far from each other as practical. If suitable features are not available within 750 feet (by survey traverse) of the project area, then the applicant shall, at the discretion of the Planning & Sustainability Director, either use alternative features or omit the features. The following reference features are allowed: survey control monuments with horizontal accuracy of at least FGDC Second Order, Class II, including City monuments; fire hydrant spindles, water main valves, and sewer force main valves; sewer or drain manhole cover centers; catch basin centers.
8. The digital plan must be accompanied by electronic documentation, such as a text file, containing the following information: the name of the applicant and the preparer of the plan; the name and version of the CAD software used to create the plan; the project address and/or parcel number.

Attachment B: Topsoil Specifications

1. The City of Portsmouth recommends a mixture of $\frac{3}{4}$ loam, and $\frac{1}{4}$ compost for all topsoil areas. This includes but is not limited to planting beds, turf areas and the green strip between the sidewalk and roadway.
2. The City requires a chemical and composition soil test for this mixture before applying to any areas.
3. The soil mixture shall be applied at a minimum depth of 6”.
4. Loam should consist of 40% sand, 40% silt, and 20% clay.
5. Compost shall meet all of the following criteria and a soil test shall be provided from the compost distributor:
 - a. Product shall be manufactured through the controlled aerobic, biological decomposition of biodegradable materials;
 - b. Product shall have undergone mesophilic and thermophilic temperatures in order to reduce the viability of pathogens and weed seeds, and stabilize the carbon such that it is beneficial to plant growth;
 - c. Product sanitization through the generation of thermophilic heat shall meet the standards of the Processes to Further Reduce Pathogens (PFRP), as defined by the Code of Federal Regulations Title 40, Part 503, Appendix B, Section B;
 - d. Product shall bear little physical resemblance to the raw material from which it originated;
 - e. Product shall be an organic matter source that has the unique ability to improve the chemical, physical, and biological characteristics of soils or growing media.

LEGAL NOTICE

NOTICE IS HEREBY GIVEN that a Public Hearing will be held by the Portsmouth City Council on Monday, August 3, 2026, at 7:00 p.m., at the Portsmouth Municipal Complex in the Eileen Dondero Foley Council Chambers, 1 Junkins Avenue, Portsmouth, NH, on a Resolution authorizing a Bond Issue and/or Notes of the City under the Municipal Finance Act of up to Six Hundred Thousand Dollars (\$600,000) for the costs related to the purchase of one fire apparatus. The complete proposed Resolution is available for review in the Office of the Portsmouth City Clerk and Portsmouth Public Library, during regular business hours.

KATELYN A. GRIGGS
PORTSMOUTH, NH DEPUTY CITY CLERK

LEGAL NOTICE

NOTICE IS HEREBY GIVEN that a Public Hearing will be held by the Portsmouth City Council on Monday, August 3, 2026, at 7:00 p.m., at the Portsmouth Municipal Complex in the Eileen Dondero Foley Council Chambers, 1 Junkins Avenue, Portsmouth, NH, on a Resolution authorizing a Bond Issue and/or Notes of the City under the Municipal Finance Act of up to Six Hundred Thousand Dollars (\$600,000) for the costs related to the purchase of one fire apparatus. The complete proposed Resolution is available for review in the Office of the Portsmouth City Clerk and Portsmouth Public Library, during regular business hours.

KATELYN A. GRIGGS
PORTSMOUTH, NH DEPUTY
CITY CLERK

CITY OF PORTSMOUTH
TWO THOUSAND TWENTY-SIX
PORTSMOUTH, NEW HAMPSHIRE

RESOLUTION # 15-2026

A Resolution authorizing a Bond Issue and/or Notes of the City under the Municipal Finance Act of up to Six Hundred Thousand Dollars (\$600,000) for costs related to the purchase of one fire apparatus.

BE IT RESOLVED:

THAT, the sum of up to Six Hundred Thousand Dollars (\$600,000) is appropriated for the acquisition of one fire apparatus including the payment of costs incidental or related thereto;

THAT, to meet this appropriation, the City Treasurer, with the approval of the City Manager, is authorized to borrow, on a competitive or negotiated basis, up to Six Hundred Thousand Dollars (\$600,000) through the issuance of bonds and/or notes of the City under the Municipal Finance Act;

THAT, the discretion of fixing the dates, maturities, rates of interest, forms and other details of such bonds is hereby delegated to the City Treasurer with the approval of the City Manager;

THAT, the expected useful life of the fire apparatus is determined to be at least ten (10) years; and

THAT, this Resolution shall take effect upon its passage.

APPROVED BY:

DEAGLAN MCEACHERN, MAYOR

ADOPTED BY THE CITY COUNCIL:

SALLY A. KELLAR, CMC/CNHMC
CITY CLERK

VE-25-FD-02: Vehicle Replacement – Marine #1

Vehicles and Equipment: Vehicles



Department(s)	Fire Department
Project Location	Citywide
Project Justification	Capital maintenance/rolling stock
Project Website	N/A
Planning Documents/Studies	N/A

Evaluation Criteria & Prioritization

Priority: A (needed within 0 to 3 years)

CORE FUNCTION	Responds to Federal or State Requirement	
	Addresses a Public Health or Safety Need	Y
	Alleviates Substandard Conditions or Deficiencies	Y
FINANCIAL BENEFIT	Eligible for Matching Funds with Limited Availability	
	Timing or Location Coordinate with Synergistic Project	
	Reduces Long-Term Operating Costs	Y
COMMUNITY PLAN OR IMPROVEMENT	Identified in Planning Document or Study	
	Improves Quality of or Provides Added Capacity to Existing Services	
	Provides Incentive for Economic Development	
	Responds to a Citywide Goal or Submitted Resident Request	



Project Description: This project is the replacement of Marine #1. The Coast Guard is looking at its staffing challenges and subsequently lifesaving missions and may require more assistance from local partners. This project would increase the safety of the operating platform for crews on the water. The Fire Department is working regionally to address potential coverage issues in the marine environment, and this project will address any shortfalls. Funding for FY27 has changed from \$250,000 to \$900,000 due to the change of style of desired boat to one with a safer, enclosed platform.

Impact on the Operating Budget	Negligible (<\$5,001)
Personnel	N/A
Non-Personnel Line-Items	N/A
Notes of Changes in Funding Plan from FY26-31 CIP:	

Project Funding		FY27	FY28	FY29	FY30	FY31	FY32	Totals 27-32
Capital Outlay (GF)	0%							\$0
Federal/State	0%							\$0
Bond/Lease	100%	\$900,000						\$900,000
Other	0%							\$0
Revenues	0%							\$0

Policies Compliance	
Percent for Art	
Cultural Plan	
Community Health Plan	
Complete Streets	

PPP	0%							\$0
	Totals	\$900,000	\$0	\$0	\$0	\$0	\$0	\$900,000

CAPITAL IMPROVEMENT PLAN

FY 27-32

Climate Action Plan	
Green Building Policy	



Karen S. Conard
City Manager

CITY OF PORTSMOUTH

Municipal Complex
1 Junkins Avenue
Portsmouth, New Hampshire 03801
kconard@portsmouthnh.gov
(603) 610-7201

Date: October 22, 2026

To: Honorable Mayor McEachern and City Council Members

From: Karen S. Conard, City Manager

Re: City Manager's Comments on City Council Agenda of October 26, 2026

10. Public Hearings and Vote on Ordinances and/or Resolutions:

A. Third and Final Reading to Amend Chapter 10, Zoning Ordinance, which will remove most parking regulations from the Zoning Ordinance to the Site Plan Review Regulations (except one and two-family dwellings):

The Planning Board, at its meeting of August 20, 2026, voted to recommend that the City Council hold first reading on amendments to the Portsmouth Zoning Ordinance related to off-street parking. The proposed amendments remove most parking regulations from the Zoning Ordinance because they are more appropriately administered through Site Plan Review Regulations. The Zoning Ordinance will still include parking requirements for one and two-family dwellings but all other references to parking regulations will be in Site Plan Review Regulations rather than in the Zoning Ordinance. These amendments are being proposed in order to simplify the Zoning Ordinance and to create a clearer separation between zoning standards and site plan review requirements.

The Planning Board is concurrently considering amendments to the Site Plan Review Regulations that would incorporate those parking standards being removed from the Zoning Ordinance. The goal of these amendments is to help simplify and modernize the City's parking regulations to streamline parking classifications, consolidate parking flexibility provisions, and provide greater administrative flexibility in applying parking requirements.

The Planning Board approved the proposed changes to the Site Plan Review Regulations on September 17, 2026. The changes will take effect when the City Council adopts the related zoning amendments.

I recommend that the City Council move to pass third and final reading as presented.

B. Public Hearing and Adoption of Resolution #15-2026 Authorizing a Bond Issue and/or Notes of the City under the Municipal Finance Act of up to Six Hundred Thousand Dollars (\$600,000) for Costs Related to the Purchase of One Fire Apparatus:

The enclosed Resolution was considered at the August 3, 2026, City Council meeting as a Public Hearing with a presentation. City Council action was tabled pending the outcome of the City's application to the FEMA Port Security Grant Program.

I recommend that the City Council move to adopt Resolution #15-2026 as presented.

11. City Manager's Items Which Require Action:

A. Request for Solid Waste Ordinance Work Session:

Department of Public Works and Legal Department staff have been reviewing the City's ordinance related to the collection of solid waste, yard waste, and recycling in preparation for the Department of Public Work's transition to the collection of solid waste via an automated side loader (one-armed bandit colloquially). During that review, it became clear that various elements of the existing ordinance should be revisited. The ordinance should not only be updated to better align with the use of wheeled trash or recycling bins (also referred to as toters) and this new collection method, but also adjusted to address existing implementation challenges within the downtown collection area which include:

- The high degree of contamination in recyclables;
- The excessive volume of trash and recyclables placed out for pickup;
- Expectations of commercial collection outside the downtown collection area;

Staff request a work session with the City Council to better inform an ordinance update.

By way of background, most commercial entities in the City are required to manage their own disposal of solid waste and recyclables. An exception is made for certain streets identified in Chapter 3, Article II, Section 3.202 as follows:

Congress Street from Middle Street to Market Square	High Street from Congress Street to Ladd Street
Ladd Street from High Street to Market Street	Market Street from Market Square to Deer Street
Daniel Street from State Street to Market Square	State Street from Daniel Street to Middle Street
Pleasant Street from Court Street to Market Square	Chapel Street from Bow Street to State Street
Porter Street from Middle Street to Pleasant Street	Sheafe Street from Chapel Street to Penhallow Street
Bow Street from Daniel Street to Market Street	Penhallow Street from State Street to Bow Street
Hanover Street from Market Street to Maplewood Avenue	High Street from Hanover Street to Deer Street
Fleet Street from Hanover Street to State Street	

The limited, defined area, called the Downtown Business District in Chapter 3, Article II, is not identical with the Zoning Ordinance's Downtown Overlay District. Staff identified commercial entities that are receiving municipal pickup outside of the ordinance defined Downtown Business District.

Staff further identified compliance issues within the Downtown Business District relative to volume of waste and recyclables. The Solid Waste Ordinance limits weekly pick-up for commercial properties in the Downtown Business District to no more than 300 US gallons of solid waste (Chapter 3, Article II, Section 3.203 (B) (1)). Waste placed curbside for pick-up must be kept in covered, sanitary containers not exceeding a volume of 100 US gallons. Recyclables placed out for collection have additional requirements and often the recyclables placed for collection by the businesses are too contaminated to be recycled (Chapter 3, Article II, Section 3.203(C)). The excessive volume of trash recyclables in the Downtown Business District is occasionally impeding pedestrian passage on the sidewalk, creating a health hazard and creating unsightliness.

I recommend that the City Council move to schedule a Solid Waste Ordinance Work Session on December 7, 2026, at 6:00 p.m. to allow staff to provide additional details on solid waste collection challenges and receive City Council and public input.

B. Request for First Reading on Sewer Ordinance:

Enclosed is a proposed comprehensive update to the City's Sewer Use Ordinance (SUO). Staff requests that this ordinance update be brought forward for first reading on November 17, 2026. This ordinance update is required by the City's federally issued Wastewater Discharge Permits for the Peirce Island and Pease Wastewater Treatment Facilities and includes federally required language to regulate industrial dischargers.

By way of background, the City of Portsmouth Sewer Division has long regulated industrial users through local ordinance following guidance issued by the NH Department of Environmental Services (NH DES) and the US Environmental Protection Agency (EPA). In 2023, the EPA issued final National Pollutant Discharge Elimination System (NPDES) Permits for the City's two Wastewater Treatment Facilities. The Permits require the City to transition from its local program to federally approved Industrial Pretreatment Programs (IPP) for each Facility.

The City submitted draft IPP program documents to EPA and NH DES in September 2024 for Pease and May 2025 for Peirce Island. Both agencies reviewed the documents, which were updated and resubmitted with all reviewers' comments addressed. EPA provided public notice of the IPP program documents and received no public comments. With the agencies' review and approval phase now complete, the City must take the next steps to update our ordinance.

A significant portion of the IPP is a comprehensive update to the SUO. The SUO was developed based on EPA guidance and templates to codify dischargers' requirements and establish the City's legal authority to administer all IPP program components.

City staff have been communicating and coordinating with the City's currently permitted industrial dischargers, reviewing their existing Permit requirements, and highlighting what will be different in their next Permits. Approximately 90–120 days after adoption of the SUO, staff anticipates issuing the new generation of Permits, as well as revised Permits for insignificant dischargers by volume of high-strength wastewater, namely the City's three microbreweries.

Legal and Public Works Department staff will provide a detailed presentation at a future public hearing and second reading.

I recommend that the City Council move to schedule first reading on November 16, 2026, regarding an amendment to the Sewer Use Ordinance which will delete in its entirety the existing ordinance in Chapter 11, Article II, and replace it with a new ordinance in Chapter 16, Utilities, Article III, Sewers.

C. Friends of Lafayette House PILOT Agreement for FY2027:

Enclosed please find the request from Friends of Lafayette House to enter into a Payment in Lieu of Taxes (PILOT) Agreement with the City in the amount of \$3,500 for FY 2027. The form of the Agreement has been approved by the City Attorney.

I recommend that the City Council move to authorize the City Manager to enter into a PILOT Agreement with Friends of Lafayette House in the amount of \$3,500 for FY2027.

D. Betty's Dream Foundation PILOT Agreement for FY2027:

Enclosed please find the request from Portsmouth Housing Authority, Management Agent for Betty's Dream Foundation to enter into a Payment in Lieu of Taxes (PILOT) Agreement with the City in the amount of \$3,000 for FY 2027. The form of the Agreement has been approved by the City Attorney.

I recommend that the City Council move to authorize the City Manager to enter into a PILOT Agreement with Betty's Dream Foundation in the amount of \$3,000 for FY2027.

E. Planning Board Recommendation Regarding Licenses and a Sidewalk Easement for 361 Hanover Street:

Enclosed please find a memorandum from Assistant Planning Director Peter Stith regarding the Planning Board's October 15, 2026, vote regarding 361 Hanover Street and a corresponding exhibit.

I recommend that the City Council move to authorize the City Manager to accept and record a Sidewalk Easement, a Landscape License, and a Pole License from 361 Hanover Steam Factory, LLC for 361 Hanover Street in a form acceptable to the City Attorney, subject to the recommendations in the enclosed memorandum from Assistant Planning Director Stith.

F. Memorandum of Agreement – Portsmouth Professional Fire Officers Association, Local #4039:

Enclosed for your consideration is a Memorandum of Agreement (MOA) between the City and the Portsmouth Professional Fire Officers Association, Local #4039, allowing for a temporary amendment to the current Collective Bargaining Agreement.

Key provisions of the MOA include:

- Correcting the pay of one internal Officer who was recently promoted;
- Allowing this Officer to progress through the subsequent pay steps; and
- Providing a one-time remedy to the current pay inequity that occurs when promoting a Firefighter to Fire Officer.

I recommend that the City Council move to approve the Memorandum of Agreement with the Portsmouth Professional Fire Officers Association, Local #4039 as presented.

G. Planning Board Recommendation on Cornwall Street:

Enclosed please find a memorandum from Assistant Planning Director Peter Stith regarding the Planning Board's October 15, 2026, vote regarding a portion of Cornwall Street. As noted in the memorandum, the Planning Board voted unanimously to recommend that the City Council approve the discontinuance of the identified portion of Cornwall Street, subject to the recording of a municipal utility easement over the existing sewer line and requesting a voluntary lot merger to align the parcel boundaries with the configuration shown on the City's tax map.

I recommend that the City Council move to schedule a public hearing on the discontinuance of the identified portion of Cornwall Street at the November 16, 2026, City Council Meeting.

H. Planning Board Recommendation on Taft Road:

Enclosed please find a memorandum from Assistant Planning Director Peter Stith regarding the Planning Board's October 15th vote regarding the request to discontinuance of a portion of Taft Road. As noted in the memorandum, the Planning Board voted unanimously to recommend that the City Council approve the discontinuance of the identified portion of Taft Road, subject to the recording of a municipal utility easement over the existing water line.

I recommend that the City Council move to approve the discontinuance of the identified portion of Taft Road, subject to the recording of a Municipal Utility Easement over the existing water line in a form acceptable to the City Attorney.

I. Planning Board Recommendation on 0 Elm Street:

Enclosed please find a memorandum from Assistant Planning Director Peter Stith regarding the Planning Board's October 15, 2026, vote regarding property located at 0 Elm Street.

The City Council has two options this evening:

- *move to authorize issuance of a Building Permit for 0 Elm Street contingent on the applicant obtaining all other required variances, approvals, and permits, and on construction of a driveway adequate for emergency vehicle access as approved by the Department of Public Works and the Fire Department; this authorization confers no private right of access over Forrest Street or any other private property; or*
- *move to deny the request on the ground that the lot has no frontage and does not abut any constructed private road or other street.*

J. Sidewalk Easement for Property Located at 48-50 Langdon Street:

At its regularly scheduled meeting on November 20, 2025, the Planning Board granted Site Plan Review and Subdivision approval for property located at 48-50 Langdon Street for the approval of a subdivision into two lots with a single-family dwelling and accessory dwelling units proposed on each lot with associated site improvements. As a part of the Site Plan approval, the Planning Board recommended that the City Council accept a Sidewalk Easement over a narrow strip at the front of the parcel, as shown on the depiction included in the City Council packet.

The Legal, Planning & Sustainability and Public Works Departments all recommend acceptance of this Easement.

I recommend that the City Council move to authorize the City Manager to accept and record a Sidewalk Easement Deed from Martin Husslage.

16. Approval of Grants/Donations:

A. Point of Graves Cemetery Donations:

Enclosed please find donation forms from an anonymous resident, Charles & Barbara Bickford, and Michael Pennington summarizing donations to the Point of Graves Cemetery Wall Replacement Project.

I recommend that the City Council move to accept with thanks donations for the Point of Graves Cemetery Wall Replacement from an anonymous resident, Charles & Barbara Bickford, and Michael Pennington, in the amounts as presented in the attached Gift and Donation Submission Forms.

B. FY26 Byrne Discretionary Community Projects Grant in the Amount of \$1,000,000 from the Office of Justice Programs to Fund NH Internet Crimes Against Children Task Force's COPS and Enhanced Capacity Program:

At the October 20, 2026, Police Commission meeting, the Board of Police Commissioners voted to approve and accept the FY26 Byrne Discretionary Community Projects Grant in the amount of \$1,000,000 from the Office of Justice Programs to fund the NH Internet Crimes

Against Children Task Force’s COPS and Enhanced Capacity Program. This grant is aimed at strengthening affiliate agencies’ investigative and forensic capabilities.

I recommend that the City Council move to accept the FY26 Byrne Discretionary Community Projects Grant in the amount of \$1,000,000 and its terms and conditions from the Office of Justice Programs to fund NH Internet Crimes Against Children Task Force's COPS and Enhanced Capacity Program.

C. **FY26 COPS Technology and Equipment Program Grant in the Amount of \$1,031,000, from the Office of Community Oriented Policing Service for the Portsmouth Police Department:**

At the October 20, 2026, Police Commission meeting, the Board of Police Commissioners voted to approve and accept the FY26 COPS Technology and Equipment Program Grant in the amount of \$1,031,000 from the Office of Community Oriented Policing Service for the Portsmouth Police Department. This Grant will be utilized for the acquisition of advanced law enforcement equipment, technologies, and interoperable communications that prevent crime and expand community policing.

I recommend that the City Council move to accept the FY26 COPS Technology and Equipment Program Grant in the amount of \$1,031,000 and its terms and conditions from the Office of Community Oriented Policing Service for the Portsmouth Police Department.

17. City Manager’s Informational Items:

A. **Annual Food and Liquor Permit Renewals:**

Enclosed in your packet this evening is a memorandum from the City’s Health Department regarding their annual food and liquor permit data.

B. **Pease Development Authority Board Meeting Update:**

I will provide a verbal update on the October 20, 2026, Pease Development Authority Board meeting.

C. **Resident Access Parking Program (RAPP) Q1 Report Back:**

Enclosed please find a presentation on RAPP Q1 results and recommendations.

D. **Off-Peak/Workweek Parking for Downtown Businesses Report Back:**

There will be a presentation on off-peak/workweek parking options for businesses at this evening’s meeting.

E. **General Fund Revenues Update:**

Deputy City Manager – Finance and Administration Nathan Lunney will provide a brief update on General Fund revenues.

F. Offsite Water and Sewer Improvements - Borthwick Avenue and Sherburne Property:

At the presentation by the Portsmouth Housing Authority (PHA) to the City Council at its regular meeting on September 28, 2026, regarding the status of their housing redevelopment project at the former Sherburne School property, one of the issues raised during that discussion was sewer infrastructure needs along Borthwick Avenue.

City staff have identified a need to upgrade this sewer line, separate from the housing project. As part of the US Environmental Protection Agency's per- and polyfluoroalkyl substances – (PFAS) requirements, the City is commencing design of a new treatment facility at the drinking water well site off Griffin Road. This new treatment system will require additional sewer capacity for sections of sewer mains including the section of Borthwick Avenue. City staff recognize that upgrading the section of sewer along Borthwick Avenue will also provide additional benefit by providing additional sewer capacity to support commercial and housing development. In addition, the existing sewer main is in an undesirable configuration outside of the roadway, causing issues with access and maintenance in occupied parking lots. The City intends to pay for this utility work with existing capital monies from the Water and Sewer Enterprise Funds.

G. Mechanic Street Pump Station 2nd Public Meeting – November 9, 2026, in Council Chambers at 6:30 pm:

Public Works staff will host a second Mechanic Street Pump Station Public Meeting to answer questions raised at the first meeting and to provide additional information on November 9th at 6:30 p.m. in City Council Chambers.

ORDINANCE # _____

THE CITY OF PORTSMOUTH ORDAINS

That Chapter 11, Article II, SEWERS be deleted in its entirety and replaced with a new Chapter 16, Article III, SEWERS to be adopted in its entirety as set forth below:

Contents

ARTICLE III: SEWERS	5
DIVISION 1—GENERAL PROVISIONS	5
Section 16.301: PURPOSE AND POLICY	5
Section 16.302: ADMINISTRATION.....	5
Section 16.303: ABBREVIATIONS.....	6
Section 16.304: DEFINITIONS.....	6
Section 16.305 – 16.310: RESERVED.....	18
DIVISION 2—GENERAL SEWER USE REQUIREMENTS	18
Section 16.311: USE OF PUBLIC SEWERS REQUIRED.....	18
Section 16.312: PRIVATE SEWAGE DISPOSAL.....	19
Section 16.313: BUILDING SEWERS AND CONNECTIONS.....	20
Section 16.314: PROHIBITED DISCHARGE STANDARDS	23
Section 16.315: FEDERAL CATEGORICAL PRETREATMENT STANDARDS	25
Section 16.316: LOCAL DISCHARGE RESTRICTIONS.....	26
Section 16.317: CITY’S RIGHT OF REVISION.....	27
Section 16.318: DILUTION.....	27
Section 16.319: MASS-BASED LIMITATIONS.....	27
Section 16.320: RESERVED	28
DIVISION 3—PRETREATMENT OF WASTEWATER.....	28
Section 16.321: PRETREATMENT FACILITIES	28
Section 16.322: ADDITIONAL PRETREATMENT MEASURES	28
Section 16.323: ACCIDENTAL DISCHARGE/SLUG CONTROL PLANS	29
Section 16.324: POLLUTION PREVENTION PLANS.....	30
Section 16.325: FATS, OILS, AND GREASE (FOG) PROGRAM	31
Section 16.326-16.330: RESERVED	32
DIVISION 4—INDUSTRIAL DISCHARGE PERMIT (IDP) APPLICATION	32
Section 16.331: INDUSTRIAL USER CLASSIFICATION SYSTEM.....	32
Section 16.332: WASTEWATER CHARACTERIZATION.....	34

Section 16.333: IDP REQUIREMENT	34
Section 16.334: EXISTING CONNECTIONS	34
Section 16.335: NEW CONNECTIONS	34
Section 16.336: FEDERAL CATEGORICAL PRETREATMENT STANDARDS	35
Section 16.337: IDP APPLICATION CONTENTS	35
Section 16.338: SIGNATORIES AND CERTIFICATION	35
Section 16.339 and 16.340: RESERVED	36
DIVISION 5—INDUSTRIAL DISCHARGE PERMIT (IDP) ISSUANCE PROCESS	36
Section 16.341: IDP DECISIONS	36
Section 16.342: IDP DURATION	36
Section 16.343: IDP CONTENT	36
Section 16.344: IDP APPEALS	38
Section 16.345: IDP MODIFICATION	38
Section 16.346: IDP TRANSFER	39
Section 16.347: IDP REISSUANCE	39
Section 16.348-16.350: RESERVED	39
DIVISION 6—REPORTING REQUIREMENTS	40
Section 16.351: BASELINE MONITORING REPORTS	40
Section 16.352: COMPLIANCE SCHEDULES/PROGRESS REPORTS	42
Section 16.353: REPORTS ON COMPLIANCE WITH CATEGORICAL PRETREATMENT DEADLINE	42
Section 16.354: PERIODIC COMPLIANCE REPORTS	42
Section 16.355: REPORTS OF CHANGED CONDITIONS	43
Section 16.356: REPORTS OF SLUGS OR POTENTIALLY ADVERSE DISCHARGES	43
Section 16.357: REPORTS FROM UNPERMITTED USERS	44
Section 16.358: NOTICE OF VIOLATION / REPEAT SAMPLING AND REPORTING	44
Section 16.359: NOTICE OF DISCHARGE OF HAZARDOUS WASTE	44
Section 16.360: ANALYTICAL REQUIREMENTS	45
Section 16.361: SAMPLE COLLECTION	45
Section 16.362: TIMING	46
Section 16.363: RECORDKEEPING	46
Section 16.364-16.370: RESERVED	47
DIVISION 7—POWERS AND AUTHORITIES OF INSPECTORS	47
Section 16.371: RIGHT OF ENTRY: INSPECTION AND SAMPLING	47
Section 16.372: ADMINISTRATIVE INSPECTION WARRANT	48
Section 16.373-16.375: RESERVED	48
DIVISION 8—CONFIDENTIAL INFORMATION	48

Section 16.376: CONFIDENTIAL INFORMATION	48
Section 16.377-16.380: RESERVED	48
DIVISION 9—PUBLICATION OF USERS IN SIGNIFICANT NONCOMPLIANCE	48
Section 16.381: ANNUAL PUBLICATION	48
Section 16.382: RESERVED	49
DIVISION 10—ADMINISTRATIVE ENFORCEMENT REMEDIES	49
Section 16.383: NOTIFICATION OF VIOLATION	49
Section 16.384: COMPLIANCE SCHEDULE DEVELOPMENT	50
Section 16.385: POLLUTION PREVENTION PLAN DEVELOPMENT	50
Section 16.386: ADMINISTRATIVE ORDERS	50
Section 16.387: TERMINATION OF CONNECTION AND REVOCATION	51
Section 16.388: EMERGENCY SUSPENSIONS	51
Section 16.389: RECOVERY OF EXPENSES	52
Section 16.390 - 16.395: RESERVED	52
DIVISION 11—JUDICIAL ENFORCEMENT REMEDIES	52
Section 16.396: INJUNCTIVE RELIEF	52
Section 16.397: CIVIL PENALTIES	52
Section 16.398: CRIMINAL PROSECUTION	53
Section 16.399: REMEDIES NONEXCLUSIVE	53
Section 16.400: RESERVED	53
DIVISION 12—AFFIRMATIVE DEFENSES TO DISCHARGE VIOLATIONS.....	53
Section 16.401: UPSET	53
Section 16.402: PROHIBITED DISCHARGE STANDARDS	54
Section 16.403: BYPASS	54
Section 16.404 – 16.405: RESERVED	56
DIVISION 13—SEPTAGE DISPOSAL.....	56
Section 16.406: SEPTIC TANK WASTE (SEPTAGE)	56
Section 16.407: RESERVED	56
DIVISION 14—SEWER USE RATES AND FEES.....	56
Section 16.408: RATES AND FEES	56
Section 16.409: IRRIGATION METERS	57
Section 16.410: BILLING AND OTHER METERS	58
Section 16.411-12: RESERVED	58
DIVISION 15—MISCELLANEOUS	58
Section 16.413: VALIDITY	58
Section 16.414: LIMITS OF LIABILITY	59

Section 16.415: INTERPRETATION.....	59
Section 16.416: APPEALS.....	59
APPENDICES.....	61
Appendix I – Maximum Allowable Industrial Mass Loading Limitations / Local Limits	61

ARTICLE III: SEWERS

DIVISION 1—GENERAL PROVISIONS

Section 16.301: PURPOSE AND POLICY

This Ordinance sets forth uniform requirements for users of the Publicly Owned Treatment Works (POTW) of the City of Portsmouth and enables the City to comply with applicable State and Federal laws, including the Clean Water Act (33 United States Code § 1251 *et seq.*), and the General Pretreatment Regulations (40 Code of Federal Regulations Part 403). The objectives of this Ordinance are:

- A. To promote, consistent with the policy of the Federal government:
 - i. The prevention or reduction of pollutants at the source whenever feasible;
 - ii. Recycling in an environmentally safe manner when the creation of pollutants cannot be prevented; and
 - iii. Treatment and disposal in an environmentally safe manner of pollution that cannot be prevented or recycled.
- B. To prevent the introduction of pollutants into the POTW that will interfere with its operation;
- C. To prevent the introduction of pollutants into the POTW that will Pass Through the POTW inadequately treated into receiving waters or otherwise be incompatible with the operation of the POTW;
- D. To protect both POTW personnel who may be affected by wastewater and biosolids in the course of their employment and the general public;
- E. To promote reuse of biosolids from the WWTFs;
- F. To provide for fees for the equitable distribution of the cost of operation, maintenance, and improvement of the POTW; and
- G. To enable the City to comply with its National Pollutant Discharge Elimination System permit conditions, Federal Industrial Pretreatment Program requirements, biosolids use and disposal requirements, and any other Federal or State laws to which the POTW is subject.

Section 16.302: ADMINISTRATION

Except as otherwise provided herein, the Director of Public Works (Director) shall have the authority to administer, implement, and enforce the provisions of this Ordinance. This shall include without limitation the authority to develop such forms, technical standards, Local Limits, Best Management Practices, rules, policies, and operational requirements as may be required to

implement the provisions of this Ordinance. This shall further include without limitation the power to recommend the adoption of fees, to issue and enter into Administrative Orders, to issue fines and penalties and to require actions to implement the purposes of this Ordinance. Any powers granted to, or duties imposed upon the Director, may be delegated by the Director to other designated persons.

Section 16.303: ABBREVIATIONS

The following abbreviations, when used in this Ordinance, shall have the following designated meanings:

BOD - Biochemical Oxygen Demand
BMP - Best Management Practice
BMR - Baseline Monitoring Report
CFR - Code of Federal Regulations
CIU - Categorical Industrial User
COD - Chemical Oxygen Demand
EPA - United States Environmental Protection Agency
FOG - Fats, Oils, and Grease
FSE - Food Service Establishment
gpd - Gallons per day
IDP - Industrial Discharge Permit
mg/L - Milligrams per liter
NHDES - New Hampshire Department of Environmental Services
NPDES - National Pollutant Discharge Elimination System
NSCIU - Non-significant Categorical Industrial User
POTW - Publicly Owned Treatment Works
RSA - New Hampshire Revised Statute Annotated
SIU - Significant Industrial User
SNC - Significant Noncompliance
TSS - Total Suspended Solids
WWTF - Wastewater Treatment Facility
°F, °C - degrees Fahrenheit, degrees Celsius

Section 16.304: DEFINITIONS

- A. Unless the context specifically indicates otherwise, the meaning of terms used in this Ordinance shall be as follows:
1. “*Authorized Representative of the Connector*” shall mean:
 - a. If the Connector is a corporation:
 - i. The president, secretary, treasurer, or vice-president of the corporation in charge of a principal business function, or any other person who performs similar policy or decision-making functions for the corporation; or

- ii. The manager of one (1) or more manufacturing, production or operating facilities, provided the manager is authorized to make management decisions that govern the operation of the regulated facility including having the explicit or implicit duty of making major capital investment recommendations, and initiate and direct other comprehensive measures to assure long-term environmental compliance with environmental laws and regulations; can ensure that the necessary systems are established or actions taken to gather complete and accurate information for individual wastewater discharge permit or general permit requirements; and where authority to sign documents has been assigned or delegated to the manager in accordance with corporate procedures.
 - b. If the Connector is a partnership or sole proprietorship: a general partner or proprietor, respectively.
 - c. If the Connector is a Federal, state, or local governmental facility: a director or highest official appointed or designated to oversee the operation and performance of the activities of the government facility.
 - d. The individuals described in paragraphs (a) through (c), above, may designate another authorized representative if the authorization is in writing, the authorization specifies the individual or position responsible for the overall operation of the facility from which the discharge originates or having overall responsibility for environmental matters for the company, and the written authorization is submitted to the City.
2. “*Best Management Practices*” or “*BMPs*” shall mean schedules of activities, prohibitions of practices, maintenance procedures, and other management practices to implement the prohibitions listed in section 16.311 of this Ordinance [40 CFR 403.5(a)(1) and (b)]. BMPs include treatment requirements, operating procedures, and practices to control plant site runoff, spillage or leaks, sludge or waste disposal, or drainage from raw materials storage. BMPs also include alternative means (i.e., management plans) of complying with, or in place of certain established s and effluent limits.
 3. “*Biochemical Oxygen Demand*” or “*BOD*” shall mean the quantity of oxygen utilized in the biochemical oxidation of organic matter under standard laboratory procedures for five (5) days at 20° centigrade, usually expressed as a concentration (e.g., mg/l).
 4. “*Building Drain*” shall mean that part of the lowest horizontal piping of a drainage system that receives the discharge from soil, waste, and other drainage pipes inside the walls of the building and conveys it to the Building Sewer, beginning five (5) feet outside the inner face of the building wall. For the purposes of this Ordinance the term "Building Drain" shall be synonymous with the terms "House Drain" and "House Sewer" as defined in the Plumbing Code.

5. “*Building Sewer*” shall mean the extension from the Building Drain to the public sewer or other place of disposal, also called house connection. For the purposes of this Ordinance the term "Building Sewer" shall be synonymous with the terms "House Drain" and "House Sewer" as defined in the Plumbing Code.
6. “*Capacity Improvements Multiplier*” shall mean the multiplier used as part of the Capacity Use Surcharge formula to generate funds to be used for capital improvements necessary to serve future users. The Capacity Improvements Multiplier shall be established as part of the rate setting process.
7. “*Capacity Use Surcharge*” shall mean a one-time fee assessed by the POTW at the time of the connection. The Capacity Use Surcharge shall be calculated as follows: (projected average daily flow/equivalent dwelling unit) multiplied by the Capacity Improvements Multiplier. The equivalent dwelling unit shall be set as part of the rate setting process.
8. “*Categorical Industrial User*” shall mean an Industrial User subject to a Categorical Pretreatment Standard or Categorical Standard;
9. “*Categorical Pretreatment Standard*” or “*Categorical Standard*” shall mean any regulation containing pollutant discharge limitations promulgated by EPA in accordance with sections 307(b) and (c) of the Clean Water Act (33 U.S.C. § 1317) that apply to a specific category of users and that appear in 40 CFR chapter I, subchapter N, parts 405—471.
10. “*Chemical Oxygen Demand*” or “*COD*” shall mean a measure of the oxygen required to oxidize all compounds, both organic and inorganic, in water.
11. “*City*” shall mean the City of Portsmouth, New Hampshire which is the control authority as that term is defined and used within the Clean Water Act and its implementing regulations.
12. “*Combined Sewer*” shall mean a sewer intended to receive both wastewater and storm or surface water.
13. “*Connector*” shall mean all persons proposing to connect or connected to the POTW, inclusive of all residential, commercial and industrial dischargers.
14. “*Daily Maximum*” shall mean the arithmetic average of all effluent samples for a pollutant collected during a calendar day.
15. “*Daily Maximum Limit*” shall mean the maximum allowable discharge limit of a pollutant during a calendar day. Where Daily Maximum Limits are expressed in units of mass, the daily discharge is the total mass discharged over the course of the day. Where Daily Maximum Limits are expressed in terms of a concentration, the daily discharge is the arithmetic average measurement of the pollutant

concentration derived from all measurements taken that day.

16. “*Department*” shall mean the Department of Public Works, including the Director or duly authorized representatives.
17. “*Director*” or “*Director of Public Works*” shall mean the person designated by the City to be responsible for the overall operation of the POTW, and who is charged with certain duties and responsibilities by this Ordinance, or duly authorized representatives.
18. “*Domestic Wastewater*” or “*Sewage*” shall mean household and toilet wastes or waste from sanitary conveniences of residences, commercial buildings, and industrial plants, excluding ground, surface, or Stormwater. (See also: Industrial Wastes.) Domestic Wastewater shall contain not more than 250 mg/L BOD and not more than 250 mg/L TSS.
19. “*Drain Layer*” shall mean a person licensed by the Department of Public Works as a layer of drains and other pipes connected to the POTW.
20. “*Environmental Protection Agency*” or “*EPA*” shall mean the United States Environmental Protection Agency or, where appropriate, the EPA Regional Water Management Division Director, or other duly authorized official of the agency.
21. “*Existing Source*” shall mean any source of discharge that is not a New Source.
22. “*Garbage*” shall mean the animal and vegetable waste resulting from the handling, preparation, cooking, and serving of foods.
23. “*Grab Sample*” shall mean a sample that is taken from a waste stream without regard to the flow in the waste stream and over a period of time not to exceed fifteen (15) minutes.
24. “*Grease*” shall mean the material removed from a Grease interceptor (trap) serving a restaurant or other facility requiring such Grease interceptors. Grease also shall mean volatile and non-volatile residual fats, fatty acids, soaps, waxes and other similar materials.
25. “*Hauler*” shall mean those persons, firms, or corporations, who pump, haul, transport, or dispose of Septage and who are licensed and regulated by the New Hampshire Department of Environmental Services pursuant to RSA 485-A.
26. “*House Drain*” shall mean that part of the lowest horizontal piping of drainage system which receives the discharge from soil, waste, and other drainage pipes inside the walls of a building and conveys it to the Building Sewer, beginning 8 feet outside the outer face of the building wall. For the purposes of this Ordinance

the term "House Drain" shall be synonymous with the term "Building Drain" as defined in Section 15.101 of the Plumbing Code.

27. *"House Sewer"* shall mean the extension from the Building Drain to the public sewer or other place of disposal including that portion of the line on public property. For the purposes of this Ordinance the term "House Sewer" shall be synonymous with the term "Building Sewer" as defined in the Plumbing Code.
28. *"Human Excrement"* shall mean the liquid or solid matter discharged from the intestinal canal of a human, or other liquid or solid waste materials that are likely to undergo bacterial decomposition; provided, however, that these terms shall not include "refuse" as defined in RSA 145-M.
29. *"Industrial Discharge Permit"* or *"IDP"* shall mean the written permit between the City and an Industrial User that outlines the conditions under which discharge to the POTW will be accepted.
30. *"Industrial User"* or *"User"* shall mean any Connector that introduces a Non-Domestic Wastewater into the POTW.
31. *"Industrial Wastes"* or *"Non-Domestic Wastewater"* shall mean the wastewater and waterborne wastes from any liquid, gaseous, or solid waste substance resulting from any process of industry, manufacturing trade or business or from development of any natural resources as distinct from Domestic Wastewater, Sewage or Unpolluted water.
32. *"Industrial Pretreatment Program"* shall mean the EPA approved pretreatment program.
33. *"Injunction"* shall mean an order to a party to affirmatively perform, or to refrain from performing, some designated action. Such orders may be issued by a court with jurisdiction over the matter or a federal, state or local authority when authorized to do so.
34. *"Injunctive Relief"* shall mean, generally, the action ordered by a court or other authorized authority.
35. *"Instantaneous Limit"* shall mean the maximum concentration of a pollutant allowed to be discharged at any time, determined from the analysis of any discrete or composite sample collected, independent of the industrial flow rate and the duration of the sampling event.
36. *"Interference"* shall mean an indirect discharge that, alone or in conjunction with indirect discharge(s) from other sources:
 - (1) Inhibits or disrupts the POTW's treatment processes or operations, or its processing, use, or disposal of sludge in compliance with applicable statutes

- and rules;
- (2) Is a cause of a violation of any requirements of the POTW's federal or state discharge permit; or
 - (3) Prevents sewage sludge use or disposal in compliance with the following statutory provisions and rules or permits issued thereunder:
 - a. Env-Sw 100 et seq. relative to solid waste management;
 - b. Env-A 100 et seq. relative to air pollution control;
 - c. The General Pretreatment Regulations For Existing and New Sources of Pollution, 40 CFR 403;
 - d. The Federal Toxic Substances Control Act, 15 U.S.C. ch. 53;
 - e. The Federal Marine Protection, Research and Sanctuaries Act, 33 U.S.C. §1401-1445 and 16 U.S.C. §§ 1431-1445; and
 - f. Env-Wq 800 and 40 CFR Part 503 relative to use or disposal of sewage sludge.
37. *“Local Limit”* shall mean specific discharge limits developed and enforced by the City upon industrial or commercial facilities to implement the general and specific discharge prohibitions listed in 40 CFR 403.5(a)(1) and (b).
 38. *“Medical/Infectious Waste”* shall mean any solid waste that is generated in the diagnosis, treatment, or immunization of human beings or animals, in research pertaining thereto, or in the production or testing of biologicals.
 39. *“National Pollutant Discharge Elimination System permit”* or *“NPDES permit”* shall mean a permit issued pursuant to section 402 of the Clean Water Act (33 U.S.C. 1342).
 40. *“Natural Outlet”* shall mean any outlet, including Storm Sewers and Combined Sewer overflows, into a Watercourse, pond, ditch, lake, or other body or surface water or groundwater.
 41. *“New Source”* shall mean:
 - a. Any building, structure, facility, or installation from which there is or may be a discharge of pollutants, the construction of which commenced subsequent to the publication of proposed Pretreatment Standards under section 307(c) of the Clean Water Act that will be applicable to such source if such standards are thereafter promulgated in accordance with that section, provided that:
 - i. The building, structure, facility, or installation is constructed at a site at which no other source is located;
 - ii. The building, structure, facility, or installation totally replaces the process or production equipment that causes the discharge of pollutants at an Existing Source; or
 - iii. The production or wastewater-generating processes of the building, structure, facility, or installation are substantially independent of an

Existing Source at the same site. In determining whether these are substantially independent, factors such as the extent to which the new facility is integrated with the existing plant, and the extent to which the new facility is engaged in the same general type of activity as the Existing Source, will be considered.

- b. Construction of a new source as defined under this paragraph has commenced if the owner or operator has:
 - i. Begun, or caused to begin, as part of a continuous on-site construction program:
 - c. Any placement, assembly, or installation of facilities or equipment; or significant site preparation work including clearing, excavation, or removal of existing buildings, structures, or facilities that is necessary for the placement, assembly, or installation of new source facilities or equipment; or
 - i. Entered into a binding contractual obligation for the purchase of facilities or equipment that are intended to be used in its operation within a reasonable time. Options to purchase or contracts that can be terminated or modified without substantial loss, and contracts for feasibility, engineering, and design studies do not constitute a contractual obligation under this subsection.
 - d. Construction on a site at which an Existing Source is located results in a modification rather than a new source if the construction does not create a new building, structure, facility, or installation meeting the criteria of paragraphs (a)(ii) or (a)(iii) above but otherwise alters, replaces, or adds to existing process or production equipment.
42. “*Noncontact Cooling Water*” shall mean water used for cooling that does not directly contact any raw material, intermediate product, waste product, or finished product.
43. “*Pass Through*” shall mean a discharge that exits the WWTF into waters of the United States in quantities or concentrations that, alone or in conjunction with a discharge or discharges from other sources, is a cause of a violation of any requirement of the City's NPDES permit, including an increase in the magnitude or duration of a violation.
44. “*Person*” shall mean any individual, partnership, copartnership, firm, company, corporation, association, joint stock company, trust, estate, governmental entity, or any other legal entity; or their legal representatives, agents, or assigns. This definition includes all Federal, State, and local governmental entities.
45. “*Per- and Polyfluoroalkyl Substances*” or “*PFAS*” shall mean a group of man-made fluorinated compounds, many of which are hydrophobic and lipophobic, manufactured and used in a variety of industries globally.

46. “*pH*” shall mean a logarithmic measure devised to express the hydrogen ion concentration of a solution, expressed in standard units. Solutions with pH values greater than seven (7) are basic (or alkaline); solutions with pH values less than seven (7) are acidic.
47. “*Pharmaceutical Waste*” shall mean a prescription drug or nonprescription or proprietary medicine that is no longer suitable for its intended purpose or is otherwise being discarded.
48. “*Plumbing Inspector*” shall mean the person employed by the City to inspect plumbing or the authorized deputy, agent or representative of the Plumbing Inspector.
49. “*Pollutant*” shall mean dredged spoil, solid waste, incinerator residue, filter backwash, Sewage, garbage, Sewage sludge, munitions, Medical/Infectious Wastes, chemical wastes, biological materials, radioactive materials, heat, wrecked or discarded equipment, rock, sand, cellar dirt, municipal, agricultural and Industrial Wastes, and characteristics of wastewater (e.g., pH, temperature, TSS, turbidity, color, BOD, COD, toxicity, or odor).
50. “*Pollution Prevention*” shall mean the use of materials, processes, or practices that reduce or eliminate the creation of pollutants or wastes at the source, or minimize their release to the environment prior to recycling, treatment or disposal. It includes practices that reduce the use of hazardous materials, energy, water or other resources. It also includes practices that protect natural resources and human health through conservation, more efficient use, or effective release minimization.
51. “*Pretreatment*” shall mean the reduction of the amount of pollutants, the elimination of pollutants, or the alteration of the nature of pollutant properties in wastewater prior to, or in lieu of, introducing such pollutants into the POTW. This reduction or alteration can be obtained by physical, chemical, or biological processes; by process changes; or by other means, except by diluting the concentration of the pollutants unless allowed by an applicable Pretreatment Standard.
52. “*Pretreatment Requirements*” shall mean any substantive or procedural requirement related to Pretreatment imposed on a Connector, other than a Pretreatment Standard.
53. “*Pretreatment Standards*” shall mean Pretreatment Standards, Prohibited Discharge Standards, Categorical Pretreatment Standards, and Local Limits.
54. “*Prohibited Discharge Standards*” or “*Prohibited Discharges*” shall mean absolute prohibitions against the discharge of certain substances as identified in this Ordinance.

55. “*Publicly Owned Treatment Works*” or “*POTW*” means the City of Portsmouth wastewater treatment facilities whether owned or operated by the City of Portsmouth and all components of its collection system including all pipes, pump stations, and other equipment and structures. It also refers to the municipality in its function as a utility to manage the POTW. These meanings are coextensive with the definitions found in the Clean Water Act and Code of Federal Regulations at 40 CFR 501:2 et seq. for “treatment works,” “publicly owned treatment works” and “municipality.”
56. “*Radiological Waste*” shall mean radioactive waste as regulated by the State of New Hampshire RSA 125-F rules.
57. “*Sanitary Sewer*” shall mean a sewer that carries liquid and water-carried wastes from residences, commercial buildings, industrial facilities, and institutions, together with minor quantities of ground, storm, and surface waters that are not admitted intentionally.
58. “*Septage*” or “*Septic Tank Waste*” shall mean any liquid, solid, or sludge pumped from chemical toilets, vaults, septic tanks, or cesspools or other holding tanks, that have received only Domestic Wastewater.
59. “*Sewage*” shall mean Human Excrement and gray water (household showers, dishwashing operations, sink drains and similar uses).
60. “*Sewer*” shall mean a pipe or conduit that carries wastewater or Stormwater, groundwater, subsurface water, or Unpolluted water from any source.
61. “*Significant Industrial User*” shall mean:
- a. Except as provided in paragraphs (b) and (c) of this section, the term significant Industrial User shall mean:
 - i. All Industrial Users subject to Categorical Pretreatment Standards under 40 CFR 403.6 and 40 CFR chapter I, subchapter N; and
 - ii. Any other Industrial User that: discharges an average of twenty-five thousand (25,000) gallons per day or more of process wastewater to the WWTF (excluding sanitary, Noncontact Cooling Water and boiler blowdown wastewater); contributes a process waste stream which makes up five (5) percent or more of the average dry weather hydraulic or organic capacity of the WWTF; or is designated as such by the City on the basis that the Industrial User has a reasonable potential for adversely affecting the WWTF's operation or for violating any Pretreatment Standard or requirement (in accordance with 40 CFR 403.8(f)(6).
 - b. The City in conjunction with EPA may determine that an Industrial User subject to Categorical Pretreatment Standards under §403.6 and 40 CFR

chapter I, subchapter N is a non-significant Categorical Industrial User rather than a significant Industrial User on a finding that the Industrial User never discharges more than 100 gallons per day (gpd) of total Categorical wastewater (excluding sanitary, non-contact cooling and boiler blowdown wastewater, unless specifically included in the Pretreatment Standard) and the following conditions are met:

- i. The Industrial User, prior to the EPA/City finding, has consistently complied with all applicable Categorical Pretreatment Standards and requirements;
 - ii. The Industrial User annually submits the certification statement required in §403.12(q) together with any additional information necessary to support the certification statement; and
 - iii. The Industrial User never discharges any untreated concentrated wastewater.
- c. Upon a finding that an Industrial User meeting the criteria in paragraph (l)(ii) of this section has no reasonable potential for adversely affecting the WWTF's operation or for violating any Pretreatment Standards or requirement, EPA and/or the City may at any time, on their own initiative or in response to a petition received from an Industrial User or WWTF, and in accordance with 40 CFR 403.8(f)(6), determine that such Industrial User is not a significant Industrial User.

62. “*Significant Noncompliance*” or “*SNC*” shall mean an Industrial User is in Significant Noncompliance if its violation meets one (1) or more of the following criteria:

- a. *Chronic violations.* A pattern of violating the same Pretreatment Standard Daily Maximum or average limit (any magnitude of exceedance) sixty-six (66) percent or more of the time in a six-month period, including Instantaneous Limits;
- b. *Technical review criteria (TRC violations).* Thirty-three (33) percent or more of the measurements exceed the same Pretreatment Standard Daily Maximum Limit or average limit by more than the TRC factor in a six-month period, including Instantaneous Limits. The TRC factor is 1.4 for Biochemical Oxygen Demand (BOD), Total Suspended Solids (TSS), oil and Grease, and 1.2 for all other pollutants except pH;
- c. For pH monitoring, excursions shall be considered SNC when:
 - i. The total time during which the pH values are outside the required range of pH values exceeds seven (7) hours and twenty-six (26) minutes in any calendar month;
 - ii. An individual excursion from the range of pH values exceeds sixty (60) minutes;
 - iii. An excursion occurs that the City believes has caused, alone or in combination with other discharges, Interference or pass-through; or

has endangered the health of POTW personnel or the general public;
or

- d. Any other discharge violation of a Pretreatment Standard or requirement including Daily Maximum, long-term average, Instantaneous Limit or narrative standard that the City believes has caused, alone or in combination with other discharges, Interference or Pass Through, including endangering the health of POTW personnel or the general public;
 - e. Any discharge of pollutants that has caused imminent endangerment to the public or to the environment, or has resulted in the City's exercise of its emergency authority to halt or prevent such a discharge;
 - f. Failure to meet, within ninety (90) days of the scheduled date, a compliance schedule milestone contained in a wastewater discharge permit or enforcement order for starting construction, completing construction, or attaining final compliance;
 - g. Failure to provide within thirty (30) days after the due date, any required reports, including baseline monitoring reports, Industrial Discharge Permit applications, reports on compliance with Categorical Pretreatment Standard deadlines, periodic self-monitoring reports, and reports on compliance with compliance schedules;
 - h. Failure to accurately report noncompliance; or
 - i. Any other violation(s) which may include a violation of Best Management Practices that the City determines will adversely affect the operation or implementation of the local pretreatment program.
63. "Slug" shall mean any discharge of water, Sewage, or industrial waste which in concentration of any given constituent or in quantity of flow exceeds for any period of duration longer than 15 minutes more than 5 times the average 24 hour concentration or flows during normal operation.
64. "Slug Discharge" shall mean any discharge at a flow rate or concentration, which could cause a violation of the Prohibited Discharge Standards in this Ordinance. A Slug Discharge is any discharge of a non-routine, episodic nature, including but not limited to an accidental spill or a non-customary batch discharge, which has a reasonable potential to cause Interference or Pass Through or in any other way violate the WWTF's regulations, Local Limits or NPDES permit conditions.
65. "Source Reduction" shall mean any practice that:
- a. Reduces the amount of any hazardous substance, pollutant, or contaminant entering any waste stream or otherwise released into the environment (including fugitive emissions) prior to recycling, treatment, or disposal; and
 - b. Reduces the hazards to public health and the environment associated with the release of such substances, pollutants, or contaminants.

The term includes equipment or technology modifications; process or procedure modifications; reformulation or redesign of products; substitution of raw materials; and improvements in housekeeping, maintenance, training, or inventory control. The term "Source Reduction" does not include any practice that alters the physical, chemical, or biological characteristics or the volume of a hazardous substance, pollutant, or contaminant through a process or activity that itself is not integral to and necessary for the production of a product or the providing of a service.

- 66. “*State*” shall mean the State of New Hampshire.
- 67. “*Storm Drain*” or “*Storm Sewer*” shall mean a drain or sewer for conveying Stormwater, groundwater, subsurface water, or Unpolluted water from any source.
- 68. “*Stormwater*” shall mean any flow occurring during or following any form of natural precipitation, and resulting from such precipitation, including snow melt.
- 69. “*Total Suspended Solids*” or “*TSS*” shall mean a measure of the suspended matter present in wastewater, effluent, or water bodies, as determined by an approved test method. Also called Nonfilterable Residue.
- 70. “*Unpolluted*” shall mean water of quality equal to or better than the water quality standards established by NHDES or water that would not cause a violation of receiving water quality standards and would not be benefitted by discharge to the WWTF.
- 71. “*Wastewater*” shall mean liquid and water-carried Industrial Wastes and/or Sewage from residential dwellings, commercial buildings, industrial and manufacturing facilities, and institutions, whether treated or untreated, which are contributed to the POTW.
- 72. “*Wastewater Treatment Facility*” or “*WWTF*” shall mean that portion of the POTW which is designed to provide treatment of municipal Sewage and industrial waste. WWTF is synonymous with “treatment works,” as defined by section 212 of the Clean Water Act (33 U.S.C. § 1292). This definition includes any devices or systems used in the treatment, recycling, and reclamation of Sewage or Industrial Wastes of a liquid nature. The term also shall mean the municipality that has jurisdiction over discharges to and from a WWTF, and any sewer that conveys wastewater to a WWTF from any person outside the City who are, by contract or agreement with the City, users of the POTW.
- 73. “*Watercourse*” shall mean a natural or artificial channel for the passage of water either continuously or intermittently.

Section 16.305 – 16.310: RESERVED

DIVISION 2—GENERAL SEWER USE REQUIREMENTS

Section 16.311: USE OF PUBLIC SEWERS REQUIRED

- A. Unlawful deposit of waste. No person shall place, deposit, or permit to be deposited in any unsanitary manner on public or private property within the City, or in any area under the jurisdiction of the City, any Sewage, pollutant or other objectionable waste.
- B. Unlawful discharge of wastewater. No person shall discharge to any Natural Outlet within the City or in any area under the jurisdiction of the City, any Sewage or other pollutant, except where suitable treatment has been provided in accordance with subsequent provisions of this Ordinance and with State and Federal laws and regulations.
- C. Sewers for Intended Uses Only. No person shall discharge or cause to be discharged directly or indirectly into the POTW any Sewage, pollutant or other waste, or substance other than that for which the particular sewer is intended, designed, and provided.
- D. Applicable Permits Required. No person shall discharge into the POTW, or into any fixture that thereafter discharges into the POTW until all applicable approvals and permits have been obtained.
- E. All Industrial Users discharging wastewater into public or private sewers connected to the POTW shall comply with applicable Pretreatment Standards and State standards for pretreatment of wastes as they may be amended from time-to-time in addition to any applicable Local Limits as the required by this Ordinance.
- F. Use of Sanitary Sewers. Except as specifically designated by the City with reference to some particular sewer, Sanitary Sewers shall be used only for the conveyance and disposal of sanitary Sewage, and for Industrial Wastes that are permitted under this Ordinance. No Sanitary Sewer shall be used to receive and convey or dispose of any storm or surface water, subsoil drainage, or Unpolluted water subject to the following exception: in areas that still have Combined Sewer-Storm Drain infrastructure, existing connections may remain until such time as a public Storm Drain becomes reasonably available.
- G. Use of Storm Sewers. Stormwater and all other Unpolluted drainage are regulated under Chapter 16, Article II.
- H. Use Designation. If the intended or designated use of any particular sewer or drain and allowable discharge thereto is unclear, the City will consider the pertinent facts and make a determination. This determination shall be final and binding.
- I. Unlawful construction. Except as otherwise provided, it shall be unlawful to construct or maintain any privy, privy vault, septic tank, cesspool, or other facility intended or used for the disposal of wastewater in any area where a public sewer is available,. The use of

portable chemical toilets is allowed at construction sites and for other temporary purposes provided the wastes are properly disposed of off site.

- A. Requirement for connection. The owner(s) of all houses, buildings, or properties used for human occupancy, employment, recreation, or other purposes, situated within the City and abutting on any street, alley, or right-of-way in which there is now located or may in the future be located a public Sanitary Sewer of the City, is required at the owners' expense to install suitable toilet facilities therein, and to connect such facilities directly with the proper public sewer in accordance with the provisions of this ordinance, within ninety (90) days subsequent to the date of official notice to do so, provided that the public sewer is gravity (not low-pressure) and located within one hundred and fifty (150) feet of the building. The City may extend the period to connect from ninety (90) days to no more than one hundred and fifty (150) days for winter conditions or other good cause.
- J. Private wastewater disposal facilities. Where a public Sanitary Sewer is not available under the provisions of paragraph (i) above, the Building Sewer shall be connected to a private wastewater disposal system complying with the provisions of State law. The owner(s) shall operate and maintain the private wastewater disposal facilities in a sanitary manner at all times, at no expense to the City. At no time shall any quantity of industrial waste be discharged to a private, Domestic Wastewater disposal facility.
- K. Discontinuance of use. At such time as a public sewer becomes available to a property serviced by a private wastewater disposal system, the owner shall connect to the public sewer, as provided above. Any septic tanks, cesspools, and similar private wastewater disposal facilities shall be cleaned of sludge and filled with clean mineral soils, and their use shall be discontinued.
- L. Additional requirements. No statement contained in the preceding paragraphs of this section shall be construed to interfere with any additional lawful requirements that may be imposed by the City.

Section 16.312: PRIVATE SEWAGE DISPOSAL

- B. Where a public sanitary or Combined Sewer is not available under the provisions of Section 16.311(I) above, the Building Sewer shall be connected to a private Sewage disposal system complying with the provisions of this Ordinance.
- C. Before commencement of construction of a private sewage disposal system the owner shall first obtain a written permit signed by the Plumbing Inspector.
- D. A permit for a private sewage disposal system shall not become effective until the installation is completed to the satisfaction of the Plumbing Inspector.
- E. The type, capacities, location and layout of a private sewage disposal system shall comply with all regulations of the N.H. Department of Environmental Services. No permit shall

be issued for any private sewage disposal system employing subsurface facilities where the percolation test results indicate poor drainage conditions exist. No septic tank or cesspool shall be permitted to discharge to any Natural Outlet.

- F. At such time as a public sewer becomes available to a property served by a private sewage disposal system, subject to the waiver provision below, a direct connection shall be made to the public sewer in compliance with this Ordinance and any septic tanks, cesspools, and similar private sewage disposal facilities shall be abandoned and filled with suitable material. The City may extend the period to connect from ninety (90) days to no more than one hundred and fifty (150) days for winter conditions or other good cause.
 - i. Waiver. Owners of private sewage disposal systems may apply for and receive a waiver of the connection requirement provided that the private sewage disposal system is adequately functioning to serve the current property uses and legally permitted under State law. The waiver shall be withdrawn, and connection required, when the private sewage disposal system is no longer adequately functioning or is not legally permitted by State law.
 - ii. A public sewer becomes available for purposes of this ordinance when any house, building or property is used for human occupancy and is located within 150 feet of the property line abutting the street, alley or right of way in which the sewer main is laid.
- G. The owner shall operate and maintain the private sewage disposal facilities in a sanitary manner at all times, at no expense to the City.
- H. No requirement contained in this Ordinance shall be construed to interfere or conflict with any additional requirements that may be imposed by the Plumbing Inspector.

Section 16.313: BUILDING SEWERS AND CONNECTIONS

- A. No person(s) shall uncover, make any connections with or opening into, alter, or disturb any public sewer or equipment, structure or appurtenance of the POTW without first obtaining authorization from the Department of Public Works. Permits to work within the NHDOT and/or City Right-of-Way (ROW) shall be obtained in addition to DIGSAFE notification.
- B. There shall be two classes of Building Sewer permits: one for residential and commercial service producing only Domestic Wastewater; and one for service to establishments producing Industrial Wastes.
 - (1) Procedure. Applications for new residential and commercial service shall be made by the Owner or a duly authorized agent. Each application shall be fully completed, accompanied by an application fee, and include any plans, specifications, or other information considered pertinent in the judgement of the City. For an establishment

discharging Industrial Wastes, an application shall be made in accordance with the requirements of this Ordinance.

- (2) Determination. If the City determines that it does not or will not have sufficient capacity to serve it shall not be obligated to provide this service. The City may at its option and discretion enter into such agreements with applicant to make readiness to serve improvements at owner's expense. If the City determines that it has sufficient capacity to provide adequate service the City will approve the service and assess a connection fee. The connection fee will consist of the following components: labor and material charges related to the work components of connecting to the main pipe as well as a capacity use surcharge. Service shall not be provided until all required department deposits or payments have been made by the applicant.
- C. At the discretion of the Director, the City may construct that section of the service connection located within the public right-of-way extending from the main sewers to the connector's property line (edge of the right-of-way). In such case the owner (connector) shall be assessed a connection fee to reimburse the City for its costs in constructing the service connection. Construction of the remaining section of the Building Sewer including connection of the structure served shall be the responsibility of the owner. All costs and expenses incident to the installation and connection of the Building Sewer shall be borne by the owner. The owner shall indemnify the City from any loss or damage that may directly or indirectly be occasioned by the installation of the Building Sewer. The owner shall be obligated to pay all costs and expenses of operation, repairs, and maintenance and of reconstruction (if needed) of the Building Sewer including the connection to the public sewer.
- D. After the initial construction of the Building Sewer, the owner shall thereafter be obligated to pay all costs, expenses of operation, repair, and maintenance and of reconstruction (if needed) of the entire Building Sewer beginning at the public sewer and ending at the building. If City personnel are called out to work on the public sewer and it is subsequently determined that the problem was on the property owner's section of the line, the property owner shall reimburse the City for all costs associated with the service call.
- E. If the owner of any building located within the City and benefited, improved, served or accommodated by any public sewer, or to which any public sewer is available, after ninety (90) days' notice from the City shall fail to connect such building as required, the owner shall be in violation of this Ordinance and the City may make such connection and may collect from such owner the costs and expenses thereof by such legal proceeding as may be permitted by law. The City shall have full authority to enter on owner's property to do whatever is necessary to properly drain the improved property into the public sewer.
- F. A separate and independent Building Sewer shall be provided for every building with the following exception. If one building stands at the rear of another on an interior lot and no private sewer is available or can be constructed to the rear building through an adjoining alley, court, yard, or driveway, the Building Sewer from the front building may be

extended to the rear building and the whole considered as one application and approved by the City.

- G. Old Building Sewers may be used in connection with new buildings only when they are found, on examination and testing conducted at Owner's expense, to meet all requirements of this Ordinance and their use approved by the City.
- H. The size, slope, alignment, materials of construction of a Building Sewer, and the methods to be used in excavating, placing of the pipe, jointing, testing, and back filling the trench, shall conform to the requirements of the building and plumbing code or other applicable rules and regulations of the City and State. The entire line when completed shall be gas tight and watertight.
- I. Whenever possible, the Building Sewer shall be brought to the building at an elevation below the basement floor. In all buildings in which any Building Drain is too low to permit gravity flow to the public sewer, sanitary Sewage carried by such Building Drain shall be lifted by a means approved by the City and discharged to the Building Sewer at the owner's expense.
- J. No person shall connect roof downspouts, exterior foundations drains, areaway drains, or other sources of surface run-off or ground water to a Building Sewer or Building Drain, which in turn is connected directly or indirectly to a public Sanitary Sewer. Any deviation or exception to this paragraph will require written approval from the City.
- K. The method of connection to the Building Sewer into the public sewer shall be acceptable to the City and shall conform to the requirements of the building and plumbing code or other applicable rules and regulations of the City or the procedure set forth in appropriate specifications of the A.S.T.M. and the W.E.F. Manual Practice No. FD-5. All such connections shall be made gas tight and watertight. Any deviation from the prescribed procedure and materials shall be approved by the City before installation.
- L. The applicant for the Building Sewer permit shall notify the City when the Building Sewer is ready for inspection and connection to the public sewer. Such notice shall be provided not less than seventy-two (72) hours in advance of the time any connection is to be made to any public sewer. The contractor shall be responsible for satisfying all other notification requirements, including DIGSAFE. The connection and testing shall be made under the supervision of the City. No Building Sewer or repair shall be covered until it has been inspected and approved by the City. If any part of a Building Sewer is covered before being inspected and approved, it shall be uncovered for inspection at the cost and expense of the owner of the building to be connected to a sewer. This requirement shall also apply to repairs or alterations to building connections, drains or pipes thereto. Premature filling of trenches before an inspection is made will subject the owner(s) to opening the trench for inspection or a penalty in accordance with this Ordinance.

Failure of inspection may result in actions through code enforcement up to and including withholding a Certificate of Occupancy or discontinuing of services.

- M. All excavations for Building Sewer installation shall be adequately guarded with barricades and lights so as to protect the public from hazard. Streets, sidewalks, parkways and other public property disturbed in the course of the work shall be restored in a manner satisfactory to the City. Prior to any excavating on any public property, a excavation permit shall be obtained from the Department of Public Works.

Section 16.314: PROHIBITED DISCHARGE STANDARDS

- A. General Prohibitions. No person shall introduce or cause to be introduced into the POTW any pollutant or wastewater that causes Pass Through or Interference. These general prohibitions apply to all users of the POTW whether or not they are subject to Categorical Pretreatment Standards or any other Federal, State, or local Pretreatment Standards, requirements or limits.
- B. Specific Prohibitions. No person shall introduce or cause to be introduced into the POTW the following pollutants, substances, or wastewater:
1. Pollutants which create a fire or explosion hazard, including, but not limited to, waste streams with a closed-cup flashpoint of less than 140°F (60°C) using the test methods specified in 40 CFR 261.21 Any gasoline, benzene, naphtha, fuel oil or other flammable or explosive liquid, gas, solid, or any substance that can generate or form any flammable combustible or explosive substance, fluid, gas, vapor or liquid when combined with air, water or other substances present in sewers.;
 2. Wastewater having a pH less than 5.5 or greater than 9.5, as measured at the point of connection to the Sanitary Sewer or other available monitoring location, or otherwise causing corrosive structural damage or hazard to the POTW equipment, or personnel, or with alkalinity in such quantities that contribute to or cause the WWTF influent pH to exceed 8.0;
 3. Solid or viscous substances including water or wastes containing fats, wax, Grease, or oils, whether emulsified or not, or containing substances that can solidify or become viscous at temperatures between 32°F and 150°F (0-65°C), in amounts that could cause obstruction of the flow in the WWTF resulting in Interference;
 4. Pollutants, including oxygen-demanding pollutants (*e.g.*, BOD, COD), or chlorine demand requirements released in a discharge at a flow rate and/or pollutant concentration that, either singly or by interaction with other pollutants, will cause Interference with the WWTF, constitute a hazard to humans or animals, create a public nuisance, exceed national Categorical Pretreatment Standards, or cause Pass Through;
 5. Wastewater containing such concentrations or quantities of pollutants that its introduction to the WWTF could cause a treatment process upset and subsequent loss of treatment ability or efficiency;

6. Wastewater having a temperature greater than 150°F (65°C), or that will inhibit biological activity in the WWTF resulting in Interference, but in no case wastewater that causes the temperature at the introduction into the wastewater treatment facility to exceed 104°F (40°C), unless upon approved by the POTW;
 7. Oils and Grease of Animal and Vegetable Origin, Petroleum oil, non-biodegradable cutting oil, or products of mineral oil origin, in excess of 100 mg/L, or in amounts that will cause Interference or Pass Through;
 8. Pollutants that result in the presence of toxic gases, vapors, or fumes within the POTW in a quantity that may cause acute worker health and safety problems;
 9. Trucked or hauled pollutants, except at discharge points designated by the City in accordance with this Ordinance;
 10. Any Medical/Infectious Waste, Pharmaceutical Waste, or Radiological Waste except as specifically authorized in an IDP;
 11. Household hazardous wastes including but not limited to paints, stains, thinners, pesticides, herbicides, anti-freeze, transmission and brake fluids, motor oil and battery acid;
 12. Wastewater causing, alone or in conjunction with other sources, the wastewater treatment facility's effluent or biosolids to fail a toxicity test; and
 13. Any hazardous waste listed or designated by the NHDES under Env-Hw 400.
 14. Prohibited wastes described in N.H. Admin. Code § Env-Wq 305.04(c)(3): Wastes introduced into the POTW by any person shall not:
 - a. Interfere with the safety, operation, maintenance, or performance of the POTW;
 - b. Have an adverse effect on the receiving stream;
 - c. Prevent disposal of sludge in the manner used by the POTW; or
 - d. Otherwise endanger life, limb, public property, or constitute a nuisance;
- C. Additional Prohibitions. No Connector shall introduce or cause to be introduced into the POTW the following substances, pollutants or wastewater, unless specifically authorized in an IDP:
15. Noxious or malodorous liquids, gases, solids, or other wastewater that, either singly or by interaction with other wastes, could be sufficient to create a public nuisance, objectionable odors, or a hazard to life, or to prevent entry into the public sewers for maintenance or repair;

16. Wastewater containing any radioactive wastes or isotopes except as specifically authorized in an IDP and in compliance with applicable State or Federal regulations;
17. Stormwater, surface water, groundwater, artesian well water, roof runoff, subsurface drainage, swimming pool drainage, condensate, deionized water, Noncontact Cooling Water, or otherwise Unpolluted wastewater;
18. Sludges, screenings, or other residues from the pretreatment of Industrial Wastes;
19. Detergents, surface-active agents, or other substances that might cause excessive foaming in the WWTF;
20. Wastewater that could cause a reading on an explosion hazard meter at the point of discharge into the POTW, or at any point in the POTW, of more than ten percent (10%) of the Lower Explosive Limit;
21. Garbage that has not been shredded to such a degree that all particles will be transported freely under the flow conditions normally prevailing in public sewers. (Garbage grinders may be connected to Sanitary Sewers from homes, hotels, institutions, restaurants, hospitals, catering establishments, or similar places where garbage originates from the preparation of food in kitchens for the purpose of consumption on the premises or when served by caterers;
22. Any quantities of flow, concentrations, or both which constitute a "Slug" as defined herein;
23. Waters or wastes which, by interaction with other water or wastes in the treatment works, release dangerous or noxious gases or objectionable odors, form suspended solids that affect the operation of the collection system, or create a condition deleterious to structures and treatment processes;
24. Any materials that exert or cause unusual concentrations of inert suspended solids (such as, but not limited to, Fullers earth, lime, slurries, and lime residues) or of dissolved solids (such as, but not limited to, sodium chloride and sodium sulfate); and
25. Wastewater containing any pollutant at a concentration that exceeds a local limit or IDP limit established for that pollutant by the City.

D. Pollutants, substances, or wastewater prohibited by this Ordinance shall not be processed or stored in such a manner that they could be discharged to the POTW.

Section 16.315: FEDERAL CATEGORICAL PRETREATMENT STANDARDS

The Federal Categorical Pretreatment Standards are found at 40 CFR Chapter I, Subchapter N,

Parts 405-471 and are hereby incorporated into the Ordinance.

- A. Where a Categorical Pretreatment Standard is expressed only in terms of either the mass or the concentration of a pollutant in wastewater, the City may impose equivalent concentration or mass limitations in accordance with 40 CFR 403.6(c).
- B. When wastewater subject to a Categorical Pretreatment Standard is mixed with wastewater not regulated by the same standard, the City shall impose an alternate limit using the combined waste stream formula in 40 CFR 403.6(e).
- C. A User may obtain a variance from a Categorical Pretreatment Standard if the User can prove, pursuant to the procedural and substantive provisions in 40 CFR 403.13, that factors relating to its discharge are fundamentally different from the factors considered by EPA when developing the Categorical Pretreatment Standard.
- D. A User may obtain a net gross adjustment to a Categorical standard in accordance with 40 CFR 403.15.

Upon promulgation of the Federal Categorical Pretreatment Standards for a particular industrial subcategory, the Federal standard, if more stringent than limitations imposed under this Ordinance for sources in that subcategory, shall, on the compliance date of the Categorical Pretreatment Standards, immediately supersede the limitations imposed under this Ordinance.

Compliance with Categorical Pretreatment Standards shall be achieved within three (3) years of the date such standards are effective, unless a shorter compliance schedule is specified in the standards.

An Industrial User subject to Categorical Pretreatment Standards shall not discharge wastewater directly or indirectly to the POTW subsequent to the compliance date of such standards unless an amendment to its Industrial Discharge Permit has been issued by the City.

Section 16.316: LOCAL DISCHARGE RESTRICTIONS

The Director is authorized to establish Local Limits by this Ordinance and pursuant to 40 CFR 403.5. In the event of a conflict between any State Pretreatment Standards, Federal Categorical Pretreatment Standards or Local Limits, the most stringent shall apply.

The Director is further authorized to develop Best Management Practices by policy, practice or as a condition of any IDP.

- A. **LOCAL LIMITS:** Numerical pollutant discharge limitations are established to protect against pass-through and Interference. No person shall discharge wastewater containing constituents at daily concentrations greater than indicated in:

Appendix I – Maximum Allowable Industrial Mass Loading Limitations / Local Limits

For industrial discharge applications, the local limits in Appendix I shall apply at the end of the process train prior to dilution with non-industrial wastewaters.

Daily concentrations are the concentration of a pollutant discharged, determined from the analysis of a flow-composited sample (or other sampling procedure approved by the City) representative of the discharge over the duration of a 24-hour day or industrial operating schedule of less than twenty-four (24) hours.

All concentration limits for metals represent "total" metal unless indicated otherwise. The Director may impose mass limitations in accordance with section 16.319 in place of the concentration-based limitations above.

Unless specifically identified in an Industrial Discharge Permit, an Industrial User shall not discharge the locally limited pollutants at concentrations twenty (20) percent greater than the background concentrations used for local limits development.

Pollution Prevention activities that result in a decreased discharge of these pollutants to the WWTF, such that the headworks loading of a pollutant is less than forty (40) percent of the allowable loading, may result, at the discretion of the City, in rescission of a local limit for that pollutant from this Ordinance.

- B. SPECIAL AGREEMENTS: The City reserves the right to enter any special or temporary agreement or arrangement between the City and any Industrial User whereby an industrial waste of unusual strength or character or a discharge of short term duration may be accepted by the City for treatment provided that the agreement does not contravene any requirements of existing Federal or State laws, and/or regulations promulgated hereunder and do not waive applicable Federal Categorical Pretreatment Standards.

Section 16.317: CITY'S RIGHT OF REVISION

The City reserves the right to establish, by ordinance or in an individual IDP, more stringent standards or requirements than those currently established in this ordinance if more stringent standards or requirements are reasonably required to fulfil the purposes of this Ordinance.

Section 16.318: DILUTION

No Industrial User shall ever increase the use of water, or in any way attempt to dilute a discharge, as a partial or complete substitute for adequate treatment to achieve compliance with a discharge limitation unless expressly authorized by an applicable Pretreatment Standard or requirement. The City may impose mass limitations on users to discourage the use of dilution to meet applicable Pretreatment Standards or requirements, or in other cases when the imposition of mass limitations is appropriate.

Section 16.319: MASS-BASED LIMITATIONS

Users implementing process changes may request that compliance be determined based on mass limitations in lieu of concentration limitations. Such mass-based limitations will be calculated from the permitted concentration-based limitations and flows and shall be equivalent to or less than the mass discharge in effect at the time of the request. The intent of a mass-based limit is to encourage and allow Pollution Prevention and/or water conservation measures that might cause a facility to increase pollutant concentrations in their discharge even though the total mass of the pollutant discharged does not increase and may in fact decrease. Decisions on granting requests for mass-based compliance limitations will be based on user-specific information and current operating conditions of the WWTF and will be at the discretion of the City. Implementation of mass-based limitations may not contravene any requirements of Federal or State laws and/or regulations implemented hereunder. For Categorical Pretreatment Standards that are expressed only in terms of pollutant concentrations, the City may establish equivalent mass limits only if the User meets all the conditions in 40 CFR 403.6 (c) (5).

Section 16.320: RESERVED

DIVISION 3—PRETREATMENT OF WASTEWATER

Section 16.321: PRETREATMENT FACILITIES

Industrial Users shall provide wastewater treatment as necessary to comply with this Ordinance and shall achieve compliance with all Categorical Pretreatment Standards, Local Limits, and the prohibitions set out in Sections 16.314, 16.315, and 16.316 of this Ordinance within the time limitations specified by EPA, the State, or the City, whichever is more stringent. All facilities required to achieve and maintain compliance shall be provided, operated, and maintained at the User's expense. Detailed plans describing such facilities and operating procedures shall be submitted to the City for review and shall be acceptable to the City and the NHDES Water Division before such facilities are constructed. Such facilities shall not be connected until approval is obtained in writing. The review of such plans and operating procedures shall in no way relieve the User of the responsibility of modifying such facilities as necessary to produce a discharge acceptable to the City under the provisions of this Ordinance. Plans and specifications for a proposed pretreatment facility shall be the result of the design of a professional engineer licensed by the State of New Hampshire.

Section 16.322: ADDITIONAL PRETREATMENT MEASURES

- A. Whenever deemed necessary, the City may require users to restrict their discharge during peak flow periods, designate that certain wastewater be discharged only into specific sewers, relocate and/or consolidate points of discharge, separate sanitary Sewage waste streams from industrial waste streams, provide for Source Reduction, and impose such other conditions as are deemed necessary to protect the POTW and determine the User's compliance with the requirements of this Ordinance.

- B. The City may require any Connector to install and maintain, on their property and at their expense, a suitable storage and flow-control facility to ensure equalization of flow. An IDP may be issued solely for flow equalization.
- C. Grease, oil, and/or sand interceptors shall be provided at the owner's expense when, in the opinion of the City, such devices are necessary for the preliminary treatment of wastewater containing excessive amounts of Grease, oil, and/or sand; except that such interceptors shall not be required for solely residential users. All interception units shall be of a type and capacity approved by the City and shall be so located as to be easily accessible for cleaning and inspection. Maintenance of interceptors requires that the owner be responsible for the proper removal and disposal by appropriate means of the captured materials, in accordance with the requirements established by the City. The owner shall maintain records of the servicing of Grease, oil, and/or sand interceptors. The form and content of such records will be determined by the City and the records shall be subject to periodic review. The removal and disposal of captured materials from interceptors shall be performed by a Septage or sludge Hauler holding a current permit issued by the State of New Hampshire, or by a Hazardous Waste Transporter currently registered with the State of New Hampshire, whichever is applicable. Grease Interceptors / Grease Traps servicing food service establishments shall be installed, maintained, and permitted in accordance with Section 16.325.
- D. Users with the potential to discharge flammable substances shall, at the discretion of the Director, install and maintain an approved combustible gas detection meter and alarm.
- E. Where pretreatment or flow equalizing facilities are provided or required for any waters or wastes, these devices shall be maintained continuously in satisfactory and effective operation at owner's expense.
- F. The owner of any building serviced by a Building Sewer carrying Industrial Wastes may, at the discretion of the City, be required to install a suitable control manhole or approved equivalent structure together with such necessary meters and other appurtenances in the Building Sewer to facilitate observation, sampling and measurement of the wastes. Such manhole shall be accessible and safely located and shall be constructed in accordance with plans approved by the City. The manhole shall be installed and maintained by the owner at owner's expense so as to be safe and accessible at all times. The owner shall perform such monitoring as the City may reasonably require including installation, use and maintenance of monitoring equipment, maintaining records and reporting the results of such monitoring to the City. Such records shall be made available upon request of the City and shall be available to other agencies having jurisdiction over discharges to the receiving waters.
- G. Dental practices that remove or place mercury containing amalgam shall comply with Federal and State regulations.

Section 16.323: ACCIDENTAL DISCHARGE/SLUG CONTROL PLANS

Each Industrial User shall provide protection from accidental discharge of prohibited materials or

their wastes regulated by this Ordinance.

The City shall upon issuance or renewal of any IDP, and at such other times as may be reasonably required, evaluate whether an SIU needs an accidental discharge/Slug control plan or other action to control Slug Discharges.

The City may require any Industrial User to develop, submit for approval, and implement such a plan. Alternatively, the City may develop such a plan for any Industrial User. An accidental discharge/Slug control plan shall address, at a minimum, the following:

- A. A description of discharge practices, including non-routine batch discharges;
- B. A description of all stored chemicals;
- C. Procedures for immediately notifying the City of any accidental or Slug Discharge, as required by Section 16.356 of this Ordinance;
- D. Procedures to prevent adverse impact from any accidental or Slug Discharge. Such procedures include, but are not limited to, inspection and maintenance of storage areas, handling and transfer of materials, loading and unloading operations, control of plant site runoff, worker training, building of containment structures or equipment, measures for containing pollutants, including solvents, and/or measures and equipment for emergency response.

All expenses and costs for the development and implementation of any plan shall be the responsibility of the Industrial User. Review and approval of such plans and operating procedures shall not relieve the Industrial User any other responsibility or condition of its IDP or from any requirement to modify its facility to meet the requirements of this Article.

Section 16.324: POLLUTION PREVENTION PLANS

The City may require any Industrial User discharging wastes into the POTW to develop and implement, at their own expense, a Pollution Prevention plan. The City may require such Users to submit as part of the Pollution Prevention plan information that demonstrates adherence to the following elements:

- A. Management Support. For changes to be effective, the visible support of top management is required. Management's support should be explicitly stated and include designation of a Pollution Prevention coordinator, goals, and time frames for reductions in volume and toxicity of waste streams, and procedures for employee training and involvement.
- B. Process Characterization. A detailed process waste diagram shall be developed that identifies and characterizes the input of raw materials, the outflow of products, and the generation of wastes.

- C. Waste Assessment. Estimates shall be developed for the amount of wastes generated by each process. This may include establishing and maintaining waste accounting systems to track sources, the rates and dates of generation, and the presence of hazardous constituents.
- D. Analysis of Waste Management Economics. Waste management economic returns shall be determined based on the consideration of:
- a. Reduced raw material purchases;
 - b. Avoidance of waste treatment, monitoring and disposal costs;
 - c. Reductions in operations and maintenance expenses;
 - d. Elimination of permitting fees and compliance costs; and
 - e. Reduced liabilities for employee/public exposure to hazardous chemicals and cleanup of waste disposal sites.
- E. Development of Pollution Prevention Alternatives. Current and past Pollution Prevention activities shall be assessed, including estimates of the reduction in the amount and toxicity of waste achieved by the identified actions. Opportunities for Pollution Prevention shall then be assessed for identified processes where raw materials become or generate wastes. Technical information on Pollution Prevention shall be solicited and exchanged, both from inside the organization and out.
- F. Evaluation and Implementation. Technically and economically feasible Pollution Prevention opportunities shall be identified and an implementation timetable with interim and final milestones shall be developed. The recommendations that are implemented shall be periodically reviewed for effectiveness.

All expenses and costs for the development and implementation of any plan shall be the responsibility of the Industrial User. Review and approval of such plans and operating procedures shall not relieve the Industrial User of any other responsibility or condition of its IDP or from any requirement to modify its facility to meet the requirements of this Ordinance.

Section 16.325: FATS, OILS, AND GREASE (FOG) PROGRAM

Grease removal systems are required for all connections to the POTW from Food Service Establishment (FSE) operations including, but not limited to, restaurants, cafeterias, nursing homes, schools, hospitals, or other connections which discharge or have the potential to discharge quantities of Grease to the POTW.

No FSE conducting food preparation or food processing operations shall discharge wastewater into the POTW without first obtaining a FOG program permit.

- A. Any FSE required to have a Grease removal system shall install:

- a. An outdoor passive in-ground Grease Interceptor, minimum 1000 gallons, where available exterior space exists, or;
 - b. An indoor passive Grease Trap sized appropriately for the Food Service if:
 - i. It can be demonstrated that no exterior space exists, and/or
 - ii. The City determines the Food Service provided is too limited to warrant the protection of an exterior 1000 gallon interceptor.
- B. No wastewater, other than from kitchen fixtures or food processing equipment, shall discharge into the Grease removal system. Wastewater from sanitary sources such as toilets and bathroom sinks is prohibited from being discharged to the Grease removal system.
- C. Grease interceptors and Grease traps shall be cleaned by a professional cleaning service at a minimum:
 - a. Exterior belowground Grease Interceptors; Quarterly (every three months), unless the Department has specified in writing an irregular cleaning schedule for an establishment;
 - b. Interior Grease Traps; monthly, unless the Department has specified in writing an irregular cleaning schedule for an establishment,
- D. Records of the dates of cleaning and means of disposal shall be maintained for a period of five years.
- E. All wastewater from food preparation operations and/or washing and clean-up operations, including, but not limited to, pot sinks, pre-rinse stations, work stations, soup kettles, braising pans, mop sinks and wastewater generated from exhaust fan hood cleaning operations shall discharge to the Grease removal system. All automatic dishwasher wastewater, excluding pre-rinse stations, shall bypass the Grease removal device and be discharged directly into the sewer system.

Section 16.326-16.330: RESERVED

DIVISION 4—INDUSTRIAL DISCHARGE PERMIT (IDP) APPLICATION

Section 16.331: INDUSTRIAL USER CLASSIFICATION SYSTEM

The City maintains an Industrial User classification system to allow the City to group users into categories that define the degree of regulatory attention required. The classification system establishes priorities for allocation of City resources, and promotes uniformity and fairness in the application of regulations affecting Industrial Users. A User may be designated at a higher

classification level if the City determines that the User has a reasonable potential for adversely affecting POTW operation, if the User has violated any Pretreatment Standard or requirement, or at the discretion of the City. Users are assigned to one of three classes.

- A. Class 1: Dischargers of large volumes of industrial wastewater (greater than 10,000 gpd), high loadings (greater than five percent [5%] of the average dry weather hydraulic or organic capacity of the WWTF), and/or chemical constituents warranting a high degree of control and monitoring. Included in this class are all users that are subject to Categorical Pretreatment Standards and users with pretreatment systems that employ automatic controls for sensing, pumping, dosing, and/or other treatment functions occurring without the manual intervention of an operator.
- B. Class 2: Discharge between 1,000 and 10,000 gpd of industrial wastewater. Also included are dischargers of greater than 100 gpd with a moderate level of pretreatment (i.e., requires an operator to manually operate equipment, add chemicals, etc.). Dischargers of up to 1,000 gpd of industrial wastewater and restaurants up to 5,000 gpd. Class 2 also includes dischargers with basic pretreatment procedures (e.g., batch pH adjustment, Grease, oil, and/or sand interceptors, silver recovery units) and whose industrial wastewater flows do not exceed 100 gpd.
- C. Class 3: Dischargers of industrial wastewater that are not otherwise classified and are not required to possess an IDP because:
 - a. Pollutants of concern are not detectible in the User's effluent;
 - b. Pollutants of concern are present in only trace amounts and are neither causing nor likely to cause pass-through or Interference;
 - c. Pollutants of concern are present in amounts too small to be effectively reduced by known treatment technologies; or
 - d. The User's waste stream contains only pollutants compatible with the WWTF.

Class 3 users (including Dental Facilities and others) may be required to implement Best Management Practices which may include: a schedule of activities, prohibitions of practices, maintenance procedures, and other management practices to prevent or reduce the discharge of pollutants to the POTW. BMPs include treatment requirements, operating procedures, and practices to control discharges to the POTW. BMPs also include alternative means (i.e., management plans) of complying with, or in place of certain established Categorical Pretreatment Standards and effluent limits.

- D. Class 4: Non discharging Federal categorical Users

The Federal Pretreatment Regulations allow, at the City's discretion, the classification of certain CIUs as nonsignificant and, thus, not subject to permitting. As defined in the Pretreatment Regulations at 40 CFR 403.3(v)(2), an NSCIU is a discharger that, among other things, never discharges more than 100 gpd of total categorical wastewater to the POTW and never discharges any untreated concentrated wastes. If an Industrial User is determined to be an NSCIU, the User is no longer an SIU and is therefore not required to be controlled through a permit or other control mechanism although the City may choose

to do so. Regardless of whether an Industrial User is determined to be an NSCIU, it is still a Categorical discharger and, as such, is still required to comply with applicable Categorical Pretreatment Standards and related reporting and notification requirements at 40 CFR 403.12(b), (c), (d), (f), (j), (l), and (p).

E. Class 5 – Potential PFAS discharger: This Class of IUs may be required to obtain an IDP.

Section 16.332: WASTEWATER CHARACTERIZATION

When requested by the City, any User shall submit information on the nature and characteristics of its wastewater discharge within sixty (60) days of the request. The City is authorized to prepare a form for this purpose and may periodically require users to update this information.

Section 16.333: IDP REQUIREMENT

No Industrial User shall discharge wastewater into the POTW without first obtaining an IDP with the following exceptions:

- A. A User who has filed a timely and complete application pursuant to Section 16.334 of this Ordinance may continue to discharge for the time period specified therein.
- B. A User who has received written notification from the City that they do not need an IDP, but shall promptly notify the City of any alteration in either flow or waste characteristics of the wastewater being discharged into the POTW.

Any violation of the terms and conditions of an IDP shall be deemed a violation of this Ordinance and subjects the User to the enforcement actions set forth in this Ordinance. Obtaining an IDP does not relieve a permittee of its obligation to comply with all Federal and State Pretreatment Standards or requirements or Local Limits, or with any other requirements of Federal, State, and local law.

Section 16.334: EXISTING CONNECTIONS

Any User required to obtain an IDP discharging wastewater into the POTW prior to the effective date of this Ordinance, and not currently covered by an IDP, and wishing to continue such discharges in the future, shall, within sixty (60) days after the effective date, apply for an IDP in accordance with this Ordinance, and shall not cause or allow discharges to the POTW to continue after one hundred twenty (120) days of the effective date of this Ordinance except in accordance with an IDP issued by the City.

Section 16.335: NEW CONNECTIONS

Any person required to obtain an Industrial Discharge Permit who proposes to begin or recommence discharging into the POTW shall obtain an IDP prior to the beginning or

recommencing of such discharge. An application for this IDP shall be filed at least ninety (90) days prior to the date upon which any discharge is proposed to begin or recommence.

Section 16.336: FEDERAL CATEGORICAL PRETREATMENT STANDARDS

Within one hundred twenty (120) days subsequent to the effective date of a Federal Categorical Pretreatment Standard, an Industrial User subject to such standards shall submit an application for an IDP amendment.

Section 16.337: IDP APPLICATION CONTENTS

- A. All users required to obtain an IDP, and other users subject to pretreatment requirements, as required by the City, shall submit a completed IDP application and application fee. The IDP application may, without limitation, require information regarding:
1. Each product produced by type, amount, process or processes, and rate of production, and amount of raw materials processed (average and maximum per day);
 2. Site plans, floor plans, mechanical and plumbing plans, and details to show all sewers, floor drains, and appurtenances by size, location, and elevation, and all points of discharge;
 3. Time, duration and rate of discharges; and
 4. Any other information reasonably required by the City.
- B. Incomplete or inaccurate applications will not be processed and will be returned to the User for revision.

Section 16.338: SIGNATORIES AND CERTIFICATION

All IDP applications and User reports shall be signed by an authorized representative of the User and contain the following certification statement:

“On behalf of the applicant (owner) named herein, I hereby apply for a permit to discharge non-Domestic Wastewater to the wastewater collection and treatment facilities owned by the City of Portsmouth, NH. I certify that I am familiar with Chapter 16, Article III, and the information contained in this application. I certify under the penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted herein is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations. I further understand that if the actual wastewater discharged differs in any significant matter from the information contained herein, any permit issued based upon this application is void and such discharge shall be in violation of the City of Portsmouth Ordinances”

If the designation of an Authorized Representative of the Connector is no longer accurate because a different individual or position has responsibility for the overall operation of the facility or overall responsibility for environmental matters for the company, a new written authorization satisfying the requirements of this Section shall be submitted to the City prior to or together with any reports to be signed by an Authorized Representative of the Connector.

Nothing in this section limits the City's authority to require certifications for any other reports, applications or documents that the City may require to implement this Ordinance.

Section 16.339 and 16.340: RESERVED

DIVISION 5—INDUSTRIAL DISCHARGE PERMIT (IDP) ISSUANCE PROCESS

Section 16.341: IDP DECISIONS

The City will evaluate the data provided by the Industrial User and may require additional information. Within thirty (30) days of receipt of a complete IDP application [or ninety (90) days in the case of an application for a new or increased discharge requiring review and approval by the NHDES Water Division], the City will determine whether or not to issue an IDP. The City may deny any application for an IDP or request such additional information as may be needed to complete the review of the application.

Section 16.342: IDP DURATION

An IDP shall be issued for a specified time period, not to exceed five (5) years from the effective date of the permit.

IDPs shall be terminated upon cessation of operations or transfer of business ownership, unless notification of such transfer is provided in accordance with Section 16.346 of this Ordinance. All IDPs issued to a particular User are void upon the issuance of a new IDP to that User.

Section 16.343: IDP CONTENT

An IDP shall include such conditions as are deemed reasonably necessary by the City to prevent Pass Through or Interference, protect the quality of the water body receiving the wastewater treatment facility's effluent, protect human health and safety, facilitate biosolids management and disposal, and protect against damage to the POTW.

A. IDPs shall contain:

1. Dates of IDP issuance and expiration, with a duration not to exceed five (5) years;
2. A statement that the IDP is nontransferable without prior notification to the City and provisions for providing the new owner or operator with a copy of the existing IDP;

3. Effluent limits including Best Management Practices and general and specific prohibitions based on the requirements of this Ordinance;
4. Identification of applicable Federal Categorical Pretreatment Standards;
5. Self-monitoring, sampling, inspection, reporting, notification, and record-keeping requirements. For pollutants to be monitored, these requirements shall include sampling locations, sampling frequencies, and sample types based on this Ordinance, and State and Federal laws, rules and regulations;
6. For users with reporting requirements, such reports at a minimum shall require:
 - a. Periodic monitoring results indicating the nature and concentration of pollutants in the discharge from the regulated processes governed by the IDP and the average and maximum daily flow for these process units;
 - b. A statement as to whether the applicable Pretreatment Standards and requirements are being met on a consistent basis and, if not, identification of additional operation and maintenance practices and/or pretreatment systems that are necessary;
 - c. Submittal of any monitoring results performed in addition to the requirements of the IDP using procedures prescribed in the permit; and
 - d. Appropriate supporting documentation.
7. A statement of applicable civil and criminal penalties for violation of Pretreatment Standards and requirements; and
8. Any applicable compliance schedule. This schedule may not extend the time for compliance beyond that required by this Ordinance, and applicable State and Federal laws, rules and regulations.

B. IDPs may contain, but need not be limited to, the following conditions:

1. Limitations on the average and/or maximum rate of discharge, time of discharge, and/or requirements for flow regulation and equalization;
2. Requirements for the installation of pretreatment technology, pollution control, or construction of appropriate containment devices, designed to reduce, eliminate, or prevent the introduction of pollutants into the POTW;
3. Requirements for the development and implementation of spill control plans or other special conditions including Best Management Practices necessary to adequately prevent accidental, unanticipated, or non-routine discharges;

4. Development and implementation of Pollution Prevention plans to reduce the amount of pollutants discharged to the POTW;
5. Requirements for installation and maintenance of inspection and sampling facilities and equipment;
6. A statement that compliance with the IDP does not relieve the permittee of responsibility for compliance with all applicable Federal and State Pretreatment Standards, including those that become effective during the term of the IDP;
7. Requirements to control Slug Discharges, if determined by the POTW to be necessary; and
8. Other conditions as deemed appropriate by the Director to ensure compliance with this Ordinance, and State and Federal laws, rules, and regulations.

Section 16.344: IDP APPEALS

Any person, including the User, may petition the Director to reconsider the terms of an IDP within thirty (30) days of notice of its issuance.

- A. Failure to submit a timely petition for review shall be deemed to be a waiver of the administrative appeal.
- B. In its petition, the appealing User shall indicate the IDP provisions objected to, the reasons for this objection, and the alternative condition, if any, it seeks to place in the IDP.
- C. The effectiveness of the IDP shall not be stayed pending the appeal.
- D. If the Director fails to act within thirty (30) days, the appeal shall be deemed to be denied.
- E. Aggrieved parties may appeal the conditions of the IDP in accordance with Section 16.416 of this Ordinance.

Section 16.345: IDP MODIFICATION

The City may modify an IDP for good cause, including, but not limited to, the following reasons:

- A. To incorporate any new or revised Federal, State, or Local Pretreatment Standards or requirements;
- B. To address significant alterations or additions to the User's operation, processes, or wastewater volume or character since the time of IDP issuance;
- C. To manage a change in the POTW that requires either a temporary or permanent reduction or elimination of the authorized discharge;

- D. To address a threat to the POTW, City personnel, the public or the water quality in the receiving waters;
- E. To remedy the violation of any terms or conditions of the IDP;
- F. To account for any misrepresentations or failure to fully disclose all relevant facts in the IDP application or in any required reporting;
- G. To incorporate the revision of or a grant of variance from Categorical Pretreatment Standards pursuant to 40 CFR 403.13;
- H. To correct typographical or other errors in the IDP; or
- I. To reflect a transfer of the facility ownership or operation to a new owner or operator.

Section 16.346: IDP TRANSFER

An IDP may be transferred only upon the approval of the City. Users shall provide at least sixty (60) days advance notice to the City of any proposed transfer. Notice to the City shall include written certification by the new owner or operator that:

- A. The new owner and/or operator has no immediate intent to change the facility's operations and processes that generate wastewater to be discharged to the POTW;
- B. Identifies the specific date on which the transfer is to occur; and
- C. Acknowledges full responsibility for complying with the existing IDP.

Failure to provide the required advance notice of a transfer or to obtain the approval of the City renders the IDP void as of the date of facility transfer.

Section 16.347: IDP REISSUANCE

A User with an expiring IDP shall apply for reissuance of the IDP by submitting a complete IDP application a minimum of sixty (60) days prior to the expiration of the User's existing IDP. An expired IDP will continue to be effective and enforceable until the IDP is reissued if:

- A. The Industrial User has submitted a complete IDP application at least sixty (60) days prior to the expiration date of the User's existing permit; and
- B. The failure to reissue the IDP, prior to expiration of the previous IDP, is not due to any act or failure to act on the part of the Industrial User.

Section 16.348-16.350: RESERVED

DIVISION 6—REPORTING REQUIREMENTS

Section 16.351: BASELINE MONITORING REPORTS

- A. Within either one hundred eighty (180) days subsequent to the effective date of a Categorical Pretreatment Standard, or the final administrative decision on a category determination under 40 CFR 403.6(a) (4), whichever is later, existing categorical users currently discharging to, or scheduled to discharge to the POTW, shall submit to the City a report that contains the information listed in paragraph (B), below. At least ninety (90) days prior to commencement of their discharge, New Sources, and sources that become categorical users subsequent to the promulgation of an applicable categorical standard, shall submit to the City a report that contains the information listed in paragraph (B), below. If necessary, a New Source shall report the method of pretreatment it intends to use to meet applicable categorical standards. A New Source also shall provide estimates of its anticipated flow and quantity of pollutants to be discharged.
- B. Users described above shall submit the information set forth below:
1. Identifying Information. The name and address of the facility, including the name of the operator and owner.
 2. Environmental Permits. A list of any environmental permits held by or for the facility.
 3. Description of Operations. A brief description of the nature, average rate of production, and standard industrial classifications of the operation(s) conducted by such User. This description should include a schematic process diagram that indicates points of discharge to the POTW from the regulated processes. Standard industrial classification shall mean a classification pursuant to the Standard Industrial Classification Manual issued by the United States Office of Management and Budget.
 4. Flow Measurement. Information showing the measured average daily and maximum daily flow, in gpd, to the POTW from regulated process streams and other streams, as necessary to allow use of the combined wastestream formula set out in 40 CFR 403.6(e).
 5. Measurement of Pollutants.
 - a. The Categorical Pretreatment Standards applicable to each regulated process.
 - b. The results of sampling and analysis identifying the nature and concentration, and/or mass, where required by the standard or by the

Director, of regulated pollutants in the discharge from each regulated process. Instantaneous, Daily Maximum, and long-term average concentrations, or mass, where required, shall be reported. The sample shall be representative of daily operations and shall be analyzed in accordance with procedures set out in Section 16.360 of this Ordinance. In cases where the Categorical Pretreatment Standard requires compliance with a Best Management Practice or Pollution Prevention alternative, the User shall submit documentation as required by the City or the applicable Categorical Pretreatment Standards to determine compliance with the Standard.

- c. The User shall take a minimum of one representative sample to compile that data necessary to comply with the requirements of this Section.
 - d. Samples should be taken immediately downstream from pretreatment facilities if such exist or immediately downstream from the regulated process if no pretreatment exists. If other wastewaters are mixed with the regulated wastewater prior to pretreatment the User should measure the flows and concentrations necessary to allow use of the combined waste stream formula in 40 CFR 403.6(e) to evaluate compliance with the Pretreatment Standards. Where an alternate concentration or mass limit has been calculated in accordance with 40 CFR 403.6(e) this adjusted limit along with supporting data shall be submitted to the City;
 - e. Sampling shall be performed in accordance with procedures set out in this Ordinance.
 - f. The City may allow the submission of a baseline report which utilizes only historical data so long as the data provides information sufficient to determine the need for industrial pretreatment measures;
 - g. The baseline report shall indicate the time, date and place of sampling and methods of analysis, and shall certify that such sampling and analysis is representative of normal work cycles and expected pollutant discharges to the POTW.
6. Certification. A statement, reviewed by the User's authorized representative and certified by a qualified professional, indicating whether the applicable Pretreatment Standards are being met on a consistent basis, and, if not, whether additional operation and maintenance (O&M) and/or additional pretreatment systems are required to attain consistent compliance with the Pretreatment Standards and requirements.
7. Compliance Schedule. If additional pretreatment and/or O&M is required to meet the Pretreatment Standards, the shortest schedule by which the User will provide such additional pretreatment and/or O&M. The completion date in this schedule shall not be later than the compliance date established for the applicable

Pretreatment Standard. A compliance schedule pursuant to this section shall meet the requirements set out in this Ordinance.

8. Signature and Certification. All baseline monitoring reports shall be signed and certified in accordance with this Ordinance.

Section 16.352: COMPLIANCE SCHEDULES/PROGRESS REPORTS

The following conditions shall apply to the compliance schedules required by this Ordinance:

- A. The schedule shall contain progress increments in the form of dates for the commencement and completion of major events leading to the construction and operation of additional pretreatment required for the User to meet the applicable Pretreatment Standards (such events include, but are not limited to, retaining an engineer, completing preliminary and final design plans, executing contracts for major components, commencing and completing construction, and beginning and conducting routine operation);
- B. No increment referred to above shall exceed nine (9) months;
- C. The User shall submit a progress report to the City no later than fourteen (14) days following each date in the schedule and the final date of compliance including, as a minimum, whether or not it complied with the increment of progress, the reason for any delay, and, if appropriate, the action being taken by the User to return to the established schedule; and
- D. In no event shall more than nine (9) months elapse between such progress reports to the City.

Section 16.353: REPORTS ON COMPLIANCE WITH CATEGORICAL PRETREATMENT DEADLINE

Within ninety (90) days, following the date for final compliance with applicable Categorical Pretreatment Standards, or in the case of a New Source following commencement of the introduction of wastewater into the POTW, any User subject to such Pretreatment Standards and requirements shall submit to the City a report containing the information described in Section 16.351 (B) (1-5) of this Ordinance. For users subject to equivalent mass or concentration limitations established in accordance with the procedures in 40 CFR 403.6(c), this report shall contain a reasonable measure of the User's long-term production rate. For all other users subject to Categorical Pretreatment Standards expressed in terms of allowable pollutant discharge per unit of production (or other measure of operation), this report shall include the User's actual production during the appropriate sampling period. All compliance reports shall be signed and certified in accordance with this Ordinance.

Section 16.354: PERIODIC COMPLIANCE REPORTS

- A. All users holding IDPs shall, at a frequency determined by the City but in no case less than twice per year for Class 1 users (annually for Class 2 users), submit a report as specified on their IDP. This report shall include the results of the analysis of wastewater samples indicating the nature and concentration of pollutants in their wastewater that are limited by this Ordinance, and the measured or estimated average and maximum daily flows for the reporting period. In cases where compliance with a Best Management Practice or Pollution Prevention alternative is required, the User shall submit documentation as required by the City or the applicable Standards to determine compliance status of the User. All periodic compliance reports shall be signed and certified in accordance with this Ordinance.
- B. All wastewater samples shall be representative of the User's typical discharge. Wastewater monitoring and flow measurement facilities shall be properly operated, kept clean and orderly, and maintained in good working order at all times. The failure of a User to maintain its monitoring facility in satisfactory working condition shall not be grounds for the User to claim that sample results are unrepresentative of its discharge.
- C. If a User subject to the reporting requirement in this Ordinance monitors any pollutant more frequently than required by the City, using the procedures prescribed in Sections 16.360 and 16.361 of this Ordinance, the results of this monitoring shall be included in the report.

Section 16.355: REPORTS OF CHANGED CONDITIONS

Each User shall notify the City of any planned significant changes to the User's operations or system that might alter the nature, quality, or volume of its wastewater at least ninety (90) days before the change.

- A. The City may require the User to submit such information the City deems necessary to evaluate the changed condition, including the submittal of an IDP application.
- B. The City may issue an IDP or modify an existing IDP in response to changed conditions or anticipated changed conditions.
- C. For purposes of this requirement, significant changes include, but are not limited to, flow increases of twenty percent (20%) or greater, and the discharge of any previously unreported pollutants.

Section 16.356: REPORTS OF SLUGS OR POTENTIALLY ADVERSE DISCHARGES

- A. In the case of any discharge, including, but not limited to, accidental discharges, discharges of a non-routine, episodic nature, a non-customary batch discharge, or a Slug, that may adversely impact the POTW, the User shall immediately telephone and notify the POTW of the incident. This notification shall include the location of the discharge, type of waste, concentration and volume, if known, and corrective actions conducted by the User.

- B. Within five (5) days following such discharge, the User shall, unless waived by the City, submit a detailed written report describing the cause(s) of the discharge and the measures to be initiated by the User to prevent similar future occurrences. Such notification shall not relieve the User of any expense, loss, damage, or other liability that may be incurred as a result of damage to the POTW, natural resources, or any other damage to person or property; nor shall such notification relieve the User of any fines, penalties, or other liability that may be imposed pursuant to this Ordinance. This report shall be signed and certified in accordance with this Ordinance.
- C. A notice shall be permanently posted on the User's bulletin board or other prominent location advising employees who to call in the event of a discharge described in paragraph (A) of this section. Employers shall ensure that all employees who could cause such a discharge to occur are advised of the emergency notification procedure.
- D. The permittee shall notify the City of any changes at its facility that may affect the potential for a Slug Discharge. The City may require the permittee to develop or modify a Slug Control Plan or take other actions to control Slug Discharges.

Section 16.357: REPORTS FROM UNPERMITTED USERS

A. The City may require users not otherwise required to obtain an IDP to perform monitoring of their discharges including the installation, use and maintenance of monitoring equipment, keeping of records and reporting the results of such monitoring to the City. Such records shall be made available upon request by the City to other agencies having jurisdiction over discharges to the receiving waters.

Section 16.358: NOTICE OF VIOLATION / REPEAT SAMPLING AND REPORTING

In the event that effluent monitoring indicates a violation (i.e., exceedance of a limit), the presence of a previously unreported pollutant, the User shall notify the City within twenty-four (24) hours of becoming aware of the exceedance. For violations (and unreported pollutants exceedances at the discretion of the City), the User shall also repeat the sampling and analysis and submit the results of the repeat analysis to the City within thirty (30) days subsequent to becoming aware of the violation. The User is not required to resample if the City monitors that pollutant at the User's facility at least once a month, or if the City samples for that pollutant between the User's initial sampling and when the User receives the results of this sampling.

Section 16.359: NOTICE OF DISCHARGE OF HAZARDOUS WASTE

Any discharge into the POTW of a substance that, if otherwise disposed would be a hazardous waste under 40 CFR Part 261 or are hazardous wastes as defined in the NHDES Hazardous Waste Rules, is prohibited unless permitted by applicable State of New Hampshire and Federal permits and the City.

In the event that a Connector becomes aware of a discharge of hazardous waste, the notification requirements of Section 16.356 items A and B will apply.

Section 16.360: ANALYTICAL REQUIREMENTS

All pollutant analyses, including sampling techniques, to be submitted as part of an IDP application or report shall be performed in accordance with the techniques prescribed in 40 CFR Part 136, unless otherwise specified in an applicable Categorical Pretreatment Standard. If 40 CFR Part 136 does not contain sampling or analytical techniques for the pollutant in question, sampling and analyses shall be performed in accordance with procedures approved by EPA.

A laboratory that is currently certified by the State of New Hampshire to perform the requested tests shall perform all analyses. Complete copies of analytical laboratory reports, including all relevant quality control data, shall be submitted as part of each IDP application or report. If, for whatever reason, any part of a laboratory report is deleted, augmented, or otherwise changed following its original issuance by the laboratory, then any IDP application or report making use of that laboratory data shall clearly and completely identify the original report content and the nature of the change that was made.

Section 16.361: SAMPLE COLLECTION

Samples collected to satisfy reporting requirements shall be based on data obtained through appropriate sampling and analysis performed during the period covered by the report, based on data that is representative of conditions occurring during the reporting period.

A. Except as indicated in paragraph (B), below, the User shall collect wastewater samples using twenty-four-hour flow-proportional composite collection techniques. In the event flow-proportional sampling is not feasible, the City may authorize the use of time-proportional sampling or a minimum of four (4) Grab Samples where the User demonstrates that this will provide a representative sample of the effluent being discharged. Using protocols (including appropriate preservation) specified in 40 CFR Part 136 and appropriate EPA guidance, multiple grab samples collected during a 24-hour period may be composited prior to the analysis as follows: for cyanide, total phenols, and sulfides the samples may be composited in the laboratory or in the field; for volatile organics and oil and Grease, the samples may be composited in the laboratory. Composite samples for other parameters unaffected by the compositing procedures as documented in approved EPA methodologies may be authorized by [the City], as appropriate. In addition, Grab Samples may be required to demonstrate compliance with Instantaneous Limits. A single Grab Sample may also be used in place of a composite sample with approval of the City when:

1. The effluent is not discharged on a continuous basis (i.e., batch discharges of short duration), and only when the batch exhibits homogeneous characteristics (i.e., completely mixed) and the pollutant can be safely assumed to be uniformly dispersed;
2. Sampling is at a facility where the City determines that a statistical relationship can be established between previous Grab Samples and composite data; and

3. The waste conditions are relatively constant (i.e., are completely mixed and homogeneous) over the period of the discharge.
- B. Samples for oil and Grease, temperature, pH, cyanide, total phenols, sulfides, and volatile organic compounds shall be obtained using grab collection techniques in accordance with 40 CFR Part 136.
- C. For sampling required in support of baseline monitoring and 90-day compliance reports required in Section[s] 16.351 and 16.353 [40 CFR 403.12(b) and (d)], a minimum of four (4) Grab Samples shall be used for pH, cyanide, total phenols, oil and Grease, sulfide and volatile organic compounds for facilities for which historical sampling data do not exist; for facilities for which historical sampling data are available, the City may authorize a lower minimum. For the reports required by Section 16.354 [40 CFR 403.12(e) and 403.12(h)], the Industrial User is required to collect the number of Grab Samples necessary to assess and assure compliance with applicable Pretreatment Standards and requirements.
- D. Samples shall only be collected by individuals who are properly qualified, through verifiable training and experience, to perform the type of sampling required. The integrity of all samples shall be ensured by following established chain-of-custody practices for evidentiary samples. Sampling and chain-of-custody records shall be maintained in accordance with the IDP. Copies of chain-of-custody records shall be submitted as part of each IDP application or report.

Section 16.362: TIMING

Written reports will be deemed to have been submitted on the date postmarked. For reports that are not mailed, the date of receipt of the report by the person designated in the Industrial Discharge Permit shall govern.

Section 16.363: RECORDKEEPING

Users subject to the reporting requirements of this Ordinance shall create, retain, and make available for inspection and copying, records of all information obtained pursuant to any monitoring activities, including documentation associated with Best Management Practices, required by this Ordinance or IDP and any additional records of information obtained pursuant to monitoring activities undertaken by the User independent of such requirements. Records shall include the date, exact location, method, and time of sampling, and the name of the person(s) obtaining the samples; the dates analyses were performed; who performed the analyses; the analytical techniques or methods used; and the results of such analyses. These records shall remain available for a period of at least five (5) years. This period shall be automatically extended for the duration of any litigation concerning the User or the City, or where the User has been specifically notified of a longer retention period by the City. The City may require records be submitted upon written request to local or State officials.

Section 16.364-16.370: RESERVED

DIVISION 7—POWERS AND AUTHORITIES OF INSPECTORS

Section 16.371: RIGHT OF ENTRY: INSPECTION AND SAMPLING

All Connectors discharging to the POTW shall allow unrestricted access by City, State and EPA personnel and their duly authorized agents (“Inspectors”) for the purpose of determining whether the Connector is complying with all requirements of this Ordinance, and any IDP or order issued hereunder. Inspectors bearing proper identification shall have access to all parts of the premises for the purposes of inspection, sampling, records examination and copying, and the performance of any additional duties.

- A. Where a Connector has security measures in force that require proper identification and clearance before entry into its premises, the Connector shall make and maintain all necessary arrangements so that, upon presentation of suitable identification, the Inspectors will be permitted to enter without delay for the purposes of performing specific responsibilities.
- B. The Inspectors shall have the right to set up on the Connector's property, or require installation of, such devices as are necessary to conduct sampling and/or metering of the Connector's operations.
- C. The Inspectors may require the Connector to install monitoring equipment as necessary. The facility's sampling and monitoring equipment shall be maintained at all times in a safe and proper operating condition by the Connector at its own expense. All devices used to measure wastewater flow and quality shall be calibrated in accordance with the manufacturer's recommendations (but at least annually) to ensure their accuracy. Calibration records shall be maintained.
- D. Any temporary or permanent obstruction to safe and easy access to the facility to be inspected and/or sampled shall be promptly removed by the Connector at the written or verbal request of the Inspectors and shall not be replaced. The costs of clearing such access shall be borne by the Connector.
- E. Unreasonable delays in allowing the Inspectors access to the Connector's premises, sampling or inspection sites, or pretreatment records shall be a violation of this Ordinance.
- F. Inspectors are authorized to obtain information concerning all industrial processes that have a bearing on the kind or source of discharge to the POTW.
- G. Inspectors shall observe all safety rules applicable to the premises established by the Connector.
- H. Inspectors shall be permitted to enter all private properties through which the City or State holds an easement for the purposes of, but not limited to, inspection, observation,

measurement, sampling, repair, and maintenance of any portion of the POTW lying within the described easement. All entry and subsequent work, if any, within the easement, shall be done in accordance with the terms of the easement.

Section 16.372: ADMINISTRATIVE INSPECTION WARRANT

The City shall have all rights available to it under State law including without limitation under RSA 595-B, to apply for any administrative inspection warrant or like legal authority to enter any building, structure, or property, or any part thereof, for purposes of enforcing this Ordinance.

Section 16.373-16.375: RESERVED

DIVISION 8—CONFIDENTIAL INFORMATION

Section 16.376: CONFIDENTIAL INFORMATION

Information and data about a Connector obtained from reports, surveys, IDP Applications, IDPs, monitoring programs, and from the City's inspection and sampling activities, shall be public records. User may, at the time of collection or submittal of information or data, request that such information or data be designated as confidential and the reason for such designation (for example that the documentation reveals proprietary methods of production entitled to protection as a trade secret under State law). That stated, in the event of any public record request, the City shall apply the current law under RSA 91-A or its equivalent relative to the determination as to whether the document or data is or is not subject to disclosure. Further, all information and data, regardless of designation shall be made available immediately upon request to governmental agencies for uses related to this Ordinance, the NPDES program or pretreatment program, and in enforcement proceedings. Wastewater constituents and characteristics and other "effluent data" as defined by 40 CFR 2.302 will not be recognized as confidential information.

Section 16.377-16.380: RESERVED

DIVISION 9—PUBLICATION OF USERS IN SIGNIFICANT NONCOMPLIANCE

Section 16.381: ANNUAL PUBLICATION

The City will publish annually, in a newspaper(s) of general circulation that provides meaningful public notice within the jurisdiction(s) served by the POTW, a list of the users that, during the previous twelve (12) months, were in Significant Noncompliance with applicable Pretreatment Standards and requirements. The term Significant Noncompliance shall be applicable to all Significant Industrial Users (or any other Industrial User that violates paragraphs (C), (D) or (H) of this Section) and shall mean:

- A. Chronic violations of wastewater discharge limits, defined here as those in which sixty-six percent (66%) or more of all the measurements taken for the same pollutant parameter

taken during a six (6) month period exceed (by any magnitude) a numeric Pretreatment Standard or Requirement, including Instantaneous Limits as defined in Division 2;

- B. Technical Review Criteria (TRC) violations, defined here as those in which thirty-three percent (33%) or more of wastewater measurements taken for each pollutant parameter during a six (6) month period equals or exceeds the product of the numeric Pretreatment Standard or Requirement including Instantaneous Limits, as defined by Division 2 multiplied by the applicable criteria (1.4 for BOD, TSS, fats, oils and Grease, and 1.2 for all other pollutants except pH);
- C. Any other violation of a Pretreatment Standard or Requirement as defined by Division 2 (Daily Maximum, long-term average, Instantaneous Limit, or narrative standard) that the Director determines has caused, alone or in combination with other discharges, Interference or Pass Through, including endangering the health of POTW personnel or the general public;
- D. Any discharge of a pollutant that has caused imminent endangerment to the public or to the environment, or has resulted in the Director's exercise of its emergency authority to halt or prevent such a discharge;
- E. Failure to meet, within ninety (90) days of the scheduled date, a compliance schedule milestone contained in an individual wastewater discharge permit or enforcement order for starting construction, completing construction, or attaining final compliance;
- F. Failure to provide within forty-five (45) days after the due date, any required reports, including baseline monitoring reports, reports on compliance with Categorical Pretreatment Standard deadlines, periodic self-monitoring reports, and reports on compliance with compliance schedules;
- G. Failure to accurately report noncompliance; or
- H. Any other violation(s), which may include a violation of Best Management Practices, which the Director determines will adversely affect the operation or implementation of the Industrial Pretreatment Program.

Section 16.382: RESERVED

DIVISION 10—ADMINISTRATIVE ENFORCEMENT REMEDIES

Section 16.383: NOTIFICATION OF VIOLATION

When the City determines that a person or Connector has violated, or continues to violate, any provision of this Ordinance, an IDP, or order issued hereunder, or any other Pretreatment Standard or requirement, the City may serve upon that person or Connector a written Notice of Violation. A response to the Notice of Violation is required within the time specified in the violation notice. A Notice of Violation may require an explanation of the violation and a plan for the satisfactory correction and prevention of a future violation. Submittal of this plan in no way relieves the Connector of liability for any violations occurring before or after receipt of the Notice of Violation. Nothing in this Ordinance shall limit the authority of the City to take any action, including emergency actions or any other enforcement action, without first issuing a Notice of Violation.

Section 16.384: COMPLIANCE SCHEDULE DEVELOPMENT

The City may require any Connector that has violated, or continues to violate, any provision of this Ordinance, an IDP or order issued hereunder, or any other Pretreatment Standard or requirement, to develop a compliance schedule as described in this Ordinance.

Section 16.385: POLLUTION PREVENTION PLAN DEVELOPMENT

The City may require any Connector that has violated or continues to violate any provision of this Ordinance, an IDP, or order issued hereunder, or any other Pretreatment Standard or requirement, to develop a Pollution Prevention plan in accordance with this Ordinance.

Section 16.386: ADMINISTRATIVE ORDERS

The City may issue any form of administrative order to implement and enforce the requirements of this Ordinance. Such administrative orders may take the form of any of the following types:

Compliance Order. This form of administrative order directs the person or Connector to achieve or restore compliance by a date specified in the order. This administrative order is not negotiated with the person or Connector.

Cease-and-Desist Order. This form of administrative order demands the immediate cessation of unauthorized discharges or unlawful conduct.

Show Cause Order. This form of administrative order directs the person or Connector to appear before the City, explain its noncompliance and show cause why enforcement action against the Connector should not be taken. Notice shall be served on the person or Connector specifying the time and place for the meeting, the proposed enforcement action, the reasons for such action, and request that the Connector show cause why enforcement action should not be taken. The notice of the meeting shall be served personally or by registered or certified mail at least ten (10) days prior to the meeting. Such notice may be served on any Authorized Representative of the Connector.

Consent/Negotiated Order. This form of administrative order reflects the negotiation of a resolution to bring the Connector into compliance. Such orders typically include specific action to be taken by the Connector correct the noncompliance within a time period specified by the order.

Section 16.387: TERMINATION OF CONNECTION AND REVOCATION

The City may terminate the connection of any Connector or revoke any IDP or other permit, permission or approval for connection, for good cause, including but not limited to the following:

- A. Violating any condition of any IDP, permit or other permission to connect;
- B. Failing to accurately report the wastewater constituents and characteristics of its discharge;
- C. Failing to report significant changes in operations or wastewater constituents and characteristics;
- D. Misrepresenting or failing to fully disclose all relevant facts in any application or report;
- E. Refusing to allow Inspectors timely access to the Connector's premises and records;
- F. Falsifying any self-monitoring reports or certification statements;
- G. Tampering with monitoring equipment;
- H. Failing to pay any fines, penalties, costs, fees or sewer charges;
- I. Failing to comply with any administrative order or meet any compliance schedule;
- J. Failing to complete a wastewater survey if requested to do so;
- K. Failing to provide advance notice of the transfer of a permitted facility;
- L. Discharging wastewater that presents an imminent hazard to the public health, safety or welfare, or to the local environment;
- M. Violating any Pretreatment Standard
- N. Violating any other requirement of this Ordinance or any applicable State or Federal law;
or
- O. Other good cause.

Section 16.388: EMERGENCY SUSPENSIONS

The City may immediately suspend a Connector's or Industrial User's discharge subsequent to informal notice to the Connector, whenever such suspension is necessary to terminate an actual or threatened discharge that reasonably appears to present or cause an imminent or substantial endangerment to the health or welfare of City personnel or the public, or an imminent or substantial damage the POTW or the environment.

- A. Any Connector notified of a suspension of its discharge shall immediately terminate or eliminate its wastewater discharge. In the event of a Connector's failure to immediately comply voluntarily with the suspension order, the City may implement such steps as deemed necessary, including immediate severance of the sewer connection and entry on private property to halt such discharge.
- B. The City may require such documentation, sampling and other action as it deems necessary from any Connector whose service has been suspended to evaluate when and if reconnection and wastewater discharges may resume.

Nothing in this section shall be interpreted as requiring a hearing prior to any emergency suspension under this section.

Section 16.389: RECOVERY OF EXPENSES

Any person or Connector violating any of the provisions of this Ordinance shall be liable to the City for any expense, loss, or damage incurred by reason of such violation, including without limitation any sampling or testing costs, any labor and material costs to prevent or repair damage to the POTW and any expenses associated with disconnection and reconnection of any service. The City may refuse to permit the restoration of any connection or of any new connection to the property until all costs, expenses, loss or damage is paid in full.

Section 16.390 - 16.395: RESERVED

DIVISION 11—JUDICIAL ENFORCEMENT REMEDIES

Section 16.396: INJUNCTIVE RELIEF

When the City determines that any person or Connector has violated, or continues to violate, any provision of this Ordinance, an IDP, or order issued pursuant to this Ordinance, or any other Pretreatment Standard or requirement, the City may petition any court with jurisdiction for any form of injunctive relief as may be appropriate to effectuate enforcement and implement the purposes of this Ordinance. Legal action for injunctive relief shall not be a bar against, or a prerequisite for, implementing any other action against a person or Connector.

Section 16.397: CIVIL PENALTIES

- A. Any person or Connector who has violated, or continues to violate, any provision of this Ordinance, an IDP, or order issued hereunder, or any other Pretreatment Standard or requirement shall be liable to the City for a maximum civil penalty of up to \$10,000 per violation, per day, plus actual damages incurred by the POTW or such greater amount as may be allowed by State law. Penalties shall accrue for each day during the period of the violation.

- B. The City may recover reasonable attorneys' fees, court costs, and other expenses associated with enforcement activities, including sampling and monitoring expenses, and the cost of any actual damages incurred by the City.
- C. In determining the amount of civil liability, the Court shall consider all relevant circumstances, including, but not limited to, the extent of harm caused by the violation, the magnitude and duration of the violation, any economic benefit gained through the Connector's violation, corrective actions implemented by the Connector, the compliance history of the Connector, and any other factor as justice requires.
- D. Filing a suit for civil penalties shall not be a bar against, or a prerequisite for, implementing any other action against a person or Connector.

Section 16.398: CRIMINAL PROSECUTION

The City shall have all criminal penalties available under State law including without limitation for the unlawful Interference and destruction of POTW infrastructure, false swearing of any reports or records submitted to the City and unsworn false statements of any kind upon which the City may rely in carrying out this Ordinance.

Section 16.399: REMEDIES NONEXCLUSIVE

The remedies provided for in this Ordinance are not exclusive. The City may take any, all, or any combination of these actions against a noncompliant person or Connector.

Section 16.400: RESERVED

DIVISION 12—AFFIRMATIVE DEFENSES TO DISCHARGE VIOLATIONS

Section 16.401: UPSET

- A. For the purposes of this section, “upset” means an exceptional incident in which there is unintentional and temporary noncompliance with Pretreatment Standards due to factors beyond the reasonable control of the User. An upset does not include noncompliance to the extent caused by operational error, improperly designed treatment facilities, inadequate treatment facilities, lack of preventive maintenance, or careless or improper operation.
- B. An upset shall constitute an affirmative defense to an action brought for noncompliance with Pretreatment Standards if the requirements of paragraph (C), below, are met.
- C. A User who intends to establish the affirmative defense of Upset shall demonstrate, through properly signed, contemporaneous operating logs, or other relevant evidence that:
 - 1. An upset occurred and the User can identify the cause(s) of the upset;

2. At the time of the upset, the facility was being operated in a prudent and workman-like manner and in compliance with applicable operation and maintenance procedures; and
3. The User has submitted the following information to the City within twenty-four (24) hours of becoming aware of the upset (if this information is provided orally, a written submittal shall be provided within five (5) days):
 - a. A description of the discharge and cause of noncompliance;
 - b. The period of noncompliance, including exact dates and times or, if not corrected, the anticipated time the noncompliance is expected to continue; and
 - c. Action being implemented and/or planned to reduce, eliminate, and prevent recurrence of the noncompliance.
- D. In any enforcement proceeding, the User seeking to establish the occurrence of an upset shall have the burden of proof.
- E. Users will have the opportunity for a judicial determination on any claim of upset only in an enforcement action brought for noncompliance with Pretreatment Standards.
- F. A User shall control production of all discharges to the extent necessary to maintain compliance with Pretreatment Standards upon reduction, loss, or failure of its treatment facility until the facility is restored or an alternative method of treatment is provided. This requirement applies in the situation where, among other things, the primary source of power of the treatment facility is reduced, lost, or fails.

Section 16.402: PROHIBITED DISCHARGE STANDARDS

A User shall have an affirmative defense to an enforcement action brought against it for noncompliance with the general prohibitions in paragraph 16.314(A) of this Ordinance or the specific prohibitions in paragraph 16.314 (B) of this Ordinance if it can prove that it did not know, or have reason to know, that its discharge, alone or in conjunction with discharges from other sources, would cause Pass Through or Interference and that either:

- A. A local limit exists for each pollutant discharged and the User was in compliance with each limit directly prior to, and during, the Pass Through or Interference; or
- B. No local limit exists, but the discharge did not change substantially in nature or constituents from the User's prior discharge when the City was regularly in compliance with its NPDES permit, and in the case of Interference, was in compliance with applicable biosolids use or disposal requirements.

Section 16.403: BYPASS

- A. For the purposes of this section,

1. "Bypass" means the intentional diversion of waste streams from any portion of a User's treatment facility.
 2. "Severe property damage" means substantial physical damage to property, damage to the treatment facilities that causes them to become inoperable, or substantial and permanent loss of natural resources that can reasonably be expected to occur in the absence of a bypass. Severe property damage does not mean economic loss caused by delays in production.
- B. A User may allow any bypass to occur that does not cause Pretreatment Standards or requirements to be violated, but only if it also is for essential maintenance to assure efficient operation. These bypasses are not subject to the provision of paragraphs (C) and (D) of this section.
- C. Notifications for bypass events:
1. If a User is aware in advance of the need for a bypass, the User shall submit prior notice to the City, at least ten (10) days before the date of the bypass, if possible.
 2. A User shall submit oral notice to the City of an unanticipated bypass that exceeds applicable Pretreatment Standards within twenty-four (24) hours from the time the User becomes aware of the bypass. A written submittal shall also be provided within five (5) days of the time the User becomes aware of the bypass. The written submittal shall contain a description of the bypass and its cause; the duration of the bypass, including exact dates and times, and, if the bypass has not been corrected, the anticipated time it is expected to continue; and steps implemented or planned to reduce, eliminate, and prevent reoccurrence of the bypass. The City may waive the written report on a case-by-case basis if the oral report has been received within twenty-four (24) hours.
- D. Bypass is prohibited, and the City may initiate enforcement action against a User for a bypass, unless
1. The bypass was unavoidable to prevent loss of life, personal injury, or severe property damage;
 2. There were no feasible alternatives to the bypass, such as the use of auxiliary treatment facilities, retention of untreated wastes, or maintenance during normal periods of equipment downtime. This condition is not satisfied if adequate back-up equipment should have been installed in the exercise of reasonable engineering judgment to prevent a bypass that occurred during normal periods of equipment downtime or preventive maintenance; and
 3. The User submitted notices as required under paragraph (C) of this section.

- E. The City may approve an anticipated bypass, subsequent to considering its adverse effects, if the City determines that it will satisfy the three conditions listed in paragraph (D) of this section.

Section 16.404 – 16.405: RESERVED

DIVISION 13—SEPTAGE DISPOSAL

Section 16.406: SEPTIC TANK WASTE (SEPTAGE)

The POTW may designate a receiving structure for the acceptance of Septage and establish procedures for its receipt. If the POTW accepts Septage the following shall apply:

- A. The City shall have authority to refuse or limit the disposal of any hauled waste for any reason including but not limited to potential Interference with the operation of the POTW and potential violation the National Pollutant Discharge Elimination System (NPDES) permit.
- B. Any Hauler seeking to dispose of Septage shall maintain and provide to the City any permit required by NH RSA 485-A. Upon renewal or revocation of such a permit, the Hauler shall be responsible for notification of such renewal or revocation to the City.
- C. Haulers shall provide all information requested by the City.
- D. The City may require Hauler to provide a waste analysis of any load prior to discharge.
- E. The City may collect samples of each hauled load.

The discharge of Industrial Wastes as "industrial Septage" is prohibited.

Section 16.407: RESERVED

DIVISION 14—SEWER USE RATES AND FEES

Section 16.408: RATES AND FEES

Rates for sewer usage, the Capacity Use Multiplier, and fees for all permits, sampling, monitoring, testing and other activities arising from the requirements of this Ordinance shall be governed by City Ordinance Chapter 1 Article XVI. Without limitation, fees may be assessed for:

- A. Applications, permits and connections required by this ordinance including Sewer Connection, Irrigation Meters, Drain Layer Permits, Fats, Oils, and Grease Program Permitting (Grease Interceptors/Grease Traps), Septage Disposal and the Industrial Pretreatment Program;
- B. Inspections, monitoring, testing and analysis that may be required to ensure compliance

- with this Ordinance; and
- C. Reviewing and responding to late filings, accidental discharges and other administrative costs due to non-compliance.

Sewer user charges shall be based upon water use whenever possible. No allowance shall be made for watering lawns or watering gardens, except for users who have installed at their cost an irrigation system as may be allowed under section 16.409 and a second water meter, meeting City specifications intended to measure water use which is reasonably calculated not to be discharged into the sewer system. Where such second meters have been installed, a separate account will be established and no sewer charges will be applied to this usage. A monthly service fee shall be charged for each irrigation meter in addition to the consumption charge, said fee to be determined by the City Council during its annual budget process.

Section 16.409: IRRIGATION METERS

Users of the City of Portsmouth's water system may request a permit for the installation of an irrigation system and irrigation meter. An application shall be completed and submitted to the Water Department for the installation of an irrigation system and irrigation meter prior to the issuance of an irrigation permit. The Water Department may deny the issuance of a permit for an irrigation system or irrigation meter when the existing water main does not provide sufficient water volume/pressure to support the demands of an irrigation system without causing unacceptably low water pressure for other customers on the same water main.

Irrigation service lines and meters shall be installed not more than four feet from the prime meter and shall be installed parallel to the prime meter. Sewer charges shall not apply to water amounts measured by irrigation meters. Shut off valves are required ahead and behind the irrigation meter and shall be within one foot of the meter. A back flow preventer (approved by the City) to protect against contamination of the water system shall be installed behind the irrigation meter.

Only a landscape irrigation system designed and installed by an Environmental Protection Agency WaterSense Certified Irrigator in accordance with the criteria set forth in this section shall be deemed to be in compliance with subparagraph (a) of this section. The Certified Irrigator shall certify in writing to the Water Division that the landscape irrigation system has been designed and installed in accordance with subparagraph (a) of this section. This certification shall be provided to the Water Division at the time of requesting final inspection of the system.

A. Automatic irrigation systems shall:

1. Be maintained in compliance with the provisions of this section;
2. Be rendered inoperative by or at the direction of the irrigation system owner or operator pending repairs if damaged in a manner that results in leakage or excessive discharge of water from broken components;
3. Include rain sensors to be installed and maintained on all irrigation systems equipped with automatic irrigation controllers and set to render the irrigation system inoperative at $\frac{1}{4}$ inch of moisture or more;

4. Include freeze sensors to be installed and maintained on all irrigation systems equipped with automatic irrigation controllers, which will render the system inoperative at 35 degrees Fahrenheit or higher lower;
5. Be designed so that spray or rotary heads are at least four (4) inches inside from any curbing, sidewalk, fencing, or building;
6. Be designed so that heads spray only towards pervious surface or landscaped area;
7. Be designed to include a zonal irrigation system; and
8. Be designed to include a master valve.

B. Operation of irrigation systems or devices:

From April 1 to September 30, landscape irrigation utilizing water, in whole or in part, obtained from the City water system, is prohibited except during the times between 6:00 p.m. and 10:00 a.m. The City Manager, or designee, may further restrict landscape irrigation to specified days of the week or otherwise restrict the irrigation schedule as circumstances dictate.

Section 16.410: BILLING AND OTHER METERS

- A. If records of metered water use are not available or do not reasonably reflect the quantity of waste discharged into the POTW, the sewer user charge shall be based upon estimated water use or on actual measurement of the volume of waste discharged into the sewer system. Sewer surcharges shall be levied upon users whose waste characteristics are found to be above normal strength.
- B. Owners of all houses, buildings, or properties used for human occupancy, employment, recreation or other purposes situated within the City who are required to be connected to the public sewer pursuant to this Ordinance, and not connected into a public sewer, shall pay sewer user charges as if connected to a public sewer.
- C. In the event that the owner or owners of a business which is commercial or industrial can clearly define and separate a portion of the potable water entering the business establishment which is totally consumed in process, the owner or owners may, at their own expense, install and maintain an A.W.W.A. approved water meter in the line supplying the portion of the water consumed in process. This meter shall be considered to be a deduct meter; the volume of water flowing through the deduct meter shall be subtracted from the volume measured by the primary water metering device located on the premises for the purpose of computing the sewer fee charge.

Section 16.411-12: RESERVED

DIVISION 15—MISCELLANEOUS

Section 16.413: VALIDITY

The invalidity of any section, clause, sentence, or provision of this Ordinance shall not affect the validity of any other part of this Ordinance, which can be given effect without such invalid part or parts.

Section 16.414: LIMITS OF LIABILITY

Neither the issuance of a permit nor the acceptance of any sewer construction by any City official or employee shall be construed as acceptance of any liability by the City or any of its employees for claims which may arise due to errors, oversights, inferior material, poor workmanship, or damages incurred in connection with construction of any Building Sewer or private Sewage disposal systems as may be required in this Ordinance.

Section 16.415: INTERPRETATION

The provisions of this Ordinance with respect to the meaning of technical terms and phrases, the classification of different types of sewers, the regulations with respect to installing or constructing connections to sewers or drains, and other technical matters shall be interpreted and administered by the Director.

Section 16.416: APPEALS

Any person or Connector aggrieved by a decision or action of the Director under this Ordinance, may appeal that decision within thirty (30) calendar days to the City Manager by submitting a request in writing to the City Manager's office setting forth the decision or action which is being appealed and a summary of the grounds for appeal. The City Manager may make such inquiries and enlist the opinions of the aggrieved person, City staff, in-house or outside legal counsel, third-party wastewater engineers or any other person deemed helpful to the consideration of the appeal. A written decision will be issued within sixty (60) days of the appeal unless extended by mutual agreement.

The City Clerk shall properly alphabetize and/or re-number the ordinances as may be necessary in accordance with this amendment.

All ordinances or parts of ordinances inconsistent herewith are hereby deleted.

This ordinance shall take effect 90 days after its passage.

APPROVED:

Deaglan McEachern, Mayor

ADOPTED BY COUNCIL:

Sally Kellar, City Clerk

APPENDICES

Appendix I – Maximum Allowable Industrial Mass Loading Limitations / Local Limits

Friends of Lafayette House

September 30, 2026

The Portsmouth City Council
c/o City Attorney
Legal Department
Portsmouth City Hall
1 Jenkins Ave
Portsmouth, NH 03801

RE: Friends of Lafayette House
413 Lafayette Rd.
Portsmouth, NH 03801
Tax Map 230-23A

Dear Rosann Lentz, and City Councilors.

Please accept this letter in regard to our tax assessment status and the application of the statute, NHRSA 72-23-k "Charitable, Non-profit Housing Projects". We are a HUD funded facility, so this specific statute applies.

Friends of Lafayette House is offering again this year to pay in lieu of taxes as follows:

Friends of Lafayette House will pay annually \$3,500.00. We feel this is a reasonable amount to recognize City services and to recognize the important charitable work that the Friends of Lafayette House does with its limited funding.

We hope you will agree to this proposal and we look forward to your response.

The City's acceptance again this year would be very much appreciated

Sincerely,

Rene Sullivan

Rene Sullivan
Executive Director
Friends of Lafayette House

Cc: Rosann Maurice-Lentz, City Assessor

400 Little Harbor Road, Box 1104 Portsmouth, NH 03801

**PAYMENT IN LIEU OF PROPERTY TAX AGREEMENT BETWEEN
THE CITY OF PORTSMOUTH AND FRIENDS OF LAFAYETTE HOUSE
(PILOT)**

This Agreement is made as of this _____ day of October, 2026, pursuant to NH RSA 72:23-k, by and between the FRIENDS OF LAFAYETTE HOUSE, having a place of business at 413 Lafayette Road, Portsmouth, New Hampshire 03801, and the CITY OF PORTSMOUTH, a municipal corporation established under the laws of the State of New Hampshire (the “CITY”), having a place of business at 1 Junkins Ave., Portsmouth, New Hampshire 03801.

RECITALS

- A. FRIENDS OF LAFAYETTE HOUSE is a New Hampshire non-profit organization dedicated to supporting Lafayette House, a group home for the developmentally disabled, located at 413 Lafayette Road, Portsmouth, New Hampshire 03801 (the “Property”).
- B. Lafayette House is a group home for the developmentally disabled, with 12 residents, 13 bedrooms, 8 bathrooms, a kitchen, living room and dining room.
- C. Lafayette House is supported by FRIENDS OF LAFAYETTE HOUSE, a tax-exempt charitable non-profit under Section 501(c)(3) of the Internal Revenue Code. The income and profits of Friends of Lafayette House are used solely for community housing purposes.
- D. RSA 72:23-k defines the property to which the Charitable, Non-Profit Housing Project property tax exemption applies and is supplemented by N.H. Code of Administrative Rules Part Rev 423.
- E. The CITY recognizes that as presently constituted the LAFAYETTE HOUSE/the Property satisfies the requirements of these laws and is therefore entitled to a property tax exemption pursuant to RSA 72:23-k.
- F. Pursuant to RSA 72:23-k, II, the FRIENDS OF LAFAYETTE HOUSE shall make a payment in lieu of taxes in the amount of \$3,500.
- G. The CITY is willing to recognize and grant to THE FRIENDS OF LAFAYETTE HOUSE an exemption from taxation and accept a payment in lieu of taxes by THE FRIENDS OF LAFAYETTE HOUSE, as set forth in this Agreement based on the current ownership and current use of Property.

WHEREFORE, based upon the mutual covenants and promises contained herein, and for other good and valuable consideration which the parties acknowledge, THE FRIENDS OF LAFAYETTE HOUSE and the CITY agree as follows:

1. **Tax Exempt Status.** The CITY recognizes, agrees, and grants to THE FRIENDS OF LAFAYETTE HOUSE that the Property and all improvements located thereon, are currently exempt from taxation under the provisions of RSA 72:23-k based on the current ownership and current use of Property.
2. **Payment in Lieu of Taxes (PILOT).**
 - (a) Commencing on the execution of this agreement, THE FRIENDS OF LAFAYETTE HOUSE shall be obligated to pay the CITY, in lieu of taxes, \$3,500.
 - (b) The PILOT payment shall be payable no later than December 1, 2026.
 - (c) THE FRIENDS OF LAFAYETTE HOUSE shall provide the CITY annually, contemporaneously with payment of the PILOT, an accounting that indicates the detailed calculation of their annual profits and the payment in lieu of taxes.
 - (d) This agreement shall be effective from its date of commencement until and including payment due on December 1, 2026, as long as THE FRIENDS OF LAFAYETTE HOUSE remains exempt from payment of property taxes under RSA 72:23-k, I & II.
 - (e) Nothing in this Agreement shall prevent THE FRIENDS OF LAFAYETTE HOUSE from challenging the CITY's assessment of the real estate or the improvements in accordance with applicable law.
 - (f) If the method of calculating the CITY's tax under RSA 72 is changed, the parties agree to enter into good faith negotiations to amend this Agreement.
3. **Lease of Property by THE FRIENDS OF LAFAYETTE HOUSE to Nonexempt Person or Entity.** In the event that all or a portion of the Property is leased by THE FRIENDS OF LAFAYETTE HOUSE to a person or entity which is not exempt from taxation, such person or entity shall pay taxes on such portion determined by multiplying the tax derived from application of the full tax rate to the assessed value of the Property by a fraction, the numerator of which shall be total square footage of the building constructed on the property (including the tenant's portion of common areas, if any) leased to such

person or entity, and the denominator of which shall be to the total square footage of the building constructed on the Property.

4. **Termination.** Either party may terminate or renegotiate this Agreement by a written instrument agreed to by the parties prior to the December 1, 2026 payment date. If the Property is sold or otherwise disposed of by THE FRIENDS OF LAFAYETTE HOUSE, this Agreement shall terminate on the date of execution of such sale or disposition. If the current use of Property is altered and/or ceases, the CITY may terminate this Agreement at its discretion.
5. **Binding Effect.** This Agreement constitutes the binding agreement of the CITY and THE FRIENDS OF LAFAYETTE HOUSE, and their respective successors and assigns. This Agreement may be modified only by a written instrument agreed to by the parties.
6. **Representation of Authority.**
 - (a) THE FRIENDS OF LAFAYETTE HOUSE represents and warrants that this Agreement is binding upon execution of this Agreement by its duly authorized member.
 - (b) The CITY represents and warrants that this Agreement is binding upon execution by the City Manager of the City after an authorizing vote of the Portsmouth City Council.
7. **Applicable Law.** This Agreement shall be construed and interpreted in accordance with the laws of the State of New Hampshire. The parties consent to the jurisdiction of the Rockingham County Superior Court to resolve any dispute hereunder.
8. **Entire Agreement.** This Agreement constitutes the entire agreement of the CITY and THE FRIENDS OF LAFAYETTE HOUSE regarding the tax-exempt status of THE FRIENDS OF LAFAYETTE HOUSE and the payment in lieu of taxes regarding the Property located at 413 Lafayette Road, Portsmouth, New Hampshire.

Authorization for the City Manager to enter into this Agreement was given by the City Council on October 26, 2026.

IN WITNESS WHEREOF, the parties have executed this Agreement as of the day and date first above written.

CITY OF PORTSMOUTH

Witness

By: _____
Karen S. Conard
City Manager
Duly Authorized

STATE OF NEW HAMPSHIRE
ROCKINGHAM, SS.

The foregoing instrument was acknowledged before me this _____ day of _____, 2026 by Karen S. Conard, City Manager for the City of Portsmouth, New Hampshire, on behalf of the City.

Notary Public
My Commission Expires

THE FRIENDS OF LAFAYETTE HOUSE

Witness

By: _____
Rene Sullivan
Duly Authorized

STATE OF NEW HAMPSHIRE
ROCKINGHAM, SS.

The foregoing instrument was acknowledged before me this _____ day of _____ 2026, by Rene Sullivan, Executive Director, on behalf of THE FRIENDS OF LAFAYETTE HOUSE.

Notary Public
My Commission Expires:



October 5, 2026

Rosann Maurice-Lentz
City Assessor
City of Portsmouth
1 Junkins Avenue
Portsmouth, NH 03801

Re: Request for 2026 Payment in Lieu of Taxes Agreement

Dear Ms. Maurice-Lentz:

Portsmouth Housing Authority serves as the management agent for Betty's Dream Foundation and is coordinating the annual payment in lieu of taxes process on the Foundation's behalf.

On behalf of Betty's Dream Foundation, Portsmouth Housing Authority respectfully requests that the City of Portsmouth approve a payment in lieu of taxes agreement for the property located at 75 Longmeadow Lane, Portsmouth, New Hampshire, pursuant to RSA 72:23-k.

Betty's Dream Foundation requests that the payment in lieu of taxes due December 1, 2026 remain at \$3,000, consistent with the amount accepted by the City in the prior year. A proposed agreement reflecting the requested amount is enclosed for the City's review.

Thank you for your consideration. Please let me know if the City or its legal department requires any revisions or additional information.

Sincerely,

Valerie Labrie

Valerie A. Labrie
Finance Director
Portsmouth Housing Authority
Management Agent for Betty's Dream Foundation

Enclosure: Proposed FY27 Payment in Lieu of Property Tax Agreement



**PAYMENT IN LIEU OF PROPERTY TAX AGREEMENT BETWEEN
THE CITY OF PORTSMOUTH AND BETTY’S DREAM FOUNDATION
(PILOT)**

This Agreement is made as of this _____ day of October, 2026, pursuant to NH RSA 72:23-k, by and between **BETTY’S DREAM FOUNDATION**, having a place of business at 75 Longmeadow Lane, Portsmouth, New Hampshire 03801, and the **CITY OF PORTSMOUTH**, a municipal corporation established under the laws of the State of New Hampshire (the “CITY”), having a place of business at 1 Junkins Avenue, Portsmouth, New Hampshire 03801.

RECITALS

- A. BETTY’S DREAM FOUNDATION is a New Hampshire nonprofit organization that supports a group home for low-income and disabled individuals located at 75 Longmeadow Lane, Portsmouth, New Hampshire 03801 (the “Property”).
- B. Betty’s Dream is a group home for persons with developmental disabilities, with 24 fully accessible apartments and a community room, kitchen, and recreation room.
- C. Betty’s Dream is supported by BETTY’S DREAM FOUNDATION, a tax-exempt charitable nonprofit under Section 501(c)(3) of the Internal Revenue Code. The income and profits of BETTY’S DREAM FOUNDATION are used solely for community housing purposes.
- D. RSA 72:23-k defines the property to which the charitable, nonprofit housing project property tax exemption applies and is supplemented by the New Hampshire Code of Administrative Rules.
- E. The CITY recognizes that, as presently constituted, BETTY’S DREAM and the Property satisfy the requirements of these laws and are therefore entitled to a property tax exemption pursuant to RSA 72:23-k.
- F. Pursuant to RSA 72:23-k, II, BETTY’S DREAM FOUNDATION shall make a payment in lieu of taxes in the amount of \$3,000 for the payment due December 1, 2026.
- G. The CITY is willing to recognize and grant to BETTY’S DREAM FOUNDATION an exemption from taxation and accept a payment in lieu of taxes by BETTY’S DREAM FOUNDATION, as set forth in this Agreement, based on the current ownership and current use of the Property.

WHEREFORE, based upon the mutual covenants and promises contained herein, and for other good and valuable consideration, the receipt and sufficiency of which the parties acknowledge, BETTY’S DREAM FOUNDATION and the CITY agree as follows:

1. Tax-Exempt Status. The CITY recognizes and agrees that the Property and all improvements located thereon are currently exempt from taxation under RSA 72:23-k based on the current ownership and current use of the Property.

2. Payment in Lieu of Taxes.

- (a) Upon execution of this Agreement, BETTY'S DREAM FOUNDATION shall be obligated to pay the CITY \$3,000 in lieu of taxes.
- (b) The payment in lieu of taxes shall be payable on or before December 1, 2026.
- (c) BETTY'S DREAM FOUNDATION shall provide the CITY annually with an accounting that indicates the detailed calculation supporting the payment in lieu of taxes.
- (d) This Agreement shall be effective from its date of commencement through and including the payment due December 1, 2026, so long as BETTY'S DREAM FOUNDATION remains exempt from property taxation under RSA 72:23-k, I and II.
- (e) Nothing in this Agreement shall prevent BETTY'S DREAM FOUNDATION from challenging the CITY's assessment of the real estate or improvements in accordance with applicable law.

3. Termination. Either party may terminate or renegotiate this Agreement by a written instrument agreed to by the parties prior to the December 1, 2026 payment date. If the Property is sold or otherwise disposed of by BETTY'S DREAM FOUNDATION, this Agreement shall terminate on the date of that sale or disposition. If the current use of the Property is altered or ceases, the CITY may terminate this Agreement at its discretion.

4. Binding Effect. This Agreement constitutes the binding agreement of the CITY and BETTY'S DREAM FOUNDATION and their respective successors and assigns. This Agreement may be modified only by a written instrument agreed to by the parties.

5. Representation of Authority.

- (a) BETTY'S DREAM FOUNDATION represents and warrants that this Agreement is binding upon execution by its duly authorized representative.
- (b) The CITY represents and warrants that this Agreement is binding upon execution by the City Manager after an authorizing vote of the Portsmouth City Council.

- 6. Applicable Law.** This Agreement shall be construed and interpreted in accordance with the laws of the State of New Hampshire. The parties consent to the jurisdiction of the Rockingham County Superior Court to resolve any dispute arising under this Agreement.
- 7. Entire Agreement.** This Agreement constitutes the entire agreement of the CITY and BETTY'S DREAM FOUNDATION regarding the tax-exempt status of BETTY'S DREAM FOUNDATION and the payment in lieu of taxes for the Property located at 75 Longmeadow Lane, Portsmouth, New Hampshire.

Authorization for the City Manager to enter into this Agreement was given by the City Council on October 26, 2026.

IN WITNESS WHEREOF, the parties have executed this Agreement as of the day and date first written above.

CITY OF PORTSMOUTH

Witness

By: _____
Karen S. Conard
City Manager
Duly Authorized

STATE OF NEW HAMPSHIRE
ROCKINGHAM, SS.

The foregoing instrument was acknowledged before me this _____ day of _____, 2026
by _____, on behalf of CITY OF PORTSMOUTH.

Notary Public
My Commission Expires: _____

BETTY'S DREAM FOUNDATION

Witness

STATE OF NEW HAMPSHIRE
ROCKINGHAM, SS.

By: _____
Curtis Hermann, Chair
Board of Directors

The foregoing instrument was acknowledged before me this _____ day of _____, 2026
by _____, on behalf of BETTY'S DREAM FOUNDATION.

Notary Public

My Commission Expires: _____



City of Portsmouth

Planning & Sustainability

Memorandum

TO: Karen Conard, City Manager

FROM: Peter Stith, AICP, Assistant Planning Director

DATE: October 19, 2026

SUBJECT: Planning Board recommendation regarding licenses and a sidewalk easement for 361 Hanover Street

On August 28, 2025, the Planning Board granted site plan and subdivision approval for four new residential buildings and the conversion of the existing building to residential use. As part of that approval, the Planning Board recommended that the City accept an easement for the portion of the City sidewalk located on the property. The Public Works and Planning Departments recommend accepting the sidewalk easement, and the Legal Department has reviewed the easement as to form.

In addition to the sidewalk easement, the applicant has requested approval of a landscape and maintenance license over portions of City-owned property adjacent to the redevelopment project, as well as a license for the installation of utility infrastructure associated with a new Eversource transformer. The request was referred to the Planning Board for a recommendation.


The sidewalk easement, landscape license, and pole license are each shown on the depiction included in the agenda packet.

The Department of Public Works and the Legal Department reviewed the proposal and recommended that the City grant: (1) a 50-year landscape and maintenance license for designated City-owned areas adjacent to the project; and (2) a pole license authorizing Eversource to install and maintain a pad-mounted transformer and associated conduit on City-owned property to serve the development. Under the proposed landscape license, the property owner would beautify and maintain the licensed areas and maintain the existing retaining wall on the landlocked portion of the site. In exchange for receiving the landscape license, the property owner would also be responsible for replacing the retaining wall when required, based on an assessment by a licensed professional engineer.

At its October 15, 2026 meeting, the Planning Board voted unanimously to recommend that the City Council approve the landscape and pole licenses, subject to the recommendations in the Department of Public Works' October 7, 2026 memorandum and the two modifications described below.


1. Amend the second bullet under Item 1 to require the owner to "**maintain the existing retaining wall during the license period and replace if necessary.**"
2. Add the following condition:

"The City may request at any time an analysis by a licensed professional engineer to assess the lifespan of the wall and the need for replacement at the owner's expense."



Legend

- Proposed Electrical Service
- Proposed Transformer
- Proposed Sidewalk Easement
- Proposed Landscape License Application



361 Hanover Street Proposed Easements and License Applications




THE PORTSMOUTH BOARD OF FIRE COMMISSIONERS
And
PORTSMOUTH PROFESSIONAL FIRE OFFICERS ASSOCIATION
LOCAL#4039

MEMORANDUM OF AGREEMENT

1. The Portsmouth Board of Fire Commissioners ("the City") and The Portsmouth Professional Fire Officers Association, Local #4039 ("the Union") are currently parties to a collective bargaining agreement that expired on June 30, 2026 ("the CBA"), but the provisions of the CBA are still in effect.
2. The City and the Union hereby agree to allow for a temporary amendment to Section V.4. (Wages, Insurance Benefits, Defense/Indemnification, And Longevity Bonus) of the current CBA to allow for the following:
 - Effective August 17, 2026, Lieutenant Timothy Cole shall be placed at the 24 Months Step of the Lieutenant Salary Schedule.
3. Following initial placement at the 24 Months Step, Lieutenant Timothy Cole shall progress through subsequent Lieutenant pay steps on the normal schedule as set forth in Section V of the CBA, with their next step increases occurring twelve months from his promotion dates.
4. This Agreement is a limited, one-time remedy. It shall not constitute a past practice, bind either Party in any grievance or arbitration proceeding, or serve as precedent for any other employee or any provision in successor contract negotiations.
5. All other provisions of the CBA will remain in effect.

Dated :


10/14/26



Portsmouth Board of Fire Commissioners

Dated:

Oct. 15, 2026



Portsmouth Professional Fire Officers Association Local 4039

Approved by City Council _____



City of Portsmouth

Planning & Sustainability

Memorandum

TO: Karen Conard, City Manager

FROM: Peter Stith, AICP, Assistant Planning Director

DATE: October 19, 2026

SUBJECT: Planning Board Recommendation on Cornwall Street

The City Council referred a request to discontinue a portion of Cornwall Street to the Planning Board for review and recommendation.

The proposed discontinuance involves an identified portion of the public right-of-way. During its review, the Planning Board considered the presence of existing municipal infrastructure within the area proposed for discontinuance and the relationship of the affected parcels to the City's tax mapping.

At its October 15, 2026 meeting, the Planning Board voted unanimously to recommend that the City Council approve the discontinuance of the identified portion of Cornwall Street, subject to the following conditions:

1. Recording of a municipal utility easement over the existing sewer line in a form acceptable to the City Attorney.
2. The City Council request a voluntary lot merger to align the parcel boundaries with the configuration shown on the City's tax map.



Trevor P. McCourt
Deputy City Attorney

CITY OF PORTSMOUTH

Legal Department
Municipal Complex
1 Junkins Avenue
Portsmouth, New Hampshire 03801
tmccourt@portsmouthnh.gov
(603) 610-7234

May 19, 2026

Rick Chellman, Chair
Portsmouth Planning Board

VIA EMAIL ONLY

Re: 94 Langdon Street (LU-25-175)
Cornwall Street Right of Way

Dear Chair Chellman:

Introduction

Planning Staff have asked me to review the history of the Cornwall Street right of way extending to the north of McDonough Street. The applicant for the above-cited land use application represents that the City may not have any rights to Cornwall Street north of McDonough Street, and does not have rights to McDonough Street crossing 94 Langdon Street (the "Property") to the railroad. Based on my research, which is described below, I believe that (1) Cornwall Street is a public right of way extending from Islington Street through to the railroad and (2) therefore, in order for the present application to proceed, a formal discontinuance of a portion of Cornwall Street by the City Council is necessary.

The central issue is whether Cornwall Street, as it was created, crosses the Property, and if so, whether it was ever discontinued by the City Council. If not, the right of way bifurcates the parcel as presented, and the current proposal cannot proceed in its present form.

This review was prompted by a review of Note 11 on the Existing Conditions Plan prepared by Haley Ward, which suggests that City action in 1965 may have released rights in the portion of Cornwall Street that previously crossed the property, together with an offer to convey an easement for existing sewer infrastructure in exchange for release of any remaining City rights in that area.

Factual Background

In response to the request of Planning staff, I conducted preliminary research into the history of Cornwall Street. The materials reviewed to date appear to provide substantial evidence that Cornwall Street was dedicated to public use, constructed and therefore accepted by the City, and that no formal discontinuance has been identified for the portion extending north of McDonough Street to the railroad property.

Attached are two plans depicting historical conditions on Cornwall Street. The first is a portion of the subdivision map by which Cornwall Street was dedicated and put to public use. The map is dated 1815 and was recorded at the Rockingham County Registry of Deeds in Book 321, Page 1, on November 10, 1845 (the “1815 Plan”). In relevant part, the plan depicts Cornwall Street extending from the northerly sideline of Islington Street through to the North Mill Pond.

The second attached plan is a right-of-way drawing prepared by the Boston and Maine Railroad Company, dated June 30, 1914 (the “1914 Plan”). Upon information and belief, between the time of the recordation of the 1815 Plan and the 1914 Plan, the railroad took by eminent domain property along the North Mill Pond. The 1914 Plan shows the location of the railroad relative to the North Mill Pond and to Cornwall Street. It indicates that, as of 1914, Cornwall Street extended from the northerly edge of McDonough Street to the edge of what remains railroad property today. The plan also depicts buildings constructed on parcels fronting Cornwall Street north of McDonough Street.

Taken together, these plans appear to show that Cornwall Street was dedicated and laid out from Islington Street to the railroad parcel. I also located materials in the Planning Department’s files indicating that, as of July 1965, the Planning and Assessing Departments were unable to identify any City action discontinuing the portion of Cornwall Street north of McDonough Street. Consistent with that information, I reviewed City Council meeting minutes from 1965 and 1966 and did not locate any reference to a discontinuance of Cornwall Street.

Applicable Law

A street may be created either by express act or by implication. Hersh v. Plonski, 156 N.H. 511 (2007). Once public rights of way are established, those rights continue indefinitely unless they are formally discontinued by public action. Blagbrough Family Realty Trust v. A & T Forest Products, Inc., 155 N.H. 29 (2007). Highways cannot be extinguished by adverse possession. Williams v. Babcock, 116 N.H. 819 (1976). Moreover, there is a strong presumption against discontinuance. Davenhall v. Cameron, 116 N.H. 695 (1976). As the Court explained in Davenhall, “highway discontinuance is not favored in the law . . . and the burden is upon the party who asserts discontinuance to prove it by clear and satisfactory evidence.” Id. at 697.

Analysis

Applied here, there is evidence that Cornwall Street was dedicated to public use through recordation of the subdivision plan in 1815. There is also evidence of acceptance of the full extent of Cornwall Street, including the portion north of McDonough Street extending at least to the railroad property. Additional support is provided by the public sewer line running beneath Cornwall Street from McDonough Street to the railroad property. The Haley Ward survey notes that this sewer line may be quite old, as it is constructed of brick.

By contrast, no evidence has been identified showing the discontinuance of any portion of Cornwall Street. As noted above, the City records I have reviewed to date would indicate that no discontinuance occurred at least as recently as 1966.

Taken together, this information and legal presumptions described above lead to a presumption that the City still holds a right of way interest in Cornwall Street from Islington Street through to the railroad property. Additional evidence may yet exist, and a discontinuance could still be pursued prospectively if appropriate. At present, however, the applicant bears the burden of proving discontinuance. Accordingly, unless and until competent evidence of discontinuance is presented, the Board should proceed on the basis that public rights in this portion of Cornwall Street may still exist.


If so, the parcel is bifurcated, and the proposal, as currently presented, cannot go forward. Should the applicant wish to pursue the project in that circumstance, the proper course is to seek discontinuance through the required public process, including notice to abutters, a public hearing, Planning Board recommendation, and City Council action.


Sincerely,

A handwritten signature in black ink, appearing to read 'Trevor P. McCourt', written over a horizontal line.

Trevor P. McCourt
Deputy City Attorney

cc: Peter Pritz, Director of Planning and Sustainability
Peter Stith, Planning Manager





RIGHT-OF-WAY AND TRACK MAP
BOSTON AND MAINE R.R.
Operated by the
BOSTON AND MAINE R.R.
STATION 2966+20 TO STATION 3018+0
JUN 1922
Office of Valuation Engineer
Boston, Mass.

HOEFLE, PHOENIX, GORMLEY & ROBERTS, PLLC

ATTORNEYS AT LAW

127 Parrott Avenue | Portsmouth, NH, 03801
Telephone: 603.436.0666 | Facsimile: 603.431.0879 | www.hpgirlaw.com

August 18, 2026

The Honorable Mayor Deaglan McEachern
Portsmouth City Council
1 Junkins Avenue
Portsmouth, NH 03801

**RE: Petition for Discontinuance of Abandoned Portion of Cornwall Street Pursuant to
NH RSA 231:43**

Dear Mayor McEachern and City Council Members:

This office represents Regan Electric Company, Inc. ("Regan Electric"), owner of real property located at 98 Cornwall Street (Tax Map 139, Lot 1) ("98 Cornwall"). Please accept this submission as Regan Electric's petition pursuant to RSA 231:43 to discontinue the abandoned portion of Cornwall Street, consisting of 2,340 S.F., that crosses 98 Cornwall and ends at land of the Boston and Maine Corporation (the Railroad). In support, Regan Electric states as follows.

Background

Cornwall Street was dedicated in 1845 by the recording of a subdivision plan (dated 1815) and was used as a public street to access residential structures on what is now 98 Cornwall from the late 1800's through the 1930's. As laid out, Cornwall Street ends at the northern property line of 98 Cornwall, where it abuts the Railroad, which was originally the southern shore of the North Mill Pond.

In the 1930's Portsmouth Ice and Coal Co., Inc. ("Portsmouth Ice & Coal") acquired the individual lots making up 98 Cornwall and removed the residential structures and blocked off Cornwall Street and began using 98 Cornwall to distribute ice and coal. In 1951, the Receiver for Portsmouth Ice & Coal sold 98 Cornwall to Charles H. Walker and the property was operated by the C.B. Walker Co. as a coal distribution facility. During the 1950's, the existing coal shed was

DANIEL C. HOEFLE	ALEC L. MCEACHERN	PETER V. DOYLE	MATTHEW J. COWAN
R. TIMOTHY PHOENIX	KEVIN M. BAUM	MONICA F. KIESER	STEPHEN H. ROBERTS In Memoriam
LAWRENCE B. GORMLEY	JACOB J.B. MARVELLEY	CHRISTOPHER P. MULLIGAN	OF COUNSEL:
R. PETER TAYLOR	GREGORY D. ROBBINS	STEPHANIE J. JOHNSON	SAMUEL REID

extended across the width of Cornwall Street, physically obstructing entry to 98 Cornwall. This coal shed was removed in the late 1970's, leaving a concrete pad and retaining wall in place. In 1980, Charles H. Walker sold 98 Cornwall and after several intervening owners Regan Electric purchased it in 1992.

Cornwell Street has not physically existed on 98 Cornwall for approximately 90 years and there is no visible evidence of it today. Under RSA 229:5, VII, the portion of Cornwall Street located on 98 Cornwall was rendered a Class VI road, based on the City not maintaining and repairing it in suitable condition for travel for a period of 5 successive years or more. The City's tax maps do not show Cornwall Street as being located on 98 Cornwall and Regan Electric has always paid property taxes on the Cornwall Street land located on 98 Cornwall, as if it owned the fee title.

Supporting Exhibits

Based upon our review of relevant title records, Cornwall Street and the surrounding lots were created (and the roadways dedicated) pursuant to a plan entitled "Plan of the Rock Field in the Town of Portsmouth," prepared by Benjamin Akerman, dated 1815, and recorded in the Rockingham County Registry of Deeds as Plan 00562 on November 10, 1845 (the "1815 Plan"). Exhibit 1. The 1815 Plan shows Cornwall Street extending to the shore of Islington Creek, a body of water now known as the North Mill Pond, and the 98 Cornwall property as consisting of approximately seven separate lots. Id. Also attached is a Certified Sanborn Map report showing the history of 98 Cornwall over time from 1887 through 1980 (the "Sanborn Maps"). Exhibit 2. The 1949 Sanborn Map shows that the buildings that had fronted Cornwall Street on the 1920 Sanborn Map had been removed, and the separate lots merged into one parcel, as it exists today, with a coal shed partially obstructing the path of Cornwall Street. Exhibit 2 at p. 5. The title history suggests the section of Cornwall Street located on 98 Cornwall was abandoned between 1930 and 1940 when Portsmouth Ice & Coal acquired ownership of the 98 Cornwall lots, resulting in the configuration shown on the 1949 Sanborn Fire Map (Exhibit 2 at p. 5). After 1949, the Sanborn Maps show Cornwall Street ending at 98 Cornwall's property line, with the coal shed extending across the entire width of Cornwall Street until its removal in the late 1970's. Exhibit 2. Today, the City's Tax Map (Exhibit 3) and GIS Map (Exhibit 4) both show Cornwall Street stopping at 98 Cornwall's property line, rather than continuing through that property to what is now the Railroad, as shown on the 1815 Plan.

The portion of Cornwall Street bisecting Regan Electric's Property cannot be used as a public way in its current condition. Photos of the area indicate that mature trees, shrubs, and other greenery have grown into the untraveled portion of Cornwall Street. (Exhibit 5). In addition, the Draft Street Discontinuance Plan prepared in support of Regan Electric's request shows a chain

link fence and a concrete retaining wall from the old coal shed, spanning across Cornwall Street at 98 Cornwall's property line. (Exhibit 6).

Justification

While Cornwall Street is a Class V road, the portion of Cornwall Street located on 98 Cornwall has not been maintained and repaired by the City of Portsmouth in suitable condition for travel for a period exceeding five years, rendering it a Class VI road pursuant to RSA 229:5, VII. As indicated on the attached exhibits, it is unlikely that this abandoned section of Cornwall Street will ever be improved for use as a public street because it would go nowhere and serve no one. Under RSA 231:43, the unused section of Cornwall Street contained within Regan Electric's Property can be discontinued by City vote. Discontinuance will be consistent with the City's maps, its tax assessments, and Regan Electric's use of its property and will cause no harm or prejudice to the City or its citizens. Any physical extension of Cornwall Street beyond the existing constructed portion would serve no public purpose and no lots require access to this unused portion of Cornwall Street for ingress or egress.

Requested Relief

Regan Electric requests the City Council vote to discontinue the abandoned portion of Cornwall Street located on 98 Cornwall Street, as shown on the Street Discontinuance Plan, subject to the City's continued right to maintain the existing sewer line passing through 98 Cornwall, as expressly provided for in RSA 231:46.


Accordingly, Regan Electric respectfully request that the City Council formally vote to:

- a. Release any and all right, title, and interest of the City in and to the abandoned portion of Cornwall Street beginning at an iron rod found at the southeasterly corner of Tax Map 139, Lot 1 thence South 57°02'43" West a distance of 38.92' to an iron rod, thence turning and running North 33°43'00" West a distance of 74.02' to an iron rod, thence turning and running North 42°03'55" East a distance of 30.95' to an iron rod, thence turning and running South 33°43'00" East a distance of 82' to the point of beginning, being a total of 2,340 s.f.; and
- b. That any such release be made subject to the retention of a sewer easement for the benefit of the City for any existing public utilities within the released area.¹

¹ The Street Discontinuance Plan shows a small portion of an existing public sewer line running through the unused portion of Cornwall Street. Regan Electric proposes reservation of a 20' sewer easement to provide the City access to the sewer line for maintenance and repairs.

Please do not hesitate to contact me for any additional information or if anything further is needed to complete the requested release. Thank you for your time and attention to this request.

Sincerely,



Stephanie J. Johnson

cc: Regan Electric
Attorney Trevor McCourt

Enclosures: Exhibit 1 – 1815 Plan
Exhibit 2 – Certified Sanborn® Map Report
Exhibit 3 – Tax Map 139
Exhibit 4 – GIS Map
Exhibit 5 – Google Earth Site Photos
Exhibit 6 – Street Discontinuance Plan




EXHIBIT 1

Regan Electric
94 Langdon Street
Portsmouth, NH 03801

Inquiry Number: 8162072.3

November 04, 2025

Certified Sanborn® Map Report



8 Armstrong Road, 4th floor
Shelton, CT 06484
Toll Free: 800.352.0050
www.edrnet.com




Site Name: Regan Shingle
Address: 84 Langdon Street
City, ST, ZIP: Portsmouth, NH 03801
Client: Exeter Environmental Assoc., LLC
EDR Inquiry: 8162072-3
Order Date: 11/04/2025
Certification: 08EA-4ADB-8BB6
Copyright: 1980



Certified Sanborn® Map


1980



This Certified Sanborn Map is a reproduction of the original map as published by the Sanborn Fire Insurance Company. It is not to be used for any purpose other than as a reference. The Sanborn Fire Insurance Company is not responsible for any errors or omissions in this map. The Sanborn Fire Insurance Company is not responsible for any damages or losses resulting from the use of this map. The Sanborn Fire Insurance Company is not responsible for any claims or liabilities resulting from the use of this map. The Sanborn Fire Insurance Company is not responsible for any claims or liabilities resulting from the use of this map.

Certification # 08EA-4ADB-8BB6

This Certified Sanborn Map combines the following sheets.
Outlined areas indicate map sheets within the collection.



Volume 1, Sheet 5
Volume 1, Sheet 4

0 Feet 150 300 600






Site Name: Ringier Building
Address: 64 Exchange Street
City, ST, ZIP: Portsmouth, NH 03801
Client: Exeter Environmental Assoc., LLC
EDR Project: 8162072-3
Order Date: 11/04/2025
Certification: 08EA-4ADB-8BB6
Copyright: 1975



Certified Sanborn® Map


1975



The Certified Sanborn Map is a reproduction of the original map as published by the Sanborn Fire Insurance Company. It is not a substitute for a current map. The Sanborn Fire Insurance Company is not responsible for any errors or omissions in this reproduction. The Sanborn Fire Insurance Company is not responsible for any damages or losses resulting from the use of this reproduction. The Sanborn Fire Insurance Company is not responsible for any claims or liabilities resulting from the use of this reproduction. The Sanborn Fire Insurance Company is not responsible for any claims or liabilities resulting from the use of this reproduction.

Certification #08EA-4ADB-8BB6

This Certified Sanborn Map combines the following sheets.
Outlined areas indicate map sheets within the collection.



Volume 1, Sheet 4
Volume 1, Sheet 5

0 Feet 150 300 600






Certified Sanborn® Map

1956


Site Name: Egan Electric
Address: 94 Langdon Street
City, ST, ZIP: Portsmouth, NH 03801
Client: Egan Environmental Assoc., LLC
EDR Inquiry: 8162072.3
Order Date: 11/07/2025
Certification: 08EA-4ADB-88B6
Copyright: 1956



This Certified Sanborn Map is a reproduction of the original map. The original map was prepared by the Sanborn Map Company, Inc. (SDC) and is a copyrighted work. The SDC is not responsible for any errors or omissions in this reproduction. The SDC is not responsible for any damages or liabilities arising from the use of this reproduction. The SDC is not responsible for any claims or damages arising from the use of this reproduction. The SDC is not responsible for any claims or damages arising from the use of this reproduction.

Certification #08EA-4ADB-88B6

This Certified Sanborn Map combines the following sheets.
Outlined areas indicate map sheets within the collection.



Volume 1, Sheet 5
Volume 1, Sheet 4






Certified Sanborn® Map

1949


Sanborn: Region 1000
Address: 84 Leighton Street
City, ST, ZIP: Portsmouth, NH 03801
Client: Exeter Environmental Assoc., LLC
EDR Inquiry: 8162072.3
Order Date: 11/04/2023
Certification #: 08BA-4ADB-88B6
Copyright: 1949



The certified Sanborn Library search results in this report can be authenticated by visiting www.edr.com/sanborn and entering the certification number. Only Environmental Data Resources Inc. (EDR) is authorized to grant rights for commercial reproduction of maps by The Sanborn Library LLC, the copyright holder for the collection.

Certification #08BA-4ADB-88B6

This Certified Sanborn Map combines the following sheets.
Outlined areas indicate map sheets within the collection.




Volume 1, Sheet 4
Volume 1, Sheet 5



Certified Sanborn® Map

1920


Site Name: Regen Electric
Address: 241 Langdon Blvd
City, ST, ZIP: Portsmouth, NH 02801
Client: Eater Environmental Assoc., LLC
EDR Inquiry: 8162072.3
Order Date: 11/01/2022
Certification: 08EA-4ADB-8BB6
Copyright: 1920



The certified Sanborn Library search results in this report can be authenticated by visiting www.edr.com/sanborn and entering the certification number. Only Environmental Data Resources Inc. (EDR) is authorized to grant rights for commercial reproduction of maps by The Sanborn Library LLC, the copyright holder for the collection.

Certification #08EA-4ADB-8BB6

This Certified Sanborn Map combines the following sheets.
Outlined areas indicate map sheets within the collection.



Volume 1, Sheet 5
Volume 1, Sheet 4






Map Data: ESRI
Source: ESRI
Map ID: 1000000000
Scale: 1:250,000
Date: 1/1/2000
Copyright: ESRI
Product: ESRI




Certified Sanborn® Map

1910



This Certified Sanborn Map combines the following sheets.
Outlined areas indicate map sheets within the collection.



Volume 1, Sheet 3
Volume 1, Sheet 4


8162072 v. 3 page 11



Certified Sanborn® Map

1904


Site Name: **Maple Heights**
Address: **64 Langdon Street**
City, ST, ZIP: **Portsmouth, NH 03801**
Client: **Eastco Environmental Assoc., LLC**
EDR Inquiry: **8162072.3**
Order Date: **11/04/2025**
Certification: **00EA-4ADB-8BB6**
Copyright: **1904**



This certified Sanborn map search results in this report can be authorized by visiting www.edr.com/sanborn and entering the certification number. Only Environmental Data Response Inc. (EDR) is authorized to grant rights for commercial reproduction of maps by The Sanborn Library LLC. The copyright notice for the collection.

Certification #00EA-4ADB-8BB6

This Certified Sanborn Map combines the following sheets.
Outlined areas indicate map sheets within the collection.



Volume 1, Sheet 5
Volume 1, Sheet 4

0 Feet 150 300 600




8162072 - 3 page 12



Certified Sanborn® Map

1898



Site Name: Regan (School)
Address: 64 Langdon Street
City, ST, ZIP: Portsmouth, NH 03801
Client: Regan Environmental Assoc., LLC
EDR Inquiry: 8162072.3
Order Date: 11/04/2025
Certification: 08EA-4ADB-8BB6
Copyright: 1898



This Certified Sanborn Map is a reproduction of the original map as published by the Sanborn Map Company. It is not a substitute for a current map. The Sanborn Map Company is not responsible for any errors or omissions in this reproduction. The Sanborn Map Company is not responsible for any damages or losses resulting from the use of this reproduction. The Sanborn Map Company is not responsible for any claims or liabilities resulting from the use of this reproduction. The Sanborn Map Company is not responsible for any claims or liabilities resulting from the use of this reproduction.

Certification # 08EA-4ADB-8BB6

This Certified Sanborn Map combines the following sheets.
Outlined areas indicate map sheets within the collection.



Volume 1, Sheet 12
Volume 1, Sheet 14




Site Name: *Superfund*
Address: 55 Langdon Street
City, ST, ZIP: Haverhill, NH 03041
Client: Eater Environmental Assoc., LLC
EDR Inquiry: 8162072-3
Order Date: 1/15/2013
Order Number: 00004-4AD8-8BB6
Copyright: 1987



Certified Sanborn® Map

1887



This Certified Sanborn Map combines the following sheets.
Outlined areas indicate map sheets within the collection.

0 Feet 150 300 600



Volume 1, Sheet 8

8162072 - 3 page 16




**MAP FOR REFERENCE ONLY
NOT A LEGAL DOCUMENT**

City of Portsmouth, NH makes no claims and no warranties, expressed or implied, concerning the validity or accuracy of the GIS data presented in this map.

Geometry updated 03/05/2025

Print map scale is approximate. Critical layout or measurement activities should not be done using this resource.





**MAP FOR REFERENCE ONLY
NOT A LEGAL DOCUMENT**

City of Portsmouth, NH makes no claims and no warranties, expressed or implied, concerning the validity or accuracy of the GIS data presented on this map.

Geometry updated 03/06/2026

Print map scale is approximate. Critical layout or measurement activities should not be done using this resource.



99 Cornwall St
Portsmouth, New Hampshire



Google

Google

100%

[Data attribution](#)

Sep 2011



101 Langdon St
Portsmouth, New Hampshire



Google

Google

0%

[Data attribution](#)

Nov 2024

File Edit View Add Tools Help

98 Cornwall Street, Portsmouth, NH




Google 100%

File Edit View Add Tools Help



98 Cornwall Street, Portsmouth, I




Google

100%

NOTES:

1. PARCEL IS SHOWN ON THE CITY OF PORTSMOUTH ASSESSORS' MAP 130 AS BEING A PORTION OF LOT 1.
2. OWNER OF RECORD:
HESON ELECTRIC COMPANY, INC.
34 LINDEN STREET
PORTSMOUTH, NH 02870
355/5372 X 2666/379
3. EXISTING EASEMENT/ENCUMBRANCE AREA:
0.346 ACRES
4. THE PURPOSE OF THIS PLAN IS TO SHOW THE PORTION OF CORNVALL STREET TO BE DEDICATED BY THE CITY OF PORTSMOUTH AS SHOWN ON ASSESSORS' MAP 130 IN THE CITY OF PORTSMOUTH.
5. ADJUTER INFORMATION TAKEN FROM THE CITY OF PORTSMOUTH ASSESSORS' GRS WEBSITE.
6. ADJUTER BUILDING LOCATIONS SHOWN HEREIN SHOULD BE CONSIDERED APPROXIMATE.
7. THE YEARS OF ADJUTERMENT VARIATES DATED 2012 TO 1960 TO ALLOW CONSTRUCTION OF A GARAGE.

ALL IMPROVED EQUIPMENT WILL BE 10' AWAY AND 12' ON EITHER SIDE OF THE EXISTING 12' WIDE SIDEWALK. THE LOCATION SHOWN HEREIN SHOULD BE CONSIDERED APPROXIMATE AND WILL BE VERIFIED IN THE FIELD DURING THE TIME OF CONSTRUCTION.



0	07/30/20	ISSUED FOR COMMENT	PAY	CSA
REV.	DATE	DESCRIPTION	BY	CHK.
OWNER: REGAN ELECTRIC COMPANY, INC.				

STREET DISCONTINUANCE
PLAN
PORTION OF CORNWALL STREET
PREPARED FOR:
THE CITY OF PORTSMOUTH
1 JUNKINS AVENUE
CITY OF PORTSMOUTH
COUNTY OF ROCKINGHAM
STATE OF NEW HAMPSHIRE

SCALE: 1"=10'		JULY 2026	
FB 443 & PG 17		5010672.001	



City of Portsmouth

Planning & Sustainability

Memorandum

TO: Karen Conard, City Manager

FROM: Peter Stith, AICP, Assistant Planning Director

DATE: October 19, 2026

SUBJECT: Planning Board Recommendation on Taft Road

The City Council referred a request to discontinue a portion of Taft Road to the Planning Board for review and recommendation.

The proposed discontinuance involves an identified portion containing existing municipal infrastructure. During its review, the Planning Board considered the need to preserve municipal access and rights associated with the existing public water infrastructure.

At its October 15, 2026 meeting, the Planning Board voted unanimously to recommend that the City Council approve the discontinuance of the identified portion of Taft Road, subject to the following condition:

1. Recording of a municipal utility easement over the existing water line in a form acceptable to the City Attorney.



Trevor P. McCourt
Deputy City Attorney

CITY OF PORTSMOUTH

Legal Department
Municipal Complex
1 Junkins Avenue
Portsmouth, New Hampshire 03801
tmccourt@portsmouthnh.gov
(603) 610-7234

Date: October 8, 2026

To: Peter Stith, Assistant Planning Director


From: Trevor P. McCourt, Deputy City Attorney

Re: 20 Taft Road
Paper Street Release Request

On August 20, 2026, Shannon Harrington and her husband, James St. Pierre, jointly wrote to the City Clerk requesting the release of the paper street along the northerly boundary of the property at 20 Taft Road (Assessor's Map 268, Lot 91), which Mrs. Harrington owns. Mrs. Harrington and Mr. St. Pierre report that they have consulted with the owners of the neighboring property at 22 Taft Road (Assessor's Map 268, Lot 90), who agree that the paper street should be divided equally between the two properties.

The paper street was dedicated to public use through the recordation of a subdivision plan titled "Plan Number One of Lots, Elwyn Park," dated October 1972 and recorded at the Rockingham County Registry of Deeds as Plan No. D-3407. The plan labels the street affecting the subject parcel as "proposed street." The City never formally accepted or opened the proposed street for public use. A City sewer lateral serving Dondero Elementary School passes through a portion of the proposed street.

The Legal, Planning and Sustainability, and Public Works Departments support releasing the City's interest in the paper street, provided that the property owners grant the City an easement protecting the existing sewer lateral serving Dondero Elementary School. As a condition of the release, the property owners should obtain, at their expense, a surveyed plan depicting both the limits of the paper street interest to be extinguished and the proposed sewer easement area. No surveyed plan has yet been prepared. The aerial photograph below shows the subject parcels and the paper street running between them.



cc:



City of Portsmouth

Planning & Sustainability

Memorandum

TO: Karen Conard, City Manager

FROM: Peter Stith, AICP, Assistant Planning Director

DATE: October 19, 2026

SUBJECT: Planning Board Recommendation on 0 Elm Street

The City Council referred a request concerning 0 Elm Street (Tax Map 210, Lot 15) to the Planning Board pursuant to RSA 674:41, I(d). The request seeks authorization for the issuance of a building permit on a lot that is proposed to be served by access over the unconstructed Forrest Street paper street. Under RSA 674:41, the City Council must obtain review and comment from the Planning Board before acting on such a request.

At its October 15, 2026 meeting, the Planning Board reviewed the request and discussed the unique circumstances of the parcel, including access considerations, emergency services access, and the physical constraints associated with the property. The Board noted that no constructed roadway presently provides access to the lot and that additional review by City departments would be beneficial in evaluating the feasibility of future development.

Following its review, the Board voted to recommend that the parcel may have an opportunity to accommodate a single-family dwelling and further recommended that additional review be obtained from the Fire Department and Department of Public Works regarding emergency access, sight distance, public safety, and utility considerations.

Staff notes that any action by the City Council under RSA 674:41 relates only to the issue of access and eligibility for issuance of a building permit under state law. Council approval does not constitute development approval and does not guarantee that the parcel is buildable under the City's land use regulations.

As noted in the legal memorandum presented to the Planning Board, the parcel is undersized and may require one or more variances from the Zoning Board of Adjustment. In addition, the property is located within the Highway Noise Overlay

District, and construction of a dwelling would require approval of a Conditional Use Permit from the Planning Board. Issuance of any building permit would remain contingent upon obtaining all required variances, conditional use permit approval, and any other applicable local, state, or federal permits and approvals.

COLBY T. GAMESTER

Attorney At Law

154 Maplewood Avenue
Portsmouth, New Hampshire 03801

(603)-427-0000
colby@gamesterlaw.com

July 29, 2026

HAND DELIVERED & VIA EMAIL

Portsmouth City Council
Attn: Deaglan McEachern, Mayor
c/o Portsmouth City Clerk
1 Junkins Avenue
Portsmouth, NH 03801
cityclerk@portsmouthnh.gov

Re: 0 Elm Street (Tax Map 210, Lot 15)
Request pursuant to RSA 674:41, I(d)
Access via private drive

Dear Mayor McEachern and Members of the City Council:

I represent Stephanie Crepeau ("Client") who is currently under contract to purchase real property located at 0 Elm Street, also known as Lot 15 on City of Portsmouth Tax Map 210 (the "Property"). Enclosed herewith is a Landowner Letter of Authorization executed by the current owner of the Property, Andrew Wolcott.

Please accept this letter to the City Council requesting that it authorize the issuance of a building permit for the construction of a single-family home at and on the Property pursuant to RSA 674:41, I(d). We respectfully request that this letter and matter be placed on the City Council's agenda for its regularly scheduled meeting on August 3, 2026.

The Property is located at the corner of two (2) paper streets: Elm Street and Forrest Street. Elm Street has never been constructed. A portion of Forrest Street has been improved (initially as a gravel driveway and now paved), but upon information and reasonable belief this improvement was not performed by the City; rather, it was constructed, and has been maintained, by the owner(s) and predecessors-in-interest of the improved lot situated at 1 Forrest Street, the corner of Forrest Street and Cutts Avenue. Enclosed herewith as Exhibit A is an aerial tax map image showing where the Property is located, as well as depicting the existing private drive within the right-of-way of Forrest Street.

This neighborhood and subdivision of land was first created in 1902 with the recording of the Buckminster Plan at the Rockingham County Registry of Deeds as Plan 270. In 1919, the Buckminster Plan was revised and recorded at the Registry as Plan 245. In both plans, the Property is identified as the "subject lot." See Exhibits B and C enclosed herewith.

It is clear that the paper streets shown on those plans were dedicated to the City and the public at large as rights-of-way; however, only a portion of this subdivision was built out prior to the construction of the interstate highway system that severed the neighborhood.

For further reference regarding Forrest Street, also enclosed is a 1988 subdivision plan prepared for David Hodgdon (Plan D-18913) which depicts the extent of the then-existing gravel driveway within the Forrest Street right-of-way; as noted above that driveway is now paved. Enclosed herewith as Exhibit D is the Hodgdon Plan.

The Property is a preexisting nonconforming lot of record. Other surrounding property owners of single-family homes on Cutts Avenue own the majority land abutting the Property on the paper streets. The City itself owns two nearby lots, as well. The City Legal Department and this office have been investigating the current legal status of Elm Street and Forrest Street, which is often not straightforward in light of the various events over the years, as well as the applicable case law and the statutory framework that vary at times since 1902 which govern paper streets, their dedication, and any express or implied acceptance by the City thereof.

My Client desires to construct a single-family home on the Property. In order to do so, she will require variance relief from the Zoning Board of Adjustment, as well as conditional use permits from the Planning Board for development within the Highway Noise Overlay District and for potential wetland buffer impacts.

My Client has not yet authorized her surveyor and engineer to proceed with extensive field work and research because the associated cost is not insignificant, and the status of the paper streets has been our primary focus to date. Rather than pursuing a final determination of whether the City retains, or has released, rights in these paper streets, we believe the most efficient path forward (so that this proposal may proceed to the City's land use boards) is through the process set forth in RSA 674:41, I(d), which is enclosed herewith in its entirety as Exhibit E.

RSA 674:41, I(d) provides that a building permit may be issued for a lot accessed by a private road where:

- (1) the local governing body, after review and comment by the planning board, or after establishing that the private road identifies and complies with policy adopted by the governing body of the municipality, has voted to authorize the issuance of building permits for the erection of buildings on said private road or portion thereof;
- (2) the municipality neither assumes responsibility for maintenance of said private roads nor liability for any damages resulting from the use thereof; and
- (3) prior to the issuance of a building permit, the applicant produces evidence that notice of the limits of municipal responsibility and liability has been recorded in the county registry of deeds for the lot.

Preliminary discussions with the Department of Public Works indicate that the DPW is amenable to treating access as a shared private driveway (rather than a full City street) until such time as future surrounding development *may* warrant formalization of a public way. The City would not maintain or plow the driveway, and trash collection would occur on Cutts Avenue. Municipal sewer service would be available via a private sewer line pump discharging to the existing sewer main on Cutts Avenue. The Fire Department's requirements for emergency vehicle access can be met through standard asphalt driveway construction and while also ensuring appropriate ingress and egress.¹

Pursuant to RSA 674:41, I(d), the City Council must first refer this request to the Planning Board for review and comment before it may authorize the issuance of a building permit. We respectfully request that the City Council refer this matter to the Planning Board to be addressed at its next regularly scheduled meeting on August 20, 2026.

Should the City Council ultimately authorize the issuance of a building permit under RSA 674:41, I(d), such authorization would of course be conditioned upon the Property obtaining any and all necessary land-use approvals from the Zoning Board of Adjustment and the Planning Board.

I am available to discuss this matter with the Council, the Planning Board, or City staff at any time. If my presence is requested or needed at the Council's August 3rd meeting, then I will have to appear via zoom as I will be out of town the week of August 3rd.

Thank you for your time and consideration of this request.

Kindest Regards,



Colby T. Gamester, Esq.

Enclosures

Cc: file
Karen Conard, City Manager
Trevor McCourt, Esq., Legal Department
Peter Rice, Department of Public Works
Chief McQuillen, Fire Department
Peter Britz, Planning Department
Stephanie Crepeau
(all via email)

¹ My Client and I have done a fair amount of research and consultation with various City Departments regarding the Property and surrounding area. We understand that with more formal plans and proposals, these Departments would, if necessary, have the opportunity to provide further comment, conditions, and limitations, if necessary and applicable.

LANDOWNER LETTER OF AUTHORIZATION

I, the Undersigned, Andrew Wolcott, the record owner of real property located at off Elm Street, Portsmouth, New Hampshire 03801, identified on Portsmouth Tax Map 210 as Lot 15 (the "Property"), hereby authorize Gamester Law Office, and its attorneys and representatives, to file any document with the City of Portsmouth (the "City"), communicate and correspond with City staff and officials, and submit applications with and appear before the City Council and the City's land use boards all regarding the Property. This Letter of Authorization shall be valid until expressly revoked in writing.



Andrew Wolcott

7/28/26
Date



Property Information

Property ID 0210-0015-0000
Location ELM ST
Owner WOLCOTT ANDREW



MAP FOR REFERENCE ONLY NOT A LEGAL DOCUMENT


City of Portsmouth, NH makes no claims and no warranties, expressed or implied, concerning the validity or accuracy of the GIS data presented on this map.

Geometry updated 03/06/2026

Print map scale is approximate.
Critical layout or measurement
activities should not be done using
this resource.




EXHIBIT C



Dec 27 10:57 AM '88

Dec 27 5:11:10 PM 42215



D-18913

TITLE LXIV PLANNING AND ZONING

CHAPTER 674 LOCAL LAND USE PLANNING AND REGULATORY POWERS

Regulation of Subdivision of Land

Section 674:41

674:41 Erection of Buildings on Streets; Appeals. –

I. From and after the time when a planning board shall expressly have been granted the authority to approve or disapprove plats by a municipality, as described in RSA 674:35, no building shall be erected on any lot within any part of the municipality nor shall a building permit be issued for the erection of a building unless the street giving access to the lot upon which such building is proposed to be placed:

- (a) Shall have been accepted or opened as, or shall otherwise have received the legal status of, a class V or better highway prior to that time; or
- (b) Corresponds in its location and lines with:
 - (1) A street shown on the official map; or
 - (2) A street on a subdivision plat approved by the planning board; or
 - (3) A street on a street plat made by and adopted by the planning board; or
 - (4) A street located and accepted by the local legislative body of the municipality, after submission to the planning board, and, in case of the planning board's disapproval, by the favorable vote required in RSA 674:40; or

[Paragraph I(c) effective until July 1, 2026; see also paragraph I(c) set out below.]

(c) Is a class VI highway, provided that:

- (1) The local governing body after review and comment by the planning board has voted to authorize the issuance of building permits for the erection of buildings on said class VI highway or a portion thereof; and
- (2) The municipality neither assumes responsibility for maintenance of said class VI highway nor liability for any damages resulting from the use thereof; and
- (3) Prior to the issuance of a building permit, the applicant shall produce evidence that notice of the limits of municipal responsibility and liability has been recorded in the county registry of deeds; or

[Paragraph I(c) effective July 1, 2026; see also paragraph I(c) set out above.]

(c) Is a class VI highway, provided that the applicant:

- (1) Signs a liability waiver acknowledging that the:
 - (A) Municipality shall not maintain the highway nor provide any services to any lot accessible by the highway;
 - (B) Municipality shall not accept any responsibility for losses or damages caused by a lack of services; and
 - (C) Responsibility for such services falls solely on the applicant; and
 - (2) Prior to the issuance of a building permit, produces evidence that this waiver has been recorded in the county register of deeds; and
 - (3) Prior to the issuance of a building permit, proves the lot and any buildings thereon are insurable; or
 - (d) Is a private road, provided that:
 - (1) The local governing body, after review and comment by the planning board, or after establishing that the private road identifies and complies with policy adopted by the governing body of the municipality, has voted to authorize the issuance of building permits for the erection of buildings on said private road or portion thereof; and
 - (2) The municipality neither assumes responsibility for maintenance of said private roads nor liability for any damages resulting from the use thereof; and
 - (3) Prior to the issuance of a building permit, the applicant shall produce evidence that notice of the limits of municipal responsibility and liability has been recorded in the county registry of deeds for the lot for which the building permit is sought; or
 - (e) Is an existing street constructed prior to the effective date of this subparagraph and is shown on a subdivision plat that was approved by the local governing body or zoning board of adjustment before the municipality authorized the planning board to approve or disapprove subdivision plats in accordance with RSA 674:35, if one or more buildings have been erected on other lots on the same street.
- II. Whenever the enforcement of the provisions of this section would entail practical difficulty or unnecessary hardship, and when the circumstances of the case do not require the building, structure or part thereof to be related to existing or proposed streets, the applicant for such permit may appeal from the decision of the administrative officer having charge of the issuance of permits to the zoning board of adjustment in any municipality which has adopted zoning regulations in accordance with RSA 674, or, in municipalities in which no board of adjustment exists, to the local legislative body, or to a board of appeals, whichever is appropriate, in accordance with RSA 674:14 and 674:15, including the requirement for a public hearing. In a municipality which does not require building permits, direct application may be made to the zoning board of adjustment, or the local legislative body, or the board of appeals for permission to erect the building. In passing on such appeal or application, the board of adjustment, local legislative body, or board of appeals may make any reasonable exception and

shall have the power to authorize or issue a permit, subject to such conditions as it may impose, if the issuance of the permit or erection of the building would not tend to distort the official map or increase the difficulty of carrying out the master plan upon which it is based, and if erection of the building or issuance of the permit will not cause hardship to future purchasers or undue financial impact on the municipality. Any such decision made in this connection by a board of adjustment, local legislative body, or by a board of appeals pursuant to this section and RSA 674:14 and 674:15 shall be in writing, together with the reasons for the decision, and shall be subject to review in the manner described in RSA 677.

II-a. Municipalities may except any lot, including island lots for islands served exclusively by boats, from the requirements of paragraphs I and II by an affirmative vote of the local legislative body pursuant to RSA 675, first submitted to the planning board for its approval and:

(a) If approved by the board, approved by a majority of those present and voting at a regular or special meeting of the local legislative body; or

(b) If disapproved by the planning board, approved by not less than 2/3 of those present and voting at a regular or special meeting of the local legislative body.

III. This section shall supersede any less stringent local ordinance, code or regulation, and no existing lot or tract of land shall be exempted from the provisions of this section except in accordance with the procedures expressly set forth in this section. For purposes of paragraph I, "the street giving access to the lot" means a street or way abutting the lot and upon which the lot has frontage. It does not include a street from which the sole access to the lot is via a private easement or right-of-way, unless such easement or right-of-way also meets the criteria set forth in subparagraphs I(a), (b), (c), (d), or (e).

IV. In addition to the requirements for the erection of buildings in paragraph I and notwithstanding the exceptions provided in paragraph II, the planning board for a county in which there are located unincorporated towns or unorganized places shall require every building which is erected on leased land located within an unincorporated town or unorganized place to have a building permit. A building permit shall be required under this paragraph regardless of the proximity of the building to any street or highway. The county shall, by resolution, authorize the planning board to issue building permits under this paragraph.

Source. 1983, 447:1. 1988, 131:2, 3. 1989, 266:20. 1995, 291:10. 1998, 344:6. 2002, 270:1, 5. 2004, 154:1, 2. 2005, 226:1, 2, eff. Sept. 3, 2005. 2025, 175:1, eff. Sept. 13, 2025; 256:1, eff. July 1, 2026.



Trevor P. McCourt
Deputy City Attorney

CITY OF PORTSMOUTH

Legal Department
Municipal Complex
1 Junkins Avenue
Portsmouth, New Hampshire 03801
tmccourt@portsmouthnh.gov
(603) 610-7234

Date: September 11, 2026

To: Peter Stith, Planning Manager

From: Trevor P. McCourt, Deputy City Attorney

Re: RSA 674:41, I(d) review and comment – 0 Elm Street (Tax Map 210, Lot 15);
Crepeau/Wolcott Request (Attorney Gamester letter dated July 29, 2026)

I. Introduction.

Attorney Colby Gamester, on behalf of Stephanie Crepeau (who is under contract to purchase the property) and its record owner, Andrew Wolcott, has asked the City Council to authorize the issuance of a building permit for a single-family home on Lot 15 (0 Elm Street, Tax Map 210) under RSA 674:41, I(d), on the theory that the lot is or would be served by a private road over the Forrest Street paper right-of-way. Because RSA 674:41, I(d)(1) requires the Council to obtain the Planning Board's review and comment before it may authorize building permits on a private road, the Council has referred the request to the Board. This memorandum is provided to assist the Board in that review: it explains what RSA 674:41 requires, applies it to the facts now before the City, identifies the limits of the Council's authority under the statute, and sets out the options I would recommend the Board transmit to the Council.

II. Statutory Framework

RSA 674:41, I bars issuance of a building permit on any parcel unless the parcel is on a street. This statute provides for issuance of building permits on streets that are not maintained by the municipality, such as Class VI roads and private roads. The basic purpose of this statute is “to ensure that a dwelling can be reached by the fire department, police department, and other agencies charged with the responsibilities of protecting the public peace, safety, and welfare. That purpose is defeated if the purported access route is not suitable for travel.” Loughlin, P., New Hampshire Practice, Land Use Planning and Zoning, Ch. 29.19, see Sanderson v. Town of Candia, 146 N.N. 598 (2001).

III. Factual Background

0 Elm Street is at the corner of two purported paper streets, Elm Street and Forrest Street. Forrest Street and Elm Street are paper streets shown on 1902 and 1919 subdivision plans entitled the Buckminster plans. The City's records confirm that Forrest Street was never accepted or used as a public way, and therefore the underlying fee likely resides with the abutters. No road has been constructed to connect 0 Elm Street to a public right of way. The improved (now paved) portion of Forrest Street serves as a driveway for 1 Forrest Street and does not reach the subject lot; what the applicant proposes is to build a new driveway. There is thus no constructed access to 0 Elm Street today. DPW reports a steep grade at the proposed access location, which may or may not be appropriate for a public road. The Fire Department advises that a drive exceeding 200 feet requires a 12-foot minimum width (16 feet recommended). Neither Department has issued a final recommendation without a plan depicting the proposed driveway. 0 Elm Street is also undersized and may require at least one variance and a conditional use permit due to its location within the Highway Noise Overlay District. Approximately nine other parcels in the Buckminster subdivision are similarly situated, without constructed access, and the City owns two nearby lots.

IV. Options for the Planning Board

There are two basic options for the Planning Board at this stage. The first would be to recommend denial, and the second would be to recommend approval with an exception from the statutory rule. The first could lead to an appeal to the Zoning Board of Adjustment, which can approve applications with conditions, and the second would require a public hearing at the City Council.

A. Paragraph II — ZBA exception (applicant-initiated; conditions allowed).

If the building inspector — the “administrative officer having charge of the issuance of permits,” not the Council — denies a permit for lack of qualifying access, the applicant may appeal to the Zoning Board of Adjustment. The ZBA may grant a “reasonable exception” for “practical difficulty or unnecessary hardship” and may issue the permit subject to such conditions as it imposes, if doing so would not distort the official map, increase the difficulty of the master plan, cause hardship to future purchasers, or impose undue financial impact on the City.

B. Paragraph II-a — legislative exception (Council vote; Board gatekeeps; no conditions).


The Council may except the lot from the requirements of paragraphs I and II by an affirmative vote, first submitted to the Planning Board for its approval: if the Board approves, a majority of the Council suffices; if the Board disapproves, a two-thirds vote is required. The vote is taken with a noticed public hearing so it is handled with the formality of a legislative enactment, not an ordinary permit vote.

V. Recommended Options.

Because there is no existing road servicing 0 Elm Street the Board's review and comment realistically takes one of two forms:

A. Recommend denial under paragraph I.

B. Recommend the City Council approve with an exception under paragraph II-a.



Inset

Legend

 Sidewalk Easement

MCDONOUGH ST

SIDEWALK EASEMENT TO BENEFIT
THE CITY OF PORTSMOUTH

LANGDON ST

Langdon Street Sidewalk Easement

Map prepared by Portsmouth Department of Public Works



City Council Website Contact Form

From City of Portsmouth <webformsubmission@portsmouthnh.gov>

Date Tue 10/13/2026 4:32 PM

To Webform Submission <webformsubmission@portsmouthnh.gov>

Cc City Council Clerk - Shr <ccclerk@portsmouthnh.gov>; City Council - Shr <ccemail@portsmouthnh.gov>; Carl E. Weber <ceweber@portsmouthnh.gov>; Karen S. Conard <kconard@portsmouthnh.gov>; Nathan D. Lunney <ndlunney@portsmouthnh.gov>; Susan G. Morrell <sgmorrell@portsmouthnh.gov>

Submitted on Tue, 10/13/2026 16:32

Submitted by: Anonymous

Submitted values are:

First Name

Lenore

Last Name

Bronson

Email

[REDACTED]

Subject

Letter re my property sewer issue

Address

[REDACTED]

Portsmouth, New Hampshire. 03801

Message

https://1drv.ms/w/c/7e91f35be2d42573/IQB-Piod03PXQaTG2Bibk6zGAQF8YBSXVx2_RKtKfT2eXWs?e=1xoEzC&nav=eyJoljoiNjYxNDUwMDUxln0

This attached copy of my original hand-delivered letter differs in a date correction (7/29/2026), the addition of quotation marks around Mr. Snyder's statement, and the addition of my email address.

Please indicate if you would like your comment to be part of the public record for the upcoming City Council meeting.

Yes

{Empty}

*subject Subject

City Council Website Contact Form

From City of Portsmouth <webformsubmission@portsmouthnh.gov>

Date Tue 10/13/2026 11:25 AM

To Webform Submission <webformsubmission@portsmouthnh.gov>

Cc City Council Clerk - Shr <ccclerk@portsmouthnh.gov>; City Council - Shr <ccemail@portsmouthnh.gov>; Carl E. Weber <ceweber@portsmouthnh.gov>; Karen S. Conard <kconard@portsmouthnh.gov>; Nathan D. Lunney <ndlunney@portsmouthnh.gov>; Susan G. Morrell <sgmorrell@portsmouthnh.gov>

Submitted on Tue, 10/13/2026 11:25

Submitted by: Anonymous

Submitted values are:

First Name

Thomas

Last Name

Nies

Email

[REDACTED]

Subject

Zoning Ordinance - Removal of Parking Regulations

Address

[REDACTED]

Portsmouth, New Hampshire. 03801

Message

Dear Mayor, Assistant Mayor, and Councilors:

Tonight will be the second reading of changes to the zoning ordinance that remove most parking regulations. Regulations will be move to the Site Plan review regulations, which are adopted by the Planning Board with no Council approval required. Given the acrimony which accompanies almost every change to parking requirements, I continue to believe this is a bad idea. That ship appears to have sailed, however.

I remain concerned that the proposed changes do not address a second issue I raised in September. The changes do not remove a section of the ordinance that allows the Zoning Board of Adjustment to impose parking requirements when granting special exceptions (Section 10.232.28). This seems inconsistent with the rest of the changes. From a conversation I had with City staff, I thought this

section was going to be removed, but perhaps a reason was identified to leave it in. I urge you to make sure that this is not an oversight.

Thank you for considering my comments.

Please indicate if you would like your comment to be part of the public record for the upcoming City Council meeting.

Yes

{Empty}

*subject Subject

City Council Website Contact Form

From City of Portsmouth <webformsubmission@portsmouthnh.gov>

Date Wed 10/14/2026 6:12 PM

To Webform Submission <webformsubmission@portsmouthnh.gov>

Cc City Council Clerk - Shr <ccclerk@portsmouthnh.gov>; City Council - Shr <ccemail@portsmouthnh.gov>; Carl E. Weber <ceweber@portsmouthnh.gov>; Karen S. Conard <kconard@portsmouthnh.gov>; Nathan D. Lunney <ndlunney@portsmouthnh.gov>; Susan G. Morrell <sgmorrell@portsmouthnh.gov>

Submitted on Wed, 10/14/2026 18:12

Submitted by: Anonymous

Submitted values are:

First Name

Steve

Last Name

Dunfey

Email

[REDACTED]

Subject

Joan Dunfey Art Exhibition at the New Hampshire Art Association

Address

[REDACTED]

Portsmouth, New Hampshire. 03801

Message

You are welcome to attend the Joan Dunfey Art Exhibition opening reception at the New Hampshire Art Association on 136 State Street. The reception takes place November 6 at 5 pm to 8 pm. Mayor McEachern will make some remarks at 6 pm. If you have any questions please email me at [REDACTED]. We always have a good crowd and we look forward to seeing you there.

Please indicate if you would like your comment to be part of the public record for the upcoming City Council meeting.

Yes

{Empty}

*subject Subject

City Council Website Contact Form

From City of Portsmouth <webformsubmission@portsmouthnh.gov>

Date Mon 10/19/2026 11:12 AM

To Webform Submission <webformsubmission@portsmouthnh.gov>

Cc City Council Clerk - Shr <ccclerk@portsmouthnh.gov>; City Council - Shr <ccemail@portsmouthnh.gov>; Carl E. Weber <ceweber@portsmouthnh.gov>; Karen S. Conard <kconard@portsmouthnh.gov>; Nathan D. Lunney <ndlunney@portsmouthnh.gov>; Susan G. Morrell <sgmorrell@portsmouthnh.gov>; Trevor McCourt <tmccourt@portsmouthnh.gov>

Submitted on Mon, 10/19/2026 - 11:12

Submitted by: Anonymous

Submitted values are:

First Name

Edwin

Last Name

Martinez

Email

[REDACTED]

Subject

Student Interview Request: Pedestrian and Bicycle Safety in Portsmouth

Address

[REDACTED]

Durham, New Hampshire. 03824

Message

Dear Councilor Hopkins,

My name is Edwin Martinez, and I am a student working on a school project about pedestrian and bicycle safety in Portsmouth, New Hampshire.

I am researching how local government addresses safety concerns for pedestrians and cyclists, including safer streets, bicycle lanes, sidewalks, and crosswalks.

I would appreciate the opportunity to interview you briefly about the City Council's priorities, current policies, and plans for improving pedestrian and bicycle safety in Portsmouth.

The interview could take place by email or at a time convenient for you. I would be happy to send my questions in advance.

Thank you for your time and consideration. I appreciate your work serving the Portsmouth community.

Sincerely,
Edwin Martinez

Please indicate if you would like your comment to be part of the public record for the upcoming City Council meeting.

Yes

{Empty}

*subject Subject

City Council Website Contact Form

From City of Portsmouth <webformsubmission@portsmouthnh.gov>

Date Tue 10/20/2026 4:12 PM

To Webform Submission <webformsubmission@portsmouthnh.gov>

Cc City Council Clerk - Shr <ccclerk@portsmouthnh.gov>; City Council - Shr <ccemail@portsmouthnh.gov>; Carl E. Weber <ceweber@portsmouthnh.gov>; Karen S. Conard <kconard@portsmouthnh.gov>; Nathan D. Lunney <ndlunney@portsmouthnh.gov>; Susan G. Morrell <sgmorrell@portsmouthnh.gov>; Trevor McCourt <tmccourt@portsmouthnh.gov>

Submitted on Tue, 10/20/2026 - 16:12

Submitted by: Anonymous

Submitted values are:

First Name

Martin

Last Name

McAuliffe

Email

[REDACTED]

Subject

Parrot Avenue parking

Address

[REDACTED]

Portsmouth, , New Hampshire. 03801

Message

Please consider the upper end of parrot Avenue where it reaches Richard Avenue to allow residents to park without limited to the four hour time. If you could put it back to the 72 hours, that would be ideal as a lot of us don't have driveways please and thank you.

Please indicate if you would like your comment to be part of the public record for the upcoming City Council meeting.

Yes

{Empty}

*subject Subject

City Council Website Contact Form

From City of Portsmouth <webformsubmission@portsmouthnh.gov>

Date Tue 10/20/2026 4:37 PM

To Webform Submission <webformsubmission@portsmouthnh.gov>

Cc City Council Clerk - Shr <ccclerk@portsmouthnh.gov>; City Council - Shr <ccemail@portsmouthnh.gov>; Carl E. Weber <ceweber@portsmouthnh.gov>; Karen S. Conard <kconard@portsmouthnh.gov>; Nathan D. Lunney <ndlunney@portsmouthnh.gov>; Susan G. Morrell <sgmorrell@portsmouthnh.gov>; Trevor McCourt <tmccourt@portsmouthnh.gov>

Submitted on Tue, 10/20/2026 - 16:37

Submitted by: Anonymous

Submitted values are:

First Name

Donna

Last Name

Funteral

Email

[REDACTED]

Subject

new parking restrictions on Parrott Ave

Address

[REDACTED]

Portsmouth, New Hampshire. 03801

Message

Dear City Councilors: My Richards Ave neighbors and I need your help. Please consider revising the current restrictions on Parrott Ave to include registered residents in the exception to the new Parrott Avenue parking policy. The current policy allows registered Library, Middle School, and Recreation staff to park on Parrott Avenue without a 4 hour limit. I believe it's only fair to consider residents of upper Richards Avenue for the same exception, since we live in the immediate neighborhood and have an ongoing need for parking near our homes.

Before I moved here, upper Richards Ave was narrowed and residents were permitted to park in the old Armory parking lot. I was a resident when the library was built and the Armory parking was removed. We were instructed to park on Parrott Ave. When the RAPP program was instituted, we all registered as residents, and then suddenly the rules were changed and the resident parking on upper

Parrott Ave was taken away.

There are often eight to ten empty spaces on Parrott Avenue because of the new four-hour limit, yet we are being forced to use parking spaces that our neighbors on lower Richards and Rockland Ave have traditionally relied on. It doesn't seem reasonable to leave spaces unused while shifting the parking burden from one group of residents to another. Please consider making registered residents an exception to the 4-hr parking limit. Thank you, Donna Funteral

Please indicate if you would like your comment to be part of the public record for the upcoming City Council meeting.

Yes

{Empty}

*subject Subject

City Council Website Contact Form

From City of Portsmouth <webformsubmission@portsmouthnh.gov>

Date Thu 10/22/2026 4:42 PM

To Webform Submission <webformsubmission@portsmouthnh.gov>

Cc City Council Clerk - Shr <ccclerk@portsmouthnh.gov>; City Council - Shr <ccemail@portsmouthnh.gov>; Carl E. Weber <ceweber@portsmouthnh.gov>; Karen S. Conard <kconard@portsmouthnh.gov>; Nathan D. Lunney <ndlunney@portsmouthnh.gov>; Susan G. Morrell <sgmorrell@portsmouthnh.gov>; Trevor McCourt <tmccourt@portsmouthnh.gov>

Submitted on Thu, 10/22/2026 - 16:42

Submitted by: Anonymous

Submitted values are:

First Name

Brian

Last Name

Collins

Email

[REDACTED]

Subject

I Need Your Help to Resolve an Excessive Parking Hardship Now Being Placed on Residents Living on the Northmost Section of Richards Ave

Address

[REDACTED]

Portsmouth, New Hampshire. 03801

Message

Hello Portsmouth City Councilors,

I am a longtime Portsmouth resident (25+ years at my current address) and understand there are many challenges with parking lately. I and my neighbors really need your help resolving the excessive parking hardship now being placed on us due to recent changes. We live on the northmost section of Richards Ave, between Parrott Ave and Middle St.

We (residents living on the northmost section of Richards Ave, between Parrott Ave and Middle St) cannot park on the section of Richards Ave we live on. Long ago it got taken away when the sidewalks got widened, but the provision provided to account for that was being allowed to park against the

northwest edge of the JFK Rec Center lot.

When the JFK got torn down to make way for the new library we were told a new parking provision would be made. That provision turned out to be park on Parrott Ave because there are only three residential houses on the Richards Ave end of Parrott Ave.

Recently, the 54 or 55 closest usable spaces on Parrott Ave, from Rogers St to Richards Ave, have had their meaningful use for us taken away by the 4 hour time limit.

The last and certainly not least important hardship factor is that winter is coming. I as well as some other residents living on the northmost section of Richards Ave being impacted by the 4 hour parking limit have physical mobility issues. As bad as parking has gotten during nice weather, it's going to get even worse in the winter.

There is already an exemption in place for people working at the Jr High, Library and Rec Center. We aren't asking for any additional infrastructure to be established. We are simply asking that registered residents living on the northmost section Richards Ave, from Parrott Ave to Middle Street, get that same exception.

We appreciate your time and consideration of what we feel is a very reasonable ask.

Sincerely,
Brian Collins

Please indicate if you would like your comment to be part of the public record for the upcoming City Council meeting.

Yes

{Empty}

*subject Subject

City Council Website Contact Form

From City of Portsmouth <webformsubmission@portsmouthnh.gov>

Date Thu 10/22/2026 3:00 PM

To Webform Submission <webformsubmission@portsmouthnh.gov>

Cc City Council Clerk - Shr <ccclerk@portsmouthnh.gov>; City Council - Shr <ccemail@portsmouthnh.gov>; Carl E. Weber <ceweber@portsmouthnh.gov>; Karen S. Conard <kconard@portsmouthnh.gov>; Nathan D. Lunney <ndlunney@portsmouthnh.gov>; Susan G. Morrell <sgmorrell@portsmouthnh.gov>; Trevor McCourt <tmccourt@portsmouthnh.gov>

Submitted on Thu, 10/22/2026 - 15:00

Submitted by: Anonymous

Submitted values are:

First Name

Kate

Last Name

Waldwick

Email

[REDACTED]

Subject

Land License Agreement at 361 Hanover Street

Address

[REDACTED]

Portsmouth, New Hampshire. 03801

Message

Hi City Councilors,

We (my husband, Bryn, and I) are reaching out about the upcoming discussion of licensing city land at 361 Hanover Street to Hampshire Development Corporation (HDC). From our understanding, it is tentatively slated for discussion on October 26th during the City Manager items discussion. We believe the current license agreement proposal, as currently presented from our City's planning board, is not in the best interest of the public or the city for several reasons.

1) The price of this land is worth more than just "maintenance" and it is the City's fiduciary responsibility to not license land far below market value: Based on previous land evaluations, this land has financial value and any agreement should result in financial compensation to the city beyond just

mowing the lawn, maintaining an existing retaining wall, and putting poles underground.

2) Access to putting utilities on public land is worth more than just the evaluation of the land: If HDC is able to put their utilities on public land, this allows them to build and sell more luxury condominiums. The increased profit that HDC will net should be factored into what is a "fair price" for licensing this land

3) Public Land should be accessible to the public: Currently, HDC has barred the public with hostile architecture (including fencing off access) from utilizing the public space along Foundry Place and plans to privatize this space in the future. We believe that any agreement should still allow the public to access this land and remove barriers of access that currently exist.

4) We believe a license should include terms more beneficial to the public: Previous more neighborhood friendly design suggestions were rejected by the developer, such as having traffic routed onto Foundry Place, since HDC "did not own the land". To get this land, we believe there should be more concessions from the developer and revisiting traffic flow onto Foundry Place

5) The only part of the land HDC proposes remaining publicly accessible along Rock Street is where they proposed putting the transformers, even though Foundry Place has ample electrical infrastructure to support putting transformers there. It's notable that while a license agreement can be renegotiated and either party can back out, a transformer is permanent and unable to be moved even long after initial license terms change.

One of us will try to attend on Monday night as well to speak during public comment, but please note that we recently welcomed our third child (who is 7 weeks old), so we may not be able to attend in person.

Thank you for your time in reading this and for your service to the city.

Please indicate if you would like your comment to be part of the public record for the upcoming City Council meeting.

Yes

{Empty}

*subject Subject

City Council Website Contact Form

From City of Portsmouth <webformsubmission@portsmouthnh.gov>

Date Sat 10/24/2026 12:58 PM

To Webform Submission <webformsubmission@portsmouthnh.gov>

Cc City Council Clerk - Shr <ccclerk@portsmouthnh.gov>; City Council - Shr <ccemail@portsmouthnh.gov>; Carl E. Weber <ceweber@portsmouthnh.gov>; Karen S. Conard <kconard@portsmouthnh.gov>; Nathan D. Lunney <ndlunney@portsmouthnh.gov>; Susan G. Morrell <sgmorrell@portsmouthnh.gov>; Trevor McCourt <tmccourt@portsmouthnh.gov>

Submitted on Sat, 10/24/2026 - 12:58

Submitted by: Anonymous

Submitted values are:

First Name

Marcie

Last Name

Vaughan

Email

[REDACTED]

Subject

Item 10.E on Monday's agenda

Address

[REDACTED]

Portsmouth , New Hampshire. 03801 3958

Message

Dear Mayor McEachern and Members of the City Council:

We live at 407 Hanover Street, directly across Rock Street from 361 Hanover. We ask that you postpone Item 10.E on Monday's agenda, the licenses of City land and sidewalk easement for 361 Hanover.

The motion asks you to approve a 50 year landscape license, with exclusive access for the project's residents to the City land behind the building, and a license for an Eversource transformer on City land along Rock Street. Both would be finalized "in a form acceptable to the City Attorney" after your vote. Neither you nor the public has seen the actual documents.

We asked for records on this matter under RSA 91-A on September 20 and have received no formal response beyond a phone call, on October 16, from City Attorney Jennifer Smith advising that the City had overlooked the request. Having received no further information as of today's date, we have renewed that request.

The transformer is needed only because of this development, and it could be placed on the developer's own land. The land behind the building should stay open to the public. The last license of City land to this property, in 2006, ended in 2024 only after we reported that its payment and public-parking terms were being violated.

Please give the public a chance to review the terms before you vote.

Respectfully,
Marcie Vaughan and Sean Caughran
407 Hanover Street, Portsmouth

Please indicate if you would like your comment to be part of the public record for the upcoming City Council meeting.

Yes

{Empty}

*subject Subject

City Council Website Contact Form

From City of Portsmouth <webformsubmission@portsmouthnh.gov>

Date Sun 10/25/2026 2:57 PM

To Webform Submission <webformsubmission@portsmouthnh.gov>

Cc City Council Clerk - Shr <ccclerk@portsmouthnh.gov>; City Council - Shr <ccemail@portsmouthnh.gov>; Carl E. Weber <ceweber@portsmouthnh.gov>; Karen S. Conard <kconard@portsmouthnh.gov>; Nathan D. Lunney <ndlunney@portsmouthnh.gov>; Susan G. Morrell <sgmorrell@portsmouthnh.gov>; Trevor McCourt <tmccourt@portsmouthnh.gov>

Submitted on Sun, 10/25/2026 - 14:56

Submitted by: Anonymous

Submitted values are:

First Name

Robin

Last Name

Husslage

Email

[REDACTED]

Subject

October 26 City Council Meeting: Planning Board Recommendation Regarding Licenses and a Sidewalk Easement for 361 Hanover Street

Address

[REDACTED]

Portsmouth, New Hampshire. 03801

Message

To: City Manager, Mayor, and City Councilors

Re: October 26 City Council Meeting: Planning Board Recommendation Regarding Licenses and a Sidewalk Easement for 361 Hanover Street

Dear Portsmouth City Council Members,

I am writing to you regarding the request before you regarding a license and easement for 361 Hanover Street property currently being developed in our Rock Street neighborhood. Firstly, throughout this process up until this point, there has not been an opportunity for the public to

comment on the proposed license and easement. The public was not invited to provide input during the October 7th site walk the developer had with the DPW nor in the Planning Board meeting discussions on October 15th. However, the developer's representatives were allowed to speak and confer with the City at both of these events. And, in this very City Council meeting, there isn't an official public session dedicated to this proposal, allowing the public to provide their input regarding the city giving away our public property and access to the property for the next 50 years!

Requests for information were sent to the City by neighbors so we could better understand the intricacies of the past and proposed arrangement between the developer and the City but we have been waiting over a month and yet no information has been forthcoming. How can you, our City Council, fairly assess and decide upon a proposal without first hearing what your citizens have to say? And, allow your citizens to ask important questions about this proposal, all of which benefits the developer and none benefiting the citizens in the neighborhood where this development is being built.

I ask you to please defer your decision until a public meeting can be held on this proposal and critical information is made available to the public prior to the meeting so we can be informed and ask questions that are important for our community to know the answers to.

Your Portsmouth Citizen and an abutter to this development,

Robin Husslage
27 Rock Street

Please indicate if you would like your comment to be part of the public record for the upcoming City Council meeting.

Yes

{Empty}

*subject Subject

City Council Website Contact Form

From City of Portsmouth <webformsubmission@portsmouthnh.gov>

Date Mon 10/26/2026 8:08 AM

To Webform Submission <webformsubmission@portsmouthnh.gov>

Cc City Council Clerk - Shr <ccclerk@portsmouthnh.gov>; City Council - Shr <ccemail@portsmouthnh.gov>; Carl E. Weber <ceweber@portsmouthnh.gov>; Karen S. Conard <kconard@portsmouthnh.gov>; Nathan D. Lunney <ndlunney@portsmouthnh.gov>; Susan G. Morrell <sgmorrell@portsmouthnh.gov>; Trevor McCourt <tmccourt@portsmouthnh.gov>

Submitted on Mon, 10/26/2026 - 08:08

Submitted by: Anonymous

Submitted values are:

First Name

Matthew

Last Name

Glenn

Email

[REDACTED]

Subject

Pedestrian path to Dondero at 20 22 Taft

Address

[REDACTED]

Portsmouth, New Hampshire. 03801

Message

Dear Mayor and Councilors,

I noticed item 11H on your agenda to release the "paper street" between the homes at 20 and 22 Taft, but maintain a sewer easement. I would like to ask if a pedestrian easement could also be maintained.

There is currently a foot path from the back of the Dondero parking lot leading to this paper street on top of the sewer line. Part of the path has been used by the school to access their "nature classroom", and while the land is very wet on either side the path itself is higher and is in fairly good shape. A few years back it could be easily walked straight through to Taft; more recently fallen branches near the back of the homes have made it more difficult.

I don't believe that any children currently use it to reach Dondero, but it would be a very convenient and more direct route for many on that side of Elwyn Park and the Woodlands with just a little brush clearing. I would ask that you consider maintaining the right for pedestrians to pass here.

Regards,

Matt Glenn

Please indicate if you would like your comment to be part of the public record for the upcoming City Council meeting.

Yes

{Empty}

*subject Subject

Rec'd
10/16/26



CITY OF PORTSMOUTH, N.H. BOARDS AND COMMISSIONS

REAPPOINTMENT APPLICATION

Instructions: Please print or type and complete all information

Committee: Trustees of the Trust Funds

Name: Peter J. Weeks

Please confirm or update your contact information below:

Street Address: ☐ No Change ☒ Updated: [REDACTED]

Mailing Address: ☐ No Change ☒ Updated: [REDACTED]

Telephone Number: ☐ No Change ☒ Updated: [REDACTED]

Email Address: ☐ No Change ☒ Updated: pgweeks@comcast.net

Eligibility and Availability

Do you remain a resident of Portsmouth? ☒ Yes ☐ No

Changes to meeting availability? ☒ No ☐ Yes: _____

Continued Service

Do you wish to be considered for reappointment? ☒ Yes ☐ No

Interested in other boards if not reappointed? ☐ Yes ☒ No

Acknowledgment

By signing, you certify the above is accurate and understand that:

- (1) Reappointment is at the discretion of the Mayor and City Council;
- (2) Review and acknowledgment of the Volunteer Handbook is mandatory (information will be emailed to you and can be found on the City Clerk's webpage); and
- (3) The taking of the Oath of Office and signing of the oath book at the City Clerk's office is required after appointment.

Signature: [Signature]

Date: 9-30-2026

Submit to: City Clerk's Office, 1 Junkins Avenue, Portsmouth, NH 03801

PARKING and TRAFFIC SAFETY COMMITTEE ACTION SHEET

9:00 A.M. – October 1, 2026
City Hall Conference Room A

PRESENT: **Members:** Committee Chair Annie Hopkins, Vice Committee Chair Erica Wygonik, Public Works Director Peter Rice, Fire Chief William McQuillen, Deputy Police Chief Mike Maloney, Stefanie Casella Planning Department, Mary Lou McElwain, Mark Syracuse, Jane Mitchell-Pate, Alternate Barbara Sadick

City Staff: City Engineer Eric Eby, Project Manager Tyler Reese, Business Administrator Jefferson Lane

ACTION ITEMS FOR CITY COUNCIL

<u>6. Middle Street, request to approve no parking area on west side of street, north of intersection with Cabot Street, by DPW.</u>

1. **Roll Call**
2. **Financial Report:** **Voted** to accept the financial report dated August 31, 2026.
3. **Public Comment Session:** Kristen Peterson (402 State Street sight line concern), Colleen Kilcoyne (402 State Street sight line concern), Nancy Ydoate (402 State Street sight line concern), Susan (Chapel & State crosswalk concerns), Tyler Garzo (feedback on traffic calming requests)
4. **Presentations:** None
5. **402 State Street, request to improve driveway sight lines, by resident.** **Voted** to place the item on file.
6. **Middle Street, request to approve no parking area on west side of street, north of intersection with Cabot Street, by DPW.** **Voted** to approve no parking on the west side of Middle Street for a distance of 60 feet north of Cabot Street, consistent with previous signage.
7. **South Street traffic calming request, report back.** The item was discussed and did not require a vote.
8. **Maplewood Avenue traffic calming request, report back.** The item was discussed and did not require a vote.
9. **Police monthly collision report:** Informational; no action required.
10. **State Street Intersections from Union to Summer:** Informational; no action required.
11. **Traffic Calming Request – Jones Avenue:** Informational; no action required.

Respectfully submitted by: Jefferson Lane



PARKING and TRAFFIC SAFETY COMMITTEE

Conference Room A at City Hall, 1 Junkins Avenue
Thursday, October 1, 2026, 9:00 AM

Members of the public also had the option to join the meeting over Zoom.

MINUTES

1. **Call To Order**

Committee Chair Annie Hopkins called the meeting to order at 9:00 AM.

2. **Attendance**

Members Present:

Public Works Director Peter Rice
Fire Chief William McQuillen
Deputy Police Chief Mike Maloney
Committee Chair Annie Hopkins
Stefanie Casella, Planning Department
Erica Wygonik
Mary Lou McElwain
Mark Syracuse
Jane Mitchell-Pate
Barbara Sadick (alternate)

City Staff Present:

Eric Eby, City Engineer
Tyler Reese, Project Manager
Jefferson Lane, Business Administrator

3. **Financial Report**

[00:05:15] Peter Rice moved to accept the financial report dated August 31st, 2026, seconded by Mark Syracuse. On a unanimous vote, the motion passed.

4. Public Comment (15 Minutes)

[00:05:54] There were six public speakers: Kristen Peterson, Colleen Kilcoyne, and Nancy Ydoate, all of 402 State Street, raised concerns about the driveway sight lines at their residence, requesting to re-install a convex mirror previously affixed to a City street lamp or to have the City evaluate parking space in front of the residence; Susan of Broad Street raised crosswalk visibility concerns at Chapel & State; Tyler Garzo, 62 McKinley Road, critiqued handling of traffic calming requests and also provided advice to residents on request verbiage.

5. Presentations

There were no presentations.

6. New Business

- A. [00:14:45] 402 State Street, request to improve driveway sight lines, by resident. Bill McQuillen moved to place the item on file, seconded by Peter Rice. Discussion ensued, including the viability of removing parking on State Street. The committee discussed how removing parking in front of one building may set a precedent for other buildings on the street. Regarding the convex mirror mentioned during public comment, Peter Rice noted that the City does not allow nor condone placement of mirrors on City-owned utilities, such as streetlamps. He noted a mirror could be affixed on private property. Following discussion, the motion passed on a unanimous vote.
- B. [00:24:54] Middle Street, request to approve no parking area on west side of street, north of intersection with Cabot Street, by DPW. Erica Wygonik moved to approve no parking on the west side of Middle Street for a distance of 60 feet north of Cabot Street, consistent with previous signage, seconded by Jane Mitchell-Pate. Eric Eby provided background on the item, noting existing sign was placed years ago, but was never codified in the City ordinance. Following discussion, the motion passed on a unanimous vote.

7. Old Business

- A. [00:27:24] South Street traffic calming request, report back. Eric Eby led the conversation with data recorded from South Street, as well as criteria for initiating traffic calming. The committee discussed the possibility of implementing a speed feedback sign, as well as discussion on increased lighting for the crosswalk at the intersection of South Street and Summit Avenue.

- B. [00:41:37] Maplewood Avenue traffic calming request, report back. Eric Eby again led the conversation with data recorded from Maplewood Avenue, finding that 85th percentile speeds were highest during the morning hours. The committee discussed the possibility of targeted enforcement during those peak hours, as well as implementation of a speed feedback sign on a utility pole.

8. Informational

- A. [00:48:31] Police Monthly Collision Report, discussion of Seacoast Pedal It Forward
B. [00:54:27] State Street Intersections From Union Street To Summer Street
C. [00:55:20] Traffic Calming Request – Jones Avenue

9. Miscellaneous

- [00:56:52] UrbanSDK traffic speed data demonstration
[01:02:00] Bicycle & Pedestrian Network Request Form (beta version) is now live

10. Adjournment

- [01:09:26] Erica Wygonik moved to adjourn the meeting, seconded by Jane Mitchell-Pate. On a unanimous vote, the motion passed. Committee Chair Annie Hopkins adjourned the meeting at 10:05 AM.

Respectfully submitted,

Jefferson Lane

Business Administrator, Department of Public Works

Gift and Donation Submission Form

Donations received by the City of Portsmouth must be accepted by the City Council. Please complete this form and submit it to the City Manager for inclusion on an upcoming agenda.

Date:	10-19-26
Department/Contact Person:	Suzanne Woodland
Donation Amount:	\$50

Are Funds to be directed to a particular department, program or fund? – If yes, please provide detail below:

City of Portsmouth General Fund - DPW

Is there a particular purpose intended with this donation:

Point of Graves Cemetery Wall Replacement Project

Other information/Special Conditions:

--

Donor Information

First & Last Name:	Anonymous South End Resident
Business Name:	
Address*:	
Phone*:	
Email*:	

Please note that gifts/donations to individual employees with a value of \$100 or more are not permitted. Information with an asterisk () indicates it will not be publicly distributed.*

Gift and Donation Submission Form

Donations received by the City of Portsmouth must be accepted by the City Council. Please complete this form and submit it to the City Manager for inclusion on an upcoming agenda.

Date:	10-13-2026
Department/Contact Person:	Suzanne Woodland
Donation Amount:	\$50

Are Funds to be directed to a particular department, program or fund? – If yes, please provide detail below:

City of Portsmouth General Fund - DPW

Is there a particular purpose intended with this donation:

Point of Graves Cemetery Wall Replacement Project

Other information/Special Conditions:

--

Donor Information

First & Last Name:	Michael Pennington
Business Name:	
Address*:	
Phone*:	
Email*:	

Please note that gifts/donations to individual employees with a value of \$100 or more are not permitted. Information with an asterisk () indicates it will not be publicly distributed.*

Gift and Donation Submission Form

Donations received by the City of Portsmouth must be accepted by the City Council. Please complete this form and submit it to the City Manager for inclusion on an upcoming agenda.

Date:	10-13-2026
Department/Contact Person:	Suzanne Woodland
Donation Amount:	\$500

Are Funds to be directed to a particular department, program or fund? – If yes, please provide detail below:

City of Portsmouth General Fund - DPW

Is there a particular purpose intended with this donation:

Point of Graves Cemetery Wall Replacement Project

Other information/Special Conditions:

--

Donor Information

First & Last Name:	Charles and Barbara Bickford
Business Name:	
Address*:	
Phone*:	
Email*:	

Please note that gifts/donations to individual employees with a value of \$100 or more are not permitted. Information with an asterisk () indicates it will not be publicly distributed.*



Department of Justice (DOJ)

Office of Justice Programs

Office of Juvenile Justice Delinquency Prevention

Washington, D.C. 20531

Name and Address of Recipient:	CITY OF PORTSMOUTH NH 1 JUNKINS AVE
City, State and Zip:	PORTSMOUTH, NH 03801
Recipient UEI:	XTL2C874AZN7
Project Title: ICACCOPS & NH ICAC Enhanced Capacity Program	Award Number: 15PJDP-26-GG-01379-BRND
Solicitation Title: OJJDP FY 2026 Invited to Apply - Byrne Discretionary Community Project Grants/Byrne Discretionary Grants Program	
Federal Award Amount: \$1,000,000.00	Federal Award Date: 9/30/26
Awarding Agency:	Office of Justice Programs Office of Juvenile Justice Delinquency Prevention
Award Type:	Initial
Funding Instrument Type:	Grant
Opportunity Category: E	
Assistance Listing: 16.753 - Congressionally Recommended Awards	
Project Period Start Date: 2/1/26	Project Period End Date: 1/31/28
Budget Period Start Date: 2/1/26	Budget Period End Date: 1/31/28
Project Description: The New Hampshire Internet Crimes Against Children Task Force proposes to use funding to maintain, strengthen, and enhance both the Task Force and its affiliate agencies' investigative and forensic capacity. Project activities include digital forensic analysis training for affiliate members, digital forensic computer hardware and additional forensic multiyear licensing agreements. Deliverable and expected outcomes include enhanced ability to efficiently triage and process the increasing volume of potential child sexual abuse imagery, enticement and extortion cases, generative artificial intelligence sexual abuse imagery, and the emerging threat of sadistic online exploitation. The subrecipient, National Criminal Justice Training Center of Fox Valley Technical College, will operate and maintain a secure investigative technology platform, which is utilized by the Task Force and other authorized criminal justice users, by providing investigative tools, reporting functions and related operations.	

Award Letter

September 30, 2026

Dear Karen Conard,

On behalf of the Attorney General, it is my pleasure to inform you the Office of Justice Programs (OJP) has approved the application submitted by CITY OF PORTSMOUTH NH for an award under the funding opportunity entitled 2026

OJJDP FY 2026 Invited to Apply - Byrne Discretionary Community Project Grants/Byrne Discretionary Grants Program. The approved award amount is \$1,000,000.

Review the Award Instrument below carefully and familiarize yourself with all conditions and requirements before accepting your award. The Award Instrument includes the Award Offer (Award Information, Project Information, Financial Information, and Award Conditions) and Award Acceptance. For COPS Office and OVW funding the Award Offer also includes any Other Award Documents.

Please note that award requirements include not only the conditions and limitations set forth in the Award Offer, but also compliance with assurances and certifications that relate to conduct during the period of performance for the award. These requirements encompass financial, administrative, and programmatic matters, as well as other important matters (e.g., specific restrictions on use of funds). Therefore, all key staff should receive the award conditions, the assurances and certifications, and the application as approved by OJP, so that they understand the award requirements. Information on all pertinent award requirements also must be provided to any subrecipient of the award.

Should you accept the award and then fail to comply with an award requirement, DOJ will pursue appropriate remedies for non-compliance, which may include termination of the award and/or a requirement to repay award funds.

Prior to accepting the award, your Entity Administrator must assign a Financial Manager, Grant Award Administrator, and Authorized Representative(s) in the Justice Grants System (JustGrants). The Entity Administrator will need to ensure the assigned Authorized Representative(s) is current and has the legal authority to accept awards and bind the entity to the award terms and conditions. To accept the award, the Authorized Representative(s) must accept all parts of the Award Offer in the Justice Grants System (JustGrants), including by executing the required declaration and certification, within 45 days from the award date.

To access your funds, you will need to enroll in the Automated Standard Application for Payments (ASAP) system, if you haven't already completed the enrollment process in ASAP. The Entity Administrator should have already received an email from ASAP to initiate this process.

Congratulations, and we look forward to working with you.

Maureen A. Henneberg
Deputy Assistant Attorney General

Office for Civil Rights Notice for All Recipients

The Office for Civil Rights (OCR), Office of Justice Programs (OJP), U.S. Department of Justice (DOJ) enforces federal civil rights laws and other provisions that prohibit discrimination by recipients of federal financial assistance from OJP, the Office of Community Oriented Policing Services (COPS), and the Office on Violence Against Women (OVW).

Several civil rights laws, including Title VI of the Civil Rights Act of 1964 and Section 504 of the Rehabilitation Act of 1973, require recipients of federal financial assistance (recipients) to give assurances that they will comply with those laws. Taken together, these and other civil rights laws prohibit recipients from discriminating in the provision of services and employment because of race, color, national origin, religion, disability, and sex or from discriminating in the provision of services on the bases of age.

Some recipients of DOJ financial assistance have additional obligations to comply with other applicable nondiscrimination provisions like the Omnibus Crime Control and Safe Streets Act of 1968, which prohibits discrimination on the basis of religion in addition to race, color, national origin, and sex. Recipients may also have related requirements regarding the development and implementation of equal employment opportunity programs.

OCR provides technical assistance, training, and other resources to help recipients comply with civil rights obligations. Further, OCR administratively enforces civil rights laws and nondiscrimination provisions by investigating DOJ recipients that are the subject of discrimination complaints. In addition, OCR conducts compliance reviews of DOJ recipients based on regulatory criteria. These investigations and compliance reviews permit OCR to evaluate whether DOJ recipients are providing services to the public and engaging in employment practices in a nondiscriminatory manner.

For more information about OCR, your civil rights and nondiscrimination responsibilities, how to notify your employees or beneficiaries of their civil rights protections and responsibilities and how to file a complaint, as well as technical

assistance, training, and other resources, please visit www.ojp.gov/program/civil-rights-office/outreach. If you would like OCR to assist you in fulfilling your civil rights or nondiscrimination responsibilities, please contact us at askOCR@ojp.usdoj.gov or www.ojp.gov/program/civil-rights-office/about#ocr-contacts.

Memorandum Regarding NEPA

NEPA Letter Type

OJP - Categorical Exclusion

NEPA Letter

National Environmental Policy Act (NEPA) record

NEPA determination: Categorical Exclusion

The OJJDP FY 2026 Byrne Discretionary Community Project Grants/Byrne Discretionary Grants Program supports projects designated for funding pursuant to the Department of Justice Appropriations Act, 2026 (Pub. L. No. 119-74, Div. A, Title II.) to improve the functioning of the criminal justice system, to prevent or combat juvenile delinquency, and to assist victims of crime (other than compensation).

None of the following activities will be conducted whether under the Office of Justice Programs federal action or a related third party action:

- (1) New construction.
- (2) Any renovation or remodeling of a property located in an environmentally or historically sensitive area, including property (a) listed on or eligible for listing on the National Register of Historic Places, or (b) located within a 100-year flood plain, a wetland, or habitat for an endangered species.
- (3) A renovation that will change the basic prior use of a facility or significantly change its size.
- (4) Research and technology whose anticipated and future application could be expected to have an effect on the environment.
- (5) Implementation of a program involving the use of chemicals (including the identification, seizure, or closure of clandestine methamphetamine laboratories).

Additionally, the proposed action is neither a phase nor a segment of a project that when reviewed in its entirety would not meet the criteria for a categorical exclusion.

Consequently, the subject federal action meets the Office of Justice Programs' criteria for a categorical exclusion as contained in paragraph 4(b) of Appendix D to Part 61 of Title 28 of the Code of Federal Regulations.

Questions about this determination may be directed to your grant manager Environmental Coordinator for the Office of Juvenile Justice and Delinquency Prevention.

NEPA Coordinator

First Name

Lou Ann

Middle Name

no value

Last Name

Holland

Award Information

This award is offered subject to the conditions or limitations set forth in the Award Information, Project Information, Financial Information, and Award Conditions.

Recipient Information

Recipient Name

UEI
XTL2C874AZN7

Street 1
1 JUNKINS AVE

Street 2

City
PORTSMOUTH

State/U.S. Territory
New Hampshire

Zip/Postal Code
03801

Country
United States

County/Parish

Province

Award Details

Federal Award Date
9/30/26

Award Type
Initial

Award Number
15PJDP-26-GG-01379-BRND

Supplement Number
00

Federal Award Amount
\$1,000,000.00

Funding Instrument Type
Grant

**Assistance Listing
Number**
16.753

Assistance Listings Program Title
Congressionally Recommended Awards

Statutory Authority

Department of Justice Appropriations Act, 2026 (Pub. L. No. 119-74, 140 Stat. 5, 30-31, para. 1(O))

[] I have read and understand the information presented in this section of the Federal Award Instrument.

Project Information

This award is offered subject to the conditions or limitations set forth in the Award Information, Project Information, Financial Information, and Award Conditions.

Solicitation Title
2026 OJJDP FY 2026 Invited to Apply - Byrne
Discretionary Community Project Grants/Byrne
Discretionary Grants Program

Awarding Agency
OJP

Program Office
OJJDP

Application Number
GRANT14702846

Grant Manager Name

William Sarrano

Phone Number

202-598-5822

E-mail Address

William.Sarrano@usdoj.gov

Project Title

ICACCOPS & NH ICAC Enhanced Capacity Program

Performance Period Start**Date**

02/01/2026

Performance Period End Date

01/31/2028

Budget Period Start Date

02/01/2026

Budget Period End Date

01/31/2028

Project Description

The New Hampshire Internet Crimes Against Children Task Force proposes to use funding to maintain, strengthen, and enhance both the Task Force and its affiliate agencies' investigative and forensic capacity. Project activities include digital forensic analysis training for affiliate members, digital forensic computer hardware and additional forensic multiyear licensing agreements. Deliverable and expected outcomes include enhanced ability to efficiently triage and process the increasing volume of potential child sexual abuse imagery, enticement and extortion cases, generative artificial intelligence sexual abuse imagery, and the emerging threat of sadistic online exploitation. The subrecipient, National Criminal Justice Training Center of Fox Valley Technical College, will operate and maintain a secure investigative technology platform, which is utilized by the Task Force and other authorized criminal justice users, by providing investigative tools, reporting functions and related operations.

☐ I have read and understand the information presented in this section of the Federal Award Instrument.

Financial Information

This award is offered subject to the conditions or limitations set forth in the Award Information, Project Information, Financial Information, and Award Conditions.

The recipient budget is currently under review.

☐ I have read and understand the information presented in this section of the Federal Award Instrument.

Award Conditions

This award is offered subject to the conditions or limitations set forth in the Award Information, Project Information, Financial Information, and Award Conditions.

Condition 1

Compliance with general appropriations-law restrictions on the use of federal funds (FY 2025)

The recipient, and any subrecipient ("subgrantee") at any tier, must comply with all applicable restrictions on the use of federal funds set out in federal appropriations statutes. Pertinent restrictions that may be set out in applicable appropriations acts are indicated at <https://ojp.gov/funding/Explore/FY25AppropriationsRestrictions.htm>, and are incorporated by reference here.

Should a question arise as to whether a particular use of federal funds by a recipient (or a subrecipient) would or might fall within the scope of an appropriations-law restriction, the recipient is to contact OJP for guidance, and may not proceed without the express prior written approval of OJP.

Condition 2

Compliance with DOJ regulations pertaining to civil rights and nondiscrimination - 28 C.F.R. Part 38

The recipient, and any subrecipient ("subgrantee") at any tier, must comply with all applicable requirements of 28 C.F.R. Part 38.

Among other things, 28 C.F.R. Part 38 states that recipients may not use direct Federal financial assistance from the Department of Justice to support or engage in any explicitly religious activities except when consistent with the Establishment Clause of the First Amendment to the U.S. Constitution and any other applicable requirements. An organization receiving Federal financial assistance also may not, in providing services funded by the Department of Justice or in outreach activities related to such services, discriminate against a program beneficiary or prospective program beneficiary on the basis of religion, a religious belief, a refusal to hold a religious belief, or refusal to attend or participate in a religious practice. Part 38 also sets out rules and requirements that pertain to recipient and subrecipient ("subgrantee") organizations that engage in or conduct explicitly religious activities, as well as rules and requirements that pertain to recipients and subrecipients that are faith-based or religious organizations. In addition, Part 38 states that a faith-based organization that participates in a Department of Justice funded program retains its independence from the Government and may continue to carry out its mission consistent with religious freedom and conscience protections in Federal law.

Recipients and subrecipients that provide social services under this award must give written notice to beneficiaries and prospective beneficiaries prior to the provision of services (if practicable) which shall include language substantially similar to the language in 28 CFR Part 38, Appendix C, sections (1) through (4). A sample written notice may be found at <https://www.ojp.gov/program/civil-rights-office/partnerships-faith-based-and-other-neighborhood-organizations>.

In certain instances, a faith-based or religious organization may be able to take religion into account when making hiring decisions, provided it satisfies certain requirements. For more information, see "Nondiscrimination provisions and the Religious Freedom Restoration Act," accessible at <https://www.ojp.gov/funding/explore/legaloverview2025/civilrightsrequirements>.

Condition 3

Requirements pertaining to prohibited conduct related to trafficking in persons (including reporting requirements and OJP authority to terminate award)

The recipient, and any subrecipient ("subgrantee") at any tier, must comply with all applicable requirements (including requirements to report allegations) pertaining to prohibited conduct related to the trafficking of persons, whether on the part of recipients, subrecipients ("subgrantees"), or individuals defined (for purposes of this condition) as "employees" of the recipient or of any subrecipient.

The details of the recipient's obligations related to prohibited conduct related to trafficking in persons are posted on the OJP web site at <https://ojp.gov/funding/Explore/ProhibitedConduct-Trafficking.htm> (Award condition: Prohibited conduct by recipients and subrecipients related to trafficking in persons (including reporting requirements and OJP authority to terminate award)), and are incorporated by reference here.

Condition 4

All subawards ("subgrants") must have specific federal authorization

The recipient, and any subrecipient ("subgrantee") at any tier, must comply with all applicable requirements for authorization of any subaward. This condition applies to agreements that -- for purposes of federal grants administrative requirements -- OJP considers a "subaward" (and therefore does not consider a procurement "contract").

The details of the requirement for authorization of any subaward are posted on the OJP website at <https://ojp.gov/funding/Explore/SubawardAuthorization.htm> (Award condition: All subawards ("subgrants") must have specific federal

authorization), and are incorporated by reference here.

Condition 5

Specific post-award approval required to use a noncompetitive approach in any procurement contract that would exceed the Simplified Acquisition Threshold

The recipient, and any subrecipient ("subgrantee") at any tier, must comply with all applicable requirements to obtain specific advance approval to use a noncompetitive approach in any procurement contract that would exceed the Simplified Acquisition Threshold, as set forth in the Federal Acquisition Regulations (FAR). See the definition of simplified acquisition threshold in the FAR at 48 CFR part 2, subpart 2.1. This condition applies to agreements that -- for purposes of federal grants administrative requirements -- OJP considers a procurement "contract" (and therefore does not consider a subaward).

The details of the requirement for advance approval to use a noncompetitive approach in a procurement contract under an OJP award are posted on the OJP website at <https://ojp.gov/funding/Explore/NoncompetitiveProcurement.htm> (Award condition: Specific post-award approval required to use a noncompetitive approach in a procurement contract (if contract would exceed Simplified Acquisition Threshold)), and are incorporated by reference here.

Condition 6

Federal Civil Rights and Nondiscrimination Laws (certification)

The recipient agrees that its compliance with all applicable Federal civil rights and nondiscrimination laws is material to the government's decision to make this award and any payment thereunder, including for purposes of the False Claims Act (31 U.S.C. 3729-3730 and 3801-3812), and, by accepting this award, certifies that it does not operate any programs (including any such programs having components relating to diversity, equity, and inclusion) that violate any applicable Federal civil rights or nondiscrimination laws.

Condition 7

Requirements of the award; remedies for non-compliance or for materially false statements

The conditions of this award are material requirements of the award. Compliance with any assurances or certifications submitted by or on behalf of the recipient that relate to conduct during the period of performance also is a material requirement of this award.

Limited Exceptions. In certain special circumstances, the U.S. Department of Justice ("DOJ") may determine that a legal notice regarding award requirements is necessary or that it will not enforce, or enforce only in part, one or more requirements otherwise applicable to the award. Any such notice or exception regarding enforcement, including any such notice or exception made during the period of performance, is (or will be during the period of performance) set out through the Office of Justice Programs ("OJP") webpage entitled "Legal Notices: Special circumstances as to particular award conditions" (ojp.gov/funding/Explore/LegalNotices-AwardReqs.htm), and incorporated by reference into the award.

By signing and accepting this award on behalf of the recipient, the authorized recipient official accepts all material requirements of the award, and specifically adopts, as if personally executed by the authorized recipient official, all assurances or certifications submitted by or on behalf of the recipient that relate to conduct during the period of performance.

Failure to comply with one or more award requirements -- whether a condition set out in full below, a condition incorporated by reference below, or an assurance or certification related to conduct during the award period -- may result in OJP taking appropriate action with respect to the recipient and the award. Among other things, the OJP may withhold award funds, disallow costs, or suspend or terminate the award. DOJ, including OJP, also may take other legal action as appropriate.

Any materially false, fictitious, or fraudulent statement to the federal government related to this award (or concealment or omission of a material fact) may be the subject of criminal prosecution (including under 18 U.S.C. 1001 and/or 1621, and/or 34 U.S.C. 10271-10273), and also may lead to imposition of civil penalties and administrative remedies for false claims or otherwise (including under 31 U.S.C. 3729-3730 and 3801-3812).

Should any provision of a requirement of this award be held to be invalid or unenforceable by its terms, that provision shall first be applied with a limited construction so as to give it the maximum effect permitted by law. Should it be held, instead, that the provision is utterly invalid or -unenforceable, such provision shall be deemed severable from this award.

Condition 8

Effect of failure to address audit issues

The recipient understands and agrees that the DOJ awarding agency (OJP or OVW, as appropriate) may withhold award funds, or may impose other related requirements, if (as determined by the DOJ awarding agency) the recipient does not satisfactorily and promptly address outstanding issues from audits required by the Part 200 Uniform Requirements (or by the terms of this award), or other outstanding issues that arise in connection with audits, investigations, or reviews of DOJ awards.

Condition 9

Applicability of Part 200 Uniform Requirements

The Uniform Administrative Requirements, Cost Principles, and Audit Requirements in 2 C.F.R. Part 200, as adopted and supplemented by DOJ in 2 C.F.R. Part 2800 (together, the "Part 200 Uniform Requirements"), including, without limitation, the provisions regarding termination in 2 C.F.R. 200.340, apply to this award from OJP.

For more information and resources on the Part 200 Uniform Requirements as they relate to OJP awards and subawards ("subgrants"), see the OJP website at <https://ojp.gov/funding/Part200UniformRequirements.htm>.

Record retention and access: Records pertinent to the award that the recipient (and any subrecipient ("subgrantee") at any tier) must retain -- typically for a period of 3 years from the date of submission of the final expenditure report (SF 425), unless a different retention period applies -- and to which the recipient (and any subrecipient ("subgrantee") at any tier) must provide access, include performance measurement information, in addition to the financial records, supporting documents, statistical records, and other pertinent records indicated at 2 C.F.R. 200.334.

In the event that an award-related question arises from documents or other materials prepared or distributed by OJP that may appear to conflict with, or differ in some way from, the provisions of the Part 200 Uniform Requirements, the recipient is to contact OJP promptly for clarification.

Condition 10

Reporting potential fraud, waste, and abuse, and similar misconduct

The recipient, and any subrecipients ("subgrantees") at any tier, must promptly refer to the DOJ Office of the Inspector General (OIG) any credible evidence that a principal, employee, agent, subrecipient, contractor, subcontractor, or other person has, in connection with funds under this award-- (1) submitted a claim that violates the False Claims Act; or (2) committed a criminal or civil violation of laws pertaining to fraud, conflict of interest, bribery, gratuity, or similar misconduct.

Potential fraud, waste, abuse, or misconduct involving or relating to funds under this award should be reported to the OIG by--(1) online submission accessible via the OIG webpage at <https://oig.justice.gov/hotline/contact-grants.htm> (select "Submit Report Online"); (2) mail directed to: U.S. Department of Justice, Office of the Inspector General, Investigations Division, ATTN: Fraud Detection Office, 950 Pennsylvania Ave., NW, Washington, DC 20530; and/or (3) by facsimile directed to the DOJ OIG Investigations Division (Attn: Grantee Reporting) at (202) 616-9881 (fax).

Additional information is available from the DOJ OIG website at <https://oig.justice.gov/hotline>.

Condition 11

Requirements related to "de minimis" indirect cost rate

A recipient that is eligible under the Part 200 Uniform Requirements and other applicable law to use the "de minimis" indirect cost rate described in 2 C.F.R. 200.414(f), and that elects to use the "de minimis" indirect cost rate, must advise OJP in writing of both its eligibility and its election, and must comply with all associated requirements in the Part

200 Uniform Requirements. The "de minimis" rate may be applied only to modified total direct costs (MTDC) as defined by the Part 200 Uniform Requirements.

Condition 12

Compliance with applicable rules regarding approval, planning, and reporting of conferences, meetings, trainings, and other events

The recipient, and any subrecipient ("subgrantee") at any tier, must comply with all applicable laws, regulations, policies, and official DOJ guidance (including specific cost limits, prior approval and reporting requirements, where applicable) governing the use of federal funds for expenses related to conferences (as that term is defined by DOJ), including the provision of food and/or beverages at such conferences, and costs of attendance at such conferences.

Information on the pertinent DOJ definition of conferences and the rules applicable to this award appears in the DOJ Grants Financial Guide (currently, as section 3.10 of "Postaward Requirements" in the "DOJ Grants Financial Guide").

Condition 13

Requirement for data on performance and effectiveness under the award

The recipient must collect and maintain data that measure the performance and effectiveness of work under this award. The data must be provided to OJP in the manner (including within the timeframes) specified by OJP in the program solicitation or other applicable written guidance. Data collection supports compliance with the Government Performance and Results Act (GPRA) and the GPRA Modernization Act of 2010, and other applicable laws.

Condition 14

Compliance with DOJ Grants Financial Guide

References to the DOJ Grants Financial Guide are to the DOJ Grants Financial Guide as posted on the OJP website (currently, the "DOJ Grants Financial Guide" available at <https://ojp.gov/financialguide/DOJ/index.htm>), including any updated version that may be posted during the period of performance. The recipient agrees to comply with the DOJ Grants Financial Guide.

Condition 15

Compliance with DOJ regulations pertaining to civil rights and nondiscrimination - 28 C.F.R. Part 42

The recipient, and any subrecipient ("subgrantee") at any tier, must comply with all applicable requirements of 28 C.F.R. Part 42, specifically including 28 C.F.R. § 42.106(d), 28 C.F.R. § 42.405(c), and 28 C.F.R. § 42.505(f), which contain notice requirements that covered recipients must follow regarding the dissemination of information regarding federal nondiscrimination requirements.

Condition 16

Determination of suitability to interact with participating minors

SCOPE. This condition applies to this award if it is indicated -- in the application for the award (as approved by DOJ)(or in the application for any subaward, at any tier), the DOJ funding announcement (solicitation), or an associated federal statute -- that a purpose of some or all of the activities to be carried out under the award (whether by the recipient, or a subrecipient at any tier) is to benefit a set of individuals under 18 years of age.

The recipient, and any subrecipient at any tier, must make determinations of suitability before certain individuals may interact with participating minors. This requirement applies regardless of an individual's employment status.

The details of this requirement are posted on the OJP web site at <https://ojp.gov/funding/Explore/Interact-Minors.htm> (Award condition: Determination of suitability required, in advance, for certain individuals who may interact with participating minors), and are incorporated by reference here.

Condition 17

Requirement to disclose whether recipient is designated "high risk" by a federal grant-making agency outside of DOJ

If the recipient is designated "high risk" by a federal grant-making agency outside of DOJ, currently or at any time during the course of the period of performance under this award, the recipient must disclose that fact and certain related information to OJP by email at OJP.ComplianceReporting@ojp.usdoj.gov. For purposes of this disclosure, high risk includes any status under which a federal awarding agency provides additional oversight due to the recipient's past performance, or other programmatic or financial concerns with the recipient. The recipient's disclosure must include the following: 1. The federal awarding agency that currently designates the recipient high risk, 2. The date the recipient was designated high risk, 3. The high-risk point of contact at that federal awarding agency (name, phone number, and email address), and 4. The reasons for the high-risk status, as set out by the federal awarding agency.

Condition 18

Employment eligibility verification for hiring under the award

1. The recipient (and any subrecipient at any tier) must--

A. Ensure that, as part of the hiring process for any position within the United States that is or will be funded (in whole or in part) with award funds, the recipient (or any subrecipient) properly verifies the employment eligibility of the individual who is being hired, consistent with the provisions of 8 U.S.C. 1324a(a)(1).

B. Notify all persons associated with the recipient (or any subrecipient) who are or will be involved in activities under this award of both--

(1) this award requirement for verification of employment eligibility, and

(2) the associated provisions in 8 U.S.C. 1324a(a)(1) that, generally speaking, make it unlawful, in the United States, to hire (or recruit for employment) certain aliens.

C. Provide training (to the extent necessary) to those persons required by this condition to be notified of the award requirement for employment eligibility verification and of the associated provisions of 8 U.S.C. 1324a(a)(1).

D. As part of the recordkeeping for the award (including pursuant to the Part 200 Uniform Requirements), maintain records of all employment eligibility verifications pertinent to compliance with this award condition in accordance with Form I-9 record retention requirements, as well as records of all pertinent notifications and trainings.

2. Monitoring

The recipient's monitoring responsibilities include monitoring of subrecipient compliance with this condition.

3. Allowable costs

To the extent that such costs are not reimbursed under any other federal program, award funds may be obligated for the reasonable, necessary, and allocable costs (if any) of actions designed to ensure compliance with this condition.

4. Rules of construction

A. Staff involved in the hiring process

For purposes of this condition, persons "who are or will be involved in activities under this award" specifically includes (without limitation) any and all recipient (or any subrecipient) officials or other staff who are or will be involved in the hiring process with respect to a position that is or will be funded (in whole or in part) with award funds.

B. Employment eligibility confirmation with E-Verify

For purposes of satisfying the requirement of this condition regarding verification of employment eligibility, the recipient (or any subrecipient) may choose to participate in, and use, E-Verify (www.e-verify.gov), provided an appropriate person authorized to act on behalf of the recipient (or subrecipient) uses E-Verify (and follows the proper E-Verify procedures, including in the event of a "Tentative Nonconfirmation" or a "Final Nonconfirmation") to confirm employment eligibility for each hiring for a position in the United States that is or will be funded (in whole or in part) with award funds.

C. "United States" specifically includes the District of Columbia, Puerto Rico, Guam, the Virgin Islands of the United States, and the Commonwealth of the Northern Mariana Islands.

D. Nothing in this condition shall be understood to authorize or require any recipient, any subrecipient at any tier, or any person or other entity, to violate any federal law, including any applicable civil rights or nondiscrimination law.

E. Nothing in this condition, including in paragraph 4.B., shall be understood to relieve any recipient, any subrecipient at any tier, or any person or other entity, of any obligation otherwise imposed by law, including 8 U.S.C. 1324a(a)(1).

Questions about E-Verify should be directed to DHS. For more information about E-Verify visit the E-Verify website (<https://www.e-verify.gov/>) or email E-Verify at E-Verify@dhs.gov. E-Verify employer agents can email E-Verify at VerifyEmployerAgent@dhs.gov.

Questions about the meaning or scope of this condition should be directed to OJP, before award acceptance.

Condition 19

Encouragement of policies to ban text messaging while driving

Pursuant to Executive Order 13513, "Federal Leadership on Reducing Text Messaging While Driving," 74 Fed. Reg. 51225 (October 1, 2009), DOJ encourages recipients and subrecipients ("subgrantees") to adopt and enforce policies banning employees from text messaging while driving any vehicle during the course of performing work funded by this award, and to establish workplace safety policies and conduct education, awareness, and other outreach to decrease crashes caused by distracted drivers.

Condition 20

Reclassification of various statutory provisions to a new Title 34 of the United States Code

On September 1, 2017, various statutory provisions previously codified elsewhere in the U.S. Code were editorially reclassified (that is, moved and renumbered) to a new Title 34, entitled "Crime Control and Law Enforcement." The reclassification encompassed a number of statutory provisions pertinent to OJP awards (that is, OJP grants and cooperative agreements), including many provisions previously codified in Title 42 of the U.S. Code.

Effective as of September 1, 2017, any reference in this award document to a statutory provision that has been reclassified to the new Title 34 of the U.S. Code is to be read as a reference to that statutory provision as reclassified to Title 34. This rule of construction specifically includes references set out in award conditions, references set out in material incorporated by reference through award conditions, and references set out in other award requirements.

Condition 21

Restrictions and certifications regarding non-disclosure agreements and related matters

No recipient or subrecipient ("subgrantee") under this award, or entity that receives a procurement contract or subcontract with any funds under this award, may require any employee or contractor to sign an internal confidentiality agreement or statement that prohibits or otherwise restricts, or purports to prohibit or restrict, the reporting (in accordance with law) of waste, fraud, or abuse to an investigative or law enforcement representative of a federal department or agency authorized to receive such information.

The foregoing is not intended, and shall not be understood by the agency making this award, to contravene requirements applicable to Standard Form 312 (which relates to classified information), Form 4414 (which relates to sensitive compartmented information), or any other form issued by a federal department or agency governing the nondisclosure of classified information.

1. In accepting this award, the recipient--

a. represents that it neither requires nor has required internal confidentiality agreements or statements from employees or contractors that currently prohibit or otherwise currently restrict (or purport to prohibit or restrict) employees or contractors from reporting waste, fraud, or abuse as described above; and

b. certifies that, if it learns or is notified that it is or has been requiring its employees or contractors to execute agreements or statements that prohibit or otherwise restrict (or purport to prohibit or restrict), reporting of waste, fraud, or abuse as described above, it will immediately stop any further obligations of award funds, will provide prompt written notification to the federal agency making this award, and will resume (or permit resumption of) such obligations only if expressly authorized to do so by that agency.

2. If the recipient does or is authorized under this award to make subawards ("subgrants"), procurement contracts, or both--

a. it represents that--

(1) it has determined that no other entity that the recipient's application proposes may or will receive award funds (whether through a subaward ("subgrant"), procurement contract, or subcontract under a procurement contract) either requires or has required internal confidentiality agreements or statements from employees or contractors that currently prohibit or otherwise currently restrict (or purport to prohibit or restrict) employees or contractors from reporting waste, fraud, or abuse as described above; and

(2) it has made appropriate inquiry, or otherwise has an adequate factual basis, to support this representation; and

b. it certifies that, if it learns or is notified that any subrecipient, contractor, or subcontractor entity that receives funds under this award is or has been requiring its employees or contractors to execute agreements or statements that prohibit or otherwise restrict (or purport to prohibit or restrict), reporting of waste, fraud, or abuse as described above, it will immediately stop any further obligations of award funds to or by that entity, will provide prompt written notification to the federal agency making this award, and will resume (or permit resumption of) such obligations only if expressly authorized to do so by that agency.

Condition 22

OJP Training Guiding Principles

Any training or training materials that the recipient -- or any subrecipient ("subgrantee") at any tier -- develops or delivers with OJP award funds must adhere to the OJP Training Guiding Principles for Grantees and Subgrantees, available at <https://www.ojp.gov/funding/implement/training-guiding-principles-grantees-and-subgrantees>.

Condition 23

Requirement to report potentially duplicative funding

If the recipient currently has other active awards of federal funds, or if the recipient receives any other award of federal funds during the period of performance for this award, the recipient promptly must determine whether funds from any of those other federal awards have been, are being, or are to be used (in whole or in part) for one or more of the identical cost items for which funds are provided under this award. If so, the recipient must promptly notify the DOJ awarding agency (OJP or OVW, as appropriate) in writing of the potential duplication, and, if so requested by the DOJ awarding agency, must seek a budget-modification or change-of-project-scope Grant Award Modification (GAM) to eliminate any inappropriate duplication of funding.

Condition 24

Required training for Grant Award Administrator and Financial Manager

The Grant Award Administrator and all Financial Managers for this award must have successfully completed an "OJP financial management and grant administration training" by 120 days after the date of the recipient's acceptance of the award. Successful completion of such a training on or after January 1, 2022, will satisfy this condition.

In the event that either the Grant Award Administrator or a Financial Manager for this award changes during the period of performance, the new Grant Award Administrator or Financial Manager must have successfully completed an "OJP financial management and grant administration training" by 120 calendar days after the date the Entity Administrator enters updated Grant Award Administrator or Financial Manager information in JustGrants. Successful completion of such a training on or after January 1, 2022, will satisfy this condition.

A list of OJP trainings that OJP will consider "OJP financial management and grant administration training" for

purposes of this condition is available at <https://onlinegfmt.training.ojp.gov/>. All trainings that satisfy this condition include a session on grant fraud prevention and detection.

The recipient should anticipate that OJP will immediately withhold ("freeze") award funds if the recipient fails to comply with this condition. The recipient's failure to comply also may lead OJP to impose additional appropriate conditions on this award.

Condition 25

Compliance with 41 U.S.C. 4712 (including prohibitions on reprisal; notice to employees)

The recipient (and any subrecipient at any tier) must comply with, and is subject to, all applicable provisions of 41 U.S.C. 4712, including all applicable provisions that prohibit, under specified circumstances, discrimination against an employee as reprisal for the employee's disclosure of information related to gross mismanagement of a federal grant, a gross waste of federal funds, an abuse of authority relating to a federal grant, a substantial and specific danger to public health or safety, or a violation of law, rule, or regulation related to a federal grant.

The recipient also must inform its employees, in writing (and in the predominant native language of the workforce), of employee rights and remedies under 41 U.S.C. 4712.

Should a question arise as to the applicability of the provisions of 41 U.S.C. 4712 to this award, the recipient is to contact the DOJ awarding agency (OJP or OVW, as appropriate) for guidance.

Condition 26

Potential imposition of additional requirements

The recipient agrees to comply with any additional requirements that may be imposed by the DOJ awarding agency (OJP or OVW, as appropriate) during the period of performance for this award, if the recipient is designated as "high-risk" for purposes of the DOJ high-risk grantee list.

Condition 27

Requirement to report actual or imminent breach of personally identifiable information (PII)

The recipient (and any "subrecipient" at any tier) must have written procedures in place to respond in the event of an actual or imminent "breach" (OMB M-17-12) if it (or a subrecipient) -- (1) creates, collects, uses, processes, stores, maintains, disseminates, discloses, or disposes of "Personally Identifiable Information (PII)" (2 CFR 200.1) within the scope of an OJP grant-funded program or activity, or (2) uses or operates a "Federal information system" (OMB Circular A-130). The recipient's breach procedures must include a requirement to report actual or imminent breach of PII to an OJP Program Manager no later than 24 hours after an occurrence of an actual breach, or the detection of an imminent breach.

Condition 28

Requirements related to System for Award Management and Universal Identifier Requirements

The recipient must comply with applicable requirements regarding the System for Award Management (SAM), currently accessible at <https://www.sam.gov/>. This includes applicable requirements regarding registration with SAM, as well as maintaining the currency of information in SAM.

The recipient also must comply with applicable restrictions on subawards ("subgrants") to first-tier subrecipients (first-tier "subgrantees"), including restrictions on subawards to entities that do not acquire and provide (to the recipient) the unique entity identifier required for SAM registration.

The details of the recipient's obligations related to SAM and to unique entity identifiers are posted on the OJP web site at <https://ojp.gov/funding/Explore/SAM.htm> (Award condition: System for Award Management (SAM) and Universal Identifier Requirements), and are incorporated by reference here.

This condition does not apply to an award to an individual who received the award as a natural person (i.e., unrelated to any business or non-profit organization that he or she may own or operate in his or her name).

Condition 29**Restrictions on "lobbying"**

In general, as a matter of federal law, federal funds awarded by OJP may not be used by the recipient, or any subrecipient ("subgrantee") at any tier, either directly or indirectly, to support or oppose the enactment, repeal, modification, or adoption of any law, regulation, or policy, at any level of government. See 18 U.S.C. 1913. (There may be exceptions if an applicable federal statute specifically authorizes certain activities that otherwise would be barred by law.)

Another federal law generally prohibits federal funds awarded by OJP from being used by the recipient, or any subrecipient at any tier, to pay any person to influence (or attempt to influence) a federal agency, a Member of Congress, or Congress (or an official or employee of any of them) with respect to the awarding of a federal grant or cooperative agreement, subgrant, contract, subcontract, or loan, or with respect to actions such as renewing, extending, or modifying any such award. See 31 U.S.C. 1352. Certain exceptions to this law apply, including an exception that applies to Indian tribes and tribal organizations.

Should any question arise as to whether a particular use of federal funds by a recipient (or subrecipient) would or might fall within the scope of these prohibitions, the recipient is to contact OJP for guidance, and may not proceed without the express prior written approval of OJP.

Condition 30**Compliance with DOJ regulations pertaining to civil rights and nondiscrimination - 28 C.F.R. Part 54**

The recipient, and any subrecipient ("subgrantee") at any tier, must comply with all applicable requirements of 28 C.F.R. Part 54, which relates to nondiscrimination on the basis of sex in certain "education programs."

Among other items, 28 C.F.R. § 54.140 contains notice requirements that covered recipients must follow regarding the dissemination of information regarding federal nondiscrimination requirements.

Condition 31**Justification of consultant rate**

Approval of this award does not indicate approval of any consultant rate in excess of \$650 per day. A detailed justification must be submitted to and approved by the OJP program office prior to obligation or expenditure of such funds.

Condition 32**Copyright; Data rights**

The recipient acknowledges that OJP reserves a royalty-free, non-exclusive, and irrevocable license to reproduce, publish, or otherwise use, and authorize others to use (in whole or in part, including in connection with derivative works), for Federal purposes: (1) any work subject to copyright developed under an award or subaward (at any tier); and (2) any rights of copyright to which a recipient or subrecipient (at any tier) purchases ownership with Federal support.

The recipient acknowledges that OJP has the right to (1) obtain, reproduce, publish, or otherwise use the data first produced under any such award or subaward; and (2) authorize others to receive, reproduce, publish, or otherwise use such data for Federal purposes. "Data" includes data as defined in Federal Acquisition Regulation (FAR) provision 52.227-14 (Rights in Data - General).

It is the responsibility of the recipient (and of each subrecipient (at any tier), if applicable) to ensure that the provisions of this condition are included in any subaward (at any tier) under this award.

The recipient has the responsibility to obtain from subrecipients, contractors, and subcontractors (if any) all rights and data necessary to fulfill the recipient's obligations to the Government under this award. If a proposed subrecipient, contractor, or subcontractor refuses to accept terms affording the Government such rights, the recipient shall promptly bring such refusal to the attention of the OJP program manager for the award and not proceed with the agreement in

question without further authorization from the OJP program office.

Condition 33

Recipient integrity and performance matters: Requirement to report information on certain civil, criminal, and administrative proceedings to SAM and FAPIIS

The recipient must comply with any and all applicable requirements regarding reporting of information on civil, criminal, and administrative proceedings connected with (or connected to the performance of) either this OJP award or any other grant, cooperative agreement, or procurement contract from the federal government. Under certain circumstances, recipients of OJP awards are required to report information about such proceedings, through the federal System for Award Management (known as "SAM"), to the designated federal integrity and performance system (currently, "FAPIIS").

The details of recipient obligations regarding the required reporting (and updating) of information on certain civil, criminal, and administrative proceedings to the federal designated integrity and performance system (currently, "FAPIIS") within SAM are posted on the OJP website at <https://ojp.gov/funding/FAPIIS.htm> (Award condition: Recipient Integrity and Performance Matters, including Recipient Reporting to FAPIIS), and are incorporated by reference here.

Condition 34

FFATA reporting: Subawards and executive compensation

The recipient must comply with applicable requirements to report first-tier subawards ("subgrants") of \$30,000 or more and, in certain circumstances, to report the names and total compensation of the five most highly compensated executives of the recipient and first-tier subrecipients (first-tier "subgrantees") of award funds. The details of recipient obligations, which derive from the Federal Funding Accountability and Transparency Act of 2006 (FFATA), are set forth in 2 C.F.R. part 170, Appendix A ("Award Term") and are incorporated by reference here.

This condition, including its reporting requirement, does not apply to-- (1) an award of less than \$30,000, or (2) an award made to an individual who received the award as a natural person (i.e., unrelated to any business or non-profit organization that he or she may own or operate in his or her name).

Note: In early March 2025, the reporting system that had been used for subaward reporting, the FFATA (Federal Funding Accountability and Transparency Act) Subaward Reporting System (FSRS) was retired and functionality moved to SAM.gov. For more information, including steps on how to connect your FSRS account to SAM.gov, visit <https://sam.gov/fsrs>.

Condition 35

Limit on use of grant funds for recipients' employees' salaries

With respect to this award, federal funds may not be used to pay cash compensation (salary plus bonuses) to any employee of the award recipient at a rate that exceeds 110% of the maximum annual salary payable to a member of the federal government's Senior Executive Service (SES) at an agency with a Certified SES Performance Appraisal System for that year. (An award recipient may compensate an employee at a higher rate, provided the amount in excess of this compensation limitation is paid with non-federal funds.)

This limitation on compensation rates allowable under this award may be waived on an individual basis at the discretion of the OJP official indicated in the program announcement under which this award is made.

Condition 36

Any website that is funded in whole or in part under this award must include the following statement on the home page, on all major entry pages (i.e., pages (exclusive of documents) whose primary purpose is to navigate the user to interior content), and on any pages from which a visitor may access or use a web-based service, including any pages that provide results or outputs from the service:

"This website is funded [insert "in part," if applicable] through a grant from the [insert name of OJP component], Office of Justice Programs, U.S. Department of Justice. Neither the U.S. Department of Justice nor any of its components operate, control, are responsible for, or necessarily endorse, this website (including, without limitation, its content, technical infrastructure, and policies, and any services or tools provided)."

The full text of the foregoing statement must be clearly visible on the home page. On other pages, the statement may

be included through a link, entitled "Notice of Federal Funding and Federal Disclaimer," to the full text of the statement.

Condition 37

The recipient agrees to submit a final report at the end of this award documenting all relevant project activities during the entire period of support under this award. This report will include detailed information about the project(s) funded, including, but not limited to, information about how the funds were actually used for each purpose area, data to support statements of progress, and data concerning individual results and outcomes of funded projects reflecting project successes and impacts. The final report is due no later than 120 days following the close of this award period or the expiration of any extension periods. This report will be submitted to the Office of Justice Programs at <https://justgrants.usdoj.gov/>

Condition 38

The recipient shall submit semiannual performance reports. Performance reports shall be submitted within 30 days after the end of the reporting periods, which are June 30 and December 31, for the life of the award. These reports will be submitted to the Office of Justice Programs, on-line through the Internet at <https://justgrants.usdoj.gov>

Condition 39

Cooperating with OJP Monitoring

The recipient agrees to cooperate with OJP monitoring of this award pursuant to OJP's guidelines, protocols, and procedures, and to cooperate with OJP (including the grant manager for this award and the Office of Chief Financial Officer (OCFO)) requests related to such monitoring, including requests related to desk reviews and/or site visits. The recipient agrees to provide to OJP all documentation necessary for OJP to complete its monitoring tasks, including documentation related to any subawards made under this award. Further, the recipient agrees to abide by reasonable deadlines set by OJP for providing the requested documents. Failure to cooperate with OJP's monitoring activities may result in actions that affect the recipient's DOJ awards, including, but not limited to: withholdings and/or other restrictions on the recipient's access to award funds; referral to the DOJ OIG for audit review; designation of the recipient as a DOJ High Risk grantee; or termination of an award(s).

Condition 40

The recipient agrees that it will submit quarterly financial status reports (the SF 425 Federal Financial Report) to OJP in JustGrants, no later than the deadlines set out in the DOJ Financial Guide and the JustGrants guidance (typically 30 days after the end of each calendar quarter). Delinquent reports may lead to funds being frozen and other remedies.

Condition 41

Confidentiality of data

The recipient (and any subrecipient at any tier) must comply with all confidentiality requirements of 34 U.S.C. 10231 and 28 C.F.R. Part 22 that are applicable to collection, use, and revelation of data or information. The recipient further agrees, as a condition of award approval, to submit a Privacy Certificate that is in accord with requirements of 28 C.F.R. Part 22 and, in particular, 28 C.F.R. 22.23 for any applicable project.

Condition 42

The recipient's budget (and budget narrative) is pending clearance by OJP.

Prior to budget clearance (and unless there is a more restrictive condition on this award, in which case the terms of that more restrictive condition apply): The recipient may not drawdown more than 10% of the award. Pre-clearance obligations, expenditures, and drawdowns may be disallowed if not in compliance with program requirements.

The recipient should be judicious in using award funds prior to budget clearance. Generally, OJP expects that recipients (depending on the specific project scope) may need to advertise for award-funded positions, pay personnel and fringe benefits for positions budgeted under the award, plan for project activities, attend training and pay training-related travel needed to begin the project, and engage in other limited activities conducted by recipient staff (i.e., generally not requiring a subaward or procurement contract under an award).

OJP will issue an Award Condition Modification upon budget clearance.

Condition 43

The recipient may not expend, or draw down any award funds for indirect costs, unless and until either -- (1) the recipient submits to OJP a current, federally-approved indirect cost rate agreement, or (2) the recipient determines that it is eligible under the Part 200 Uniform Requirements to use the "de minimis" indirect cost rate described in 2 C.F.R. 200.414(f), and advises OJP in writing of both its eligibility and its election.

The financial review of the budget for this award is pending. If the OJP Office of the Chief Financial Officer (OCFO) determines as part of its financial review that the recipient already has submitted the documentation concerning indirect costs described above, this condition will be released through an Award Condition Modification (ACM) upon completion of the OCFO final budget review.

If the OJP OCFO instead determines as part of its financial review that the recipient has not yet submitted the required documentation concerning indirect costs, this condition will not be released until OJP (including its OCFO) receives and reviews a satisfactory submission.

Condition 44

As of the first day of the period of performance for the award, the recipient may choose to incur project costs using non-federal funds, but any such project costs are incurred at the recipient's risk until, at a minimum, all applicable withholding conditions are removed by OJP (via an Award Condition Modification (ACM)).

Except to the extent (if any) that an award condition expressly precludes reimbursement of project costs incurred "at-risk," if and when the recipient makes a valid acceptance of this award and OJP removes each applicable withholding condition through an Award Condition Modification (ACM), the recipient is authorized to reimburse itself for project costs incurred "at-risk" earlier during the period of performance (such as project costs incurred prior to award acceptance or prior to removal of an applicable withholding condition), provided that those project costs otherwise are allowable costs under the award.

Condition 45**OJJDP- Printing and Publications**

The recipient shall submit to OJJDP a copy of all interim and final reports and proposed publications (including those prepared for conferences, journals, and other presentations) resulting from this award, for review and comment prior to publishing. Any publication produced with grant funds must contain the following statement: "This project was supported by Grant # () awarded by the Office of Juvenile Justice and Delinquency Prevention, Office of Justice Programs, U.S. Department of Justice. The opinions, findings, and conclusions or recommendations expressed in this publication/program/exhibition are those of the author(s) and do not necessarily reflect those of the Department of Justice. All reports and products may be required to display the OJJDP logo on the cover (or other location) with the agreement of OJJDP. OJJDP defines publications as any planned, written, visual or sound materials substantively based on the project, formally prepared by the award recipient for dissemination to the public.

Condition 46

All electronic and information technology materials developed or maintained under this award must be compliant with Section 508 of the Rehabilitation Act of 1973. Please refer to www.section508.gov for more detail.

[] *I have read and understand the information presented in this section of the Federal Award Instrument.*

Award Acceptance**Declaration and Certification to the U.S. Department of Justice as to Acceptance**

By checking the declaration and certification box below, I--

A. Declare to the U.S. Department of Justice (DOJ), under penalty of perjury, that I have authority to make this

declaration and certification on behalf of the applicant.

B. Certify to DOJ, under penalty of perjury, on behalf of myself and the applicant, to the best of my knowledge and belief, that the following are true as of the date of this award acceptance: (1) I have conducted or there was conducted (including by applicant's legal counsel as appropriate and made available to me) a diligent review of all terms and conditions of, and all supporting materials submitted in connection with, this award, including any assurances and certifications (including anything submitted in connection therewith by a person on behalf of the applicant before, after, or at the time of the application submission and any materials that accompany this acceptance and certification); and (2) I have the legal authority to accept this award on behalf of the applicant.

C. Accept this award on behalf of the applicant.

D. Declare the following to DOJ, under penalty of perjury, on behalf of myself and the applicant: (1) I understand that, in taking (or not taking) any action pursuant to this declaration and certification, DOJ will rely upon this declaration and certification as a material representation; and (2) I understand that any materially false, fictitious, or fraudulent information or statement in this declaration and certification (or concealment or omission of a material fact as to either) may be the subject of criminal prosecution (including under 18 U.S.C. §§ 1001 and/or 1621, and/or 34 U.S.C. §§ 10271-10273), and also may subject me and the applicant to civil penalties and administrative remedies under the federal False Claims Act (including under 31 U.S.C. §§ 3729-3730 and/or §§ 3801-3812) or otherwise.

Agency Approval

Title of Approving Official
Deputy Assistant Attorney General

Name of Approving Official
Maureen A. Henneberg

Signed Date And Time
9/29/26 8:02 PM

Authorized Representative

☐ Declaration and Certification

Entity Acceptance

Title of Authorized Entity Official
no value

Signed Date And Time
no value



Department of Justice (DOJ)

Office of Community Oriented Policing Services (COPS Office)

Washington, D.C. 20531

Name and Address of Recipient:	CITY OF PORTSMOUTH NH 1 JUNKINS AVE
City, State and Zip:	PORTSMOUTH, NH 03801
Recipient UEI:	XTL2C874AZN7
Project Title: Portsmouth Police IT & Security	Award Number: 15JCOPS-26-GG-00535-TECP
Solicitation Title: FY26 COPS Technology and Equipment Program	
Federal Award Amount: \$1,031,000.00	Federal Award Date: 9/25/26
Awarding Agency:	Office of Community Oriented Policing Services
Award Type:	Initial
Funding Instrument Type:	Grant
Opportunity Category: D	
Assistance Listing: 16.710 - Public Safety Partnership and Community Policing Grants	
Project Period Start Date: 1/23/26	Project Period End Date: 1/31/28
Budget Period Start Date: 1/23/26	Budget Period End Date: 1/31/28

Project Description:
The FY26 Technology and Equipment Program (TEP) provides funding to state, territorial, local, Tribal, and other entities designated under the heading Community Oriented Policing Services, Technology and Equipment Community Projects / COPS Law Enforcement Technology and Equipment in the Congressional Joint Explanatory Statement – Division C, which is incorporated by reference into Public Law 119-74, to develop and acquire effective law enforcement equipment, technologies and interoperable communications that assist in responding to and preventing crime and expand the implementation of community policing. Equipment funded under this program should meet any applicable requirements of the National Institute of Standards and Technology's Office of Law Enforcement Standards.

Award Letter

September 25, 2026

Dear Seth Tondreault,

On behalf of the Attorney General, it is my pleasure to inform you the Office of Community Oriented Policing Services (the COPS Office) has approved the application submitted by CITY OF PORTSMOUTH NH for an award under the funding opportunity entitled 2026 FY26 COPS Technology and Equipment Program. The approved award amount is \$1,031,000.

Review the Award Instrument below carefully and familiarize yourself with all conditions and requirements before accepting your award. The Award Instrument includes the Award Offer (Award Information, Project Information, Financial Information, and Award Conditions) and Award Acceptance. For COPS Office and OVW funding the Award Offer also includes any Other Award Documents.

Please note that award requirements include not only the conditions and limitations set forth in the Award Offer, but

Page: 1 of 18

also compliance with assurances and certifications that relate to conduct during the period of performance for the award. These requirements encompass financial, administrative, and programmatic matters, as well as other important matters (e.g., specific restrictions on use of funds). Therefore, all key staff should receive the award conditions, the assurances and certifications, and the application as approved by the COPS Office, so that they understand the award requirements. Information on all pertinent award requirements also must be provided to any subrecipient of the award.

Should you accept the award and then fail to comply with an award requirement, DOJ will pursue appropriate remedies for non-compliance, which may include termination of the award and/or a requirement to repay award funds.

Prior to accepting the award, your Entity Administrator must assign a Financial Manager, Grant Award Administrator, and Authorized Representative(s) in the Justice Grants System (JustGrants). The Entity Administrator will need to ensure the assigned Authorized Representative(s) is current and has the legal authority to accept awards and bind the entity to the award terms and conditions. To accept the award, the Authorized Representative(s) must accept all parts of the Award Offer in the Justice Grants System (JustGrants), including by executing the required declaration and certification, within 45 days from the award date.

To access your funds, you will need to enroll in the Automated Standard Application for Payments (ASAP) system, if you haven't already completed the enrollment process in ASAP. The Entity Administrator should have already received an email from ASAP to initiate this process.

Congratulations, and we look forward to working with you.

Cory D. Randolph
COPS Office Deputy Director

Office for Civil Rights Notice for All Recipients

The Office for Civil Rights (OCR), Office of Justice Programs (OJP), U.S. Department of Justice (DOJ) enforces federal civil rights laws and other provisions that prohibit discrimination by recipients of federal financial assistance from OJP, the Office of Community Oriented Policing Services (COPS), and the Office on Violence Against Women (OVW).

Several civil rights laws, including Title VI of the Civil Rights Act of 1964 and Section 504 of the Rehabilitation Act of 1973, require recipients of federal financial assistance (recipients) to give assurances that they will comply with those laws. Taken together, these and other civil rights laws prohibit recipients from discriminating in the provision of services and employment because of race, color, national origin, religion, disability, and sex or from discriminating in the provision of services on the bases of age.

Some recipients of DOJ financial assistance have additional obligations to comply with other applicable nondiscrimination provisions like the Omnibus Crime Control and Safe Streets Act of 1968, which prohibits discrimination on the basis of religion in addition to race, color, national origin, and sex. Recipients may also have related requirements regarding the development and implementation of equal employment opportunity programs.

OCR provides technical assistance, training, and other resources to help recipients comply with civil rights obligations. Further, OCR administratively enforces civil rights laws and nondiscrimination provisions by investigating DOJ recipients that are the subject of discrimination complaints. In addition, OCR conducts compliance reviews of DOJ recipients based on regulatory criteria. These investigations and compliance reviews permit OCR to evaluate whether DOJ recipients are providing services to the public and engaging in employment practices in a nondiscriminatory manner.

For more information about OCR, your civil rights and nondiscrimination responsibilities, how to notify your employees or beneficiaries of their civil rights protections and responsibilities and how to file a complaint, as well as technical assistance, training, and other resources, please visit www.ojp.gov/program/civil-rights-office/outreach. If you would like OCR to assist you in fulfilling your civil rights or nondiscrimination responsibilities, please contact us at askOCR@oip.usdoj.gov or www.ojp.gov/program/civil-rights-office/about#ocr-contacts.

Award Information

This award is offered subject to the conditions or limitations set forth in the Award Information, Project Information, Financial Information, and Award Conditions.

Recipient Information

Recipient Name

UEI

XTL2C874AZN7

ORI Number

Street 1

1 JUNKINS AVE

Street 2

City

PORTSMOUTH

State/U.S. Territory

New Hampshire

Zip/Postal Code

03801

Country

United States

County/Parish

Province

Award Details

Federal Award Date

9/25/26

Award Type

Initial

Award Number

15JCOPS-26-GG-00535-TECP

Supplement Number

00

Federal Award Amount

\$1,031,000.00

Funding Instrument Type

Grant

Assistance Listing

Number

16.710

Assistance Listings Program Title

Public Safety Partnership and Community Policing Grants

Statutory Authority

Omnibus Crime Control and Safe Streets Act of 1968, as amended, and the Violent Crime Control and Law Enforcement Act of 1994, Title I, Part Q, Public Law 103-322, 34 U.S.C. § 10381 et seq.

☐ I have read and understand the information presented in this section of the Federal Award Instrument.

Project Information

This award is offered subject to the conditions or limitations set forth in the Award Information, Project Information, Financial Information, and Award Conditions.

Solicitation Title

Awarding Agency

Application Number
GRANT14702819

Grant Manager Name
Tyler Turnbull

Phone Number
202-445-6351

E-mail Address
tyler.turnbull@usdoj.gov

Project Title
Portsmouth Police IT & Security

Performance Period Start Date
01/23/2026

Performance Period End Date
01/31/2028

Budget Period Start Date
01/23/2026

Budget Period End Date
01/31/2028

Project Description

The FY26 Technology and Equipment Program (TEP) provides funding to state, territorial, local, Tribal, and other entities designated under the heading Community Oriented Policing Services, Technology and Equipment Community Projects / COPS Law Enforcement Technology and Equipment in the Congressional Joint Explanatory Statement – Division C, which is incorporated by reference into Public Law 119-74, to develop and acquire effective law enforcement equipment, technologies and interoperable communications that assist in responding to and preventing crime and expand the implementation of community policing. Equipment funded under this program should meet any applicable requirements of the National Institute of Standards and Technology's Office of Law Enforcement Standards.

[] I have read and understand the information presented in this section of the Federal Award Instrument.

Financial Information

This award is offered subject to the conditions or limitations set forth in the Award Information, Project Information, Financial Information, and Award Conditions.

A financial analysis of budgeted costs has been completed. All costs listed in the approved budget below were programmatically approved based on the final proposed detailed budget and budget narratives submitted by your agency to the COPS Office. Any adjustments or edits to the proposed budget are explained below.

Budget Clearance Date: 8/4/26 6:27 PM

Budget Summary

Budget Category	Proposed Budget	Change	Approved Budget	Percentages
Sworn Officer Positions:	\$0	\$0	\$0	
Civilian or Non-Sworn Personnel:	\$0	\$0	\$0	
Travel:	\$0	\$0	\$0	

Equipment:	\$886,900	\$0	\$886,900	
Supplies:	\$144,100	\$0	\$144,100	
SubAwards:	\$0	\$0	\$0	
Procurement Contracts:	\$0	\$0	\$0	
Other Costs:	\$0	\$0	\$0	
Total Direct Costs:	\$1,031,000	\$0	\$1,031,000	
Indirect Costs:	\$0	\$0	\$0	
Total Project Costs:	\$1,031,000	\$0	\$1,031,000	
Federal Funds:	\$1,031,000	\$0	\$1,031,000	100.00%
Match Amount:	\$0	\$0	\$0	0.00%
Program Income:	\$0	\$0	\$0	0.00%

☐ I have read and understand the information presented in this section of the Federal Award Instrument.

Other Award Documents

National Environmental Policy Act (NEPA) Notice of Funding Opportunity Title: FY26 COPS Technology and Equipment Program NEPA Determination: Additional Information Required The Technology and Equipment Program (TEP) supports a range of activities through its funding for law enforcement technologies, interoperable communications, and related law enforcement and public safety equipment. As applicable, recipients of funding under this program must assist the Office of Community Oriented Policing Services (COPS Office) in complying with NEPA and other related federal environmental impact analyses requirements in the use of award funds, whether the funds are used directly by the recipient or a third party. Your agency's proposed project scope or location is such that your agency may need to complete an Environmental Assessment (EA) and/or an Environmental Impact Statement (EIS), as directed by COPS Office. Accordingly, prior to obligating funds for any of the activities specified below, your agency must first ensure compliance with all NEPA requirements. At this time, additional information is needed to determine if any of the following activities will be conducted by the recipient or a related third party under this COPS Office award: (1) new construction; (2) any property renovation or remodeling, including, but not limited to, a property: (a) listed in an environmentally or historically sensitive area; (b) listed on or eligible for listing on the National Register of Historic Places; or (c) located within a 100-year flood plain, a wetland, or habitat for an endangered species; (3) a renovation that will change the basic prior use of a facility or significantly change its size; or (4) research and technology whose anticipated and future application could be expected to have an effect on the environment. Please be sure to carefully review the award conditions and the TEP Award Owner's Manual for more information about environmental compliance. If you have any questions about this determination, please contact your COPS Office Grant Manager.

☐ I have read and understand the information presented in this section of the Federal Award Instrument.

Award Conditions

This award is offered subject to the conditions or limitations set forth in the Award Information, Project Information, Financial Information, and Award Conditions.

Condition 1

Restrictions on Internal Confidentiality Agreements: No recipient or subrecipient under this award, or entity that receives a contract or subcontract with any funds under this award, may require any employee or contractor to sign an internal confidentiality agreement or statement that prohibits or otherwise restricts the lawful reporting of waste, fraud, or abuse to an investigative or law enforcement representative of a federal department or agency authorized to receive such information. Consolidated Appropriations Act, 2026, Public Law 119-75, Division E, Title VII, Section 742.

Condition 2

Compliance with 8 U.S.C. § 1373: Authority to obligate or expend contingent on compliance with this condition. State or local government entity recipients of this award, and any subrecipient of this award at any tier that is an entity of a State or of a unit of local government, must comply with 8 U.S.C. §1373, which provides that such entities may not prohibit, or in any way restrict, any government entity or official from sending to, receiving from, maintaining, or exchanging information regarding citizenship or immigration status, lawful or unlawful, of any individual with components of the U.S. Department of Homeland Security or any other federal, state or local government entity. This includes any prohibitions or restrictions imposed or established by a State or local government entity or official.

Any obligations or expenditures of a recipient or subrecipient that are impermissible under this condition shall be unallowable costs for purposes of this award.

References to the Immigration and Naturalization Service in 8 U.S.C. 1373 are to be read, as a legal matter, as references to components of the U.S. Department of Homeland Security.

Condition 3

Federal Civil Rights and Nondiscrimination Laws (certification): The recipient agrees that its compliance with all applicable Federal civil rights and nondiscrimination laws is material to the government's decision to make this award and any payment thereunder, including for purposes of the False Claims Act (31 U.S.C. 3729-3730 and 3801-3812), and, by accepting this award, certifies that it does not operate any programs (including any such programs having components relating to diversity, equity, and inclusion) that violate any applicable Federal civil rights or nondiscrimination laws.

Condition 4

Federal Laws, Presidential Memoranda, and Executive Orders: Recipients of grant funding must comply with all applicable federal laws and Presidential Memoranda and all Executive Orders by the President.

Condition 5

Award Monitoring Activities: Federal law requires that recipients receiving federal funding from the COPS Office must be monitored to ensure compliance with their award conditions and other applicable statutes and regulations. The COPS Office is also interested in tracking the progress of our programs and the advancement of community policing. Both aspects of award implementation—compliance and programmatic benefits—are part of the monitoring process coordinated by the U.S. Department of Justice. Award monitoring activities conducted by the COPS Office include site visits, enhanced office-based grant reviews, alleged noncompliance reviews, financial and programmatic reporting, and audit resolution. As a COPS Office award recipient, you agree to cooperate with and respond to any requests for information pertaining to your award. This includes all financial records, such as general accounting ledgers and all supporting documents. All information pertinent to the implementation of the award is subject to agency review throughout the life of the award, during the close-out process and for three-years after the submission of the final expenditure report. 2 C.F.R. §§ 200.334 and 200.337, and, as applicable, 34 U.S.C. § 10385(a).

Condition 6

Authorized Representative Responsibility: The recipient understands that, in accepting this award, the Authorized Representatives declare and certify, among other things, that they possess the requisite legal authority to accept the award on behalf of the recipient entity and, in so doing, accept (or adopt) all material requirements throughout the period of performance under this award. The recipient further understands, and agrees, that it will not assign anyone to the role of Authorized Representative during the period of performance under the award without first ensuring that the individual has the requisite legal authority.

Condition 7

Contract Provision: All contracts made by the award recipients under the federal award must contain the provisions required under 2 C.F.R. Part 200, Appendix II to Part 200—Contract Provisions for Non-Federal Entity Contracts Under Federal Awards. Please see appendices in the Award Owner's Manual for a full text of the contract provisions.

Condition 8

Award Owner's Manual: The recipient agrees to comply with the terms and conditions in the applicable award year COPS Office Program Award Owner's Manual; DOJ Grants Financial Guide; COPS Office statute (34 U.S.C. § 10381, et seq.) as applicable; Students, Teachers, and Officers Preventing (STOP) School Violence Act of 2018 (34 U.S.C. § 10551, et seq.) as applicable; the requirements of 2 C.F.R. Part 200 (Uniform Administrative Requirements, Cost Principles, and Audit Requirements for Federal Awards), including subsequent changes, as adopted by the U.S. Department of Justice in 2 C.F.R. § 2800.101; 48 C.F.R. Part 31 (FAR Part 31) as applicable (Contract Cost Principles and Procedures); the Cooperative Agreement as applicable; representations made in the application; and all other applicable program requirements, laws, orders, regulations, or circulars.

Failure to comply with one or more award requirements may result in remedial action including, but not limited to, withholding award funds, disallowing costs, suspending, or terminating the award, or other legal action as appropriate.

Should any provision of a condition of this award be held to be invalid or unenforceable by its terms, then that provision shall first be applied with a limited construction so as to give it the maximum effect permitted by law (to any person or circumstance) under this award. Should it be held, instead, that a condition (or a provision thereof) is of utter invalidity or unenforceability, such condition (or such provision) shall be deemed severable from this award.

Condition 9

Federal Civil Rights: The recipient and any subrecipient must comply with applicable federal civil rights and nondiscrimination statutes and regulations including: Section 601 of the Civil Rights Act of 1964 (42 U.S.C. § 2000d), as implemented in Subparts C and D of 28 C.F.R. Part 42; section 504 of the Rehabilitation Act of 1973 (29 U.S.C. § 794), as implemented in Subpart G of 28 C.F.R. Part 42; section 901 of the Education Amendments of 1972 (20 U.S.C. § 1681), as implemented in Subpart D of 28 C.F.R. Parts 42 and 54; section 303 of the Age Discrimination Act of 1975 (42 U.S.C. § 6102), as implemented in Subpart I of 28 C.F.R. Part 42; and section 809(c) of Title I of the Omnibus Crime Control and Safe Streets Act of 1968 (34 U.S.C. § 10228(c)), as implemented in Subpart D of 28 C.F.R. Part 42. In addition to applicable federal statutes and regulations that pertain to civil rights and nondiscrimination, the recipient and any subrecipient must comply with the requirements in 28 C.F.R. Parts 22 (Confidentiality of Identifiable Research and Statistical Information); 28 C.F.R. Part 23 (Criminal Intelligence Systems Operating Policies); 28 C.F.R. Part 38 (Partnerships with Faith-Based and Other Neighborhood Organizations); and 28 C.F.R. Part 46 (Protection of Human Subjects). For an overview of the civil rights laws and nondiscrimination requirements in connection with your award, please see <https://www.ojp.gov/program/civil-rights/overview>.

Condition 10

Duplicative Funding: The recipient understands and agrees to notify the COPS Office if it receives, from any other source, funding for the same item or service also funded under this award.

Condition 11

Prohibited conduct by recipients and subrecipients related to trafficking in persons (including reporting requirements and COPS Office authority to terminate award): The recipient and subrecipient agree to comply with the following requirements of 2 C.F.R. Part 175, Appendix A to Part 175 – Award Term:

I. Trafficking in Persons

(a) Provisions applicable to a recipient that is a private entity. (1) Under this award, the recipient, its employees, subrecipients under this award, and subrecipient's employees must not engage in:

(i) Severe forms of trafficking in persons;

(ii) The procurement of a commercial sex act during the period of time that this award or any subaward is in effect;

(iii) The use of forced labor in the performance of this award or any subaward; or

(iv) Acts that directly support or advance trafficking in persons, including the following acts:

(A) Destroying, concealing, removing, confiscating, or otherwise denying an employee access to that employee's identity or immigration documents;

(B) Failing to provide return transportation or pay for return transportation costs to an employee from a country outside

the United States to the country from which the employee was recruited upon the end of employment if requested by the employee, unless:

- (1) Exempted from the requirement to provide or pay for such return transportation by the Federal department or agency providing or entering into the grant or cooperative agreement; or
- (2) The employee is a victim of human trafficking seeking victim services or legal redress in the country of employment or a witness in a human trafficking enforcement action;
- (C) Soliciting a person for the purpose of employment, or offering employment, by means of materially false or fraudulent pretenses, representations, or promises regarding that employment;
- (D) Charging recruited employees a placement or recruitment fee; or
- (E) Providing or arranging housing that fails to meet the host country's housing and safety standards.

(2) The Federal agency may unilaterally terminate this award or take any remedial actions authorized by 22 U.S.C. 7104b(c), without penalty, if any private entity under this award:

- (i) Is determined to have violated a prohibition in paragraph (a)(1) of this appendix; or
- (ii) Has an employee that is determined to have violated a prohibition in paragraph

(a)(1) of this this appendix through conduct that is either:

(A) Associated with the performance under this award; or

(B) Imputed to the recipient or the subrecipient using the standards and due process for imputing the conduct of an individual to an organization that are provided in 2 CFR part 180, "OMB Guidelines to Agencies on Government-wide Debarment and Suspension (Nonprocurement)," as implemented by DOJ at 2 C.F.R. Part 2867.

(b) Provision applicable to a recipient other than a private entity. (1) The Federal agency may unilaterally terminate this award or take any remedial actions authorized by 22 U.S.C. 7104b(c), without penalty, if a subrecipient that is a private entity under this award:

(i) Is determined to have violated a prohibition in paragraph (a)(1) of this appendix; or

(ii) Has an employee that is determined to have violated a prohibition in paragraph (a)(1) of this appendix through conduct that is either:

(A) Associated with the performance under this award; or

(B) Imputed to the subrecipient using the standards and due process for imputing the conduct of an individual to an organization that are provided in 2 CFR part 180, "OMB Guidelines to Agencies on Government-wide Debarment and Suspension (Nonprocurement)," as implemented by 2 C.F.R. Part 2867.

(c) Provisions applicable to any recipient.

(1) The recipient must inform the Federal agency and the Inspector General of the Federal agency immediately of any information you receive from any source alleging a violation of a prohibition in paragraph (a)(1) of this appendix.

(2) The Federal agency's right to unilaterally terminate this award as described in paragraphs (a)(2) or (b)(1) of this appendix:

(i) Implements the requirements of 22 U.S.C. 78, and

(ii) Is in addition to all other remedies for noncompliance that are available to the Federal agency under this award.

(3) The recipient must include the requirements of paragraph (a)(1) of this award term in any subaward it makes to a private entity.

(4) If applicable, the recipient must also comply with the compliance plan and certification requirements in 2 CFR 175.105(b).

(d) Definitions. For purposes of this award term:

Employee means either:

(1) An individual employed by the recipient or a subrecipient who is engaged in the performance of the project or program under this award; or

(2) Another person engaged in the performance of the project or program under this award and not compensated by the recipient including, but not limited to, a volunteer or individual whose services are contributed by a third party as an in-kind contribution toward cost sharing requirements.

Private Entity means any entity, including for-profit organizations, nonprofit organizations, institutions of higher education, and hospitals. The term does not include foreign public entities, Indian Tribes, local governments, or states as defined in 2 CFR 200.1.

The terms "severe forms of trafficking in persons," "commercial sex act," "sex trafficking," "Abuse or threatened abuse of law or legal process," "coercion," "debt bondage," and "involuntary servitude" have the meanings given at section 103 of the TVPA, as amended (22 U.S.C. 7102).

Termination: Recipient understands and agrees that the COPS Office may terminate funding, in whole or in part, for the following reasons:

- (1) When the recipient fails to comply with the terms and conditions of a Federal award.
 - (2) When the recipient agrees to the termination and termination conditions.
 - (3) When the recipient provides the COPS Office written notification requesting termination including the reasons, effective date, and the portion of the award to be terminated. The COPS Office may terminate the entire award if the remaining portion will not accomplish the purposes of the award.
 - (4) Pursuant to any other award terms and conditions, including, when an award no longer effectuates the program goals or agency priorities to the extent such termination is authorized by law.
2. C.F.R. § 200.340.

Condition 13

Recipient Integrity and Performance Matters: For awards over \$500,000, the recipient agrees to comply with the following requirements of 2 C.F.R. Part 200, Appendix XII to Part 200 – Award Term and Condition for Recipient Integrity and Performance Matters:

I. Reporting of Matters Related to Recipient Integrity and Performance

(a) General Reporting Requirement.

(1) If the total value of your active grants, cooperative agreements, and procurement contracts from all Federal agencies exceeds \$10,000,000 for any period of time during the period of performance of this Federal award, then you as the recipient must ensure the information available in the responsibility/qualification records through the System for Award Management (SAM.gov), about civil, criminal, or administrative proceedings described in paragraph (b) of this award term is current and complete. This is a statutory requirement under section 872 of Public Law 110-417, as amended (41 U.S.C. 2313). As required by section 3010 of Public Law 111-212, all information posted in responsibility/qualification records in SAM.gov on or after April 15, 2011 (except past performance reviews required for Federal procurement contracts) will be publicly available.

(b) Proceedings About Which You Must Report.

(1) You must submit the required information about each proceeding that—

(i) Is in connection with the award or performance of a grant, cooperative agreement, or procurement contract from the Federal Government;

(ii) Reached its final disposition during the most recent five-year period; and

(iii) Is one of the following—

(A) A criminal proceeding that resulted in a conviction;

(B) A civil proceeding that resulted in a finding of fault and liability and payment of a monetary fine, penalty, reimbursement, restitution, or damages of \$5,000 or more;

(C) An administrative proceeding that resulted in a finding of fault and liability and your payment of either a monetary fine or penalty of \$5,000 or more or reimbursement, restitution, or damages in excess of \$100,000; or

(D) Any other criminal, civil, or administrative proceeding if—

(1) It could have led to an outcome described in paragraph (b)(1)(iii)(A) through (C);

(2) It had a different disposition arrived at by consent or compromise with an acknowledgment of fault on your part; and

(3) The requirement in this award term to disclose information about the proceeding does not conflict with applicable laws and regulations.

(c) Reporting Procedures. Enter the required information in SAM.gov for each proceeding described in paragraph (b) of this award term. You do not need to submit the information a second time under grants and cooperative agreements that you received if you already provided the information in SAM.gov because you were required to do so under Federal procurement contracts that you were awarded.

(d) Reporting Frequency. During any period of time when you are subject to the requirement in paragraph (a) of this award term, you must report proceedings information in SAM.gov for the most recent five-year period, either to report new information about a proceeding that you have not reported previously or affirm that there is no new information to report. If you have Federal contract, grant, and cooperative agreement awards with a cumulative total value greater than \$10,000,000, you must disclose semiannually any information about the criminal, civil, and administrative proceedings.

(e) Definitions. For purposes of this award term—

Administrative proceeding means a nonjudicial process that is adjudicatory in nature to make a determination of fault or liability (for example, Securities and Exchange Commission Administrative proceedings, Civilian Board of Contract Appeals proceedings, and Armed Services Board of Contract Appeals proceedings). This includes proceedings at the Federal and State level but only in connection with the performance of a Federal contract or grant. It does not include audits, site visits, corrective plans, or inspection of deliverables.

Conviction means a judgment or conviction of a criminal offense by any court of competent jurisdiction, whether entered upon a verdict or a plea, and includes a conviction entered upon a plea of nolo contendere. Total value of

currently active grants, cooperative agreements, and procurement contracts includes the value of the Federal share already received plus any anticipated Federal share under those awards (such as continuation funding).

Condition 14

Reporting Subawards and Executive Compensation: The recipient agrees to comply with the following requirements of 2 C.F.R. Part 170, Appendix A to Part 170 – Award Term:

I. Reporting Subawards and Executive Compensation

(a) Reporting of first-tier subawards—(1) Applicability. Unless the recipient is exempt as provided in paragraph (d) of this award term, the recipient must report each subaward that equals or exceeds \$30,000 in Federal funds for a subaward to an entity or Federal agency. The recipient must also report a subaward if a modification increases the Federal funding to an amount that equals or exceeds \$30,000. All reported subawards should reflect the total amount of the subaward.

(2) Reporting Requirements. (i) The entity or Federal agency must report each subaward described in paragraph (a)(1) of this award term to the Federal Funding Accountability and Transparency Act Subaward Reporting System (FSRS) at <http://www.fsr.gov>.

(ii) For subaward information, report no later than the end of the month following the month in which the subaward was issued. (For example, if the subaward was made on November 7, 2025, the subaward must be reported by no later than December 31, 2025).

(b) Reporting total compensation of recipient executives for entities—(1) Applicability. The recipient must report the total compensation for each of the recipient's five most highly compensated executives for the preceding completed fiscal year if:

(i) The total Federal funding authorized to date under this Federal award equals or exceeds \$30,000;

(ii) in the preceding fiscal year, the recipient received:

(A) 80 percent or more of the recipient's annual gross revenues from Federal procurement contracts (and subcontracts) and Federal awards (and subawards) subject to the Transparency Act; and

(B) \$25,000,000 or more in annual gross revenues from Federal procurement contracts (and subcontracts) and Federal awards (and subawards) subject to the Transparency Act; and,

(iii) The public does not have access to information about the compensation of the executives through periodic reports filed under section 13(a) or 15(d) of the Securities Exchange Act of 1934 (15 U.S.C. 78m(a), 78o(d)) or section 6104 of the Internal Revenue Code of 1986 after receiving this subaward. (To determine if the public has access to the compensation information, see the U.S. Security and Exchange Commission total compensation filings at <http://www.sec.gov/answers/excomp.htm>.)

(2) Reporting Requirements. The recipient must report executive total compensation described in paragraph (b)(1) of this appendix:

(i) As part of the recipient's registration profile at <https://www.sam.gov>.

(ii) No later than the month following the month in which this Federal award is made, and annually after that. (For example, if this Federal award was made on November 7, 2025, the executive total compensation must be reported by no later than December 31, 2025.)

(c) Reporting of total compensation of subrecipient executives—(1) Applicability. Unless a first-tier subrecipient is exempt as provided in paragraph (d) of this appendix, the recipient must report the executive total compensation of each of the subrecipient's five most highly compensated executives for the subrecipient's preceding completed fiscal year, if:

(i) The total Federal funding authorized to date under the subaward equals or exceeds \$30,000;

(ii) In the subrecipient's preceding fiscal year, the subrecipient received:

(A) 80 percent or more of its annual gross revenues from Federal procurement contracts

(and subcontracts) and Federal awards (and subawards) subject to the Transparency Act; and,

(B) \$25,000,000 or more in annual gross revenues from Federal procurement contracts (and subcontracts), and Federal awards (and subawards) subject to the Transparency Act; and

(iii) The public does not have access to information about the compensation of the executives through periodic reports filed under section 13(a) or 15(d) of the Securities Exchange Act of 1934 (15 U.S.C. 78m(a), 78o(d)) or section 6104 of the Internal Revenue Code of 1986 after receiving this subaward. (To determine if the public has access to the compensation information, see

the U.S. Security and Exchange Commission total compensation filings at <http://www.sec.gov/answers/excomp.htm>.)

(2) Reporting Requirements. Subrecipients must report to the recipient their executive total compensation described in paragraph

(c)(1) of this appendix. The recipient is required to submit this information to the Federal Funding Accountability and Transparency Act Subaward Reporting System (FSRS) at <http://www.fsrs.gov> no later than the end of the month following the month in which the subaward was made. (For example, if the subaward was made on November 7, 2025, the subaward must be reported by no later than December 31, 2025).

(d) Exemptions. (1) A recipient with gross income under \$300,000 in the previous tax year is exempt from the requirements to report:

(i) Subawards, and

(ii) The total compensation of the five most highly compensated executives of any subrecipient.

(e) Definitions. For purposes of this award term:

Entity includes:

(1) Whether for profit or nonprofit:

(i) A corporation;

(ii) An association;

(iii) A partnership;

(iv) A limited liability company;

(v) A limited liability partnership;

(vi) A sole proprietorship;

(vii) Any other legal business entity;

(viii) Another grantee or contractor that is not excluded by subparagraph (2); and

(ix) Any State or locality;

(2) Does not include:

(i) An individual recipient of Federal financial assistance; or

(ii) A Federal employee.

Executive means an officer, managing partner, or any other employee holding a management position.

Subaward has the meaning given in 2 CFR200.1.

Subrecipient has the meaning given in 2CFR 200.1.

Total Compensation means the cash and noncash dollar value an executive earns during an entity's preceding fiscal year. This includes all items of compensation as prescribed in 17 CFR 229.402(c)(2).

Condition 15

Assurances and Certifications: The recipient acknowledges its agreement to comply with the Assurances and Certifications forms that were signed as part of its application.

Condition 16

Conflict of Interest: Recipients and subrecipients must disclose in writing to the COPS Office or pass-through entity, as applicable, any potential conflict of interest affecting the awarded federal funding in 2 C.F.R. § 200.112.

Condition 17

Debarment and Suspension: The recipient agrees not to award federal funds under this program to any party which is debarred or suspended from participation in federal assistance programs. 2 C.F.R. Part 180 (Government-wide Nonprocurement Debarment and Suspension) and 2 C.F.R. Part 2867 (DOJ Nonprocurement Debarment and Suspension).

Condition 18

Equal Employment Opportunity Plan (EEOP): Please see the Office for Civil Rights website <https://www.ojp.gov/eeop-notice> for current information on the recipient's responsibilities related to the federal regulations pertaining to the development and implementation of an Equal Employment Opportunity Plan.

Condition 19

Employment Eligibility: The recipient agrees to complete and keep on file, as appropriate, the Department of Homeland Security, U.S. Citizenship and Immigration Services (USCIS) Employment Eligibility Verification Form (I-9). This form is to be used by recipients of federal funds to verify that persons are eligible to work in the United States. Immigration Reform and Control Act of 1986 (IRCA), Public Law 99-603.

Condition 20

Enhancement of Contractor Protection from Reprisal for Disclosure of Certain Information: Recipients and

subrecipients agree not to discharge, demote, or otherwise discriminate against an employee as reprisal for the employee disclosing information that he or she reasonably believes is evidence of gross mismanagement of a federal contract or award, a gross waste of federal funds, an abuse of authority relating to a federal contract or award, a substantial and specific danger to public health or safety, or a violation of law, rule, or regulation related to a Federal contract (including the competition for or negotiation of a contract) or award. Recipients and subrecipients also agree to provide to their employees in writing (in the predominant native language of the workforce) of the rights and remedies provided in 41 U.S.C. § 4712. Please see appendices in the Award Owner's Manual for a full text of the statute.

Condition 21

False Statements: False statements or claims made in connection with COPS Office awards may result in fines, imprisonment, debarment from participating in federal awards or contracts, and/or any other remedy available by law. 31 U.S.C. § 3729-3733.

Condition 22

Mandatory Disclosure: Recipients and subrecipients must timely disclose in writing to the Federal awarding agency or pass-through entity, as applicable, all federal criminal law violations involving fraud, bribery, or gratuity that may potentially affect the awarded federal funding. Recipients that receive an award over \$500,000 must also report certain civil, criminal, or administrative proceedings in SAM and are required to comply with the Term and Condition for Recipient Integrity and Performance Matters as set out in 2 C.F.R. Part 200, Appendix XII to Part 200. Failure to make required disclosures can result in any of the remedies, including suspension and debarment, described in 2 C.F.R. § 200.339. 2 C.F.R. § 200.113.

Condition 23

Reports/Performance Goals: To assist the COPS Office in monitoring and tracking the performance of your award, your agency will be responsible for submitting semi-annual programmatic performance reports that describe project activities during the reporting period and quarterly Federal Financial Reports using Standard Form 425 (SF-425). 2 C.F.R. §§ 200.328 - 200.329. The performance report is used to track your agency's progress in implementing the award, and, as applicable, community policing strategies including gauging the effectiveness of your agency's community policing capacity. The Federal Financial Report is used to track the expenditures of the recipient's award funds on a cumulative basis throughout the life of the award.

Condition 24

System for Award Management (SAM.gov) and Universal Identifier Requirements: The recipient agrees to comply with the following requirements of 2 C.F.R. Part 25, Appendix A to Part 25 – Award Term:

I. System for Award Management (SAM.gov) and Universal Identifier Requirements

(a) Requirement for System for Award Management. (1) Unless exempt from this requirement under 2 CFR 25.110, the recipient must maintain a current and active registration in SAM.gov. The recipient's registration must always be current and active until the recipient submits all final reports required under this Federal award or receives the final payment, whichever is later. The recipient must review and update its information in SAM.gov at least annually from the date of its initial registration or any subsequent updates to ensure it is current, accurate, and complete. If applicable, this includes identifying the recipient's immediate and highest-level owner and subsidiaries and providing information about the recipient's predecessors that have received a Federal award or contract within the last three years.

(b) Requirement for Unique Entity Identifier (UEI). (1) If the recipient is authorized to make subawards under this Federal award, the recipient:

(i) Must notify potential subrecipients that no entity may receive a subaward until the entity has provided its UEI to the recipient.

(ii) Must not make a subaward to an entity unless the entity has provided its UEI to the recipient. Subrecipients are not required to complete full registration in SAM.gov to obtain a UEI.

(c) Definitions. For the purposes of this award term:

System for Award Management (SAM.gov) means the Federal repository into which a recipient must provide the information required for the conduct of business as a recipient. Additional information about registration procedures may be found in SAM.gov (currently at <https://www.sam.gov>).

Unique entity identifier means the universal identifier assigned by SAM.gov to uniquely identify an entity.

Entity is defined at 2 CFR 25.400 and includes all of the following types as defined in 2 CFR 200.1:

(1) Non-Federal entity;

- (2) Foreign organization;
- (3) Foreign public entity;
- (4) Domestic for-profit organization; and
- (5) Federal agency.

Subaward has the meaning given in 2 CFR 200.1.

Subrecipient has the meaning given in 2 CFR 200.1.

Condition 25

Additional High-Risk Recipient Requirements: The recipient agrees to comply with any additional requirements that may be imposed during the award performance period if the awarding agency determines that the recipient is a high-risk recipient. 2 C.F.R. § 200.208.

Condition 26

Criminal Intelligence Systems: Recipients using award funds to operate an interjurisdictional criminal intelligence system must comply with the operating principles of 28 C.F.R. Part 23. At the time of application, the recipient assured the COPS Office that it will comply with the requirements of 28 C.F.R. Part 23.

Condition 27

Allowable Costs: The funding under this award is for the payment of approved costs for program-specific purposes. The allowable costs approved for your agency's award are limited to those listed in your agency's award package. In accordance with 2 C.F.R. § 200.400(g), the recipient or subrecipient must not earn or keep any profit resulting from the award. Your agency may not use award funds for any costs not identified as allowable in the award package.

Condition 28

Prohibition on Certain Telecommunications and Video Surveillance Services or Equipment: Recipient agrees that it, and its subrecipients, will not use award funds to extend, renew, or enter into any contract to procure or obtain any covered telecommunication and video surveillance services or equipment as described in 2 CFR §200.216. Covered services and equipment include telecommunications or video surveillance services or equipment produced or provided by Huawei Technologies Company or ZTE Corporation (or any subsidiary or affiliate of such entities); Hytera Communications Corporation, Hangzhou Hikvision Digital Technology Company, or Dahua Technology Company (or any subsidiary or affiliate of such entities); or an entity that the Secretary of Defense, in consultation with the Director of the National Intelligence or the Director of the Federal Bureau of Investigation, reasonably believes to be an entity owned or controlled by, or otherwise connected to, the government of China. The use of award funds on covered telecommunications or video surveillance services or equipment are unallowable.

2. C.F.R. §§ 200.216 & 471. See also Section 889 of the John S. McCain National Defense Authorization Act of Fiscal Year 2019, Public Law 115-232.

Condition 29

Sole Source Justification: Recipients who have been awarded funding for the procurement of an item (or group of items) or service in excess of the simplified acquisition threshold (currently, \$350,000) and who plan to seek approval for use of a noncompetitive procurement process must provide a written sole source justification to the COPS Office for approval prior to obligating, expending, or drawing down award funds for that item or service. 2 C.F.R. § 200.325(b)(2).

Condition 30

Buy America Preference

Recipients of an award of Federal financial assistance for the construction, alteration, maintenance, or repair of infrastructure are hereby notified that none of the funds provided under this award may be used for an infrastructure project unless:

(1) All iron and steel used in the project are produced in the United States—this means all manufacturing processes, from the initial melting stage through the application of coatings, occurred in the United States;

(2) All manufactured products used in the project are produced in the United States— this means the manufactured product was manufactured in the United States; and the cost of the components of the manufactured product that are mined, produced, or manufactured in the United States is greater than 55 percent of the total cost of all components of the manufactured product, unless another standard that meets or exceeds this standard has been established under applicable law or regulation for determining the minimum amount of domestic content of the manufactured product; and

(3) All construction materials are manufactured in the United States—this means that all manufacturing processes for the construction material occurred in the United States. The construction material standards are listed below.

Incorporation into an infrastructure project. The Buy America Preference only applies to articles, materials, and supplies that are consumed in, incorporated into, or affixed to an infrastructure project. As such, it does not apply to tools, equipment, and supplies, such as temporary scaffolding, brought to the construction site and removed at or before the completion of the infrastructure project. Nor does a Buy America Preference apply to equipment and furnishings, such as movable chairs, desks, and portable computer equipment, that are used at or within the finished infrastructure project but are not an integral part of the structure or permanently affixed to the infrastructure project.

Categorization of articles, materials, and supplies. An article, material, or supply should only be classified into one of the following categories: (i) Iron or steel products; (ii) Manufactured products; (iii) Construction materials; or (iv) Section 70917(c) materials. An article, material, or supply should not be considered to fall into multiple categories. In some cases, an article, material, or supply may not fall under any of the categories listed in this paragraph. The classification of an article, material, or supply as falling into one of the categories listed in this paragraph must be made based on its status at the time it is brought to the work site for incorporation into an infrastructure project. In general, the work site is the location of the infrastructure project at which the iron, steel, manufactured products, and construction materials will be incorporated.

Application of the Buy America Preference by category. An article, material, or supply incorporated into an infrastructure project must meet the Buy America Preference for only the single category in which it is classified.

Determining the cost of components for manufactured products. In determining whether the cost of components for manufactured products is greater than 55 percent of the total cost of all components, use the following instructions:

(a) For components purchased by the manufacturer, the acquisition cost, including transportation costs to the place of incorporation into the manufactured product (whether or not such costs are paid to a domestic firm), and any applicable duty (whether or not a duty-free entry certificate is issued); or

(b) For components manufactured by the manufacturer, all costs associated with the manufacture of the component, including transportation costs as described in paragraph (a), plus allocable overhead costs, but excluding profit. Cost of components does not include any costs associated with the manufacture of the manufactured product.

Construction material standards. The Buy America Preference applies to the following construction materials incorporated into infrastructure projects. Each construction material is followed by a standard for the material to be considered "produced in the United States." Except as specifically provided, only a single standard should be applied to a single construction material.

(1) Non-ferrous metals. All manufacturing processes, from initial smelting or melting through final shaping, coating, and assembly, occurred in the United States.

(2) Plastic and polymer-based products. All manufacturing processes, from initial combination of constituent plastic or polymer-based inputs, or, where applicable, constituent composite materials, until the item is in its final form, occurred in the United States.

(3) Glass. All manufacturing processes, from initial batching and melting of raw materials through annealing, cooling, and cutting, occurred in the United States.

(4) Fiber optic cable (including drop cable). All manufacturing processes, from the initial ribboning (if applicable), through buffering, fiber stranding and jacketing, occurred in the United States. All manufacturing processes also include the standards for glass and optical fiber, but not for non-ferrous metals, plastic and polymer-based products, or any others.

(5) Optical fiber. All manufacturing processes, from the initial preform fabrication stage through the completion of the draw, occurred in the United States.

(6) Lumber. All manufacturing processes, from initial debarking through treatment and planing, occurred in the United States.

(7) Drywall. All manufacturing processes, from initial blending of mined or synthetic gypsum plaster and additives through cutting and drying of sandwiched panels, occurred in the United States.

(8) Engineered wood. All manufacturing processes from the initial combination of constituent materials until the wood product is in its final form, occurred in the United States.

Waivers.

When necessary, recipients may apply for, and the Office of Community Oriented Policing Services (COPS Office) may grant, a waiver from these requirements.

The COPS Office may waive the application of the Buy America Preference when it has determined that one of the following exceptions applies:

- (1) applying the Buy America Preference would be inconsistent with the public interest;
- (2) the types of iron, steel, manufactured products, or construction materials are not produced in the United States in sufficient and reasonably available quantities or of a satisfactory quality; or
- (3) the inclusion of iron, steel, manufactured products, or construction materials produced in the United States will increase the cost of the overall project by more than 25 percent.

A request to waive the application of the Buy America Preference must be in writing. If requested, the COPS Office will provide instructions on the format, contents, and supporting materials required for any waiver request. Waiver requests are subject to public comment periods of no less than 15 days and must be reviewed by the Made in America Office.

Recipients do not need to obtain a waiver of the Buy America Preference requirements from the COPS Office if they will use only iron, steel, manufactured products, and construction materials that meet the criteria as specified above for the project.

If a recipient determines a waiver is necessary, an application for a waiver should be submitted as soon as possible and provide detailed information to expedite the COPS Office's review. Recipients agree not to obligate, expend or draw down funds for infrastructure projects or activities unless they comply with the Buy America Preference requirements or request and obtain a waiver of the requirements from the COPS Office.

If you have any questions about this requirement or requesting a waiver of the requirement, please contact your COPS Office Program Manager at 800-421-6770.

Condition 31

Domestic preferences for procurements: Recipient agrees that it, and its subrecipients, to the greatest extent practicable, will provide a preference for the purchase, acquisition, or use of goods, products, and materials produced in, and services offered in, the United States. 2. C.F.R. § 200.322 and Executive Order 14005, Ensuring the Future is Made in All of America by All of America's Workers, January 25, 2021.

Condition 32

Requirement to report actual or imminent breach of personally identifiable information (PII).

The recipient (and any subrecipient at any tier) must have written procedures in place to respond in the event of an actual or imminent breach (as defined in OMB M-17-12) if it (or a subrecipient)-- 1) creates, collects, uses, processes, stores, maintains, disseminates, discloses, or disposes of personally identifiable information (PII) (as defined in 2 C.F.R. 200.1) within the scope of a COPS Office grant-funded program or activity, or 2) uses or operates a Federal information system (as defined in OMB Circular A-130). The recipient's breach procedures must include a requirement to report actual or imminent breach of PII to the recipient's COPS Office Program Manager no later than 24 hours after an occurrence of an actual breach, or the detection of an imminent breach.

Condition 33

Community Policing: Community policing activities to be initiated or enhanced by your agency were identified and described in your award application. All equipment, technology, training, and civilian positions awarded under your agency's COPS Office award must be linked to the implementation or enhancement of community policing. 34 U.S.C. § 10382 (c)(10).

Condition 34

Travel Costs: Travel costs for transportation, lodging and subsistence, and related items are allowable with prior approval from the COPS Office. Payment for allowable travel costs will be in accordance with 2 C.F.R. § 200.475.

Condition 35

The Paperwork Reduction Act Clearance and Privacy Act Review: Recipient agrees, if required, to submit all surveys, interview protocols, and other information collections to the COPS Office for submission to the Office of Management and Budget (OMB) for clearance under the Paperwork Reduction Act (PRA). Before submission to OMB, all information collections that request personally identifiable information must be reviewed by the COPS Office to ensure compliance with the Privacy Act. The Privacy Act compliance review and the PRA clearance process may take several months to complete. 44 U.S.C. §§ 3501-3520 and 5 U.S.C. § 552a.

Condition 36

Evaluations: The COPS Office may conduct monitoring or sponsor national evaluations of its award programs. The recipient agrees to cooperate with the monitors and evaluators. 34 U.S.C. § 10385(b).

Condition 37

Extensions: Recipients may request an extension of the award period to receive additional time to implement their award program. Such extensions do not provide additional funding. Only those recipients that can provide a reasonable justification for delays will be granted no-cost extensions. Extension requests must be received prior to the end date of the award. 2 C.F.R. §§ 200.308(f)(10) and 200.309.

Condition 38

Supplementing, not Supplanting: State, local, and tribal government recipients must use award funds to supplement, and not supplant, state, local, or Bureau of Indian Affairs (BIA) funds that are already committed or otherwise would have been committed for award purposes (hiring, training, purchases, and/or activities) during the award period. In other words, state, local, and tribal government recipients may not use COPS Office funds to supplant (replace) state, local, or BIA funds that would have been dedicated to the COPS Office-funded item(s) in the absence of the COPS Office award. 34 U.S.C. § 10384(a).

Condition 39

Modifications: Award modifications are evaluated on a case-by-case basis in accordance with 2 C.F.R. § 200.308(i). For federal awards in excess of the simplified acquisition threshold (currently, \$350,000), any modification request involving the reallocation of funding between budget categories that exceed or are expected to exceed 10 percent (10%) of the total approved budget requires prior written approval by the COPS Office. Regardless of the federal award amount or budget modification percentage, any reallocation of funding is limited to approved budget categories. In addition, any budget modification that changes the scope of the project requires prior written approval by the COPS Office.

Condition 40

State Information Technology Point of Contact: The recipient agrees to ensure that the appropriate State Information Technology Point of Contact receives written notification regarding any technology or information-sharing project funded by this award during the obligation and expenditure period. This is to facilitate communication among local and state governmental entities regarding various information technology projects being conducted with these award funds. In addition, the recipient agrees to maintain an administrative file documenting the meeting of this requirement. For a list of State Information Technology Points of Contact, go to <https://it.ojp.gov/technology-contacts>.

Condition 41

Computer Network Requirement: The recipient understands and agrees that no award funds may be used to maintain or establish a computer network unless such network blocks the viewing, downloading, and exchanging of pornography. Nothing in this requirement limits the use of funds necessary for any federal, state, tribal, or local law enforcement agency or any other entity carrying out criminal investigations, prosecution, or adjudication activities. Commerce, Justice, Science; Energy and Water Development; and Interior and Environment Appropriations Act, 2026, Public Law 119-74, Division A, Title V, Section 527.

Condition 42

Contracts and/or MOUs with Other Jurisdictions: Items funded under this award must only be used for law enforcement activities or services that benefit your agency and the population that it serves and cannot be utilized by other agencies unless the items benefit the population that your agency serves.

Condition 43

Unmanned Aircraft Systems: Recipients using award funding for Unmanned Aircraft Systems (UAS) understand and agree to the following:

1. Any UAS purchased must be one manufactured by an entity included, as of the date of purchase on the U.S. Department of War, Defense Contract Management Agency (DCMA) Blue UAS Cleared List (available at <https://bluelist.appsplatformportals.us/>);
2. Any UAS purchased must not be manufactured by an entity that will be included, as of the date of purchase, on the International Trade Administration of the Department of Commerce's Consolidated Screening List (available at <https://www.trade.gov/consolidated-screening-list>);
3. No modifications or additional accessories that are not on the DCMA Blue UAS Cleared List will be introduced to the purchased UAS. Further, the applicant understands that the entity operating the UAS must have sufficient policies and procedures regarding privacy, civil liberties, and information technology cybersecurity related to the operation of the UAS; and
4. Counter-UAS or activities are unallowable under this program.

For the purpose of this award condition, the terms "unmanned aircraft system," "drone," and "unmanned aerial vehicle" all have the meaning given to the term "unmanned aircraft system" in 49 U.S.C. § 44801(12). The term "counter-UAS" has the meaning given to the term "counter-UAS system" in 49 U.S.C. § 44801(5).

Condition 44

Compliance with National Environmental Policy Act and related statutes: Upon request, the recipient must assist the COPS Office in complying with the National Environmental Policy Act (NEPA), the National Historic Preservation Act, and other related federal environmental impact analyses requirements in the use of these award funds. Accordingly, the recipient agrees to determine if new construction or renovation or remodeling of a property will be funded by the grant, and if so, agrees to comply with all NEPA requirements prior to obligating, expending, or drawing down award funds for any award purposes. The recipient understands and agrees that complying with NEPA may require the preparation of an environmental study, including an Environmental Assessment (EA) and/or an Environmental Impact Statement (EIS), as directed by the COPS Office. The NEPA compliance process may take several months to complete. 42 U.S.C. §§ 4321 et seq.

Condition 45

National Environmental Policy Act (NEPA) withholding

The recipient acknowledges that compliance with the National Environmental Policy Act (NEPA), the National Historic Preservation Act, and other related federal environmental impact analyses requirements are required for use of these award funds. The recipient understands and agrees that complying with NEPA may require the preparation of an environmental study, including an Environmental Assessment (EA) and/or an Environmental Impact Statement (EIS), as directed by the COPS Office. The NEPA compliance process may take several months to complete. 42 U.S.C. §§ 4321 et seq. The recipient agrees not to obligate, expend or draw down funds for any NEPA triggering activity that requires NEPA compliance such as new construction, renovation, or remodeling of a property until it has complied with all NEPA requirements, and the COPS Office has issued an Award Condition Modification (ACM) to remove this award condition.

☐ I have read and understand the information presented in this section of the Federal Award Instrument.

Award Acceptance**Declaration and Certification to the U.S. Department of Justice as to Acceptance**

By checking the declaration and certification box below, I--

A. Declare to the U.S. Department of Justice (DOJ), under penalty of perjury, that I have authority to make this declaration and certification on behalf of the applicant.

B. Certify to DOJ, under penalty of perjury, on behalf of myself and the applicant, to the best of my knowledge and belief, that the following are true as of the date of this award acceptance: (1) I have conducted or there was conducted (including by applicant's legal counsel as appropriate and made available to me) a diligent review of all terms and conditions of, and all supporting materials submitted in connection with, this award, including any assurances and certifications (including anything submitted in connection therewith by a person on behalf of the applicant before, after, or at the time of the application submission and any materials that accompany this acceptance and certification); and (2) I have the legal authority to accept this award on behalf of the applicant.

C. Accept this award on behalf of the applicant.

D. Declare the following to DOJ, under penalty of perjury, on behalf of myself and the applicant: (1) I understand that, in taking (or not taking) any action pursuant to this declaration and certification, DOJ will rely upon this declaration and certification as a material representation; and (2) I understand that any materially false, fictitious, or fraudulent information or statement in this declaration and certification (or concealment or omission of a material fact as to either) may be the subject of criminal prosecution (including under 18 U.S.C. §§ 1001 and/or 1621, and/or 34 U.S.C. §§ 10271-10273), and also may subject me and the applicant to civil penalties and administrative remedies under the federal False Claims Act (including under 31 U.S.C. §§ 3729-3730 and/or §§ 3801-3812) or otherwise.

Agency Approval

Title of Approving Official
COPS Office Deputy Director

Name of Approving Official
Cory D. Randolph

Signed Date And Time
9/23/26 8:04 PM

Authorized Representative

☐ Declaration and Certification (Law Enforcement Executive/Program Official)

Entity Acceptance

Title of Authorized Entity Official
no value

Name of Authorized Entity Official
no value

Signed Date And Time
no value

☐ Declaration and Certification (Government Executive/Financial Official)

Entity Acceptance

Title of Authorized Entity Official
City Manager



Name of Authorized Entity Official
no value


Signed Date And Time
no value

Memo

To: Karen Conard, City Manager
Kim McNamara, Health Officer
From: Kristin Shaw, Deputy Health Officer
Date: October 21, 2026
Re: Food Permits

Please find the updated Food and Liquor permit data as of October 7, 2026, after annual renewals. These numbers do not include seasonal permits, farmers' market permits, or temporary event permits.





Please let me know if you have any additional questions. As always, seat numbers are self-reported, and we have new businesses going through the permitting process (approximately 6 in the permitting pipeline, 3 of them are change of ownership.)

These numbers indicate a decrease from 2025; contributors include:

- 11 brick and mortar closures
 - Includes 2 caterers, a private yacht club, 3 sandwich shops, 3 restaurants, 2 retail stores)
- 3 change-of-ownership closures – currently in permitting pipeline
- 1 temporary closure – Gilly’s for street reconstruction
- 3 mobile units did not renew their annual licenses
- 2 mobile units changed to seasonal licenses (not included here)

Downtown Parking

City Council Quarterly Report



Resident Access Parking Program (RAPP) and Downtown Workforce Parking Program (DWPP) update, resident feedback, and a new downtown business option

October 26, 2026

Policy amended September 28, 2026

Additional amendments effective October 1, 2026



RAPP update: residents still a priority

~80%

of parking on RAPP program streets is
residents

+23%

more midday availability on program streets


+26%

more evening availability on program streets

- Residents remain the clear majority of parkers on the RAPP streets. Their share eased from 88% in August to about 80% in September as more non-residents pay and enforcement addresses non-payers.
- Roughly 23% more parking is open at midday and in the evening than before the pilot, because all-day non-resident parking has moved off these streets.
- Early mornings remain steady, since residents were already parked at home overnight.

Spillover is fading, and more drivers are paying

Share of transactions on RAPP streets



Spillover has largely faded.

Early on, surrounding streets had up to 8% less availability. That is now under 2%, so the pilot has not pushed parking into nearby neighborhoods.

More non-residents are paying, and enforcement is ramping up.

In July the City issued 380 warnings and 189 citations, mostly on Parrott Avenue.

Foundry workforce participation is up 51%.

From 450 in FY26 to about 680 since RAPP began on July 1, a sign that workers who had used RAPP-area spaces have relocated to the Foundry Garage.

Downtown Workforce (DWPP) participation is growing

718

downtown workers enrolled in the program

7% → 12%

Parrott Avenue paid sessions
that are workforce

~6.9 hrs

average workforce stay on Parrott Avenue

- The Foundry Garage remains the primary workforce venue. Of the 718 enrolled, most use the Foundry sticker; 53 have registered for the Parrott Avenue pilot.
- On Parrott Avenue, the workforce share of paid sessions nearly doubled from July to September, with an average stay just under 7 hours, consistent with a mix of full-time and part-time shifts.
- Under the amended policy (effective October 1), the Foundry sticker is \$3 for up to 12 hours, and workers may buy up to 26 per month.

Other observations in the data

The Parrott Avenue Lot


- Under the amended policy, non-residents are no longer permitted to park in the lot. **The Lot is for registered residents and registered downtown workers.**
- Early counts still show a core of non-resident and out-of-state vehicles (Maine, Massachusetts, and others), so compliance and enforcement are still ramping up.
- This is a place to watch as the restriction takes hold.

Enforcement

- Information flyers came first, then warnings, followed by citations.
- Parrott Avenue and the South End see the most enforcement activity.
- The citation rate has declined over the course of the program as users have adjusted their behavior.

The overall pilot is doing what it was designed to do: more availability for residents, minimal spillover, and a workable paid option for everyone else.

The Parrott Avenue Lot is no longer full



Average weekday composition of the 183-space lot, after October 1

Residents	Downtown Workforce	Warned / Cited	Open
57 (31%)	54 (30%)	46 (25%)	26 (14%)

- Before October 1, the lot was at nearly 100% occupancy, full for much of the day. With the focus on registered resident and workforce, it has settled near 86%, right at the 85% benchmark for a healthy lot, so about one space in seven is open.
- The lot now serves its intended users: registered residents (31%) and the downtown workforce (30%), a roughly even split. About a quarter of vehicles are still non-compliant and are being warned or cited; as enforcement continues, those spaces open for residents and workforce.

What we are hearing from residents

Sudbury Street

- Residents on Sudbury Street have asked to be included in the RAPP Program.
- The street has 5 on-street spaces.


Richards Avenue and Parrott Avenue

- Residents on Richards Avenue, north of Parrott Avenue have asked that the Parrott Avenue spaces from Richards Avenue to the Library entrance return to 72-hour parking for registered residents.
- Richards Avenue (north of Parrott Avenue) is posted no parking on both sides, and driveways are limited; these residents rely on those spaces.

For Council to weigh: both requests are being evaluated. Hearing and responding to this kind of resident feedback is part of what the pilot is for.

Monthly Pass Status

Monthly passes in the Foundry and Hanover garages



Takeaway: 762 of the 1,100 monthly passes are sold (69%), leaving 338 available, and non-residents hold the majority. On-street and lot inventory will be added as it is compiled.

A new option for downtown businesses outside the DWPP

Who the DWPP now serves

The amended policy focuses the deep discount for employees of restaurants, retail, personal service, and hospitality businesses, and their owners.

Workers from prior DWPP businesses in clerical and support roles are covered through March 1, 2027.

The gap, and a proposed fix

Other downtown businesses, such as offices and professional services, no longer qualify for the \$3 rate.

Proposed: a \$10 sticker for a 10-hour weekday only in the Foundry Garage, open to those businesses.

Offered in the Foundry, which has room at peak (66%), not Hanover (near full at 94%).

How the Foundry options compare, for a workday

\$3

DWPP sticker, up to 12 hours (qualifying businesses)

\$10

Proposed sticker, 10 hours, weekday only (downtown businesses)

~\$20

Standard rate, 10 hours at \$2 per hour

The proposed Downtown Business 10-hour weekday sticker is a 50% discount on the standard rate.

Next Steps

- 1 Continue the RAPP, DWPP, and Parrott Avenue Lot pilots and report to Council quarterly.
- 2 Evaluate resident requests to adjust the RAPP zone (Sudbury Street, and Parrott Avenue near Richards).
- 3 Decide on the proposed \$10 Foundry weekday only sticker for businesses outside the DWPP.
- 4 Continue enforcement, and keep watching spillover, citations, and workforce participation.

The parking system is a delicate balance, especially until we add supply. We will keep listening, measuring, and adjusting to serve residents, businesses, workers, and visitors.