



Civil Engineers  
Structural Engineers  
Traffic Engineers  
Land Surveyors  
Landscape Architects  
Scientists



March 23, 2020

TFM Project No: 47361.00

Juliet Walker, Planning Director  
Portsmouth Planning Department  
**City Hall, 3rd Floor**  
**1 Junkins Avenue**  
**Portsmouth, NH 03801**

**Re: Response to Comments from the January TAC Review for Condominium Development, Banfield Road, Tax Map 256, Lot 2**

Dear Juliet,

On behalf of our client, Green & Company, TF Moran, Inc. (TFM) respectfully submits the following revised plans and letter in response to the comments made by the Technical Advisory Committee (TAC) at our January meeting.

Based upon discussions held with City Staff and the review engineering firm, changes have been made to the underground stormwater management system and we have submitted revised plans addressing the review engineer's comments, we are anticipating their concurrence that the stormwater management system will provide treatment and storage for the development.

Included in this submittal are the following material:

- 9 Copies: 11"x17" Plan Set of the "The Village at Banfield Woods", Banfield Road, Portsmouth, NH, Tax Map 256, Lot 2, Dated September 25, 2019, last revised March 20, 2020.
- 1 Copies: 22"x34" Plan Set of the "The Village at Banfield Woods," Banfield Road, Portsmouth, NH, Tax Map 256, Lot 2, Dated September 25, 2019, last revised March 20, 2020.
- 10 Copies: Impact of "Response to Mark West Review of January 28, 2020 and questions related to Wildlife," by Gove Environmental Services, Inc, Dated February 28, 2020.
- 10 Copies: Impact of "Interpretation of Zoning Ordinances", by John Kuzinevich, Esq., Dated January 15, 2020.
- 10 Copies: "Proposed Stormwater Treatment System Assessment," by Milone and MacBroom, Dated February 28, 2020.
- Electronic Copy: "Drainage Analysis Summary for The Village ay Banfield Woods," By TFMoran, Dated March 23, 2020.

TFMoran, Inc.  
48 Constitution Drive, Bedford, NH 03110  
NH 03801  
T(603) 472-4488      www.tfmoran.com



TFMoran, inc. Seacoast Division  
170 Commerce Way-Suite 102, Portsmouth,  
T(603) 431-2222

To facilitate your review of the plans, we have provided TAC comments along with our responses, which are shown in **bold blue**.

**Comments from the January TAC Review for Condominium Development:**

1. Plans are generally incomplete for this level of review. They are also shown at a scale that is too large to show all the detailing.  
*Response: Dave Desfosses (DPW) clarified they wanted more detail on the Stormtech Systems and the ecopassages only. More details for the underground stormwater management system have been provided. Additionally, 2 meetings with CMA, DPW Staff and City Staff have been held to discuss the details of the underground stormwater management systems and the three ecopassages. The revised plan set addresses the concerns on the underground stormwater management systems, and we are in the process of obtaining concurrence with CMA.*
2. The utility plans are not showing water lines for fire suppression.  
*Response: Additional water services are shown for fire suppression. (See Sheets C-12 through C-15.)*
3. Is the proposed common open space designated under a recordable conservation restriction? Additionally, what are the limits of the common open space and how are areas abutting the LCAs behind and beside the proposed houses protected from encroachment over time. How is the common open space proposed to be monumental and/or fenced to prevent unauthorized encroachment into the buffer zone areas?  
*Response: The LCAs have been revised to be more square and are shown on the condominium site plan (S-03) as required in the Open Space Planned Unit Development Regulations. The common area behind the LACs will be monumented to prevent unauthorized encroachment into the buffer zone. The common open space will not be designated under a recordable conservation easement, however, it will be part of the recordable condominium documents.*
4. The narrow roadways and driveways, together with a lack of visitor parking, will likely result in vehicles parking along the main roadway and causing difficulty for 2-way traffic within the site. Applicant should indicate areas for visitor parking, perhaps around the cul-de-sac.  
*Response: At the June work session, visitor parking was provided and TAC recommended removing it. The long-shared drives have been widened to 18' to allow additional visitor parking and emergency access.*
5. Confirm that you did not include the proposed LCAs in the calculation of common open space.  
*Response: The LCAs are not included in the common opens space calculations.*
6. In your summary of zoning requirements, please add a column for "proposed" next to "required"  
*Response: This column was added. (See Sheet S-03.)*

7. The applicant will need to be prepared to make the case to the Planning Board how the OSPUD goals are satisfied by this proposed development, specifically “preserve natural features” and “create usable open space” and that “the anticipated impacts of the proposed PUD on traffic, market values, stormwater runoff or environmental factors will not be more detrimental to the surrounding area than the impacts of conventional residential development of the site.”

*Response: Only 7.33 acres of the 44.88 acres is being developed (16%). The total upland on the site (including the buffer area) is 25.54 acres. Only 28% of the upland is being impacted. A large contiguous portion of the lot will remain in its natural vegetated state. We are also creating usable open space contiguous with the conservation land on Map 255, Lot 3. The Stormwater Management Report shows there will be no increases in off-site flows from the new development; the stormwater will be treated in accordance with city and state standards. A conventional subdivision on this property would create the same number of single-family lots as the OSPUD. The impacts on traffic and market values would be similar to that of a conventional subdivision. The OSPUD reduces the impervious area.*

8. Sections 10.725.44 and 45 encourage community open space that connects to other public or private open spaces and allows for public access. Has the applicant explored this as staff previously suggested?

*Response: The open space and common area abuts land currently under a conservation easement on Map 255, Lot 3. (See Sheet S-03). Access to the open space is available through the abutting conservation easement. Public access to the open space is not viable from this property as it would create additional wetland impact.*

9. Did the applicant consider whether two-family or townhomes might be feasible in order to minimize impervious surface and overall site impacts?

*Response: We did consider two-family and townhouses for this site. When considering the access, parking, wastewater, utilities and impervious area; impacts are very similar. Given the similarities, the applicant has chosen single-family homes.*

10. The report provided by Mr. Gove and the peer review comments provided to the Conservation Commission note there will be significant impacts to habitat and existing natural features. The peer review comments also noted that some of the analysis provided by Mr. Gove was incomplete. How is the applicant proposing to address the outstanding concerns in this regard?

*Response: See Gove Environmental's letter entitled "Response to Mark West Review of January 28, 2020 and questions related to Wildlife corridors as related to the site", submitted to the City on February 28, 2020.*

11. If septic systems are proposed than the City will require full designs being submitted for review. This will likely include third party review as well. There is a marginal amount of soil on site and septic systems will need to be designed carefully with contingencies. The applicant should consider installing a force main to Peverley Hill Rd.

*Response: Full designs will be submitted upon approval of the project.*

*Preliminary information was provided to the City's review engineer to demonstrate that systems were feasible in this area. Installing a force main to Peverley Hill Road would incur additional wetland impacts and temporarily impact traffic flow. These impacts are not necessary as the site is suitable for septic systems.*

12. The runoff from the site will go to an existing wetland area. There have been concerns by current residents in this area about impacts from runoff along the roadway and flooding of properties in heavy rain events. What is this project doing to reduce the stormwater in this area, so the current impacts seen by residents is not made worse?

*Response: The post development flows do not increase from the pre-development flows. Flows for larger storms were decreased. The post development stormwater elevation at the culvert crossing remain the same or slightly lower than pre-development stormwater elevations.*

13. The design of the stormwater features is also not complete and is conceptually flawed. The systems should not be placed under the roadways as when they need to be worked on or replaced, there will be no access to homes. These stormwater areas should be placed adjacent to the roadways for access and inspections. TAC requests a third-party peer review of the stormwater analysis.

*Response: Two meetings have been held with the City and their review engineer (CMA) to demonstrate the stormwater design is adequate. Additional revisions have been made to eliminate one underground system and split the other system into multiple units to facilitate unforeseen future maintenance. A second underdrain system was provided to ensure that ground water would not flow into the stormwater drainage system.*

*This stormwater system design was proposed to address the Conservation Commissions comments to reduce buffer impact.*

14. An 8" water main will be required for fire flow to hydrants.

*Response: An 8" water main has been provided on the plans. (See Sheets C-12 through C-15.)*

15. A deceleration lane (or shoulder) may be required for an entrance drive that is so narrow. Typical speeds/traffic load on Banfield Rd require more thought on this driveway. Maybe the driveway should be wider near the road?

*Response: Mr. Eby responded that Mr. Pernaw addressed this in the traffic memorandum, it is fine as designed. Further, a deceleration lane or wider roadway entrance would require additional wetland impact.*

16. The applicant's plan of three individual crossings seems flawed and overly complex. A small bridge meeting current codes or other another design that is more appropriate and located a little farther from Banfield Road should be considered.

*Response: A bridge is not an option as adequate elevation over the wetland does not exist. After discussion with DPW, the requirement of 2% for 20' was reduced allowing us to relocated the ecopassages to increase the height of the tunnels. Two ecopassages are slightly over 24 inches in height, as recommended in the ecopassage documents, and one is 23 inches in height.*

17. Curb stops for water shut offs should not be located in paved areas.

*Response: These have been relocated.*

18. A blanket easement will be required for the entire developed portion so that water department personnel can access valves, hydrants and meters for leak detection and metering. Hydrants will need a maintenance program set up. Main maintenance will be private.

*Response: This has been provided, as noted on Sheet S-03.*

19. Please add stationing to roadway.

*Response: Stationing was added to the Site Layout Plans.*

20. There appears to be a very deep ledge cut on the far side of the wetland crossing. It seems like the crossing spot was chosen to minimize wetland disturbance in lieu of constructability and long-term maintenance.


*Response: The wetland permit requires us to cross where there is the least disturbance to the wetland. This crossing location is preferred by the Conservation Commission and NHDES; and the road can be constructed where depicted on the plans.*

21. There will need to be a tapping saddle and valve on the 20" main in Banfield to supply water. Therefore, the valve shown in the entrance drive is not required.

*Response: This has been revised and shown on the plans. (See Sheet C-13.)*

We trust the above responses satisfy the concerns expressed at the January meeting of the Technical Advisory Committee. We look forward to discussing these or at the next TAC meeting.

Respectfully,  
TFMoran, Inc.



Jack McTigue, PE  
Senior Project Manager

JJM/sdr

cc: Rick Green, Michael Green and Jenna Green

**GENERAL INFORMATION**

**OWNER**  
 MAP 256 LOT 2  
 MAUD HETT REVOCABLE TRUST  
 334 HUDSON ROAD  
 STOWE, MA 01775

**APPLICANT/PREPARED FOR**

GREEN AND COMPANY REAL ESTATE  
 11 LAFAYETTE RD, SUITE X  
 NORTH HAMPTON, NH 03868

**RESOURCE LIST**

PLANNING/ZONING DEPARTMENT  
 1 JUNKINS AVE  
 PORTSMOUTH, NH 03801  
 603-610-7216  
 JULIET WALKER, PLANNING DIRECTOR

BUILDING DEPARTMENT  
 1 JUNKINS AVE  
 PORTSMOUTH, NH 03801  
 603-610-7243  
 ROBERT MARSILIA,  
 CHIEF BUILDING INSPECTOR

PUBLIC WORKS  
 600 PEVERLY HILL RD  
 PORTSMOUTH, NH 03801  
 603-427-1530  
 PETER RICE, PUBLIC WORKS DIRECTOR

POLICE DEPARTMENT  
 3 JUNKINS AVE  
 PORTSMOUTH, NH 03801  
 603-427-1510  
 ROBERT MERNER, CHIEF

FIRE DEPARTMENT  
 170 COURT STREET  
 PORTSMOUTH, NH 03801  
 603-427-1515  
 TODD GERMAIN, CHIEF

**ASSOCIATED PROFESSIONALS**

ENVIRONMENTAL SERVICES  
 GOVE ENVIRONMENTAL SERVICES  
 8 CONTINENTAL DRIVE  
 BUILDING 2 - UNIT H  
 EXETER, NH 03833

SOIL SCIENTIST  
 GOVE ENVIRONMENTAL SERVICES, INC.  
 8 CONTINENTAL DRIVE  
 BUILDING 2 - UNIT H  
 EXETER, NH 03833  
 JIM GOVE, CERTIFIED SOIL SCIENTIST

TRAFFIC ENGINEER  
 STEPHEN G. PERNAW  
 & COMPANY, INC.  
 PO BOX 1721  
 CONCORD, NH 03302  
 (603) 731-8500  
 STEPHEN G. PERNAW, PE, PTOE


SURFACE DISPOSAL SYSTEM  
 DESIGNER  
 G. R. SPAULDING DESIGN  
 CONSULTANTS LLC.  
 P.O. BOX 248  
 CANTERBURY, NH 03224  
 GARY R. SPAULDING, SSD

# THE VILLAGE AT BANFIELD WOODS

**BANFIELD ROAD  
 PORTSMOUTH, NEW HAMPSHIRE**

**SEPTEMBER 25, 2019  
 LAST REVISED MARCH 20, 2020**

**VICINITY PLAN**



**INDEX OF SHEETS**


SHEET	SHEET TITLE
C-00	COVER
P-01	PRESENTATION LANDSCAPE PLAN
C-01	NOTES & LEGEND
S-01	EXISTING CONDITIONS PLAN
S-02	WETLAND IMPACT PLAN
S-03	CONDOMINIUM SITE PLAN
C-02	WETLAND IMPACT PLAN
C-03	SITE PREPARATION PLAN
C-04	OVERALL SITE LAYOUT PLAN
C-05 - C-07	SITE LAYOUT PLAN
C-08	OVERALL GRADING & DRAINAGE PLAN
C-09 - C-11	GRADING & DRAINAGE PLAN
C-12	OVERALL UTILITY PLAN
C-13 - C-15	UTILITY PLAN
C-16 - C-19	LANDSCAPE PLAN
C-20	LIGHTING PLAN
C-21 - C-22	ROAD-A PROFILE
C-23 - C-25	EROSION CONTROL PLAN
C-26	EROSION CONTROL NOTES
C-27	WETLAND CROSSING PLAN
C-28 - C-31	FIRE TRUCK MOVEMENT PLAN
C-32 - C-37	DETAILS
REFERENCE PLANS BY ASSOCIATED PROFESSIONALS	
-	ARCHITECTURAL ELEVATION PLAN

**SITE DEVELOPMENT PLANS**

TAX MAP 256 LOT 2  
**COVER**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**  
 OWNED BY  
**WALTER D HETT TRUST**  
 PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**

SCALE: NTS SEPTEMBER 25, 2019

Copyright 2019 © Thomas F. Moran, Inc.  
 48 Constitution Drive, Bedford, N.H. 03110  
 All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.  
 This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.



**THESE PLANS ARE PERMIT DRAWINGS ONLY AND HAVE NOT BEEN DETAILED FOR CONSTRUCTION OR BIDDING.**

REV	DATE	DESCRIPTION	DR	CK
4	3/20/2020	PROGRESS PRINT	RCK	JJM
3	3/4/2020	UPDATE PLANS PER REGULATORY COMMENTS	RCK	JJM
2	12/27/2019	IN HOUSE REVISIONS	RCK	JJM
1	12/23/19	REVISED PER REGULATORY COMMENTS	RCK	JJM

Civil Engineers Structural Engineers Traffic Engineers Land Surveyors Landscape Architects Scientists	48 Constitution Drive Bedford, NH 03110 Phone (603) 472-4488 Fax (603) 472-9747 www.tfmoran.com
	F I L E 47361.00 DR RCK FB CK JUM CADFILE COVER

Mar 23, 2020 - 4:39pm  
 F:\MSC Projects\47361 - Portsmouth\47361-00 - Green & Co - Banfield Road\Design\Production Drawings\Cover.dwg

LEGEND	
<b>PROPOSED</b>	
	LARGE DECIDUOUS SHRUBS
	SMALL DECIDUOUS SHRUBS
	LARGE EVERGREEN SHRUBS
	SMALL EVERGREEN SHRUBS
	EVERGREEN TREE
	ORNAMENTAL DECIDUOUS TREE
	MAJOR DECIDUOUS TREE

NOTE: SELECTED LANDSCAPE PLANT SPECIES TO BE NATIVE OR IMPROVED NATIVE TO NEW ENGLAND.



HORIZONTAL SCALE 1"=50'  
50 25 0 50

MAP 266 LOT 3  
N/F  
ANDREW R. & CAROL ANN CROTEAU  
285 BANFIELD ROAD  
PORTSMOUTH, NH 03801  
RCRD BK. # 1843 PG. # 336

MAP 266 LOT 1  
N/F  
RICCI CONSTRUCTION CO INC  
225 BANFIELD ROAD  
PORTSMOUTH, NH 03801  
RCRD BK. # 2527 PG. # 0322

MAP 266 LOT 2  
N/F  
DENISE ARNOLD  
261 BANFIELD ROAD  
PORTSMOUTH, NH 03801  
RCRD BK. # 3644 PG. # 1

**SITE DEVELOPMENT PLANS**

TAX MAP 256 LOT 2  
**PRELIMINARY LANDSCAPE PLAN**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**  
OWNED BY  
**WALTER D HETT TRUST**  
PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**

SCALE: 1"=50'

SEPTEMBER 25, 2019



Civil Engineers  
Structural Engineers  
Traffic Engineers  
Land Surveyors  
Landscape Architects  
Scientists

48 Constitution Drive  
Bedford, NH 03110  
Phone (603) 472-4488  
Fax (603) 472-9747  
www.tfmoran.com

FILE	47361.00	DR	RCK	FB		
		CK	JJM	CADFILE	LANDSCAPE	P-01






SSSS SYMBOL		SSSS MAP NAME		HYDROLOGIC SOIL GROUP	
41	CHATFIELD-HOLLIS-ROCK OUTCROP COMPLEX	B		B	
135	CHATFIELD VARIANT-NEWFIELDS COMPLEX	C		C	
538	SQUAMSCOTT FINE SANDY LOAM	C		C	
656	RIDGEBURY FINE SANDY LOAM	C		C	

SOILS LEGEND:		SOILS LEGEND:	
SLOPE PHASE:	ALPHA	SLOPE PHASE:	ALPHA
0-8%	B	0-8%	B
8-15%	C	8-15%	C
15-25%	D	15-25%	D
25%+	E	25%+	E

MAP 256 LOT 3  
N/F  
SHIRLEY N. GARRETT REV  
TRUST 2000  
BARBERRY LANE  
PORTSMOUTH, NH 03801  
RCRD BK. # 4298 PG. # 2633

LINE	BEARING	DISTANCE
L1	N 14°03'49" W	163.61'
L2	N 62°46'56" E	140.17'
L3	N 60°47'10" E	174.31'
L4	N 61°20'44" E	105.56'
L5	N 60°58'42" E	115.75'
L6	S 40°08'01" W	22.98'
L7	S 48°30'23" E	159.80'
L8	S 45°44'06" E	110.28'
L9	S 58°19'16" W	135.27'
L10	S 53°23'55" W	154.49'
L11	S 51°24'17" W	145.51'
L12	S 48°41'16" W	83.08'
L13	S 48°05'39" W	99.00'
L14	S 52°42'36" W	173.00'
L15	S 57°03'44" W	173.81'
L16	S 60°20'11" W	108.27'
L17	S 57°50'14" W	143.89'
L18	S 59°00'53" W	162.66'
L19	S 60°14'59" W	117.96'
L20	S 59°39'51" W	113.08'
L21	S 58°23'21" W	176.30'



**NOTES:**

- THE PARCEL IS LOCATED IN THE SINGLE RESIDENCE A (SRA) ZONING DISTRICT.
- THE PARCEL IS SHOWN ON THE CITY OF PORTSMOUTH ASSESSOR'S MAP 256 AS LOT 2.
- THE PARCEL IS LOCATED IN ZONE X AS SHOWN ON NATIONAL FLOOD INSURANCE PROGRAM (NFIP), FLOOD INSURANCE RATE MAP (FIRM) ROCKINGHAM COUNTY, NEW HAMPSHIRE, PANEL 270 OF 681, MAP NUMBER 33015C0270E, WITH AN EFFECTIVE DATE OF MAY 17, 2005.
- DIMENSIONAL REQUIREMENTS:**  
MINIMUM LOT SIZE: 1 ACRE  
MINIMUM LOT AREA PER DWELLING UNIT: 1 ACRE  
CONTINUOUS STREET FRONTAGE: 150'  
LOT DEPTH: 200'  
MINIMUM YARD DIMENSIONS:  
FRONT: 30'  
SIDE: 20'  
REAR: 40'  
**MAXIMUM STRUCTURE DIMENSIONS:**  
STRUCTURE HEIGHT: 35'(SLOPED ROOF) 30'(FLAT ROOF)  
BUILDING COVERAGE: 10%  
MINIMUM OPEN SPACE: 50%  
PER THE CITY OF PORTSMOUTH ZONING ORDINANCE SECTION 10.520.
- OWNER OF RECORD:**  
MAP 256 LOT 2:  
N/F  
THE WALTER D. HETT TRUST  
WALTER D. HETT, TRUSTEE  
334 HUDSON ROAD  
STOW, MA 01775  
RCRD BK.#4553 PG.#432
- PARCEL AREA:**  
MAP 256 LOT 2:  
1,955,150 S.F.  
(44.884 ACRES)
- THE INTENT OF THIS PLAN IS TO SHOW THE LOCATION OF BOUNDARIES IN ACCORDANCE WITH THE CURRENT LEGAL DESCRIPTIONS. IT IS NOT AN ATTEMPT TO DEFINE THE EXTENT OF OWNERSHIP OR DEFINE THE LIMITS OF TITLE.
- THE PURPOSE OF THIS PLAN IS TO SHOW THE BOUNDARY LINES, TOPOGRAPHY AND CURRENT SITE FEATURES OF MAP 256 LOT 2.
- FIELD SURVEY COMPLETED BY TCE AND EJS IN MAY & JUNE 2019 USING A TOPCON DS103 AND A TOPCON FC-5000 DATA COLLECTOR.
- HORIZONTAL DATUM IS NAD83 (2011) PER STATIC GPS OBSERVATIONS. THE VERTICAL DATUM IS NAVD88 (GEOID12B) PER STATIC GPS OBSERVATIONS. THE CONTOUR INTERVAL IS 2 FEET.
- EASEMENTS, RIGHTS, AND RESTRICTIONS SHOWN OR IDENTIFIED ARE THOSE WHICH WERE FOUND DURING RESEARCH PERFORMED AT THE ROCKINGHAM COUNTY REGISTRY OF DEEDS. OTHER RIGHTS, EASEMENTS, OR RESTRICTIONS MAY EXIST WHICH A TITLE EXAMINATION OF SUBJECT PARCEL(S) WOULD DETERMINE.
- THE LOCATION OF ANY UNDERGROUND UTILITY INFORMATION SHOWN ON THIS PLAN IS APPROXIMATE. TFMORAN, INC. MAKES NO CLAIM TO THE ACCURACY OR COMPLETENESS OF UNDERGROUND UTILITIES SHOWN. PRIOR TO ANY EXCAVATION ON SITE THE CONTRACTOR SHALL CONTACT DIG SAFE.
- WETLAND DELINEATION WAS COMPLETED BY GOVE ENVIRONMENTAL SERVICES IN MAY, 2019 IN ACCORDANCE WITH THE 1987 ARMY CORP OF ENGINEERS WETLAND MANUAL AND THE 2012 REGIONAL SUPPLEMENT TO THE CORPS OF ENGINEERS WETLAND DELINEATION MANUAL: NORTHCENTRAL AND NORTHEAST REGION. FIELD LOCATED BY TFMORAN, INC.
- SEE SHEET C-02 FOR TEST PIT & LEDGE PROBE LOGS.
- SOILS NOTE:**  
THIS MAP PRODUCT IS WITHIN THE TECHNICAL STANDARDS OF THE NATIONAL COOPERATIVE SOIL SURVEY. IT IS A SPECIAL PURPOSE PRODUCT, INTENDED FOR INFILTRATION REQUIREMENTS BY THE NH DES ALTERATION OF TERRAIN BUREAU. IT WAS PRODUCED BY A PROFESSIONAL SOIL SCIENTIST, AND IS NOT A PRODUCT OF THE USDA NATURAL RESOURCES CONSERVATION SERVICE. THERE IS A REPORT THAT ACCOMPANIES THIS MAP.  
THE SITE SPECIFIC SOIL SURVEY (SSSS) WAS PRODUCED DECEMBER 19, 2019 AND WAS PREPARED BY JAMES P. GOVE, CSS # 004, GOVE ENVIRONMENTAL SERVICES, INC. THE SURVEY AREA IS LOCATED ON BANFIELD ROAD, PORTSMOUTH, NH.  
SOILS WERE IDENTIFIED WITH THE NEW HAMPSHIRE STATE-WIDE NUMERICAL SOIL LEGEND, USDA NRCS, DURHAM, NH, ISSUE # 10, JANUARY 2011. THE NUMERIC LEGEND WAS AMENDED TO IDENTIFY THE CORRECT SOIL COMPONENTS OF THE COMPLEX.  
HYDROLOGIC SOIL GROUP FROM KSAT VALUES FOR NEW HAMPSHIRE SOILS, SOCIETY OF SOIL SCIENTISTS OF NEW ENGLAND, SPECIAL PUBLICATION NO. 5, SEPTEMBER, 2009.

**PLAN REFERENCES:**

- "SUBDIVISION PLAN FOR WALTER D. HETT & THE TEMPLE OF ISRAEL BANFIELD ROAD COUNTY OF ROCKINGHAM PORTSMOUTH, NH", BY MILLETTE, SPRAGUE, AND COLWELL, INC. DATED JUNE 25, 1999 WITH REVISION 3 DATED 12/02/99. RCRD PLAN D-27695.
- "PROPERTY OF SWIFTWATER GIRL SCOUT COUNCIL, CITY OF PORTSMOUTH" BY JON MOORE DATED AUGUST 1972. RCRD PLAN D-3206



I CERTIFY THAT THIS SURVEY AND PLAN WERE PREPARED BY THOSE UNDER MY DIRECT SUPERVISION AND ARE THE RESULT OF A FIELD SURVEY CONDUCTED IN JUNE 2019. THIS SURVEY CONFORMS TO THE ACCURACY REQUIREMENTS OF AN URBAN SURVEY OF THE NEW HAMPSHIRE CODE OF ADMINISTRATIVE RULES OF THE BOARD OF LICENSURE FOR LAND SURVEYORS. I FURTHER CERTIFY THAT THIS SURVEY IS CORRECT TO THE BEST OF MY PROFESSIONAL KNOWLEDGE, AND THE FIELD TRAVERSE SURVEY EXCEEDS A PRECISION OF 1:15,000.

\_\_\_\_\_  
LICENSED LAND SURVEYOR  
DATE \_\_\_\_\_

**LEGEND:**

- |   |      |                                     |
|---|------|-------------------------------------|
| ASSESSOR'S MAP NUMBER/<br>LOT NUMBER    | AG   | ABOVE GRADE                         |
| BK./PG.                                 | BG   | BELOW GRADE                         |
| EL                                      | BS   | BOOK/PAGE                           |
| ES                                      | BU   | BUILDING                            |
| NRP                                     | EV   | ELEVATION                           |
| I                                       | ES   | EVERSOURCE                          |
| INDUSTRIAL                              | NR   | NATURAL RESOURCE PROTECTION         |
| INVERT                                  | IND  | INDUSTRIAL                          |
| DUCTILE IRON                            | INV  | INVERT                              |
| LEDGE PROBE                             | DI   | DUCTILE IRON                        |
| NOW OR FORMERLY                         | LP   | LEDGE PROBE                         |
| PUBLIC SERVICE COMPANY OF NEW HAMPSHIRE | N/F  | NOW OR FORMERLY                     |
| RURAL                                   | R    | RURAL                               |
| REINFORCED CONCRETE PIPE                | RCP  | REINFORCED CONCRETE PIPE            |
| ROCKINGHAM COUNTY REGISTRY OF DEEDS     | RCRD | ROCKINGHAM COUNTY REGISTRY OF DEEDS |
| SINGLE RESIDENCE A                      | SRA  | SINGLE RESIDENCE A                  |
| SQUARE FEET                             | S.F. | SQUARE FEET                         |
| TEMPORARY BENCH MARK                    | TBM  | TEMPORARY BENCH MARK                |
| TEST PIT                                | TP   | TEST PIT                            |
| TEST PIT/LEDGE PROBE                    | TP   | TEST PIT/LEDGE PROBE                |
| MAILBOX                                 | MB   | MAILBOX                             |
| GUY WIRE                                | GW   | GUY WIRE                            |
| HYDRANT                                 | HY   | HYDRANT                             |

- SIGN
- UTILITY POLE W/LIGHT
- UTILITY POLE
- WATER SHUTOFF VALVE
- WATER VALVE
- GAS VALVE
- BOULDER
- PROPERTY LINE
- DRAIN LINE
- EXISTING CONTOUR
- GAS LINE
- OVERHEAD UTILITY LINE
- WATER MAIN
- CHAINLINK FENCE
- STONEWALL
- TREELINE
- WETLAND SETBACK
- EDGE OF WETLAND
- SOILS LINE



Copyright 2020 © Thomas F. Moran, Inc.  
48 Constitution Drive, Bedford, N.H. 03110  
All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.  
This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.



CONTACT DIG SAFE 72 BUSINESS HOURS PRIOR TO CONSTRUCTION

**TAX MAP 256 LOT 2**  
**EXISTING CONDITIONS PLAN**  
**BANFIELD ROAD**  
**PORTSMOUTH, NEW HAMPSHIRE**  
**COUNTY OF ROCKINGHAM**  
OWNED BY  
**THE WALTER D. HETT TRUST**  
PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**

SCALE: 1" = 100' (22x34)  
1" = 200' (11x17) SEPTEMBER 25, 2019

<b>TFM</b>	<b>MSC</b>	Civil Engineers	170 Commerce Way, Suite 102
		Structural Engineers	Portsmouth, NH 03801
		Traffic Engineers	Phone (603) 431-2222
		Land Surveyors	Fax (603) 431-0910
		Landscape Architects	www.tfmoran.com
		Scientists	

A division of TFMoran, Inc.

FILE	47361-00	DR	EJS	FB	559	S-01
REV.	DATE	DESCRIPTION	DR	CK		

Map 02 2020 - 1:27am  
F:\MSC Projects\47361 - Banfield Road - Portsmouth\47361-100 - Green & Co - Banfield Road\Ca\Survey\Drawings\47361-100 Survey.dwg




CITY OF PORTSMOUTH PLANNING BOARD

CHAIRPERSON \_\_\_\_\_ DATE \_\_\_\_\_

LINE	BEARING	DISTANCE
L1	N 14°03'49" W	163.61'
L2	S 62°46'56" E	140.17'
L3	N 80°47'10" E	174.31'
L4	N 61°20'44" E	105.56'
L5	N 60°58'42" E	115.75'
L6	S 40°08'01" E	22.98'
L7	S 48°30'23" E	159.80'
L8	S 45°44'06" E	110.28'
L9	S 58°19'16" W	135.27'
L10	S 53°23'55" W	154.49'
L11	S 51°04'17" W	145.51'
L12	S 45°41'16" W	83.08'
L13	S 48°05'39" W	99.00'
L14	S 52°42'36" W	173.00'
L15	S 57°03'44" W	173.81'
L16	S 60°20'11" W	108.27'
L17	S 57°50'14" W	143.88'
L18	S 59°00'53" W	162.66'
L19	S 60°14'59" W	117.96'
L20	S 59°39'51" W	113.08'
L21	S 58°23'21" W	176.30'

LOCATION PLAN



NOTES:

- THE PARCEL IS LOCATED IN THE SINGLE RESIDENCE A (SRA) ZONING DISTRICT.
- THE PARCEL IS SHOWN ON THE CITY OF PORTSMOUTH ASSESSOR'S MAP 256 AS LOT 2.
- THE PARCEL IS LOCATED IN ZONE X AS SHOWN ON NATIONAL FLOOD INSURANCE PROGRAM (NFIP), FLOOD INSURANCE RATE MAP (FIRM) ROCKINGHAM COUNTY, NEW HAMPSHIRE, PANEL 270 OF 681, MAP NUMBER 3301500270E, WITH AN EFFECTIVE DATE OF MAY 17, 2005.
- DIMENSIONAL REQUIREMENTS:**  

REQUIRED:	PROPOSED:
MINIMUM LOT SIZE:	1 ACRE / 44.884 ACRES
LOT AREA PER DWELLING UNIT:	1 ACRE / N/A
CONTINUOUS STREET FRONTAGE:	150' / 1,730'
LOT DEPTH:	200' / 876'

**MINIMUM YARD DIMENSIONS:**  
 FRONT: 30' / 254'  
 SIDE: 20' / 53'  
 REAR: 40' / 89.9'  
**MAXIMUM STRUCTURE DIMENSIONS:**  
 STRUCTURE HEIGHT: 35' (SLOPED ROOF) / 30' (FLAT ROOF)  
 BUILDING COVERAGE: 10% / 2.12%  
 MINIMUM OPEN SPACE: 50% / 94.67%  
 PER THE CITY OF PORTSMOUTH ZONING ORDINANCE SECTION 10.520.  
**OPEN SPACE RESIDENTIAL PUD (OS-PUD):**  

REQUIRED:	PROPOSED:
MINIMUM LOT AREA:	10 ACRES / 44.884 ACRES
MINIMUM STREET FRONTAGE:	100' / 1,730'
MINIMUM EXTERNAL YARDS:	
FRONT:	100' / 254'
SIDE & REAR:	50' / 53.0'; 89.9'
MINIMUM INTERNAL YARDS:	
FRONT:	20' / 20.9'
SIDE & REAR:	25' / 53.0'; 89.9'
MINIMUM SEPARATION BETWEEN STRUCTURES:	30' / 31.0'
MINIMUM OPEN SPACE:	25% / 94.67%
PER THE CITY OF PORTSMOUTH ZONING ORDINANCE SECTION 10.725	
- OWNER OF RECORD:  
 MAP 256 LOT 2:  
 THE WALTER D. HETT TRUST  
 WALTER D. HETT, TRUSTEE  
 334 HUDSON ROAD  
 STOW, MA 01775  
 RCRD BK.#4553 PG.#432
- TOTAL PARCEL AREA:**  
 MAP 256 LOT 2:  
 1,955,150 S.F. (44.884 ACRES)  
**COMMON AREA:**  
 1,955,150 S.F. (44.884 ACRES)
- THE INTENT OF THIS PLAN IS TO SHOW THE LOCATION OF BOUNDARIES IN ACCORDANCE WITH THE CURRENT LEGAL DESCRIPTIONS. IT IS NOT AN ATTEMPT TO DEFINE THE EXTENT OF OWNERSHIP OR DEFINE THE LIMITS OF TITLE.
- THE PURPOSE OF THIS PLAN IS TO DEPICT THE COMMON AREAS AND LIMITED COMMON AREAS ASSOCIATED WITH THE OPEN SPACE PLANNED UNIT DEVELOPMENT OF MAP 256 LOT 2. CONSTRUCTION OF UNITS NOT YET BEGUN. THE FINAL METES AND BOUNDS OF THE UNITS AND THEIR ASSIGNED LIMITED COMMON AREAS SHALL BE DETERMINED BY AS-BUILT PLANS WITH AN AMENDED CONDOMINIUM SITE PLAN TO BE RECORDED UPON COMPLETION OF EACH UNIT.
- THESE UNITS ARE FOR RESIDENTIAL USE ONLY.
- FIELD SURVEY COMPLETED BY TCE AND EJS IN MAY & JUNE 2019 USING A TOPCON DS103 AND A TOPCON FC-5000 DATA COLLECTOR.
- HORIZONTAL DATUM IS NAD83 (2011) PER STATIC GPS OBSERVATIONS.
- EASEMENTS, RIGHTS, AND RESTRICTIONS SHOWN OR IDENTIFIED ARE THOSE WHICH WERE FOUND DURING RESEARCH PERFORMED AT THE ROCKINGHAM COUNTY REGISTRY OF DEEDS. OTHER RIGHTS, EASEMENTS, OR RESTRICTIONS MAY EXIST WHICH A TITLE EXAMINATION OF SUBJECT PARCEL(S) WOULD DETERMINE.
- WETLAND DELINEATION WAS COMPLETED BY GOVE ENVIRONMENTAL SERVICES IN MAY, 2019 IN ACCORDANCE WITH THE 1987 ARMY CORP OF ENGINEERS WETLAND MANUAL AND THE 2012 REGIONAL SUPPLEMENT TO THE CORPS OF ENGINEERS WETLAND DELINEATION MANUAL: NORTHCENTRAL AND NORTHEAST REGION. FIELD LOCATED BY TFMORAN, INC.
- THE LOCATION OF ANY UNDERGROUND UTILITY INFORMATION SHOWN ON THIS PLAN IS APPROXIMATE. TFMORAN, INC. MAKES NO CLAIM TO THE ACCURACY OR COMPLETENESS OF UNDERGROUND UTILITIES SHOWN. PRIOR TO ANY EXCAVATION ON SITE THE CONTRACTOR SHALL CONTACT DIG SAFE.
- AN EASEMENT SHALL BE GRANTED TO THE CITY OF PORTSMOUTH TO ALLOW WATER DEPARTMENT PERSONNEL ACCESS TO VALVES, HYDRANTS AND METERS FOR LEAK DETECTION, METERING AND MAINTENANCE.

PLAN REFERENCES:


- "SUBDIVISION PLAN FOR WALTER D. HETT & THE TEMPLE OF ISRAEL BANFIELD ROAD COUNTY OF ROCKINGHAM PORTSMOUTH, NH", BY MILLETTE, SPRAGUE, AND COLWELL, INC. DATED JUNE 25, 1999 WITH REVISION 3 DATED 12/02/99. RCRD PLAN D-27695.
- "PROPERTY OF SWIFTWATER GIRL SCOUT COUNCIL, CITY OF PORTSMOUTH" BY JON MOORE DATED AUGUST 1972. RCRD PLAN D-3206

I HEREBY CERTIFY THAT THIS PLAN IS ACCURATE AND COMPLIES WITH NHRSA 356-B:20(1). ALL UNITS OR PORTIONS THEREOF DEPICTED ON ANY PORTION OF THE SUBMITTED LAND OTHER THAN WITHIN THE BOUNDARIES OF ANY CONVERTIBLE LAND HAVE NOT YET BEGUN.

I CERTIFY THAT THIS SURVEY AND PLAN WERE PREPARED BY ME OR BY THOSE UNDER MY DIRECT SUPERVISION. THIS SURVEY IS AN URBAN SURVEY AS CLASSIFIED IN THE NH CODE OF ADMINISTRATIVE RULES OF THE BOARD OF LICENSURE FOR LAND SURVEYORS. I CERTIFY THAT THIS SURVEY WAS MADE ON THE GROUND AND IS CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF. THE TRAVERSE WAS COMPLETED BY TOTAL STATION, WITH A PRECISION GREATER THAN 1:15,000.

LEGEND:

AG	ASSESSOR'S MAP NUMBER/ LOT NUMBER
BG	ABOVE GRADE
BK./PG.	BELOW GRADE
NRP	BOOK/PAGE
I	NATURAL RESOURCE PROTECTION
LCA	INDUSTRIAL
MON/TBS	LIMITED COMMON AREA
N/F	MONUMENT TO BE SET
PSF	NOW OR FORMERLY
PUD	PROPOSED SEPTIC FIELD
R	PLANNED UNIT DEVELOPMENT
RCRD	RURAL
SRA	ROCKINGHAM COUNTY REGISTRY OF DEEDS
S.F.	SINGLE RESIDENCE A
⊙	SQUARE FEET
○	BOULDER
---	PROPERTY LINE
—○—	CHAINLINK FENCE
—	STONEWALL
---	WETLAND SETBACK
---	EDGE OF WETLAND
▨	PAVEMENT
▨	WETLANDS
+	COMMON OPEN SPACE
+	100' WIDE ELECTRIC EASEMENT
+	12' RIGHT OF WAY



REV.	DATE	DESCRIPTION	ID	BMK
1	3/23/2020	REVISED LCA BOUNDARIES, ADDED NOTE 15		
			DR	CK



CONTACT DIG SAFE 72 BUSINESS HOURS PRIOR TO CONSTRUCTION

LIMITED COMMON AREA:

LCA	S.F.
LCA 1	8,071
LCA 2	7,950
LCA 3	12,048
LCA 4	13,016
LCA 5	12,587
LCA 6	7,108
LCA 7	13,804
LCA 8	11,038
LCA 9	13,443
LCA 10	13,550
LCA 11	15,500
LCA 12	12,483
LCA 13	10,714
LCA 14	14,387
LCA 15	18,120
LCA 16	12,304
LCA 17	15,553
LCA 18	11,591
LCA 19	7,470
LCA 20	9,677
LCA 21	15,268
LCA 22	13,160

MAP 256 LOT 1  
 N/F  
 SWIFT WATER GIRL SCOUT COUNCIL  
 ONE COMMERCE DRIVE  
 BEDFORD, NH 03110  
 RCRD BK.#2167 PG.#147  
 RCRD PLAN D-3206

MAP 256 LOT 2  
 1,955,150 S.F.  
 (44.884 AC)

MAP 256 LOT 2-1  
 N/F  
 TEMPLE OF ISRAEL  
 200 STATE STREET  
 PORTSMOUTH, NH 03801  
 RCRD BK.#3465 PG.# 1111

MAP 254 LOT 2  
 N/F  
 T. BEYAR REALTY LLC  
 14 LAFAYETTE ROAD-PO BOX 695  
 NORTH HAMPTON, NH 03842  
 RCRD BK.# 4004 PG.# 0763

MAP 254 LOT 1  
 N/F  
 RICCI CONSTRUCTION CO INC  
 225 BANFIELD ROAD  
 PORTSMOUTH, NH 03801  
 RCRD BK.# 1743 PG.# 0192

MAP 266 LOT 2  
 N/F  
 DENISE ARNOLD  
 261 BANFIELD ROAD  
 PORTSMOUTH, NH 03801  
 RCRD BK.# 3644 PG.# 1763

MAP 266 LOT 1  
 N/F  
 RICCI CONSTRUCTION CO INC  
 225 BANFIELD ROAD  
 PORTSMOUTH, NH 03801  
 RCRD BK.# 2527 PG.# 0322

MAP 266 LOT 1  
 N/F  
 RICCI CONSTRUCTION CO INC  
 225 BANFIELD ROAD  
 PORTSMOUTH, NH 03801  
 RCRD BK.# 0322

MAP 266 LOT 3  
 N/F  
 ANDREW R. & CAROL ANN CROTEAU  
 285 BANFIELD ROAD  
 PORTSMOUTH, NH 03801  
 RCRD BK.# 1843 PG.# 336

MAP 266 LOT 5  
 N/F  
 HOPE FOR TOMORROW FOUNDATION  
 1 STONERIDGE DRIVE  
 RYE, NH 03870  
 RCRD BK.# 5783 PG.# 602

Copyright 2020 © Thomas F. Moran, Inc.  
 48 Constitution Drive, Bedford, N.H. 03110  
 All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.  
 This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.

TFM MSC  
 A division of TFMoran, Inc.  
 Civil Engineers  
 Structural Engineers  
 Traffic Engineers  
 Land Surveyors  
 Landscape Architects  
 Scientists  
 170 Commerce Way, Suite 102  
 Portsmouth, NH 03801  
 Phone (603) 431-2222  
 Fax (603) 431-0910  
 www.tfmoran.com

F I L E N O	47361-00	DR	EJS	FB	559	S-03
C K	BMK	CAD/FE				

TAX MAP 256 LOT 2  
**CONDOMINIUM SITE PLAN**  
**BANFIELD ROAD**  
**PORTSMOUTH, NEW HAMPSHIRE**  
**COUNTY OF ROCKINGHAM**  
 OWNED BY  
**THE WALTER D. HETT TRUST**  
 PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**  
 SCALE: 1" = 100' (22x34) 1" = 200' (11x17) **DECEMBER 23, 2019**

Mar 23, 2020 - 4:17pm F:\MSC Projects\47361 - Banfield Road - Portsmouth\47361-100 - Green & Co - Banfield Road\Carlson Survey\Drawings\47361-100 Survey.dwg

MAP 256 LOT 3

N/F  
SHIRLEY N. GARRETT REV  
TRUST 2000  
BARBERRY LANE  
PORTSMOUTH, NH 03801  
RCRD BK. # 4298 PG. # 2633

- NOTES:
1. THE PURPOSE OF THIS PLAN IS TO SHOW THE WETLAND IMPACTS AND WETLAND BUFFER IMPACTS ASSOCIATED WITH THE CONDOMINIUM DEVELOPMENT OF TAX MAP 256 LOT 2.
  2. FIELD SURVEY WAS COMPLETED BY TCE AND EJS IN MAY & JUNE 2019 USING A TOPCON DS103 AND A TOPCON FC-5000 DATA COLLECTOR.
  3. THE PURPOSE OF THE BUILDING FOOTPRINTS SHOWN ON THE PLAN ARE FOR ILLUSTRATIVE PURPOSES ONLY. FOOTPRINTS MAY CHANGE DURING CONSTRUCTION, BUT WILL REMAIN WITHIN REQUIRED SETBACKS. INDIVIDUAL GRADING PLAN ARE REQUIRED FOR EACH AREA OF HOMES TO BE DEVELOPED (PRIOR TO BUILDING PERMIT).
  4. DENSITY CALCULATIONS:  
TOTAL LOT AREA: 44.88 ACRES  
WETLAND AREA: 18.97 ACRES  
STEEP SLOPES OVER 15%: 2.20 ACRES  
TOTAL DEVELOPABLE AREA: 23.71 ACRES (REMAINING LAND IS WETLANDS AND STEEP SLOPES OVER 15%)  
MAXIMUM UNITS FOR DEVELOPMENT: 23 SINGLE FAMILY HOUSES  
PROPOSED UNITS FOR OPEN SPACE PLANNED UNIT DEVELOPMENT: 22 UNITS
  5. PARKING CALCULATIONS:  
REQUIRED: 1.3 SPACES/UNIT PLUS ONE (1) VISITOR SPACE FOR EVERY 5 DWELLING UNITS.  
TOTAL REQUIRED = 33 SPACES  
  
PROPOSED: 88 SPACES (2 GARAGED SPACES PER UNIT, PLUS 44 SPACES ON PRIVATE DRIVEWAYS)
  6. WETLANDS DELINEATION WAS COMPLETED BY GOVE ENVIRONMENTAL SERVICES IN MAY 2019 AND FIELD LOCATED BY MSC A DIVISION OF TFMORAN, INC.
  7. STEEP SLOPE AREAS ARE APPROXIMATE. TOWN REGULATIONS DEFINE SLOPES OF 15% AND GREATER TO BE NON-BUILDABLE.
  8. EXAMINATION OF THE FLOOD INSURANCE RATE MAP FOR THE TOWN OF PORTSMOUTH, NEW HAMPSHIRE, ROCKINGHAM COUNTY, COMMUNITY PANEL NUMBER 0270, EFFECTIVE DATE: MAY 17, 2005, INDICATES THAT THE SUBJECT PARCEL IS NOT LOCATED WITHIN A FLOOD HAZARD AREA.
  9. WETLAND IMPACTS WILL REQUIRE AN APPLICATION TO NHDES WETLANDS BUREAU AND A CONDITIONAL USE PERMIT FROM THE CITY OF PORTSMOUTH. OBTAINING THESE PERMITS WILL DEPEND ON THE WETLAND FUNCTION AND VALUES, AND SENSITIVITY OF THE PROJECT.
  10. SITE DEVELOPMENT MAY REQUIRE RETAINING WALLS FOR GRADE CHANGES.
  11. PRIOR TO ANY EXCAVATION ON SITE THE CONTRACTOR SHALL CONTACT DIG SAFE AT 811.

WETLAND	WETLAND AREA	TEMPORARY WETLAND IMPACT	PERMANENT WETLAND IMPACT	BUFFER IMPACT
A	815,360 S.F.	1,135 S.F.	2,693 S.F.	10,052 S.F.
B	26,935 S.F.	0 S.F.	0 S.F.	3,583 S.F.
TOTALS	842,295 S.F.	3,828 S.F.		13,635 S.F.

LEGEND

PERMANENT WETLAND IMPACT  
TEMPORARY WETLAND IMPACT  
PERMANENT WETLAND BUFFER IMPACT  
P- PERMANENT  
T- TEMPORARY

TAX MAP 256 LOT 2  
**WETLAND IMPACT PLAN**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**  
OWNED BY  
**WALTER D HETT TRUST**  
PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**  
**1"=160' (11"X17")**  
**SCALE: 1"=80' (22"X34")** **SEPTEMBER 25, 2019**



**TFM** Civil Engineers  
Structural Engineers  
Traffic Engineers  
Land Surveyors  
Landscape Architects  
Scientists

48 Constitution Drive  
Bedford, NH 03110  
Phone (603) 472-4488  
Fax (603) 472-9747  
www.tfmoran.com

47361.00 DR RCK FB  
CK JUM CADFILE -  
WETLAND IMPACT

C-02

REV	DATE	DESCRIPTION	DR	CK
4	3/20/2020	PROGRESS PRINT	RCK	JJM
3	3/4/2020	UPDATE PLANS PER REGULATORY COMMENTS	RCK	JJM
2	12/27/2019	IN HOUSE REVISIONS	RCK	JJM
1	12/03/19	Revised Alignment Per Regulatory Comments	RCK	JJM



MAP 256 LOT 1  
N/F  
SWIFT WATER GIRL SCOUT COUNCIL  
ONE COMMERCE DRIVE  
BEDFORD, NH 03110  
RCRD BK.#2167 PG.#147  
RCRD PLAN D-3206

MAP 266 LOT 5  
N/F  
HOPE FOR TOMORROW FOUNDATION  
1 STONERIDGE DRIVE  
RYE, NH 03870  
RCRD BK. # 5783 PG. # 602

MAP 266 LOT 3  
N/F  
ANDREW R. & CAROL ANN CROTEAU  
285 BANFIELD ROAD  
PORTSMOUTH, NH 03801  
RCRD BK. # 1843 PG. # 336

MAP 266 LOT 1  
N/F  
RICCI CONSTRUCTION CO INC  
225 BANFIELD ROAD  
PORTSMOUTH, NH 03801  
RCRD BK. # 2527 PG. # 0322

MAP 266 LOT 2  
N/F  
DENISE ARNOLD  
261 BANFIELD ROAD  
PORTSMOUTH, NH 03801  
RCRD BK. # 3644 PG. # 1763


MAP 266 LOT 1  
N/F  
RICCI CONSTRUCTION CO INC  
225 BANFIELD ROAD  
PORTSMOUTH, NH 03801  
RCRD BK. # 2527 PG. # 0322

MAP 254 LOT 1  
N/F  
RICCI CONSTRUCTION CO INC  
225 BANFIELD ROAD  
PORTSMOUTH, NH 03801  
RCRD BK.# 1743 PG.# 0192

Mar 23, 2020 - 4:40pm  
F:\MISC Projects\47361 - Portsmouth\47361-00 - Green & Co - Banfield Road\Design\Production Drawings\Wetland Impact.dwg

Copyright 2019 © Thomas F. Moran, Inc.  
48 Constitution Drive, Bedford, N.H. 03110  
All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.  
This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.






- ### NOTES
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING AND DETERMINING THE LOCATIONS, SIZE, AND ELEVATIONS OF ALL EXISTING UTILITIES, SHOWN OR NOT SHOWN ON THESE PLANS PRIOR TO THE START OF ANY DEMOLITION. THE LOCATIONS SHOWN ON THESE PLANS ARE NOT GUARANTEED BY THE OWNER OR THE ENGINEER. THE ENGINEER SHALL BE NOTIFIED IN WRITING OF ANY UTILITIES INTERFERING WITH THE PROPOSED DEMOLITION TO DETERMINE APPROPRIATE ACTION TO BE TAKEN BEFORE PROCEEDING WITH THE WORK. IT IS ALSO THE CONTRACTOR'S RESPONSIBILITY TO ANTICIPATE CONFLICTS AND REPAIR EXISTING UTILITIES AS NECESSARY TO COMPLETE THE WORK AT NO ADDITIONAL COST TO THE OWNER.
  - THE CONTRACTOR SHALL MAINTAIN EMERGENCY ACCESS TO ALL AREAS AFFECTED BY WORK AT ALL TIMES.
  - EXISTING UTILITY SERVICES TO BE DISCONTINUED ARE TO BE CAPPED AS REQUIRED BY THE RESPECTIVE UTILITY COMPANIES.
  - CONSTRUCTION DEBRIS AND INVASIVE SPECIES SHALL BE REMOVED FROM SITE AND DISPOSED OF IN A LEGAL MANNER.
  - PRIOR TO THE START OF WORK, THE CONTRACTOR SHALL PLACE ORANGE CONSTRUCTION FENCING AROUND EACH TREE TO BE RETAINED, OR ADEQUATELY MARK, THROUGHOUT CONSTRUCTION. NO STOCKPILES OF MATERIAL ARE PERMITTED WITHIN THE DRIP LINE OF THE TREES TO BE SAVED.
  - CONTACT THE LANDSCAPE ARCHITECT IMMEDIATELY IF ANY TREES ARE DAMAGED DURING CONSTRUCTION.

- ### CONSTRUCTION SEQUENCE NOTES
- TO MINIMIZE EROSION AND SEDIMENTATION DUE TO CONSTRUCTION, CONSTRUCTION SHALL FOLLOW THIS GENERAL CONSTRUCTION SEQUENCE.
- MODIFICATIONS TO THE SEQUENCE NECESSARY DUE TO THE CONTRACTOR'S SCHEDULE SHALL INCLUDE APPROPRIATE TEMPORARY AND PERMANENT EROSION AND SEDIMENTATION CONTROL MEASURES.
- THE CONTRACTOR SHALL SCHEDULE WORK SUCH THAT ANY CONSTRUCTION AREA IS STABILIZED WITHIN 45 DAYS OF INITIAL DISTURBANCE EXCEPT AS NOTED BELOW. NO MORE THAN 5 ACRES OF DISTURBED LAND SHALL BE UNSTABILIZED AT ANY ONE TIME.
- THE PROJECT SHALL BE MANAGED SO THAT IT MEETS THE REQUIREMENTS AND INTENT OF RSA 430:53 AND CHAPTER ARG 3800 RELATIVE TO INVASIVE SPECIES.
- DO NOT DISCHARGE SEDIMENT-LADEN WATERS FROM CONSTRUCTION ACTIVITIES (RUNOFF, WATER FROM EXCAVATIONS) TO THE INFILTRATION BASIN.
  - DO NOT PLACE INFILTRATION SYSTEMS/BIORETENTION AREAS INTO SERVICE UNTIL THE CONTRIBUTING AREAS HAVE BEEN FULLY STABILIZED.
  - AFTER THE BASIN IS EXCAVATED TO THE FINAL DESIGN ELEVATION, THE FLOOR SHOULD BE DEEPLY TILLED WITH A ROTARY TILLER OR DISC HARROW TO RESTORE THE INFILTRATION RATES, FOLLOWED BY A PASS WITH A LEVELING DRAG.
- NOTIFY EASEMENT OWNERS PRIOR TO COMMENCEMENT OF WORK WITHIN THE RESPECTIVE EASEMENT.
  - INSTALL ALL PERIMETER EROSION PROTECTION MEASURES AS INDICATED ON THE PLANS PRIOR TO THE COMMENCEMENT OF CONSTRUCTION.
  - PONDS AND SWALES SHALL BE INSTALLED BEFORE ROUGH GRADING THE SITE.
  - DURING CONSTRUCTION EVERY EFFORT SHALL BE MADE TO MANAGE SURFACE RUNOFF QUALITY.
  - DAILY, OR AS REQUIRED, CONSTRUCT TEMPORARY BERMS, DRAINS, DITCHES, SILT BARRIERS, SEDIMENT TRAPS, ETC. MULCH AND SEED AS REQUIRED. (TEMPORARY SEED MIXTURE OF WINTER RYE APPLIED AT A RATE OF 2.5 LBS/1000 SF SHALL BE USED).
  - CONDUCT MAJOR EARTHWORK, INCLUDING CLEARING AND GRUBBING, WITHIN THE LIMITS OF WORK. ALL CUT AND FILL SLOPES SHALL BE SEEDED WITHIN 72 HOURS AFTER GRADING.
  - ALL STRIPPED TOPSOIL AND OTHER EARTH MATERIALS SHALL BE STOCKPILED OUTSIDE THE IMMEDIATE WORK AND WETLAND AREAS. A SILT BARRIER SHALL BE CONSTRUCTED AROUND THESE PILES IN A MANNER TO PROVIDE ACCESS AND AVOID SEDIMENT OUTSIDE OF THE WORK AREA.
  - CONSTRUCT TEMPORARY CULVERTS AND DIVERSIONS AS REQUIRED.
  - BEGIN PERMANENT AND TEMPORARY INSTALLATION OF SEED AND MULCH.
  - PERFORM EARTHWORK NECESSARY TO ESTABLISH ROUGH GRADING AROUND PROPOSED ROAD AND ACCESS DRIVES. MANAGE EXPOSED SOIL SURFACES TO AVOID TRANSPORTING SEDIMENTS INTO WETLANDS.
  - INSTALL SUBSURFACE UTILITIES (WATER, SEWER, GAS, ELECTRIC, COMMUNICATIONS, DRAINAGE, DRAINAGE FACILITIES, ETC.).
  - CONSTRUCT PROPOSED ROADWAY, RAIN GARDENS, BIORETENTION AREAS AND DRAINAGE SWALES. ALL DITCHES, SWALES SHALL BE FULLY STABILIZED PRIOR TO DIRECTING FLOW TO THEM.
  - COMPLETE BUILDINGS, BIORETENTION AREAS, AND LOAM AND SEED UNSTABLE AREAS.
  - COMPLETE SEEDING AND MULCHING. SEED TO BE APPLIED WITH BROADCAST SPREADER OR BY HYDRO-SEEDING, THEN ROLLED, RAKED OR DRAGGED TO ASSURE SEED/SOIL CONTACT.
  - REMOVE TEMPORARY EROSION CONTROL MEASURES AFTER SEEDED AREAS HAVE BECOME FIRMLY ESTABLISHED AND SITE IMPROVEMENTS ARE COMPLETE.
  - DURING THE COURSE OF THE WORK AND UPON COMPLETION, THE CONTRACTOR SHALL REMOVE ALL SEDIMENT DEPOSITS, EITHER ON OR OFF SITE, INCLUDING CATCH BASINS, AND SUMPS, DRAIN PIPES AND DITCHES, CURB LINES, ALONG SILT BARRIERS, ETC. RESULTING FROM SOIL AND/OR CONSTRUCTION OPERATIONS.
  - SEE WINTER CONSTRUCTION SEQUENCE FOR WORK CONDUCTED AFTER OCTOBER 15TH.

MAP 254 LOT 1  
 N/F  
 RICCI CONSTRUCTION CO INC  
 225 BANFIELD ROAD  
 PORTSMOUTH, NH 03801  
 RCRD BK.# 1743 PG.# 0192

MAP 266 LOT 1  
 N/F  
 RICCI CONSTRUCTION CO INC  
 225 BANFIELD ROAD  
 PORTSMOUTH, NH 03801  
 RCRD BK. # 2527 PG. # 0322




## SITE DEVELOPMENT PLANS

TAX MAP 256 LOT 2  
**SITE PREPARATION PLAN**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**

OWNED BY  
**WALTER D HETT TRUST**  
 PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**  
**1"=120' (11"X17")**  
**SCALE: 1"=60' (22"X34")** **SEPTEMBER 25, 2019**

REV	DATE	DESCRIPTION	DR	CK
4	3/20/2020	PROGRESS PRINT	RCK	JJM
3	3/4/2020	UPDATE PLANS PER REGULATORY COMMENTS	RCK	JJM
2	12/27/2019	IN HOUSE REVISIONS	RCK	JJM
1	12/23/19	NO REVISIONS THIS SHEET	RCK	JJM



Copyright 2019 © Thomas F. Moran, Inc.  
 48 Constitution Drive, Bedford, N.H. 03110

All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.

This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.



<b>TFM</b>	Civil Engineers	48 Constitution Drive
	Structural Engineers	Bedford, NH 03110
	Traffic Engineers	Phone (603) 472-4488
	Land Surveyors	Fax (603) 472-9747
	Landscape Architects	www.tfmoran.com
	Scientists	

Mar 23, 2020 - 4:41pm  
 F:\MISC Projects\47381 - Portsmouth\47381-00 - Green & Co - Banfield Road\Design\Production Drawings\SitePrep.dwg

MAP 256 LOT 3

N/F  
SHIRLEY N. GARRETT REV  
TRUST 2000  
BARBERRY LANE  
PORTSMOUTH, NH 03801  
RCRD BK. # 4298 PG. # 2633

**SITE DATA**

OWNER OF RECORD OF MAP 256 LOT 02: HETT MAUD REVOCABLE TRUST,  
334 HUDSON ROAD, STOW, MA 01775  
DEED REFERENCE TO PARCEL 15 BK 4553 PG 0432  
AREA OF PARCEL = 1,955,150± SF OR 44.88± ACRES

ZONED: SINGLE RESIDENCE A (SRA)  
EXISTING USE: N/A  
PROPOSED USE: SINGLE FAMILY CONDOMINIUM UNITS

THE PURPOSE OF THIS PLAN IS TO DEPICT A DEVELOPMENT OF 22 SINGLE FAMILY CONDOMINIUM UNITS WITH ASSOCIATED ROADWAY, UTILITIES, AND SITE IMPROVEMENTS.

DENSITY CALCULATIONS:  
TOTAL LOT AREA: 44.88 ACRES  
WETLAND AREA: 18.97 ACRES  
STEEP SLOPES OVER 15%: 2.20 ACRES  
TOTAL DEVELOPABLE AREA: 23.71 ACRES (REMAINING LAND IS WETLANDS AND STEEP SLOPES OVER 15%)  
MAXIMUM UNITS FOR DEVELOPMENT: 23 SINGLE FAMILY HOUSES  
PROPOSED UNITS FOR OPEN SPACE PLANNED UNIT DEVELOPMENT: 22 THREE (3) BEDROOM UNITS

PARKING CALCULATIONS:  
REQUIRED: 1.3 SPACES/UNIT PLUS ONE (1) VISITOR SPACE FOR EVERY 5 DWELLING UNITS.  
TOTAL REQUIRED = 33 SPACES

PROPOSED: 88 SPACES (2 GARAGED SPACES PER UNIT, PLUS 44 SPACES ON PRIVATE DRIVEWAYS)


EFFECTIVE IMPERVIOUS SURFACE CALCULATIONS:  
IMPERVIOUS AREA/TOTAL LOT AREA = 15,286.5 SF/1,955,150 SF = 0.0539  
TOTAL EFFECTIVE IMPERVIOUS SURFACE = 5.39%

**NOTES**

1. ALL DIMENSIONS ARE TO THE FACE OF CURB UNLESS NOTED OTHERWISE.
2. LIGHTING, SIGNAGE, LANDSCAPING, AND SCREENING SHALL MEET THE REQUIREMENTS OF THE CITY ZONING ORDINANCE AND SITE PLAN REGULATIONS.
3. ALL CONDITIONS ON THIS PLAN SHALL REMAIN IN EFFECT IN PERPETUITY PURSUANT TO THE REQUIREMENTS OF THE SITE PLAN REVIEW REGULATIONS.

**SIGN LEGEND**

ID	SIGN	SIZE (INCHES)		DESIGN (COLORING, TEXT SIZE, SPACING, SHAPE, RETROFLECTIVITY, ETC.)	NO. OF SIGNS
		WIDTH	HEIGHT		
R1-1		30	30	REFER TO THE 2009 MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD) FOR STREETS AND HIGHWAYS	1
R713		12	18	REFER TO THE 2009 MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD) FOR STREETS AND HIGHWAYS	17



MAP 256 LOT 1  
N/F  
SWIFT WATER GIRL SCOUT COUNCIL  
ONE COMMERCE DRIVE  
BEDFORD, NH 03110  
RCRD BK.#2167 PG.#147  
RCRD PLAN D-3206

MAP 266 LOT 5  
N/F  
HOPE FOR TOMORROW FOUNDATION  
1 STONERIDGE DRIVE  
RYE, NH 03870  
RCRD BK. # 5783 PG. # 602


MAP 266 LOT 3  
N/F  
ANDREW R. & CAROL ANN CROTEAU  
285 BANFIELD ROAD  
PORTSMOUTH, NH 03801  
RCRD BK. # 1843 PG. # 336

MAP 266 LOT 1  
N/F  
RICCI CONSTRUCTION CO INC  
225 BANFIELD ROAD  
PORTSMOUTH, NH 03801  
RCRD BK. # 2527 PG. # 0322

MAP 266 LOT 2  
N/F  
DENISE ARNOLD  
261 BANFIELD ROAD  
PORTSMOUTH, NH 03801  
RCRD BK. # 3644 PG. # 1763

MAP 266 LOT 1  
N/F  
RICCI CONSTRUCTION CO INC  
225 BANFIELD ROAD  
PORTSMOUTH, NH 03801  
RCRD BK. # 2527 PG. # 0322


MAP 254 LOT 1  
N/F  
RICCI CONSTRUCTION CO INC  
225 BANFIELD ROAD  
PORTSMOUTH, NH 03801  
RCRD BK.# 1743 PG.# 0192



**SITE DEVELOPMENT PLANS**

TAX MAP 256 LOT 2  
**OVERALL SITE LAYOUT PLAN**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**  
OWNED BY  
**WALTER D HETT TRUST**  
PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**  
**1"=160' (11"X17")**  
**SCALE: 1"=80' (22"X34")** **SEPTEMBER 25, 2019**

Copyright 2019 © Thomas F. Moran, Inc.  
48 Constitution Drive, Bedford, N.H. 03110  
All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.  
This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.





REV	DATE	DESCRIPTION	DR	CK
4	3/20/2020	PROGRESS PRINT	RCK	JJM
3	3/4/2020	UPDATE PLANS PER REGULATORY COMMENTS	RCK	JJM
2	12/27/2019	IN HOUSE REVISIONS	RCK	JJM
1	12/23/19	NO REVISIONS THIS SHEET	RCK	JJM

	Civil Engineers Structural Engineers Traffic Engineers Land Surveyors Landscape Architects Scientists	48 Constitution Drive Bedford, NH 03110 Phone (603) 472-4488 Fax (603) 472-9747 www.tfmoran.com
	47361.00	DR RCK FB CK JUM CADFILE
		C-04


Mar 23, 2020 - 4:41pm F:\MISC Projects\47361 - Portsmouth\47361-00 - Green & Co - Banfield Road\Design\Production Drawings\SiteLayout.dwg

Mar 23, 2020 - 4:41pm F:\MISC Projects\47361-00 - Banfield Road - Portsmouth\47361-00 - Green & Co - Banfield Road\Design\Production Drawings\SiteLayout.dwg



**SITE DEVELOPMENT PLANS**  
 TAX MAP 256 LOT 2  
**SITE LAYOUT PLAN**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**  
 OWNED BY  
**WALTER D HETT TRUST**  
 PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**  
**1"=60' (11"X17")**  
**SCALE: 1"=30' (22"X34")** **SEPTEMBER 25, 2019**

Copyright 2019 © Thomas F. Moran, Inc.  
 48 Constitution Drive, Bedford, N.H. 03110  
 All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.  
 This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.




REV	DATE	DESCRIPTION	DR	CK
4	3/20/2020	PROGRESS PRINT	RCK	JJM
3	3/4/2020	UPDATE PLANS PER REGULATORY COMMENTS	RCK	JJM
2	12/27/2019	IN HOUSE REVISIONS	RCK	JJM
1	12/23/19	NO REVISIONS THIS SHEET	RCK	JJM

<b>TFM</b>	Civil Engineers	48 Constitution Drive
	Structural Engineers	Bedford, NH 03110
	Traffic Engineers	Phone (603) 472-4488
	Land Surveyors	Fax (603) 472-9747
	Landscape Architects	www.tfmoran.com
	Scientists	

47361.00	DR RCK FB		
	CK JJM CADFILE	SITELAYOUT	C-07



Mar 23, 2020 - 4:41pm  
 F:\MISC Projects\47381 - Portsmouth\47381-00 - Green & Co - Banfield Road\Design\Production Drawings\SiteLayout.dwg



**SITE DEVELOPMENT PLANS**

TAX MAP 256 LOT 2  
**SITE LAYOUT PLAN**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**

OWNED BY  
**WALTER D HETT TRUST**  
 PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**  
**1"=60' (11"X17")**  
**SCALE: 1"=30' (22"X34")** **SEPTEMBER 25, 2019**



REV	DATE	DESCRIPTION	DR	CK
4	3/20/2020	PROGRESS PRINT	RCK	JJM
3	3/4/2020	UPDATE PLANS PER REGULATORY COMMENTS	RCK	JJM
2	12/27/2019	IN HOUSE REVISIONS	RCK	JJM
1	12/23/19	NO REVISIONS THIS SHEET	RCK	JJM

Copyright 2019 © Thomas F. Moran, Inc.  
 48 Constitution Drive, Bedford, N.H. 03110  
 All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.  
 This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.





Civil Engineers  
 Structural Engineers  
 Traffic Engineers  
 Land Surveyors  
 Landscape Architects  
 Scientists

48 Constitution Drive  
 Bedford, NH 03110  
 Phone (603) 472-4488  
 Fax (603) 472-9747  
 www.tfmoran.com

47361.00	DR	RCK	FB	-	C-06
	CK	JJM	CADFILE	SITELAYOUT	





Mar 23, 2020 - 4:41pm  
F:\MSC Projects\47381 - Portsmouth\47381-00 - Green & Co - Banfield Road\Design\Production Drawings\Sitelayout.dwg



**SITE DEVELOPMENT PLANS**

TAX MAP 256 LOT 2  
**SITE LAYOUT PLAN**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**  
 OWNED BY  
**WALTER D HETT TRUST**  
 PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**  
**1"=60' (11"X17")**  
**SCALE: 1"=30' (22"X34")** **SEPTEMBER 25, 2019**



REV	DATE	DESCRIPTION	DR	CK
4	3/20/2020	PROGRESS PRINT	RCK	JJM
3	3/4/2020	UPDATE PLANS PER REGULATORY COMMENTS	RCK	JJM
2	12/27/2019	IN HOUSE REVISIONS	RCK	JJM
1	12/23/19	NO REVISIONS THIS SHEET	RCK	JJM

Copyright 2019 © Thomas F. Moran, Inc.  
 48 Constitution Drive, Bedford, N.H. 03110  
 All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.  
 This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.



	Civil Engineers Structural Engineers Traffic Engineers Land Surveyors Landscape Architects Scientists			48 Constitution Drive Bedford, NH 03110 Phone (603) 472-4488 Fax (603) 472-9747 www.tfmoran.com	
	47361.00	DR CK	RCK JUM	FB CADFILE	SITELAYOUT

**BEST MANAGEMENT PRACTICES FOR BLASTING**

1. PURPOSE. THE PURPOSE OF THIS PART IS TO ESTABLISH BEST MANAGEMENT PRACTICES FOR BLASTING TO MINIMIZE THE POTENTIAL FOR GROUNDWATER CONTAMINATION, TO ENSURE THAT THE GROUNDWATER CAN BE USED FOR EXISTING AND FUTURE DRINKING WATER SUPPLY SOURCES. (SEE RN3 AT P. V) #12342, EFF 8-15-17
2. LOADING PRACTICES. THE FOLLOWING BLAST HOLE LOADING PRACTICES SHALL BE IMPLEMENTED:
  - A. THE DRILLER SHALL MAINTAIN DRILLING LOGS TO DOCUMENT:
    - I. THE DEPTHS AND LENGTHS OF VOIDS, CAVITIES, AND FAULT ZONES OR OTHER WEAK ZONES ENCOUNTERED; AND
    - II. GROUNDWATER CONDITIONS;
  - B. THE DRILLER SHALL COMMUNICATE THE CONTENTS OF THE DRILLING LOGS DIRECTLY TO THE BLASTER;
  - C. EXPLOSIVE PRODUCTS SHALL BE MANAGED ON SITE SUCH THAT THEY ARE:
    - I. USED IN THE BOREHOLE;
    - II. RETURNED TO THE DELIVERY VEHICLE; OR
    - III. PLACED IN SECURE CONTAINERS FOR OFF-SITE DISPOSAL;
  - D. SPILLAGE AROUND THE BOREHOLE SHALL BE:
    - I. PLACED IN THE BOREHOLE; OR
    - II. CLEANED UP AND RETURNED TO AN APPROPRIATE VEHICLE FOR HANDLING OR PLACEMENT IN SECURED CONTAINERS FOR OFF-SITE DISPOSAL;
  - E. LOADED EXPLOSIVES SHALL BE DETONATED AS SOON AS POSSIBLE AND NOT LEFT IN THE BLAST HOLES OVERNIGHT, UNLESS WEATHER OR OTHER SAFETY CONCERNS REASONABLY DICTATE THAT DETONATION SHOULD BE POSTPONED;
  - F. LOADING EQUIPMENT SHALL BE CLEANED IN AN AREA WHERE WASTEWATER CAN BE PROPERLY CONTAINED AND HANDLED IN A MANNER THAT PREVENTS RELEASE OF CONTAMINANTS TO THE ENVIRONMENT; AND
  - G. EXPLOSIVES SHALL BE LOADED IN ACCORDANCE WITH INDUSTRY STANDARD PRACTICES FOR PRIMING, STEMMING, DECKING AND COLUMN RISE TO MAINTAIN GOOD CONTINUITY IN THE COLUMN LOAD TO PROMOTE COMPLETE DETONATION. SOURCE. (SEE RN3 AT P. V) #12342, EFF 8-15-17
3. EXPLOSIVE SELECTION. EXPLOSIVE PRODUCTS SHALL BE SELECTED THAT ARE:
  - A. APPROPRIATE FOR SITE CONDITIONS AND SAFE BLAST EXECUTION; AND
  - B. HAVE THE APPROPRIATE WATER RESISTANCE FOR THE SITE CONDITIONS PRESENT.
4. PREVENTION OF MISFIRES. INDUSTRY-STANDARD PRACTICES SHALL BE IMPLEMENTED TO PREVENT MISFIRES.
5. MUCK AND ROCK MANAGEMENT.
  - A. FOR PURPOSES OF THIS PART, THE FOLLOWING DEFINITIONS APPLY:
    - I. "BLASTED MATERIAL" MEANS ALL OF THE EARTH MATERIAL LOOSENED AS A RESULT OF THE BLASTING;
    - II. "MUCK" MEANS THE BLASTED MATERIAL REMAINING AFTER THE ROCKS HAVE BEEN REMOVED; AND
    - III. "ROCKS" MEANS THE LARGER PIECES OF BLASTED MATERIAL THAT ARE SEPARATED FROM THE MUCK FOR USE ELSEWHERE, INCLUDING FOR FEEDSTOCK OF A ROCK CRUSHING OPERATION.
  - B. MUCK SHALL BE REMOVED FROM THE BLAST AREA AS SOON AS REASONABLY POSSIBLE.
  - C. ROCKS SHALL BE MANAGED SO AS TO PREVENT WATER SUPPLY WELLS OR SURFACE WATERS FROM BEING CONTAMINATED BY RUNOFF.
6. SPILL PREVENTION MEASURES AND SPILL MITIGATION.
  - A. FUEL AND OTHER REGULATED SUBSTANCES SHALL BE MANAGED AS REQUIRED BY ENV-WQ 401.04.
  - B. PERSONNEL WORKING AT THE BLAST SITE SHALL BE TRAINED IN HOW TO RESPOND TO A SPILL OF THE REGULATED SUBSTANCES BEING USED AT THE SITE.
7. FUELING AND MAINTENANCE OF CONSTRUCTION EQUIPMENT.
  - A. IF ANY CONSTRUCTION EQUIPMENT, INCLUDING BUT NOT LIMITED TO EARTHMOVING, EXCAVATION, AND BORING EQUIPMENT, WILL BE FUELED FROM A TANK TRUCK OR OTHER CONTAINER THAT IS MOVED AROUND THE SITE, THE FOLLOWING SHALL APPLY:
    - I. PORTABLE CONTAINMENT EQUIPMENT THAT IS SIZED TO CONTAIN THE MOST LIKELY VOLUME OF FUEL TO BE SPILLED DURING A FUEL TRANSFER SHALL BE USED, WHERE THE MOST LIKELY VOLUME TO BE SPILLED IS DETERMINED BASED ON THE FUEL TRANSFER RATE, THE AMOUNT OF FUEL BEING TRANSFERRED, THE DISTANCE BETWEEN THE HOSE NOZZLE AND PUMP SHUT OFF SWITCH, AND THE RESPONSE TIME OF PERSONNEL AND EQUIPMENT AVAILABLE AT THE FACILITY;
    - II. THE CONTAINMENT EQUIPMENT SHALL BE POSITIONED TO CATCH ANY FUEL SPILLS DUE TO OVERFILLING THE EQUIPMENT AND ANY OTHER SPILLS THAT MIGHT OCCUR AT OR NEAR THE FUEL FILLER PORT TO THAT EQUIPMENT;
    - III. THE TYPE OF CONTAINMENT EQUIPMENT USED AND ITS POSITIONING AND USE SHALL ACCOUNT FOR ALL OF THE DRIP POINTS ASSOCIATED WITH THE FUEL FILLING PORT AND THE HOSE FROM THE FUEL DELIVERY TRUCK; AND
    - IV. PERSONNEL SHALL NOT LEAVE THE IMMEDIATE AREA WHILE FUEL IS BEING TRANSFERRED, TO ENSURE THAT ANY SPILLS WILL BE OF LIMITED VOLUME.
  - B. IF THE SITE WILL HAVE A FIXED LOCATION FOR FUELING CONSTRUCTION EQUIPMENT, THE FOLLOWING SHALL APPLY:
    - I. ALL FUEL CONTAINERS, INCLUDING BUT NOT LIMITED TO SKID-MOUNTED TANKS, DRUMS, AND FIVE GALLON CANS, SHALL HAVE SECONDARY CONTAINMENT THAT:
      1. IS CAPABLE OF CONTAINING 110% OF THE VOLUME OF THE LARGEST FUEL STORAGE CONTAINER; AND
      2. HAS AN IMPERVIOUS FLOOR;
    - II. SECONDARY CONTAINMENT FOR TANKS MAY COMPRISE A METAL, PLASTIC, POLYMER OR PRECAST CONCRETE VAULT PROVIDING 110 PERCENT OF THE VOLUME OF THE LARGEST FUEL STORAGE CONTAINER;
    - III. FOR FUEL CONTAINERS, SECONDARY CONTAINMENT MAY COMPRISE CONTAINMENT PALLETS;
    - IV. THE AREA WHERE FUEL IS TRANSFERRED SHALL BE A FLAT, IMPERVIOUS AREA THAT:
      1. IS ADJACENT TO THE FUEL CONTAINER(S); AND
      2. EXTENDS BEYOND THE FULL REACH, OR LENGTH, OF THE FUEL HOSE; AND
    - V. SECONDARY CONTAINMENT AREAS MAY BE IN THE FORM OF A BASIN THAT IS:
      1. SLOPED DOWN TO A CENTRAL LOW POINT OR BERMED ALONG THE PERIMETER;
      2. LINED WITH A CONTINUOUS SHEET OF 20 MIL OR THICKER POLYMER MATERIAL OR APPROPRIATE GEOMEMBRANE LINER; AND
      3. BACKFILLED WITH AT LEAST 6 INCHES OF SAND.




**SITE DEVELOPMENT PLANS**


TAX MAP 256 LOT 2  
**OVERALL GRADING & DRAINAGE PLAN**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**

OWNED BY  
**WALTER D HETT TRUST**  
 PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**

**1"=160' (11"X17")**  
**SCALE: 1"=80' (22"X34')** **SEPTEMBER 25, 2019**



REV	DATE	DESCRIPTION	DR	CK
4	3/20/2020	PROGRESS PRINT	RCK	JJM
3	3/4/2020	UPDATE PLANS PER REGULATORY COMMENTS	RCK	JJM
2	12/27/2019	IN HOUSE REVISIONS	RCK	JJM
1	12/23/19	REVISED PER REGULATORY COMMENTS	RCK	JJM




Copyright 2019 © Thomas F. Moran, Inc.  
 48 Constitution Drive, Bedford, N.H. 03110  
 All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.  
 This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.



	Civil Engineers	48 Constitution Drive
	Structural Engineers	Bedford, NH 03110
	Traffic Engineers	Phone (603) 472-4488
	Land Surveyors	Fax (603) 472-9747
	Landscape Architects	www.tfmoran.com
	Scientists	

Mar 23, 2020 - 4:42pm  
 F:\MISC Projects\47361 - Portsmouth - Portsmouth\47361-00 - Green & Co - Banfield Road\Design\Production Drawings\Grading\Drainage.dwg

Mar 23, 2020 - 4:42pm F:\MISC Projects\47361 - Green & Co - Banfield Road\Design\Production Drawings\Grading\Drainage.dwg




**SITE DEVELOPMENT PLANS**


TAX MAP 256 LOT 2  
**GRADING & DRAINAGE PLAN**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**

OWNED BY  
**WALTER D HETT TRUST**  
 PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**

**1"=60' (11'X17')**  
**SCALE: 1"=30' (22'X34')** **SEPTEMBER 25, 2019**






Copyright 2019 © Thomas F. Moran, Inc.  
 48 Constitution Drive, Bedford, N.H. 03110  
 All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.  
 This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.



REV	DATE	DESCRIPTION	DR	CK
4	3/20/2020	PROGRESS PRINT	RCK	JJM
3	3/4/2020	UPDATE PLANS PER REGULATORY COMMENTS	RCK	JJM
2	12/27/2019	IN HOUSE REVISIONS	RCK	JJM
1	12/23/19	REVISED PER REGULATORY COMMENTS	RCK	JJM


	Civil Engineers Structural Engineers Traffic Engineers Land Surveyors Landscape Architects Scientists	48 Constitution Drive Bedford, NH 03110 Phone (603) 472-4488 Fax (603) 472-9747 www.tfmoran.com
	FILE NO. 47361.00 DR RCK FB CK JUM CADFILE	GRADING/DRAINAGE

Mar 23, 2020 - 4:42pm  
F:\MISC Projects\47361 - Portsmouth\47361-00 - Green & Co - Banfield Road\Design\Production Drawings\Grading\Drainage.dwg



**SITE DEVELOPMENT PLANS**  
 TAX MAP 256 LOT 2  
**GRADING & DRAINAGE PLAN**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**  
 OWNED BY  
**WALTER D HETT TRUST**  
 PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**  
**1"=60' (11'X17')**  
**SCALE: 1"=30' (22'X34')** **SEPTEMBER 25, 2019**

Copyright 2019 © Thomas F. Moran, Inc.  
 48 Constitution Drive, Bedford, N.H. 03110  
 All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.  
 This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.



REV	DATE	DESCRIPTION	DR	CK
4	3/20/2020	PROGRESS PRINT	RCK	JJM
3	3/4/2020	UPDATE PLANS PER REGULATORY COMMENTS	RCK	JJM
2	12/27/2019	IN HOUSE REVISIONS	RCK	JJM
1	12/23/19	REVISED PER REGULATORY COMMENTS	RCK	JJM


<b>TFM</b>	Civil Engineers Structural Engineers Traffic Engineers Land Surveyors Landscape Architects Scientists		48 Constitution Drive Bedford, NH 03110 Phone (603) 472-4488 Fax (603) 472-9747 www.tfmoran.com
	47361.00	DR RCK FB CK JJM CADFILE	C-10

Mar 23, 2020 - 4:42pm  
F:\MISC Projects\47361 - Portsmouth\47361-00 - Green & Co - Banfield Road\Design\Production Drawings\Grading\Drainage.dwg



**SITE DEVELOPMENT PLANS**  
 TAX MAP 256 LOT 2  
**GRADING & DRAINAGE PLAN**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**  
 OWNED BY  
**WALTER D HETT TRUST**  
 PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**  
**1"=60' (11'X17')**  
**SCALE: 1"=30' (22'X34')** **SEPTEMBER 25, 2019**

Copyright 2019 © Thomas F. Moran, Inc.  
 48 Constitution Drive, Bedford, N.H. 03110  
 All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.  
 This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.




REV	DATE	DESCRIPTION	DR	CK
4	3/20/2020	PROGRESS PRINT	RCK	JJM
3	3/4/2020	UPDATE PLANS PER REGULATORY COMMENTS	RCK	JJM
2	12/27/2019	IN HOUSE REVISIONS	RCK	JJM
1	12/23/19	REVISED PER REGULATORY COMMENTS	RCK	JJM

<b>TFM</b>	Civil Engineers Structural Engineers Traffic Engineers Land Surveyors Landscape Architects Scientists			48 Constitution Drive Bedford, NH 03110 Phone (603) 472-4488 Fax (603) 472-9747 www.tfmoran.com
	47361.00	DR RCK FB CK JUM CADFILE	GRADING/DRAINAGE	

**NOTES**

1. ALL CONDOMINIUM UNITS SHALL HAVE FIRE SUPPRESSION SPRINKLERS SYSTEMS INSTALLED.
2. SEE UTILITY NOTES ON NOTES AND LEGEND SHEET (C-02)

UTILITY COLOR LEGEND	
WATER	
SEPTIC	
ELECTRIC & COMMUNICATIONS	
GAS	



**SITE DEVELOPMENT PLANS**

TAX MAP 256 LOT 2  
**OVERALL UTILITY PLAN**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**

OWNED BY  
**WALTER D HETT TRUST**



PREPARED FOR

**GREEN & COMPANY REAL ESTATE**

1"=160' (11"X17")

SCALE: 1"=80' (22"X34")

SEPTEMBER 25, 2019



REV	DATE	DESCRIPTION	DR	CK
4	3/20/2020	PROGRESS PRINT	RCK	JJM
3	3/4/2020	UPDATE PLANS PER REGULATORY COMMENTS	RCK	JJM
2	12/27/2019	IN HOUSE REVISIONS	RCK	JJM
1	12/23/19	NO REVISIONS THIS SHEET	RCK	JJM

	Civil Engineers	48 Constitution Drive
	Structural Engineers	Bedford, NH 03110
	Traffic Engineers	Phone (603) 472-4488
	Land Surveyors	Fax (603) 472-9747
	Landscape Architects	www.tfmoran.com
	Scientists	



Copyright 2019 © Thomas F. Moran, Inc.  
 48 Constitution Drive, Bedford, N.H. 03110  
 All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.  
 This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.





Mar 23, 2020 - 4:43pm  
 F:\MISC Projects\47361 - Portsmouth\47361-00 - Green & Co - Banfield Road\Design\Production Drawings\Utility.dwg

Mar 23, 2020 - 4:43pm  
F:\MISC Projects\47361 - Portsmouth\47361-00 - Green & Co - Banfield Road\Design\Production Drawings\Utility.dwg

Copyright 2019 © Thomas F. Moran, Inc.  
48 Constitution Drive, Bedford, N.H. 03110  
All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.  
This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.



**SITE DEVELOPMENT PLANS**  
TAX MAP 256 LOT 2  
**UTILITY PLAN**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**  
OWNED BY  
**WALTER D HETT TRUST**  
PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**  
**1"=60' (11"X17")**  
**SCALE: 1"=30' (22"X34")**      **SEPTEMBER 25, 2019**






REV	DATE	DESCRIPTION	DR	CK
4	3/20/2020	PROGRESS PRINT	RCK	JJM
3	3/4/2020	UPDATE PLANS PER REGULATORY COMMENTS	RCK	JJM
2	12/27/2019	IN HOUSE REVISIONS	RCK	JJM
1	12/23/19	NO REVISIONS THIS SHEET	RCK	JJM

<b>TFM</b>	Civil Engineers	48 Constitution Drive
	Structural Engineers	Bedford, NH 03110
	Traffic Engineers	Phone (603) 472-4488
	Land Surveyors	Fax (603) 472-9747
	Landscape Architects	www.tfmoran.com
	Scientists	

47361.00	DR RCK	FB	-
	CK JJM	CADFILE	UTILITY


C-15

Mar 23, 2020 - 4:43pm  
F:\MISC Projects\47381 - Banfield Road - Portsmouth\47381-00 - Green & Co - Banfield Road\Design\Production Drawings\Utility.dwg



**SITE DEVELOPMENT PLANS**  
 TAX MAP 256 LOT 2  
**UTILITY PLAN**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**  
 OWNED BY  
**WALTER D HETT TRUST**  
 PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**  
**1"=60' (11"X17")**  
**SCALE: 1"=30' (22'X34")** **SEPTEMBER 25, 2019**

Copyright 2019 © Thomas F. Moran, Inc.  
 48 Constitution Drive, Bedford, N.H. 03110  
 All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.  
 This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.





REV	DATE	DESCRIPTION	DR	CK
4	3/20/2020	PROGRESS PRINT	RCK	JJM
3	3/4/2020	UPDATE PLANS PER REGULATORY COMMENTS	RCK	JJM
2	12/27/2019	IN HOUSE REVISIONS	RCK	JJM
1	12/23/19	NO REVISIONS THIS SHEET	RCK	JJM

<b>TFM</b>	Civil Engineers	48 Constitution Drive
	Structural Engineers	Bedford, NH 03110
	Traffic Engineers	Phone (603) 472-4488
	Land Surveyors	Fax (603) 472-9747
	Landscape Architects	www.tfmoran.com
	Scientists	



47361.00	DR RCK	FB	-						
	CK	JJM	CADFILE	UTILITY					C-14



Mar 23, 2020 - 4:43pm F:\MISC Projects\47381 - Banfield Road - Portsmouth\47381-00 - Green & Co - Banfield Road\Design\Production Drawings\Utility.dwg




**SITE DEVELOPMENT PLANS**  
TAX MAP 256 LOT 2  
**UTILITY PLAN**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**  
OWNED BY  
**WALTER D HETT TRUST**  
PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**  
**1"=60' (11"X17")**  
**SCALE: 1"=30' (22"X34")** **SEPTEMBER 25, 2019**



REV	DATE	DESCRIPTION	DR	CK
4	3/20/2020	PROGRESS PRINT	RCK	JJM
3	3/4/2020	UPDATE PLANS PER REGULATORY COMMENTS	RCK	JJM
2	12/27/2019	IN HOUSE REVISIONS	RCK	JJM
1	12/23/19	NO REVISIONS THIS SHEET	RCK	JJM


Copyright 2019 © Thomas F. Moran, Inc.  
48 Constitution Drive, Bedford, N.H. 03110  
All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.  
This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.



Civil Engineers  
Structural Engineers  
Traffic Engineers  
Land Surveyors  
Landscape Architects  
Scientists

48 Constitution Drive  
Bedford, NH 03110  
Phone (603) 472-4488  
Fax (603) 472-9747  
www.tfmoran.com

47361.00	DR	RCK	FB	-	UTILITY	C-13
	CK	JJM	CADFILE			



**LANDSCAPE NOTES**

1. CONTRACTOR WILL LOCATE, VERIFY AND MARK ALL EXISTING AND NEWLY INSTALLED UNDERGROUND UTILITIES PRIOR TO ANY LAWNWORK OR PLANTING. ANY CONFLICTS WHICH MIGHT OCCUR BETWEEN PLANTING AND UTILITIES WILL IMMEDIATELY BE REPORTED TO THE LANDSCAPE ARCHITECT OR OWNERS' REPRESENTATIVE, SO THAT ALTERNATE PLANTING LOCATIONS CAN BE DETERMINED.
2. CONTRACTOR WILL FURNISH AND PLANT ALL PLANTS IN QUANTITIES AS SHOWN ON THIS PLAN. IN CASES OF DISCREPANCY BETWEEN PLAN AND LIST CLARIFY WITH LANDSCAPE ARCHITECT PRIOR TO PLACING PURCHASE ORDER AND AGAIN PRIOR TO PLANTING.
3. SEE PLANTING DETAILS AND IF INCLUDED, SPECIFICATIONS FOR ADDITIONAL INFORMATION.
4. NO SUBSTITUTION OF PLANT MATERIALS WILL BE ALLOWED WITHOUT PRIOR WRITTEN APPROVAL OF THE LANDSCAPE ARCHITECT OR OWNER'S REPRESENTATIVE.
5. IT IS THE CONTRACTOR'S RESPONSIBILITY TO MAKE THE APPROPRIATE ARRANGEMENTS TO PROVIDE ALL PLANTS AND MATERIALS TO ACCOMMODATE PLANTING WITHIN THE TIME ALLOWED BY THE CONSTRUCTION SCHEDULE.
6. PLANTING SHALL BE COMPLETED FROM APRIL 15TH THROUGH OCTOBER 15TH UNLESS OTHERWISE NOTED IN SPECIFICATIONS. THERE WILL BE NO PLANTING DURING JULY AND AUGUST UNLESS SPECIAL PROVISIONS ARE MADE FOR DROUGHT BY PROVIDING ADDITIONAL WATERING.
7. ALL PLANTS WILL BE NURSERY GROWN.
8. PLANTS WILL BE IN ACCORDANCE, AT A MINIMUM, WITH CURRENT EDITION OF "AMERICAN STANDARDS FOR NURSERY STOCK" AS PUBLISHED BY THE AMERICAN HORTICULTURE INDUSTRY ASSOCIATION.
9. TREES WILL BE PRUNED IN ACCORDANCE WITH THE LATEST EDITION OF ANSI A300 PART 1, "TREE, SHRUB AND OTHER WOODY PLANT MAINTENANCE STANDARD PRACTICES".
10. PLANTS MATERIAL IS SUBJECT TO APPROVAL / REJECTION BY THE LANDSCAPE ARCHITECT AT THE SITE AND AT THE NURSERY.
11. ALL PLANTS WILL BE MOVED WITH ROOT SYSTEMS AS SOLID UNITS AND WITH BALLS OF EARTH FIRMLY WRAPPED WITH BURLAP. NO PLANT WILL BE ACCEPTED WHEN BALL OF EARTH SURROUNDING ITS ROOTS HAS BEEN BADLY CRACKED OR BROKEN BEFORE PLANTING. ALL PLANTS THAT CANNOT BE PLANTED AT ONCE WILL BE HELED-IN BY SETTING IN THE GROUND AND COVERING THE BALLS WITH SOIL AND THEN WATERING. DURING TRANSPORT, ALL PLANT MATERIALS WILL BE WRAPPED WITH WIND PROOF COVERING.
12. NEWLY PLANTED MATERIAL WILL BEAR THE SAME RELATIONSHIP TO FINISHED GRADE AS TO THE ORIGINAL GRADE OF THE PLANT PRIOR TO DIGGING.
13. PROPOSED TREES OVERHANGING SIDEWALKS, ROADS OR PARKING WILL BEGIN BRANCHING NATURALLY (NOT PRUNED) AT 6' HEIGHT.
14. MULCH FOR PLANTED AREAS (NOT INCLUDING RAIN GARDENS) WILL BE AGED SHREDDED PINE BARK, PARTIALLY DECOMPOSED, DARK BROWN IN COLOR AND FREE OF WOOD CHIPS UNLESS OTHERWISE SHOWN.
15. PLANT MATERIAL WILL BE LOCATED OUTSIDE BUILDING DRIPLINES AND ROOF VALLEY POINTS OF CONCENTRATION TO PREVENT DAMAGE TO PLANTS. CLARIFY DISCREPANCIES WITH LANDSCAPE ARCHITECT PRIOR TO INSTALLATION.
16. ALL DISTURBED AREAS NOT TO BE PAVED OR OTHERWISE TREATED, WILL RECEIVE SIX (6) INCH LOAM AND SEED AT THE DIRECTION OF THE LANDSCAPE ARCHITECT OR OWNER'S REPRESENTATIVE.
17. TREE STAKES AND WRAP WILL REMAIN IN PLACE FOR NO LESS THAN 6 MONTHS AND NO MORE THAN 1 YEAR. CONTRACTOR WILL REMOVE.
18. ALL PLANT GROUPINGS WILL BE IN MULCH BEDS UNLESS OTHERWISE SPECIFIED OR NOTED ON PLANS. WHERE MULCHED PLANT BED ADJUTS LAWN, PROVIDE TURF CUT EDGE.
19. ALL PLANT BEDS WILL INTERSECT WITH PAVEMENT AT 90 DEGREES UNLESS OTHERWISE NOTED ON PLANS.

**LANDSCAPE GUARANTEE AND MAINTENANCE NOTES**

1. CONTRACTOR WILL BE RESPONSIBLE FOR ALL MEANS, METHODS AND TECHNIQUES OF WATERING.
2. CONTRACTOR WILL BEGIN WATERING IMMEDIATELY AFTER PLANTING. ALL PLANTS WILL BE THOROUGHLY WATERED TWICE DURING THE FIRST 24 HOUR PERIOD AFTER PLANTING. ALL PLANTS WILL BE WATERED WEEKLY, OR MORE OFTEN, IF NECESSARY DURING THE FIRST GROWING SEASON BUT NOT LESS THAN ONE YEAR.
3. WATER ALL LAWNS AS REQUIRED. DO NOT LET NEWLY PLANTED LAWNS DRY OUT DURING THE FIRST FOUR WEEKS MINIMUM.
4. ALL NEW LAWNS WILL BE MAINTAINED AND MOWED A MINIMUM THREE (3) TIMES BEFORE REQUESTING REVIEW BY LANDSCAPE ARCHITECT OR OWNER'S REPRESENTATIVE FOR ACCEPTANCE. MAINTENANCE AND MOWING WILL CONTINUE UNTIL ACCEPTED BY LANDSCAPE ARCHITECT OR OWNER'S REPRESENTATIVE IS ISSUED IN WRITING.
5. THE CONTRACTOR WILL MAINTAIN AND GUARANTEE ALL PLANTINGS TO BE IN GOOD HEALTHY, FLOURISHING AND ACCEPTABLE CONDITION FOR A PERIOD OF ONE (1) YEAR BEGINNING AT THE DATE OF ACCEPTANCE BY THE LANDSCAPE ARCHITECT OR OWNER'S REPRESENTATIVE. ALL GRASSES, TREES AND SHRUBS THAT, IN THE OPINION OF THE LANDSCAPE ARCHITECT OR OWNER'S REPRESENTATIVE SHOWING LESS THAN 80% HEALTHY GROWTH AT THE END OF ONE (1) YEAR PERIOD WILL BE IMMEDIATELY REPLACED BY THE CONTRACTOR.
6. DECIDUOUS PLANT MATERIAL INSTALLED AFTER SEPTEMBER 30 AND BEFORE APRIL 15 WILL NOT BE REVIEWED THAT SEASON FOR ACCEPTANCE DUE TO STAGE OF LEAF PHYSIOLOGY. THIS PLANT MATERIAL WILL NOT BE REVIEWED UNTIL FOLLOWING GROWING SEASON. GUARANTEE PERIOD WILL BEGIN ONLY AFTER ACCEPTANCE BY LANDSCAPE ARCHITECT OR OWNER'S REPRESENTATIVE.
7. EVERGREEN PLANT MATERIAL INSTALLED AFTER OCTOBER 30 AND BEFORE APRIL 15 WILL NOT BE REVIEWED THAT SEASON FOR ACCEPTANCE DUE TO END OF GROWTH SEASON. THIS PLANT MATERIAL WILL NOT BE REVIEWED UNTIL FOLLOWING GROWING SEASON. GUARANTEE PERIOD WILL BEGIN ONLY AFTER ACCEPTANCE BY LANDSCAPE ARCHITECT OR OWNER'S REPRESENTATIVE.

**HYDROSEEDING NOTES**

1. HYDROSEEDING MAY BE USED AS AN ALTERNATE METHOD OF SEEDING. THE APPLICATION OF LIMESTONE AS NECESSARY, FERTILIZER AND GRASS SEED MAY BE ACCOMPLISHED IN ONE OPERATION BY THE USE OF A SPRAYING MACHINE APPROVED BY THE LANDSCAPE ARCHITECT OR CIVIL ENGINEER. THE MATERIALS SHALL BE MIXED WITH WATER IN THE MACHINE AND SHALL CONFORM TO RELATIVE REQUIREMENTS OF SECTION 644 OF NH. STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION.
2. (FOR MASSACHUSETTS PROJECTS PLUG IN - SECTION 765.65 OF MASS. DPW CURRENT STANDARD SPECIFICATIONS FOR HIGHWAYS AND BRIDGES).

**INVASIVE PLANT NOTES**

1. EXISTING NON-NATIVE, INVASIVE PLANT SPECIES WILL BE IDENTIFIED, REMOVED, DESTROYED AND LEGALLY DISPOSED OF OFF-SITE IN ACCORDANCE WITH THE LATEST UNIVERSITY OF NEW HAMPSHIRE COOPERATIVE EXTENSION METHODS OF DISPOSING NON-NATIVE INVASIVE PLANTS. SEE "MANAGE AND CONTROL INVASIVES" AND PROPERLY DISPOSE OF INVASIVE PLANTS".

**PRICING & CONSTRUCTION DOCUMENT NOTES**

1. CONTRACTOR WILL PRICE PLANT MATERIAL IN QUANTITIES SUFFICIENT TO COMPLETE PLANTINGS GRAPHICALLY SHOWN ON THESE DRAWINGS OR IN PLANT LIST, WHICHEVER IS GREATER. IN CASES OF DISCREPANCY BETWEEN PLAN AND LIST CLARIFY WITH LANDSCAPE ARCHITECT PRIOR TO PLACING PURCHASE ORDER AND AGAIN PRIOR TO PLANTING.
2. CONTRACTOR WILL VERIFY PRIOR TO PRICING IF SITE SOILS ARE VERY POORLY DRAINING OR IF LEDGE IS PRESENT. IF CONTRACTOR ENCOUNTERS VERY POORLY DRAINING SOILS (BATH TUB EFFECT) OR LEDGE THAT IMPACTS PROPOSED PLANTING PLAN, NOTIFY LANDSCAPE ARCHITECT OR OWNERS' REPRESENTATIVE FOR DIRECTION PRIOR TO PRICING AND AGAIN PRIOR TO PERFORMING ANY WORK.
3. CONTRACTOR WILL STAKE OR PLACE ON GROUND ALL PROPOSED PLANT MATERIALS PER PLAN. CONTACT LANDSCAPE ARCHITECT FOR REVIEW AND APPROVAL PRIOR TO INSTALLATION.
4. COORDINATE WITH LANDSCAPE ARCHITECT'S CONTRACTED NUMBER OF SITE VISITS WHEN PLANNING FOR INSPECTION. NOTIFY LANDSCAPE ARCHITECT 72 HOURS MINIMUM IN ADVANCE OF REQUESTED SITE VISIT.
5. CONTRACTOR WILL DEVELOP A WRITTEN WATERING SCHEDULE AND WILL SUBMIT WATERING SCHEDULE TO OWNERS' REPRESENTATIVE. CONTRACTOR WILL WATER ALL NEW PLANTS INCLUDING LAWNS THAT ARE NOT "IRRIGATED" VIA A PERMANENT IRRIGATION SYSTEM FOR THE FIRST 12 MONTHS.

**PORTSMOUTH NOTES**

1. THE PROPERTY OWNER AND ALL FUTURE PROPERTY OWNER'S WILL BE RESPONSIBLE FOR THE MAINTENANCE AND OF ALL REQUIRED SCREENING AND LANDSCAPE MATERIALS INDICATED ON THESE PLANS.
- 2.
3. ALL REQUIRED PLANT MATERIAL WILL BE TENDED TO AND KEPT FREE OF REFUSE AND DEBRIS.
4. ALL REQUIRED FENCES AND WALLS WILL BE MAINTAINED IN GOOD REPAIR.
5. THE PROPERTY OWNER WILL BE RESPONSIBLE TO REMOVE AND REPLACE DEAD OR DISEASED PLANT MATERIALS IMMEDIATELY WITH THE SAME TYPE, SIZE AND QUANTITY OF PLANT MATERIALS AS ORIGINALLY INSTALLED. UNLESS ALTERNATIVE PLANTINGS ARE REQUESTED, JUSTIFIED AND APPROVED BY THE PLANNING BOARD OR PLANNING DIRECTOR.
6. ALL IMPROVEMENTS SHOWN ON THIS PLAN WILL BE CONSTRUCTED AND MAINTAINED IN ACCORDANCE WITH THIS PLAN BY THE PROPERTY OWNER AND ALL FUTURE PROPERTY OWNERS. NO CHANGES WILL BE MADE TO THIS PLAN WITHOUT THE WRITTEN APPROVAL OF THE PORTSMOUTH PLANNING BOARD OR PLANNING DIRECTOR.
7. THE LANDSCAPE PLAN WILL BE RECORDED IN THE ROCKINGHAM COUNTY REGISTRY OF DEEDS.


**SEEDING NOTES**

1. SLOPES UP TO AND INCLUDING 3:1 GRADE, SEED WILL BE NEW ENGLAND EROSION CONTROL & RESTORATION MIX PER NEW ENGLAND WETLANDS PLANTS INC., AMHERST, MA.
2. SLOPES STEEPER THAN 3:1 GRADE, SEED WILL BE NEW ENGLAND EROSION CONTROL & RESTORATION MIX PER NEW ENGLAND WETLANDS PLANTS INC., AMHERST, MA. SEE CIVIL FOR ADDITIONAL EROSION CONTROL MEASURES.
3. GENERAL SEED WILL BE NHDOT SPECIFICATION SECTION 644, TABLE 644-1-PARK SEED TYPE 15, INCLUDING NOTES TO TABLE 1, 2 & 3.



**SITE DEVELOPMENT PLANS**

TAX MAP 256 LOT 2  
**OVERALL LANDSCAPE PLAN**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**  
 OWNED BY  
**WALTER D HETT TRUST**  
 PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**  
**1"=120' (11"X17")**  
**SCALE: 1"=60' (22"X34")** **SEPTEMBER 25, 2019**



REV	DATE	DESCRIPTION	RCK	JJM
1	12/23/19	NO REVISIONS THIS SHEET	RCK	JJM
			DR	CK



Civil Engineers  
 Structural Engineers  
 Traffic Engineers  
 Land Surveyors  
 Landscape Architects  
 Scientists



48 Constitution Drive  
 Bedford, NH 03110  
 Phone (603) 472-4488  
 Fax (603) 472-9747  
 www.tfmoran.com

Copyright 2019 © Thomas F. Moran, Inc.  
 48 Constitution Drive, Bedford, N.H. 03110  
 All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.  
 This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.



Mar 23, 2020 - 4:43pm F:\MISC Projects\47381 - Portsmouth\47381-00 - Green & Co - Banfield Road\Design\Production Drawings\Landscape.dwg

MATCHLINE



**LANDSCAPE LEGEND**

SYMBOL	QTY	BOTANICAL NAME COMMON NAME	SIZE	REMARKS
<b>SHADE TREES</b>				
	12	ACER RUBRUM 'OCTOBER GLORY' **OCTOBER GLORY RED MAPLE	3" TO 3 1/2" CAL.	B&B
	10	ACER SACCHARUM 'COMMEMORATION' **COMMEMORATION SUGAR MAPLE	3" TO 3 1/2" CAL.	B&B
	23	BETULA N. 'HERITAGE' *RIVER BIRCH	12' TO 14' CLUMP	B&B
	20	NYSSA SYLVATICA *BLACK GUM	2 1/2 TO 3" CAL.	B&B
	12	QUERCUS ALBA *WHITE OAK	3" TO 3 1/2" CAL.	B&B
	11	QUERCUS RUBRA *RED OAK	3" TO 3 1/2" CAL.	B&B

**LANDSCAPE LEGEND**

SYMBOL	QTY	BOTANICAL NAME COMMON NAME	SIZE	REMARKS
<b>SMALL/FLOWERING TREES</b>				
	8	CARPINUS CAROLINIANA *AMERICAN HORNBEAM	2' TO 2 1/2" CAL.	B&B
	36	CRATAEGUS CRUSGALLI INERMIS **THORNLESS COCKSPUR HAWTHORN	2 1/2" TO 3" CAL.	B&B
	24	PRUNUS VIRGINIANA 'SCHUBERT' *CANADA RED CHERRY	2 1/2" TO 3" CAL.	B&B
<b>EVERGREEN TREES</b>				
	19	ABIES BALSAMAE *BALSAM FIR	6' TO 7'	B&B
	14	JUNIPERUS VIRGINIANA *EASTERN RED CEDAR	6' TO 7'	B&B
	38	PICEA GLAUCA WHITE SPRUCE	7' TO 8'	B&B
	25	PINUS STROBUS *WHITE PINE	6' TO 7'	B&B

**LANDSCAPE LEGEND**


SYMBOL	QTY	BOTANICAL NAME COMMON NAME	SIZE	REMARKS
<b>DECIDUOUS SHRUB</b>				
	24	AMELANCHEIR CANADENSIS SHADBLOW SERVICEBERRY	5' TO 6' CLUMP	B&B
	34	CLETHRA ALNIFOLIA 'COMPACTA' **COMPACT SUMMERSWEET	7 GAL.	CONT.
	60	CORNUS SERICEA 'ALLEMAN'S COMPACTA' **ALLEMAN'S COMPACT RED-OSIER DOGWOOD	3' TO 4'	CONT.
	48	PHYSOCARPUS O. 'BURGUNDY CANDY' **BURGUNDY CANDY NINEBARK	2 GAL.	CONT.
	14	VIBURNUM DENTATUM *ARROWWOOD VIBURNUM	4' TO 5'	B&B
	19	VIBURNUM TRILOBUM *AMERICAN CRANBERRY VIBURNUM	4' TO 5'	B&B
	6	VIBURNUM PRUNIFOLIUM *BLACKHAW VIBURNUM	4' TO 5'	B&B

**LANDSCAPE LEGEND**

SYMBOL	QTY	BOTANICAL NAME COMMON NAME	SIZE	REMARKS
<b>EVERGREEN SHRUB</b>				
	23	ARCTOSTAPHYLOS UVA-URSI *BEARBERRY	1 GAL.	CONT.
	26	AZALEA 'GIRARD'S CRIMSON' GIRARD'S CRIMSON AZALEA	3 GAL.	CONT.
	26	AZALEA 'GIRARD'S RENEE MICHELE' GIRARD'S RENEE MICHELE AZALEA	3 GAL.	CONT.
	39	RHODODENDRON 'ROSEUM PINK' **ROSEUM PINK CATAWBA RHODODENDRON	7 GAL.	CONT.
	20	ILEX GLABRA 'COMPACTA' **COMPACT INKBERRY	3 GAL.	CONT.
	25	JUNIPERUS H. 'BAR HARBOR' *BAR HARBOR JUNIPER	3 GAL.	CONT.
	126	JUNIPERUS C. 'ANGELICA BLUE' ANGELICA BLUE JUNIPER	5 GAL.	CONT.
	14	PINUS M. 'MOPS' MOPS MUGO PINE	3 GAL.	CONT.
	58	THUJA O. NIGRA DARK AMERICAN ARBORVITAE	5' TO 6'	B&B

\*NATIVE  
\*\*IMPROVED NATIVE

SYMBOL	QTY	BOTANICAL NAME COMMON NAME	SIZE	REMARKS
<b>GRASSES AND GRASS MIXES</b>				
	11	PANICUM VIRGATUM 'CLOUD NINE' CLOUD NINE SWITCH GRASS	3 GAL.	CONT.
	3 LBS	NEW ENGLAND CONSERVATION WILDLIFE MIX	25 LBS/ACRE	BULK LBS



REV.	DATE	DESCRIPTION	DR	CK
3	3/4/2020	UPDATE PLANS PER REGULATORY COMMENTS	RCK	JJM
2	12/27/2019	IN HOUSE REVISIONS	RCK	JJM
1	12/23/19	NO REVISIONS THIS SHEET	RCK	JJM

**SITE DEVELOPMENT PLANS**

TAX MAP 256 LOT 2  
**LANDSCAPE PLAN**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**  
 OWNED BY  
**WALTER D HETT TRUST**  
 PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**  
**1"=60' (11"X17")**  
**SCALE: 1"=30' (22"X34")** **SEPTEMBER 25, 2019**




Civil Engineers  
 Structural Engineers  
 Traffic Engineers  
 Land Surveyors  
 Landscape Architects  
 Scientists  
 48 Constitution Drive  
 Bedford, NH 03110  
 Phone (603) 472-4488  
 Fax (603) 472-9747  
 www.tfmoran.com

FILE NO.	47361.00	DR	MSK	FB			
		CK	JJM	CADFILE	LANDSCAPE		C-17

Mar 23, 2020 - 4:43pm F:\MISC Projects\47361 - Portsmouth\47361-00 - Green & Co - Banfield Road\Design\Production Drawings\Landscape.dwg


Copyright 2019 © Thomas F. Moran, Inc.  
 48 Constitution Drive, Bedford, N.H. 03110  
 All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.  
 This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.





**SITE DEVELOPMENT PLANS**  
 TAX MAP 256 LOT 2  
**LANDSCAPE PLAN**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**  
 OWNED BY  
**WALTER D HETT TRUST**  
 PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**  
**1"=60' (11'X17")**  
**SCALE: 1"=30' (22"X34")** **SEPTEMBER 25, 2019**

Copyright 2019 © Thomas F. Moran, Inc.  
 48 Constitution Drive, Bedford, N.H. 03110  
 All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.  
 This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.




REV	DATE	DESCRIPTION	DR	CK
3	3/4/2020	UPDATE PLANS PER REGULATORY COMMENTS	RCK	JJM
2	12/27/2019	IN HOUSE REVISIONS	RCK	JJM
1	12/23/19	NO REVISIONS THIS SHEET	RCK	JJM






<b>TFM</b>	Civil Engineers	48 Constitution Drive
	Structural Engineers	Bedford, NH 03110
	Traffic Engineers	Phone (603) 472-4488
	Land Surveyors	Fax (603) 472-9747
	Landscape Architects	www.tfmoran.com
	Scientists	

FILE NO: 47361.00	DR: MSK	FB	
CK: JUM	CADFILE	LANDSCAPE	C-18

Mar 23, 2020 - 4:43pm F:\MSC Projects\47361 - Portsmouth\47361-00 - Green & Co - Banfield Road\Design\Production Drawings\Landscape.dwg



Copyright 2019 © Thomas F. Moran, Inc.  
 48 Constitution Drive, Bedford, N.H. 03110  
 All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.  
 This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.



**SITE DEVELOPMENT PLANS**  
 TAX MAP 256 LOT 2  
**LANDSCAPE PLAN**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**  
 OWNED BY  
**WALTER D HETT TRUST**  
 PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**  
**1"=60' (11"X17")**  
**SCALE: 1"=30' (22"X34")** **SEPTEMBER 25, 2019**

REV	DATE	DESCRIPTION	DR	CK
3	3/4/2020	UPDATE PLANS PER REGULATORY COMMENTS	RCK	JJM
2	12/27/2019	IN HOUSE REVISIONS	RCK	JJM
1	12/23/19	NO REVISIONS THIS SHEET	RCK	JJM



**TFM** Civil Engineers  
 Structural Engineers  
 Traffic Engineers  
 Landscape Architects  
 Scientists

48 Constitution Drive  
 Bedford, NH 03110  
 Phone (603) 472-4488  
 Fax (603) 472-9747  
 www.tfmoran.com

47361.00 DR MSK FB  
 CK JJM CADFILE LANDSCAPE

C-19

Mar 23, 2020 - 4:43pm  
 F:\MISC Projects\47361 - Banfield Road - Portsmouth\47361-00 - Green & Co - Banfield Road\Design\Production Drawings\landscape.dwg



Mar 23, 2020 - 4:44pm  
F:\MISC Projects\47361 - Banfield Road - Portsmouth\47361-00 - Green & Co - Banfield Road\Design\Production Drawings\Lighting.dwg


Copyright 2019 © Thomas F. Moran, Inc.  
48 Constitution Drive, Bedford, N.H. 03110

All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.

This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.



Luminaire Schedule				
Symbol	Qty	Label	Arrangement	Description
<input checked="" type="checkbox"/>	1	P4	SINGLE	COL18-IV-48VLED-NW-350-HS-PT/ MOUNTED ON 12' WOOD POLE PROVIDED BY OTHERS



REV	DATE	DESCRIPTION	DR	CK
4	3/20/2020	PROGRESS PRINT	RCK	JJM
3	3/4/2020	UPDATE PLANS PER REGULATORY COMMENTS	RCK	JJM
2	12/27/2019	IN HOUSE REVISIONS	RCK	JJM
1	12/23/19	NO REVISIONS THIS SHEET	RCK	JJM



**SITE DEVELOPMENT PLANS**

TAX MAP 256 LOT 2  
**LIGHTING PLAN**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**

OWNED BY  
**WALTER D HETT TRUST**  
PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**  
**1"=60' (11"X17")**  
**SCALE: 1"=30' (22"X34")** **SEPTEMBER 25, 2019**

<b>TFM</b>	Civil Engineers Structural Engineers Traffic Engineers Land Surveyors Landscape Architects Scientists			48 Constitution Drive Bedford, NH 03110 Phone (603) 472-4488 Fax (603) 472-9747 www.tfmoran.com
	47361.00	DR RCK CK JJM	FB CADFILE	C-20

Mar 23, 2020 - 4:44pm F:\MISC Projects\47381 - Banfield Road - Portsmouth\47381-00 - Green & Co - Banfield Road\Design\Production Drawings\Plan and Profile.dwg




**SITE DEVELOPMENT PLANS**

TAX MAP 256 LOT 2  
**ROAD-A PROFILE**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**

OWNED BY  
**WALTER D HETT TRUST**  
 PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**

**1"=80' (11"X17")**  
**SCALE: 1"=40' (22"X34")** **SEPTEMBER 25, 2019**


Copyright 2019 © Thomas F. Moran, Inc.  
 48 Constitution Drive, Bedford, N.H. 03110  
 All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.  
 This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.




REV	DATE	DESCRIPTION	DR	CK
4	3/20/2020	PROGRESS PRINT	RCK	JJM
3	3/4/2020	UPDATE PLANS PER REGULATORY COMMENTS	RCK	JJM
2	12/27/2019	IN HOUSE REVISIONS	RCK	JJM
1	12/23/19	REVISED PER REGULATORY COMMENTS	RCK	JJM

	Civil Engineers Structural Engineers Traffic Engineers Land Surveyors Landscape Architects Scientists	48 Constitution Drive Bedford, NH 03110 Phone (603) 472-4488 Fax (603) 472-9747 www.tfmoran.com
	47361.00	DR RCK FB CK JIM CADFILE


Mar 23, 2020 - 4:44pm  
F:\MSC Projects\47381 - Portsmouth\47381-00 - Green & Co - Banfield Road\Design\Production Drawings\Plan and Profile.dwg



Copyright 2019 © Thomas F. Moran, Inc.  
48 Constitution Drive, Bedford, N.H. 03110  
All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.  
This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.



REV	DATE	DESCRIPTION	DR	CK
4	3/20/2020	PROGRESS PRINT	RCK	JJM
3	3/4/2020	UPDATE PLANS PER REGULATORY COMMENTS	RCK	JJM
2	12/27/2019	IN HOUSE REVISIONS	RCK	JJM
1	12/23/19	REVISIONS PER REGULATORY COMMENTS	RCK	JJM





**SITE DEVELOPMENT PLANS**  
TAX MAP 256 LOT 2  
**ROAD-A PROFILE**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**  
OWNED BY  
**WALTER D HETT TRUST**  
PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**  
**1"=80 (11"X17")**  
**SCALE: 1"=40' (22"X34")** **SEPTEMBER 25, 2019**

<b>TFM</b>	Civil Engineers	48 Constitution Drive
	Structural Engineers	Bedford, NH 03110
	Traffic Engineers	Phone (603) 472-4488
	Land Surveyors	Fax (603) 472-9747
	Landscape Architects	www.tfmoran.com
	Scientists	

47361.00 DR RCK FB  
CK JUM CADFILE PLAN AND PROFILE C-22






**NOTES**

- SEE GENERAL EROSION CONTROL NOTES ON THE EROSION CONTROL DETAIL SHEET AND THE APPROVED SWPPP.
- INSTALL SILT BARRIER ALONG THE PERIMETER OF THE AREA TO BE DISTURBED AS FIRST ORDER OF WORK.
- PROVIDE INLET PROTECTION BARRIERS AROUND ALL EXISTING AND PROPOSED STORM DRAINAGE INLETS WITHIN THE WORK LIMITS AND MAINTAIN FOR THE DURATION OF THE PROJECT UNTIL PAVEMENT HAS BEEN INSTALLED. INLET PROTECTION BARRIERS SHALL BE IN PLACE AT ALL CATCH BASINS PRIOR TO THE DISTURBANCE OF SOIL.
- DUST CONTROL SHALL BE MAINTAINED THROUGHOUT THE CONSTRUCTION PERIOD. IT SHALL BE ACCOMPLISHED BY THE UNIFORM APPLICATION OF CALCIUM CHLORIDE AT THE RATE OF 1-1/2 POUNDS PER SQUARE YARD BY MEANS OF A LIME SPREADER OR OTHER APPROVED METHOD. WATER MAY ALSO BE USED FOR DUST CONTROL, AND APPLIED BY SPRINKLING WITH WATER TRUCK DISTRIBUTORS, AS REQUIRED.
- THE SITE WILL REQUIRE A USEPA NPDES PERMIT FOR STORMWATER DISCHARGE FOR THE SITE CONSTRUCTION SINCE THE DISTURBANCE EXCEEDS ONE ACRE. THE CONSTRUCTION SITE OPERATOR SHALL DEVELOP AND IMPLEMENT A CONSTRUCTION STORM WATER POLLUTION PREVENTION PLAN (SWPPP) IN ACCORDANCE WITH EPA REGULATIONS AND THE CONSTRUCTION GENERAL PERMIT WHICH SHALL REMAIN ON SITE AND MADE ACCESSIBLE TO THE PUBLIC. THE SITE CONTRACTOR SHALL COORDINATE WITH THE OWNER TO SUBMIT AN NOI AT LEAST 14 DAYS IN ADVANCE OF ANY EARTHWORK ACTIVITIES AT THE SITE. A COMPLETED NOTICE OF TERMINATION (NOT) SHALL BE SUBMITTED TO NPDES PERMITTING AUTHORITY WITHIN 30 DAYS AFTER EITHER OF THE FOLLOWING CONDITIONS HAVE BEEN MET: FINAL STABILIZATION HAS BEEN ACHIEVED ON ALL PORTIONS OF THE SITE FOR WHICH THE PERMITEE IS RESPONSIBLE FOR, OR ANOTHER OPERATOR/PERMITEE HAS ASSUMED CONTROL OVER ALL AREAS OF THE SITE THAT HAVE NOT BEEN FINALLY STABILIZED.
- SILT PROTECTION MEASURES SHALL BE INSTALLED IN ACCORDANCE WITH THE DETAILS CONTAINED IN THIS PLAN SET.
- CONSTRUCT JUTE MATTING ON ALL SLOPES STEEPER THAN 3:1, DISTURBED AREAS SLOPING TOWARDS WETLANDS AND ALL LOCATIONS SHOWN ON PLAN.
- INSPECT EROSION CONTROL MEASURES WEEKLY AND AFTER EACH RAIN STORM OF 0.10" OR GREATER. REPAIR/MODIFY SILT BARRIER AS NECESSARY TO MAXIMIZE FILTER EFFICIENCY. REMOVE SEDIMENT WHEN SEDIMENT IS 1/3 THE STRUCTURE HEIGHT.
- PROVIDE SILT BARRIERS AT THE BASE OF CUT AND FILL SLOPES UNTIL COMPLETION OF THE PROJECT OR UNTIL VEGETATION BECOMES ESTABLISHED ON SLOPES. EROSION PROTECTION BELOW FILL SLOPES SHALL BE PLACED IMMEDIATELY AFTER CLEARING, PRIOR TO EMBANKMENT CONSTRUCTION.
- ALL DISTURBED AREAS SHALL BE REVEGETATED AS QUICKLY AS POSSIBLE. ALL CUT AND FILL SLOPES SHALL BE SEEDED WITHIN 72 HOURS AFTER GRADING.
- ALL WORK AREAS TO BE STABILIZED AT THE END OF EACH WORK DAY AND PRIOR TO ANY PREDICTED SIGNIFICANT RAIN EVENT.
- AN AREA SHALL BE CONSIDERED STABLE IF ONE OF THE FOLLOWING HAS OCCURRED:  
 A. BASE COURSE GRAVELS ARE INSTALLED IN AREAS TO BE PAVED  
 B. A MINIMUM OF 85% VEGETATED GROWTH HAS BEEN ESTABLISHED  
 C. A MINIMUM OF 3" OF NON-EROSIVE MATERIAL SUCH AS STONE OR RIP RAP HAS BEEN INSTALLED  
 D. EROSION CONTROL BLANKETS HAVE BEEN PROPERLY INSTALLED
- ALL CATCH BASINS, MANHOLES, AND DRAIN LINES SHALL BE THOROUGHLY CLEANED OF ALL SEDIMENT AND DEBRIS AFTER ALL AREAS HAVE BEEN STABILIZED.
- CONTRACTOR IS RESPONSIBLE FOR MAINTAINING SLOPE STABILITY DURING CONSTRUCTION.
- THE EROSION CONTROL PRACTICES SHOWN ON THESE PLANS ARE ILLUSTRATIVE ONLY AND SHALL BE SUPPLEMENTED BY THE SITE CONTRACTOR AS NEEDED.
- EROSION CONTROL BERM MAY BE USED IN PLACE OF ONE LAYER OF SILT SOCK.
- TURBIDITY CURTAIN TO BE USED IN PLACE OF DOUBLE LAYER OF SILT SOCK WHEN STANDING WATER IS ENCOUNTERED.

SOIL LEGEND	
SITE SPECIFIC SOILS	135B
NRCS SOILS	538A

SOIL LEGEND PER SITE SPECIFIC SOIL SURVEY (SSS)		
SSS SYMBOL	SSS MAP NAME	HYDROLOGIC SOIL GROUP
41	CHATFIELD-HOLLIS-ROCK OUTCROP COMPLEX	B
135	CHATFIELD VARIANT-NEWFIELDS COMPLEX	C
538	SQUAMSCOTT FINE SANDY LOAM	C
656	RIDGEBURY FINE SANDY LOAM	C
SLOPE PHASE:		
0-8%	B	
8-15%	C	
15-25%	D	
25%+	E	

SOIL LEGEND PER USDA NRCS WEB SOIL SURVEY			
NRCS SYMBOL	NRCS DESCRIPTION		HYDROLOGIC SOIL GROUP
38B	ELDRIDGE FINE SANDY LOAM, - 8% SLOPES	3%	C/D
140B	CHATFIELD-HOLLIS-CANTON COMPLEX, 0% - 8%		B
140C	CHATFIELD-HOLLIS-CANTON COMPLEX, 8% - 15%		B
299	UDORTMENTS		-
538A	SQUAMSCOTT FINE SANDY LOAM, 0% - 5%		C/D



REV	DATE	DESCRIPTION	DR	CK
4	3/20/2020	PROGRESS PRINT	RCK	JJM
3	3/4/2020	UPDATE PLANS PER REGULATORY COMMENTS	RCK	JJM
2	12/27/2019	IN HOUSE REVISIONS	RCK	JJM
1	12/23/19	NO REVISIONS THIS SHEET	RCK	JJM

**SITE DEVELOPMENT PLANS**  
 TAX MAP 256 LOT 2  
**EROSION CONTROL PLAN**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**  
 OWNED BY  
**WALTER D HETT TRUST**  
 PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**  
**1"=60' (11"X17")**  
**SCALE: 1"=30' (22"X34")** **SEPTEMBER 25, 2019**


Copyright 2019 © Thomas F. Moran, Inc.  
 48 Constitution Drive, Bedford, N.H. 03110  
 All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.  
 This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.



	Civil Engineers	48 Constitution Drive
	Structural Engineers	Bedford, NH 03110
	Traffic Engineers	Phone (603) 472-4488
	Land Surveyors	Fax (603) 472-9747
	Landscape Architects	www.tfmoran.com
	Scientists	


Mar 23, 2020 - 4:44pm  
 F:\MISC Projects\47381 - Portsmouth\47381-00 - Green & Co - Banfield Road\Design\Production Drawings\Erosion.dwg

Mar 23, 2020 - 4:44pm  
F:\MISC Projects\47381 - Portsmouth\47381-00 - Green & Co - Banfield Road\Design\Production Drawings\Erosion.dwg



**SITE DEVELOPMENT PLANS**  
 TAX MAP 256 LOT 2  
**EROSION CONTROL PLAN**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**  
 OWNED BY  
**WALTER D HETT TRUST**  
 PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**  
**1"=60' (11"X17")**  
**SCALE: 1"=30' (22"X34")** **SEPTEMBER 25, 2019**


Copyright 2019 © Thomas F. Moran, Inc.  
 48 Constitution Drive, Bedford, N.H. 03110  
 All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.  
 This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.



REV	DATE	DESCRIPTION	DR	CK
4	3/20/2020	PROGRESS PRINT	RCK	JJM
3	3/4/2020	UPDATE PLANS PER REGULATORY COMMENTS	RCK	JJM
2	12/27/2019	IN HOUSE REVISIONS	RCK	JJM
1	12/23/19	NO REVISIONS THIS SHEET	RCK	JJM

<b>TFM</b>	Civil Engineers	48 Constitution Drive Bedford, NH 03110 Phone (603) 472-4488 Fax (603) 472-9747 www.tfmoran.com	
	Structural Engineers Traffic Engineers Land Surveyors Landscape Architects Scientists		
47361.00	DR RCK FB CK JJM CADFILE	EROSION	C-24

Mar 23, 2020 - 4:44pm F:\MISC Projects\47381 - Portsmouth\47381-00 - Green & Co - Banfield Road\Design\Production Drawings\Erosion.dwg





**SITE DEVELOPMENT PLANS**

TAX MAP 256 LOT 2  
**EROSION CONTROL PLAN**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**

OWNED BY  
**WALTER D HETT TRUST**

PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**

**1"=60' (11"X17")**  
**SCALE: 1"=30' (22"X34")** **SEPTEMBER 25, 2019**



REV	DATE	DESCRIPTION	DR	CK
4	3/20/2020	PROGRESS PRINT	RCK	JJM
3	3/4/2020	UPDATE PLANS PER REGULATORY COMMENTS	RCK	JJM
2	12/27/2019	IN HOUSE REVISIONS	RCK	JJM
1	12/23/19	NO REVISIONS THIS SHEET	RCK	JJM


Copyright 2019 © Thomas F. Moran, Inc.  
 48 Constitution Drive, Bedford, N.H. 03110  
 All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.  
 This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.



<b>TFM</b>	Civil Engineers Structural Engineers Traffic Engineers Land Surveyors Landscape Architects Scientists			48 Constitution Drive Bedford, NH 03110 Phone (603) 472-4488 Fax (603) 472-9747 www.tfmoran.com
	47361.00	DR RCK CK JMM	FB CADFILE	EROSION

C-25







TYPICAL WETLAND CROSSING - OPEN TRENCH  
NOT TO SCALE

- NOTES:
- GRUBBING SHALL NOT TAKE PLACE BEYOND THE LIMIT OF WORK AS SHOWN ON THE APPROVED PLANS.
  - WATER ACCUMULATING WITH IN THE WORK AREA SHALL BE PUMPED TO A SEDIMENT BAG OR SEDIMENT TRAP PRIOR TO DISCHARGING.
  - HAZARDOUS OR POLLUTANT MATERIAL STORAGE AREAS AND EQUIPMENT REFUELING AREAS SHALL BE LOCATED AT LEAST 100' BACK FROM THE EDGE OF WETLAND.
  - ALL EXCESS EXCAVATED MATERIAL SHALL BE IMMEDIATELY REMOVED FROM THE EDGE OR WETLAND.
  - ALL DISTURBED AREAS WITHIN 50' OF THE EDGE OF WETLAND SHALL BE BLANKETED OR MATTED WITHIN 24 HOURS OF INITIAL DISTURBANCE UNLESS OTHERWISE AUTHORIZED. APPROPRIATE WETLAND PROTECTION SHALL BE PROVIDED WITHIN THE CHANNEL.
  - PROVIDE SECONDARY CONTAINMENT TO CAPTURE DRIPS, SPILLS, OR LEAKS OF FUEL OR OIL.

- WETLAND CROSSING -- SEQUENCE OF CONSTRUCTION
- THE PLACEMENT OF THESE STRUCTURES WILL BE DONE IN THE ORDER AS NUMBERED BELOW. EACH SEQUENCE BELOW WILL BE COMPLETED BEFORE THE NEXT STEP IN THE SEQUENCE COMMENCES. NO STEPS WILL BE REMOVED.
- THE TIME OF WETLAND DISTURBANCE WILL BE LIMITED AND WILL BE SCHEDULED DURING LOW FLOW OR NO FLOW CONDITIONS.
- AT WETLAND CROSSING, THE WETLAND BUFFER SHALL BE MAINTAINED TO THE LARGEST EXTENT FEASIBLE. CLEARING, SOD DISTURBANCE, EXCAVATION, AND EQUIPMENT TRAFFIC SHOULD BE MINIMIZED. ACTIVITIES SUCH AS STACKING CUT LOGS, DISCHARGING RAIN WATER FROM TRENCHES, WELDING PIPE JOINTS, STORING PIPE SECTIONS, REFUELING AND MAINTAINING EQUIPMENT SHOULD BE ACCOMPLISHED OUTSIDE OF THESE BUFFERS.
  - INSTALL APPROPRIATE SEDIMENT BARRIER DOWNSLOPE OF ALL SPOIL/EXCAVATION FROM CROSSING AREAS PRIOR TO THE COMMENCEMENT OF CONSTRUCTION.
    - NOTE: THE SEDIMENT BARRIER FOR THE SPOIL CROSSING AREAS MUST BE A MINIMUM OF 10' FROM THE EDGE OF WETLAND
  - INSTALL WATER PUMP. IF A LEVEL AREA IS REQUIRED, GRADE THE PUMP AREA, THEN PLACE A 4" LAYER OF #57 STONE OR REINFORCED EROSION CONTROL BLANKET.
  - DURING THE EXCAVATION FOR THE PLACEMENT OF THE WETLAND CROSSING:
    - ALL WATER THAT NEEDS TO BE PUMPED FROM THE EXCAVATED TRENCH AREA WILL BE REMOVED BY DISCHARGE THROUGH A PUMPED WATER FILTER BAG. SEE FILTER BAG PAD DETAIL.
    - IF THE AREA THAT THE BAG IS PLACED ON IS GREATER THAN 5% SLOPE, THEN A PUMPED WATER FILTER BAG PAD WILL BE CONSTRUCTED. SEE SEDIMENT FILTER BAG WITH GRAVEL PAD DETAIL.
  - EXCAVATE MATERIAL FOR TRENCH AREA. THE MATERIAL WILL THEN BE PLACED IN A DESIGNATED AREAS FOR LATER USE. KEEP WETLAND TOPSOIL SEPARATE FOR LATER USE.
  - INSTALL CROSSING
    - INSTALL ECOPASSAGE FOOTING.
    - INSTALL ECOPASSAGE.
    - INSTALL CONDUITS FOR UTILITIES.
    - BACKFILL WILL THEN BE PLACED AROUND AND/OR ON THE ECOPASSAGES. BACK FILL SHALL BE COMPACTED IN A MAXIMUM OF 12' LIFTS.
  - THE WETLAND AND SURROUNDING AREA NOT BEING DEVELOPED WILL BE RESTORED TO ORIGINAL CONTOURS. ALL DISTURBED AREAS WILL BE SEEDED AND MULCHED.
  - THE PUMPING OF WATER TO THE WATER FILTER BAG AS SHOWN IN STEP 4 OF THE INSTALLATION WILL CONTINUE DURING RESTORATION PROCEDURES.
  - THE SPOIL FROM CROSSING PLACEMENT AREAS WILL BE REGRADED, SEEDED AND MULCHED.
    - THE SILT BARRIER SHALL BE PLACED DOWN GRADIENT OF THE SPOIL STORAGE AREA AND WILL REMAIN IN PLACE AND MAINTAINED UNTIL PERMANENT VEGETATED STABILIZATION IS ACHIEVED.
    - PERMANENT STABILIZATION WILL BE ACHIEVED WHEN A UNIFORM 85% VEGETATIVE COVER OF THE ENTIRE SEEDED AREA IS ESTABLISHED.
  - REMOVE PUMPED WATER FILTER BAGS. THE AREA UTILIZED FOR THE PUMPED WATER FILTER BAG/PAD WILL BE REGRADED, SEEDED AND MULCHED.
  - THE PUMPING AREA AS SHOWN IN INSTALLATION SEQUENCE 4 WILL BE REGRADED, SEEDED AND MULCHED.
  - ALL AREAS THAT WERE DISTURBED DURING THE CONSTRUCTION OF THE WETLAND CROSSING WILL BE RETURNED TO THEIR ORIGINAL CONTOURS. SILT BARRIERS WILL BE PLACED DOWNSLOPE OF ANY AREAS THAT WILL BE REGRADED. THE AREAS WILL BE SEEDED AND MULCHED AS PER THE EROSION CONTROL NOTES. WILL REMAIN IN PLACE AND MAINTAINED UNTIL PERMANENT VEGETATED STABILIZATION IS ACHIEVED.
  - UPON COMPLETION OF AN EARTH DISTURBANCE ACTIVITY OR ANY STAGE OR PHASE OF AN ACTIVITY, THE SITE SHALL BE IMMEDIATELY SEEDED, MULCHED, OR OTHERWISE PROTECTED FROM ACCELERATED EROSION AND SEDIMENTATION.



PLAN VIEW



SECTION A-A

SEDIMENT FILTER BAG WITH GRAVEL PAD  
NOT TO SCALE


- SEDIMENT FILTER BAG GENERAL NOTES:
- CONTRACTOR SHALL EXERCISE CAUTION NOT TO BURST OR DAMAGE THE SEDIMENT FILTER BAG WHEN PUMPING.
  - THE LENGTH AND WIDTH OF THE TEMPORARY SEDIMENT BAG SHOWN ON THIS DRAWING MAY VARY PER VENDOR SPECIFICATIONS. THE MINIMUM "FOOTPRINT" OF THE BAG SHALL BE 10 x 15 FEET.
  - SEDIMENT FILTER BAGS SHALL BE EQUIPPED WITH A SEWN-IN SLEEVE OF SUFFICIENT SIZE TO ACCEPT A MINIMUM 4 INCH DIAMETER PUMP DISCHARGE HOSE. THE DISCHARGE HOSE SHOULD BE EXTENDED INTO THIS SLEEVE A MINIMUM OF 6 INCHES AND BE TIGHTLY SECURED WITH A HOSE CLAMP OR OTHER SUITABLE MEANS TO PREVENT LEAKAGE. HOSE CONNECTION THROUGH A SLIT IN THE BAG WILL NOT BE ACCEPTABLE.
  - THE PUMP DISCHARGE HOSE CONNECTION SLEEVE SHALL BE SECURELY TIED OFF DURING DISPOSAL OF THE SEDIMENT FILTER BAG IN ORDER TO PREVENT LEAKAGE OF COLLECTED SEDIMENTS.
  - SEDIMENT FILTER BAG SHALL BE MAINTAINED AND REPLACED WHEN ONE HALF FULL OF SEDIMENT OR IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.

**SITE DEVELOPMENT PLANS**

TAX MAP 256 LOT 2  
**WETLAND CROSSING PLAN**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**

OWNED BY  
**WALTER D HETT TRUST**  
PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**

SCALE: NTS SEPTEMBER 25, 2019



REV	DATE	DESCRIPTION	DR	CK
4	3/20/2020	PROGRESS PRINT	RCK	JJM
3	3/4/2020	UPDATE PLANS PER REGULATORY COMMENTS	RCK	JJM
2	12/27/2019	IN HOUSE REVISIONS	RCK	JJM
1	12/23/19	NO REVISIONS THIS SHEET	RCK	JJM


**TFM** Civil Engineers  
Structural Engineers  
Traffic Engineers  
Land Surveyors  
Landscape Architects  
Scientists


48 Constitution Drive  
Bedford, NH 03110  
Phone (603) 472-4488  
Fax (603) 472-9747  
www.tfmoran.com

47361.00 DR RCK FB  
CK JUM CADFILE WETLAND CROSSING SEQUENCE C-27


Mar 23, 2020 - 4:45pm F:\MSC Projects\47361 - Portsmouth - Portsmouth\47361-00 - Green & Co - Banfield Road\Design\Production Drawings\Wetland Crossing Sequence.dwg

Copyright 2019 © Thomas F. Moran, Inc.  
48 Constitution Drive, Bedford, N.H. 03110  
All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.  
This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.







FIRE TRUCK TURNING FROM ROAD-A SOUTHWEST ONTO BANFIELD ROAD




FIRE TRUCK TURNING FROM ROAD-A NORTHEAST ONTO BANFIELD ROAD



FIRE TRUCK DRIVING NORTHEAST TURNING ONTO ROAD-A



FIRE TRUCK DRIVING SOUTHWEST TURNING ONTO ROAD-A




**SITE DEVELOPMENT PLANS**

TAX MAP 256 LOT 2  
**FIRE TRUCK MOVEMENT PLAN**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**

OWNED BY  
**WALTER D HETT TRUST**  
 PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**



SCALE: NTS

SEPTEMBER 25, 2019



REV	DATE	DESCRIPTION	DR	CK
4	3/20/2020	PROGRESS PRINT	RCK	JJM
3	3/4/2020	UPDATE PLANS PER REGULATORY COMMENTS	RCK	JJM
2	12/27/2019	IN HOUSE REVISIONS	RCK	JJM
1	12/23/19	NO REVISIONS THIS SHEET	RCK	JJM

Copyright 2019 © Thomas F. Moran, Inc.  
 48 Constitution Drive, Bedford, N.H. 03110  
 All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.  
 This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.





Civil Engineers  
 Structural Engineers  
 Traffic Engineers  
 Land Surveyors  
 Landscape Architects  
 Scientists

48 Constitution Drive  
 Bedford, NH 03110  
 Phone (603) 472-4488  
 Fax (603) 472-9747  
 www.tfmoran.com

47361.00	DR	RCK	FB	-		
	CK	JJM	CADFILE	TRUCK MOVEMENT		C-28

Mar 23, 2020 - 4:46pm F:\MISC Projects\47361 - Portsmouth\47361-00 - Green & Co - Banfield Road\Design\Production Drawings\Truck Movement.dwg

Mar 23, 2020 - 4:46pm F:\MISC Projects\47361 - Portsmouth\47361-00 - Green & Co - Banfield Road\Design\Production Drawings\Truck Movement.dwg



**SITE DEVELOPMENT PLANS**  
 TAX MAP 256 LOT 2  
**FIRE TRUCK MOVEMENT PLAN**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**  
 OWNED BY  
**WALTER D HETT TRUST**  
 PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**  
**1"=60' (11"X17")**  
**SCALE: 1"=30' (22"X34")** **SEPTEMBER 25, 2019**

Copyright 2019 © Thomas F. Moran, Inc.  
 48 Constitution Drive, Bedford, N.H. 03110  
 All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.  
 This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.




HORIZONTAL SCALE 1"=30'  
 30 15 0 30

REV	DATE	DESCRIPTION	DR	CK
4	3/20/2020	PROGRESS PRINT	RCK	JJM
3	3/4/2020	UPDATE PLANS PER REGULATORY COMMENTS	RCK	JJM
2	12/27/2019	IN HOUSE REVISIONS	RCK	JJM
1	12/23/19		RCK	JJM

<b>TFM</b>	Civil Engineers Structural Engineers Traffic Engineers Land Surveyors Landscape Architects Scientists			48 Constitution Drive Bedford, NH 03110 Phone (603) 472-4488 Fax (603) 472-9747 www.tfmoran.com	
	47361.00	DR CK	RCK JUM	FB CADFILE	- TRUCK MOVEMENT

Mar 23, 2020 - 4:46pm F:\MISC Projects\47381 - Banfield Road - Portsmouth\47381-00 - Green & Co - Banfield Road\Design\Production Drawings\Truck Movement Driveways.dwg




MAP 256 LOT 2  
1,955,150 S.F.  
(44.884 AC)

**SITE DEVELOPMENT PLANS**

TAX MAP 256 LOT 2  
**FIRE TRUCK MOVEMENT PLAN**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**  
OWNED BY  
**WALTER D HETT TRUST**  
PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**

SCALE: NTS

SEPTEMBER 25, 2019



REV	DATE	DESCRIPTION	DR	CK
4	3/20/2020	PROGRESS PRINT	RCK	JJM
3	3/4/2020	UPDATE PLANS PER REGULATORY COMMENTS	RCK	JJM
2	12/27/2019	IN HOUSE REVISIONS	RCK	JJM
1	12/23/19	NO REVISIONS THIS SHEET	RCK	JJM

Copyright 2019 © Thomas F. Moran, Inc.  
48 Constitution Drive, Bedford, N.H. 03110  
All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.  
This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.






Civil Engineers  
Structural Engineers  
Traffic Engineers  
Land Surveyors  
Landscape Architects  
Scientists

48 Constitution Drive  
Bedford, NH 03110  
Phone (603) 472-4488  
Fax (603) 472-9747  
www.tfmoran.com

47361.00 DR RCK FB  
CK JMM CADFILE TRUCK MOVEMENT DRIVEWAYS C-30




Mar 23, 2020 - 4:46pm  
F:\MISC Projects\47361 - Portsmouth - Banfield Road\Design\Production Drawings\Truck Movement Driveways.dwg




**SITE DEVELOPMENT PLANS**  
 TAX MAP 256 LOT 2  
**FIRE TRUCK MOVEMENT PLAN**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**  
 OWNED BY  
**WALTER D HETT TRUST**  
 PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**  
**1"=60' (11"X17")**  
**SCALE: 1"=30' (22"X34")** **SEPTEMBER 25, 2019**

Copyright 2019 © Thomas F. Moran, Inc.  
 48 Constitution Drive, Bedford, N.H. 03110  
 All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.  
 This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.



REV	DATE	DESCRIPTION	DR	CK
4	3/20/2020	PROGRESS PRINT	RCK	JJM
3	3/4/2020	UPDATE PLANS PER REGULATORY COMMENTS	RCK	JJM
2	12/27/2019	IN HOUSE REVISIONS	RCK	JJM
1	12/23/19		RCK	JJM


<b>TFM</b>	Civil Engineers Structural Engineers Traffic Engineers Land Surveyors Landscape Architects Scientists			48 Constitution Drive Bedford, NH 03110 Phone (603) 472-4488 Fax (603) 472-9747 www.tfmoran.com	
	47361.00	DR CK	RCK JJM	FB CADFILE	TRUCK MOVEMENT DRIVEWAYS



**NOTES**

1. FILTER CLOTH - WILL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING OF STONE SURFACE.
2. WATER - ALL SURFACE WATER FLOWING OR DIVERTED TOWARD CONSTRUCTION ENTRANCES SHALL BE PIPED ACROSS THE ENTRANCE. IF PIPING IS IMPRACTICAL, A MOUNTABLE BERM WITH 5:1 SLOPES WILL BE PERMITTED.
3. MAINTENANCE - THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHTS-OF-WAY MUST BE REMOVED IMMEDIATELY.
4. WASHING - WHEELS SHALL BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC RIGHTS-OF-WAY. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH STONE AND WHICH DRAINS INTO AN APPROVED SEDIMENT TRAPPING DEVICE.
5. PERIODIC INSPECTION AND NEEDED MAINTENANCE SHALL BE PROVIDED AFTER EACH RAIN STORM EVENT.

**STABILIZED CONSTRUCTION ENTRANCE**  
NOT TO SCALE




**NOTES:**

1. ALL MATERIAL TO MEET Filterrex™ SPECIFICATIONS
2. FilterSoxx™ COMPOST/SOIL/ROCK/SEED FILL TO MEET APPLICATION REQUIREMENTS.
3. COMPOST MATERIAL TO BE DISPERSED ON SITE, AS DETERMINED BY ENGINEER.
4. SIZE OF SOCK TO BE PER MANUFACTURER'S SPECIFICATIONS

**FILTREXX™ FILTERSOXX™ STAKING**  
NOT TO SCALE

**MAINTENANCE:**

THE OUTLET PROTECTION SHOULD BE CHECKED AT LEAST ANNUALLY AND AFTER EVERY MAJOR STORM. IF THE RIP RAP HAS BEEN DISPLACED, UNDERMINED OR DAMAGED, IT SHOULD BE CHECKED TO SEE THAT EROSION IS NOT OCCURRING. THE DOWNSTREAM CHANNEL SHOULD BE KEPT CLEAR OF OBSTRUCTIONS SUCH AS FALLEN TREES, DEBRIS, AND SEDIMENT THAT COULD CHANGE FLOW PATTERNS AND/OR TAILWATER DEPTHS ON THE PIPES. REPAIRS MUST BE CARRIED OUT IMMEDIATELY TO AVOID ADDITIONAL DAMAGE TO THE OUTLET PROTECTION APRON.



% OF WEIGHT SMALLER FOR d50=3" THAN THE GIVEN SIZE	SIZE OF STONE (INCHES)
100	4.50 TO 6.00
85	3.90 TO 5.40
50	3.00 TO 4.50
15	0.90 TO 1.50


**CONSTRUCTION SPECIFICATIONS:**

1. THE SUBGRADE FOR THE FILTER MATERIAL, GEOTEXTILE FABRIC, AND RIP RAP SHALL BE PREPARED TO THE LINES AND GRADES SHOWN ON THE PLANS.
2. THE ROCK OR GRAVEL USED FOR FILTER OR RIP RAP SHALL CONFORM TO THE SPECIFIED GRADATION.
3. GEOTEXTILE FABRICS SHALL BE PROTECTED FROM PUNCTURE OR TEARING DURING THE PLACEMENT OF THE RIP RAP. DAMAGED AREAS IN THE FABRIC SHALL BE REPAIRED BY PLACING A PIECE OF FABRIC OVER THE DAMAGED AREA OR BY COMPLETE REPLACEMENT OF THE FABRIC. ALL OVERLAPS REQUIRED FOR REPAIRS OR JOINING TWO PIECES OF FABRIC SHALL BE A MINIMUM OF 12".
4. STONE FOR THE RIP RAP MAY BE PLACED BY EQUIPMENT AND SHALL BE CONSTRUCTED TO THE FULL LAYER THICKNESS IN ONE OPERATION AND IN SUCH A MANNER AS TO PREVENT SEGREGATION OF THE STONE SIZES.
5. ADD ANIMAL SCREEN TO FLARED END SECTION OUTLET.


**RIPRAP DIMENSIONS**

LOCATION	FES01	FES02	FES03	FES04	FES05	FES06	FES07	FES08	FES09
d50 STONE SIZE (IN)	3	3	3	3	3	3	3	3	3
L-LENGTH OF APRON (FT)	7	9	17	12	7	7	7	7	7
W-WIDTH OF APRON (FT)	6	6	10	8	6	7	7	7	7
T-DEPTH OF APRON (IN)	7	7	7	7	7	9	9	9	9


**RIP RAP AND FLARED END SECTION WITH OUTLET PROTECTION**  
NOT TO SCALE




**SEDIMENT FOREBAY DETAIL**  
NOT TO SCALE



**STONE CHECK DAM**  
NOT TO SCALE




**STONE CHECK DAM**  
NOT TO SCALE



**NOTES**

1. THE GEOTEXTILE FABRIC SHALL MEET THE DESIGN CRITERIA FOR BEST MANAGEMENT PRACTICE FOR SILT FENCES, OF THE NEW HAMPSHIRE STORMWATER MANUAL, DECEMBER 2008.
2. THE HEIGHT OF THE BARRIER SHALL NOT EXCEED 36 INCHES.
3. WHEN JOINTS ARE NECESSARY, FILTER CLOTH SHALL BE SPICED TOGETHER ONLY AT A SUPPORT POST, WITH A MINIMUM 6-INCH OVERLAP, AND SECURELY SEALED. SEE MANUFACTURER'S RECOMMENDATIONS.
4. POSTS SHALL BE SPACED A MAXIMUM OF 10 FEET APART AT THE BARRIER LOCATION AND DRIVEN SECURELY INTO THE GROUND (MINIMUM OF 16 INCHES). WHEN EXTRA STRENGTH FABRIC IS USED WITHOUT THE WIRE SUPPORT FENCE, POST SPACING SHALL BE AS MANUFACTURER RECOMMENDS.
5. A TRENCH SHALL BE EXCAVATED APPROXIMATELY 6 INCHES WIDE AND 6 INCHES DEEP ALONG THE LINE OF POSTS AND UPSLOPE FROM THE BARRIER IN ACCORDANCE WITH RECOMMENDATIONS.
6. THE FABRIC SHALL NOT EXTEND MORE THAN 36 INCHES ABOVE THE ORIGINAL GROUND SURFACE, AND WILL EXTEND TO A MINIMUM OF 8 INCHES INTO THE TRENCH. FILTER FABRIC SHALL NOT BE STAPLED INTO EXISTING TREES.
7. THE TRENCH SHALL BE BACKFILLED AND THE SOIL COMPACTED OVER THE FILTER FABRIC.
8. FILTER BARRIERS SHALL BE REMOVED WHEN THEY HAVE SERVED THEIR USEFUL PURPOSE, BUT NOT BEFORE THE UPSLOPE AREA HAS BEEN PERMANENTLY STABILIZED.
9. FILTER BARRIERS SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL, AND AT LEAST DAILY DURING PROLONGED RAINFALL, ANY REQUIRED REPAIRS SHALL BE MADE IMMEDIATELY.
10. SHOULD THE FABRIC DECOMPOSE OR BECOME INEFFECTIVE PRIOR TO THE END OF THE EXPECTED USABLE LIFE AND THE BARRIER STILL BE NECESSARY, THE FABRIC SHALL BE REPLACED PROMPTLY.
11. SEDIMENT DEPOSITS SHOULD BE REMOVED WHEN THEY REACH APPROXIMATELY ONE-THIRD THE HEIGHT OF THE BARRIER.
12. ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER THE SILT FENCE OR FILTER BARRIER IS NO LONGER REQUIRED, SHALL BE DRESSED TO CONFORM TO THE EXISTING GRADE, PREPARED AND SEEDED.

**SILT FENCE**  
NOT TO SCALE




**NOTES:**

1. INSTALL PER MANUFACTURER'S SPECIFICATIONS.
2. INSPECTION SHOULD OCCUR FOLLOWING ANY RAIN EVENT > 1/4".
3. EMPTY THE SEDIMENT BAG PER MANUFACTURER'S SPECIFICATIONS.
4. REMOVED CAKED ON SILT FROM SEDIMENT BAG AND FLUSH WITH MEDIUM SPRAY WITH OPTIMAL FILTRATION.
5. REPLACE BAG IF TORN OR PUNCTURED TO > 1/2" DIAMETER ON LOWER HALF OF BAG.

ALL PRODUCTS MANUFACTURED BY INLET & PIPE PROTECTION, INC. A DIVISION OF ADS, INC. WWW.INLETFILTERS.COM (866) 287-8655 INFO@INLETFILTERS.COM

**INLET PROTECTION**  
NOT TO SCALE




**NOTES**

1. CONCRETE SHALL BE 5000 PSI.
2. GRATING TO BE EQUIVALENT TO 38W4 (4-1/2" X 3/8") SMOOTH GRATING - GALVANIZED - LOAD BANDING AS PROVIDED BY LAUREL CUSTOM GRATING, LLC.
3. ALL REINFORCEMENT PER ASTM A-615-75.
4. DESIGN LOAD: H-20 LOADING
5. ABUTMENT TO BE DESIGNED BY A STRUCTURAL ENGINEER PRIOR TO INSTALLATION.
6. FOLLOW UTILITY AND GAS LINE TRENCH DETAILS FOR SAND BEDDING.

**ECO PASSAGE #1 DETAIL**  
NOT TO SCALE

% OF WEIGHT SMALLER FOR d50=12" THAN THE GIVEN SIZE	SIZE OF STONE (INCHES)
100	18.00 TO 24.00
85	15.60 TO 21.6
50	12.00 TO 18.00
15	3.60 TO 6.00




**NOTES**

1. SEE ECO PASSAGE #1 DETAIL FOR NOTES.

**ECO PASSAGE #2 AND #3 DETAIL**  
NOT TO SCALE

% OF WEIGHT SMALLER FOR d50=3" THAN THE GIVEN SIZE	SIZE OF STONE (INCHES)
100	4.50 TO 6.00
85	3.90 TO 5.40
50	3.00 TO 4.50
15	0.90 TO 1.50



**FRAME & GRATE (TYPE B)**  
NOT TO SCALE

**SITE DEVELOPMENT PLANS**

TAX MAP 256 LOT 2

**DETAILS**

**THE VILLAGE AT BANFIELD WOODS**  
PORTSMOUTH, NH

OWNED BY

**WALTER D HETT TRUST**

PREPARED FOR

**GREEN & COMPANY REAL ESTATE**

SCALE: NTS

SEPTEMBER 25, 2019




Civil Engineers  
Structural Engineers  
Traffic Engineers  
Land Surveyors  
Landscape Architects  
Scientists

48 Constitution Drive  
Bedford, NH 03110  
Phone (603) 472-4488  
Fax (603) 472-9747  
www.tfmoran.com

47361.00	DR	RCK	FB						
	CK	JJM	CADFILE						

C-32




REV	DATE	DESCRIPTION	DR	CK
4	3/20/2020	PROGRESS PRINT	RCK	JJM
3	3/4/2020	UPDATE PLANS PER REGULATORY COMMENTS	RCK	JJM
2	12/27/2019	IN HOUSE REVISIONS	RCK	JJM
1	12/23/19	NO REVISIONS THIS SHEET	RCK	JJM

Mar 23, 2020 - 4:47pm  
F:\MISC Projects\47361 - Portsmouth\47361-00 - Green & Co - Banfield Road\Design\Production Drawings\Details.dwg


Copyright 2019 © Thomas F. Moran, Inc.  
48 Constitution Drive, Bedford, N.H. 03110  
All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.  
This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.





- NOTES:**
1. USE KEY JOINT AT ALL LOCATIONS WHERE OVERLAY MEETS EXISTING PAVEMENT.
  2. NEW PAVEMENT SHALL BE FLUSH WITH EXISTING PAVEMENT AND SHALL MEET OVERLAY GRADE WHERE IT ABUTS EXISTING PAVEMENT TO BE OVERLAYED.

**KEY JOINT DETAIL**  
NOT TO SCALE




- LENGTH: AS REQUIRED  
 WEIGHT PER LINEAR FOOT: 2.50 LBS (MIN)  
 HOLES: 3/8" DIAMETER, 1" C-C FULL LENGTH  
 STEEL: SHALL CONFORM TO ASTM A-499 (GRADE 60) OR ASTM A-576 (GRADE 1070 - 1080)  
 FINISH: SHALL BE PAINTED WITH 2 COATS OF AN APPROVED MEDIUM GREEN BAKED-ON OR AIR-DRIED PAINT OF WEATHER RESISTANT QUALITY. ALL FABRICATION SHALL BE COMPLETE BEFORE PAINTING.


- NOTE:**
1. WHERE LEDGE APPLICATION EXISTS, DRILL & GROUT TO A MINIMUM OF 2"
  2. ALL SIGNAGE SHALL FOLLOW THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES STANDARDS AND NHDOT STANDARDS.
  3. SIGN, HARDWARE, AND INSTALLATION SHALL CONFORM TO THE LATEST NHDOT STANDARD SPECIFICATIONS.

**SIGN POST**  
NOT TO SCALE

IN AREAS WHERE OVERLAY IS PROPOSED, FULL-DEPTH PAVEMENT REPAIR SHALL BE IN PLACE PRIOR TO INSTALLATION OF FINAL OVERLAY COURSE




**TRENCH PATCH**  
NOT TO SCALE




- NOTES**
1. BASE SHOWN IS PROTOTYPICAL. VERIFY THAT LIGHT POLE BASE INSTALLED MEETS LIGHT POLE MANUFACTURER'S SPECIFICATIONS. COORDINATE WITH ELECTRICAL CONTRACTOR.
  2. WHERE LIGHT POLE BASES ARE PLACED IN AREAS NOT PROTECTED BY CURBING, A 3'-0" REVEAL OF BASE IS REQUIRED WITH REVEAL TO BE PAINTED SAFETY YELLOW. WHERE LIGHT POLE BASES ARE PLACED IN FIELD APPLICATIONS OR PROTECTED BY CURBING, THE BASE IS TO BE PLACED 2" ABOVE FINISHED GRADE.
  3. BASE CONCRETE TO BE 4,000 PSI, SMOOTH FINISH.
  4. POLES SHALL BE FACTORY CUT TO PROVIDE REQUIRED MOUNTING HEIGHTS.

**LIGHT POLE BASE**  
NOT TO SCALE




- NOTES**
1. TRAFFIC PAINT SHALL BE APPLIED AS SPECIFIED BY THE MANUFACTURER AND SHALL MEET THE REQUIREMENTS OF AASHTO M248 TYPE "F". APPLY TWO COATS.
  2. SYMBOLS AND PARKING STALLS SHALL CONFORM TO THE REQUIREMENTS OF THE AMERICANS WITH DISABILITIES ACT, LATEST EDITION.

**STOP BAR & LEGEND**  
NOT TO SCALE




- NOTES**
1. APPLY TACK COAT PRIOR TO PLACEMENT OF CURB.
  2. BITUMINOUS CURB MATERIAL SHALL MEET THE REQUIREMENTS OF NHDOT SECTION 609.
  3. CAPE COD BERM DIMENSIONS SHALL MATCH THOSE GIVEN IN THIS DETAIL.

**CAPE COD BERM**  
NOT TO SCALE



**STANDARD DUTY PAVEMENT**



**OVERLAY**


- NOTES**
1. SEE GRADING & EROSION CONTROL PLAN FOR PAVEMENT SLOPE AND CROSS-SLOPE.
  2. PROVIDE CLEAN BUTT TO EXISTING PAVEMENT- USE TACK COAT. A TACK COAT SHALL ALSO BE PLACED BETWEEN GRAVEL COURSE AND SUCCESSIVE LAYERS OF BITUMINOUS CONCRETE. SPECIFICALLY, A TACK COAT SHALL BE PLACED ATOP THE BINDER COURSE PAVEMENT PRIOR TO PLACING THE WEARING COURSE.
  3. REMOVE ALL LOAM AND/OR YIELDING MATERIAL BELOW PAVEMENT.
  4. BITUMINOUS MATERIALS SHALL CONFORM TO NHDOT SPECIFICATION SECTION 401.
  5. BITUMINOUS CONCRETE SHALL BE COMPACTED TO AT LEAST 92.5% OF THEORETICAL MAXIMUM DENSITY AS DETERMINED BY ASTM D2041 OR AASHTO T209. PLACEMENT TEMPERATURES OF BITUMINOUS CONCRETE MIXES, IN GENERAL, RANGE BETWEEN 270 AND 310 DEGREES FAHRENHEIT.
  6. PAVEMENT BASE COURSE AGGREGATE SHALL CONFORM TO NHDOT SPECIFICATION SECTION 304, ITEM 304.3 AND COMPACTED TO A MINIMUM OF 95% OF MODIFIED PROCTOR MAXIMUM DRY DENSITY.
  7. PAVEMENT SUBBASE COURSE AGGREGATE AND AGGREGATE FOR SUBGRADE REPAIR AREAS SHALL BE SUITABLE FOR USE AS STRUCTURAL FILL AND BE PROOF ROLLED AND COMPACTED TO 95% MODIFIED PROCTOR MAXIMUM DRY DENSITY.
  8. THE EXPOSED SOIL SUBGRADE SHOULD BE PROOF ROLLED PRIOR TO THE PLACEMENT OF SUBBASE GRAVEL, AND SOFT AREAS SHOULD BE REPAIRED AND REPLACED.
  9. ALL PARKING SPACES SHALL BE STANDARD DUTY. ALL OTHER LOCATIONS SHALL BE HEAVY DUTY.

**PAVEMENT SECTIONS**  
NOT TO SCALE

**SITE DEVELOPMENT PLANS**

TAX MAP 256 LOT 2  
**DETAILS**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**  
 OWNED BY  
**WALTER D HETT TRUST**  
 PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**

SCALE: NTS SEPTEMBER 25, 2019




REV	DATE	DESCRIPTION	DR	CK
4	3/20/2020	PROGRESS PRINT	RCK	JJM
3	3/4/2020	UPDATE PLANS PER REGULATORY COMMENTS	RCK	JJM
2	12/27/2019	IN HOUSE REVISIONS	RCK	JJM
1	12/23/19	NO REVISIONS THIS SHEET	RCK	JJM

**TFM** Civil Engineers  
 Structural Engineers  
 Traffic Engineers  
 Land Surveyors  
 Landscape Architects  
 Scientists

48 Constitution Drive  
 Bedford, NH 03110  
 Phone (603) 472-4488  
 Fax (603) 472-9747  
 www.tfmoran.com

FILE 47361.00 DR RCK FB  
 CK JJM CADFILE -  
 DETAILS C-33






**NOTES**

- POUR THRUST BLOCKS AGAINST UNDISTURBED MATERIAL, WHERE TRENCH WALL HAS BEEN DISTURBED. EXCAVATE LOOSE MATERIAL AND EXTEND THRUST BLOCK TO UNDISTURBED MATERIAL. NO PIPE JOINTS SHALL BE COVERED WITH CONCRETE.
- ON BENDS AND TEES, EXTEND THRUST BLOCKS FULL LENGTH OF FITTING.
- PLACE BOARD IN FRONT OF ALL PLUGS BEFORE POURING THRUST BLOCKS.
- WHERE MECHANICAL JOINT PIPE IS USED, MECHANICAL JOINT PLUG WITH RETAINER GLAND MAY BE SUBSTITUTED FOR END BLOCKINGS.
- INSTALLATION AND STANDARD DIMENSIONAL REQUIREMENTS SHALL BE IN ACCORDANCE WITH THE CITY/TOWN ESTABLISHED RULES AND PROCEDURES.

REACTION TYPE	PIPE SIZE			
	4"	6"	8"	10"
A 90°	0.89	2.19	3.82	11.14
B 180°	0.65	1.55	2.78	8.38
C 45°	0.48	1.19	2.12	6.02
D 22-1/2°	0.25	0.60	1.06	3.08
E 11-1/4°	0.13	0.30	0.54	1.54


TEST PRESSURE = 200psi

**THRUST BLOCKS**  
NOT TO SCALE




- NOTES:**
- POLYETHYLENE PIPE WITH TRACER WIRE MAY BE USED IN LIEU OF TYPE "K" COPPER TUBING.
  - VALVE TO OPEN LEFT.

**BURIED GATE VALVE**  
NOT TO SCALE




**WATER SERVICE CONNECTION - COPPER PIPE**  
NOT TO SCALE




- NOTES:**
- ALL MATERIALS AND INSTALLATION PROCEDURES WILL CONFORM TO EXETER DPW TECHNICAL SPECIFICATIONS.
  - ALL WATER MAIN SHOULD HAVE A MINIMUM DEPTH OF 5' FROM TOP OF PIPE TO FINISH GRADE.

**TYPICAL UTILITY SEPARATION**  
NOT TO SCALE




**WATER MAIN TRENCH**  
NOT TO SCALE




**DRAIN MANHOLE**  
NOT TO SCALE

- NOTES:**
- MANHOLE FRAME & COVER: SHALL BE NEENAH R-1653A OR APPROVED EQUAL. MANHOLES SHALL MEET NHDOT SPECIFICATIONS AND SHALL HAVE THE WORD "DRAIN" STAMPED ON THE COVER.
  - ALL COMPONENTS SHALL BE DESIGNED FOR HS-20 LOADING.
  - REINFORCING SHALL CONFORM TO ASTM 185 OR ASTM 1497 & ASTM A615, GRADE 60.
  - ALL CONCRETE SHALL BE NHDOT CLASS A.
  - LARGER DIAMETER STRUCTURES SHALL BE USED AS REQUIRED DUE TO NUMBER, ANGLE OR SIZE OF PIPES AT THE STRUCTURE.
  - ALL CASTINGS SHALL BE MADE IN THE USA.




- NOTES:**
- BEDDING - BEDDING FOR PIPES SHALL CONSIST OF PREPARING THE BOTTOM OF THE TRENCH TO SUPPORT THE ENTIRE LENGTH OF THE PIPE AT A UNIFORM SLOPE AND ALIGNMENT. CRUSHED STONE SHALL BE USED TO BED THE PIPE TO THE ELEVATION SHOWN ON THE DRAWINGS. NORMAL PIPE BEDDING IS CRUSHED STONE TO THE HAUNCH OF THE PIPE AND SAND BEDDING 6" ABOVE THE CROWN. IF THE TOP OF THE PIPE IS LESS THAN 30" FROM FINISH GRADE, BED PIPE COMPLETELY IN STONE UP TO 6" ABOVE PIPE CROWN. UNDERDRAIN TO HAVE 4" MINIMUM OF STONE OVER PIPE OR AS NECESSARY TO BE IN CONTACT WITH GRAVEL LAYER OF SELECTS ABOVE.
  - COMPACTION - ALL BACKFILL SHALL BE COMPACTED AT OR NEAR OPTIMUM MOISTURE CONTENT BY PNEUMATIC TAMPERS, VIBRATORY COMPACTORS OR OTHER APPROVED MEANS. BACKFILL BENEATH PAVED SURFACES SHALL BE COMPACTED TO NOT LESS THAN 95% OF AASHTO T99, METHOD C.
  - SUITABLE MATERIAL - IN ROADS, ROAD SHOULDERS, WALKWAYS AND TRAVELED WAYS, SUITABLE MATERIAL FOR TRENCH BACKFILL SHALL BE THE NATURAL MATERIAL EXCAVATED DURING THE COURSE OF CONSTRUCTION, BUT SHALL EXCLUDE DEBRIS; PIECES OF PAVEMENT; ORGANIC MATTER; TOP SOIL; ALL WET OR SOFT MUCK, PEAT, OR CLAY; ALL EXCAVATED LEDGE MATERIAL; ROCKS OVER 6" IN LARGEST DIMENSION; FROZEN EARTH AND ANY MATERIAL WHICH, AS DETERMINED BY THE ENGINEER, WILL NOT PROVIDE SUFFICIENT SUPPORT OR MAINTAIN THE COMPLETED CONSTRUCTION IN A STABLE CONDITION.
  - BASE COURSE AND PAVEMENT - SHALL MEET THE REQUIREMENT OF THE NHDOT LATEST EDITION OF THE STANDARD SPECIFICATIONS FOR HIGHWAYS AND BRIDGES DIVISION 300 AND 400 RESPECTIVELY.

**TRENCH FOR DRAIN LINE**  
NOT TO SCALE



- NOTES:**
- CLASS III CONCRETE SHALL BE 4,500 PSI AFTER 28 DAYS.
  - DESIGN LOAD: H-20 LOADING
  - GRADE 60 REINFORCED NO. 4 STEEL REBAR TO CONFORM TO ASTM A-615 ON REQUIRED CENTERS OR EQUAL.
  - CAST IRON FRAME AND COVER ARE MANUFACTURED OF GREY CAST IRON CONFORMING TO ASTM A48-76 CLASS 30.


**CURB INLET**  
NOT TO SCALE



THREE-WAY HYDRANT KENNEDY K-81A  
GUARDIAN  
ELMIRA, N.Y.


- SPECIFICATIONS**
- 150 PSI WORKING PRESSURE
  - 300 PSI TEST PRESSURE
  - HYDRANT DRAIN SHALL BE PLUGGED
  - DRY TOP DESIGN VALVE SHALL OPEN WHEN OPERATING NUT IS TURNED CLOCKWISE AND BE SO INDICATED ON HYDRANT
  - OPERATING NUT SHALL BE STANDARD AWWA PENTAGON OPERATING NUT WITH 1 1/2" POINT TO FLAT DIMENSION
  - THREADS SHALL BE NATIONAL STANDARD HOSE THREAD NOZZLES

**PORTSMOUTH FIRE HYDRANT**  
NOT TO SCALE




- NOTES:**
- ELECTRIC SERVICE INSTALLATION AND STANDARD DIMENSIONAL REQUIREMENTS SHALL BE IN ACCORDANCE WITH FEDERAL, STATE AND LOCAL CODES.
  - COMMUNICATION SERVICE INSTALLATION SHALL MEET ALL CONSTRUCTION REQUIREMENTS.
  - ACTUAL NUMBER OF CONDUITS TO BE DETERMINED BY RESPECTIVE COMPANIES.
  - VERIFY INSTALLATION REQUIREMENTS WITH RESPECTIVE COMPANIES.

**ELECTRIC/COMMUNICATIONS CONDUIT**  
NOT TO SCALE



- NOTES:**
- FOR MINIMUM DIMENSIONAL REQUIREMENT REFER TO THE GEOTECHNICAL REPORT PREPARED BY JOHN TURNER CONSULTING, INC. ON JULY 3, 2013.

**FOUNDATION DRAIN LINES**  
NOT TO SCALE




- NOTES:**
- ALL SECTIONS SHALL BE PRECAST CONCRETE NHDOT CLASS AA, 4,000 PSI.
  - CATCH BASINS SHALL MEET NHDOT SPECIFICATIONS.
  - ALL COMPONENTS SHALL BE DESIGNED FOR HS-20 LOADING.
  - LARGER DIAMETER STRUCTURES SHALL BE USED AS REQUIRED DUE TO NUMBER, ANGLE OR SIZE OF PIPES AT THE STRUCTURE.
  - ALL CASTINGS SHALL BE MADE IN THE USA.

**ECCENTRIC CATCH BASIN WITH HOODED OUTLET**  
NOT TO SCALE

REV	DATE	DESCRIPTION	DR	CK
4	3/20/2020	PROGRESS PRINT	RCK	JJM
3	3/4/2020	UPDATE PLANS PER REGULATORY COMMENTS	RCK	JJM
2	12/27/2019	IN HOUSE REVISIONS	RCK	JJM
1	12/23/19	NO REVISIONS THIS SHEET	RCK	JJM

**SITE DEVELOPMENT PLANS**  
TAX MAP 256 LOT 2  
**DETAILS**  
**THE VILLAGE AT BANFIELD WOODS**  
PORTSMOUTH, NH  
OWNED BY  
**WALTER D HETT TRUST**  
PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**  
SCALE: NTS  
SEPTEMBER 25, 2019




**TFM** Civil Engineers, Structural Engineers, Traffic Engineers, Land Surveyors, Landscape Architects, Scientists.  
48 Constitution Drive, Bedford, NH 03110, Phone (603) 472-4488, Fax (603) 472-9747, www.tfmoran.com  
47361.00 DR RCK FB, CK JUM CADFILE, DETAILS, C-34

Mar 23, 2020 - 4:47pm F:\MISC Projects\47361 - Portsmouth\47361-00 - Green & Co - Banfield Road\Design\Production Drawings\Details.dwg

Copyright 2019 © Thomas F. Moran, Inc. 48 Constitution Drive, Bedford, N.H. 03110. All rights reserved. This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.



Mar 23, 2020 - 4:47pm F:\MISC Projects\47361 - Green & Co - Banfield Road\Design\Production Drawings\Details.dwg







ELEVATIONS			
OUTLET STRUCTURE	#1	#3 AND #4	
A	34.50	37.60	
B	33.50	NA	
C	NA	35.85 (1")	
D	33.25	32.50	

NOTE: SEE GRADING AND DRAINAGE PLAN FOR RIM ELEVATIONS, INVERTS IN AND INVERTS OUT.


- HDPE IMPERMEABLE LINER NOTE:**
- HDPE LINER TO BE INSTALLED PER MANUFACTURES SPECIFICATIONS
  - SEAMS SHALL BE FUSION WELDED OR EXTRUSION WELDED.
  - FUSION WELD:
    - THE SEAM SHALL BE PRODUCED BY SELF PROPELLED WEDGE WELDING APPARATUS. THE MEMBRANE SHALL HAVE AN OVERLAP OF APPROXIMATELY 150MM (6.0 INCHES). THE AREA SHALL BE PREPARED BY WIPING THE AREA WITH A CLEAN DRY CLOTH TO REMOVE ANY FOREIGN MATTER.
  - EXTRUSION WELD:
    - THE SEAM SHALL BE PRODUCED BY EXTRUDING MOLTEN RESIN AT THE EDGE OF TWO OVERLAPPED SHEETS OF GEOMEMBRANE TO AFFECT A HOMOGENEOUS BOND. THE WELD AREA SHALL BE PREPARED BY SANDING OR GRINDING TO A DEPTH OF LESS THAN .02 MM IN THE SHEET SURFACE TO BE IN CONTACT WITH THE EXTRUDATE. GRINDING REQUIRED ALONG A SEAM SHALL BE DONE CONCURRENT WITH OR WITHIN TWENTY MINUTES OF THE SEAMING OPERATION AND SHALL NOT DAMAGE THE GEOMEMBRANE. MEMBRANE SHALL BE OVERLAPPED A MINIMUM OF 75 MM (3.0 INCHES) PRIOR TO SEAMING. THE WELD AREA SHALL BE KEPT CLEAN AND DRY DURING THIS PROCESS.
  - SEAMS TO BE TESTED IN ACCORDANCE WITH ASTM D6392 STANDARDS

8" DIA. ADS PERFORATED SMOOTH WALL SUBDRAIN HEADER PIPE TO CONNECT TO AN 8" DIA. SMOOTH WALL THAT WILL CONVEY SEEPAGE TO POINT OF DISCHARGE: USE STANDARD MIRADRAIN CONNECTIONS

END VIEW OF PIPE/FABRIC CONNECTION. CUT AN "X" IN THE FABRIC SLIGHTLY LARGER THAN PIPE. PULL THE FABRIC AROUND THE PIPE TO CREATE THE "BOOT" AND THEN SECURE WITH A HOSE-CLAMP.



NOTE: CUT FABRIC AND WRAP AROUND PIPE SO THAT PIPE BUTTS DIRECTLY AGAINST ACF R-TANK PIPE EFFLUENT SHALL NOT PASS THROUGH FABRIC



GEOMETRY: LENGTH = 28.15 IN. (715 MM)  
 WIDTH = 18.75 IN. (475 MM)  
 HEIGHT = 23.85 IN. (605 MM)  
 TANK VOLUME = 8.65 CF  
 VOID INTERNAL VOLUME: 65%  
 VOID SURFACE AREA: 95%

LOAD RATING: 33.4 PSF (MODULE ONLY)  
 HS25 (WITH ACF COVER SYSTEM)

MATERIAL: 100% RECYCLED POLYPROPYLENE


SMALL PLATES PER SEGMENT TOTAL: 9/10

**R-TANK<sup>HD</sup> - DOUBLE MODULE**

FOR ADDITIONAL INFORMATION PLEASE CONTACT: ACF ENVIRONMENTAL, 1-800-446-3636, www.acfenvironmental.com 5/18


**R-TANK<sup>SD</sup> TYPICAL TANK INLET/OUTLET DETAIL**  
NOT TO SCALE

**FABRIC PIPE BOOT FOR R-TANK<sup>HD</sup>**  
NOT TO SCALE




NOTE: 1. SEE DRAINAGE PLAN FOR LOCATIONS AND ELEVATIONS

**MAINTENANCE PORT**  
PORT USED FOR INSPECTION PURPOSES AND FOR SYSTEM MAINTENANCE AS REQUIRED. WATER SHALL BE PUMPED INTO THE SYSTEM AND RESUSPEND ACCUMULATED SEDIMENT. MINIMUM REQUIRED MAINTENANCE INCLUDES A QUARTERLY INSPECTION FOR THE FIRST YEAR OF OPERATION AND A YEARLY INSPECTION THEREAFTER FLUSH AS NEEDED.



**MAINTENANCE PORT**  
NOT TO SCALE

Copyright 2019 © Thomas F. Moran, Inc.  
 48 Constitution Drive, Bedford, N.H. 03110  
 All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.  
 This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.



REV.	DATE	DESCRIPTION	DR	CK
4	3/20/2020	PROGRESS PRINT	RCK	JJM
3	3/4/2020	UPDATE PLANS PER REGULATORY COMMENTS	RCK	JJM
2	12/27/2019	IN HOUSE REVISIONS	RCK	JJM
1	12/23/19	NO REVISIONS THIS SHEET	RCK	JJM

**SITE DEVELOPMENT PLANS**

TAX MAP 256 LOT 2

**DETAILS**

**THE VILLAGE AT BANFIELD WOODS**  
PORTSMOUTH, NH

OWNED BY  
**WALTER D HETT TRUST**

PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**


SCALE: NTS SEPTEMBER 25, 2019

Civil Engineers  
Structural Engineers  
Traffic Engineers  
Land Surveyors  
Landscape Architects  
Scientists

48 Constitution Drive  
Bedford, NH 03110  
Phone (603) 472-4488  
Fax (603) 472-9747  
www.tfmoran.com


C-35

47361.00	DR RCK	FB	-	
	CK JJM	CADFILE	DETAILS	




**ROADWAY TYPICAL SECTION**  
NOT TO SCALE


- NOTES:**
- SEE GRADING & DRAINAGE PLAN FOR PAVEMENT SLOPE AND CROSS-SLOPE.
  - PROVIDE CLEAN BUTT TO EXISTING PAVEMENT- USE TACK COAT SPECIFICALLY, A TACK COAT SHALL BE PLACED ATOP THE BINDER COURSE PAVEMENT PRIOR TO PLACING THE WEARING COURSE.
  - REMOVE ALL LOAM AND/OR YIELDING MATERIAL BELOW PAVEMENT.
  - ALL ROADWAY TO CONFORM TO THE STREET DESIGN AND CONSTRUCTION REQUIREMENTS IN THE TOWN OF PORTSMOUTH, NH SUBDIVISION REGULATIONS.
  - BITUMINOUS CONCRETE SHALL BE COMPACTED TO AT LEAST 92.5% OF THEORETICAL MAXIMUM DENSITY AS DETERMINED BY ASTM D2041 OR AASHTO T209. PLACEMENT TEMPERATURES OF BITUMINOUS CONCRETE MIXES, IN GENERAL, RANGE BETWEEN 270 AND 310 DEGREES FAHRENHEIT.
  - PAVEMENT BASE COURSE AGGREGATE SHALL CONFORM TO NHDOT SPECIFICATION SECTION 304, ITEM 304.4 AND COMPACTED TO A MINIMUM OF 95% OF MODIFIED PROCTOR MAXIMUM DRY DENSITY.
  - PAVEMENT SUBBASE COURSE AGGREGATE AND AGGREGATE FOR SUBGRADE REPAIR AREAS SHALL BE SUITABLE FOR USE AS STRUCTURAL FILL AND BE PROOF ROLLED AND COMPACTED TO 95% MODIFIED PROCTOR MAXIMUM DRY DENSITY.
  - THE EXPOSED SOIL SUBGRADE SHOULD BE PROOF ROLLED PRIOR TO THE PLACEMENT OF SUBBASE GRAVEL, AND SOFT AREAS SHOULD BE REPAIRED AND REPLACED.



**RETAINING WALL TYPICAL SECTION**  
NOT TO SCALE



**SLOPE STABILIZATION ADJACENT TO WETLANDS**  
FOR EROSION CONTROL  
NOT TO SCALE



**SITE DEVELOPMENT PLANS**

TAX MAP 256 LOT 2  
**DETAILS**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**  
OWNED BY  
**WALTER D HETT TRUST**  
PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**

SCALE: NTS

SEPTEMBER 25, 2019

REV	DATE	DESCRIPTION	DR	CK
4	3/20/2020	PROGRESS PRINT	RCK	JJM
3	3/4/2020	UPDATE PLANS PER REGULATORY COMMENTS	RCK	JJM
2	12/27/2019	IN HOUSE REVISIONS	RCK	JJM
1	12/23/19	NO REVISIONS THIS SHEET	RCK	JJM

**TFM** Civil Engineers  
Structural Engineers  
Traffic Engineers  
Land Surveyors  
Landscape Architects  
Scientists


48 Constitution Drive  
Bedford, NH 03110  
Phone (603) 472-4488  
Fax (603) 472-9747  
www.tfmoran.com

FILE: 47361.00  
DR: RCK  
CK: JJM  
FB: CADFILE  
DETAILS  
C-36


Mar 23, 2020 - 4:47pm F:\MSC Projects\47361 - Banfield Road - Portsmouth\47361-00 - Green & Co - Banfield Road\Design\Production Drawings\Details.dwg

Copyright 2019 © Thomas F. Moran, Inc.  
48 Constitution Drive, Bedford, N.H. 03110  
All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.  
This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.







**TL-2 EAGRT UNIT**  
**PREFERRED PLATFORM FOR OFFSET ENERGY ABSORBING**  
**GUARDRAIL TERMINAL (EAGRT)**  
 NOT TO SCALE



SECTION A-A  
 PLATFORM SLOPE GRADING



SECTION B-B  
 PLATFORM APPROACH GRADING



ELEVATION TABLE			
	BIORETENTION #1	BIORETENTION #2	BIORETENTION #3
A	56.00	46.00	43.50
B	54.50	44.50	42.00
C	53.17	43.17	41.67
D	57.50	47.75	45.25
E	58.00	48.50	46.00
F	58.10 (Road)	48.00	45.00
G	53.20 (0.2")	43.25 (3")	42.75 (0.5")

**BIORETENTION SYSTEM MAINTENANCE**

MAINTENANCE SCHEDULE TO BEGIN AFTER CONSTRUCTION IS FINISHED AND BASIN STABILIZATION IS COMPLETE.

- CONTRACTOR AND LAND OWNERS TO PERFORM SCHEDULED MAINTENANCE ON THE BIORETENTION SYSTEM IN ACCORDANCE WITH THE STORMWATER OPERATION AND MAINTENANCE MANUAL.

**BIORETENTION DETAIL**

NOT TO SCALE

NOTE: SEE PLANS FOR BED, BERM AND OVERFLOW ELEVATIONS


**SEEDING**

- USE NEW ENGLAND EROSION CONTROL/RESTORATION MIX FOR MOIST SITES BY NEW ENGLAND WETLAND PLANTS, INC. OR EQUIVALENT.
- SEED AT A RATE OF 1LB/1250SF. APPLY TO BARE SOIL. LIGHTLY MULCH WITH CLEAN WEED FREE STRAW.

**BIORETENTION SYSTEM CONSTRUCTION**

- CLEAR AND GRUB THE AREA WHERE THE BIORETENTION SYSTEMS ARE TO BE LOCATED. STOCKPILE LOAM FOR REUSE ON SLOPES.
- GRADE BIORETENTION SYSTEM ACCORDING TO PLAN AND DETAILS. SIDE SLOPES SHALL HAVE 6" LOAM AND SEED AND A SLOPE NOT TO EXCEED 3:1. BOTTOM OF BIORETENTION SYSTEM AREAS TO BE CONSTRUCTED WITH MANUFACTURED SOIL (SEE BIORETENTION SYSTEM CONSTRUCTION DETAIL).
- BOTTOM OF THE BIORETENTION SYSTEM TO BE SEEDED WITH NEW ENGLAND EROSION CONTROL/RESTORATION MIX THAT MEETS NH STATE STANDARDS.
- SOIL SPECIFICATION TO CONFORM TO THE LATEST UNH STORMWATER CENTER BIORETENTION SOIL SPECIFICATIONS. A COPY OF THE 2017 UNHSC BIORETENTION SPECIFICATION ARE INCLUDED IN THE STORMWATER OPERATION AND MAINTENANCE MANUAL.
- THE CONTRACTOR SHALL TAKE MEASURES TO PREVENT EQUIPMENT & VEHICLE TRAFFIC FROM DRIVING IN THE AREA OF THE PROPOSED BIORETENTION SYSTEM AREA DURING CONSTRUCTION.

**BIORETENTION SYSTEM**  
 NOT TO SCALE



**HYBRID BIORETENTION SYSTEM STRUCTURE**  
**BIORETENTION SYSTEMS #2 AND #3**

**SITE DEVELOPMENT PLANS**


TAX MAP 256 LOT 2

**DETAILS**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**

OWNED BY  
**WALTER D HETT TRUST**  
 PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**

SCALE: NTS

SEPTEMBER 25, 2019



REV	DATE	DESCRIPTION	DR	CK
4	3/20/2020	PROGRESS PRINT	RCK	JJM
3	3/4/2020	UPDATE PLANS PER REGULATORY COMMENTS	RCK	JJM
2	12/27/2019	IN HOUSE REVISIONS	RCK	JJM
1	12/23/19	NO REVISIONS THIS SHEET	RCK	JJM

**TFM** Civil Engineers  
 Structural Engineers  
 Traffic Engineers  
 Land Surveyors  
 Landscape Architects  
 Scientists

48 Constitution Drive  
 Bedford, NH 03110  
 Phone (603) 472-4488  
 Fax (603) 472-9747  
 www.tfmoran.com

47361.00 DR RCK FB  
 CK JJM CADFILE  
 DETAILS

C-37

Mar 23, 2020 - 4:47pm  
 F:\MISC Projects\47361 - Green & Co - Banfield Road\Design\Production Drawings\Details.dwg

Copyright 2019 © Thomas F. Moran, Inc.  
 48 Constitution Drive, Bedford, N.H. 03110  
 All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.  
 This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.





*Memorandum*

Date: Friday, February 28, 2020  
To: Peter Britz, Environmental Planner  
Org: Portsmouth Planning Department, 1 Junkins Avenue, Portsmouth, NH 03801  
From: Jim Gove  
Re: Banfield Road Project for Green and Company  
Subject: Response to Mark West Review of January 28, 2020 and questions related to Wildlife corridors as related to the site

The review points out that the Nature Conservancy shows the site in question as part of a prioritized habitat block and wildlife corridor. The GES, Inc. reports have identified the presence of wildlife corridors on the site of which there are many both on and off the site as summarized below.

As noted by the review, GES, Inc. identified the access road to the site as potentially limiting wildlife movement along that specific corridor. What has not been recognized is that numerous wildlife corridors exist over the entire site and the lands beyond. GES, Inc. has attached a plan showing the site and the surrounding areas. The plan is named "Upland/Wetland Habitat Map". The base map is an infrared aerial photo with the wetlands boundaries (outside of the site) being interpreted and the wetlands shown colored in green and the wildlife corridors have been shown as black arrows.

There are numerous wildlife corridors on and off the site. Wildlife movement is not confined to just the areas of the development but are present around the site and in adjacent parcels. Most movement is along drainage ways, valleys, edges of wetlands, and along any streams. Wildlife also moves along man-made corridors, like railroad tracks and electric powerlines. Less movement is over the tops of hills, rock outcrops, and steep areas. The wildlife has many ways to move around the area, and move around the proposed development.

Of the numerous wildlife corridors shown, only two would be limited by the development.

- a. The first is at the wetland impact area along Banfield Road. In the West review, there was a concern that the proposed eco-passage was built with less height than recommended. The recommendation for the eco-passages is 2 feet high, with an opening of 2 feet wide. In redesigning this area, the eco-passages have been changed in the design, and are now proposed to have heights of 1.9 feet, 2.0 feet, and 2.2 feet. The openings all have a width of 5 feet which is 2.5 times larger than recommended, allowing for better wildlife passage. Where typically only one eco-passage is used, the project is proposing three eco-passages. The eco-passages now meet or exceed the recommended design. As discussed at the

8 Continental Dr Bldg 2 Unit H, Exeter, NH 03833-7526

Ph (603) 778 0644 / Fax (603) 778 0654

*www.gesinc.biz*

*info@gesinc.biz*



Conservation Commission meeting, these eco-passages are to help reptile and amphibian species to continue to move in the wetland. Also, the height of the access road across the wetlands is from 1.4 feet tall to 2.7 feet tall. This height of road will not be an impediment to deer, fox, coyote, raccoon, skunk, weasel, fisher, squirrel and chipmunk. There will continue to be wildlife movement through this corridor.

- b. The second is a valley between the two lobes of the development. The West review noted that the large retaining walls connecting the two development areas will permanently impact wildlife movement because the walls were up to 10 feet high and West recommended the elimination of the large retaining walls. In redesigning this area the retaining wall for the road connecting the two development areas is now reduced to 2 feet to 3.2 feet in height. This height will not be an impediment from the movement of mammals crossing along the corridor. As discussed above, deer, fox, coyote, skunk, raccoon, fisher, weasel, squirrel, or chipmunk will not find a 2-foot retaining wall an impediment to crossing through the valley between the two wetland areas. Further, the retaining wall is only on the north side of the proposed road, with the south side having no retaining wall.

These modifications clearly show that the Applicant has significantly minimized these impacts to these 2 travel corridors.

Another important point to note is that there has been discussion about the development area being the only upland on site, and that it is the only island of upland habitat in the area and is surrounded by wetlands. The Upland/Wetland Habitat Map shows that this is in fact not the case. To the south, west and north of the development site are large areas of uplands. Going west from the development envelope is an uninterrupted continuous tract of upland habitat. To the south, after crossing a wetland, is another tract of upland. To the north, after crossing a wetland, is another tract of uplands.

On the site, of the 44.8 acres making up the subject property, 19.34 acres is wetlands and 25.46 acres of upland, with only 7.3 acres of upland and 0.09 acres of wetland for the crossing being used for the development area. This means that on the site, outside of the development envelope, is 18.2 acres of upland, which means approximately 40% of the 44.88 acre site will remain as undeveloped upland and approximately 83% of the 44.8 acre site will remain undeveloped overall.

In the West review, a recommendation was to provide information as to how the open space area will be managed and protected from future impact. The following is adapted from the Open Space restrictions of a condominium project in Atkinson:

The Open Space as depicted on the plans, is and shall forever be and remain subject to the following deed restrictions:



- 1) The purpose of the Open Space after completion of the proposed development depicted on the site plan is to retain the area forever in its scenic and open space conditions and to prevent any use of the Open Space that will significantly impair, or interfere with, its conservation value.
- 2) To protect and conserve the natural biological diversity of the region including exemplary natural communities, wetlands and other significant wildlife habitats on the restricted property.
- 3) It shall be maintained in perpetuity as open space.
- 4) No structure of any kind, size or shape shall be constructed on the Open Space.
- 5) Upon completion of the proposed development, no filling or excavation of soil or other alteration of topography or cutting or removal of standing trees shall be allowed, except those that present an imminent threat to person or property. In addition, trees may be removed in accordance with accepted silvicultural forest practices as outlined in the publication entitled **Good Forestry Practices in the Granite State** by the Society for the Protection of NH Forests. No disturbance of other natural features shall be allowed unless such activities are commonly necessary to maintain the existing natural environment of the open space.
- 6) There shall be no dumping or depositing of trash, debris, stumps, yard waste, hazardous fluid or materials, vehicle bodies or parts within the Open Space.

There has been discussion that there may be an alternative access to the site via an abutting parcel of land. The abutting parcel is not owned by the project and it --was found not to be available to the project. In addition, the abutting property -- would also require a longer wetland crossing to access uplands. This is not a feasible access because it is not the least impacting alternative and is not owned by the project. Therefore, the proposed access road at the location depicted on Banfield Road is the least impacting alternative.

Copy to:

NH DES Wetlands Bureau Application# 2020-0344.  
Amended plans of eco-passages.

Attachments:

- 1) West Environmental Inc. letter of 01-28-2020
- 2) Upland/Wetland Habitat Plan
- 3) Eco-passage cross-section
- 4) RetainWall cross-section



THIS PAGE IS INTENTIONALLY BLANK

Peter Britz, Environmental Planner  
Portsmouth Planning Department  
1 Junkins Avenue  
Portsmouth, NH 03801

January 28, 2020

**RE: Third Review of Banfield Road Project Green and Company Portsmouth**

Dear Peter:

West Environmental, Inc. (WEI) submits this third review report of the above referenced project based on information presented by the applicant at the December 11, 2019. Some of the new information presented addressed issues raised in our report from December 10, 2019 but no formal response to the report was submitted.

**2019 Wildlife Habitat Assessment**

As discussed in our 12-10-19 report the revised Wildlife Habitat Assessment (WHA) provides more information on wildlife habitat and the species that likely utilize this site. We have attached the Connect the Coast Map prepared by the Nature Conservancy indicating that the Hett parcel to be developed is within a Prioritized Habitat Block. In addition, this map confirms that wildlife movement is in an east-west direction.

WEI agrees with the statement "*The greatest issue with this development is the bisecting of the site with the proposed road, limiting any existing and potential wildlife travel.*" The reports from Gove Environmental indicate that development itself and the large retaining walls in the stretch of road connecting the two development areas **will permanently impact wildlife movement on the site**. The applicant's consultants presented information regarding the retaining walls (up to 10 feet high) and the proposed 4'x4' box culvert. While we understand that this design eliminated impacts to the wetland buffers the road itself now has a greater impact to wildlife movement.

The eco-passage located at the wetland crossing was also presented at the Conservation Commission Meeting to help reptile and amphibian species continue to move through the wetland. It is proposed to be built with less height than is recommended which may reduce its effectiveness to promote passage. WEI recommended consultation with the NH Fish and Game and we have reviewed email correspondence with Kim Tuttle.


She indicated that the design was interesting and had some basic recommendations but did not endorse the design. She also referred the applicant to Sandi Houghton at her office.

It is our understanding that the hydrology and septic designs are being independently reviewed.

**Recommendations:**

1. The applicant's consultants should examine alternative stormwater management designs that eliminate the large retaining walls in the under-road detention option and distribute the treatment systems into smaller watersheds. Some impact in the outer 25 feet of the 100-foot wetland buffer for smaller detention/treatment systems would have less impact on wildlife. These areas could also be planted with shrub buffers on their outer slopes to minimize habitat impact. There are also areas outside the 100-foot buffers where rain gardens could be located.
2. The applicant's consultants should continue to research the eco-passages to verify that they will function with an altered design.
3. The applicant should provide information as to how the open space area will be managed and protected from future impact. This element of the project is the most important mitigation for wildlife habitat impacts and it will require signage and other permanent restrictions.

Sincerely,  
West Environmental, Inc.




Mark C. West,  
NH Certified Wetland Scientist

Cc: Vicky Nelson

# Upland Wetland Habitat Map

Prepared By: Gove Environmental Services, Inc.  
Date: 2/27/2020  
BW 1 Inch = 400 Feet




Approximate Wetland ■

Approximate Development Envelope ■

Potential Wildlife Corridors ↔

THIS PAGE IS INTENTIONALLY BLANK



**TFM**

PROJECT	47361.00	DR	CK	FB	CADFILE
---------	----------	----	----	----	---------

Civil Engineers Structural  
 Engineers Traffic  
 Engineers Land Surveyors  
 Landscape Architects  
 Scientists

170 Commerce Way, Suite  
 102 Portsmouth, NH 03801  
 Phone (603) 431-2222  
 Fax (603) 431-0910  
 www.TFMoran.com


TAX MAP 256 LOT2  
**ECOPASSAGES**  
**PROFILE**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NEW HAMPSHIRE**  
 OWNED BY  
**GREEN & COMPANY REAL ESTATE**

**SCALE: H:1"=30' / V:1"=3'**      **DATE: 2/20/20**

REV.	DATE

**C-1**






PROJECT NO.	47361.00	DR	FB
		CK	CADFILE

Civil Engineers Structural  
 Engineers Traffic  
 Engineers Land Surveyors  
 Landscape Architects  
 Scientists

170 Commerce Way, Suite  
 102 Portsmouth, NH 03801  
 Phone (603) 431-2222  
 Fax (603) 431-0910  
 www.TFMoran.com

TAX MAP 256 LOT2  
**RETAINING WALL AREA**  
**PROFILE**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NEW HAMPSHIRE**  
 OWNED BY  
**GREEN & COMPANY REAL ESTATE**

**SCALE: H:1"=30' / V:1"=3'**      **DATE: 2/20/20**

REV.	DATE

**C-2**

Feb 27, 2020 - 10:38am  
 F:\MSC-Projects\47361 - Banfield Road - Portsmouth\47361-00 - Green & Co - Banfield Road\Design\Production Drawings\XREF\47361-00\_3D.dwg

John Kuzinevich, Esq.  
Law Office of John Kuzinevich

71 Gurnet Road  
Duxbury, Massachusetts 02332

Telephone: 781 536-8835  
Cell: 508 245-2105

E-mail: jjkuz@comcast.net

January 15, 2020

Juliet Walker  
Planning Director  
City Hall  
One Junkins Avenue  
Portsmouth, NH 03801

Re: Proposed Subdivision, 0 Banfield Road, Portsmouth  
Tax Map 256, Lot 2

Interpretation of Zoning Ordinance

Dear Juliet:

As you are aware I represent Green & Company ("Applicant") concerning the Village at Banfield Woods, a proposed subdivision located at 0 Banfield Road, Portsmouth. This letter will address whether or not townhomes may be constructed as a matter of right in the SRA district when a Planned Unit Development is designed. At the formal TAC meeting of January 7, 2020, Corey Colwell, one of the engineers representing the Applicant, stated that townhomes were not considered because they are prohibited in SRA districts. You then indicated he was incorrect and that they were allowed in all PUDs, presumably under authority of 10.722.10 (c). As a matter of law you are incorrect and townhouses are prohibited in the SRA district.

I acknowledge that the Planning Department probably thought townhomes would be available in all PUDs and has interpreted the Ordinance in that manner. However, first and foremost an ordinance is interpreted by its written words; not the interpretation of the enforcing agency. *Appeal of Fournier*, No. 2018-0617 ( N.H. Nov. 14, 2019). Ordinances and regulations are construed in the same manner as statutes. *Petition of Parker*, 158 N.H. 499, 502 (2009). Here, application of the statutory rules of construction yields no other conclusion but that townhomes are prohibited in the SRA district. Follows is my analysis.

All words of an ordinance are to be given meaning and reconciled to a meaningful whole. *In re: Portsmouth Regional Hospital*, 148 N.H. 55 (2002); *Town of Wolfeboro v. Smith*, 131 N.H. 449 (1989). Here, the use table, Section 10.440 (page 4-7) unambiguously shows under line 1.40 that townhouses are prohibited in the SRA district. This must be given meaning. Section 10.712.50 provides "a development authorized...under this Article shall comply with all applicable zoning, site plan and subdivision regulations other than those waived or modified hereunder." Nowhere in Article 7 are the uses

established by Section 10.440 waived or modified. Thus, in order to comply with the Ordinance, townhomes must be prohibited. To argue that Article 7 supersedes the uses established by 10.440 means a residential PUD could be placed in any district including GA/MH, GB, WB, OR, I or WI. This would be a nonsensical construction which would vitiate the very concept of zoning. An ordinance cannot be read out of existence by an agency's interpretation. *Appeal of Morrissey*, 165 N.H. 87, 96-97 (2013). Rather, townhomes would be permitted in the 10 districts in which they are already allowed, thus giving effect to the zoning provisions as mandated by 10.712.50. This is the only construction which prevents conflict or ambiguity.


Section 10.722.10 (c) does not alter this. First it does not expressly say that it supersedes the use table. Second, it says a PUD "may" include various uses including townhomes. May is a word of permission indicating discretion to either perform or not perform an act. *Appeal of New Hampshire Division of State Police*, 171 N.H. 262 (2018). Thus, there is no requirement that the specific use be available in all districts. Had that been the intent the ordinance, it would have needed to use the word "shall" and an appropriate modifier such as, if desired. Shall is a mandatory word which would clearly show an intent to modify the established uses, as in shall allow. *City of Rochester v. Corpening*, 153 N.H. 383 (2006). Thus in a SRA district, a PUD would have only single family homes. In other residential districts, there could be townhomes if desired as they are already an allowed use.

This interpretation is confirmed by 10.722.30 which specifically ties accessory uses to those permitted in each specific district. It further goes on to specifically exclude certain accessory uses, clearly evidencing when it is superseding the use table. It did not resort to this type of construction concerning townhouses in the SRA district although the drafters clearly know how to do it if that was the desired outcome. Likewise, in 10.723 density is determined by reference to the density in each specific district. It further shows that the district's are treated separately as when a project is in two districts, the density allowed in each district is calculated separately. This shows that the individual requirements of each district cannot be ignored.

Further, as a rule of construction use of a word in one section and use of a different word in another section indicates a different meaning to each. *State v. Bankunczyk*, 164 N.H. 77 (2012). The word "shall" is used in many sections of the ordinance. This indicates that the drafters meant something different when the word "may" is used. In this case it reinforces the permissive nature of the word and that townhomes do not have to be allowed in all districts.

For all of the above reasons, as a matter of law, townhomes are not permitted in a SRA district. I would be happy to discuss this further with you or City Attorney Sullivan. Thank you.

Sincerely,



John Kuzinevich

Copy to: City Attorney Sullivan  
Clients

February 28, 2020  
Project No. 6535-20

Green and Company Real Estate  
c/o: Mr. Jack McTigue, PE, CPESC  
Project Manager  
TF Moran, Inc. (TFM)  
170 Commerce Way, Suite 102  
Portsmouth, New Hampshire 03801

RE: Proposed Stormwater Treatment System Assessment  
The Village at Banfield Woods  
Banfield Road  
Portsmouth, New Hampshire

Dear jack:

As requested, Milone & MacBroom, Inc. (MMI) has reviewed your design drawings and data to evaluate the proposed Stormwater Treatment Systems #1 and #2 (System) to be located under the entrance road to the residential development project off of Banfield Road. As part of this evaluation, we have also reviewed your previous test pit subsurface exploration data in order to develop an approximate hydrogeologic model.

The proposed System is shown on TFM Sheet C-09 with latest revision date of January 28, 2020. The System collectively will consist of four individual systems; the two smaller systems to the south are about 42± feet by 14.5± feet in plan and the larger two systems to the north are about 51± feet by 14.5± feet in plan. In the east-west direction, the systems are separated by about 10± feet and by about 10± feet to 15± feet in the north-south direction as shown on Sheet C-09. A wetland area is located about 100± feet south and east of the proposed System.

MMI understands that the proposed System will consist of modular R-Tank system components that will be directly underlain by a 1 foot filtration layer below which will in turn be underlain by a 1 foot crushed stone layer with perforated piping to collect and convey infiltration from the system to a dedicated catch basin. This combined system will be enveloped on the sides and bottom by high density polyethylene (HDPE) membrane in order to contain the stormwater and force it through the infiltration media below the R-Tank system components. In order to prevent groundwater intrusion from impacting upon the HDPE enveloped R-Tank system, filtration layer and underlying crushed stone, a dedicated subdrainage system below and along the sides of the HDPE will be required.

Subsurface data at test pits TP-1, TP-100, TP-5084 and TP-5085, which are proximate to the proposed System, indicate a seasonal high water table varying from about 24± inches to 30±

inches below ground surface (bgs). Additionally, top of bedrock was identified in these test pits to vary from about 24± inches to 54± inches bgs.

Based on our review of Sheet C-09, the System will be located within a general topographic high of bedrock. The access road over the proposed System will require cuts varying from about 2± feet to 17± feet, and the bottom of the System will be up to about 29± feet bgs. Most of these cuts will be into bedrock that will require drilling and blasting.

Review of available USGS geologic publications indicates that bedrock at the development site is mapped as consisting of a blastomylonitic quartz-feldspar granitic gneiss and pegmatite intruded into the Rye Complex of the Breakfast Hill Granite of Novotny. Groundwater migration will be through existing joint sets and fractures, as well as new fractures caused by blasting operations. We have estimated the average hydraulic conductivity,  $k$ , of this fractured igneous rock formation to be on the order of  $3 \times 10^{-4}$  meters per second (m/sec) based on review of representative values presented by Domenico and Schwartz 1990 (an excerpt from their work is attached).

We have modeled this system using a partially penetrating "slot". To be conservative, we take this rectangular System footprint and consider the entire System sides as a "slot" drain with ambient groundwater conditions on the system outside and drawdown conditions on the inside (i.e. within the System footprint).

We have used the methodology developed in the combined design manual entitled "Dewatering and Groundwater Control" prepared by the Army, Navy and Air Force. Refer to the attachments for further reference.

Given these parameters, we modeled the proposed system consistent with the gravity flow model (c) as provided by Figure 4-3 of the aforementioned "Dewatering and Groundwater Control" document. Conservatively we calculate the aggregate system "length" as the sum of all four sides of the overall combined system to be a 300± foot "slot" drain with the requirement that the groundwater level inside the system not rise above the bottom of the underlying composite system. Given this restriction and the measured seasonal high water table conditions, a permanent lowering of the water table inside the system footprint of about 8± feet is required.

Our calculations are attached hereto and show that the anticipated steady state outflow from the proposed dedicated subdrainage system to be constructed below the HDPE enveloped R-Tank system, filtration layer and underlying crushed stone could be as much as about 1,350± gallons per hour. The steady state flow rate would be anticipated to be somewhat lower once groundwater levels equilibrate with the future topographic changes.

In order to minimize rock excavation depths and hence costs, we recommend that the dedicated subdrainage system to be constructed below the HDPE enveloped R-Tank system, filtration layer and underlying crushed stone consist of CCW MiraDRAIN 900 composite with a bottom layer of Mirafi 140N or similar filtration geotextile. The attached cross section provides for an illustration of the recommended drainage system. Additionally, we recommend a minimum 1 foot thickness

of ¾ inch crushed stone be placed along the System sidewalls to collect and transmit seepage down to the CCW MiraDRAIN 900.

Next we evaluate the ability of the CCW MiraDRAIN 900 to pass the groundwater influx. The CCW MiraDRAIN 900 has a specified maximum hydraulic capacity of 21 gal/min-ft which exceeds the estimated unit influx rate of 4.5 gal/min-ft. Therefor the CCW MiraDRAIN 900 is adequate for this application.

The next aspect of the system is to consider the hydraulic capacity of a single 6 inch diameter perforated HDPE pipe with smooth interior surface laid at a relatively flat slope of 0.005 (i.e. 6 inches per 100 feet) to be placed along the south side of the System. This perforated HDPE pipe will be wrapped in the same Mirafi 140N geotextile as shown on the attached sketch to collect System drainage along the south side and convey it to a dedicated catch basin. Using the "conveyance factor" method as provided by the ADS, Inc. Drainage Handbook (pertinent excerpts are attached hereto), we calculate a "conveyance factor" of 6.1. The resultant volumetric flow rate able to be conveyed by the pipe is then estimated at 0.43 cfs which is much greater than the total system outflow of 1,350± gallons per hour (i.e. 0.05 cfs). These calculations are attached hereto.

Based on these analyses, the proposed HDPE enveloped R-Tank system, filtration layer and underlying crushed stone System will not be impacted by steady state groundwater flow conditions given the recommended subdrainage system as described herein.


Please do not hesitate to contact the undersigned should you have any questions or if we can be of further assistance at this time.

Very truly yours,  
MILONE & MACBROOM, INC.



Charles E. Teale, PE, LSP, LEP  
New Hampshire Regional Office manager

Attachments: TFM Sheet C-09, Test Pit Logs and Stormwater Treatment System Section  
Domenico and Schwartz 1990 Excerpts  
"Dewatering and Groundwater Control" excerpts  
CCW MiraDRAIN 9000 Information  
Proposed Subdrainage Section  
ADS Drainage Manual excerpts  
MMI Calculations



135D

538B

28

OCS-02  
SLAB TOP  
RIM 37.2  
INV. IN 28.10  
INV. OUT 28.00  
(SEE DETAILS  
FOR ORIFICES)

CB-02  
SLAB-TOP  
GRATE 34.80  
INV. OUT 31.80  
SUMP 28.80

INV=27.6  
PROPOSED  
FES #1

PC 1+75.41


135C

OCS-01  
RIM 36.96  
INV. IN 28.10  
INV. OUT 28.00  
(SEE DETAILS  
FOR ORIFICES)

CB-01  
SLAB-TOP  
GRATE 34.80  
INV. OUT 31.80  
SUMP 28.80


INV=31.5

PROPOSED  
FES #2



TEST PIT #5038: 0-4 INCHES, 10YR 3/3, FINE SANDY LOAM, GR 4-14 INCHES, 10YR 4/6, FINE SANDY LOAM, GR 14-24 INCHES, 6/4, GRAVELY FINE SANDY LOAM, 24-60 INCHES, 2.5Y 5/2, SILT LOAM, BLOCKY, CONCENTRATIONS ESHWT: 24 INCHES REFUSAL: N/A OBSERVEE	TEST PIT #5038B: 0-2 INCHES, 10YR 3/2, FINE SANDY LOAM, GR 2-14 INCHES, 10YR 5/6, FINE SANDY LOAM, GR 14-24 INCHES, 2.5Y 6/4, GRAVELY FINE SANDY FRIABLE 24-29 INCHES, 2.5Y 6/3, FINE SANDY LOAM, M 29-40 INCHES, 2.5Y 6/3, FINE SANDY LOAM, M REDOX CONCENTRATIONS ESHWT: 29 INCHES REFUSAL: 40 INCHES OB	TEST PIT #5039: 0-3 INCHES, 10YR 3/2, FINE SANDY LOAM, GR 3-24 INCHES, 2.5Y 4/6, FINE SANDY LOAM, GR ESHWT: N/A REFUSAL: 24 INCHES OBSERVEE	TEST PIT #5040: 0-3 INCHES, 10YR 3/2, FINE SANDY LOAM, GR 3-30 INCHES, 2.5Y 5/4, FINE SANDY LOAM, GR 30-38 INCHES, 2.5Y 5/6, GRAVELY FINE SANDY ESHWT: N/A REFUSAL: 38 INCHES OBSERVEE	TEST PIT #5041: 0-3 INCHES, 10YR 3/2, FINE SANDY LOAM, GR 3-20 INCHES, 10YR 4/6, FINE SANDY LOAM, GR ESHWT: N/A REFUSAL: 20 INCHES OBSERVEE	TEST PIT #5084: 0-6 INCHES, 10YR 3/2, FINE SANDY LOAM, GR 6-24 INCHES, 2.5Y 5/6, GRAVELY FINE SANDY FRIABLE 24-38 INCHES, 2.5Y 5/6, GRAVELY FINE SANDY FRIABLE, WITH 10% REDOX CONCENTRATIONS ESHWT: 24 INCHES REFUSAL: 38 INCHES OB	TEST PIT #5085: 0-4 INCHES, 10YR 3/2, FINE SANDY LOAM, GR 4-24 INCHES, 10YR 5/6, FINE SANDY LOAM, GR ESHWT: N/A REFUSAL: 24 INCHES OBSERVEE	TEST PIT #5086: 0-6 INCHES, 10YR 3/3, FINE SANDY LOAM, GR 6-24 INCHES, 2.5Y 5/6, FINE SANDY LOAM, GR 24-68 INCHES, 2.5Y 5/2, FINE SANDY LOAM, M REDOX CONCENTRATIONS ESHWT: 24 INCHES REFUSAL: N/A OBSERVEE
TEST PIT #5028: 0-2 INCHES, 10YR 3/2, FINE SANDY LOAM, GRANULAR, FRIABLE 2-4 INCHES, 10YR 3/3, FINE SANDY LOAM, GRANULAR, FRIABLE 4-36 INCHES, 10YR 4/4, FINE SANDY LOAM, GRANULAR, FRIABLE ESHWT: N/A REFUSAL: 36 INCHES OBSERVED WATER: N/A	TEST PIT # 5029: 0-2 INCHES, 10YR 3/2, FINE SANDY LOAM, GRANULAR, FRIABLE 2-8 INCHES, 10YR 4/3, GRAVELY FINE SANDY LOAM, GRANULAR, FRIABLE 8-24 INCHES, 10YR 5/4, GRAVELY FINE SANDY LOAM, GRANULAR, FRIABLE 24-40 INCHES, 2.5Y 6/4, GRAVELY FINE SANDY LOAM, GRANULAR, FRIABLE 40-44 INCHES, 2.5Y 6/4, GRAVELY FINE SANDY LOAM, GRANULAR FRIABLE, WITH 10% REDOX CONCENTRATIONS ESHWT: 40 INCHES REFUSAL: 44 INCHES OBSERVED WATER: N/A	TEST PIT #5030: 0-3 INCHES, 10YR 3/2, FINE SANDY LOAM, GRANULAR, FRIABLE 3-8 INCHES, 2.5Y 6/4, FINE SANDY LOAM, GRANULAR, FRIABLE 8-30 INCHES, 2.5Y 7/4, GRAVELY FINE SANDY LOAM, GRANULAR, FRIABLE 30-40 INCHES, 2.5Y 6/4, GRAVELY FINE SANDY LOAM, MASSIVE, FIRM, WITH 10% REDOX CONCENTRATIONS ESHWT: 30 INCHES REFUSAL: 40 INCHES OBSERVED WATER: N/A	TEST PIT #5031: 0-5 INCHES, 10YR 3/2, FINE SANDY LOAM, GRANULAR, FRIABLE 5-12 INCHES, 10YR 4/4, FINE SANDY LOAM, GRANULAR, FRIABLE 12-24 INCHES, 2.5Y 5/4, FINE SANDY LOAM, GRANULAR, FRIABLE 24-40 INCHES, 2.5Y 6/4, FINE SANDY LOAM, MASSIVE, FIRM, WITH 10% REDOX CONCENTRATIONS ESHWT: 24 INCHES REFUSAL: 40 INCHES OBSERVED WATER: N/A	TEST PIT #5032: 0-3 INCHES, 10YR 3/2, FINE SANDY LOAM, GRANULAR, FRIABLE 3-6 INCHES, 10YR 4/4, FINE SANDY LOAM, GRANULAR, FRIABLE 6-14 INCHES, 2.5Y 5/4, FINE SANDY LOAM, GRANULAR, FRIABLE 14-36 INCHES, 2.5Y 6/4, FINE SANDY LOAM, GRANULAR, FRIABLE ESHWT: N/A REFUSAL: 36 INCHES OBSERVED WATER: N/A	TEST PIT #5033: 0-2 INCHES, 10YR 3/3, FINE SANDY LOAM, GRANULAR, FRIABLE 2-15 INCHES, 10YR 5/6, FINE SANDY LOAM, GRANULAR, FRIABLE 15-23 INCHES, 2.5Y 6/4, FINE SANDY LOAM, GRANULAR, FRIABLE 23-52 INCHES, 2.5Y 4/3, FINE SANDY LOAM, MASSIVE, FIRM, WITH 30% REDOX CONCENTRATIONS ESHWT: 23 INCHES REFUSAL: N/A OBSERVED WATER: N/A		
GRANULAR, FRIABLE 4, GRANULAR, FRIABLE OBSERVED WATER: N/A	GRANULAR, FRIABLE M, GRANULAR, FRIABLE M, PLATY, FIRM, ATIONS OBSERVED WATER: N/A	GRANULAR, FRIABLE 4, GRANULAR, FRIABLE M, GRANULAR, FRIABLE M, PLATY, FIRM, ATIONS OBSERVED WATER: N/A	GRANULAR, FRIABLE 4, GRANULAR, FRIABLE M, PLATY, FIRM, ATIONS OBSERVED WATER: N/A	GRANULAR, FRIABLE 4, GRANULAR, FRIABLE M, PLATY, FIRM, ATIONS OBSERVED WATER: N/A	GRANULAR, FRIABLE 4, GRANULAR, FRIABLE M, PLATY, FIRM, ATIONS OBSERVED WATER: N/A	GRANULAR, FRIABLE M, GRANULAR, FRIABLE M, PLATY, FIRM, ATIONS OBSERVED WATER: N/A	GRANULAR, FRIABLE M, GRANULAR, FRIABLE M, PLATY, FIRM, ATIONS OBSERVED WATER: N/A





## Representative Values

---

The following tables show representative values of hydraulic conductivity for various unconsolidated sedimentary materials, sedimentary rocks and crystalline rocks (from [Domenico and Schwartz 1990](#)):

<b>Unconsolidated Sedimentary Materials</b>	
<b>Material</b>	<b>Hydraulic Conductivity (m/sec)</b>
Gravel	$3 \times 10^{-4}$ to $3 \times 10^{-2}$
Coarse sand	$9 \times 10^{-7}$ to $6 \times 10^{-3}$
Medium sand	$9 \times 10^{-7}$ to $5 \times 10^{-4}$
Fine sand	$2 \times 10^{-7}$ to $2 \times 10^{-4}$
Silt, loess	$1 \times 10^{-9}$ to $2 \times 10^{-5}$
Till	$1 \times 10^{-12}$ to $2 \times 10^{-6}$
Clay	$1 \times 10^{-11}$ to $4.7 \times 10^{-9}$
Unweathered marine clay	$8 \times 10^{-13}$ to $2 \times 10^{-9}$

<b>Sedimentary Rocks</b>	
<b>Rock Type</b>	<b>Hydraulic Conductivity (m/sec)</b>
Karst and reef limestone	$1 \times 10^{-6}$ to $2 \times 10^{-2}$
Limestone, dolomite	$1 \times 10^{-9}$ to $6 \times 10^{-6}$
Sandstone	$3 \times 10^{-10}$ to $6 \times 10^{-6}$
Siltstone	$1 \times 10^{-11}$ to $1.4 \times 10^{-8}$
Salt	$1 \times 10^{-12}$ to $1 \times 10^{-10}$
Anhydrite	$4 \times 10^{-13}$ to $2 \times 10^{-8}$
Shale	$1 \times 10^{-13}$ to $2 \times 10^{-9}$

<b>Crystalline Rocks</b>	
<b>Material</b>	<b>Hydraulic Conductivity (m/sec)</b>
Permeable basalt	$4 \times 10^{-7}$ to $2 \times 10^{-2}$
Fractured igneous and metamorphic rock	$8 \times 10^{-9}$ to $3 \times 10^{-4}$
Weathered granite	$3.3 \times 10^{-6}$ to $5.2 \times 10^{-5}$
Weathered gabbro	$5.5 \times 10^{-7}$ to $3.8 \times 10^{-6}$
Basalt	$2 \times 10^{-11}$ to $4.2 \times 10^{-7}$
Unfractured igneous and metamorphic rock	$3 \times 10^{-14}$ to $2 \times 10^{-10}$


**ARMY TM 5-818-5  
NAVY NAVFAC P-418  
AIR FORCE AFM 88-5, Chap 6**

---

**DEWATERING  
AND  
GROUNDWATER CONTROL**

---

**DEPARTMENTS OF THE ARMY, THE NAVY, AND THE AIR FORCE  
NOVEMBER 1983**




**FLOW**

$$Q_p = \frac{kDx(H - h_0)}{L + E_A} \quad (1)$$


**MAX RESIDUAL HEAD DOWNSTREAM OF SLOT**

$$h_D = \frac{E_A(H - h_0)}{L + E_A} + h_0 \quad (2)$$

WHERE  $E_A$  IS AN ADDITIONAL LENGTH FACTOR OBTAINED FROM THE FIGURE BELOW



**ARTESIAN FLOW**



**FLOW**


$$Q_p = \left( 0.73 + 0.27 \frac{H - h_0}{H} \right) \frac{kx}{2L} (H^2 - h_0^2) \quad (3)$$

**MAX RESIDUAL HEAD DOWNSTREAM OF SLOT**

$$h_D = h_0 \left[ \frac{1.46}{L} (H - h_0) + 1 \right] \quad (4)$$

WHERE  $L \geq 3H$

**GRAVITY FLOW**



**FLOW**

$$Q_p = \frac{kDx(H - D)}{L - L_0} \quad (5)$$

**MAX RESIDUAL HEAD DOWNSTREAM OF SLOT**

$$h_D = h_0 \left[ \frac{1.46}{L_0} (D - h_0) + 1 \right] \quad (6)$$

PROVIDED  $h_0 \leq D$ ;  $L_0 \geq 3D$

WHERE  $L_0 = \frac{L(D^2 - h_0^2) \left( 0.73 + 0.27 \frac{D - h_0}{D} \right)}{2D(H - D) + (D^2 - h_0^2) \left( 0.73 + 0.27 \frac{D - h_0}{D} \right)} \quad (7)$

**COMBINED ARTESIAN AND GRAVITY FLOWS**

(Modified from "Foundation Engineering," G. A. Leonards, ed., 1962. McGraw-Hill Book Company. Used with permission of McGraw-Hill Book Company.)

Figure 4-3. Flow and head for partially penetrating line slot; single-line source; artesian, gravity, and combined flows.



# WATERPROOFING

## MiraDRAIN 9000

### Description

CCW MiraDRAIN 9000 is a high-performance, high-strength drainage composite consisting of a three-dimensional, high-impact polypropylene core and a woven filter fabric. The filter fabric is bonded to the individual dimples of the molded polypropylene core to minimize fabric intrusion into the flow channels caused by overburden pressure. The fabric serves as a filter medium to prevent the passage of particles into the core, while allowing surface moisture to pass freely. CCW MiraDRAIN 9000's woven, monofilament fabric withstands high abrasion from applied overburden and prevents intrusion into the drainage core due to its low elongation characteristics. The woven fabric is better suited to receive a directly poured concrete topping than nonwoven geotextile fabrics.

CCW MiraDRAIN 9000 is designed for use in horizontal plaza, roof deck and between-slab drainage applications where single-sided subsurface drainage is required. CCW MiraDRAIN 9000 also serves as a protection course when used in conjunction with CCW Waterproofing Membranes.

### Features and Benefits

- Relieves hydrostatic pressure buildup
- Consistent and proven long-term performance due to a multi-directional core configuration providing a uniform flow path for water to escape
- High-flow drainage capacity ensuring effective drainage for virtually any horizontal application
- No-clogging drainage performance
- High-compressive-strength system withstands overburden stresses
- Enhances waterproofing system by channeling water away and providing a secondary water retention layer
- Cost-saving, lightweight, easy-to-install panels eliminate the need for bringing aggregate to the construction site

### Installation

CCW MiraDRAIN prefabricated drainage panels may be installed in a variety of construction applications. They may be installed in split slabs, plaza decks and planter applications. CCW MiraDRAIN can be cut with a utility knife or scissors. Concrete may be placed directly

onto either side of the panels. The panels can terminate at the top of the footing and are flexible enough to form right angles to cover the top of the footing. CCW MiraDRAIN eliminates the need for a protection course over waterproofing systems. Native soils can be used over CCW MiraDRAIN. (Contact your local CCW representative for specific guidelines). The CCW MiraDRAIN should be attached with CCW CAV-GRIP, CCW Contact Adhesive or SecurTAPE™. Apply CCW CAV-GRIP or CCW Contact Adhesive over entire surface of waterproofing membrane and back side of MiraDRAIN and mate the two surfaces together.

For standard installation details, follow the CCW MiraDRAIN detail drawings. For non-standard installation instructions contact your local Carlisle Coatings & Waterproofing representative.

### Underslab / Horizontal Applications

#### Floor Slabs and Concrete-Lined Channels

Proper preparation of the subgrade will require grading to a 2% minimum slope. The area of installation should be clear of rubble, rock, large soil clods, etc. Place CCW MiraDRAIN with the fabric side toward the soil. The flange of the second and subsequent panels should be placed over the back side of the preceding dimpled core and butted as close as possible to the preceding panel. The panel joints, longitudinal and transverse on the CCW MiraDRAIN core, should be sealed with a strip of CCW-705, CCW-701 or duct tape. This will aid in preventing concrete or soil from intruding into the CCW MiraDRAIN core during subsequent construction phases. Construction traffic should be minimized over the installed CCW MiraDRAIN. Sand and/or concrete may be poured directly over the CCW MiraDRAIN core.

#### Planters

Place the CCW MiraDRAIN in the planter so that the fabric on the vertical and horizontal surfaces faces the soil. Utilize the installation procedures and attachment method appropriate for the type of substrate. Overlap the fabric of the vertical panel onto the horizontal panel at the transition point. If cutting of the panels is required, exposed cuts must be covered with supplemental pieces of filter fabric to prevent soil intrusion. A minimum overlap of 6" (15 cm) will be required to cover cut sections.

# WATERPROOFING

## MiraDRAIN 9000

### Plaza Decks

Place fabric side up over a properly waterproofed substrate. The panels should be placed so that water runs with the overlap not against it. Secure CCW MiraDRAIN to the substrate with ballast or CCW CAV-GRIP, CCW Contact Adhesive or SecurTAPE to hold it in place. The first panels should be placed with the flanged edge uphill. Cut the fabric along the flange edge and strip off this fabric exposing the edge of the core and the flange. Place the dimpled edge over the preceding flanged edge to join the next panel. Secure the remaining fabric flap with CCW CAV-GRIP, CCW Contact Adhesive, CCW-704 Mastic, CCW LM800-XL, Aluma-Grip 701 or duct tape. Terminal edges that have been cut will require a supplemental piece of filter fabric to seal the panel from soil intrusion and if there is insufficient fabric, the core shall be cut out from the fabric by a depth of 3 dimples to provide excess fabric for wrapping behind the core.

### Drainage Collector/Discharge System

#### Collector Pipe

Place collector pipe as required in design details. For installations where a collector pipe is specified, encapsulate the collector pipe in a gravel bed with a supplemental section of filter fabric as a separator/filter.

### Limitations

- Limit ultraviolet exposure by backfilling within 30 days of installation. Any panels damaged during installation should be replaced by the installer.
- CCW MiraDRAIN is resistant to chemicals in normal soil environments. However, some reagents may affect its performance. Consult CCW representatives concerning the suitability of CCW MiraDRAIN in unusual soil environments.

### Packaging

4' x 50' (1.22 m x 15.24 m) rolls


CCW MiraDRAIN 9000 is made in the USA and is sold through a highly qualified sales representative network.

### Typical Properties

Property	Method	Unit	Typical Value
<b>CORE</b>			
Thickness	ASTM D1777	in (mm)	0.40 (10.16)
Compressive Strength	ASTM D1621 (mod)	psf (kPa)	21,000 psi
Maximum Flow Rate	ASTM D4716	gpm/ft (l/min/m)	23 gpm/ft
<b>FABRIC</b>			
Apparent Opening Size	ASTM D4751	US Std Sieve (mm)	40 (0.43)
Water Flow Rate	ASTM D4491	gpm/ft <sup>2</sup> (l/min/m)	145 (5,907)
Grab Tensile Strength	ASTM D4632	lbs (N)	365 (1624)
Grab Longation	ASTM D4632	%	24
CBR Puncture Strength	ASTM D6241	lbs (N)	675 (3004)

### Limited Warranty

Carlisle Coatings & Waterproofing Incorporated (Carlisle) warrants this product to be free of defects in workmanship and materials only at the time of shipment from our factory. If any Carlisle materials prove to contain manufacturing defects that substantially affect their performance, Carlisle will, at its option, replace the materials or refund its purchase price. This limited warranty is the only warranty extended by Carlisle with respect to its materials. There are no other warranties, including the implied warranties of merchantability and fitness for a particular purpose. Carlisle specifically disclaims liability for any incidental, consequential, or other damages, including but not limited to, loss of profits or damages to a structure or its contents, arising under any theory of law whatsoever. The dollar value of Carlisle's liability and buyer's remedy under this limited warranty shall not exceed the purchase price of the Carlisle material in question.



12" wide chimney drains of 3/4" crushed stone

Estimated Groundwater Level

TP 100  
15' Rt

6.00%

34.58

31.10

29.60

28.60

5.0'

38.35

32.70

31.20

30.20

R-TANKS

FILTER LAYER

CRUSHED STONE AND UNDERDRAIN

CCW MiraDRAIN 9000 with Mirafi 140N on underside

8" dia. ADS perforated smooth wall subdrain header pipe to connect to an 8" dia. solid smooth wall pipe that will convey seepage to point of discharge; use standard MiraDRAIN connections.

Mirafi 140N

## 3-3 THE CONVEYANCE METHOD

Conveyance provides a convenient means of selecting a variety of pipe options that will satisfy a project's flow requirements. Conveyance factors are based on a greatly simplified version of the Manning's equation shown in Equation 3-1 and 3-1 (a). In the following discussion, example problems and subsequent sections, the pipe is assumed to be flowing full. This assumption typically allows for a simplified, yet accurate analysis of the given conditions. Each project should be evaluated on a case-by-case basis to determine the best, most-representative design method.

$$Q = \frac{(1.486)(A)(R^{2/3})(S^{1/2})}{n}$$

Equation 3-1

Where:

- Q = pipe capacity, (cfs)
- n = Manning's "n"
- A = cross-sectional flow area of the pipe (ft.<sup>2</sup>)
- R = hydraulic radius (ft.):

$$R = \frac{A}{P}$$

P = Wetted perimeter (ft); Pipe inside circumference, or ( $\pi$ )(inside diameter) for full flowing pipe conditions

S = pipe slope (feet/foot)

Or, in metric units:

$$Q = \frac{(A)(R^{2/3})(S^{1/2})}{n}$$

Equation 3-1(a)

Where:

- Q = pipe capacity, m<sup>3</sup>/s
- n = Manning's "n"
- A = cross-sectional flow-area of the pipe (m<sup>2</sup>)
- P = Wetted perimeter (ft); Pipe circumference, or ( $\pi$ )(diameter) for full flowing pipe conditions
- R = hydraulic radius (m),

$$R = \frac{A}{P}$$

S = pipe slope (m/m)



For a specific full-flowing pipe installation, the parameters  $n$ ,  $A$ , and  $R$  are easily defined constants. The flow-carrying ability, or conveyance factor, of the pipe can then be defined as shown in Equation 3-2 or 3-2(a).

$$k = \frac{(1.486)(A)(R^{2/3})}{n} \quad \text{Equation 3-2}$$

Or, in metric units:

$$k = \frac{(A)(R^{2/3})}{n} \quad \text{Equation 3-2(a)}$$

By substitution, the Manning's formula can then be reduced to the following equation.

$$Q = kS^{1/2} \quad \text{Equation 3-3}$$

Equation 3-3 can also be written as shown in Equation 3-4.

$$k = \frac{Q}{S^{1/2}} \quad \text{Equation 3-4}$$

Direct substitution of design conditions into Equation 3-4 will determine the minimum conveyance factor allowed. Table 3-2 or 3-2 is then used as a guide to select a pipe having a conveyance factor of at least that calculated.

Table 3-1 and 3-2 require knowledge of the Manning's "n" value. These tables can also be used for any materials if the specific Manning's "n" is known.

The Manning's "n" is a critical value in the conveyance concept. Among pipes of the same diameter and slope, Manning's "n" will be the only factor that will have an effect on conveyance, and therefore capacity. When comparing identical field conditions, conveyance has a direct relationship to capacity. That is, if the slope is held constant, tripling conveyance will triple the capacity; halving conveyance will halve the capacity.

Example problems involving conveyance factors are explained in a subsequent section.

**Table 3-1**  
**Conveyance Factors (Standard Units)**

Design Manning's Values for ADS Thermoplastic Pipe *	
Product	Diameter
N-12, MEGA GREEN, N-12 STIB, N-12 WTIB, HP STORM, SaniTite, SaniTite HP, N-12 Low Head	4" - 60"
Single Wall Highway and Heavy Duty *	18" - 24" 12" - 15" 10" 8"
TripleWall and Smoothwall Sewer & Drain	3" - 6"
Conveyance Equations: $k = Q/(s^{0.5})$ $Q = k s^{0.5}$	
Design Manning's "n"	
"n" = 0.012	
"n" = 0.020 "n" = 0.018 "n" = 0.017 "n" = 0.016 "n" = 0.015	
"n" = 0.009 **	

		Conveyance Factors for Circular Pipe Flowing Full																
		Manning's "n" Values																
Dia. (in.)	Area (sq. ft.)	0.009	0.010	0.011	0.012	0.013	0.014	0.015	0.016	0.017	0.018	0.019	0.020	0.021	0.022	0.023	0.024	0.025
3	0.05	1.3	1.1	1.0	1.0	0.9	0.8	0.8	0.7	0.7	0.6	0.6	0.6	0.5	0.5	0.5	0.5	0.5
4	0.09	2.7	2.5	2.2	2.1	1.9	1.8	1.6	1.5	1.5	1.4	1.3	1.2	1.2	1.1	1.1	1.0	1.0
6	0.20	8.1	7.3	6.6	6.1	5.6	5.2	4.9	4.6	4.3	4.1	3.8	3.6	3.5	3.3	3.2	3.0	2.9
8	0.35	17.5	15.7	14.3	13.1	12.1	11.2	10.5	9.8	9.2	8.7	8.3	7.9	7.5	7.1	6.8	6.5	6.3
10	0.55	31.6	28.5	25.9	23.7	21.9	20.3	19.0	17.8	16.8	15.8	15.0	14.2	13.6	12.9	12.4	11.9	11.4
12	0.79	51.5	46.3	42.1	38.6	35.6	33.1	30.9	28.9	27.2	25.7	24.4	23.2	22.1	21.1	20.1	19.3	18.5
15	1.23	93.3	84.0	76.3	70.0	64.6	60.0	56.0	52.5	49.4	46.7	44.2	42.0	40.0	38.2	36.5	35.0	33.6
18	1.77	151.7	136.6	124.1	113.8	105.0	97.5	91.0	85.3	80.3	75.9	71.9	68.3	65.0	62.1	59.4	56.9	54.6
21	2.41	228.9	206.0	187.3	171.6	158.4	147.1	137.3	128.7	121.2	114.4	108.4	103.0	98.1	93.6	89.6	85.8	82.4
24	3.14	326.8	294.1	267.3	245.1	226.2	210.1	196.1	183.8	173.0	163.4	154.8	147.0	140.0	133.7	127.9	122.5	117.6
27	3.98	447.3	402.6	366.0	335.5	309.7	287.6	268.4	251.6	236.8	223.7	211.9	201.3	191.7	183.0	175.0	167.8	161.0
30	4.91	592.5	533.2	484.7	444.3	410.2	380.9	355.5	333.3	313.7	296.2	280.6	266.6	253.9	242.4	231.8	222.2	213.3
33	5.94	763.9	687.5	625.0	572.9	528.9	491.1	458.3	429.7	404.4	382.0	361.9	343.8	327.4	312.5	298.9	286.5	275.0
36	7.07	963.4	867.1	788.2	722.6	667.0	619.3	578.0	541.9	510.0	481.7	456.4	433.5	412.9	394.1	377.0	361.3	346.8
42	9.62	1453.2	1307.9	1189.0	1089.9	1006.1	934.2	871.9	817.5	769.4	726.6	688.4	654.0	622.8	594.5	568.7	545.0	523.2
45	11.04	1746.8	1572.1	1429.2	1310.1	1209.3	1122.9	1048.1	982.6	924.8	873.4	827.4	786.1	748.6	714.6	683.5	655.0	628.8
48	12.57	2074.8	1867.4	1697.6	1556.1	1436.4	1333.8	1244.9	1167.1	1098.4	1037.4	982.8	933.7	889.2	848.8	811.9	778.1	746.9
54	15.90	2840.5	2556.4	2324.0	2130.4	1966.5	1826.0	1704.3	1597.8	1503.8	1420.2	1345.5	1278.2	1217.4	1162.0	1111.5	1065.2	1022.6
60	19.63	3762.0	3385.8	3078.0	2821.5	2604.4	2418.4	2257.2	2116.1	1991.6	1881.0	1782.0	1692.9	1612.3	1539.0	1472.1	1410.7	1354.3
72	28.27	6117.3	5505.6	5005.1	4588.0	4235.1	3932.6	3670.4	3441.0	3238.6	3058.7	2897.7	2752.8	2621.7	2502.5	2393.7	2294.0	2202.2

\* Corrugated Polyethylene Pipe Association (2000) "Hydraulic Considerations for Corrugated Polyethylene Pipe"

\*\* "Lingedburg, Michael, "Civil Engineer Reference Manual"

ESTIMATE FLOW INTO THE COMBINED STORMWATER TREATMENT SYSTEM #1 AND #2 COLLECTIVELY. REFER TO TFM SITE DEVELOPMENT PLANS FOR "THE VILLAGE AT BANFIELD WOODS" DATED SEPTEMBER 25, 2019.

ASSUMPTIONS USED IN THIS ASSESSMENT:

- 1) GROUNDWATER @  $2' \pm$  ABOVE TOP OF SYSTEMS #1 AND #2 OR ABOUT  $2' \pm$  BELOW TOP OF PAVEMENT.
- 2) BOTTOM AND SIDES OF BOTH SYSTEMS TO BE ENVELOPED WITH IMPERVIOUS BARRIER RESULTING IN NO LEAKAGE.
- 3) BOTH SYSTEMS WILL BE UNDERLAIN WITH A SYNTHETIC DRAINAGE MEDIUM, CCW MIRADRAIN 9000, THAT HAS A MAX DRAINAGE CAPACITY OF  $21 \frac{\text{GAL}}{\text{MIN/FT}}$
- 4) A 6"  $\phi$  PERFORATED SUBDRAIN WILL BE PLACED ALONG THE SOUTH SIDE OF THE SYSTEM PROXIMATE TO STA 1+95 $\pm$  THAT WILL CONVEY COLLECTED SEEPAGE BY GRAVITY AWAY FROM THE SYSTEM.
- 5) A 12" THICK CRUSHED STONE LAYER WILL ALSO BE PLACED BETWEEN THE VERTICAL ROCK CUTS AND THE IMPERVIOUS SIDE WALLS OF THE SYSTEMS.
- 6) BEDROCK AT THE SITE IS MAPPED AS THE "RYE COMPLEX, BREAKFAST HILL GRANITE OF NOVOTNY".
- 7) ROCK REMOVAL WILL REQUIRE DRILLING + BLASTING.
- 8) GROUNDWATER WILL MIGRATE THROUGH BEDROCK JOINTS + FRACTURES + ZONES OF OVERBLAST ROCK.
- 9) FROM DOMENICO + SCHWARTZ 1990, WE USE A HYDRAULIC CONDUCTIVITY OF  $3 \times 10^{-4}$  m/SEC FOR FRACTURED IGNEOUS ROCK.
- 10) USE FIG 4-3 OF THE COMBINED ARMY (TMS-818-5), NAVY (P-418) + AIRFORCE (AFM 88-5, CHPT 6) DATED NOV. 1983 FOR A PARTIALLY PENETRATING LINE SLOT DRAINAGE SYSTEM.
- 11) CONSERVATIVELY ASSUME INFILTRATION ON ALL SIDES OF THE COMBINED BASINS EQUALING ABOUT 300 $\pm$  LF.

12) REFER TO FIG 4.3 FOR DIMENSION DETAILS FOR GRAVITY FLOW MODEL.

FROM FIG 4.3 - GRAVITY FLOW

$$Q_p = \left( 0.73 + 0.27 \left( \frac{H - h_o}{H} \right) \right) \frac{K}{2L} (H^2 - h_o^2)$$

$$H = 8' \pm \text{ TO } 10' \pm ; \text{ USE } 10'$$

$$h_o = \text{THICKNESS OF DRAINAGE LAYER} \approx 0.5'' \pm \approx 0.04' \pm$$

(CCW MIRADRAIN 9000)

$$L = 100' \pm \text{ (ASSUMED)}$$

$$K = 3 \times 10^{-4} \text{ m/sec} = 3.6 \text{ FT/HR}$$

$$Q_p \left( \frac{\text{FT}}{\text{FT}} \right) = \left( 0.73 + 0.27 \left( \frac{10 - 0.04}{10} \right) \right) \frac{3.6}{2(100)} (10^2 - 0.04^2) = 0.60 \frac{\text{FT}^3}{\text{HR/FT}}$$

$$= 4.5 \frac{\text{GAL}}{\text{HR/FT}}$$

ASSUME INFILTRATION OVER ALL FOUR SIDES -  
 CONTRIBUTING LENGTH  $\approx 42'$  WIDE BY  $44'$  LONG  
 (COMBINED FOOTPRINT)

TOTAL PERIMETER LENGTH  $\approx 300' \pm$  LF

$$Q_p(300 \text{ FT}) = 4.5(300) = 1,350 \frac{\text{GAL}}{\text{HR}}$$

NOW CHECK PERMEABILITY OF CCW MIRADRAIN 9000 TO  
 ABSORB AND TRANSMIT 1,350 GAL/HR. MAX FLOW RATE  
 THROUGH CCW MIRADRAIN 900  
 IS  $21 \frac{\text{GAL}}{\text{MIN/FT}}$  OR  $1,260 \frac{\text{GAL}}{\text{HR/FT}}$ . SINCE ALL DRAINAGE WILL

BE CONVEYED TO THE SOUTH PERIMETER WITH A LENGTH OF  
 $42$  FT, EACH FT OF THE DRAIN MUST PASS AT LEAST  $4.5 \text{ GAL/HR/FT}$

SINCE THE DRAIN CAN PASS 1,260  $\frac{\text{GAL}}{\text{HR/FT}}$   $\rightarrow$  4.5  $\frac{\text{GAL}}{\text{HR/FT}}$   
 THE CCWMIRA DRAIN 9000 IS HYDRAULICALLY ADEQUATE  
 TO ABSORB AND CONVEY THE GROUNDWATER  
 SEEPAGE.

NOW CHECK HYDRAULIC CONDUCTIVITY OF THE 6" HDPE  
 SUBDRAIN TO BE LOCATED ALONG SOUTH SIDE OF SYSTEM.

TO ESTIMATE THE CAPACITY OF A 6" HDPE SMOOTH WALL  
 PERFORATED PIPE, REFER TO THE "CONVEYANCE FACTOR"  
 AS TABULATED ON TABLE 3.1 OF THE ADS DRAINAGE  
 HANDBOOK FOR A MANNINGS "n" VALUE OF 0.012. THE  
 CONVEYANCE FACTOR "K" IS SHOWN AS 6.1.

FROM ADS EQUATION 3-3:

$$Q = K (S^{0.5}) \quad \text{WHERE } S \text{ IS THE SLOPE OF THE PIPE}$$

FOR A RELATIVELY FLAT SLOPE OF 6" PER 100'

$$Q = 6.1 (0.005^{1/2}) = 0.43 \frac{\text{FT}^3}{\text{S}}$$

SINCE THE SUBDRAIN MUST PASS A COMBINED FLOW  
 OF AT LEAST 1,350  $\frac{\text{GAL}}{\text{HR}}$  OR 0.05  $\frac{\text{FT}^3}{\text{S}}$ , THE

6" ADS PERFORATED SMOOTH BORE PIPE  
 IS ADEQUATE.

# ***DRAINAGE ANALYSIS***


F O R

## **The Village at Banfield Woods**

**0 Banfield Road**  
County of Rockingham  
Portsmouth, New Hampshire

Tax Map 256, Lot 2

December 27, 2019  
Last Revised March 23, 2020



Prepared By:



Civil Engineers  
Structural Engineers  
Traffic Engineers  
Land Surveyors  
Landscape Architects  
Scientists

(This Page Is Intentionally Blank)

## Contents

1.0 SUMMARY .....	1
1.1 - Pre- and Post-Development Flow Comparison .....	1
1.2 – Best Management Practices .....	1
2.0 - PROJECT DESCRIPTION .....	2
3.0 - CALCULATION METHODS .....	2
4.0 – PRE-DEVELOPMENT CONDITION .....	4
5.0 – POST-DEVELOPMENT CONDITION .....	4
6.0 – BMP EFFICIENCIES .....	5
7.0 – LOW IMPACT DESIGN .....	5
8.0 – BEST MANAGEMENT PRACTICES .....	6
8.1 – Temporary Practices: .....	6
8.2 – Permanent Practices:.....	7
8.0 – CONCLUSION .....	8

## Table of Figures

Table 1 - Pre and Post Flows .....	1
Table 2 - Precipitaytion Estimates .....	2

## Appedices

APPENDIX A - EXTREME PRECIPITATION TABLE .....	9
APPENDIX B - PRE-DRAINAGE .....	13
APPENDIX C - PRE-DRAINAGE (10 Yr. Storm Event) .....	27
APPENDIX D - POST DRAINAGE .....	39
APPENDIX E - POST DRAINAGE (10 Yr. Storm Event) .....	61
APPENDIX F - BMP WORKSHEETS .....	99
APPENDIX G - RIP RAP CALCULATIONS .....	127
APPENDIX H - INLET CAPACITY CALCULATIONS .....	139
APPENDIX I - NRCS WEB SOIL SURVEY .....	143
REPORT	
HYDROLOGIC SOIL GROUP BASED ON NRCS	
APPENDIX J - SOIL REPORT AND TEST PIT LOGS .....	175
REPORT	
TEST PIT LOGS	
HYDROLOGIC SOIL GROUP BASED ON SITE SPECIFIC SOIL GROUPS AND NRCS	
APPENDIX K - NHDES ONE STOP DATA MAPPER .....	195
APPENDIX L - CURVE NUMBER MAP .....	201
APPENDIX M - PRE AND POST DRAINAGE PLANS .....	205



(This Page Is Intentionally Blank)

## **1.0 SUMMARY**

This drainage study was completed to assess the pre- and post-development runoff rates for the proposed subdivision for the 2-year, 10-year, 25-year, and the 50-year storm events. There is no increase in drainage flows in the post development study.

In addition, Best Management Practices were developed to formulate a plan that assures stormwater quality both during and after construction. The following summarizes the findings from the study.

### **1.1 - Pre- and Post-Development Flow Comparison**

The pre- and post-development watershed areas have been analyzed for each of the six lots. Table 1 compares pre- and post-development peak runoff rates during all storm events analyzed for each Point of Interest.

The drainage flows in post development remain the same or show a slight decrease for the Pre-Development Flows.

Area Number	2-Year (Flow - cfs)		2-Year (Volume - cf)		10-Year (Flow - cfs)		25-Year (Flow - cfs)		50-Year (Flow - cfs)	
	Pre-Dev.	Post-Dev.	Pre-Dev.	Post-Dev.	Pre-Dev.	Post-Dev.	Pre-Dev.	Post-Dev.	Pre-Dev.	Post-Dev.
POI-1	0.3	0.3	3,189	3,189	1.1	1.1	1.8	1.8	2.5	2.5
POI-2	11.5	10.1	176,319	182,572	21.8	21.6	42.7	41.4	70.4	68.5
Total Volume			179,508	185,761						

*Table 1 - Pre and Post Flows*

### **1.2 – Best Management Practices**

Best Management Practices have been incorporated into the drainage design which provide for temporary erosion control measures during the construction process and permanent erosion control measures after construction is complete. Temporary measures include construction sequencing, silt barriers and provisions for stabilization of inactive areas. Permanent erosion control measures include turf establishment on all disturbed areas that have not been paved, one bioretention area, two hybrid bioretention areas and an underground stormwater treatment area consisting of 4 sets of tanks using R-tank chambers and engineered soil filtration.

## **2.0 - PROJECT DESCRIPTION**

The existing lot is a 44.884 acre. The proposed development will only effect 17% of the lot with a 5% impervious cover.

The proposal is for a multi-family condominium site comprising of 22 single-family dwelling units. This project has been before the Technical Advisory Committee in work sessions and one review meeting and the Conservation Commission. This site has a significant amount of upland, surrounded by wetlands. We have worked on solutions to minimize impacts to the wetlands and their 100' buffers.

The disturbance on the lot is limited to the western section of the lot. This is the area focused on for the drainage report. The calculations show that the proposed drainage flows remain the same or slightly less than the existing drainage flows.

## **3.0 - CALCULATION METHODS**

The design storms analyzed in this study are the 2-year, 10-year, 25-year and the 50-year, 24-hour storm events. The software program, HydroCAD version 10.00<sup>1</sup> was utilized to calculate the peak runoff rates from these storm events. The program estimates the peak rates using the TR-20 method. A Type III storm pattern was used in the model. Rainfall frequencies for the analyzed region were also incorporated into the model. Rainfall frequencies from the Northeast Regional Climate Center were used to determine the storm-event intensities, see Table 2. Design standards were taken from the New Hampshire Stormwater Manual, December 2008<sup>2</sup>.

<b>PRECIPITATION ESTIMATES</b>	
<b>Storm-Event (yr)</b>	<b>Rainfall (in)</b>
2	3.24
10	4.91
25	6.23
50	7.46

*Table 2 - Precipitation Estimates*

Time of Concentration is the time it takes for water to flow from the most hydraulically remote point to the watershed outlet following the route that takes the longest watercourse length. This time is determined by calculating the time it takes runoff to travel this route under one of three hydrologic conditions: sheet flow, shallow concentrated flow or channel flow. Because the Intensity-Duration-Frequency (IDF) curve is steep with short  $T_c$ 's, estimating the actual intensity is subject to error and

<sup>1</sup> HydroCAD version 10.00, HydroCAD Software Solutions LLC, Chocorua, NH, 2013.

<sup>2</sup> New Hampshire Stormwater Manual: Volume One - Stormwater and Antidegradation, December 2008; Volume Two - Post-Construction Best Management Practices Selection and Design, December 2008; Volume Three - Erosion and Sediment Controls During Construction, December 2008.

overestimates actual runoff. Due to this, the  $T_c$ 's are adjusted to a minimum of 5 minutes.

The National Resources Conservation Service (NRCS) Web Soil shows that approximately half the soil in the area to be (140) Chatfield-Hollis-Canton complex, 0 to 15 percent slopes and rocky. Chatfield soil is well drained soil with high runoff potential. It is grouped as a Hydrologic Soil Group B soil. Hollis soil is somewhat-excessively-drained with a very high runoff potential and grouped as a Hydrologic Soil Group D soil. Canton soil is a well-drained soil with a low runoff potential. It is grouped as a Hydrologic Soil Group B soil.

The next major soil group in the study area is (538) Squamscott fine sandy loam, 0 to 5 % slopes. It is a poorly-drained with a medium runoff potential and grouped as a Hydrologic Soil Group C/D soil.

The remainder of the soil is classed as (134) Maybid silt loam, 0 to 5 % slopes, and (38) Edlridge fine sandy loam, 3 to 8 % slopes. Neither of these are in the area being developed, both are grouped as a Hydrologic Soil Group C/D soil. See Appendix G for more detail.

Curve number are based on the soil's hydrologic properties, ranging from 30 to 100. The lower numbers indicate the soils have less runoff potential (amount of rainwater that is not retained) and higher curve numbers indicate high runoff potential. Several curve numbers were used in the analysis of this property. For areas in the buffer that were going to be mowed, at most, once a year, a curve number was used that was more than the original undisturbed woods and less than well maintained lawns.

Existing Woods - Woods Good	55	70
Powerlines – Powerlines - Brush, Good	48	65
Wetlands – Brush, Good	48	65
Lawns - >75% Grass Cover, Good	61	74
Restored Buffer Areas – Woods Grass Combo, Good (Areas that would be mowed one or less times a year)	58	72
Roads and Driveways – Paved Parking	98	98
Houses – Roofs	98	98

## **4.0 – PRE-DEVELOPMENT CONDITION**

There are nine watershed areas that have been used to identify the pre-development conditions. The pre-development watersheds are depicted on the attached plan entitled “Pre-Development Drainage Plan,” Appendix I - Sheet D-1.

Except for a small portion in the northeast corner of the lot, stormwater from offsite and onsite drain to two ‘valleys’ in the property. The first of these areas is orientated in a north/south direction near the middle of the property. The second area is orientated in the east/west direction, just north of Banfield Road. Wetlands exists in both of these areas.

The two low areas direct the water to two culverts near the middle of the property that direct water under Banfield road to the property to the south of Banfield Road.

See Table 1 for Pre-development Stormwater Flows Offsite. Appendix A in this Drainage Study documents the peak runoff rates. Appendix B and C in this Drainage Study documents the computations for these peak stormwater flows.

## **5.0 – POST-DEVELOPMENT CONDITION**

There are 22 drainage areas that have been used to define identify the post development conditions. Post-development watershed areas are depicted on the attached plan entitled “Post-Development Drainage Plan,” Appendix I - Sheet D-2.

Table 1 summarizes the Post-Development Stormwater Flows Offsite for the 2-year, 10-year, 25-year and 50-year Type III storm events for the watershed areas. Appendix A in this Drainage Study documents the peak runoff rates. Appendix D and E in this Drainage Study documents the computations for these peak stormwater flows.

Four deep sump curb inlets are used at the entrance to the site to capture water and provide some pretreatment. Because of the topography and the locations of the wetlands and buffers, additional treatment to the stormwater is not feasible.

One underground detentions area is used to capture runoff form the roadway, drives, and buildings from approximately 175’ to 500’ into the site. The underground stormwater management system captures the water through 4 deep-sump catch basins, providing the pretreatment to the stormwater before it enters the system. Four sets of R-Tanks hold and detain the stormwater as it filters a layer of engineered soil, removing most of the contaminants. Outlet structures meter the release of larger storms.

Two Hybrid bioretention areas treat the stormwater from 500’ to the cul-de-sac, including some of the houses and drives along the outer edge of the cul-de-sac. The stormwater enters through four catchbasins for pretreatment prior to in entering the ponding areas. Stormwater is held in the pond area as it filters through an engineered soil, filtering out

contaminants. In addition, the hybrid design offers an anaerobic area (absence of free oxygen) that further aids in the denitrification process.

One conventional bioretention area is used to treat the stormwater for a portion of the cul-de-sac and the grassed area in the center of the cul-de-sac. A forebay near the front of the island in the cul-de-sac provides pretreatment prior to the water entering the Bioretention Area 1. Engineered soil will filter the soil before being captured by underdrains and flowing back into the undisturbed woods. An outlet control structure is used to meter the flow of the water to keep storm flows to a minimum.

The remainder of the roof runoff not captured by these systems will be treated by overland flow through the wetland buffers.

For channel protection, the state DES uses the 2-year volume. The site remains in the 0.1 acre-ft allowed.

For all the storm events analyzed, the runoff from site remains the same or a slight decrease than the existing runoff. The proposed storm flows will have no adverse effects on the abutting properties.

## **6.0 – BMP EFFICIENCIES**

Appendix B of Volume 2 of the New Hampshire Stormwater<sup>3</sup> lists the pollutant removal efficiencies of various BMP's. The bioretention area and filtration practices are listed as having a 90% efficiency for removing Total Suspended Solids (TSS) and 65% efficiencies in removing Total Nitrogen (TN) and Total Phosphorous (TP). Based on UNHSC data, the Hybrid bioretention systems offer further denitrification of the stormwater, showing approximately a 30% increase in removal of TP and an additional 20% removal for TN.

## **7.0 – LOW IMPACT DESIGN**

Low Impact Design (LID) is utilized in the design and implementation of this project. This site is laid out to provide the maximum greenspace for the proposed development. The total area of the lot is 44.884 acres (1,955,150 sf). The total proposed disturbed area is 7.591 acres (330,672 sf) or 17% of the lot. The total impervious area on the lot, including roofs, is 2.228 acres (97,030 sf). This is only 5% impervious cover on the lot.

The original lot had 28' wide roadway (two 12' lanes and a 4' walkway) and a cul-de-sac was reduced from having an exterior 90' arc to an exterior 60' arc. This totaled approximately 16,400 sf or 35% reduction in impervious roadway.

---

<sup>3</sup> New Hampshire Stormwater Manual: Volume One - Stormwater and Antidegradation, December 2008; Volume Two - Post-Construction Best Management Practices Selection and Design, December 2008; Volume Three - Erosion and Sediment Controls During Construction, December 2008.

The impervious roadway is being captured and treated using the Bioretention Area #1 which is using soil and plant-based media to filter and treat the stormwater. Bioretention Areas #2 and #3 add an anaerobic zone on top of the filtration that the conventional bioretention area offers. The Underground Detention System uses engineered soil to treat and attenuate stormwater flows, similar to the bioretention system. Refer to section 6 for the pollutant efficiency removal rates.

In the April 2009 article titled "Managing Stormwater with Low Impact Development Practices: Addressing Barriers to LID" it speaks of LID's as "practices that manage stormwater by minimizing impervious cover and by using natural or man-made systems to filter and recharge stormwater into the ground. Roads, parking lots, and other types of impervious cover are the most significant contributors to stormwater runoff".

The project has minimized the impervious cover and provided treatment in several disperse systems. It is a Low Impact Design.

## **8.0 – BEST MANAGEMENT PRACTICES**

All soil erosion and sediment control measures shall be in accordance with regulations and principles as outlined in the *New Hampshire Stormwater Manual, Volumes Two and Three, December 2008*. The intent of the outlined measures is to minimize erosion and sedimentation during construction, stabilize and protect the site from erosion after construction is complete and mitigate any adverse impacts to stormwater quality resulting from development. Best Management Practices for this project include:

- Temporary practices to be implemented during construction.
- Permanent practices to be implemented after construction.

### **8.1 – Temporary Practices:**

1. Erosion, sediment, and stormwater detention measures must be installed as directed by the engineer.
2. All disturbed areas, as well as loam stockpiles, shall be seeded and contained by a silt barrier.
3. Silt barriers must be installed prior to any construction commencing. All erosion control devices including silt barriers and storm drain inlet filters shall be inspected at least once per week and following any rainfall. All necessary maintenance shall be completed within twenty-four (24) hours.

4. Any silt barriers found to be failing must be replaced immediately. Sediment is to be removed from behind the silt fence if found to be one-third the height of the silt barrier or greater.
5. Any area of the site, which has been disturbed and where construction activity will not occur for more than twenty-one (21) days, shall be temporarily stabilized by mulching and seeding.
6. No construction materials shall be buried on-site.
7. After all areas have been stabilized, temporary practices are to be removed, and the area they are removed from must be smoothed and revegetated.
8. Areas must be temporarily stabilized within 14 days of disturbance or seeded and mulched within 3 days of final stabilization.
9. After November 15<sup>th</sup>, incomplete driveways or parking areas must be protected with a minimum of 3" of crushed gravel, meeting the standards of NHDOT item 304.3.
10. An area is considered stabilized if it has met one of the following:
  - a) A minimum of 85% vegetative growth has been established.
  - b) Base course gravel has been installed in areas to be paved.
  - c) Stone, rip rap, or any other non-erosive material has been installed with a minimum thickness of 3".
  - d) Erosion control blankets have been installed.

## **8.2 – Permanent Practices:**

The objectives for developing permanent Best Management Practices for this site include the following:

1. Maintain existing runoff flow characteristics.
  - a) Drainage is structured to minimize any offsite increase in runoff
2. Treatment BMP's are established to ensure the water quality.
3. Maintenance schedules are set to safeguard the long term working of the stormwater BMP's.



## **8.0 – CONCLUSION**

The proposed development of the lot located at 0 Banfield Road, Portsmouth, NH shows slight decreases in the stormwater flows for the storm events analyzed and will have no adverse effects on surrounding properties. There will be little to not change stormwater runoff characteristics for the lot. Appropriate erosion and sediment control practices will be implemented to reduce possible erosion and siltation. Best Management Practices will be developed in accordance with the *New Hampshire Stormwater Manual, Volumes Two and Three, December 2008* to formulate a plan that assures stormwater quality both during and after construction.

Submitted by,

MSC a division of TFMoran, Inc.

Jack McTigue, PE  
Project Manager

**APPENDIX A**  
**EXTREME PRECIPITATION TABLE**

(This Page Is Intentionally Blank)

# Extreme Precipitation Tables

## Northeast Regional Climate Center

Data represents point estimates calculated from partial duration series. All precipitation amounts are displayed in inches.

<b>Smoothing</b>	Yes
<b>State</b>	New Hampshire
<b>Location</b>	
<b>Longitude</b>	70.793 degrees West
<b>Latitude</b>	43.041 degrees North
<b>Elevation</b>	0 feet
<b>Date/Time</b>	Tue, 22 Oct 2019 08:54:52 -0400

### Extreme Precipitation Estimates

	5min	10min	15min	30min	60min	120min		1hr	2hr	3hr	6hr	12hr	24hr	48hr		1day	2day	4day	7day	10day	
<b>1yr</b>	0.26	0.40	0.50	0.65	0.82	1.04	<b>1yr</b>	0.71	0.98	1.22	1.57	2.04	2.68	2.95	<b>1yr</b>	2.37	2.83	3.25	3.97	4.59	<b>1yr</b>
<b>2yr</b>	0.32	0.50	0.62	0.81	1.02	1.30	<b>2yr</b>	0.88	1.18	1.52	1.95	2.50	3.24	3.60	<b>2yr</b>	2.86	3.46	3.97	4.71	5.36	<b>2yr</b>
<b>5yr</b>	0.37	0.58	0.73	0.98	1.25	1.61	<b>5yr</b>	1.08	1.47	1.89	2.44	3.16	4.10	4.62	<b>5yr</b>	3.63	4.44	5.08	5.98	6.76	<b>5yr</b>
<b>10yr</b>	0.41	0.65	0.82	1.12	1.45	1.90	<b>10yr</b>	1.25	1.73	2.24	2.91	3.77	4.91	5.58	<b>10yr</b>	4.35	5.36	6.14	7.17	8.05	<b>10yr</b>
<b>25yr</b>	0.48	0.76	0.97	1.34	1.78	2.35	<b>25yr</b>	1.54	2.15	2.79	3.65	4.77	6.23	7.16	<b>25yr</b>	5.51	6.89	7.88	9.12	10.15	<b>25yr</b>
<b>50yr</b>	0.54	0.86	1.10	1.54	2.08	2.77	<b>50yr</b>	1.79	2.53	3.30	4.35	5.71	7.46	8.67	<b>50yr</b>	6.61	8.33	9.53	10.93	12.10	<b>50yr</b>
<b>100yr</b>	0.60	0.97	1.25	1.78	2.43	3.27	<b>100yr</b>	2.09	2.99	3.92	5.19	6.82	8.95	10.48	<b>100yr</b>	7.92	10.08	11.52	13.11	14.43	<b>100yr</b>
<b>200yr</b>	0.68	1.11	1.43	2.05	2.84	3.85	<b>200yr</b>	2.45	3.53	4.64	6.17	8.15	10.72	12.68	<b>200yr</b>	9.49	12.19	13.94	15.74	17.21	<b>200yr</b>
<b>500yr</b>	0.80	1.32	1.72	2.50	3.49	4.79	<b>500yr</b>	3.01	4.40	5.80	7.76	10.31	13.63	16.31	<b>500yr</b>	12.07	15.69	17.92	20.04	21.75	<b>500yr</b>

### Lower Confidence Limits

	5min	10min	15min	30min	60min	120min		1hr	2hr	3hr	6hr	12hr	24hr	48hr		1day	2day	4day	7day	10day	
<b>1yr</b>	0.23	0.36	0.44	0.59	0.72	0.89	<b>1yr</b>	0.63	0.87	0.92	1.32	1.67	2.25	2.57	<b>1yr</b>	1.99	2.47	2.88	3.16	3.92	<b>1yr</b>
<b>2yr</b>	0.32	0.49	0.60	0.81	1.00	1.19	<b>2yr</b>	0.86	1.16	1.37	1.82	2.34	3.08	3.49	<b>2yr</b>	2.73	3.36	3.86	4.59	5.11	<b>2yr</b>
<b>5yr</b>	0.35	0.54	0.67	0.92	1.18	1.41	<b>5yr</b>	1.01	1.38	1.61	2.12	2.73	3.83	4.26	<b>5yr</b>	3.39	4.09	4.77	5.61	6.32	<b>5yr</b>
<b>10yr</b>	0.39	0.60	0.74	1.03	1.33	1.61	<b>10yr</b>	1.15	1.57	1.81	2.39	3.06	4.43	4.96	<b>10yr</b>	3.92	4.77	5.55	6.52	7.31	<b>10yr</b>
<b>25yr</b>	0.44	0.67	0.84	1.20	1.58	1.91	<b>25yr</b>	1.36	1.87	2.10	2.76	3.54	4.76	6.03	<b>25yr</b>	4.21	5.80	6.82	7.97	8.84	<b>25yr</b>
<b>50yr</b>	0.49	0.74	0.92	1.33	1.79	2.18	<b>50yr</b>	1.54	2.13	2.35	3.07	3.94	5.38	6.99	<b>50yr</b>	4.76	6.73	7.97	9.28	10.23	<b>50yr</b>
<b>100yr</b>	0.54	0.82	1.03	1.49	2.04	2.49	<b>100yr</b>	1.76	2.43	2.63	3.42	4.36	6.05	8.11	<b>100yr</b>	5.36	7.79	9.33	10.81	11.82	<b>100yr</b>
<b>200yr</b>	0.60	0.91	1.15	1.66	2.32	2.84	<b>200yr</b>	2.00	2.77	2.94	3.78	4.82	6.79	9.40	<b>200yr</b>	6.01	9.03	10.92	12.62	13.69	<b>200yr</b>
<b>500yr</b>	0.70	1.04	1.34	1.95	2.78	3.39	<b>500yr</b>	2.40	3.32	3.42	4.32	5.50	7.92	11.42	<b>500yr</b>	7.01	10.98	13.45	15.51	16.59	<b>500yr</b>

### Upper Confidence Limits

	5min	10min	15min	30min	60min	120min		1hr	2hr	3hr	6hr	12hr	24hr	48hr		1day	2day	4day	7day	10day	
<b>1yr</b>	0.29	0.44	0.54	0.72	0.89	1.09	<b>1yr</b>	0.77	1.06	1.26	1.74	2.20	3.02	3.16	<b>1yr</b>	2.67	3.04	3.61	4.40	5.09	<b>1yr</b>
<b>2yr</b>	0.34	0.52	0.64	0.86	1.07	1.27	<b>2yr</b>	0.92	1.24	1.48	1.96	2.51	3.45	3.71	<b>2yr</b>	3.06	3.57	4.10	4.86	5.68	<b>2yr</b>
<b>5yr</b>	0.40	0.62	0.77	1.05	1.34	1.62	<b>5yr</b>	1.15	1.59	1.88	2.53	3.24	4.37	4.97	<b>5yr</b>	3.87	4.78	5.41	6.39	7.17	<b>5yr</b>
<b>10yr</b>	0.47	0.72	0.89	1.25	1.61	1.98	<b>10yr</b>	1.39	1.93	2.28	3.10	3.93	5.38	6.19	<b>10yr</b>	4.76	5.96	6.79	7.85	8.76	<b>10yr</b>
<b>25yr</b>	0.58	0.88	1.09	1.56	2.05	2.57	<b>25yr</b>	1.77	2.51	2.95	4.06	5.12	7.86	8.30	<b>25yr</b>	6.95	7.98	9.07	10.33	11.41	<b>25yr</b>
<b>50yr</b>	0.67	1.02	1.27	1.83	2.46	3.13	<b>50yr</b>	2.12	3.06	3.59	4.98	6.27	9.84	10.38	<b>50yr</b>	8.71	9.98	11.30	12.71	13.95	<b>50yr</b>
<b>100yr</b>	0.79	1.19	1.49	2.16	2.96	3.81	<b>100yr</b>	2.55	3.73	4.36	6.13	7.69	12.31	12.97	<b>100yr</b>	10.90	12.47	14.07	15.65	17.05	<b>100yr</b>
<b>200yr</b>	0.92	1.39	1.76	2.55	3.55	4.65	<b>200yr</b>	3.07	4.55	5.32	7.55	9.44	15.45	16.23	<b>200yr</b>	13.67	15.61	17.54	19.27	20.86	<b>200yr</b>
<b>500yr</b>	1.14	1.70	2.19	3.18	4.52	6.04	<b>500yr</b>	3.90	5.90	6.90	9.97	12.40	20.87	21.84	<b>500yr</b>	18.47	21.00	23.47	25.36	27.25	<b>500yr</b>





(This Page Is Intentionally Blank)

**APPENDIX B**  
**PRE-DRAINAGE**

(This Page Is Intentionally Blank)

**PRE-DEVELOPMENT  
DRAINAGE**



**Routing Diagram for 477361-00\_PRE-&-POST\_2020-03-02**  
 Prepared by {enter your company name here}, Printed 3/4/2020  
 HydroCAD® 10.00-25 s/n 00866 © 2019 HydroCAD Software Solutions LLC



(This Page Is Intentionally Blank)

**477361-00\_PRE-&-POST\_2020-03-02**

Prepared by {enter your company name here}

Printed 3/4/2020

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Page 1

**Area Listing (selected nodes)**

Area (sq-ft)	CN	Description (subcatchment-numbers)
101,486	48	Brush, Good, HSG B (ES01, ES02, ES03, ES08, ES09)
393,326	65	Brush, Good, HSG C (ES01, ES02, ES04, ES05, ES06, ES07, ES08, ES09)
18,932	98	Paved parking, HSG C (ES03, ES04)
138,635	48	Power Line - Brush, Good, HSG B (ES01, ES02, ES03, ES09)
135,237	65	Power Line - Brush, Good, HSG C (ES01, ES02, ES03, ES08, ES09)
920,956	55	Woods, Good, HSG B (ES01, ES02, ES03, ES04, ES05, ES06, ES08, ES09)
1,288,885	70	Woods, Good, HSG C (ES01, ES02, ES03, ES04, ES05, ES06, ES07, ES08, ES09)
<b>2,997,457</b>	<b>63</b>	<b>TOTAL AREA</b>

**477361-00\_PRE-&-POST\_2020-03-02**

Prepared by {enter your company name here}

Printed 3/4/2020

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Page 2

**Soil Listing (selected nodes)**

Area (sq-ft)	Soil Group	Subcatchment Numbers
0	HSG A	
1,161,077	HSG B	ES01, ES02, ES03, ES04, ES05, ES06, ES08, ES09
1,836,380	HSG C	ES01, ES02, ES03, ES04, ES05, ES06, ES07, ES08, ES09
0	HSG D	
0	Other	
<b>2,997,457</b>		<b>TOTAL AREA</b>

**477361-00\_PRE-&-POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Pre-Development

Type III 24-hr 2-YR Rainfall=3.73"

Printed 3/4/2020

Page 3

Time span=0.00-24.00 hrs, dt=0.06 hrs, 401 points x 2  
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN  
 Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**Subcatchment ES01: ES-01** Runoff Area=57,405 sf 0.00% Impervious Runoff Depth>0.67"  
 Flow Length=415' Tc=53.2 min CN=61 Runoff=0.3 cfs 3,189 cf

**Subcatchment ES02: ES-02** Runoff Area=501,780 sf 0.00% Impervious Runoff Depth>0.45"  
 Flow Length=740' Tc=95.8 min CN=56 Runoff=1.2 cfs 18,634 cf

**Subcatchment ES03: ES-03** Runoff Area=502,327 sf 1.43% Impervious Runoff Depth>0.97"  
 Flow Length=800' Tc=40.5 min CN=67 Runoff=5.8 cfs 40,633 cf

**Subcatchment ES04: ES-04** Runoff Area=477,519 sf 2.46% Impervious Runoff Depth>1.02"  
 Flow Length=1,231' Tc=53.0 min CN=68 Runoff=5.1 cfs 40,654 cf

**Subcatchment ES05: ES-05** Runoff Area=117,705 sf 0.00% Impervious Runoff Depth>1.02"  
 Flow Length=350' Slope=0.0200 '/' Tc=43.1 min CN=68 Runoff=1.4 cfs 10,053 cf

**Subcatchment ES06: ES-06** Runoff Area=57,841 sf 0.00% Impervious Runoff Depth>0.97"  
 Flow Length=374' Tc=29.7 min CN=67 Runoff=0.8 cfs 4,695 cf

**Subcatchment ES07: ES-07** Runoff Area=42,503 sf 0.00% Impervious Runoff Depth>1.09"  
 Flow Length=250' Tc=27.5 min CN=69 Runoff=0.7 cfs 3,848 cf

**Subcatchment ES08: ES-08** Runoff Area=202,428 sf 0.00% Impervious Runoff Depth>1.03"  
 Flow Length=695' Tc=34.9 min CN=68 Runoff=2.7 cfs 17,334 cf

**Subcatchment ES09: ES-09** Runoff Area=1,037,949 sf 0.00% Impervious Runoff Depth>0.62"  
 Flow Length=1,835' Tc=75.9 min CN=60 Runoff=4.6 cfs 53,255 cf

**Reach ER01: ER-01** Avg. Flow Depth=0.03' Max Vel=0.25 fps Inflow=1.2 cfs 18,634 cf  
 n=0.050 L=537.0' S=0.0065 '/' Capacity=1,413.2 cfs Outflow=1.0 cfs 18,085 cf

**Reach ER02: ER02** Avg. Flow Depth=0.11' Max Vel=0.31 fps Inflow=5.1 cfs 50,841 cf  
 n=0.080 L=635.0' S=0.0058 '/' Capacity=703.8 cfs Outflow=3.8 cfs 49,004 cf

**Reach ER03: ER03** Avg. Flow Depth=0.02' Max Vel=0.20 fps Inflow=0.8 cfs 10,875 cf  
 n=0.080 L=981.0' S=0.0180 '/' Capacity=1,122.7 cfs Outflow=0.5 cfs 10,186 cf

**Reach ER04: ER-05** Avg. Flow Depth=0.08' Max Vel=0.44 fps Inflow=5.7 cfs 70,588 cf  
 n=0.080 L=682.0' S=0.0161 '/' Capacity=2,431.4 cfs Outflow=5.2 cfs 68,974 cf

**Pond EP01: CULVERT** Peak Elev=24.20' Storage=5,119 cf Inflow=12.0 cfs 176,696 cf  
 Primary=11.5 cfs 176,319 cf Secondary=0.0 cfs 0 cf Outflow=11.5 cfs 176,319 cf

**Pond EP02: EP02** Peak Elev=43.58' Storage=8,453 cf Inflow=2.7 cfs 18,596 cf  
 Outflow=0.8 cfs 10,875 cf

**Link EP01: Ex Pol-01** Inflow=11.5 cfs 176,319 cf  
 Primary=11.5 cfs 176,319 cf

**477361-00\_PRE-&-POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Pre-Development  
*Type III 24-hr 2-YR Rainfall=3.73"*

Printed 3/4/2020

Page 4

**Link EPol02: Ex Pol-02**

Inflow=0.3 cfs 3,189 cf  
Primary=0.3 cfs 3,189 cf

**Link EPol03: Proposed Wildlife Crossings**

Inflow=5.1 cfs 50,841 cf  
Primary=5.1 cfs 50,841 cf

**Total Runoff Area = 2,997,457 sf   Runoff Volume = 192,296 cf   Average Runoff Depth = 0.77"**  
**99.37% Pervious = 2,978,525 sf   0.63% Impervious = 18,932 sf**

Time span=0.00-24.00 hrs, dt=0.06 hrs, 401 points x 2  
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN  
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

<b>Subcatchment ES01: ES-01</b>	Runoff Area=57,405 sf 0.00% Impervious Runoff Depth>1.75" Flow Length=415' Tc=53.2 min CN=61 Runoff=1.1 cfs 8,366 cf
<b>Subcatchment ES02: ES-02</b>	Runoff Area=501,780 sf 0.00% Impervious Runoff Depth>1.35" Flow Length=740' Tc=95.8 min CN=56 Runoff=4.8 cfs 56,442 cf
<b>Subcatchment ES03: ES-03</b>	Runoff Area=502,327 sf 1.43% Impervious Runoff Depth>2.25" Flow Length=800' Tc=40.5 min CN=67 Runoff=14.6 cfs 94,062 cf
<b>Subcatchment ES04: ES-04</b>	Runoff Area=477,519 sf 2.46% Impervious Runoff Depth>2.32" Flow Length=1,231' Tc=53.0 min CN=68 Runoff=12.5 cfs 92,516 cf
<b>Subcatchment ES05: ES-05</b>	Runoff Area=117,705 sf 0.00% Impervious Runoff Depth>2.33" Flow Length=350' Slope=0.0200 '/ Tc=43.1 min CN=68 Runoff=3.5 cfs 22,865 cf
<b>Subcatchment ES06: ES-06</b>	Runoff Area=57,841 sf 0.00% Impervious Runoff Depth>2.25" Flow Length=374' Tc=29.7 min CN=67 Runoff=2.0 cfs 10,862 cf
<b>Subcatchment ES07: ES-07</b>	Runoff Area=42,503 sf 0.00% Impervious Runoff Depth>2.43" Flow Length=250' Tc=27.5 min CN=69 Runoff=1.6 cfs 8,597 cf
<b>Subcatchment ES08: ES-08</b>	Runoff Area=202,428 sf 0.00% Impervious Runoff Depth>2.34" Flow Length=695' Tc=34.9 min CN=68 Runoff=6.6 cfs 39,407 cf
<b>Subcatchment ES09: ES-09</b>	Runoff Area=1,037,949 sf 0.00% Impervious Runoff Depth>1.66" Flow Length=1,835' Tc=75.9 min CN=60 Runoff=14.8 cfs 143,476 cf
<b>Reach ER01: ER-01</b>	Avg. Flow Depth=0.08' Max Vel=0.42 fps Inflow=4.8 cfs 56,442 cf n=0.050 L=537.0' S=0.0065 '/ Capacity=1,413.2 cfs Outflow=4.5 cfs 55,208 cf
<b>Reach ER02: ER02</b>	Avg. Flow Depth=0.22' Max Vel=0.49 fps Inflow=13.9 cfs 125,703 cf n=0.080 L=635.0' S=0.0058 '/ Capacity=703.8 cfs Outflow=12.2 cfs 122,960 cf
<b>Reach ER03: ER03</b>	Avg. Flow Depth=0.07' Max Vel=0.42 fps Inflow=5.3 cfs 34,464 cf n=0.080 L=981.0' S=0.0180 '/ Capacity=1,122.7 cfs Outflow=3.0 cfs 33,187 cf
<b>Reach ER04: ER-05</b>	Avg. Flow Depth=0.16' Max Vel=0.70 fps Inflow=17.7 cfs 182,883 cf n=0.080 L=682.0' S=0.0161 '/ Capacity=2,431.4 cfs Outflow=17.1 cfs 179,807 cf
<b>Pond EP01: CULVERT</b>	Peak Elev=25.76' Storage=83,762 cf Inflow=39.3 cfs 452,036 cf Primary=21.8 cfs 451,376 cf Secondary=0.0 cfs 0 cf Outflow=21.8 cfs 451,376 cf
<b>Pond EP02: EP02</b>	Peak Elev=43.72' Storage=11,287 cf Inflow=6.7 cfs 42,324 cf Outflow=5.3 cfs 34,464 cf
<b>Link EP01: Ex Pol-01</b>	Inflow=21.8 cfs 451,376 cf Primary=21.8 cfs 451,376 cf

**477361-00\_PRE-&-POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Pre-Development  
*Type III 24-hr 10-YR Rainfall=5.65"*

Printed 3/4/2020

Page 6

**Link EPol02: Ex Pol-02**

Inflow=1.1 cfs 8,366 cf  
Primary=1.1 cfs 8,366 cf

**Link EPol03: Proposed Wildlife Crossings**

Inflow=13.9 cfs 125,703 cf  
Primary=13.9 cfs 125,703 cf

**Total Runoff Area = 2,997,457 sf   Runoff Volume = 476,593 cf   Average Runoff Depth = 1.91"**  
**99.37% Pervious = 2,978,525 sf   0.63% Impervious = 18,932 sf**

**477361-00\_PRE-&-POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Pre-Development

Type III 24-hr 25-YR Rainfall=7.16"

Printed 3/4/2020

Page 7

Time span=0.00-24.00 hrs, dt=0.06 hrs, 401 points x 2  
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN  
 Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**Subcatchment ES01: ES-01** Runoff Area=57,405 sf 0.00% Impervious Runoff Depth>2.78"  
 Flow Length=415' Tc=53.2 min CN=61 Runoff=1.8 cfs 13,302 cf

**Subcatchment ES02: ES-02** Runoff Area=501,780 sf 0.00% Impervious Runoff Depth>2.26"  
 Flow Length=740' Tc=95.8 min CN=56 Runoff=8.5 cfs 94,422 cf

**Subcatchment ES03: ES-03** Runoff Area=502,327 sf 1.43% Impervious Runoff Depth>3.40"  
 Flow Length=800' Tc=40.5 min CN=67 Runoff=22.5 cfs 142,514 cf

**Subcatchment ES04: ES-04** Runoff Area=477,519 sf 2.46% Impervious Runoff Depth>3.50"  
 Flow Length=1,231' Tc=53.0 min CN=68 Runoff=19.1 cfs 139,214 cf

**Subcatchment ES05: ES-05** Runoff Area=117,705 sf 0.00% Impervious Runoff Depth>3.51"  
 Flow Length=350' Slope=0.0200 '/' Tc=43.1 min CN=68 Runoff=5.3 cfs 34,398 cf

**Subcatchment ES06: ES-06** Runoff Area=57,841 sf 0.00% Impervious Runoff Depth>3.41"  
 Flow Length=374' Tc=29.7 min CN=67 Runoff=3.0 cfs 16,452 cf

**Subcatchment ES07: ES-07** Runoff Area=42,503 sf 0.00% Impervious Runoff Depth>3.63"  
 Flow Length=250' Tc=27.5 min CN=69 Runoff=2.4 cfs 12,840 cf

**Subcatchment ES08: ES-08** Runoff Area=202,428 sf 0.00% Impervious Runoff Depth>3.51"  
 Flow Length=695' Tc=34.9 min CN=68 Runoff=10.1 cfs 59,273 cf

**Subcatchment ES09: ES-09** Runoff Area=1,037,949 sf 0.00% Impervious Runoff Depth>2.66"  
 Flow Length=1,835' Tc=75.9 min CN=60 Runoff=24.9 cfs 230,355 cf

**Reach ER01: ER-01** Avg. Flow Depth=0.11' Max Vel=0.54 fps Inflow=8.5 cfs 94,422 cf  
 n=0.050 L=537.0' S=0.0065 '/' Capacity=1,413.2 cfs Outflow=8.2 cfs 92,827 cf

**Reach ER02: ER02** Avg. Flow Depth=0.31' Max Vel=0.59 fps Inflow=24.1 cfs 193,227 cf  
 n=0.080 L=635.0' S=0.0058 '/' Capacity=703.8 cfs Outflow=21.7 cfs 189,947 cf

**Reach ER03: ER03** Avg. Flow Depth=0.11' Max Vel=0.55 fps Inflow=9.1 cfs 55,735 cf  
 n=0.080 L=981.0' S=0.0180 '/' Capacity=1,122.7 cfs Outflow=6.2 cfs 54,013 cf

**Reach ER04: ER-05** Avg. Flow Depth=0.22' Max Vel=0.86 fps Inflow=29.3 cfs 289,628 cf  
 n=0.080 L=682.0' S=0.0161 '/' Capacity=2,431.4 cfs Outflow=28.6 cfs 285,926 cf

**Pond EP01: CULVERT** Peak Elev=26.20' Storage=163,831 cf Inflow=67.9 cfs 711,214 cf  
 Primary=23.9 cfs 618,854 cf Secondary=18.8 cfs 91,441 cf Outflow=42.7 cfs 710,295 cf

**Pond EP02: EP02** Peak Elev=43.81' Storage=13,224 cf Inflow=10.2 cfs 63,690 cf  
 Outflow=9.1 cfs 55,735 cf

**Link EP01: Ex Pol-01** Inflow=42.7 cfs 710,295 cf  
 Primary=42.7 cfs 710,295 cf



**477361-00\_PRE-&-POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Pre-Development

Type III 24-hr 25-YR Rainfall=7.16"

Printed 3/4/2020

Page 8

**Link EPol02: Ex Pol-02**

Inflow=1.8 cfs 13,302 cf  
Primary=1.8 cfs 13,302 cf

**Link EPol03: Proposed Wildlife Crossings**

Inflow=24.1 cfs 193,227 cf  
Primary=24.1 cfs 193,227 cf

**Total Runoff Area = 2,997,457 sf   Runoff Volume = 742,770 cf   Average Runoff Depth = 2.97"**  
**99.37% Pervious = 2,978,525 sf   0.63% Impervious = 18,932 sf**

**477361-00\_PRE-&-POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Pre-Development

Type III 24-hr 50-YR Rainfall=8.58"

Printed 3/4/2020

Page 9

Time span=0.00-24.00 hrs, dt=0.06 hrs, 401 points x 2  
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN  
 Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**Subcatchment ES01: ES-01** Runoff Area=57,405 sf 0.00% Impervious Runoff Depth>3.84"  
 Flow Length=415' Tc=53.2 min CN=61 Runoff=2.5 cfs 18,392 cf

**Subcatchment ES02: ES-02** Runoff Area=501,780 sf 0.00% Impervious Runoff Depth>3.22"  
 Flow Length=740' Tc=95.8 min CN=56 Runoff=12.6 cfs 134,614 cf

**Subcatchment ES03: ES-03** Runoff Area=502,327 sf 1.43% Impervious Runoff Depth>4.57"  
 Flow Length=800' Tc=40.5 min CN=67 Runoff=30.4 cfs 191,246 cf

**Subcatchment ES04: ES-04** Runoff Area=477,519 sf 2.46% Impervious Runoff Depth>4.67"  
 Flow Length=1,231' Tc=53.0 min CN=68 Runoff=25.6 cfs 186,014 cf

**Subcatchment ES05: ES-05** Runoff Area=117,705 sf 0.00% Impervious Runoff Depth>4.69"  
 Flow Length=350' Slope=0.0200 '/' Tc=43.1 min CN=68 Runoff=7.1 cfs 45,955 cf

**Subcatchment ES06: ES-06** Runoff Area=57,841 sf 0.00% Impervious Runoff Depth>4.58"  
 Flow Length=374' Tc=29.7 min CN=67 Runoff=4.1 cfs 22,075 cf

**Subcatchment ES07: ES-07** Runoff Area=42,503 sf 0.00% Impervious Runoff Depth>4.82"  
 Flow Length=250' Tc=27.5 min CN=69 Runoff=3.3 cfs 17,076 cf

**Subcatchment ES08: ES-08** Runoff Area=202,428 sf 0.00% Impervious Runoff Depth>4.69"  
 Flow Length=695' Tc=34.9 min CN=68 Runoff=13.5 cfs 79,179 cf

**Subcatchment ES09: ES-09** Runoff Area=1,037,949 sf 0.00% Impervious Runoff Depth>3.70"  
 Flow Length=1,835' Tc=75.9 min CN=60 Runoff=35.3 cfs 320,406 cf

**Reach ER01: ER-01** Avg. Flow Depth=0.14' Max Vel=0.62 fps Inflow=12.6 cfs 134,614 cf  
 n=0.050 L=537.0' S=0.0065 '/' Capacity=1,413.2 cfs Outflow=12.2 cfs 132,764 cf

**Reach ER02: ER02** Avg. Flow Depth=0.38' Max Vel=0.67 fps Inflow=34.4 cfs 261,044 cf  
 n=0.080 L=635.0' S=0.0058 '/' Capacity=703.8 cfs Outflow=31.4 cfs 257,296 cf

**Reach ER03: ER03** Avg. Flow Depth=0.14' Max Vel=0.64 fps Inflow=12.5 cfs 77,068 cf  
 n=0.080 L=981.0' S=0.0180 '/' Capacity=1,122.7 cfs Outflow=9.6 cfs 75,030 cf

**Reach ER04: ER-05** Avg. Flow Depth=0.28' Max Vel=0.98 fps Inflow=41.3 cfs 399,585 cf  
 n=0.080 L=682.0' S=0.0161 '/' Capacity=2,431.4 cfs Outflow=40.5 cfs 395,285 cf

**Pond EP01: CULVERT** Peak Elev=26.41' Storage=209,760 cf Inflow=97.6 cfs 976,590 cf  
 Primary=24.9 cfs 717,300 cf Secondary=45.5 cfs 258,096 cf Outflow=70.4 cfs 975,396 cf

**Pond EP02: EP02** Peak Elev=43.88' Storage=14,875 cf Inflow=13.7 cfs 85,106 cf  
 Outflow=12.5 cfs 77,068 cf

**Link EP01: Ex Pol-01** Inflow=70.4 cfs 975,396 cf  
 Primary=70.4 cfs 975,396 cf

**477361-00\_PRE-&-POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Pre-Development  
*Type III 24-hr 50-YR Rainfall=8.58"*

Printed 3/4/2020

Page 10

**Link EPol02: Ex Pol-02**

Inflow=2.5 cfs 18,392 cf  
Primary=2.5 cfs 18,392 cf

**Link EPol03: Proposed Wildlife Crossings**

Inflow=34.4 cfs 261,044 cf  
Primary=34.4 cfs 261,044 cf

**Total Runoff Area = 2,997,457 sf   Runoff Volume = 1,014,957 cf   Average Runoff Depth = 4.06"**  
**99.37% Pervious = 2,978,525 sf   0.63% Impervious = 18,932 sf**

**APPENDIX C**  
**PRE-DRAINAGE**  
**(10 Yr Storm Event)**

(This Page Is Intentionally Blank)

**477361-00\_PRE-&POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Pre-Development (10 yr)  
Type III 24-hr 10-YR Rainfall=5.65"

Printed 3/4/2020

Page 1

**Summary for Subcatchment ES01: ES-01**

Runoff = 1.1 cfs @ 12.78 hrs, Volume= 8,366 cf, Depth> 1.75"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs  
Type III 24-hr 10-YR Rainfall=5.65"

Area (sf)	CN	Description
9,442	55	Woods, Good, HSG B
122	48	Brush, Good, HSG B
* 13,602	48	Power Line - Brush, Good, HSG B
16,200	70	Woods, Good, HSG C
7,778	65	Brush, Good, HSG C
10,261	65	Power Line - Brush, Good, HSG C
57,405	61	Weighted Average
57,405		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
49.1	100	0.0100	0.03		<b>Sheet Flow, Sheet-Flow</b> Woods: Dense underbrush n= 0.800 P2= 3.23"
3.4	205	0.0400	1.00		<b>Shallow Concentrated Flow, Shallow Concentrated</b> Woodland Kv= 5.0 fps
0.7	110	0.0100	2.68	374.84	<b>Channel Flow, Channel Flow</b> Area= 140.0 sf Perim= 80.9' r= 1.73' n= 0.080 Earth, long dense weeds
53.2	415	Total			

**Summary for Subcatchment ES02: ES-02**

Runoff = 4.8 cfs @ 13.43 hrs, Volume= 56,442 cf, Depth> 1.35"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs  
Type III 24-hr 10-YR Rainfall=5.65"

Area (sf)	CN	Description
209,453	55	Woods, Good, HSG B
82,831	48	Brush, Good, HSG B
53,777	48	Power Line - Brush, Good, HSG B
21,794	70	Woods, Good, HSG C
126,184	65	Brush, Good, HSG C
7,741	65	Power Line - Brush, Good, HSG C
501,780	56	Weighted Average
501,780		100.00% Pervious Area

**477361-00\_PRE-&-POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Pre-Development (10 yr)  
Type III 24-hr 10-YR Rainfall=5.65"

Printed 3/4/2020

Page 2

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
37.2	100	0.0200	0.04		<b>Sheet Flow, Shallow</b> Woods: Dense underbrush n= 0.800 P2= 3.23"
58.0	550	0.0010	0.16		<b>Shallow Concentrated Flow, Shallow Channel</b> Woodland Kv= 5.0 fps
0.6	90	0.0100	2.41	714.05	<b>Channel Flow, Concentrated</b> Area= 296.0 sf Perim= 200.0' r= 1.48' n= 0.080 Earth, long dense weeds
95.8	740	Total			

**Summary for Subcatchment ES03: ES-03**

Runoff = 14.6 cfs @ 12.59 hrs, Volume= 94,062 cf, Depth> 2.25"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs  
Type III 24-hr 10-YR Rainfall=5.65"

Area (sf)	CN	Description
66,527	55	Woods, Good, HSG B
16,804	48	Brush, Good, HSG B
844	48	Power Line - Brush, Good, HSG B
7,176	98	Paved parking, HSG C
109,654	70	Woods, Good, HSG C
229,477	70	Woods, Good, HSG C
71,845	65	Power Line - Brush, Good, HSG C
502,327	67	Weighted Average
495,151		98.57% Pervious Area
7,176		1.43% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
28.2	100	0.0400	0.06		<b>Sheet Flow, Sheet Flow</b> Woods: Dense underbrush n= 0.800 P2= 3.23"
12.3	700	0.0360	0.95		<b>Shallow Concentrated Flow, Shallow Flow</b> Woodland Kv= 5.0 fps
40.5	800	Total			

**Summary for Subcatchment ES04: ES-04**

Runoff = 12.5 cfs @ 12.76 hrs, Volume= 92,516 cf, Depth> 2.32"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs  
Type III 24-hr 10-YR Rainfall=5.65"

**477361-00\_PRE-&-POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Pre-Development (10 yr)  
Type III 24-hr 10-YR Rainfall=5.65"

Printed 3/4/2020

Page 3

Area (sf)	CN	Description
0	98	Paved parking, HSG B
19,701	55	Woods, Good, HSG B
0	48	Brush, Good, HSG B
11,756	98	Paved parking, HSG C
284,228	70	Woods, Good, HSG C
161,834	65	Brush, Good, HSG C
477,519	68	Weighted Average
465,763		97.54% Pervious Area
11,756		2.46% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
37.2	100	0.0200	0.04		<b>Sheet Flow, Sheet Flow</b> Woods: Dense underbrush n= 0.800 P2= 3.23"
9.7	421	0.0210	0.72		<b>Shallow Concentrated Flow, Shallow Flow</b> Woodland Kv= 5.0 fps
6.1	710	0.0070	1.95	699.40	<b>Channel Flow, Channel Flow</b> Area= 358.0 sf Perim= 254.0' r= 1.41' n= 0.080 Earth, long dense weeds
53.0	1,231	Total			

**Summary for Subcatchment ES05: ES-05**

Runoff = 3.5 cfs @ 12.62 hrs, Volume= 22,865 cf, Depth> 2.33"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs  
Type III 24-hr 10-YR Rainfall=5.65"

Area (sf)	CN	Description
9,092	55	Woods, Good, HSG B
91,250	70	Woods, Good, HSG C
17,363	65	Brush, Good, HSG C
117,705	68	Weighted Average
117,705		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
37.2	100	0.0200	0.04		<b>Sheet Flow, Sheet Flow</b> Woods: Dense underbrush n= 0.800 P2= 3.23"
5.9	250	0.0200	0.71		<b>Shallow Concentrated Flow, Shallow Channel</b> Woodland Kv= 5.0 fps
43.1	350	Total			



**477361-00\_PRE-&POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Pre-Development (10 yr)

Type III 24-hr 10-YR Rainfall=5.65"

Printed 3/4/2020

Page 4

**Summary for Subcatchment ES06: ES-06**

Runoff = 2.0 cfs @ 12.44 hrs, Volume= 10,862 cf, Depth&gt; 2.25"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs  
Type III 24-hr 10-YR Rainfall=5.65"

Area (sf)	CN	Description
8,412	55	Woods, Good, HSG B
44,689	70	Woods, Good, HSG C
4,740	65	Brush, Good, HSG C
57,841	67	Weighted Average
57,841		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
25.8	100	0.0500	0.06		<b>Sheet Flow, Sheet Flow</b> Woods: Dense underbrush n= 0.800 P2= 3.23"
3.9	274	0.0550	1.17		<b>Shallow Concentrated Flow, Shallow Channel</b> Woodland Kv= 5.0 fps
29.7	374	Total			

**Summary for Subcatchment ES07: ES-07**

Runoff = 1.6 cfs @ 12.40 hrs, Volume= 8,597 cf, Depth&gt; 2.43"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs  
Type III 24-hr 10-YR Rainfall=5.65"

Area (sf)	CN	Description
37,671	70	Woods, Good, HSG C
4,832	65	Brush, Good, HSG C
42,503	69	Weighted Average
42,503		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
24.0	100	0.0600	0.07		<b>Sheet Flow, Sheet Flow</b> Woods: Dense underbrush n= 0.800 P2= 3.23"
3.5	150	0.0200	0.71		<b>Shallow Concentrated Flow, Shallow Channel</b> Woodland Kv= 5.0 fps
27.5	250	Total			

**Summary for Subcatchment ES08: ES-08**

Runoff = 6.6 cfs @ 12.51 hrs, Volume= 39,407 cf, Depth&gt; 2.34"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs  
Type III 24-hr 10-YR Rainfall=5.65"

**477361-00\_PRE-&POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Pre-Development (10 yr)  
Type III 24-hr 10-YR Rainfall=5.65"

Printed 3/4/2020

Page 5

Area (sf)	CN	Description
15,357	55	Woods, Good, HSG B
3	48	Brush, Good, HSG B
137,613	70	Woods, Good, HSG C
43,258	65	Brush, Good, HSG C
6,197	65	Power Line - Brush, Good, HSG C
202,428	68	Weighted Average
202,428		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
25.8	100	0.0500	0.06		<b>Sheet Flow, Sheet Flow</b> Woods: Dense underbrush n= 0.800 P2= 3.23"
8.7	505	0.0378	0.97		<b>Shallow Concentrated Flow, Shallow Channel</b> Woodland Kv= 5.0 fps
0.4	90	0.0156	3.35	1,072.87	<b>Channel Flow, Channel Flow</b> Area= 320.0 sf Perim= 184.2' r= 1.74' n= 0.080 Earth, long dense weeds
34.9	695	Total			

**Summary for Subcatchment ES09: ES-09**

Runoff = 14.8 cfs @ 13.10 hrs, Volume= 143,476 cf, Depth> 1.66"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs  
Type III 24-hr 10-YR Rainfall=5.65"

Area (sf)	CN	Description
582,972	55	Woods, Good, HSG B
1,726	48	Brush, Good, HSG B
70,412	48	Power Line - Brush, Good, HSG B
316,309	70	Woods, Good, HSG C
27,337	65	Brush, Good, HSG C
39,193	65	Power Line - Brush, Good, HSG C
1,037,949	60	Weighted Average
1,037,949		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
31.6	100	0.0300	0.05		<b>Sheet Flow, Sheet Flow</b> Woods: Dense underbrush n= 0.800 P2= 3.23"
15.1	808	0.0320	0.89		<b>Shallow Concentrated Flow, Shallow Channel</b> Woodland Kv= 5.0 fps
27.1	515	0.0040	0.32		<b>Shallow Concentrated Flow, Shallow Channel</b> Woodland Kv= 5.0 fps
2.1	412	0.0170	3.28	594.29	<b>Channel Flow, Channel Flow</b> Area= 181.4 sf Perim= 115.3' r= 1.57' n= 0.080 Earth, long dense weeds
75.9	1,835	Total			

Summary for Reach ER01: ER-01

Inflow Area = 501,780 sf, 0.00% Impervious, Inflow Depth > 1.35" for 10-YR event  
Inflow = 4.8 cfs @ 13.43 hrs, Volume= 56,442 cf  
Outflow = 4.5 cfs @ 13.70 hrs, Volume= 55,208 cf, Atten= 6%, Lag= 15.9 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs / 2  
Max. Velocity= 0.42 fps, Min. Travel Time= 21.1 min  
Avg. Velocity = 0.24 fps, Avg. Travel Time= 36.7 min

Peak Storage= 5,651 cf @ 13.70 hrs  
Average Depth at Peak Storage= 0.08' , Surface Width= 142.58'  
Bank-Full Depth= 2.00' Flow Area= 470.0 sf, Capacity= 1,413.2 cfs

135.00' x 2.00' deep channel, n= 0.050 Scattered brush, heavy weeds  
Side Slope Z-value= 50.0 ' / ' Top Width= 335.00'  
Length= 537.0' Slope= 0.0065 ' / '  
Inlet Invert= 26.50', Outlet Invert= 23.00'



Summary for Reach ER02: ER02

Inflow Area = 695,568 sf, 1.69% Impervious, Inflow Depth > 2.17" for 10-YR event  
Inflow = 13.9 cfs @ 12.85 hrs, Volume= 125,703 cf  
Outflow = 12.2 cfs @ 13.10 hrs, Volume= 122,960 cf, Atten= 12%, Lag= 15.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs / 2  
Max. Velocity= 0.49 fps, Min. Travel Time= 21.8 min  
Avg. Velocity = 0.23 fps, Avg. Travel Time= 45.6 min

Peak Storage= 16,021 cf @ 13.10 hrs  
Average Depth at Peak Storage= 0.22' , Surface Width= 125.94'  
Bank-Full Depth= 2.00' Flow Area= 408.0 sf, Capacity= 703.8 cfs

104.00' x 2.00' deep channel, n= 0.080 Earth, long dense weeds  
Side Slope Z-value= 50.0 ' / ' Top Width= 304.00'  
Length= 635.0' Slope= 0.0058 ' / '  
Inlet Invert= 25.70', Outlet Invert= 22.00'



Summary for Reach ER03: ER03

Inflow Area = 218,049 sf, 0.00% Impervious, Inflow Depth > 1.90" for 10-YR event  
Inflow = 5.3 cfs @ 12.77 hrs, Volume= 34,464 cf  
Outflow = 3.0 cfs @ 13.26 hrs, Volume= 33,187 cf, Atten= 42%, Lag= 29.4 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs / 2  
Max. Velocity= 0.42 fps, Min. Travel Time= 39.3 min  
Avg. Velocity = 0.24 fps, Avg. Travel Time= 69.4 min

Peak Storage= 7,178 cf @ 13.26 hrs  
Average Depth at Peak Storage= 0.07' , Surface Width= 109.15'  
Bank-Full Depth= 2.00' Flow Area= 358.0 sf, Capacity= 1,122.7 cfs

104.00' x 2.00' deep channel, n= 0.080 Earth, long dense weeds  
Side Slope Z-value= 50.0 25.0 '/' Top Width= 254.00'  
Length= 981.0' Slope= 0.0180 '/'  
Inlet Invert= 43.50', Outlet Invert= 25.80'




Summary for Reach ER04: ER-05

Inflow Area = 1,240,377 sf, 0.00% Impervious, Inflow Depth > 1.77" for 10-YR event  
Inflow = 17.7 cfs @ 12.99 hrs, Volume= 182,883 cf  
Outflow = 17.1 cfs @ 13.17 hrs, Volume= 179,807 cf, Atten= 4%, Lag= 11.1 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs / 2  
Max. Velocity= 0.70 fps, Min. Travel Time= 16.2 min  
Avg. Velocity = 0.35 fps, Avg. Travel Time= 32.8 min

Peak Storage= 16,575 cf @ 13.17 hrs  
Average Depth at Peak Storage= 0.16' , Surface Width= 150.78'  
Bank-Full Depth= 3.00' Flow Area= 569.4 sf, Capacity= 2,431.4 cfs

146.00' x 3.00' deep channel, n= 0.080 Earth, long dense weeds  
Side Slope Z-value= 17.0 12.2 '/' Top Width= 233.60'  
Length= 682.0' Slope= 0.0161 '/'  
Inlet Invert= 33.00', Outlet Invert= 22.00'



**Summary for Pond EP01: CULVERT**

[62] Hint: Exceeded Reach ER01 OUTLET depth by 2.69' @ 14.22 hrs  
 [62] Hint: Exceeded Reach ER02 OUTLET depth by 3.62' @ 14.34 hrs  
 [62] Hint: Exceeded Reach ER04 OUTLET depth by 3.65' @ 14.28 hrs

Inflow Area = 2,940,052 sf, 0.64% Impervious, Inflow Depth > 1.85" for 10-YR event  
 Inflow = 39.3 cfs @ 13.05 hrs, Volume= 452,036 cf  
 Outflow = 21.8 cfs @ 14.17 hrs, Volume= 451,376 cf, Atten= 44%, Lag= 67.3 min  
 Primary = 21.8 cfs @ 14.17 hrs, Volume= 451,376 cf  
 Secondary = 0.0 cfs @ 0.00 hrs, Volume= 0 cf

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs / 2  
 Peak Elev= 25.76' @ 14.17 hrs Surf.Area= 144,280 sf Storage= 83,762 cf

Plug-Flow detention time= 32.9 min calculated for 450,251 cf (100% of inflow)  
 Center-of-Mass det. time= 32.1 min ( 950.8 - 918.7 )

Volume	Invert	Avail.Storage	Storage Description			
#1	22.00'	349,966 cf	<b>Custom Stage Data (Irregular)</b> Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)	
22.00	10	40.0	0	0	10	
24.00	5,297	274.3	3,691	3,691	5,879	
25.00	33,326	789.9	17,303	20,995	49,546	
26.00	194,732	2,359.1	102,872	123,867	442,774	
27.00	258,992	2,650.0	226,100	349,966	558,757	

Device	Routing	Invert	Outlet Devices
#1	Primary	22.40'	<b>15.0" Round RCP_Round 15"</b> L= 33.5' RCP, groove end projecting, Ke= 0.200 Inlet / Outlet Invert= 22.40' / 22.35' S= 0.0015 '/ Cc= 0.900 n= 0.011 Concrete pipe, straight & clean, Flow Area= 1.23 sf
#2	Primary	22.40'	<b>15.0" Round RCP_Round 15"</b> L= 33.5' RCP, groove end projecting, Ke= 0.200 Inlet / Outlet Invert= 22.40' / 22.35' S= 0.0015 '/ Cc= 0.900 n= 0.011 Concrete pipe, straight & clean, Flow Area= 1.23 sf
#3	Secondary	25.93'	<b>50.0' long x 20.0' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63

**Primary OutFlow** Max=21.8 cfs @ 14.17 hrs HW=25.76' TW=0.00' (Dynamic Tailwater)

- ↑1=RCP\_Round 15" (Barrel Controls 10.9 cfs @ 8.90 fps)
- ↑2=RCP\_Round 15" (Barrel Controls 10.9 cfs @ 8.90 fps)

**Secondary OutFlow** Max=0.0 cfs @ 0.00 hrs HW=22.00' TW=0.00' (Dynamic Tailwater)

- ↑3=Broad-Crested Rectangular Weir ( Controls 0.0 cfs)

**477361-00\_PRE-&POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Pre-Development (10 yr)  
Type III 24-hr 10-YR Rainfall=5.65"

Printed 3/4/2020

Page 9

**Summary for Pond EP02: EP02**

Inflow Area = 218,049 sf, 0.00% Impervious, Inflow Depth > 2.33" for 10-YR event  
Inflow = 6.7 cfs @ 12.50 hrs, Volume= 42,324 cf  
Outflow = 5.3 cfs @ 12.77 hrs, Volume= 34,464 cf, Atten= 21%, Lag= 16.1 min  
Primary = 5.3 cfs @ 12.77 hrs, Volume= 34,464 cf

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs / 2  
Peak Elev= 43.72' @ 12.78 hrs Surf.Area= 21,559 sf Storage= 11,287 cf

Plug-Flow detention time= 117.4 min calculated for 34,464 cf (81% of inflow)  
Center-of-Mass det. time= 44.3 min ( 913.8 - 869.5 )

Volume	Invert	Avail.Storage	Storage Description			
#1	43.00'	17,987 cf	<b>Custom Stage Data (Irregular)</b> Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)	
43.00	10,339	760.4	0	0	10,339	
44.00	26,935	899.1	17,987	17,987	28,674	

Device	Routing	Invert	Outlet Devices							
#1	Primary	43.53'	<b>25.0' long x 10.0' breadth Broad-Crested Rectangular Weir</b>							
			Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60							
			Coef. (English) 2.49 2.56 2.70 2.69 2.68 2.69 2.67 2.64							

**Primary OutFlow** Max=5.2 cfs @ 12.77 hrs HW=43.72' TW=43.54' (Dynamic Tailwater)  
↑1=**Broad-Crested Rectangular Weir** (Weir Controls 5.2 cfs @ 1.09 fps)

**Summary for Link EP01: Ex Pol-01**

Inflow Area = 2,940,052 sf, 0.64% Impervious, Inflow Depth > 1.84" for 10-YR event  
Inflow = 21.8 cfs @ 14.17 hrs, Volume= 451,376 cf  
Primary = 21.8 cfs @ 14.17 hrs, Volume= 451,376 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs

**Summary for Link EP02: Ex Pol-02**

Inflow Area = 57,405 sf, 0.00% Impervious, Inflow Depth > 1.75" for 10-YR event  
Inflow = 1.1 cfs @ 12.78 hrs, Volume= 8,366 cf  
Primary = 1.1 cfs @ 12.78 hrs, Volume= 8,366 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs

**Summary for Link EPol03: Proposed Wildlife Crossings**

Inflow Area = 695,568 sf, 1.69% Impervious, Inflow Depth > 2.17" for 10-YR event  
Inflow = 13.9 cfs @ 12.85 hrs, Volume= 125,703 cf  
Primary = 13.9 cfs @ 12.85 hrs, Volume= 125,703 cf, Atten= 0%, Lag= 0.0 min




Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs

**APPENDIX D**  
**POST DRAINAGE**



(This Page Is Intentionally Blank)

**POST DEVELOPMENT  
DRAINAGE**



**Routing Diagram for 477361-00\_PRE-&-POST\_2020-03-02**  
 Prepared by {enter your company name here}, Printed 3/4/2020  
 HydroCAD® 10.00-25 s/n 00866 © 2019 HydroCAD Software Solutions LLC

(This Page Is Intentionally Blank)

**477361-00\_PRE-&-POST\_2020-03-02**

Prepared by {enter your company name here}

Printed 3/4/2020

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Page 1

**Area Listing (selected nodes)**

Area (sq-ft)	CN	Description (subcatchment-numbers)
41,015	61	>75% Grass cover, Good, HSG B (PS03, PS05, PS06, PS08, PS09, PS10, PS11, PS12, PS13, PS17, PS18, PS19, PS22)
167,029	74	>75% Grass cover, Good, HSG C (PS03, PS04, PS05, PS06, PS07, PS08, PS09, PS10, PS11, PS12, PS13, PS14, PS15, PS16, PS17, PS18, PS19, PS20, PS21, PS22)
101,365	48	Brush, Good, HSG B (PS01, PS02, PS03, PS09)
618,870	65	Brush, Good, HSG C (PS01, PS02, PS03, PS04, PS05, PS06, PS07, PS08, PS09)
16,298	98	Paved parking, HSG B (PS03, PS09, PS10, PS11, PS12, PS13, PS17, PS18, PS19, PS20, PS21, PS22)
60,995	98	Paved parking, HSG C (PS03, PS04, PS05, PS06, PS08, PS09, PS10, PS11, PS12, PS13, PS14, PS15, PS16, PS17, PS18, PS19, PS20, PS21, PS22)
138,638	48	Power Line - Brush, Good, HSG B (PS01, PS02, PS03, PS08, PS09)
135,237	65	Power Line - Brush, Good, HSG C (PS01, PS02, PS03, PS08, PS09)
12,388	98	Roofs, HSG B (PS03, PS05, PS06, PS08, PS09, PS10, PS11, PS17, PS19)
28,996	98	Roofs, HSG C (PS03, PS04, PS05, PS06, PS07, PS08, PS09, PS10, PS11, PS14, PS16, PS17, PS18, PS19)
847,317	55	Woods, Good, HSG B (PS01, PS02, PS03, PS04, PS05, PS06, PS08, PS09)
806,253	70	Woods, Good, HSG C (PS01, PS02, PS03, PS04, PS05, PS06, PS07, PS08, PS09)
4,054	58	Woods/grass comb., Good, HSG B (PS06, PS12, PS13, PS18, PS19)
19,002	72	Woods/grass comb., Good, HSG C (PS03, PS04, PS06, PS07, PS08, PS12, PS13, PS14, PS15, PS18, PS19, PS20, PS21)
<b>2,997,457</b>	<b>64</b>	<b>TOTAL AREA</b>

**477361-00\_PRE-&-POST\_2020-03-02**

Prepared by {enter your company name here}

Printed 3/4/2020

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Page 2

**Soil Listing (selected nodes)**

Area (sq-ft)	Soil Group	Subcatchment Numbers
0	HSG A	
1,161,075	HSG B	PS01, PS02, PS03, PS04, PS05, PS06, PS08, PS09, PS10, PS11, PS12, PS13, PS17, PS18, PS19, PS20, PS21, PS22
1,836,382	HSG C	PS01, PS02, PS03, PS04, PS05, PS06, PS07, PS08, PS09, PS10, PS11, PS12, PS13, PS14, PS15, PS16, PS17, PS18, PS19, PS20, PS21, PS22
0	HSG D	
0	Other	
<b>2,997,457</b>		<b>TOTAL AREA</b>

**477361-00\_PRE-&-POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Post Development  
Type III 24-hr 2-YR Rainfall=3.73"

Printed 3/4/2020

Page 3

Time span=0.00-24.00 hrs, dt=0.06 hrs, 401 points x 2  
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN  
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

<b>Subcatchment PS01: PS-01</b>	Runoff Area=57,405 sf 0.00% Impervious Runoff Depth>0.67" Flow Length=415' Tc=53.2 min CN=61 Runoff=0.3 cfs 3,189 cf
<b>Subcatchment PS02: PS-02</b>	Runoff Area=501,780 sf 0.00% Impervious Runoff Depth>0.45" Flow Length=740' Tc=95.8 min CN=56 Runoff=1.2 cfs 18,634 cf
<b>Subcatchment PS03: ES-03</b>	Runoff Area=483,638 sf 3.20% Impervious Runoff Depth>0.86" Flow Length=800' Tc=40.5 min CN=65 Runoff=4.8 cfs 34,855 cf
<b>Subcatchment PS04: PS-04</b>	Runoff Area=460,441 sf 3.70% Impervious Runoff Depth>1.08" Flow Length=1,231' Tc=52.0 min CN=69 Runoff=5.3 cfs 41,377 cf
<b>Subcatchment PS05: PS-05</b>	Runoff Area=117,283 sf 8.10% Impervious Runoff Depth>1.26" Flow Length=375' Tc=41.3 min CN=72 Runoff=1.9 cfs 12,318 cf
<b>Subcatchment PS06: PS-06</b>	Runoff Area=63,674 sf 8.10% Impervious Runoff Depth>1.27" Flow Length=337' Tc=16.9 min CN=72 Runoff=1.5 cfs 6,733 cf
<b>Subcatchment PS07: PS-07</b>	Runoff Area=32,586 sf 5.06% Impervious Runoff Depth>1.20" Flow Length=316' Tc=28.1 min CN=71 Runoff=0.6 cfs 3,269 cf
<b>Subcatchment PS08: PS-08</b>	Runoff Area=155,960 sf 3.58% Impervious Runoff Depth>1.15" Flow Length=599' Tc=13.3 min CN=70 Runoff=3.5 cfs 14,937 cf
<b>Subcatchment PS09: PS-09</b>	Runoff Area=1,008,725 sf 0.85% Impervious Runoff Depth>0.62" Flow Length=1,835' Tc=75.9 min CN=60 Runoff=4.4 cfs 51,755 cf
<b>Subcatchment PS10: PS-10</b>	Runoff Area=32,468 sf 52.74% Impervious Runoff Depth>2.21" Flow Length=483' Tc=13.2 min CN=85 Runoff=1.5 cfs 5,988 cf
<b>Subcatchment PS11: PS-11</b>	Runoff Area=12,159 sf 58.76% Impervious Runoff Depth>2.22" Flow Length=452' Tc=7.5 min CN=85 Runoff=0.7 cfs 2,245 cf
<b>Subcatchment PS12: PS-12</b>	Runoff Area=4,911 sf 36.61% Impervious Runoff Depth>1.60" Flow Length=139' Tc=5.0 min CN=77 Runoff=0.2 cfs 656 cf
<b>Subcatchment PS13: PS-13</b>	Runoff Area=4,559 sf 39.96% Impervious Runoff Depth>1.97" Flow Length=139' Tc=5.0 min CN=82 Runoff=0.2 cfs 750 cf
<b>Subcatchment PS14: PS-14</b>	Runoff Area=5,051 sf 20.97% Impervious Runoff Depth>1.67" Flow Length=96' Tc=5.0 min CN=78 Runoff=0.2 cfs 704 cf
<b>Subcatchment PS15: PS-15</b>	Runoff Area=4,235 sf 19.50% Impervious Runoff Depth>1.67" Flow Length=96' Tc=5.0 min CN=78 Runoff=0.2 cfs 590 cf
<b>Subcatchment PS16: PS-16</b>	Runoff Area=8,958 sf 58.47% Impervious Runoff Depth>2.48" Flow Length=117' Tc=5.6 min CN=88 Runoff=0.6 cfs 1,850 cf

**477361-00\_PRE-&-POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Post Development

Type III 24-hr 2-YR Rainfall=3.73"

Printed 3/4/2020

Page 4

<b>Subcatchment PS17: PS-17</b>	Runoff Area=12,705 sf 47.10% Impervious Runoff Depth>2.13" Flow Length=166' Tc=7.3 min CN=84 Runoff=0.7 cfs 2,258 cf
<b>Subcatchment PS18: PS-18</b>	Runoff Area=7,913 sf 43.27% Impervious Runoff Depth>1.90" Flow Length=124' Tc=5.0 min CN=81 Runoff=0.4 cfs 1,250 cf
<b>Subcatchment PS19: PS-19</b>	Runoff Area=7,620 sf 43.87% Impervious Runoff Depth>1.90" Flow Length=164' Tc=5.0 min CN=81 Runoff=0.4 cfs 1,204 cf
<b>Subcatchment PS20: PS-20</b>	Runoff Area=3,773 sf 66.10% Impervious Runoff Depth>2.57" Flow Length=128' Tc=5.0 min CN=89 Runoff=0.3 cfs 808 cf
<b>Subcatchment PS21: PS-21</b>	Runoff Area=3,612 sf 69.10% Impervious Runoff Depth>2.66" Flow Length=124' Tc=5.0 min CN=90 Runoff=0.3 cfs 801 cf
<b>Subcatchment PS22: PS-22</b>	Runoff Area=8,001 sf 37.17% Impervious Runoff Depth>1.47" Flow Length=128' Slope=0.0250 '/' Tc=5.0 min CN=75 Runoff=0.3 cfs 977 cf
<b>Reach 2R: PR-05</b>	Avg. Flow Depth=0.01' Max Vel=0.05 fps Inflow=0.0 cfs 444 cf n=0.100 L=1,100.0' S=0.0050 '/' Capacity=60.8 cfs Outflow=0.0 cfs 246 cf
<b>Reach PR01: PR-01</b>	Avg. Flow Depth=0.03' Max Vel=0.25 fps Inflow=1.2 cfs 18,634 cf n=0.050 L=537.0' S=0.0065 '/' Capacity=1,413.2 cfs Outflow=1.0 cfs 18,085 cf
<b>Reach PR02: PR02</b>	Avg. Flow Depth=0.10' Max Vel=0.45 fps Inflow=5.6 cfs 67,739 cf n=0.050 L=668.0' S=0.0055 '/' Capacity=1,097.9 cfs Outflow=4.7 cfs 66,004 cf
<b>Reach PR03: PR03</b>	Avg. Flow Depth=0.04' Max Vel=0.29 fps Inflow=2.0 cfs 21,412 cf n=0.080 L=894.0' S=0.0187 '/' Capacity=1,142.3 cfs Outflow=1.2 cfs 20,585 cf
<b>Reach PR04: PR-04</b>	Avg. Flow Depth=0.07' Max Vel=0.40 fps Inflow=4.4 cfs 65,359 cf n=0.080 L=682.0' S=0.0161 '/' Capacity=2,431.4 cfs Outflow=4.0 cfs 63,780 cf
<b>Reach PR05a: PR-05</b>	Avg. Flow Depth=0.00' Max Vel=0.00 fps Inflow=0.0 cfs 0 cf n=0.100 L=46.0' S=0.0152 '/' Capacity=106.1 cfs Outflow=0.0 cfs 0 cf
<b>Reach PR05b: PR-05</b>	Avg. Flow Depth=0.02' Max Vel=0.18 fps Inflow=0.1 cfs 4,207 cf n=0.100 L=46.0' S=0.0326 '/' Capacity=155.3 cfs Outflow=0.1 cfs 4,186 cf
<b>Reach PR06: PR-06</b>	Avg. Flow Depth=0.06' Max Vel=0.15 fps Inflow=0.3 cfs 6,962 cf n=0.100 L=193.0' S=0.0047 '/' Capacity=58.7 cfs Outflow=0.3 cfs 6,874 cf
<b>Reach PR07: PR-07</b>	Avg. Flow Depth=0.09' Max Vel=0.47 fps Inflow=4.4 cfs 51,822 cf n=0.080 L=682.0' S=0.0161 '/' Capacity=992.5 cfs Outflow=3.9 cfs 50,421 cf
<b>Pond 1P: (new Pond)</b>	Peak Elev=26.57' Inflow=0.3 cfs 808 cf Outflow=0.3 cfs 808 cf
<b>Pond 2P: (new Pond)</b>	Peak Elev=26.57' Inflow=0.3 cfs 801 cf Outflow=0.3 cfs 801 cf

**477361-00\_PRE-&-POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Post Development

Type III 24-hr 2-YR Rainfall=3.73"

Printed 3/4/2020

Page 5

<b>Pond CB01: CB-01</b>	Peak Elev=32.54' Inflow=0.4 cfs 1,250 cf 12.0" Round Culvert n=0.013 L=12.0' S=0.0125 '/' Outflow=0.4 cfs 1,250 cf
<b>Pond CB02: CB-02</b>	Peak Elev=32.47' Inflow=0.4 cfs 1,204 cf 22.0" Round Culvert n=0.013 L=12.0' S=0.0125 '/' Outflow=0.4 cfs 1,204 cf
<b>Pond CB03: CB-03</b>	Peak Elev=41.38' Inflow=0.6 cfs 1,850 cf 12.0" Round Culvert n=0.013 L=42.0' S=0.0429 '/' Outflow=0.6 cfs 1,850 cf
<b>Pond CB04: CB-04</b>	Peak Elev=41.42' Inflow=0.7 cfs 2,258 cf 12.0" Round Culvert n=0.013 L=37.0' S=0.0486 '/' Outflow=0.7 cfs 2,258 cf
<b>Pond CB05: CB-05</b>	Peak Elev=47.33' Inflow=0.2 cfs 704 cf 6.0" Round Culvert n=0.013 L=15.0' S=0.0100 '/' Outflow=0.2 cfs 704 cf
<b>Pond CB06: CB-06</b>	Peak Elev=45.45' Inflow=0.2 cfs 590 cf 6.0" Round Culvert n=0.013 L=15.0' S=0.0100 '/' Outflow=0.2 cfs 590 cf
<b>Pond CB07: CB-07</b>	Peak Elev=50.20' Inflow=1.7 cfs 6,644 cf 12.0" Round Culvert n=0.013 L=114.0' S=0.0175 '/' Outflow=1.7 cfs 6,644 cf
<b>Pond CB08: CB-08</b>	Peak Elev=49.99' Inflow=0.9 cfs 2,994 cf 12.0" Round Culvert n=0.013 L=110.0' S=0.0318 '/' Outflow=0.9 cfs 2,994 cf
<b>Pond MH01: MH 1</b>	Peak Elev=28.66' Inflow=0.1 cfs 4,207 cf 12.0" Round Culvert n=0.012 L=91.0' S=0.0082 '/' Outflow=0.1 cfs 4,207 cf
<b>Pond MH05: MH 5</b>	Peak Elev=51.32' Inflow=0.0 cfs 66 cf 12.0" Round Culvert n=0.013 L=65.0' S=0.0523 '/' Outflow=0.0 cfs 66 cf
<b>Pond P003a: R-Tank #1 and 2</b>	Peak Elev=31.83' Storage=1,359 cf Inflow=0.8 cfs 2,453 cf Primary=0.0 cfs 1,781 cf Secondary=0.0 cfs 0 cf Outflow=0.0 cfs 1,781 cf
<b>Pond PP01: CULVERTS</b>	Peak Elev=24.00' Storage=3,674 cf Inflow=10.2 cfs 182,969 cf Primary=10.1 cfs 182,572 cf Secondary=0.0 cfs 0 cf Outflow=10.1 cfs 182,572 cf
<b>Pond PP02: PP02</b>	Peak Elev=43.63' Storage=9,353 cf Inflow=3.6 cfs 29,195 cf Outflow=2.0 cfs 21,412 cf
<b>Pond PP03b: R-Tank #3 and 4</b>	Peak Elev=34.58' Storage=2,509 cf Inflow=1.2 cfs 4,107 cf Primary=0.1 cfs 2,426 cf Secondary=0.0 cfs 0 cf Outflow=0.1 cfs 2,426 cf
<b>Pond PP04A: Bioretention Area #2</b>	Peak Elev=47.33' Storage=2,873 cf Inflow=1.8 cfs 7,348 cf Primary=0.3 cfs 6,962 cf Secondary=0.0 cfs 0 cf Outflow=0.3 cfs 6,962 cf
<b>Pond PP04B: Bioretention Area #3</b>	Peak Elev=45.25' Storage=3,140 cf Inflow=1.1 cfs 3,585 cf Primary=0.0 cfs 444 cf Secondary=0.0 cfs 0 cf Outflow=0.0 cfs 444 cf
<b>Pond PP05: Bioretention Pond #1</b>	Peak Elev=56.04' Storage=911 cf Inflow=0.3 cfs 977 cf Outflow=0.0 cfs 66 cf



**477361-00\_PRE-&-POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Post Development  
Type III 24-hr 2-YR Rainfall=3.73"

Printed 3/4/2020

Page 6

**Pond PP06: Wildlife Crossings**

Peak Elev=26.32' Storage=130 cf Inflow=5.4 cfs 62,770 cf

Primary=5.4 cfs 62,721 cf Secondary=0.0 cfs 31 cf Tertiary=0.0 cfs 0 cf Outflow=5.4 cfs 62,752 cf

**Link PPol01: Pr Pol-01**

Inflow=10.1 cfs 182,572 cf

Primary=10.1 cfs 182,572 cf

**Link PPol02: Pr Pol-02**

Inflow=0.3 cfs 3,189 cf

Primary=0.3 cfs 3,189 cf

**Link PPol03: Proposed Wildlife Crossings**

Inflow=5.4 cfs 62,770 cf

Primary=5.4 cfs 62,770 cf

**Total Runoff Area = 2,997,457 sf Runoff Volume = 207,149 cf Average Runoff Depth = 0.83"**

**96.04% Pervious = 2,878,780 sf 3.96% Impervious = 118,677 sf**

Time span=0.00-24.00 hrs, dt=0.06 hrs, 401 points x 2  
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN  
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

<b>Subcatchment PS01: PS-01</b>	Runoff Area=57,405 sf 0.00% Impervious Runoff Depth>1.75" Flow Length=415' Tc=53.2 min CN=61 Runoff=1.1 cfs 8,366 cf
<b>Subcatchment PS02: PS-02</b>	Runoff Area=501,780 sf 0.00% Impervious Runoff Depth>1.35" Flow Length=740' Tc=95.8 min CN=56 Runoff=4.8 cfs 56,442 cf
<b>Subcatchment PS03: ES-03</b>	Runoff Area=483,638 sf 3.20% Impervious Runoff Depth>2.08" Flow Length=800' Tc=40.5 min CN=65 Runoff=12.9 cfs 83,789 cf
<b>Subcatchment PS04: PS-04</b>	Runoff Area=460,441 sf 3.70% Impervious Runoff Depth>2.41" Flow Length=1,231' Tc=52.0 min CN=69 Runoff=12.7 cfs 92,551 cf
<b>Subcatchment PS05: PS-05</b>	Runoff Area=117,283 sf 8.10% Impervious Runoff Depth>2.68" Flow Length=375' Tc=41.3 min CN=72 Runoff=4.1 cfs 26,241 cf
<b>Subcatchment PS06: PS-06</b>	Runoff Area=63,674 sf 8.10% Impervious Runoff Depth>2.70" Flow Length=337' Tc=16.9 min CN=72 Runoff=3.3 cfs 14,329 cf
<b>Subcatchment PS07: PS-07</b>	Runoff Area=32,586 sf 5.06% Impervious Runoff Depth>2.60" Flow Length=316' Tc=28.1 min CN=71 Runoff=1.3 cfs 7,070 cf
<b>Subcatchment PS08: PS-08</b>	Runoff Area=155,960 sf 3.58% Impervious Runoff Depth>2.52" Flow Length=599' Tc=13.3 min CN=70 Runoff=8.3 cfs 32,799 cf
<b>Subcatchment PS09: PS-09</b>	Runoff Area=1,008,725 sf 0.85% Impervious Runoff Depth>1.66" Flow Length=1,835' Tc=75.9 min CN=60 Runoff=14.4 cfs 139,436 cf
<b>Subcatchment PS10: PS-10</b>	Runoff Area=32,468 sf 52.74% Impervious Runoff Depth>3.97" Flow Length=483' Tc=13.2 min CN=85 Runoff=2.7 cfs 10,729 cf
<b>Subcatchment PS11: PS-11</b>	Runoff Area=12,159 sf 58.76% Impervious Runoff Depth>3.97" Flow Length=452' Tc=7.5 min CN=85 Runoff=1.2 cfs 4,022 cf
<b>Subcatchment PS12: PS-12</b>	Runoff Area=4,911 sf 36.61% Impervious Runoff Depth>3.17" Flow Length=139' Tc=5.0 min CN=77 Runoff=0.4 cfs 1,299 cf
<b>Subcatchment PS13: PS-13</b>	Runoff Area=4,559 sf 39.96% Impervious Runoff Depth>3.66" Flow Length=139' Tc=5.0 min CN=82 Runoff=0.4 cfs 1,392 cf
<b>Subcatchment PS14: PS-14</b>	Runoff Area=5,051 sf 20.97% Impervious Runoff Depth>3.27" Flow Length=96' Tc=5.0 min CN=78 Runoff=0.4 cfs 1,376 cf
<b>Subcatchment PS15: PS-15</b>	Runoff Area=4,235 sf 19.50% Impervious Runoff Depth>3.27" Flow Length=96' Tc=5.0 min CN=78 Runoff=0.4 cfs 1,154 cf
<b>Subcatchment PS16: PS-16</b>	Runoff Area=8,958 sf 58.47% Impervious Runoff Depth>4.29" Flow Length=117' Tc=5.6 min CN=88 Runoff=1.0 cfs 3,200 cf

<b>Subcatchment PS17: PS-17</b>	Runoff Area=12,705 sf 47.10% Impervious Runoff Depth>3.87" Flow Length=166' Tc=7.3 min CN=84 Runoff=1.2 cfs 4,093 cf
<b>Subcatchment PS18: PS-18</b>	Runoff Area=7,913 sf 43.27% Impervious Runoff Depth>3.56" Flow Length=124' Tc=5.0 min CN=81 Runoff=0.8 cfs 2,350 cf
<b>Subcatchment PS19: PS-19</b>	Runoff Area=7,620 sf 43.87% Impervious Runoff Depth>3.56" Flow Length=164' Tc=5.0 min CN=81 Runoff=0.7 cfs 2,263 cf
<b>Subcatchment PS20: PS-20</b>	Runoff Area=3,773 sf 66.10% Impervious Runoff Depth>4.39" Flow Length=128' Tc=5.0 min CN=89 Runoff=0.4 cfs 1,382 cf
<b>Subcatchment PS21: PS-21</b>	Runoff Area=3,612 sf 69.10% Impervious Runoff Depth>4.50" Flow Length=124' Tc=5.0 min CN=90 Runoff=0.4 cfs 1,355 cf
<b>Subcatchment PS22: PS-22</b>	Runoff Area=8,001 sf 37.17% Impervious Runoff Depth>2.98" Flow Length=128' Slope=0.0250 '/' Tc=5.0 min CN=75 Runoff=0.6 cfs 1,990 cf
<b>Reach 2R: PR-05</b>	Avg. Flow Depth=0.03' Max Vel=0.11 fps Inflow=0.5 cfs 3,393 cf n=0.100 L=1,100.0' S=0.0050 '/' Capacity=60.8 cfs Outflow=0.1 cfs 2,861 cf
<b>Reach PR01: PR-01</b>	Avg. Flow Depth=0.08' Max Vel=0.42 fps Inflow=4.8 cfs 56,442 cf n=0.050 L=537.0' S=0.0065 '/' Capacity=1,413.2 cfs Outflow=4.5 cfs 55,208 cf
<b>Reach PR02: PR02</b>	Avg. Flow Depth=0.20' Max Vel=0.71 fps Inflow=17.3 cfs 152,048 cf n=0.050 L=668.0' S=0.0055 '/' Capacity=1,097.9 cfs Outflow=15.9 cfs 149,571 cf
<b>Reach PR03: PR03</b>	Avg. Flow Depth=0.09' Max Vel=0.52 fps Inflow=7.3 cfs 52,606 cf n=0.080 L=894.0' S=0.0187 '/' Capacity=1,142.3 cfs Outflow=5.2 cfs 51,160 cf
<b>Reach PR04: PR-04</b>	Avg. Flow Depth=0.15' Max Vel=0.65 fps Inflow=14.7 cfs 170,095 cf n=0.080 L=682.0' S=0.0161 '/' Capacity=2,431.4 cfs Outflow=14.0 cfs 167,052 cf
<b>Reach PR05a: PR-05</b>	Avg. Flow Depth=0.00' Max Vel=0.00 fps Inflow=0.0 cfs 0 cf n=0.100 L=46.0' S=0.0152 '/' Capacity=106.1 cfs Outflow=0.0 cfs 0 cf
<b>Reach PR05b: PR-05</b>	Avg. Flow Depth=0.02' Max Vel=0.20 fps Inflow=0.1 cfs 5,650 cf n=0.100 L=46.0' S=0.0326 '/' Capacity=155.3 cfs Outflow=0.1 cfs 5,623 cf
<b>Reach PR06: PR-06</b>	Avg. Flow Depth=0.13' Max Vel=0.24 fps Inflow=1.4 cfs 13,019 cf n=0.100 L=193.0' S=0.0047 '/' Capacity=58.7 cfs Outflow=1.2 cfs 12,897 cf
<b>Reach PR07: PR-07</b>	Avg. Flow Depth=0.19' Max Vel=0.74 fps Inflow=14.4 cfs 139,519 cf n=0.080 L=682.0' S=0.0161 '/' Capacity=992.5 cfs Outflow=13.7 cfs 137,296 cf
<b>Pond 1P: (new Pond)</b>	Peak Elev=26.60' Inflow=0.4 cfs 1,382 cf Outflow=0.4 cfs 1,382 cf
<b>Pond 2P: (new Pond)</b>	Peak Elev=26.60' Inflow=0.4 cfs 1,355 cf Outflow=0.4 cfs 1,355 cf

<b>Pond CB01: CB-01</b>	Peak Elev=33.79' Inflow=0.8 cfs 2,350 cf 12.0" Round Culvert n=0.013 L=12.0' S=0.0125 '/' Outflow=0.8 cfs 2,350 cf
<b>Pond CB02: CB-02</b>	Peak Elev=33.98' Inflow=0.7 cfs 2,263 cf 22.0" Round Culvert n=0.013 L=12.0' S=0.0125 '/' Outflow=0.7 cfs 2,259 cf
<b>Pond CB03: CB-03</b>	Peak Elev=41.51' Inflow=1.0 cfs 3,200 cf 12.0" Round Culvert n=0.013 L=42.0' S=0.0429 '/' Outflow=1.0 cfs 3,200 cf
<b>Pond CB04: CB-04</b>	Peak Elev=41.58' Inflow=1.2 cfs 4,093 cf 12.0" Round Culvert n=0.013 L=37.0' S=0.0486 '/' Outflow=1.2 cfs 4,093 cf
<b>Pond CB05: CB-05</b>	Peak Elev=47.98' Inflow=0.4 cfs 1,376 cf 6.0" Round Culvert n=0.013 L=15.0' S=0.0100 '/' Outflow=0.4 cfs 1,376 cf
<b>Pond CB06: CB-06</b>	Peak Elev=45.60' Inflow=0.4 cfs 1,154 cf 6.0" Round Culvert n=0.013 L=15.0' S=0.0100 '/' Outflow=0.4 cfs 1,154 cf
<b>Pond CB07: CB-07</b>	Peak Elev=50.61' Inflow=3.0 cfs 12,028 cf 12.0" Round Culvert n=0.013 L=114.0' S=0.0175 '/' Outflow=3.0 cfs 12,028 cf
<b>Pond CB08: CB-08</b>	Peak Elev=50.18' Inflow=1.6 cfs 5,414 cf 12.0" Round Culvert n=0.013 L=110.0' S=0.0318 '/' Outflow=1.6 cfs 5,414 cf
<b>Pond MH01: MH 1</b>	Peak Elev=28.67' Inflow=0.1 cfs 5,650 cf 12.0" Round Culvert n=0.012 L=91.0' S=0.0082 '/' Outflow=0.1 cfs 5,650 cf
<b>Pond MH05: MH 5</b>	Peak Elev=51.32' Inflow=0.0 cfs 83 cf 12.0" Round Culvert n=0.013 L=65.0' S=0.0523 '/' Outflow=0.0 cfs 83 cf
<b>Pond P003a: R-Tank #1 and 2</b>	Peak Elev=33.79' Storage=3,609 cf Inflow=1.5 cfs 5,570 cf Primary=0.1 cfs 2,569 cf Secondary=0.0 cfs 0 cf Outflow=0.1 cfs 2,569 cf
<b>Pond PP01: CULVERTS</b>	Peak Elev=25.72' Storage=78,114 cf Inflow=36.2 cfs 458,481 cf Primary=21.6 cfs 457,784 cf Secondary=0.0 cfs 0 cf Outflow=21.6 cfs 457,784 cf
<b>Pond PP02: PP02</b>	Peak Elev=43.77' Storage=12,394 cf Inflow=8.2 cfs 60,537 cf Outflow=7.3 cfs 52,606 cf
<b>Pond PP03b: R-Tank #3 and 4</b>	Peak Elev=36.69' Storage=4,461 cf Inflow=2.2 cfs 7,294 cf Primary=0.1 cfs 3,081 cf Secondary=0.0 cfs 961 cf Outflow=0.1 cfs 4,041 cf
<b>Pond PP04A: Bioretention Area #2</b>	Peak Elev=47.97' Storage=4,724 cf Inflow=3.3 cfs 13,404 cf Primary=1.4 cfs 13,019 cf Secondary=0.0 cfs 0 cf Outflow=1.4 cfs 13,019 cf
<b>Pond PP04B: Bioretention Area #3</b>	Peak Elev=45.38' Storage=3,476 cf Inflow=1.9 cfs 6,568 cf Primary=0.5 cfs 3,393 cf Secondary=0.0 cfs 0 cf Outflow=0.5 cfs 3,393 cf
<b>Pond PP05: Bioretention Pond #1</b>	Peak Elev=56.75' Storage=1,906 cf Inflow=0.6 cfs 1,990 cf Outflow=0.0 cfs 83 cf

**477361-00\_PRE-&-POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Post Development  
Type III 24-hr 10-YR Rainfall=5.65"

Printed 3/4/2020

Page 10

**Pond PP06: Wildlife Crossings**

Peak Elev=26.76' Storage=520 cf Inflow=17.1 cfs 145,093 cf

Primary=12.7 cfs 131,716 cf Secondary=4.4 cfs 13,354 cf Tertiary=0.0 cfs 0 cf Outflow=17.1 cfs 145,070 cf

**Link PPol01: Pr Pol-01**

Inflow=21.6 cfs 457,784 cf

Primary=21.6 cfs 457,784 cf

**Link PPol02: Pr Pol-02**

Inflow=1.1 cfs 8,366 cf

Primary=1.1 cfs 8,366 cf

**Link PPol03: Proposed Wildlife Crossings**

Inflow=17.1 cfs 145,093 cf

Primary=17.1 cfs 145,093 cf

**Total Runoff Area = 2,997,457 sf Runoff Volume = 497,631 cf Average Runoff Depth = 1.99"**

**96.04% Pervious = 2,878,780 sf 3.96% Impervious = 118,677 sf**

Time span=0.00-24.00 hrs, dt=0.06 hrs, 401 points x 2  
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN  
 Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

<b>Subcatchment PS01: PS-01</b>	Runoff Area=57,405 sf 0.00% Impervious Runoff Depth>2.78" Flow Length=415' Tc=53.2 min CN=61 Runoff=1.8 cfs 13,302 cf
<b>Subcatchment PS02: PS-02</b>	Runoff Area=501,780 sf 0.00% Impervious Runoff Depth>2.26" Flow Length=740' Tc=95.8 min CN=56 Runoff=8.5 cfs 94,422 cf
<b>Subcatchment PS03: ES-03</b>	Runoff Area=483,638 sf 3.20% Impervious Runoff Depth>3.20" Flow Length=800' Tc=40.5 min CN=65 Runoff=20.3 cfs 128,855 cf
<b>Subcatchment PS04: PS-04</b>	Runoff Area=460,441 sf 3.70% Impervious Runoff Depth>3.60" Flow Length=1,231' Tc=52.0 min CN=69 Runoff=19.2 cfs 138,298 cf
<b>Subcatchment PS05: PS-05</b>	Runoff Area=117,283 sf 8.10% Impervious Runoff Depth>3.93" Flow Length=375' Tc=41.3 min CN=72 Runoff=6.1 cfs 38,434 cf
<b>Subcatchment PS06: PS-06</b>	Runoff Area=63,674 sf 8.10% Impervious Runoff Depth>3.95" Flow Length=337' Tc=16.9 min CN=72 Runoff=4.9 cfs 20,978 cf
<b>Subcatchment PS07: PS-07</b>	Runoff Area=32,586 sf 5.06% Impervious Runoff Depth>3.84" Flow Length=316' Tc=28.1 min CN=71 Runoff=2.0 cfs 10,419 cf
<b>Subcatchment PS08: PS-08</b>	Runoff Area=155,960 sf 3.58% Impervious Runoff Depth>3.74" Flow Length=599' Tc=13.3 min CN=70 Runoff=12.4 cfs 48,643 cf
<b>Subcatchment PS09: PS-09</b>	Runoff Area=1,008,725 sf 0.85% Impervious Runoff Depth>2.66" Flow Length=1,835' Tc=75.9 min CN=60 Runoff=24.2 cfs 223,869 cf
<b>Subcatchment PS10: PS-10</b>	Runoff Area=32,468 sf 52.74% Impervious Runoff Depth>5.40" Flow Length=483' Tc=13.2 min CN=85 Runoff=3.6 cfs 14,598 cf
<b>Subcatchment PS11: PS-11</b>	Runoff Area=12,159 sf 58.76% Impervious Runoff Depth>5.40" Flow Length=452' Tc=7.5 min CN=85 Runoff=1.6 cfs 5,472 cf
<b>Subcatchment PS12: PS-12</b>	Runoff Area=4,911 sf 36.61% Impervious Runoff Depth>4.51" Flow Length=139' Tc=5.0 min CN=77 Runoff=0.6 cfs 1,845 cf
<b>Subcatchment PS13: PS-13</b>	Runoff Area=4,559 sf 39.96% Impervious Runoff Depth>5.06" Flow Length=139' Tc=5.0 min CN=82 Runoff=0.6 cfs 1,924 cf
<b>Subcatchment PS14: PS-14</b>	Runoff Area=5,051 sf 20.97% Impervious Runoff Depth>4.62" Flow Length=96' Tc=5.0 min CN=78 Runoff=0.6 cfs 1,944 cf
<b>Subcatchment PS15: PS-15</b>	Runoff Area=4,235 sf 19.50% Impervious Runoff Depth>4.62" Flow Length=96' Tc=5.0 min CN=78 Runoff=0.5 cfs 1,630 cf
<b>Subcatchment PS16: PS-16</b>	Runoff Area=8,958 sf 58.47% Impervious Runoff Depth>5.75" Flow Length=117' Tc=5.6 min CN=88 Runoff=1.3 cfs 4,289 cf

**477361-00\_PRE-&-POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Post Development

Type III 24-hr 25-YR Rainfall=7.16"

Printed 3/4/2020

Page 12

<b>Subcatchment PS17: PS-17</b>	Runoff Area=12,705 sf 47.10% Impervious Runoff Depth>5.29" Flow Length=166' Tc=7.3 min CN=84 Runoff=1.6 cfs 5,598 cf
<b>Subcatchment PS18: PS-18</b>	Runoff Area=7,913 sf 43.27% Impervious Runoff Depth>4.95" Flow Length=124' Tc=5.0 min CN=81 Runoff=1.0 cfs 3,265 cf
<b>Subcatchment PS19: PS-19</b>	Runoff Area=7,620 sf 43.87% Impervious Runoff Depth>4.95" Flow Length=164' Tc=5.0 min CN=81 Runoff=1.0 cfs 3,144 cf
<b>Subcatchment PS20: PS-20</b>	Runoff Area=3,773 sf 66.10% Impervious Runoff Depth>5.86" Flow Length=128' Tc=5.0 min CN=89 Runoff=0.6 cfs 1,843 cf
<b>Subcatchment PS21: PS-21</b>	Runoff Area=3,612 sf 69.10% Impervious Runoff Depth>5.98" Flow Length=124' Tc=5.0 min CN=90 Runoff=0.6 cfs 1,799 cf
<b>Subcatchment PS22: PS-22</b>	Runoff Area=8,001 sf 37.17% Impervious Runoff Depth>4.29" Flow Length=128' Slope=0.0250 '/' Tc=5.0 min CN=75 Runoff=0.9 cfs 2,859 cf
<b>Reach 2R: PR-05</b>	Avg. Flow Depth=0.06' Max Vel=0.15 fps Inflow=1.5 cfs 5,841 cf n=0.100 L=1,100.0' S=0.0050 '/' Capacity=60.8 cfs Outflow=0.3 cfs 5,220 cf
<b>Reach PR01: PR-01</b>	Avg. Flow Depth=0.11' Max Vel=0.54 fps Inflow=8.5 cfs 94,422 cf n=0.050 L=537.0' S=0.0065 '/' Capacity=1,413.2 cfs Outflow=8.2 cfs 92,827 cf
<b>Reach PR02: PR02</b>	Avg. Flow Depth=0.27' Max Vel=0.86 fps Inflow=29.1 cfs 228,626 cf n=0.050 L=668.0' S=0.0055 '/' Capacity=1,097.9 cfs Outflow=27.3 cfs 225,708 cf
<b>Reach PR03: PR03</b>	Avg. Flow Depth=0.14' Max Vel=0.65 fps Inflow=12.1 cfs 79,656 cf n=0.080 L=894.0' S=0.0187 '/' Capacity=1,142.3 cfs Outflow=9.6 cfs 77,821 cf
<b>Reach PR04: PR-04</b>	Avg. Flow Depth=0.20' Max Vel=0.80 fps Inflow=24.8 cfs 269,844 cf n=0.080 L=682.0' S=0.0161 '/' Capacity=2,431.4 cfs Outflow=24.0 cfs 266,209 cf
<b>Reach PR05a: PR-05</b>	Avg. Flow Depth=0.05' Max Vel=0.25 fps Inflow=0.5 cfs 2,665 cf n=0.100 L=46.0' S=0.0152 '/' Capacity=106.1 cfs Outflow=0.5 cfs 2,665 cf
<b>Reach PR05b: PR-05</b>	Avg. Flow Depth=0.02' Max Vel=0.20 fps Inflow=0.1 cfs 6,254 cf n=0.100 L=46.0' S=0.0326 '/' Capacity=155.3 cfs Outflow=0.1 cfs 6,225 cf
<b>Reach PR06: PR-06</b>	Avg. Flow Depth=0.20' Max Vel=0.30 fps Inflow=3.4 cfs 18,001 cf n=0.100 L=193.0' S=0.0047 '/' Capacity=58.7 cfs Outflow=2.5 cfs 17,859 cf
<b>Reach PR07: PR-07</b>	Avg. Flow Depth=0.26' Max Vel=0.90 fps Inflow=24.2 cfs 223,961 cf n=0.080 L=682.0' S=0.0161 '/' Capacity=992.5 cfs Outflow=23.3 cfs 221,202 cf
<b>Pond 1P: (new Pond)</b>	Peak Elev=26.63' Inflow=0.6 cfs 1,843 cf Outflow=0.6 cfs 1,843 cf
<b>Pond 2P: (new Pond)</b>	Peak Elev=26.62' Inflow=0.6 cfs 1,799 cf Outflow=0.6 cfs 1,799 cf

<b>Pond CB01: CB-01</b>	Peak Elev=34.48'	Inflow=1.0 cfs	3,265 cf
	12.0" Round Culvert n=0.013	L=12.0'	S=0.0125 '/ Outflow=1.0 cfs 3,266 cf
<b>Pond CB02: CB-02</b>	Peak Elev=34.48'	Inflow=1.0 cfs	3,144 cf
	22.0" Round Culvert n=0.013	L=12.0'	S=0.0125 '/ Outflow=1.0 cfs 3,138 cf
<b>Pond CB03: CB-03</b>	Peak Elev=41.60'	Inflow=1.3 cfs	4,289 cf
	12.0" Round Culvert n=0.013	L=42.0'	S=0.0429 '/ Outflow=1.3 cfs 4,289 cf
<b>Pond CB04: CB-04</b>	Peak Elev=41.69'	Inflow=1.6 cfs	5,598 cf
	12.0" Round Culvert n=0.013	L=37.0'	S=0.0486 '/ Outflow=1.6 cfs 5,598 cf
<b>Pond CB05: CB-05</b>	Peak Elev=48.18'	Inflow=0.6 cfs	1,944 cf
	6.0" Round Culvert n=0.013	L=15.0'	S=0.0100 '/ Outflow=0.6 cfs 1,944 cf
<b>Pond CB06: CB-06</b>	Peak Elev=45.75'	Inflow=0.5 cfs	1,630 cf
	6.0" Round Culvert n=0.013	L=15.0'	S=0.0100 '/ Outflow=0.5 cfs 1,630 cf
<b>Pond CB07: CB-07</b>	Peak Elev=51.11'	Inflow=4.0 cfs	16,443 cf
	12.0" Round Culvert n=0.013	L=114.0'	S=0.0175 '/ Outflow=4.0 cfs 16,443 cf
<b>Pond CB08: CB-08</b>	Peak Elev=50.33'	Inflow=2.2 cfs	7,396 cf
	12.0" Round Culvert n=0.013	L=110.0'	S=0.0318 '/ Outflow=2.2 cfs 7,396 cf
<b>Pond MH01: MH 1</b>	Peak Elev=28.68'	Inflow=0.1 cfs	6,254 cf
	12.0" Round Culvert n=0.012	L=91.0'	S=0.0082 '/ Outflow=0.1 cfs 6,254 cf
<b>Pond MH05: MH 5</b>	Peak Elev=51.32'	Inflow=0.0 cfs	92 cf
	12.0" Round Culvert n=0.013	L=65.0'	S=0.0523 '/ Outflow=0.0 cfs 92 cf
<b>Pond P003a: R-Tank #1 and 2</b>	Peak Elev=34.48'	Storage=4,100 cf	Inflow=2.1 cfs 9,304 cf
	Primary=0.1 cfs 2,868 cf	Secondary=0.5 cfs 2,665 cf	Outflow=0.5 cfs 5,533 cf
<b>Pond PP01: CULVERTS</b>	Peak Elev=26.19'	Storage=161,217 cf	Inflow=63.3 cfs 718,821 cf
	Primary=23.9 cfs 631,236 cf	Secondary=17.5 cfs 86,635 cf	Outflow=41.4 cfs 717,871 cf
<b>Pond PP02: PP02</b>	Peak Elev=43.87'	Storage=14,715 cf	Inflow=13.3 cfs 87,691 cf
			Outflow=12.1 cfs 79,656 cf
<b>Pond PP03b: R-Tank #3 and 4</b>	Peak Elev=37.77'	Storage=5,263 cf	Inflow=2.9 cfs 9,887 cf
	Primary=0.1 cfs 3,386 cf	Secondary=0.7 cfs 2,900 cf	Outflow=0.8 cfs 6,286 cf
<b>Pond PP04A: Bioretention Area #2</b>	Peak Elev=48.10'	Storage=5,178 cf	Inflow=4.4 cfs 18,386 cf
	Primary=2.6 cfs 17,436 cf	Secondary=0.8 cfs 565 cf	Outflow=3.4 cfs 18,001 cf
<b>Pond PP04B: Bioretention Area #3</b>	Peak Elev=45.52'	Storage=3,838 cf	Inflow=2.6 cfs 9,026 cf
	Primary=1.4 cfs 5,826 cf	Secondary=0.0 cfs 15 cf	Outflow=1.5 cfs 5,841 cf
<b>Pond PP05: Bioretention Pond #1</b>	Peak Elev=57.27'	Storage=2,767 cf	Inflow=0.9 cfs 2,859 cf
			Outflow=0.0 cfs 92 cf



**477361-00\_PRE-&-POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Post Development  
Type III 24-hr 25-YR Rainfall=7.16"

Printed 3/4/2020

Page 14

**Pond PP06: Wildlife Crossings**

Peak Elev=27.04' Storage=1,017 cf Inflow=29.0 cfs 220,627 cf

Primary=18.4 cfs 186,193 cf Secondary=8.8 cfs 31,627 cf Tertiary=1.8 cfs 2,781 cf Outflow=29.0 cfs 220,601 cf

**Link PPol01: Pr Pol-01**

Inflow=41.4 cfs 717,871 cf

Primary=41.4 cfs 717,871 cf

**Link PPol02: Pr Pol-02**

Inflow=1.8 cfs 13,302 cf

Primary=1.8 cfs 13,302 cf

**Link PPol03: Proposed Wildlife Crossings**

Inflow=29.0 cfs 220,627 cf

Primary=29.0 cfs 220,627 cf

**Total Runoff Area = 2,997,457 sf Runoff Volume = 767,430 cf Average Runoff Depth = 3.07"**

**96.04% Pervious = 2,878,780 sf 3.96% Impervious = 118,677 sf**

**477361-00\_PRE-&-POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Post Development  
Type III 24-hr 50-YR Rainfall=8.58"

Printed 3/4/2020

Page 15

Time span=0.00-24.00 hrs, dt=0.06 hrs, 401 points x 2  
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN  
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

<b>Subcatchment PS01: PS-01</b>	Runoff Area=57,405 sf 0.00% Impervious Runoff Depth>3.84" Flow Length=415' Tc=53.2 min CN=61 Runoff=2.5 cfs 18,392 cf
<b>Subcatchment PS02: PS-02</b>	Runoff Area=501,780 sf 0.00% Impervious Runoff Depth>3.22" Flow Length=740' Tc=95.8 min CN=56 Runoff=12.6 cfs 134,614 cf
<b>Subcatchment PS03: ES-03</b>	Runoff Area=483,638 sf 3.20% Impervious Runoff Depth>4.33" Flow Length=800' Tc=40.5 min CN=65 Runoff=27.7 cfs 174,537 cf
<b>Subcatchment PS04: PS-04</b>	Runoff Area=460,441 sf 3.70% Impervious Runoff Depth>4.79" Flow Length=1,231' Tc=52.0 min CN=69 Runoff=25.6 cfs 183,980 cf
<b>Subcatchment PS05: PS-05</b>	Runoff Area=117,283 sf 8.10% Impervious Runoff Depth>5.17" Flow Length=375' Tc=41.3 min CN=72 Runoff=8.0 cfs 50,485 cf
<b>Subcatchment PS06: PS-06</b>	Runoff Area=63,674 sf 8.10% Impervious Runoff Depth>5.19" Flow Length=337' Tc=16.9 min CN=72 Runoff=6.4 cfs 27,548 cf
<b>Subcatchment PS07: PS-07</b>	Runoff Area=32,586 sf 5.06% Impervious Runoff Depth>5.06" Flow Length=316' Tc=28.1 min CN=71 Runoff=2.6 cfs 13,740 cf
<b>Subcatchment PS08: PS-08</b>	Runoff Area=155,960 sf 3.58% Impervious Runoff Depth>4.96" Flow Length=599' Tc=13.3 min CN=70 Runoff=16.4 cfs 64,403 cf
<b>Subcatchment PS09: PS-09</b>	Runoff Area=1,008,725 sf 0.85% Impervious Runoff Depth>3.70" Flow Length=1,835' Tc=75.9 min CN=60 Runoff=34.3 cfs 311,385 cf
<b>Subcatchment PS10: PS-10</b>	Runoff Area=32,468 sf 52.74% Impervious Runoff Depth>6.76" Flow Length=483' Tc=13.2 min CN=85 Runoff=4.5 cfs 18,294 cf
<b>Subcatchment PS11: PS-11</b>	Runoff Area=12,159 sf 58.76% Impervious Runoff Depth>6.77" Flow Length=452' Tc=7.5 min CN=85 Runoff=2.0 cfs 6,858 cf
<b>Subcatchment PS12: PS-12</b>	Runoff Area=4,911 sf 36.61% Impervious Runoff Depth>5.81" Flow Length=139' Tc=5.0 min CN=77 Runoff=0.8 cfs 2,376 cf
<b>Subcatchment PS13: PS-13</b>	Runoff Area=4,559 sf 39.96% Impervious Runoff Depth>6.41" Flow Length=139' Tc=5.0 min CN=82 Runoff=0.8 cfs 2,435 cf
<b>Subcatchment PS14: PS-14</b>	Runoff Area=5,051 sf 20.97% Impervious Runoff Depth>5.93" Flow Length=96' Tc=5.0 min CN=78 Runoff=0.8 cfs 2,494 cf
<b>Subcatchment PS15: PS-15</b>	Runoff Area=4,235 sf 19.50% Impervious Runoff Depth>5.93" Flow Length=96' Tc=5.0 min CN=78 Runoff=0.7 cfs 2,091 cf
<b>Subcatchment PS16: PS-16</b>	Runoff Area=8,958 sf 58.47% Impervious Runoff Depth>7.13" Flow Length=117' Tc=5.6 min CN=88 Runoff=1.6 cfs 5,324 cf

**477361-00\_PRE-&-POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Post Development

Type III 24-hr 50-YR Rainfall=8.58"

Printed 3/4/2020

Page 16

<b>Subcatchment PS17: PS-17</b>	Runoff Area=12,705 sf 47.10% Impervious Runoff Depth>6.65" Flow Length=166' Tc=7.3 min CN=84 Runoff=2.0 cfs 7,038 cf
<b>Subcatchment PS18: PS-18</b>	Runoff Area=7,913 sf 43.27% Impervious Runoff Depth>6.29" Flow Length=124' Tc=5.0 min CN=81 Runoff=1.3 cfs 4,146 cf
<b>Subcatchment PS19: PS-19</b>	Runoff Area=7,620 sf 43.87% Impervious Runoff Depth>6.29" Flow Length=164' Tc=5.0 min CN=81 Runoff=1.3 cfs 3,993 cf
<b>Subcatchment PS20: PS-20</b>	Runoff Area=3,773 sf 66.10% Impervious Runoff Depth>7.25" Flow Length=128' Tc=5.0 min CN=89 Runoff=0.7 cfs 2,280 cf
<b>Subcatchment PS21: PS-21</b>	Runoff Area=3,612 sf 69.10% Impervious Runoff Depth>7.37" Flow Length=124' Tc=5.0 min CN=90 Runoff=0.7 cfs 2,219 cf
<b>Subcatchment PS22: PS-22</b>	Runoff Area=8,001 sf 37.17% Impervious Runoff Depth>5.56" Flow Length=128' Slope=0.0250 '/' Tc=5.0 min CN=75 Runoff=1.2 cfs 3,710 cf
<b>Reach 2R: PR-05</b>	Avg. Flow Depth=0.08' Max Vel=0.18 fps Inflow=2.8 cfs 8,192 cf n=0.100 L=1,100.0' S=0.0050 '/' Capacity=60.8 cfs Outflow=0.5 cfs 7,503 cf
<b>Reach PR01: PR-01</b>	Avg. Flow Depth=0.14' Max Vel=0.62 fps Inflow=12.6 cfs 134,614 cf n=0.050 L=537.0' S=0.0065 '/' Capacity=1,413.2 cfs Outflow=12.2 cfs 132,764 cf
<b>Reach PR02: PR02</b>	Avg. Flow Depth=0.33' Max Vel=0.97 fps Inflow=40.4 cfs 305,470 cf n=0.050 L=668.0' S=0.0055 '/' Capacity=1,097.9 cfs Outflow=38.5 cfs 302,179 cf
<b>Reach PR03: PR03</b>	Avg. Flow Depth=0.17' Max Vel=0.75 fps Inflow=16.6 cfs 106,267 cf n=0.080 L=894.0' S=0.0187 '/' Capacity=1,142.3 cfs Outflow=13.9 cfs 104,209 cf
<b>Reach PR04: PR-04</b>	Avg. Flow Depth=0.25' Max Vel=0.92 fps Inflow=35.2 cfs 373,031 cf n=0.080 L=682.0' S=0.0161 '/' Capacity=2,431.4 cfs Outflow=34.3 cfs 368,799 cf
<b>Reach PR05a: PR-05</b>	Avg. Flow Depth=0.16' Max Vel=0.47 fps Inflow=2.9 cfs 6,313 cf n=0.100 L=46.0' S=0.0152 '/' Capacity=106.1 cfs Outflow=2.9 cfs 6,313 cf
<b>Reach PR05b: PR-05</b>	Avg. Flow Depth=0.02' Max Vel=0.21 fps Inflow=0.1 cfs 6,526 cf n=0.100 L=46.0' S=0.0326 '/' Capacity=155.3 cfs Outflow=0.1 cfs 6,497 cf
<b>Reach PR06: PR-06</b>	Avg. Flow Depth=0.26' Max Vel=0.35 fps Inflow=4.9 cfs 22,784 cf n=0.100 L=193.0' S=0.0047 '/' Capacity=58.7 cfs Outflow=3.9 cfs 22,619 cf
<b>Reach PR07: PR-07</b>	Avg. Flow Depth=0.32' Max Vel=1.02 fps Inflow=34.3 cfs 311,871 cf n=0.080 L=682.0' S=0.0161 '/' Capacity=992.5 cfs Outflow=33.3 cfs 308,628 cf
<b>Pond 1P: (new Pond)</b>	Peak Elev=26.64' Inflow=0.7 cfs 2,280 cf Outflow=0.7 cfs 2,280 cf
<b>Pond 2P: (new Pond)</b>	Peak Elev=26.64' Inflow=0.7 cfs 2,219 cf Outflow=0.7 cfs 2,219 cf

<b>Pond CB01: CB-01</b>	Peak Elev=34.89'	Inflow=1.3 cfs	4,146 cf
	12.0" Round Culvert n=0.013 L=12.0' S=0.0125 '/'	Outflow=1.3 cfs	4,146 cf
<b>Pond CB02: CB-02</b>	Peak Elev=34.88'	Inflow=1.3 cfs	3,993 cf
	22.0" Round Culvert n=0.013 L=12.0' S=0.0125 '/'	Outflow=1.3 cfs	3,983 cf
<b>Pond CB03: CB-03</b>	Peak Elev=41.68'	Inflow=1.6 cfs	5,324 cf
	12.0" Round Culvert n=0.013 L=42.0' S=0.0429 '/'	Outflow=1.6 cfs	5,324 cf
<b>Pond CB04: CB-04</b>	Peak Elev=41.80'	Inflow=2.0 cfs	7,038 cf
	12.0" Round Culvert n=0.013 L=37.0' S=0.0486 '/'	Outflow=2.0 cfs	7,038 cf
<b>Pond CB05: CB-05</b>	Peak Elev=48.58'	Inflow=0.8 cfs	2,494 cf
	6.0" Round Culvert n=0.013 L=15.0' S=0.0100 '/'	Outflow=0.8 cfs	2,494 cf
<b>Pond CB06: CB-06</b>	Peak Elev=46.01'	Inflow=0.7 cfs	2,091 cf
	6.0" Round Culvert n=0.013 L=15.0' S=0.0100 '/'	Outflow=0.7 cfs	2,091 cf
<b>Pond CB07: CB-07</b>	Peak Elev=51.72'	Inflow=5.0 cfs	20,670 cf
	12.0" Round Culvert n=0.013 L=114.0' S=0.0175 '/'	Outflow=5.0 cfs	20,670 cf
<b>Pond CB08: CB-08</b>	Peak Elev=50.49'	Inflow=2.7 cfs	9,292 cf
	12.0" Round Culvert n=0.013 L=110.0' S=0.0318 '/'	Outflow=2.7 cfs	9,292 cf
<b>Pond MH01: MH 1</b>	Peak Elev=28.68'	Inflow=0.1 cfs	6,526 cf
	12.0" Round Culvert n=0.012 L=91.0' S=0.0082 '/'	Outflow=0.1 cfs	6,526 cf
<b>Pond MH05: MH 5</b>	Peak Elev=51.37'	Inflow=0.0 cfs	486 cf
	12.0" Round Culvert n=0.013 L=65.0' S=0.0523 '/'	Outflow=0.0 cfs	486 cf
<b>Pond P003a: R-Tank #1 and 2</b>	Peak Elev=34.88'	Storage=4,337 cf	Inflow=2.8 cfs 13,216 cf
	Primary=0.1 cfs 2,978 cf	Secondary=2.9 cfs 6,313 cf	Outflow=3.0 cfs 9,290 cf
<b>Pond PP01: CULVERTS</b>	Peak Elev=26.40'	Storage=206,422 cf	Inflow=91.1 cfs 985,781 cf
	Primary=24.9 cfs 728,667 cf	Secondary=43.7 cfs 255,873 cf	Outflow=68.5 cfs 984,541 cf
<b>Pond PP02: PP02</b>	Peak Elev=43.95'	Storage=16,719 cf	Inflow=18.1 cfs 114,392 cf
			Outflow=16.6 cfs 106,267 cf
<b>Pond PP03b: R-Tank #3 and 4</b>	Peak Elev=38.27'	Storage=5,503 cf	Inflow=3.6 cfs 12,362 cf
	Primary=0.1 cfs 3,548 cf	Secondary=1.6 cfs 5,087 cf	Outflow=1.7 cfs 8,635 cf
<b>Pond PP04A: Bioretention Area #2</b>	Peak Elev=48.19'	Storage=5,486 cf	Inflow=5.5 cfs 23,165 cf
	Primary=2.9 cfs 20,980 cf	Secondary=2.0 cfs 1,804 cf	Outflow=4.9 cfs 22,784 cf
<b>Pond PP04B: Bioretention Area #3</b>	Peak Elev=45.60'	Storage=4,053 cf	Inflow=3.3 cfs 11,384 cf
	Primary=2.1 cfs 7,782 cf	Secondary=0.7 cfs 410 cf	Outflow=2.8 cfs 8,192 cf
<b>Pond PP05: Bioretention Pond #1</b>	Peak Elev=57.52'	Storage=3,235 cf	Inflow=1.2 cfs 3,710 cf
			Outflow=0.0 cfs 486 cf

**477361-00\_PRE-&-POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Post Development  
*Type III 24-hr 50-YR Rainfall=8.58"*

Printed 3/4/2020

Page 18

**Pond PP06: Wildlife Crossings** Peak Elev=27.25' Storage=1,660 cf Inflow=40.2 cfs 296,783 cf  
Primary=23.1 cfs 236,192 cf Secondary=12.6 cfs 50,841 cf Tertiary=4.4 cfs 9,720 cf Outflow=40.2 cfs 296,753 cf

**Link PPol01: Pr Pol-01** Inflow=68.5 cfs 984,541 cf  
Primary=68.5 cfs 984,541 cf

**Link PPol02: Pr Pol-02** Inflow=2.5 cfs 18,392 cf  
Primary=2.5 cfs 18,392 cf

**Link PPol03: Proposed Wildlife Crossings** Inflow=40.2 cfs 296,783 cf  
Primary=40.2 cfs 296,783 cf

**Total Runoff Area = 2,997,457 sf Runoff Volume = 1,042,344 cf Average Runoff Depth = 4.17"**  
**96.04% Pervious = 2,878,780 sf 3.96% Impervious = 118,677 sf**

**APPENDIX E**  
**POST DRAINAGE**  
**(10 Yr Storm Event)**

(This Page Is Intentionally Blank)

**477361-00\_PRE-&-POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Post Development (10 yr)  
Type III 24-hr 10-YR Rainfall=5.65"

Printed 3/4/2020

Page 1

**Summary for Subcatchment PS01: PS-01**

Runoff = 1.1 cfs @ 12.78 hrs, Volume= 8,366 cf, Depth> 1.75"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs  
Type III 24-hr 10-YR Rainfall=5.65"

Area (sf)	CN	Description
9,442	55	Woods, Good, HSG B
122	48	Brush, Good, HSG B
13,602	48	Power Line - Brush, Good, HSG B
16,200	70	Woods, Good, HSG C
7,778	65	Brush, Good, HSG C
10,261	65	Power Line - Brush, Good, HSG C
57,405	61	Weighted Average
57,405		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
49.1	100	0.0100	0.03		<b>Sheet Flow, Sheet-Flow</b> Woods: Dense underbrush n= 0.800 P2= 3.23"
3.4	205	0.0400	1.00		<b>Shallow Concentrated Flow, Shallow Concentrated</b> Woodland Kv= 5.0 fps
0.7	110	0.0100	2.68	374.84	<b>Channel Flow, Channel Flow</b> Area= 140.0 sf Perim= 80.9' r= 1.73' n= 0.080 Earth, long dense weeds
53.2	415	Total			

**Summary for Subcatchment PS02: PS-02**

Runoff = 4.8 cfs @ 13.43 hrs, Volume= 56,442 cf, Depth> 1.35"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs  
Type III 24-hr 10-YR Rainfall=5.65"

Area (sf)	CN	Description
209,453	55	Woods, Good, HSG B
82,831	48	Brush, Good, HSG B
53,777	48	Power Line - Brush, Good, HSG B
21,794	70	Woods, Good, HSG C
126,184	65	Brush, Good, HSG C
7,741	65	Power Line - Brush, Good, HSG C
501,780	56	Weighted Average
501,780		100.00% Pervious Area



**477361-00\_PRE-&-POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Post Development (10 yr)  
Type III 24-hr 10-YR Rainfall=5.65"

Printed 3/4/2020

Page 2

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
37.2	100	0.0200	0.04		<b>Sheet Flow, Shallow</b> Woods: Dense underbrush n= 0.800 P2= 3.23"
58.0	550	0.0010	0.16		<b>Shallow Concentrated Flow, Shallow Channel</b> Woodland Kv= 5.0 fps
0.6	90	0.0100	2.41	714.05	<b>Channel Flow, Concentrated</b> Area= 296.0 sf Perim= 200.0' r= 1.48' n= 0.080 Earth, long dense weeds
95.8	740	Total			

**Summary for Subcatchment PS03: ES-03**

Runoff = 12.9 cfs @ 12.59 hrs, Volume= 83,789 cf, Depth> 2.08"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs  
Type III 24-hr 10-YR Rainfall=5.65"

Area (sf)	CN	Description
2,148	98	Paved parking, HSG B
2,609	98	Roofs, HSG B
6,992	61	>75% Grass cover, Good, HSG B
47,744	55	Woods, Good, HSG B
16,804	48	Brush, Good, HSG B
844	48	Power Line - Brush, Good, HSG B
8,479	98	Paved parking, HSG C
2,230	98	Roofs, HSG C
14,892	74	>75% Grass cover, Good, HSG C
75,358	70	Woods, Good, HSG C
232,548	65	Brush, Good, HSG C
71,845	65	Power Line - Brush, Good, HSG C
1,145	72	Woods/grass comb., Good, HSG C
483,638	65	Weighted Average
468,172		96.80% Pervious Area
15,466		3.20% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
28.2	100	0.0400	0.06		<b>Sheet Flow, Sheet Flow</b> Woods: Dense underbrush n= 0.800 P2= 3.23"
12.3	700	0.0360	0.95		<b>Shallow Concentrated Flow, Shallow Flow</b> Woodland Kv= 5.0 fps
40.5	800	Total			

**477361-00\_PRE-&POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Post Development (10 yr)  
Type III 24-hr 10-YR Rainfall=5.65"

Printed 3/4/2020

Page 3

**Summary for Subcatchment PS04: PS-04**

Runoff = 12.7 cfs @ 12.74 hrs, Volume= 92,551 cf, Depth> 2.41"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs  
Type III 24-hr 10-YR Rainfall=5.65"

Area (sf)	CN	Description
0	98	Paved parking, HSG B
0	98	Roofs, HSG B
0	61	>75% Grass cover, Good, HSG B
18,261	55	Woods, Good, HSG B
0	48	Brush, Good, HSG B
0	48	Power Line - Brush, Good, HSG B
13,586	98	Paved parking, HSG C
3,431	98	Roofs, HSG C
19,621	74	>75% Grass cover, Good, HSG C
248,714	70	Woods, Good, HSG C
154,834	65	Brush, Good, HSG C
1,994	72	Woods/grass comb., Good, HSG C
460,441	69	Weighted Average
443,424		96.30% Pervious Area
17,017		3.70% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
37.2	100	0.0200	0.04		<b>Sheet Flow, Sheet Flow</b> Woods: Dense underbrush n= 0.800 P2= 3.23"
9.7	421	0.0210	0.72		<b>Shallow Concentrated Flow, Shallow Flow</b> Woodland Kv= 5.0 fps
5.1	710	0.0100	2.34	835.95	<b>Channel Flow, Channel Flow</b> Area= 358.0 sf Perim= 254.0' r= 1.41' n= 0.080 Earth, long dense weeds
52.0	1,231	Total			

**Summary for Subcatchment PS05: PS-05**

Runoff = 4.1 cfs @ 12.58 hrs, Volume= 26,241 cf, Depth> 2.68"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs  
Type III 24-hr 10-YR Rainfall=5.65"

**477361-00\_PRE-&-POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Post Development (10 yr)  
Type III 24-hr 10-YR Rainfall=5.65"

Printed 3/4/2020

Page 4

Area (sf)	CN	Description
0	98	Paved parking, HSG B
1,372	98	Roofs, HSG B
6,689	61	>75% Grass cover, Good, HSG B
1,161	55	Woods, Good, HSG B
0	48	Brush, Good, HSG B
2,910	98	Paved parking, HSG C
5,221	98	Roofs, HSG C
31,592	74	>75% Grass cover, Good, HSG C
50,975	70	Woods, Good, HSG C
17,363	65	Brush, Good, HSG C
117,283	72	Weighted Average
107,780		91.90% Pervious Area
9,503		8.10% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
37.2	100	0.0200	0.04		<b>Sheet Flow, Sheet Flow</b> Woods: Dense underbrush n= 0.800 P2= 3.23"
4.1	275	0.0500	1.12		<b>Shallow Concentrated Flow, Shallow Channel</b> Woodland Kv= 5.0 fps
41.3	375	Total			

**Summary for Subcatchment PS06: PS-06**

Runoff = 3.3 cfs @ 12.24 hrs, Volume= 14,329 cf, Depth> 2.70"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs  
Type III 24-hr 10-YR Rainfall=5.65"

Area (sf)	CN	Description
0	98	Paved parking, HSG B
244	98	Roofs, HSG B
3,297	61	>75% Grass cover, Good, HSG B
4,211	55	Woods, Good, HSG B
539	58	Woods/grass comb., Good, HSG B
1,904	98	Paved parking, HSG C
3,008	98	Roofs, HSG C
20,224	74	>75% Grass cover, Good, HSG C
22,797	70	Woods, Good, HSG C
4,735	65	Brush, Good, HSG C
2,715	72	Woods/grass comb., Good, HSG C
63,674	72	Weighted Average
58,518		91.90% Pervious Area
5,156		8.10% Impervious Area

**477361-00\_PRE-&POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Post Development (10 yr)  
Type III 24-hr 10-YR Rainfall=5.65"

Printed 3/4/2020

Page 5

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
12.9	100	0.0100	0.13		<b>Sheet Flow, Sheet Flow</b> Grass: Short n= 0.150 P2= 3.23"
3.9	237	0.0400	1.00		<b>Shallow Concentrated Flow, Shallow Channel</b> Woodland Kv= 5.0 fps
16.9	337	Total			

**Summary for Subcatchment PS07: PS-07**

Runoff = 1.3 cfs @ 12.40 hrs, Volume= 7,070 cf, Depth> 2.60"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs  
Type III 24-hr 10-YR Rainfall=5.65"

Area (sf)	CN	Description
0	98	Paved roads w/curbs & sewers, HSG C
1,648	98	Roofs, HSG C
6,087	74	>75% Grass cover, Good, HSG C
18,941	70	Woods, Good, HSG C
4,832	65	Brush, Good, HSG C
1,078	72	Woods/grass comb., Good, HSG C
32,586	71	Weighted Average
30,938		94.94% Pervious Area
1,648		5.06% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.8	50	0.0300	0.17		<b>Sheet Flow, Sheet Flow</b> Grass: Short n= 0.150 P2= 3.23"
18.2	50	0.0300	0.05		<b>Sheet Flow, Sheet Flow</b> Woods: Dense underbrush n= 0.800 P2= 3.23"
5.1	216	0.0200	0.71		<b>Shallow Concentrated Flow, Shallow Channel</b> Woodland Kv= 5.0 fps
28.1	316	Total			

**Summary for Subcatchment PS08: PS-08**

Runoff = 8.3 cfs @ 12.19 hrs, Volume= 32,799 cf, Depth> 2.52"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs  
Type III 24-hr 10-YR Rainfall=5.65"

**477361-00\_PRE-&-POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Post Development (10 yr)  
Type III 24-hr 10-YR Rainfall=5.65"

Printed 3/4/2020

Page 6

Area (sf)	CN	Description
0	98	Paved parking, HSG B
154	98	Roofs, HSG B
772	61	>75% Grass cover, Good, HSG B
97	55	Woods, Good, HSG B
0	48	Brush, Good, HSG B
3	48	Power Line - Brush, Good, HSG B
574	98	Paved parking, HSG C
4,850	98	Roofs, HSG C
21,977	74	>75% Grass cover, Good, HSG C
75,234	70	Woods, Good, HSG C
43,259	65	Brush, Good, HSG C
6,197	65	Power Line - Brush, Good, HSG C
2,843	72	Woods/grass comb., Good, HSG C
155,960	70	Weighted Average
150,382		96.42% Pervious Area
5,578		3.58% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.9	100	0.0700	0.28		<b>Sheet Flow, Sheet Flow</b> Grass: Short n= 0.150 P2= 3.23"
7.0	409	0.0378	0.97		<b>Shallow Concentrated Flow, Shallow Channel</b> Woodland Kv= 5.0 fps
0.4	90	0.0156	3.35	1,072.87	<b>Channel Flow, Channel Flow</b> Area= 320.0 sf Perim= 184.2' r= 1.74' n= 0.080 Earth, long dense weeds
13.3	599	Total			

**Summary for Subcatchment PS09: PS-09**

Runoff = 14.4 cfs @ 13.10 hrs, Volume= 139,436 cf, Depth> 1.66"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs  
Type III 24-hr 10-YR Rainfall=5.65"

**477361-00\_PRE-&-POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Post Development (10 yr)  
 Type III 24-hr 10-YR Rainfall=5.65"

Printed 3/4/2020

Page 7

Area (sf)	CN	Description
1,512	98	Paved parking, HSG B
3,924	98	Roofs, HSG B
8,482	61	>75% Grass cover, Good, HSG B
556,948	55	Woods, Good, HSG B
1,608	48	Brush, Good, HSG B
70,412	48	Power Line - Brush, Good, HSG B
332	98	Paved parking, HSG C
2,813	98	Roofs, HSG C
19,924	74	>75% Grass cover, Good, HSG C
276,240	70	Woods, Good, HSG C
27,337	65	Brush, Good, HSG C
39,193	65	Power Line - Brush, Good, HSG C
1,008,725	60	Weighted Average
1,000,144		99.15% Pervious Area
8,581		0.85% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
31.6	100	0.0300	0.05		<b>Sheet Flow, Sheet Flow</b> Woods: Dense underbrush n= 0.800 P2= 3.23"
15.1	808	0.0320	0.89		<b>Shallow Concentrated Flow, Shallow Channel</b> Woodland Kv= 5.0 fps
27.1	515	0.0040	0.32		<b>Shallow Concentrated Flow, Shallow Channel</b> Woodland Kv= 5.0 fps
2.1	412	0.0170	3.28	594.29	<b>Channel Flow, Channel Flow</b> Area= 181.4 sf Perim= 115.3' r= 1.57' n= 0.080 Earth, long dense weeds
75.9	1,835	Total			

**Summary for Subcatchment PS10: PS-10**

Runoff = 2.7 cfs @ 12.18 hrs, Volume= 10,729 cf, Depth> 3.97"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs  
 Type III 24-hr 10-YR Rainfall=5.65"

**477361-00\_PRE-&-POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Post Development (10 yr)  
Type III 24-hr 10-YR Rainfall=5.65"

Printed 3/4/2020

Page 8

Area (sf)	CN	Description
4,190	98	Paved parking, HSG B
2,107	98	Roofs, HSG B
3,848	61	>75% Grass cover, Good, HSG B
0	55	Woods, Good, HSG B
0	48	Brush, Good, HSG B
8,981	98	Paved parking, HSG C
1,847	98	Roofs, HSG C
11,495	74	>75% Grass cover, Good, HSG C
0	70	Woods, Good, HSG C
0	65	Brush, Good, HSG C
32,468	85	Weighted Average
15,343		47.26% Pervious Area
17,125		52.74% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
12.9	100	0.0100	0.13		<b>Sheet Flow, Sheet Flow</b> Grass: Short n= 0.150 P2= 3.23"
0.3	383	0.0150	21.93	438.64	<b>Channel Flow, Channel Flow</b> Area= 20.0 sf Perim= 10.2' r= 1.96' n= 0.013 Asphalt, smooth
13.2	483	Total			

**Summary for Subcatchment PS11: PS-11**

Runoff = 1.2 cfs @ 12.11 hrs, Volume= 4,022 cf, Depth> 3.97"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs  
Type III 24-hr 10-YR Rainfall=5.65"

Area (sf)	CN	Description
2,472	98	Paved parking, HSG B
911	98	Roofs, HSG B
2,470	61	>75% Grass cover, Good, HSG B
0	55	Woods, Good, HSG B
0	48	Brush, Good, HSG B
2,828	98	Paved parking, HSG C
934	98	Roofs, HSG C
2,544	74	>75% Grass cover, Good, HSG C
0	70	Woods, Good, HSG C
0	65	Brush, Good, HSG C
12,159	85	Weighted Average
5,014		41.24% Pervious Area
7,145		58.76% Impervious Area

**477361-00\_PRE-&-POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Post Development (10 yr)  
Type III 24-hr 10-YR Rainfall=5.65"

Printed 3/4/2020

Page 9

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.2	69	0.0200	0.16		<b>Sheet Flow, Sheet Flow</b> Grass: Short n= 0.150 P2= 3.23"
0.3	383	0.0150	21.93	438.64	<b>Channel Flow, Channel Flow</b> Area= 20.0 sf Perim= 10.2' r= 1.96' n= 0.013 Asphalt, smooth
7.5	452	Total			

**Summary for Subcatchment PS12: PS-12**

[49] Hint: Tc<2dt may require smaller dt

Runoff = 0.4 cfs @ 12.08 hrs, Volume= 1,299 cf, Depth> 3.17"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs  
Type III 24-hr 10-YR Rainfall=5.65"

Area (sf)	CN	Description
791	98	Paved parking, HSG B
0	98	Roofs, HSG B
248	61	>75% Grass cover, Good, HSG B
1,545	58	Woods/grass comb., Good, HSG B
1,007	98	Paved parking, HSG C
0	98	Roofs, HSG C
269	74	>75% Grass cover, Good, HSG C
1,051	72	Woods/grass comb., Good, HSG C
4,911	77	Weighted Average
3,113		63.39% Pervious Area
1,798		36.61% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.6	3	0.0200	0.08		<b>Sheet Flow, Sheet Flow</b> Grass: Short n= 0.150 P2= 3.23"
0.1	136	0.0100	17.91	358.14	<b>Channel Flow, Channel Flow</b> Area= 20.0 sf Perim= 10.2' r= 1.96' n= 0.013 Asphalt, smooth
4.3					<b>Direct Entry, Min Tc of 5 Min</b>
5.0	139	Total			

**Summary for Subcatchment PS13: PS-13**

[49] Hint: Tc<2dt may require smaller dt

Runoff = 0.4 cfs @ 12.07 hrs, Volume= 1,392 cf, Depth> 3.66"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs  
Type III 24-hr 10-YR Rainfall=5.65"



**477361-00\_PRE-&POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Post Development (10 yr)  
Type III 24-hr 10-YR Rainfall=5.65"

Printed 3/4/2020

Page 10

Area (sf)	CN	Description
565	98	Paved parking, HSG B
0	98	Roofs, HSG B
130	61	>75% Grass cover, Good, HSG B
133	58	Woods/grass comb., Good, HSG B
1,257	98	Paved parking, HSG C
0	98	Roofs, HSG C
518	74	>75% Grass cover, Good, HSG C
1,956	72	Woods/grass comb., Good, HSG C
4,559	82	Weighted Average
2,737		60.04% Pervious Area
1,822		39.96% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.6	3	0.0200	0.08		<b>Sheet Flow, Sheet Flow</b> Grass: Short n= 0.150 P2= 3.23"
0.1	136	0.0100	17.91	358.14	<b>Channel Flow, Channel Flow</b> Area= 20.0 sf Perim= 10.2' r= 1.96' n= 0.013 Asphalt, smooth
4.3					<b>Direct Entry, Min Tc of 5 Min</b>
5.0	139	Total			

**Summary for Subcatchment PS14: PS-14**

[49] Hint: Tc<2dt may require smaller dt

Runoff = 0.4 cfs @ 12.08 hrs, Volume= 1,376 cf, Depth> 3.27"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs  
Type III 24-hr 10-YR Rainfall=5.65"

Area (sf)	CN	Description
813	98	Paved parking, HSG C
246	98	Roofs, HSG C
1,636	74	>75% Grass cover, Good, HSG C
0	70	Woods, Good, HSG C
2,356	72	Woods/grass comb., Good, HSG C
5,051	78	Weighted Average
3,992		79.03% Pervious Area
1,059		20.97% Impervious Area

**477361-00\_PRE-&-POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Post Development (10 yr)  
Type III 24-hr 10-YR Rainfall=5.65"

Printed 3/4/2020

Page 11

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.6	3	0.0200	0.08		<b>Sheet Flow, Sheet Flow</b> Grass: Short n= 0.150 P2= 3.23"
0.1	93	0.0100	17.91	358.14	<b>Channel Flow, Channel Flow</b> Area= 20.0 sf Perim= 10.2' r= 1.96' n= 0.013 Asphalt, smooth
4.3					<b>Direct Entry, Min Tc of 5 Min</b>
5.0	96	Total			

**Summary for Subcatchment PS15: PS-15**

[49] Hint: Tc<2dt may require smaller dt

Runoff = 0.4 cfs @ 12.08 hrs, Volume= 1,154 cf, Depth> 3.27"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs  
Type III 24-hr 10-YR Rainfall=5.65"

Area (sf)	CN	Description
826	98	Paved parking, HSG C
0	98	Roofs, HSG C
1,548	74	>75% Grass cover, Good, HSG C
0	70	Woods, Good, HSG C
1,861	72	Woods/grass comb., Good, HSG C
4,235	78	Weighted Average
3,409		80.50% Pervious Area
826		19.50% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.6	3	0.0200	0.08		<b>Sheet Flow, Sheet Flow</b> Grass: Short n= 0.150 P2= 3.23"
0.1	93	0.0100	17.91	358.14	<b>Channel Flow, Channel Flow</b> Area= 20.0 sf Perim= 10.2' r= 1.96' n= 0.013 Asphalt, smooth
4.3					<b>Direct Entry, Min Tc of 5 Min</b>
5.0	96	Total			

**Summary for Subcatchment PS16: PS-16**

[49] Hint: Tc<2dt may require smaller dt

Runoff = 1.0 cfs @ 12.08 hrs, Volume= 3,200 cf, Depth> 4.29"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs  
Type III 24-hr 10-YR Rainfall=5.65"

**477361-00\_PRE-&POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Post Development (10 yr)  
Type III 24-hr 10-YR Rainfall=5.65"

Printed 3/4/2020

Page 12

Area (sf)	CN	Description
4,626	98	Paved parking, HSG C
612	98	Roofs, HSG C
3,720	74	>75% Grass cover, Good, HSG C
0	70	Woods, Good, HSG C
0	65	Brush, Good, HSG C
8,958	88	Weighted Average
3,720		41.53% Pervious Area
5,238		58.47% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.6	50	0.0200	0.15		<b>Sheet Flow, Sheet Flow</b> Grass: Short n= 0.150 P2= 3.23"
0.0	67	0.0400	35.81	716.29	<b>Channel Flow, Channel Flow</b> Area= 20.0 sf Perim= 10.2' r= 1.96' n= 0.013 Asphalt, smooth
5.6	117	Total			

**Summary for Subcatchment PS17: PS-17**

Runoff = 1.2 cfs @ 12.11 hrs, Volume= 4,093 cf, Depth> 3.87"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs  
Type III 24-hr 10-YR Rainfall=5.65"

Area (sf)	CN	Description
782	98	Paved parking, HSG B
754	98	Roofs, HSG B
1,392	61	>75% Grass cover, Good, HSG B
0	55	Woods, Good, HSG B
0	48	Brush, Good, HSG B
3,514	98	Paved parking, HSG C
934	98	Roofs, HSG C
5,329	74	>75% Grass cover, Good, HSG C
0	70	Woods, Good, HSG C
0	65	Brush, Good, HSG C
12,705	84	Weighted Average
6,721		52.90% Pervious Area
5,984		47.10% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.2	68	0.0200	0.16		<b>Sheet Flow, Sheet Flow</b> Grass: Short n= 0.150 P2= 3.23"
0.1	98	0.0300	31.02	620.33	<b>Channel Flow, Channel Flow</b> Area= 20.0 sf Perim= 10.2' r= 1.96' n= 0.013 Asphalt, smooth
7.3	166	Total			

**477361-00\_PRE-&-POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Post Development (10 yr)  
Type III 24-hr 10-YR Rainfall=5.65"

Printed 3/4/2020

Page 13

**Summary for Subcatchment PS18: PS-18**

[49] Hint: Tc<2dt may require smaller dt

Runoff = 0.8 cfs @ 12.07 hrs, Volume= 2,350 cf, Depth> 3.56"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs  
Type III 24-hr 10-YR Rainfall=5.65"

Area (sf)	CN	Description
611	98	Paved parking, HSG B
0	98	Roofs, HSG B
182	61	>75% Grass cover, Good, HSG B
0	55	Woods, Good, HSG B
1,535	58	Woods/grass comb., Good, HSG B
2,125	98	Paved parking, HSG C
688	98	Roofs, HSG C
2,348	74	>75% Grass cover, Good, HSG C
0	70	Woods, Good, HSG C
424	72	Woods/grass comb., Good, HSG C
7,913	81	Weighted Average
4,489		56.73% Pervious Area
3,424		43.27% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.1	22	0.2500	0.35		<b>Sheet Flow, Sheet Flow</b> Grass: Short n= 0.150 P2= 3.23"
0.1	102	0.0300	31.02	620.33	<b>Channel Flow, Channel Flow</b> Area= 20.0 sf Perim= 10.2' r= 1.96' n= 0.013 Asphalt, smooth
3.8					<b>Direct Entry, Min Tc of 5 Min</b>
5.0	124	Total			

**Summary for Subcatchment PS19: PS-19**

[49] Hint: Tc<2dt may require smaller dt

Runoff = 0.7 cfs @ 12.07 hrs, Volume= 2,263 cf, Depth> 3.56"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs  
Type III 24-hr 10-YR Rainfall=5.65"

**477361-00\_PRE-&-POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Post Development (10 yr)  
Type III 24-hr 10-YR Rainfall=5.65"

Printed 3/4/2020

Page 14

Area (sf)	CN	Description
865	98	Paved parking, HSG B
313	98	Roofs, HSG B
1,705	61	>75% Grass cover, Good, HSG B
0	55	Woods, Good, HSG B
302	58	Woods/grass comb., Good, HSG B
1,631	98	Paved parking, HSG C
534	98	Roofs, HSG C
1,922	74	>75% Grass cover, Good, HSG C
0	70	Woods, Good, HSG C
348	72	Woods/grass comb., Good, HSG C
7,620	81	Weighted Average
4,277		56.13% Pervious Area
3,343		43.87% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.3	44	0.0600	0.23		<b>Sheet Flow, Sheet Flow</b> Grass: Short n= 0.150 P2= 3.23"
0.1	120	0.0300	31.02	620.33	<b>Channel Flow, Channel Flow</b> Area= 20.0 sf Perim= 10.2' r= 1.96' n= 0.013 Asphalt, smooth
1.6					<b>Direct Entry, Min Tc of 5 Min</b>
5.0	164	Total			

**Summary for Subcatchment PS20: PS-20**

[49] Hint: Tc<2dt may require smaller dt

Runoff = 0.4 cfs @ 12.07 hrs, Volume= 1,382 cf, Depth> 4.39"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs  
Type III 24-hr 10-YR Rainfall=5.65"

Area (sf)	CN	Description
14	98	Paved parking, HSG B
0	48	Brush, Good, HSG B
2,480	98	Paved parking, HSG C
0	98	Roofs, HSG C
584	74	>75% Grass cover, Good, HSG C
0	70	Woods, Good, HSG C
695	72	Woods/grass comb., Good, HSG C
3,773	89	Weighted Average
1,279		33.90% Pervious Area
2,494		66.10% Impervious Area

**477361-00\_PRE-&-POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Post Development (10 yr)  
Type III 24-hr 10-YR Rainfall=5.65"

Printed 3/4/2020

Page 15

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.9	22	0.3300	0.39		<b>Sheet Flow, Sheet Flow</b> Grass: Short n= 0.150 P2= 3.23"
0.0	106	0.0600	43.86	877.27	<b>Channel Flow, Channel Flow</b> Area= 20.0 sf Perim= 10.2' r= 1.96' n= 0.013 Asphalt, smooth
4.1					<b>Direct Entry, Min Tc of 5 Min</b>
5.0	128	Total			

**Summary for Subcatchment PS21: PS-21**

[49] Hint: Tc<2dt may require smaller dt

Runoff = 0.4 cfs @ 12.07 hrs, Volume= 1,355 cf, Depth> 4.50"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs  
Type III 24-hr 10-YR Rainfall=5.65"

Area (sf)	CN	Description
10	98	Paved parking, HSG B
2,486	98	Paved parking, HSG C
0	98	Roofs, HSG C
580	74	>75% Grass cover, Good, HSG C
0	70	Woods, Good, HSG C
536	72	Woods/grass comb., Good, HSG C
3,612	90	Weighted Average
1,116		30.90% Pervious Area
2,496		69.10% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.9	22	0.3300	0.39		<b>Sheet Flow, Sheet Flow</b> Grass: Short n= 0.150 P2= 3.23"
0.0	102	0.0600	43.86	877.27	<b>Channel Flow, Channel Flow</b> Area= 20.0 sf Perim= 10.2' r= 1.96' n= 0.013 Asphalt, smooth
4.1					<b>Direct Entry, Min Tc of 5 Min</b>
5.0	124	Total			

**Summary for Subcatchment PS22: PS-22**

[49] Hint: Tc<2dt may require smaller dt

Runoff = 0.6 cfs @ 12.08 hrs, Volume= 1,990 cf, Depth> 2.98"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs  
Type III 24-hr 10-YR Rainfall=5.65"

**477361-00\_PRE-&-POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Post Development (10 yr)  
Type III 24-hr 10-YR Rainfall=5.65"

Printed 3/4/2020

Page 16

Area (sf)	CN	Description
2,338	98	Paved parking, HSG B
0	98	Roofs, HSG B
4,808	61	>75% Grass cover, Good, HSG B
0	55	Woods, Good, HSG B
0	48	Brush, Good, HSG B
636	98	Paved parking, HSG C
0	98	Roofs, HSG C
219	74	>75% Grass cover, Good, HSG C
0	70	Woods, Good, HSG C
0	65	Brush, Good, HSG C
8,001	75	Weighted Average
5,027		62.83% Pervious Area
2,974		37.17% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.6	128	0.0250	3.87	7.74	<b>Channel Flow, Channel Flow</b> Area= 2.0 sf Perim= 20.2' r= 0.10' n= 0.013 Asphalt, smooth
4.4					<b>Direct Entry, Min Tc of 5 Min</b>
5.0	128	Total			

**Summary for Reach 2R: PR-05**

Inflow Area = 20,953 sf, 46.74% Impervious, Inflow Depth > 1.94" for 10-YR event  
 Inflow = 0.5 cfs @ 12.50 hrs, Volume= 3,393 cf  
 Outflow = 0.1 cfs @ 14.59 hrs, Volume= 2,861 cf, Atten= 77%, Lag= 125.3 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs / 2  
 Max. Velocity= 0.11 fps, Min. Travel Time= 172.5 min  
 Avg. Velocity = 0.08 fps, Avg. Travel Time= 228.8 min

Peak Storage= 1,162 cf @ 14.59 hrs  
 Average Depth at Peak Storage= 0.03', Surface Width= 33.33'  
 Bank-Full Depth= 1.00' Flow Area= 80.0 sf, Capacity= 60.8 cfs

30.00' x 1.00' deep channel, n= 0.100 Earth, dense brush, high stage  
 Side Slope Z-value= 50.0 ' / ' Top Width= 130.00'  
 Length= 1,100.0' Slope= 0.0050 ' / '  
 Inlet Invert= 27.50', Outlet Invert= 22.00'



**477361-00\_PRE-&-POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Post Development (10 yr)  
Type III 24-hr 10-YR Rainfall=5.65"

Printed 3/4/2020

Page 17

**Summary for Reach PR01: PR-01**

Inflow Area = 501,780 sf, 0.00% Impervious, Inflow Depth > 1.35" for 10-YR event  
Inflow = 4.8 cfs @ 13.43 hrs, Volume= 56,442 cf  
Outflow = 4.5 cfs @ 13.70 hrs, Volume= 55,208 cf, Atten= 6%, Lag= 15.9 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs / 2  
Max. Velocity= 0.42 fps, Min. Travel Time= 21.1 min  
Avg. Velocity = 0.24 fps, Avg. Travel Time= 36.7 min

Peak Storage= 5,651 cf @ 13.70 hrs  
Average Depth at Peak Storage= 0.08' , Surface Width= 142.58'  
Bank-Full Depth= 2.00' Flow Area= 470.0 sf, Capacity= 1,413.2 cfs

135.00' x 2.00' deep channel, n= 0.050 Scattered brush, heavy weeds  
Side Slope Z-value= 50.0 ' / ' Top Width= 335.00'  
Length= 537.0' Slope= 0.0065 ' / '  
Inlet Invert= 26.50', Outlet Invert= 23.00'



**Summary for Reach PR02: PR02**

Inflow Area = 760,995 sf, 10.02% Impervious, Inflow Depth > 2.40" for 10-YR event  
Inflow = 17.3 cfs @ 12.84 hrs, Volume= 152,048 cf  
Outflow = 15.9 cfs @ 13.02 hrs, Volume= 149,571 cf, Atten= 8%, Lag= 10.8 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs / 2  
Max. Velocity= 0.71 fps, Min. Travel Time= 15.7 min  
Avg. Velocity = 0.28 fps, Avg. Travel Time= 39.2 min

Peak Storage= 14,957 cf @ 13.02 hrs  
Average Depth at Peak Storage= 0.20' , Surface Width= 123.67'  
Bank-Full Depth= 2.00' Flow Area= 408.0 sf, Capacity= 1,097.9 cfs

104.00' x 2.00' deep channel, n= 0.050 Scattered brush, heavy weeds  
Side Slope Z-value= 50.0 ' / ' Top Width= 304.00'  
Length= 668.0' Slope= 0.0055 ' / '  
Inlet Invert= 25.70', Outlet Invert= 22.00'





**477361-00\_PRE-&POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Post Development (10 yr)  
Type III 24-hr 10-YR Rainfall=5.65"

Printed 3/4/2020

Page 18


**Summary for Reach PR03: PR03**

Inflow Area = 255,973 sf, 14.18% Impervious, Inflow Depth > 2.47" for 10-YR event  
Inflow = 7.3 cfs @ 12.65 hrs, Volume= 52,606 cf  
Outflow = 5.2 cfs @ 13.02 hrs, Volume= 51,160 cf, Atten= 29%, Lag= 22.4 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs / 2  
Max. Velocity= 0.52 fps, Min. Travel Time= 28.9 min  
Avg. Velocity = 0.27 fps, Avg. Travel Time= 54.8 min

Peak Storage= 9,004 cf @ 13.02 hrs  
Average Depth at Peak Storage= 0.09' , Surface Width= 111.02'  
Bank-Full Depth= 2.00' Flow Area= 358.0 sf, Capacity= 1,142.3 cfs

104.00' x 2.00' deep channel, n= 0.080 Earth, long dense weeds  
Side Slope Z-value= 50.0 25.0 '/' Top Width= 254.00'  
Length= 894.0' Slope= 0.0187 '/'  
Inlet Invert= 43.50', Outlet Invert= 26.80'



**Summary for Reach PR04: PR-04**

[63] Warning: Exceeded Reach PR07 INLET depth by 0.05' @ 12.30 hrs

Inflow Area = 1,172,686 sf, 1.46% Impervious, Inflow Depth > 1.74" for 10-YR event  
Inflow = 14.7 cfs @ 13.28 hrs, Volume= 170,095 cf  
Outflow = 14.0 cfs @ 13.48 hrs, Volume= 167,052 cf, Atten= 5%, Lag= 11.8 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs / 2  
Max. Velocity= 0.65 fps, Min. Travel Time= 17.5 min  
Avg. Velocity = 0.34 fps, Avg. Travel Time= 33.7 min

Peak Storage= 14,689 cf @ 13.48 hrs  
Average Depth at Peak Storage= 0.15' , Surface Width= 150.25'  
Bank-Full Depth= 3.00' Flow Area= 569.4 sf, Capacity= 2,431.4 cfs

146.00' x 3.00' deep channel, n= 0.080 Earth, long dense weeds  
Side Slope Z-value= 17.0 12.2 '/' Top Width= 233.60'  
Length= 682.0' Slope= 0.0161 '/'  
Inlet Invert= 33.00', Outlet Invert= 22.00'



**Summary for Reach PR05a: PR-05**

Inflow = 0.0 cfs @ 0.00 hrs, Volume= 0 cf  
 Outflow = 0.0 cfs @ 0.00 hrs, Volume= 0 cf, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs / 2  
 Max. Velocity= 0.00 fps, Min. Travel Time= 0.0 min  
 Avg. Velocity = 0.00 fps, Avg. Travel Time= 0.0 min

Peak Storage= 0 cf @ 0.00 hrs  
 Average Depth at Peak Storage= 0.00'  
 Bank-Full Depth= 1.00' Flow Area= 80.0 sf, Capacity= 106.1 cfs

30.00' x 1.00' deep channel, n= 0.100 Earth, dense brush, high stage  
 Side Slope Z-value= 50.0 ' ' Top Width= 130.00'  
 Length= 46.0' Slope= 0.0152 ' '  
 Inlet Invert= 27.50', Outlet Invert= 26.80'




**Summary for Reach PR05b: PR-05**

Inflow Area = 37,196 sf, 48.36% Impervious, Inflow Depth > 1.82" for 10-YR event  
 Inflow = 0.1 cfs @ 15.89 hrs, Volume= 5,650 cf  
 Outflow = 0.1 cfs @ 15.93 hrs, Volume= 5,623 cf, Atten= 0%, Lag= 2.1 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs / 2  
 Max. Velocity= 0.20 fps, Min. Travel Time= 3.9 min  
 Avg. Velocity = 0.17 fps, Avg. Travel Time= 4.5 min

Peak Storage= 29 cf @ 15.93 hrs  
 Average Depth at Peak Storage= 0.02' , Surface Width= 32.03'  
 Bank-Full Depth= 1.00' Flow Area= 80.0 sf, Capacity= 155.3 cfs

30.00' x 1.00' deep channel, n= 0.100 Earth, dense brush, high stage  
 Side Slope Z-value= 50.0 ' ' Top Width= 130.00'  
 Length= 46.0' Slope= 0.0326 ' '  
 Inlet Invert= 27.50', Outlet Invert= 26.00'



**Summary for Reach PR06: PR-06**

Inflow Area = 42,430 sf, 47.09% Impervious, Inflow Depth > 3.68" for 10-YR event  
 Inflow = 1.4 cfs @ 12.49 hrs, Volume= 13,019 cf  
 Outflow = 1.2 cfs @ 12.65 hrs, Volume= 12,897 cf, Atten= 20%, Lag= 9.8 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs / 2  
 Max. Velocity= 0.24 fps, Min. Travel Time= 13.6 min  
 Avg. Velocity = 0.13 fps, Avg. Travel Time= 25.1 min

Peak Storage= 939 cf @ 12.65 hrs  
 Average Depth at Peak Storage= 0.13' , Surface Width= 43.28'  
 Bank-Full Depth= 1.00' Flow Area= 80.0 sf, Capacity= 58.7 cfs

30.00' x 1.00' deep channel, n= 0.100 Earth, dense brush, high stage  
 Side Slope Z-value= 50.0 ' / ' Top Width= 130.00'  
 Length= 193.0' Slope= 0.0047 ' / '  
 Inlet Invert= 44.90', Outlet Invert= 44.00'




**Summary for Reach PR07: PR-07**

Inflow Area = 1,016,726 sf, 1.14% Impervious, Inflow Depth > 1.65" for 10-YR event  
 Inflow = 14.4 cfs @ 13.10 hrs, Volume= 139,519 cf  
 Outflow = 13.7 cfs @ 13.29 hrs, Volume= 137,296 cf, Atten= 5%, Lag= 11.8 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs / 2  
 Max. Velocity= 0.74 fps, Min. Travel Time= 15.3 min  
 Avg. Velocity = 0.35 fps, Avg. Travel Time= 32.5 min

Peak Storage= 12,544 cf @ 13.29 hrs  
 Average Depth at Peak Storage= 0.19' , Surface Width= 104.26'  
 Bank-Full Depth= 2.00' Flow Area= 346.0 sf, Capacity= 992.5 cfs

88.00' x 2.00' deep channel, n= 0.080 Earth, long dense weeds  
 Side Slope Z-value= 25.0 60.0 ' / ' Top Width= 258.00'  
 Length= 682.0' Slope= 0.0161 ' / '  
 Inlet Invert= 33.00', Outlet Invert= 22.00'



**Summary for Pond 1P: (new Pond)**

[57] Hint: Peaked at 26.60' (Flood elevation advised)

Inflow Area = 3,773 sf, 66.10% Impervious, Inflow Depth > 4.39" for 10-YR event  
 Inflow = 0.4 cfs @ 12.07 hrs, Volume= 1,382 cf  
 Outflow = 0.4 cfs @ 12.07 hrs, Volume= 1,382 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.4 cfs @ 12.07 hrs, Volume= 1,382 cf

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs / 2  
 Peak Elev= 26.60' @ 12.07 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	26.50'	<b>48.0" W x 4.0" H Vert. Orifice/Grate</b> C= 0.600 Limited to weir flow at low heads

**Primary OutFlow** Max=0.4 cfs @ 12.07 hrs HW=26.60' TW=0.00' (Dynamic Tailwater)  
 ↑1=Orifice/Grate (Orifice Controls 0.4 cfs @ 1.02 fps)

**Summary for Pond 2P: (new Pond)**

[57] Hint: Peaked at 26.60' (Flood elevation advised)

Inflow Area = 3,612 sf, 69.10% Impervious, Inflow Depth > 4.50" for 10-YR event  
 Inflow = 0.4 cfs @ 12.07 hrs, Volume= 1,355 cf  
 Outflow = 0.4 cfs @ 12.07 hrs, Volume= 1,355 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.4 cfs @ 12.07 hrs, Volume= 1,355 cf

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs / 2  
 Peak Elev= 26.60' @ 12.07 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	26.50'	<b>48.0" W x 4.0" H Vert. Orifice/Grate</b> C= 0.600 Limited to weir flow at low heads

**Primary OutFlow** Max=0.4 cfs @ 12.07 hrs HW=26.60' TW=25.74' (Dynamic Tailwater)  
 ↑1=Orifice/Grate (Orifice Controls 0.4 cfs @ 1.02 fps)

**Summary for Pond CB01: CB-01**

[87] Warning: Oscillations may require smaller dt or Finer Routing (severity=44)

Inflow Area = 7,913 sf, 43.27% Impervious, Inflow Depth > 3.56" for 10-YR event  
 Inflow = 0.8 cfs @ 12.07 hrs, Volume= 2,350 cf  
 Outflow = 0.8 cfs @ 12.07 hrs, Volume= 2,350 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.8 cfs @ 12.07 hrs, Volume= 2,350 cf

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs / 2  
 Peak Elev= 33.79' @ 18.12 hrs  
 Flood Elev= 35.40'

Device	Routing	Invert	Outlet Devices
#1	Primary	32.20'	<b>12.0" Round Culvert</b> L= 12.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 32.20' / 32.05' S= 0.0125 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.7 cfs @ 12.07 hrs HW=32.67' TW=31.81' (Dynamic Tailwater)  
 ↑**1=Culvert** (Barrel Controls 0.7 cfs @ 2.92 fps)

**Summary for Pond CB02: CB-02**

[87] Warning: Oscillations may require smaller dt or Finer Routing (severity=68)

Inflow Area = 7,620 sf, 43.87% Impervious, Inflow Depth > 3.56" for 10-YR event  
 Inflow = 0.7 cfs @ 12.07 hrs, Volume= 2,263 cf  
 Outflow = 0.7 cfs @ 12.07 hrs, Volume= 2,259 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.7 cfs @ 12.07 hrs, Volume= 2,259 cf

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs / 2  
 Peak Elev= 33.98' @ 17.61 hrs  
 Flood Elev= 35.40'

Device	Routing	Invert	Outlet Devices
#1	Primary	32.20'	<b>22.0" Round Culvert</b> L= 12.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 32.20' / 32.05' S= 0.0125 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 2.64 sf

**Primary OutFlow** Max=0.7 cfs @ 12.07 hrs HW=32.58' TW=31.81' (Dynamic Tailwater)  
 ↑**1=Culvert** (Barrel Controls 0.7 cfs @ 2.73 fps)

**Summary for Pond CB03: CB-03**

Inflow Area = 8,958 sf, 58.47% Impervious, Inflow Depth > 4.29" for 10-YR event  
 Inflow = 1.0 cfs @ 12.08 hrs, Volume= 3,200 cf  
 Outflow = 1.0 cfs @ 12.08 hrs, Volume= 3,200 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 1.0 cfs @ 12.08 hrs, Volume= 3,200 cf

**477361-00\_PRE-&POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Post Development (10 yr)  
Type III 24-hr 10-YR Rainfall=5.65"

Printed 3/4/2020

Page 23

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs / 2

Peak Elev= 41.51' @ 12.08 hrs

Flood Elev= 45.95'

Device	Routing	Invert	Outlet Devices
#1	Primary	41.00'	<b>12.0" Round Culvert</b> L= 42.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 41.00' / 39.20' S= 0.0429 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.9 cfs @ 12.08 hrs HW=41.50' TW=34.26' (Dynamic Tailwater)

↑**1=Culvert** (Inlet Controls 0.9 cfs @ 2.40 fps)

**Summary for Pond CB04: CB-04**

Inflow Area = 12,705 sf, 47.10% Impervious, Inflow Depth > 3.87" for 10-YR event  
 Inflow = 1.2 cfs @ 12.11 hrs, Volume= 4,093 cf  
 Outflow = 1.2 cfs @ 12.11 hrs, Volume= 4,093 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 1.2 cfs @ 12.11 hrs, Volume= 4,093 cf

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs / 2

Peak Elev= 41.58' @ 12.11 hrs

Flood Elev= 44.90'

Device	Routing	Invert	Outlet Devices
#1	Primary	41.00'	<b>12.0" Round Culvert</b> L= 37.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 41.00' / 39.20' S= 0.0486 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=1.2 cfs @ 12.11 hrs HW=41.57' TW=34.48' (Dynamic Tailwater)

↑**1=Culvert** (Inlet Controls 1.2 cfs @ 2.57 fps)

**Summary for Pond CB05: CB-05**

Inflow Area = 5,051 sf, 20.97% Impervious, Inflow Depth > 3.27" for 10-YR event  
 Inflow = 0.4 cfs @ 12.08 hrs, Volume= 1,376 cf  
 Outflow = 0.4 cfs @ 12.08 hrs, Volume= 1,376 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.4 cfs @ 12.08 hrs, Volume= 1,376 cf

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs / 2

Peak Elev= 47.98' @ 12.47 hrs

Flood Elev= 48.58'

Device	Routing	Invert	Outlet Devices
#1	Primary	46.30'	<b>6.0" Round Culvert</b> L= 15.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 46.30' / 46.15' S= 0.0100 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.20 sf

**Primary OutFlow** Max=0.4 cfs @ 12.08 hrs HW=47.22' TW=47.02' (Dynamic Tailwater)

↑1=Culvert (Inlet Controls 0.4 cfs @ 2.18 fps)

**Summary for Pond CB06: CB-06**

Inflow Area = 4,235 sf, 19.50% Impervious, Inflow Depth > 3.27" for 10-YR event  
 Inflow = 0.4 cfs @ 12.08 hrs, Volume= 1,154 cf  
 Outflow = 0.4 cfs @ 12.08 hrs, Volume= 1,154 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.4 cfs @ 12.08 hrs, Volume= 1,154 cf

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs / 2

Peak Elev= 45.60' @ 12.08 hrs

Flood Elev= 48.58'

Device	Routing	Invert	Outlet Devices
#1	Primary	45.15'	<b>6.0" Round Culvert</b> L= 15.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 45.15' / 45.00' S= 0.0100 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.20 sf

**Primary OutFlow** Max=0.4 cfs @ 12.08 hrs HW=45.59' TW=44.77' (Dynamic Tailwater)

↑1=Culvert (Barrel Controls 0.4 cfs @ 2.60 fps)

**Summary for Pond CB07: CB-07**

Inflow Area = 37,379 sf, 50.62% Impervious, Inflow Depth > 3.86" for 10-YR event  
 Inflow = 3.0 cfs @ 12.17 hrs, Volume= 12,028 cf  
 Outflow = 3.0 cfs @ 12.17 hrs, Volume= 12,028 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 3.0 cfs @ 12.17 hrs, Volume= 12,028 cf

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs / 2

Peak Elev= 50.61' @ 12.17 hrs

Flood Elev= 52.50'

Device	Routing	Invert	Outlet Devices
#1	Primary	49.50'	<b>12.0" Round Culvert</b> L= 114.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 49.50' / 47.50' S= 0.0175 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=2.9 cfs @ 12.17 hrs HW=50.60' TW=47.41' (Dynamic Tailwater)

↑1=Culvert (Inlet Controls 2.9 cfs @ 3.73 fps)

**Summary for Pond CB08: CB-08**

Inflow Area = 16,718 sf, 53.64% Impervious, Inflow Depth > 3.89" for 10-YR event  
 Inflow = 1.6 cfs @ 12.10 hrs, Volume= 5,414 cf  
 Outflow = 1.6 cfs @ 12.10 hrs, Volume= 5,414 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 1.6 cfs @ 12.10 hrs, Volume= 5,414 cf

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs / 2  
 Peak Elev= 50.18' @ 12.10 hrs  
 Flood Elev= 52.50'

Device	Routing	Invert	Outlet Devices
#1	Primary	49.50'	<b>12.0" Round Culvert</b> L= 110.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 49.50' / 46.00' S= 0.0318 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=1.5 cfs @ 12.10 hrs HW=50.17' TW=44.85' (Dynamic Tailwater)  
 ↑**1=Culvert** (Inlet Controls 1.5 cfs @ 2.78 fps)

**Summary for Pond MH01: MH 1**

[57] Hint: Peaked at 28.67' (Flood elevation advised)

Inflow Area = 37,196 sf, 48.36% Impervious, Inflow Depth > 1.82" for 10-YR event  
 Inflow = 0.1 cfs @ 15.89 hrs, Volume= 5,650 cf  
 Outflow = 0.1 cfs @ 15.89 hrs, Volume= 5,650 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.1 cfs @ 15.89 hrs, Volume= 5,650 cf

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs / 2  
 Peak Elev= 28.67' @ 15.89 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	28.50'	<b>12.0" Round Culvert</b> L= 91.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 28.50' / 27.75' S= 0.0082 '/ Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.1 cfs @ 15.89 hrs HW=28.67' TW=27.52' (Dynamic Tailwater)  
 ↑**1=Culvert** (Barrel Controls 0.1 cfs @ 2.04 fps)

**Summary for Pond MH05: MH 5**

[57] Hint: Peaked at 51.32' (Flood elevation advised)

Inflow Area = 8,001 sf, 37.17% Impervious, Inflow Depth > 0.12" for 10-YR event  
 Inflow = 0.0 cfs @ 24.00 hrs, Volume= 83 cf  
 Outflow = 0.0 cfs @ 24.00 hrs, Volume= 83 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.0 cfs @ 24.00 hrs, Volume= 83 cf



**477361-00\_PRE-&POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Post Development (10 yr)  
Type III 24-hr 10-YR Rainfall=5.65"

Printed 3/4/2020

Page 26

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs / 2

Peak Elev= 51.32' @ 24.00 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	51.30'	<b>12.0" Round Culvert</b> L= 65.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 51.30' / 47.90' S= 0.0523 ' S= 0.0523 ' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.0 cfs @ 24.00 hrs HW=51.32' TW=33.04' (Dynamic Tailwater)

↑1=Culvert (Inlet Controls 0.0 cfs @ 0.49 fps)

**Summary for Pond P003a: R-Tank #1 and 2**

[80] Warning: Exceeded Pond CB01 by 1.32' @ 21.78 hrs (3.2 cfs 13,781 cf)

[80] Warning: Exceeded Pond CB02 by 1.58' @ 17.52 hrs (8.4 cfs 43,523 cf)

Inflow Area =	15,533 sf, 43.57% Impervious, Inflow Depth > 4.30" for 10-YR event
Inflow =	1.5 cfs @ 12.07 hrs, Volume= 5,570 cf
Outflow =	0.1 cfs @ 18.15 hrs, Volume= 2,569 cf, Atten= 96%, Lag= 364.7 min
Primary =	0.1 cfs @ 18.15 hrs, Volume= 2,569 cf
Secondary =	0.0 cfs @ 0.00 hrs, Volume= 0 cf

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs / 2

Peak Elev= 33.79' @ 18.15 hrs Surf.Area= 2,953 sf Storage= 3,609 cf

Flood Elev= 36.68' Surf.Area= 2,953 sf Storage= 4,369 cf

Plug-Flow detention time= 352.9 min calculated for 2,569 cf (46% of inflow)

Center-of-Mass det. time= 222.1 min ( 1,056.9 - 834.8 )

Volume	Invert	Avail.Storage	Storage Description
#1	28.95'	295 cf	<b>14.50'W x 50.90'L x 1.00'H StoneL</b> 738 cf Overall x 40.0% Voids
#2	29.95'	221 cf	<b>14.50'W x 50.90'L x 1.50'H Filter SoilL-Impervious</b> 1,107 cf Overall x 20.0% Voids
#3B	31.45'	588 cf	<b>14.50'W x 50.92'L x 3.48'H Field B</b> 2,570 cf Overall - 1,099 cf Embedded = 1,471 cf x 40.0% Voids
#4B	31.70'	1,044 cf	<b>ACF R-Tank SD 3 x 160 Inside #3</b> Inside= 15.7"W x 26.8"H => 2.78 sf x 2.35'L = 6.5 cf Outside= 15.7"W x 26.8"H => 2.93 sf x 2.35'L = 6.9 cf 160 Chambers in 8 Rows
#5	28.95'	295 cf	<b>14.50'W x 50.90'L x 1.00'H StoneR</b> 738 cf Overall x 40.0% Voids
#6	29.95'	221 cf	<b>14.50'W x 50.90'L x 1.50'H Filter SoilR-Impervious</b> 1,107 cf Overall x 20.0% Voids
#7C	31.45'	588 cf	<b>14.50'W x 50.92'L x 3.48'H Field C</b> 2,570 cf Overall - 1,099 cf Embedded = 1,471 cf x 40.0% Voids
#8C	31.70'	1,044 cf	<b>ACF R-Tank SD 3 x 160 Inside #7</b> Inside= 15.7"W x 26.8"H => 2.78 sf x 2.35'L = 6.5 cf Outside= 15.7"W x 26.8"H => 2.93 sf x 2.35'L = 6.9 cf 160 Chambers in 8 Rows

**477361-00\_PRE-&POST\_2020-03-02**

Post Development (10 yr)  
Type III 24-hr 10-YR Rainfall=5.65"

Prepared by {enter your company name here}

Printed 3/4/2020

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Page 27

#9	28.95'	72 cf	<b>4.00'D x 5.70'H Vertical Cone/Cylinder-Impervious</b>
			4,369 cf Total Available Storage

Storage Group B created with Chamber Wizard  
Storage Group C created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	28.95'	<b>12.0" Round UD-Culvert</b> L= 20.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 28.95' / 28.10' S= 0.0425 ' / ' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf
#2	Device 1	28.95'	<b>1.0" Vert. UD-Orifice</b> C= 0.600 Limited to weir flow at low heads
#3	Device 2	28.95'	<b>10.000 in/hr Exfiltration over Surface area</b>
#4	Secondary	33.25'	<b>18.0" Round Culvert</b> L= 53.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 33.25' / 32.45' S= 0.0151 ' / ' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 1.77 sf
#5	Device 4	34.35'	<b>12.0" Horiz. Top of Stand Pipe</b> C= 0.600 Limited to weir flow at low heads

**Primary OutFlow** Max=0.1 cfs @ 18.15 hrs HW=33.79' TW=28.67' (Dynamic Tailwater)

- ↑1=UD-Culvert (Passes 0.1 cfs of 7.9 cfs potential flow)
- ↑2=UD-Orifice (Orifice Controls 0.1 cfs @ 10.55 fps)
- ↑3=Exfiltration (Passes 0.1 cfs of 0.7 cfs potential flow)

**Secondary OutFlow** Max=0.0 cfs @ 0.00 hrs HW=28.95' TW=27.50' (Dynamic Tailwater)

- ↑4=Culvert ( Controls 0.0 cfs)
- ↑5=Top of Stand Pipe ( Controls 0.0 cfs)

**Summary for Pond PP01: CULVERTS**

- [62] Hint: Exceeded Reach 2R OUTLET depth by 3.69' @ 14.22 hrs
- [62] Hint: Exceeded Reach PR01 OUTLET depth by 2.66' @ 14.34 hrs
- [62] Hint: Exceeded Reach PR02 OUTLET depth by 3.61' @ 14.34 hrs
- [62] Hint: Exceeded Reach PR04 OUTLET depth by 3.61' @ 14.40 hrs

Inflow Area =	2,940,052 sf,	4.04% Impervious,	Inflow Depth > 1.87" for 10-YR event
Inflow =	36.2 cfs @ 13.18 hrs,	Volume=	458,481 cf
Outflow =	21.6 cfs @ 14.25 hrs,	Volume=	457,784 cf, Atten= 40%, Lag= 64.6 min
Primary =	21.6 cfs @ 14.25 hrs,	Volume=	457,784 cf
Secondary =	0.0 cfs @ 0.00 hrs,	Volume=	0 cf

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs / 2  
Peak Elev= 25.72' @ 14.25 hrs Surf.Area= 136,388 sf Storage= 78,114 cf

Plug-Flow detention time= 30.5 min calculated for 456,643 cf (100% of inflow)  
Center-of-Mass det. time= 29.7 min ( 954.1 - 924.3 )

**477361-00\_PRE-&POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Post Development (10 yr)  
Type III 24-hr 10-YR Rainfall=5.65"

Printed 3/4/2020

Page 28

Volume	Invert	Avail.Storage	Storage Description			
#1	22.00'	347,907 cf	<b>Custom Stage Data (Irregular)</b> Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)	
22.00	10	40.0	0	0	10	
24.00	5,297	274.3	3,691	3,691	5,879	
25.00	33,326	789.9	17,303	20,995	49,546	
26.00	194,474	2,151.9	102,768	123,763	368,395	
27.00	255,187	2,316.1	224,144	347,907	426,819	

Device	Routing	Invert	Outlet Devices
#1	Primary	22.40'	<b>15.0" Round RCP_Round 15"</b> L= 33.5' RCP, groove end projecting, Ke= 0.200 Inlet / Outlet Invert= 22.40' / 22.35' S= 0.0015 '/ Cc= 0.900 n= 0.011 Concrete pipe, straight & clean, Flow Area= 1.23 sf
#2	Primary	22.40'	<b>15.0" Round RCP_Round 15"</b> L= 33.5' RCP, groove end projecting, Ke= 0.200 Inlet / Outlet Invert= 22.40' / 22.35' S= 0.0015 '/ Cc= 0.900 n= 0.011 Concrete pipe, straight & clean, Flow Area= 1.23 sf
#3	Secondary	25.93'	<b>50.0' long x 20.0' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63

**Primary OutFlow** Max=21.6 cfs @ 14.25 hrs HW=25.72' TW=0.00' (Dynamic Tailwater)

└─1=RCP\_Round 15" (Barrel Controls 10.8 cfs @ 8.81 fps)

└─2=RCP\_Round 15" (Barrel Controls 10.8 cfs @ 8.81 fps)

**Secondary OutFlow** Max=0.0 cfs @ 0.00 hrs HW=22.00' TW=0.00' (Dynamic Tailwater)

└─3=Broad-Crested Rectangular Weir ( Controls 0.0 cfs)

**Summary for Pond PP02: PP02**

Inflow Area = 255,973 sf, 14.18% Impervious, Inflow Depth > 2.84" for 10-YR event  
 Inflow = 8.2 cfs @ 12.49 hrs, Volume= 60,537 cf  
 Outflow = 7.3 cfs @ 12.65 hrs, Volume= 52,606 cf, Atten= 10%, Lag= 9.1 min  
 Primary = 7.3 cfs @ 12.65 hrs, Volume= 52,606 cf

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs / 2

Peak Elev= 43.77' @ 12.67 hrs Surf.Area= 22,491 sf Storage= 12,394 cf

Plug-Flow detention time= 92.8 min calculated for 52,606 cf (87% of inflow)

Center-of-Mass det. time= 36.8 min ( 907.2 - 870.4 )

Volume	Invert	Avail.Storage	Storage Description			
#1	43.00'	17,987 cf	<b>Custom Stage Data (Irregular)</b> Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)	
43.00	10,339	760.4	0	0	10,339	
44.00	26,935	899.1	17,987	17,987	28,674	

**477361-00\_PRE-&POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Post Development (10 yr)  
Type III 24-hr 10-YR Rainfall=5.65"

Printed 3/4/2020

Page 29

Device	Routing	Invert	Outlet Devices
#1	Primary	43.53'	<b>25.0' long x 10.0' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.49 2.56 2.70 2.69 2.68 2.69 2.67 2.64

**Primary OutFlow** Max=7.3 cfs @ 12.65 hrs HW=43.77' TW=43.57' (Dynamic Tailwater)

↳ **1=Broad-Crested Rectangular Weir** (Weir Controls 7.3 cfs @ 1.21 fps)

**Summary for Pond PP03b: R-Tank #3 and 4**

Inflow Area = 21,663 sf, 51.80% Impervious, Inflow Depth > 4.04" for 10-YR event  
 Inflow = 2.2 cfs @ 12.10 hrs, Volume= 7,294 cf  
 Outflow = 0.1 cfs @ 14.58 hrs, Volume= 4,041 cf, Atten= 95%, Lag= 148.9 min  
 Primary = 0.1 cfs @ 14.58 hrs, Volume= 3,081 cf  
 Secondary = 0.0 cfs @ 14.58 hrs, Volume= 961 cf

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs / 2  
 Peak Elev= 36.69' @ 14.58 hrs Surf.Area= 2,409 sf Storage= 4,461 cf  
 Flood Elev= 39.85' Surf.Area= 2,409 sf Storage= 5,540 cf

Plug-Flow detention time= 312.2 min calculated for 4,031 cf (55% of inflow)  
 Center-of-Mass det. time= 205.8 min ( 1,006.2 - 800.4 )

Volume	Invert	Avail.Storage	Storage Description
#1	30.20'	241 cf	<b>14.50'W x 41.53'L x 1.00'H StoneL</b> 602 cf Overall x 40.0% Voids
#2	31.20'	181 cf	<b>14.50'W x 41.53'L x 1.50'H Filter SoilL-Impervious</b> 903 cf Overall x 20.0% Voids
#3B	32.70'	667 cf	<b>14.50'W x 41.53'L x 5.65'H Field B</b> 3,400 cf Overall - 1,732 cf Embedded = 1,668 cf x 40.0% Voids
#4B	32.95'	1,646 cf	<b>ACF R-Tank SD 6 x 128 Inside #3</b> Inside= 15.7"W x 52.8"H => 5.48 sf x 2.35'L = 12.9 cf Outside= 15.7"W x 52.8"H => 5.77 sf x 2.35'L = 13.5 cf 128 Chambers in 8 Rows
#5	30.20'	241 cf	<b>14.50'W x 41.53'L x 1.00'H StoneR</b> 602 cf Overall x 40.0% Voids
#6	31.20'	181 cf	<b>14.50'W x 41.53'L x 1.50'H Filter SoilR-Impervious</b> 903 cf Overall x 20.0% Voids
#7C	32.70'	667 cf	<b>14.50'W x 41.53'L x 5.65'H Field C</b> 3,400 cf Overall - 1,732 cf Embedded = 1,668 cf x 40.0% Voids
#8C	32.95'	1,646 cf	<b>ACF R-Tank SD 6 x 128 Inside #7</b> Inside= 15.7"W x 52.8"H => 5.48 sf x 2.35'L = 12.9 cf Outside= 15.7"W x 52.8"H => 5.77 sf x 2.35'L = 13.5 cf 128 Chambers in 8 Rows
#9	30.20'	72 cf	<b>4.00'D x 5.70'H Vertical Cone/Cylinder-Impervious</b>
		5,540 cf	Total Available Storage

Storage Group B created with Chamber Wizard  
 Storage Group C created with Chamber Wizard

**477361-00\_PRE-&-POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Post Development (10 yr)  
Type III 24-hr 10-YR Rainfall=5.65"

Printed 3/4/2020

Page 30

Device	Routing	Invert	Outlet Devices
#1	Primary	29.80'	<b>18.0" Round UD-Culvert</b> L= 57.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 29.80' / 28.60' S= 0.0211 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 1.77 sf
#2	Device 1	30.20'	<b>1.0" Vert. UD-Orifice</b> C= 0.600 Limited to weir flow at low heads
#3	Device 2	30.20'	<b>10.000 in/hr UD-Exfiltration over Surface area</b>
#4	Secondary	32.50'	<b>18.0" Round Culvert</b> L= 10.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 32.50' / 32.00' S= 0.0500 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 1.77 sf
#5	Device 4	35.85'	<b>1.0" Vert. Orifice X 2.00</b> C= 0.600 Limited to weir flow at low heads
#6	Device 4	37.60'	<b>6.0" Horiz. Grate X 2.00</b> C= 0.600 Limited to weir flow at low heads

**Primary OutFlow** Max=0.1 cfs @ 14.58 hrs HW=36.69' TW=28.67' (Dynamic Tailwater)

- ↑ 1=UD-Culvert (Passes 0.1 cfs of 21.1 cfs potential flow)
- ↑ 2=UD-Orifice (Orifice Controls 0.1 cfs @ 12.23 fps)
- ↑ 3=UD-Exfiltration (Passes 0.1 cfs of 0.6 cfs potential flow)

**Secondary OutFlow** Max=0.0 cfs @ 14.58 hrs HW=36.69' TW=33.44' (Dynamic Tailwater)

- ↑ 4=Culvert (Passes 0.0 cfs of 15.3 cfs potential flow)
- ↑ 5=Orifice (Orifice Controls 0.0 cfs @ 4.31 fps)
- ↑ 6=Grate ( Controls 0.0 cfs)

**Summary for Pond PP04A: Bioretention Area #2**

[87] Warning: Oscillations may require smaller dt or Finer Routing (severity=41)

Inflow Area = 42,430 sf, 47.09% Impervious, Inflow Depth > 3.79" for 10-YR event  
 Inflow = 3.3 cfs @ 12.16 hrs, Volume= 13,404 cf  
 Outflow = 1.4 cfs @ 12.49 hrs, Volume= 13,019 cf, Atten= 56%, Lag= 19.8 min  
 Primary = 1.4 cfs @ 12.49 hrs, Volume= 13,019 cf  
 Secondary = 0.0 cfs @ 0.00 hrs, Volume= 0 cf

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs / 2  
 Peak Elev= 47.97' @ 12.49 hrs Surf.Area= 3,269 sf Storage= 4,724 cf  
 Flood Elev= 49.00' Surf.Area= 4,729 sf Storage= 7,722 cf

Plug-Flow detention time= 109.7 min calculated for 13,019 cf (97% of inflow)  
 Center-of-Mass det. time= 93.2 min ( 904.2 - 810.9 )

Volume	Invert	Avail.Storage	Storage Description
#1	45.25'	386 cf	<b>Engineered Soil Above Invert (Irregular)</b> Listed below (Recalc) -Impervious 965 cf Overall x 40.0% Voids
#2	46.00'	7,336 cf	<b>Custom Stage Data (Irregular)</b> Listed below (Recalc)
		7,722 cf	Total Available Storage

**477361-00\_PRE-&POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Post Development (10 yr)  
Type III 24-hr 10-YR Rainfall=5.65"

Printed 3/4/2020

Page 31

Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
45.25	1,287	332.5	0	0	1,287
46.00	1,287	332.5	965	965	1,536

Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
46.00	1,287	332.5	0	0	1,287
48.50	3,958	379.6	6,252	6,252	4,101
48.75	4,729	392.2	1,084	7,336	4,880

Device	Routing	Invert	Outlet Devices
#1	Primary	45.25'	<b>12.0" Round Culvert</b> L= 24.0' CMP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 45.25' / 45.00' S= 0.0104 1' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#2	Device 1	45.25'	<b>3.0" Vert. Orifice</b> C= 0.600 Limited to weir flow at low heads
#3	Device 2	46.00'	<b>10.000 in/hr Exfiltration Filter Soil over Surface area</b>
#4	Device 1	47.75'	<b>12.0" Horiz. Top of Stand Pipe</b> C= 0.600 Limited to weir flow at low heads
#5	Secondary	48.00'	<b>10.0' long x 4.0' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.38 2.54 2.69 2.68 2.67 2.67 2.65 2.66 2.66 2.68 2.72 2.73 2.76 2.79 2.88 3.07 3.32

**Primary OutFlow** Max=1.4 cfs @ 12.49 hrs HW=47.97' TW=45.01' (Dynamic Tailwater)

- 1=Culvert (Passes 1.4 cfs of 5.6 cfs potential flow)
- 2=Orifice (Orifice Controls 0.4 cfs @ 7.75 fps)
- 3=Exfiltration Filter Soil (Passes 0.4 cfs of 0.8 cfs potential flow)
- 4=Top of Stand Pipe (Weir Controls 1.1 cfs @ 1.53 fps)

**Secondary OutFlow** Max=0.0 cfs @ 0.00 hrs HW=45.25' TW=44.90' (Dynamic Tailwater)

- 5=Broad-Crested Rectangular Weir ( Controls 0.0 cfs)

**Summary for Pond PP04B: Bioretention Area #3**

Inflow Area =	20,953 sf, 46.74% Impervious, Inflow Depth > 3.76" for 10-YR event
Inflow =	1.9 cfs @ 12.09 hrs, Volume= 6,568 cf
Outflow =	0.5 cfs @ 12.50 hrs, Volume= 3,393 cf, Atten= 74%, Lag= 24.4 min
Primary =	0.5 cfs @ 12.50 hrs, Volume= 3,393 cf
Secondary =	0.0 cfs @ 0.00 hrs, Volume= 0 cf

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs / 2  
Peak Elev= 45.38' @ 12.50 hrs Surf.Area= 2,575 sf Storage= 3,476 cf  
Flood Elev= 46.50' Surf.Area= 3,665 sf Storage= 6,152 cf

Plug-Flow detention time= 226.1 min calculated for 3,385 cf (52% of inflow)  
Center-of-Mass det. time= 116.3 min ( 924.2 - 807.9 )

**477361-00\_PRE-&POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Post Development (10 yr)  
Type III 24-hr 10-YR Rainfall=5.65"

Printed 3/4/2020

Page 32

Volume	Invert	Avail.Storage	Storage Description
#1	42.75'	285 cf	<b>Engineered Soil Above Invert (Irregular)</b> Listed below (Recalc) -Impervious 713 cf Overall x 40.0% Voids
#2	43.50'	5,867 cf	<b>Custom Stage Data (Irregular)</b> Listed below (Recalc)
		6,152 cf	Total Available Storage

Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.75	950	287.5	0	0	950
43.50	950	287.5	713	713	1,166

Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
43.50	950	287.5	0	0	950
46.00	3,283	334.6	4,999	4,999	3,408
46.25	3,665	347.1	868	5,867	4,091

Device	Routing	Invert	Outlet Devices
#1	Primary	42.75'	<b>15.0" Round Culvert</b> L= 24.0' CMP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 42.75' / 42.50' S= 0.0104 ' S= 0.0104 ' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 1.23 sf
#2	Device 1	42.75'	<b>0.5" Vert. Orifice</b> C= 0.600 Limited to weir flow at low heads
#3	Device 2	43.50'	<b>10.000 in/hr Exfiltration over Surface area</b>
#4	Device 1	45.25'	<b>12.0" Horiz. Top of Stand Pipe</b> C= 0.600 Limited to weir flow at low heads
#5	Secondary	45.50'	<b>10.0' long x 4.0' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.38 2.54 2.69 2.68 2.67 2.67 2.65 2.66 2.66 2.68 2.72 2.73 2.76 2.79 2.88 3.07 3.32

**Primary OutFlow** Max=0.5 cfs @ 12.50 hrs HW=45.38' TW=27.51' (Dynamic Tailwater)

- ↑ 1=Culvert (Passes 0.5 cfs of 8.4 cfs potential flow)
- ↑ 2=Orifice (Orifice Controls 0.0 cfs @ 7.78 fps)
- ↑ 3=Exfiltration (Passes 0.0 cfs of 0.6 cfs potential flow)
- ↑ 4=Top of Stand Pipe (Weir Controls 0.5 cfs @ 1.18 fps)

**Secondary OutFlow** Max=0.0 cfs @ 0.00 hrs HW=42.75' TW=27.50' (Dynamic Tailwater)

- ↑ 5=Broad-Crested Rectangular Weir ( Controls 0.0 cfs)

**Summary for Pond PP05: Bloretention Pond #1**

Inflow Area = 8,001 sf, 37.17% Impervious, Inflow Depth > 2.98" for 10-YR event  
 Inflow = 0.6 cfs @ 12.08 hrs, Volume= 1,990 cf  
 Outflow = 0.0 cfs @ 24.00 hrs, Volume= 83 cf, Atten= 100%, Lag= 715.4 min  
 Primary = 0.0 cfs @ 24.00 hrs, Volume= 83 cf

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs / 2

**477361-00\_PRE-&POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Post Development (10 yr)  
Type III 24-hr 10-YR Rainfall=5.65"

Printed 3/4/2020

Page 33

Peak Elev= 56.75' @ 24.00 hrs Surf.Area= 1,559 sf Storage= 1,906 cf  
Flood Elev= 58.50' Surf.Area= 2,696 sf Storage= 5,552 cf

Plug-Flow detention time= 454.2 min calculated for 83 cf (4% of inflow)  
Center-of-Mass det. time= 240.7 min ( 1,068.5 - 827.8 )

Volume	Invert	Avail.Storage	Storage Description			
#1	53.33'	5,552 cf	<b>Custom Stage Data (Irregular)</b> Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
53.33	1,227	140.7	0.0	0	0	1,227
53.50	1,227	140.7	0.0	0	0	1,251
54.50	1,227	140.7	40.0	491	491	1,392
56.00	1,227	140.1	20.0	368	859	1,603
57.00	1,677	159.6	100.0	1,446	2,305	2,091
58.00	2,184	178.4	100.0	1,925	4,230	2,624
58.10	2,696	205.8	100.0	244	4,474	3,462
58.50	2,696	205.8	100.0	1,078	5,552	3,545

Device	Routing	Invert	Outlet Devices
#1	Primary	53.20'	<b>12.0" Round Culvert</b> L= 87.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 53.20' / 52.30' S= 0.0103 ' S= 0.0103 ' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#2	Device 1	53.50'	<b>0.2" Vert. Orifice/Grate</b> C= 0.600 Limited to weir flow at low heads
#3	Device 1	57.50'	<b>12.0" Horiz. Orifice/Grate</b> C= 0.600 Limited to weir flow at low heads

**Primary OutFlow** Max=0.0 cfs @ 24.00 hrs HW=56.75' TW=51.32' (Dynamic Tailwater)

- 1=Culvert (Passes 0.0 cfs of 5.7 cfs potential flow)
- 2=Orifice/Grate (Orifice Controls 0.0 cfs @ 8.67 fps)
- 3=Orifice/Grate ( Controls 0.0 cfs)

**Summary for Pond PP06: Wildlife Crossings**

Inflow Area = 720,187 sf, 7.75% Impervious, Inflow Depth > 2.42" for 10-YR event  
 Inflow = 17.1 cfs @ 12.82 hrs, Volume= 145,093 cf  
 Outflow = 17.1 cfs @ 12.84 hrs, Volume= 145,070 cf, Atten= 0%, Lag= 0.8 min  
 Primary = 12.7 cfs @ 12.84 hrs, Volume= 131,716 cf  
 Secondary = 4.4 cfs @ 12.84 hrs, Volume= 13,354 cf  
 Tertiary = 0.0 cfs @ 0.00 hrs, Volume= 0 cf

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs / 2  
Peak Elev= 26.76' @ 12.84 hrs Surf.Area= 1,361 sf Storage= 520 cf

Plug-Flow detention time= 0.4 min calculated for 144,708 cf (100% of inflow)  
Center-of-Mass det. time= 0.4 min ( 899.4 - 899.0 )



**477361-00\_PRE-&POST\_2020-03-02**

Prepared by {enter your company name here}

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Post Development (10 yr)  
Type III 24-hr 10-YR Rainfall=5.65"

Printed 3/4/2020

Page 34

Volume	Invert	Avail.Storage	Storage Description			
#1	25.50'	7,358 cf	<b>Custom Stage Data (Irregular)</b> Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)	
25.50	10	40.0	0	0	10	
26.00	141	144.3	31	31	1,540	
27.00	2,025	318.1	900	932	7,940	
28.00	12,270	467.3	6,427	7,358	17,273	

Device	Routing	Invert	Outlet Devices
#1	Primary	25.80'	<b>60.0" W x 23.0" H Box Culvert</b> L= 31.5' RCP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 25.80' / 25.70' S= 0.0032 ' / Cc= 0.900 n= 0.011 Concrete pipe, straight & clean, Flow Area= 9.58 sf
#2	Secondary	26.30'	<b>60.0" W x 24.0" H Box Culvert</b> L= 31.5' RCP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 26.30' / 26.20' S= 0.0032 ' / Cc= 0.900 n= 0.011 Concrete pipe, straight & clean, Flow Area= 10.00 sf
#3	Tertiary	26.80'	<b>60.0" W x 26.0" H Box Culvert</b> L= 31.5' RCP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 26.80' / 26.70' S= 0.0032 ' / Cc= 0.900 n= 0.011 Concrete pipe, straight & clean, Flow Area= 10.83 sf
#4	Tertiary	27.70'	<b>50.0' long x 35.0' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63

**Primary OutFlow** Max=12.7 cfs @ 12.84 hrs HW=26.76' TW=25.89' (Dynamic Tailwater)

↑1=Culvert (Barrel Controls 12.7 cfs @ 3.54 fps)

**Secondary OutFlow** Max=4.4 cfs @ 12.84 hrs HW=26.76' TW=25.89' (Dynamic Tailwater)

↑2=Culvert (Barrel Controls 4.4 cfs @ 2.59 fps)

**Tertiary OutFlow** Max=0.0 cfs @ 0.00 hrs HW=25.50' TW=25.70' (Dynamic Tailwater)

↑3=Culvert ( Controls 0.0 cfs)

↑4=Broad-Crested Rectangular Weir ( Controls 0.0 cfs)

**Summary for Link PPol01: Pr Pol-01**

Inflow Area = 2,940,052 sf, 4.04% Impervious, Inflow Depth > 1.87" for 10-YR event  
 Inflow = 21.6 cfs @ 14.25 hrs, Volume= 457,784 cf  
 Primary = 21.6 cfs @ 14.25 hrs, Volume= 457,784 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs

**Summary for Link PPol02: Pr Pol-02**

Inflow Area = 57,405 sf, 0.00% Impervious, Inflow Depth > 1.75" for 10-YR event  
Inflow = 1.1 cfs @ 12.78 hrs, Volume= 8,366 cf  
Primary = 1.1 cfs @ 12.78 hrs, Volume= 8,366 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs

**Summary for Link PPol03: Proposed Wildlife Crossings**

Inflow Area = 720,187 sf, 7.75% Impervious, Inflow Depth > 2.42" for 10-YR event  
Inflow = 17.1 cfs @ 12.82 hrs, Volume= 145,093 cf  
Primary = 17.1 cfs @ 12.82 hrs, Volume= 145,093 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.06 hrs

(This Page Is Intentionally Blank)

**APPENDIX F**  
**BMP WORKSHEETS**

(This Page Is Intentionally Blank)



## FILTRATION PRACTICE DESIGN CRITERIA (Env-Wq 1508.07)

Type/Node Name:

**PP03a R-Tanks 1 and 2**

Enter the type of filtration practice (e.g., bioretention system) and the node name in the drainage analysis, if applicable

		Have you reviewed the restrictions on unlined systems outlined in Env-Wq 1508.07(a)?	
0.36	ac	A = Area draining to the practice	
0.16	ac	A <sub>I</sub> = Impervious area draining to the practice	
0.44	decimal	I = percent impervious area draining to the practice, in decimal form	
0.44	unitless	R <sub>v</sub> = Runoff coefficient = 0.05 + (0.9 x I)	
0.16	ac-in	WQV = 1" x R <sub>v</sub> x A	
572	cf	WQV conversion (ac-in x 43,560 sf/ac x 1ft/12")	
143	cf	25% x WQV (check calc for sediment forebay volume)	
429	cf	75% x WQV (check calc for surface sand filter volume)	
Deep Sump CB		Method of Pretreatment? (not required for clean or roof runoff)	
NA	cf	V <sub>SED</sub> = sediment forebay volume, if used for pretreatment	← ≥ 25%WQV
1,476	sf	A <sub>SA</sub> = surface area of the practice	
NA	iph	K <sub>sat</sub> <sub>DESIGN</sub> = design infiltration rate <sup>1</sup>	
Yes	Yes/No	If K <sub>sat</sub> (prior to factor of safety) is < 0.50 iph, has an underdrain been provided?	
-	hours	T <sub>DRAIN</sub> = drain time = V / (A <sub>SA</sub> * I <sub>DESIGN</sub> )	← ≤ 72-hrs
29.95	feet	E <sub>FC</sub> = elevation of the bottom of the filter course material <sup>2</sup>	
28.95	feet	E <sub>UD</sub> = invert elevation of the underdrain (UD), if applicable	
NA	feet	E <sub>SHWT</sub> = elevation of SHWT (if none found, enter the lowest elevation of the test pit)	
NA	feet	E <sub>ROCK</sub> = elevation of bedrock (if none found, enter the lowest elevation of the test pit)	
1.00	feet	D <sub>FC to UD</sub> = depth to UD from the bottom of the filter course	← ≥ 1'
#VALUE!	feet	D <sub>FC to ROCK</sub> = depth to bedrock from the bottom of the filter course	← ≥ 1'
#VALUE!	feet	D <sub>FC to SHWT</sub> = depth to SHWT from the bottom of the filter course	← ≥ 1'
34.88	ft	Peak elevation of the 50-year storm event (infiltration can be used in analysis)	
34.93	ft	Elevation of the top of the practice	
YES		50 peak elevation ≤ Elevation of the top of the practice	← yes

**If a surface sand filter or underground sand filter is proposed:**

YES	ac	Drainage Area check.	← < 10 ac
	cf	V = volume of storage <sup>3</sup> (attach a stage-storage table)	← ≥ 75%WQV
	inches	D <sub>FC</sub> = filter course thickness	← 18", or 24" if within GPA
Sheet		Note what sheet in the plan set contains the filter course specification	
	Yes/No	Access grate provided?	← yes



**Stage-Area-Storage for Pond P003a: R-Tank #1 and 2**

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
29.20	1,476	0	34.50	2,953	3,962
29.30	1,476	60	34.60	2,953	4,023
29.40	1,476	121	34.70	2,953	4,083
29.50	1,476	181	34.80	2,953	4,143
29.60	1,476	241	34.90	2,953	4,203
29.70	1,476	302	35.00	2,953	4,263
29.80	1,476	362	35.10	2,953	4,322
29.90	1,476	422	35.20	2,953	4,369
30.00	1,476	482	35.30	2,953	4,369
30.10	1,476	543	35.40	2,953	4,369
30.20	1,476	603	35.50	2,953	4,369
30.30	1,476	634	35.60	2,953	4,369
30.40	1,476	665	35.70	2,953	4,369
30.50	1,476	695	35.80	2,953	4,369
30.60	1,476	726	35.90	2,953	4,369
30.70	1,476	757	36.00	2,953	4,369
30.80	1,476	788	36.10	2,953	4,369
30.90	1,476	818	36.20	2,953	4,369
31.00	1,476	849	36.30	2,953	4,369
31.10	1,476	880	36.40	2,953	4,369
31.20	1,476	911	36.50	2,953	4,369
31.30	1,476	942	36.60	2,953	4,369
31.40	1,476	972	36.70	2,953	4,369
31.50	1,476	1,003	36.80	2,953	4,369
31.60	1,476	1,034	36.90	2,953	4,369
31.70	2,953	1,065			
31.80	2,953	1,125			
31.90	2,953	1,185			
32.00	2,953	1,273			
32.10	2,953	1,387			
32.20	2,953	1,502			
32.30	2,953	1,616			
32.40	2,953	1,731			
32.50	2,953	1,845			
32.60	2,953	1,960			
32.70	2,953	2,074			
32.80	2,953	2,189			
32.90	2,953	2,303			
33.00	2,953	2,418			
33.10	2,953	2,532			
33.20	2,953	2,647			
33.30	2,953	2,761			
33.40	2,953	2,876			
33.50	2,953	2,990			
33.60	2,953	3,105			
33.70	2,953	3,219			
33.80	2,953	3,334			
33.90	2,953	3,448			
34.00	2,953	3,563			
34.10	2,953	3,677			
34.20	2,953	3,781			
34.30	2,953	3,842			
34.40	2,953	3,902			



(This Page Is Intentionally Blank)



## FILTRATION PRACTICE DESIGN CRITERIA (Env-Wq 1508.07)

**Type/Node Name:** \_\_\_\_\_

**PP03b R-Tanks 3 and 4**

Enter the type of filtration practice (e.g., bioretention system) and the node name in the drainage analysis, if applicable

		Have you reviewed the restrictions on unlined systems outlined in Env-Wq 1508.07(a)?	
0.50	ac	A = Area draining to the practice	
0.26	ac	A <sub>I</sub> = Impervious area draining to the practice	
0.52	decimal	I = percent impervious area draining to the practice, in decimal form	
0.52	unitless	R <sub>v</sub> = Runoff coefficient = 0.05 + (0.9 x I)	
0.26	ac-in	WQV = 1" x R <sub>v</sub> x A	
932	cf	WQV conversion (ac-in x 43,560 sf/ac x 1ft/12")	
233	cf	25% x WQV (check calc for sediment forebay volume)	
699	cf	75% x WQV (check calc for surface sand filter volume)	
Deep Sump CB		Method of Pretreatment? (not required for clean or roof runoff)	
NA	cf	V <sub>SED</sub> = sediment forebay volume, if used for pretreatment	← ≥ 25%WQV
1,204	sf	A <sub>SA</sub> = surface area of the practice	
NA	iph	K <sub>sat</sub> <sub>DESIGN</sub> = design infiltration rate <sup>1</sup>	
Yes	Yes/No	If K <sub>sat</sub> (prior to factor of safety) is < 0.50 iph, has an underdrain been provided?	
-	hours	T <sub>DRAIN</sub> = drain time = V / (A <sub>SA</sub> * I <sub>DESIGN</sub> )	← ≤ 72-hrs
31.20	feet	E <sub>FC</sub> = elevation of the bottom of the filter course material <sup>2</sup>	
30.20	feet	E <sub>UD</sub> = invert elevation of the underdrain (UD), if applicable	
NA	feet	E <sub>SHWT</sub> = elevation of SHWT (if none found, enter the lowest elevation of the test pit)	
NA	feet	E <sub>ROCK</sub> = elevation of bedrock (if none found, enter the lowest elevation of the test pit)	
1.00	feet	D <sub>FC to UD</sub> = depth to UD from the bottom of the filter course	← ≥ 1'
#VALUE!	feet	D <sub>FC to ROCK</sub> = depth to bedrock from the bottom of the filter course	← ≥ 1'
#VALUE!	feet	D <sub>FC to SHWT</sub> = depth to SHWT from the bottom of the filter course	← ≥ 1'
38.27	ft	Peak elevation of the 50-year storm event (infiltration can be used in analysis)	
38.35	ft	Elevation of the top of the practice	
YES		50 peak elevation ≤ Elevation of the top of the practice	← yes

**If a surface sand filter or underground sand filter is proposed:**

YES	ac	Drainage Area check.	← < 10 ac
	cf	V = volume of storage <sup>3</sup> (attach a stage-storage table)	← ≥ 75%WQV
	inches	D <sub>FC</sub> = filter course thickness	← 18", or 24" if within GPA
Sheet		Note what sheet in the plan set contains the filter course specification	
	Yes/No	Access grate provided?	← yes



**Stage-Area-Storage for Pond PP03b: R-Tank #3 and 4**

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
30.20	1,204	0	31.26	1,204	510
30.22	1,204	10	31.28	1,204	515
30.24	1,204	20	31.30	1,204	520
30.26	1,204	30	31.32	1,204	525
30.28	1,204	40	31.34	1,204	530
30.30	1,204	49	31.36	1,204	535
30.32	1,204	59	31.38	1,204	540
30.34	1,204	69	31.40	1,204	545
30.36	1,204	79	31.42	1,204	550
30.38	1,204	89	31.44	1,204	555
30.40	1,204	99	31.46	1,204	560
30.42	1,204	109	31.48	1,204	565
30.44	1,204	119	31.50	1,204	570
30.46	1,204	129	31.52	1,204	575
30.48	1,204	138	31.54	1,204	580
30.50	1,204	148	31.56	1,204	586
30.52	1,204	158	31.58	1,204	591
30.54	1,204	168	31.60	1,204	596
30.56	1,204	178	31.62	1,204	601
30.58	1,204	188	31.64	1,204	606
30.60	1,204	198	31.66	1,204	611
30.62	1,204	208	31.68	1,204	616
30.64	1,204	217	31.70	1,204	621
30.66	1,204	227	31.72	1,204	626
30.68	1,204	237	31.74	1,204	631
30.70	1,204	247	31.76	1,204	636
30.72	1,204	257	31.78	1,204	641
30.74	1,204	267	31.80	1,204	646
30.76	1,204	277	31.82	1,204	651
30.78	1,204	287	31.84	1,204	657
30.80	1,204	297	31.86	1,204	662
30.82	1,204	306	31.88	1,204	667
30.84	1,204	316	31.90	1,204	672
30.86	1,204	326	31.92	1,204	677
30.88	1,204	336	31.94	1,204	682
30.90	1,204	346	31.96	1,204	687
30.92	1,204	356	31.98	1,204	692
30.94	1,204	366	32.00	1,204	697
30.96	1,204	376	32.02	1,204	702
30.98	1,204	386	32.04	1,204	707
31.00	1,204	395	32.06	1,204	712
31.02	1,204	405	32.08	1,204	717
31.04	1,204	415	32.10	1,204	722
31.06	1,204	425	32.12	1,204	727
31.08	1,204	435	32.14	1,204	733
31.10	1,204	445	32.16	1,204	738
31.12	1,204	455	32.18	1,204	743
31.14	1,204	465	32.20	1,204	748
31.16	1,204	475	32.22	1,204	753
31.18	1,204	484	32.24	1,204	758
31.20	1,204	494	32.26	1,204	763
31.22	1,204	499	32.28	1,204	768
31.24	1,204	504	32.30	1,204	773

**Stage-Area-Storage for Pond PP03b: R-Tank #3 and 4 (continued)**

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
32.32	1,204	778	33.38	2,409	1,397
32.34	1,204	783	33.40	2,409	1,416
32.36	1,204	788	33.42	2,409	1,434
32.38	1,204	793	33.44	2,409	1,453
32.40	1,204	798	33.46	2,409	1,471
32.42	1,204	804	33.48	2,409	1,490
32.44	1,204	809	33.50	2,409	1,508
32.46	1,204	814	33.52	2,409	1,527
32.48	1,204	819	33.54	2,409	1,545
32.50	1,204	824	33.56	2,409	1,564
32.52	1,204	829	33.58	2,409	1,583
32.54	1,204	834	33.60	2,409	1,601
32.56	1,204	839	33.62	2,409	1,620
32.58	1,204	844	33.64	2,409	1,638
32.60	1,204	849	33.66	2,409	1,657
32.62	1,204	854	33.68	2,409	1,675
32.64	1,204	859	33.70	2,409	1,694
32.66	1,204	864	33.72	2,409	1,712
32.68	1,204	869	33.74	2,409	1,731
32.70	<b>2,409</b>	874	33.76	2,409	1,750
32.72	2,409	884	33.78	2,409	1,768
32.74	2,409	894	33.80	2,409	1,787
32.76	2,409	904	33.82	2,409	1,805
32.78	2,409	914	33.84	2,409	1,824
32.80	2,409	924	33.86	2,409	1,842
32.82	2,409	934	33.88	2,409	1,861
32.84	2,409	944	33.90	2,409	1,879
32.86	2,409	954	33.92	2,409	1,898
32.88	2,409	963	33.94	2,409	1,917
32.90	2,409	973	33.96	2,409	1,935
32.92	2,409	983	33.98	2,409	1,954
32.94	2,409	993	34.00	2,409	1,972
32.96	2,409	1,007	34.02	2,409	1,991
32.98	2,409	1,026	34.04	2,409	2,009
33.00	2,409	1,044	34.06	2,409	2,028
33.02	2,409	1,063	34.08	2,409	2,046
33.04	2,409	1,082	34.10	2,409	2,065
33.06	2,409	1,100	34.12	2,409	2,084
33.08	2,409	1,119	34.14	2,409	2,102
33.10	2,409	1,137	34.16	2,409	2,121
33.12	2,409	1,156	34.18	2,409	2,139
33.14	2,409	1,174	34.20	2,409	2,158
33.16	2,409	1,193	34.22	2,409	2,176
33.18	2,409	1,211	34.24	2,409	2,195
33.20	2,409	1,230	34.26	2,409	2,213
33.22	2,409	1,249	34.28	2,409	2,232
33.24	2,409	1,267	34.30	2,409	2,251
33.26	2,409	1,286	34.32	2,409	2,269
33.28	2,409	1,304	34.34	2,409	2,288
33.30	2,409	1,323	34.36	2,409	2,306
33.32	2,409	1,341	34.38	2,409	2,325
33.34	2,409	1,360	34.40	2,409	2,343
33.36	2,409	1,378	34.42	2,409	2,362

**Stage-Area-Storage for Pond PP03b: R-Tank #3 and 4 (continued)**

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
34.44	2,409	2,380	35.50	2,409	3,364
34.46	2,409	2,399	35.52	2,409	3,382
34.48	2,409	2,418	35.54	2,409	3,401
34.50	2,409	2,436	35.56	2,409	3,419
34.52	2,409	2,455	35.58	2,409	3,438
34.54	2,409	2,473	35.60	2,409	3,457
34.56	2,409	2,492	35.62	2,409	3,475
34.58	2,409	2,510	35.64	2,409	3,494
34.60	2,409	2,529	35.66	2,409	3,512
34.62	2,409	2,547	35.68	2,409	3,531
34.64	2,409	2,566	35.70	2,409	3,549
34.66	2,409	2,585	35.72	2,409	3,568
34.68	2,409	2,603	35.74	2,409	3,586
34.70	2,409	2,622	35.76	2,409	3,605
34.72	2,409	2,640	35.78	2,409	3,624
34.74	2,409	2,659	35.80	2,409	3,642
34.76	2,409	2,677	35.82	2,409	3,661
34.78	2,409	2,696	35.84	2,409	3,679
34.80	2,409	2,714	35.86	2,409	3,698
34.82	2,409	2,733	35.88	2,409	3,716
34.84	2,409	2,752	35.90	2,409	3,735
34.86	2,409	2,770	35.92	2,409	3,753
34.88	2,409	2,789	35.94	2,409	3,772
34.90	2,409	2,807	35.96	2,409	3,790
34.92	2,409	2,826	35.98	2,409	3,808
34.94	2,409	2,844	36.00	2,409	3,826
34.96	2,409	2,863	36.02	2,409	3,845
34.98	2,409	2,881	36.04	2,409	3,863
35.00	2,409	2,900	36.06	2,409	3,881
35.02	2,409	2,918	36.08	2,409	3,900
35.04	2,409	2,937	36.10	2,409	3,918
35.06	2,409	2,956	36.12	2,409	3,936
35.08	2,409	2,974	36.14	2,409	3,955
35.10	2,409	2,993	36.16	2,409	3,973
35.12	2,409	3,011	36.18	2,409	3,991
35.14	2,409	3,030	36.20	2,409	4,009
35.16	2,409	3,048	36.22	2,409	4,028
35.18	2,409	3,067	36.24	2,409	4,046
35.20	2,409	3,085	36.26	2,409	4,064
35.22	2,409	3,104	36.28	2,409	4,083
35.24	2,409	3,123	36.30	2,409	4,101
35.26	2,409	3,141	36.32	2,409	4,119
35.28	2,409	3,160	36.34	2,409	4,138
35.30	2,409	3,178	36.36	2,409	4,156
35.32	2,409	3,197	36.38	2,409	4,174
35.34	2,409	3,215	36.40	2,409	4,193
35.36	2,409	3,234	36.42	2,409	4,211
35.38	2,409	3,252	36.44	2,409	4,229
35.40	2,409	3,271	36.46	2,409	4,247
35.42	2,409	3,290	36.48	2,409	4,266
35.44	2,409	3,308	36.50	2,409	4,284
35.46	2,409	3,327	36.52	2,409	4,302
35.48	2,409	3,345	36.54	2,409	4,321

**Stage-Area-Storage for Pond PP03b: R-Tank #3 and 4 (continued)**

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
36.56	2,409	4,339	37.62	2,409	5,190
36.58	2,409	4,357	37.64	2,409	5,200
36.60	2,409	4,376	37.66	2,409	5,210
36.62	2,409	4,394	37.68	2,409	5,219
36.64	2,409	4,412	37.70	2,409	5,229
36.66	2,409	4,430	37.72	2,409	5,239
36.68	2,409	4,449	37.74	2,409	5,248
36.70	2,409	4,467	37.76	2,409	5,258
36.72	2,409	4,485	37.78	2,409	5,267
36.74	2,409	4,504	37.80	2,409	5,277
36.76	2,409	4,522	37.82	2,409	5,287
36.78	2,409	4,540	37.84	2,409	5,296
36.80	2,409	4,559	37.86	2,409	5,306
36.82	2,409	4,577	37.88	2,409	5,316
36.84	2,409	4,595	37.90	2,409	5,325
36.86	2,409	4,614	37.92	2,409	5,335
36.88	2,409	4,632	37.94	2,409	5,345
36.90	2,409	4,650	37.96	2,409	5,354
36.92	2,409	4,668	37.98	2,409	5,364
36.94	2,409	4,687	38.00	2,409	5,373
36.96	2,409	4,705	38.02	2,409	5,383
36.98	2,409	4,723	38.04	2,409	5,393
37.00	2,409	4,742	38.06	2,409	5,402
37.02	2,409	4,760	38.08	2,409	5,412
37.04	2,409	4,778	38.10	2,409	5,422
37.06	2,409	4,797	38.12	2,409	5,431
37.08	2,409	4,815	38.14	2,409	5,441
37.10	2,409	4,833	38.16	2,409	5,451
37.12	2,409	4,851	38.18	2,409	5,460
37.14	2,409	4,870	38.20	2,409	5,470
37.16	2,409	4,888	38.22	2,409	5,479
37.18	2,409	4,906	38.24	2,409	5,489
37.20	2,409	4,925	38.26	2,409	5,499
37.22	2,409	4,943	38.28	2,409	5,508
37.24	2,409	4,961	38.30	2,409	5,518
37.26	2,409	4,980	38.32	2,409	5,528
37.28	2,409	4,998	38.34	2,409	5,537
37.30	2,409	5,016	38.36	2,409	<b>5,540</b>
37.32	2,409	5,034	38.38	2,409	5,540
37.34	2,409	5,053	38.40	2,409	5,540
37.36	2,409	5,065	38.42	2,409	5,540
37.38	2,409	5,075	38.44	2,409	5,540
37.40	2,409	5,084	38.46	2,409	5,540
37.42	2,409	5,094	38.48	2,409	5,540
37.44	2,409	5,104	38.50	2,409	5,540
37.46	2,409	5,113	38.52	2,409	5,540
37.48	2,409	5,123	38.54	2,409	5,540
37.50	2,409	5,133	38.56	2,409	5,540
37.52	2,409	5,142	38.58	2,409	5,540
37.54	2,409	5,152	38.60	2,409	5,540
37.56	2,409	5,162	38.62	2,409	5,540
37.58	2,409	5,171	38.64	2,409	5,540
37.60	2,409	5,181	38.66	2,409	5,540

**Stage-Area-Storage for Pond PP03b: R-Tank #3 and 4 (continued)**

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
38.68	2,409	5,540	39.74	2,409	5,540
38.70	2,409	5,540	39.76	2,409	5,540
38.72	2,409	5,540	39.78	2,409	5,540
38.74	2,409	5,540	39.80	2,409	5,540
38.76	2,409	5,540	39.82	2,409	5,540
38.78	2,409	5,540	39.84	2,409	5,540
38.80	2,409	5,540			
38.82	2,409	5,540			
38.84	2,409	5,540			
38.86	2,409	5,540			
38.88	2,409	5,540			
38.90	2,409	5,540			
38.92	2,409	5,540			
38.94	2,409	5,540			
38.96	2,409	5,540			
38.98	2,409	5,540			
39.00	2,409	5,540			
39.02	2,409	5,540			
39.04	2,409	5,540			
39.06	2,409	5,540			
39.08	2,409	5,540			
39.10	2,409	5,540			
39.12	2,409	5,540			
39.14	2,409	5,540			
39.16	2,409	5,540			
39.18	2,409	5,540			
39.20	2,409	5,540			
39.22	2,409	5,540			
39.24	2,409	5,540			
39.26	2,409	5,540			
39.28	2,409	5,540			
39.30	2,409	5,540			
39.32	2,409	5,540			
39.34	2,409	5,540			
39.36	2,409	5,540			
39.38	2,409	5,540			
39.40	2,409	5,540			
39.42	2,409	5,540			
39.44	2,409	5,540			
39.46	2,409	5,540			
39.48	2,409	5,540			
39.50	2,409	5,540			
39.52	2,409	5,540			
39.54	2,409	5,540			
39.56	2,409	5,540			
39.58	2,409	5,540			
39.60	2,409	5,540			
39.62	2,409	5,540			
39.64	2,409	5,540			
39.66	2,409	5,540			
39.68	2,409	5,540			
39.70	2,409	5,540			
39.72	2,409	5,540			



(This Page Is Intentionally Blank)



## FILTRATION PRACTICE DESIGN CRITERIA (Env-Wq 1508.07)

Type/Node Name:

**PP-04a BIORETENTION AREA #2**

Enter the type of filtration practice (e.g., bioretention system) and the node name in the drainage analysis, if applicable

		Have you reviewed the restrictions on unlined systems outlined in Env-Wq 1508.07(a)?	
0.97	ac	A = Area draining to the practice	
0.46	ac	A <sub>I</sub> = Impervious area draining to the practice	
0.47	decimal	I = percent impervious area draining to the practice, in decimal form	
0.47	unitless	R <sub>v</sub> = Runoff coefficient = 0.05 + (0.9 x I)	
0.46	ac-in	WQV = 1" x R <sub>v</sub> x A	
1,675	cf	WQV conversion (ac-in x 43,560 sf/ac x 1ft/12")	
419	cf	25% x WQV (check calc for sediment forebay volume)	
1,256	cf	75% x WQV (check calc for surface sand filter volume)	
Deep Sump		Method of Pretreatment? (not required for clean or roof runoff)	
-	cf	V <sub>SED</sub> = sediment forebay volume, if used for pretreatment	← ≥ 25%WQV
1,287	sf	A <sub>SA</sub> = surface area of the practice	
NA	iph	K <sub>sat</sub> <sub>DESIGN</sub> = design infiltration rate <sup>1</sup>	
Yes	Yes/No	If K <sub>sat</sub> (prior to factor of safety) is < 0.50 iph, has an underdrain been provided?	
-	hours	T <sub>DRAIN</sub> = drain time = V / (A <sub>SA</sub> * I <sub>DESIGN</sub> )	← ≤ 72-hrs
44.50	feet	E <sub>FC</sub> = elevation of the bottom of the filter course material <sup>2</sup>	
43.50	feet	E <sub>UD</sub> = invert elevation of the underdrain (UD), if applicable	
NA	feet	E <sub>SHWT</sub> = elevation of SHWT (if none found, enter the lowest elevation of the test pit)	
NA	feet	E <sub>ROCK</sub> = elevation of bedrock (if none found, enter the lowest elevation of the test pit)	
1.00	feet	D <sub>FC to UD</sub> = depth to UD from the bottom of the filter course	← ≥ 1'
#VALUE!	feet	D <sub>FC to ROCK</sub> = depth to bedrock from the bottom of the filter course	← ≥ 1'
#VALUE!	feet	D <sub>FC to SHWT</sub> = depth to SHWT from the bottom of the filter course	← ≥ 1'
48.19	ft	Peak elevation of the 50-year storm event (infiltration can be used in analysis)	
48.75	ft	Elevation of the top of the practice	
YES		50 peak elevation ≤ Elevation of the top of the practice	← yes

**If a surface sand filter or underground sand filter is proposed:**

YES	ac	Drainage Area check.	← < 10 ac
	cf	V = volume of storage <sup>3</sup> (attach a stage-storage table)	← ≥ 75%WQV
	inches	D <sub>FC</sub> = filter course thickness	← 18", or 24" if within GPA
Sheet		Note what sheet in the plan set contains the filter course specification	
	Yes/No	Access grate provided?	← yes



**Stage-Area-Storage for Pond PP04A: Bioretention Area #2**

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
45.25	0	0	47.90	3,184	4,499
45.30	0	26	47.95	3,245	4,660
45.35	0	51	48.00	3,307	4,824
45.40	0	77	48.05	3,369	4,991
45.45	0	103	48.10	3,432	5,161
45.50	0	129	48.15	3,496	5,334
45.55	0	154	48.20	3,560	5,511
45.60	0	180	48.25	3,625	5,690
45.65	0	206	48.30	3,691	5,873
45.70	0	232	48.35	3,757	6,059
45.75	0	257	48.40	3,823	6,249
45.80	0	283	48.45	3,890	6,442
45.85	0	309	48.50	3,958	6,638
45.90	0	335	48.55	4,107	6,839
45.95	0	360	48.60	4,258	7,048
46.00	1,287	386	48.65	4,412	7,265
46.05	1,326	451	48.70	4,569	7,490
46.10	1,366	519	48.75	<b>4,729</b>	<b>7,722</b>
46.15	1,406	588	48.80	4,729	7,722
46.20	1,447	659	48.85	4,729	7,722
46.25	1,488	733	48.90	4,729	7,722
46.30	1,530	808	48.95	4,729	7,722
46.35	1,573	886	49.00	4,729	7,722
46.40	1,616	965			
46.45	1,660	1,047			
46.50	1,704	1,131			
46.55	1,749	1,218			
46.60	1,795	1,306			
46.65	1,841	1,397			
46.70	1,888	1,490			
46.75	1,935	1,586			
46.80	1,983	1,684			
46.85	2,031	1,784			
46.90	2,080	1,887			
46.95	2,130	1,992			
47.00	2,180	2,100			
47.05	2,231	2,210			
47.10	2,282	2,323			
47.15	2,334	2,439			
47.20	2,387	2,557			
47.25	2,440	2,677			
47.30	2,493	2,801			
47.35	2,548	2,927			
47.40	2,603	3,055			
47.45	2,658	3,187			
47.50	2,714	3,321			
47.55	2,771	3,458			
47.60	2,828	3,598			
47.65	2,886	3,741			
47.70	2,944	3,887			
<b>47.75</b>	<b>3,003</b>	<b>4,036</b>			
47.80	3,063	4,187			
47.85	3,123	4,342			

(This Page Is Intentionally Blank)



## FILTRATION PRACTICE DESIGN CRITERIA (Env-Wq 1508.07)

Type/Node Name: \_\_\_\_\_

**PP-04b BIORETENTION AREA #3**

Enter the type of filtration practice (e.g., bioretention system) and the node name in the drainage analysis, if applicable

		Have you reviewed the restrictions on unlined systems outlined in Env-Wq 1508.07(a)?	
0.48	ac	A = Area draining to the practice	
0.22	ac	A <sub>I</sub> = Impervious area draining to the practice	
0.47	decimal	I = percent impervious area draining to the practice, in decimal form	
0.47	unitless	R <sub>v</sub> = Runoff coefficient = 0.05 + (0.9 x I)	
0.23	ac-in	WQV = 1" x R <sub>v</sub> x A	
822	cf	WQV conversion (ac-in x 43,560 sf/ac x 1ft/12")	
205	cf	25% x WQV (check calc for sediment forebay volume)	
616	cf	75% x WQV (check calc for surface sand filter volume)	
Deep Sump CB		Method of Pretreatment? (not required for clean or roof runoff)	
NA	cf	V <sub>SED</sub> = sediment forebay volume, if used for pretreatment	← ≥ 25%WQV
950	sf	A <sub>SA</sub> = surface area of the practice	
NA	iph	K <sub>sat</sub> <sub>DESIGN</sub> = design infiltration rate <sup>1</sup>	
Yes	Yes/No	If K <sub>sat</sub> (prior to factor of safety) is < 0.50 iph, has an underdrain been provided?	
-	hours	T <sub>DRAIN</sub> = drain time = V / (A <sub>SA</sub> * I <sub>DESIGN</sub> )	← ≤ 72-hrs
42.00	feet	E <sub>FC</sub> = elevation of the bottom of the filter course material <sup>2</sup>	
41.00	feet	E <sub>UD</sub> = invert elevation of the underdrain (UD), if applicable	
NA	feet	E <sub>SHWT</sub> = elevation of SHWT (if none found, enter the lowest elevation of the test pit)	
NA	feet	E <sub>ROCK</sub> = elevation of bedrock (if none found, enter the lowest elevation of the test pit)	
1.00	feet	D <sub>FC to UD</sub> = depth to UD from the bottom of the filter course	← ≥ 1'
#VALUE!	feet	D <sub>FC to ROCK</sub> = depth to bedrock from the bottom of the filter course	← ≥ 1'
#VALUE!	feet	D <sub>FC to SHWT</sub> = depth to SHWT from the bottom of the filter course	← ≥ 1'
45.60	ft	Peak elevation of the 50-year storm event (infiltration can be used in analysis)	
46.00	ft	Elevation of the top of the practice	
YES		50 peak elevation ≤ Elevation of the top of the practice	← yes

**If a surface sand filter or underground sand filter is proposed:**

YES	ac	Drainage Area check.	← < 10 ac
	cf	V = volume of storage <sup>3</sup> (attach a stage-storage table)	← ≥ 75%WQV
	inches	D <sub>FC</sub> = filter course thickness	← 18", or 24" if within GPA
Sheet		Note what sheet in the plan set contains the filter course specification	
	Yes/No	Access grate provided?	← yes



**Stage-Area-Storage for Pond PP04B: Bioretention Area #3**

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
42.75	0	0	45.40	2,595	3,525
42.80	0	19	45.45	2,649	3,656
42.85	0	38	45.50	2,704	3,790
42.90	0	57	45.55	2,760	3,926
42.95	0	76	45.60	2,816	4,066
43.00	0	95	45.65	2,872	4,208
43.05	0	114	45.70	2,929	4,353
43.10	0	133	45.75	2,987	4,501
43.15	0	152	45.80	3,045	4,652
43.20	0	171	45.85	3,103	4,805
43.25	0	190	45.90	3,163	4,962
43.30	0	209	45.95	3,223	5,122
43.35	0	228	46.00	3,283	5,284
43.40	0	247	46.05	3,358	5,450
43.45	0	266	46.10	3,433	5,620
43.50	950	285	46.15	3,510	5,794
43.55	983	333	46.20	3,587	5,971
43.60	1,016	383	46.25	<b>3,665</b>	<b>6,152</b>
43.65	1,050	435	46.30	3,665	6,152
43.70	1,085	488	46.35	3,665	6,152
43.75	1,120	543	46.40	3,665	6,152
43.80	1,156	600	46.45	3,665	6,152
43.85	1,192	659	46.50	3,665	6,152
43.90	1,229	720			
43.95	1,266	782			
44.00	1,304	846			
44.05	1,343	912			
44.10	1,382	981			
44.15	1,422	1,051			
44.20	1,462	1,123			
44.25	1,503	1,197			
44.30	1,544	1,273			
44.35	1,586	1,351			
44.40	1,628	1,432			
44.45	1,671	1,514			
44.50	1,715	1,599			
44.55	1,759	1,686			
44.60	1,804	1,775			
44.65	1,849	1,866			
44.70	1,895	1,960			
44.75	1,941	2,056			
44.80	1,988	2,154			
44.85	2,036	2,254			
44.90	2,084	2,357			
44.95	2,132	2,463			
45.00	2,182	2,571			
45.05	2,231	2,681			
45.10	2,282	2,794			
45.15	2,332	2,909			
45.20	2,384	3,027			
<b>45.25</b>	<b>2,436</b>	<b>3,147</b>			
45.30	2,488	3,271			
45.35	2,542	3,396			



(This Page Is Intentionally Blank)



## FILTRATION PRACTICE DESIGN CRITERIA (Env-Wq 1508.07)

**Type/Node Name:** \_\_\_\_\_

**PP-05 BIORETENTION AREA #1**

Enter the type of filtration practice (e.g., bioretention system) and the node name in the drainage analysis, if applicable

		Have you reviewed the restrictions on unlined systems outlined in Env-Wq 1508.07(a)?	
0.18	ac	A = Area draining to the practice	
0.07	ac	A <sub>I</sub> = Impervious area draining to the practice	
0.37	decimal	I = percent impervious area draining to the practice, in decimal form	
0.38	unitless	R <sub>v</sub> = Runoff coefficient = 0.05 + (0.9 x I)	
0.07	ac-in	WQV = 1" x R <sub>v</sub> x A	
256	cf	WQV conversion (ac-in x 43,560 sf/ac x 1ft/12")	
64	cf	25% x WQV (check calc for sediment forebay volume)	
192	cf	75% x WQV (check calc for surface sand filter volume)	
	Forbay	Method of Pretreatment? (not required for clean or roof runoff)	
140	cf	V <sub>SED</sub> = sediment forebay volume, if used for pretreatment	← ≥ 25%WQV
1,227	sf	A <sub>SA</sub> = surface area of the practice	
NA	iph	K <sub>sat</sub> DESIGN = design infiltration rate <sup>1</sup>	
Yes	Yes/No	If K <sub>sat</sub> (prior to factor of safety) is < 0.50 iph, has an underdrain been provided?	
-	hours	T <sub>DRAIN</sub> = drain time = V / (A <sub>SA</sub> * I <sub>DESIGN</sub> )	← ≤ 72-hrs
54.50	feet	E <sub>FC</sub> = elevation of the bottom of the filter course material <sup>2</sup>	
53.50	feet	E <sub>UD</sub> = invert elevation of the underdrain (UD), if applicable	
NA	feet	E <sub>SHWT</sub> = elevation of SHWT (if none found, enter the lowest elevation of the test pit)	
NA	feet	E <sub>ROCK</sub> = elevation of bedrock (if none found, enter the lowest elevation of the test pit)	
1.00	feet	D <sub>FC to UD</sub> = depth to UD from the bottom of the filter course	← ≥ 1'
#VALUE!	feet	D <sub>FC to ROCK</sub> = depth to bedrock from the bottom of the filter course	← ≥ 1'
#VALUE!	feet	D <sub>FC to SHWT</sub> = depth to SHWT from the bottom of the filter course	← ≥ 1'
57.52	ft	Peak elevation of the 50-year storm event (infiltration can be used in analysis)	
58.00	ft	Elevation of the top of the practice	
YES		50 peak elevation ≤ Elevation of the top of the practice	← yes

**If a surface sand filter or underground sand filter is proposed:**

YES	ac	Drainage Area check.	← < 10 ac
	cf	V = volume of storage <sup>3</sup> (attach a stage-storage table)	← ≥ 75%WQV
	inches	D <sub>FC</sub> = filter course thickness	← 18", or 24" if within GPA
Sheet		Note what sheet in the plan set contains the filter course specification	
	Yes/No	Access grate provided?	← yes



**Stage-Area-Storage for Pond PP05: Bloretention Pond #1**

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
53.33	1,227	0	54.39	1,227	437
53.35	1,227	0	54.41	1,227	447
53.37	1,227	0	54.43	1,227	456
53.39	1,227	0	54.45	1,227	466
53.41	1,227	0	54.47	1,227	476
53.43	1,227	0	54.49	1,227	486
53.45	1,227	0	54.51	1,227	493
53.47	1,227	0	54.53	1,227	498
53.49	1,227	0	54.55	1,227	503
53.51	1,227	5	54.57	1,227	508
53.53	1,227	15	54.59	1,227	513
53.55	1,227	25	54.61	1,227	518
53.57	1,227	34	54.63	1,227	523
53.59	1,227	44	54.65	1,227	528
53.61	1,227	54	54.67	1,227	533
53.63	1,227	64	54.69	1,227	537
53.65	1,227	74	54.71	1,227	542
53.67	1,227	83	54.73	1,227	547
53.69	1,227	93	54.75	1,227	552
53.71	1,227	103	54.77	1,227	557
53.73	1,227	113	54.79	1,227	562
53.75	1,227	123	54.81	1,227	567
53.77	1,227	133	54.83	1,227	572
53.79	1,227	142	54.85	1,227	577
53.81	1,227	152	54.87	1,227	582
53.83	1,227	162	54.89	1,227	587
53.85	1,227	172	54.91	1,227	591
53.87	1,227	182	54.93	1,227	596
53.89	1,227	191	54.95	1,227	601
53.91	1,227	201	54.97	1,227	606
53.93	1,227	211	54.99	1,227	611
53.95	1,227	221	55.01	1,227	616
53.97	1,227	231	55.03	1,227	621
53.99	1,227	240	55.05	1,227	626
54.01	1,227	250	55.07	1,227	631
54.03	1,227	260	55.09	1,227	636
54.05	1,227	270	55.11	1,227	640
54.07	1,227	280	55.13	1,227	645
54.09	1,227	290	55.15	1,227	650
54.11	1,227	299	55.17	1,227	655
54.13	1,227	309	55.19	1,227	660
54.15	1,227	319	55.21	1,227	665
54.17	1,227	329	55.23	1,227	670
54.19	1,227	339	55.25	1,227	675
54.21	1,227	348	55.27	1,227	680
54.23	1,227	358	55.29	1,227	685
54.25	1,227	368	55.31	1,227	690
54.27	1,227	378	55.33	1,227	694
54.29	1,227	388	55.35	1,227	699
54.31	1,227	398	55.37	1,227	704
54.33	1,227	407	55.39	1,227	709
54.35	1,227	417	55.41	1,227	714
54.37	1,227	427	55.43	1,227	719

**Stage-Area-Storage for Pond PP05: Bloretention Pond #1 (continued)**

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
55.45	1,227	724	56.51	1,448	1,540
55.47	1,227	729	56.53	1,457	1,569
55.49	1,227	734	56.55	1,466	1,598
55.51	1,227	739	56.57	1,475	1,628
55.53	1,227	744	56.59	1,484	1,657
55.55	1,227	748	56.61	1,493	1,687
55.57	1,227	753	56.63	1,502	1,717
55.59	1,227	758	56.65	1,512	1,747
55.61	1,227	763	56.67	1,521	1,778
55.63	1,227	768	56.69	1,530	1,808
55.65	1,227	773	56.71	1,539	1,839
55.67	1,227	778	56.73	1,549	1,870
55.69	1,227	783	56.75	1,558	1,901
55.71	1,227	788	56.77	1,567	1,932
55.73	1,227	793	56.79	1,577	1,963
55.75	1,227	798	56.81	1,586	1,995
55.77	1,227	802	56.83	1,596	2,027
55.79	1,227	807	56.85	1,605	2,059
55.81	1,227	812	56.87	1,615	2,091
55.83	1,227	817	56.89	1,624	2,124
55.85	1,227	822	56.91	1,634	2,156
55.87	1,227	827	56.93	1,643	2,189
55.89	1,227	832	56.95	1,653	2,222
55.91	1,227	837	56.97	1,662	2,255
55.93	1,227	842	56.99	1,672	2,288
55.95	1,227	847	57.01	1,682	2,322
55.97	1,227	852	57.03	1,691	2,356
55.99	1,227	856	57.05	1,701	2,389
56.01	1,231	871	57.07	1,710	2,424
56.03	1,239	896	57.09	1,720	2,458
56.05	1,248	921	57.11	1,729	2,492
56.07	1,256	946	57.13	1,739	2,527
56.09	1,265	971	57.15	1,749	2,562
56.11	1,273	996	57.17	1,758	2,597
56.13	1,282	1,022	57.19	1,768	2,632
56.15	1,290	1,048	57.21	1,778	2,668
56.17	1,299	1,074	57.23	1,788	2,703
56.19	1,307	1,100	57.25	1,797	2,739
56.21	1,316	1,126	57.27	1,807	2,775
56.23	1,324	1,152	57.29	1,817	2,812
56.25	1,333	1,179	57.31	1,827	2,848
56.27	1,342	1,206	57.33	1,837	2,885
56.29	1,350	1,232	57.35	1,847	2,921
56.31	1,359	1,260	57.37	1,857	2,959
56.33	1,368	1,287	57.39	1,867	2,996
56.35	1,377	1,314	57.41	1,877	3,033
56.37	1,385	1,342	57.43	1,887	3,071
56.39	1,394	1,370	57.45	1,897	3,109
56.41	1,403	1,398	57.47	1,907	3,147
56.43	1,412	1,426	57.49	1,917	3,185
56.45	1,421	1,454	57.51	1,927	3,223
56.47	1,430	1,483	57.53	1,937	3,262
56.49	1,439	1,511	57.55	1,948	3,301

**Stage-Area-Storage for Pond PP05: Bloretention Pond #1 (continued)**

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
57.57	1,958	3,340
57.59	1,968	3,379
57.61	1,978	3,419
57.63	1,989	3,458
57.65	1,999	3,498
57.67	2,009	3,538
57.69	2,020	3,579
57.71	2,030	3,619
57.73	2,041	3,660
57.75	2,051	3,701
57.77	2,061	3,742
57.79	2,072	3,783
57.81	2,083	3,825
57.83	2,093	3,866
57.85	2,104	3,908
57.87	2,114	3,951
57.89	2,125	3,993
57.91	2,136	4,036
57.93	2,146	4,078
57.95	2,157	4,121
57.97	2,168	4,165
57.99	2,179	4,208
58.01	2,233	4,252
58.03	2,332	4,298
58.05	2,433	4,345
58.07	2,537	4,395
58.09	2,642	4,447
58.11	<b>2,696</b>	4,500
58.13	2,696	4,554
58.15	2,696	4,608
58.17	2,696	4,662
58.19	2,696	4,716
58.21	2,696	4,770
58.23	2,696	4,824
58.25	2,696	4,878
58.27	2,696	4,932
58.29	2,696	4,986
58.31	2,696	5,040
58.33	2,696	5,094
58.35	2,696	5,148
58.37	2,696	5,201
58.39	2,696	5,255
58.41	2,696	5,309
58.43	2,696	5,363
58.45	2,696	5,417
58.47	2,696	5,471
58.49	2,696	<b>5,525</b>

(This Page Is Intentionally Blank)

**APPENDIX G**  
**RIPRAP CALCULATIONS**



(This Page Is Intentionally Blank)

**RIPRAP OUTLET PROTECTION**

Location: FES #1- (MH01) Outlet of Underdrain for R-Tanks

Design Flow =	Q =	0.1	cfs
Tailwater =	Tw =	0.666667	feet
Pipe Dia.=	Do =	1	feet

$La = \text{Length} = 3Q/Do^{(3/2)} + 7Do = 7 \text{ feet}$

$W_1 = \text{Width} = 3Do + (0.4)(La) = 6 \text{ feet (or Width of Channel)}$

$W_2 = \text{Width} = 3Do = 3 \text{ feet}$

$D = \text{Depth} = (1.5)(1.5d50) = 7 \text{ inches (or Min. 6")}$

$d50 = (.02)(Q)^{(4/3)} / (Tw * Do) = 3.00 \text{ inches (or Min. 3")}$

**Rock Riprap Gradation**

% of weight smaller than the given size.

Size of stone (inches)

- 100
- 85
- 50
- 15

(See Last Page of Calculations  
 for 25-Year Flows)

- 4.50 - 6.00
- 3.90 - 5.40
- 3.00 - 4.50
- 0.90 - 1.50

**RIPRAP OUTLET PROTECTION**

Location: FES#2 - (P003A) Outlet from Overflow of R-Tanks

Design Flow =	Q =	0.5	cfs
Tailwater =	Tw =	0.666667	feet
Pipe Dia.=	Do =	1	feet

$La = \text{Length} = 3Q/Do^{(3/2)} + 7Do = 9 \text{ feet}$

$W = \text{Width} = 3Do + (0.4)(La) = 6 \text{ feet (or Width of Channel)}$   
 $W_2 = \text{Width} = 3Do = 3 \text{ feet}$

$D = \text{Depth} = (1.5)(1.5d50) = 7 \text{ inches (or Min. 6")}$

$d50 = (.02)(Q)^{(4/3)} / (Tw * Do) = 3.00 \text{ inches (or Min. 3")}$

**Rock Riprap Gradation**

% of weight smaller than the given size.

Size of stone (inches)

100		4.50	-	6.00
85		3.90	-	5.40
50		3.00	-	4.50
15	(See Last Page of Calculations for 25-Year Flows)	0.90	-	1.50

### RIPRAP OUTLET PROTECTION

Location: FES#3 - (PP04a)From Bioretention Area #3

Design Flow =	Q =	3.4	cfs
Tailwater =	Tw =	0.666667	feet
Pipe Dia.=	Do =	1	feet

$$La = \text{Length} = 3Q/Do^{(3/2)} + 7Do = \mathbf{17 \text{ feet}}$$

$$W = \text{Width} = 3Do + (0.4)(La) = \mathbf{10 \text{ feet (or Width of Channel)}}$$

$$W_2 = \text{Width} = 3Do = \mathbf{3 \text{ feet}}$$

$$D = \text{Depth} = (1.5)(1.5d50) = \mathbf{7 \text{ inches (or Min. 6')}}}$$

$$d50 = (.02)(Q)^{(4/3)} / (Tw * Do) = \mathbf{3.00 \text{ inches (or Min. 3')}}}$$

### Rock Riprap Gradation

% of weight smaller than the given size.

Size of stone (inches)

100		4.50	-	6.00
85		3.90	-	5.40
50		3.00	-	4.50
15		0.90	-	1.50

(See Last Page of Calculations  
for 25-Year Flows)

### RIPRAP OUTLET PROTECTION

Location: FES#4 - (PP04b)From Bioretention Area #4

Design Flow =	Q =	1.5	cfs
Tailwater =	Tw =	0.666667	feet
Pipe Dia.=	Do =	1	feet

$$La = \text{Length} = 3Q/Do^{(3/2)} + 7Do = \mathbf{12} \text{ feet}$$

$$W = \text{Width} = 3Do + (0.4)(La) = \mathbf{8} \text{ feet (or Width of Channel)}$$

$$W_2 = \text{Width} = 3Do = \mathbf{3} \text{ feet}$$

$$D = \text{Depth} = (1.5)(1.5d50) = \mathbf{7} \text{ inches (or Min. 6")}$$

$$d50 = (.02)(Q)^{(4/3)} / (Tw * Do) = \mathbf{3.00} \text{ inches (or Min. 3")}$$

### Rock Riprap Gradation

% of weight smaller than the given size.

Size of stone (inches)

100		4.50	-	6.00
85		3.90	-	5.40
50		3.00	-	4.50
15	(See Last Page of Calculations for 25-Year Flows)	0.90	-	1.50

## RIPRAP OUTLET PROTECTION

Location: FES#5 - (PP05) From Bioretention Area #1

Design Flow =	Q =	0	cfs
Tailwater =	Tw =	0.666667	feet
Pipe Dia.=	Do =	1	feet

$$La = \text{Length} = 3Q/Do^{(3/2)} + 7Do = \mathbf{7} \text{ feet}$$

$$W = \text{Width} = 3Do + (0.4)(La) = \mathbf{6} \text{ feet (or Width of Channel)}$$

$$W_2 = \text{Width} = 3Do = \mathbf{3} \text{ feet}$$

$$D = \text{Depth} = (1.5)(1.5d50) = \mathbf{7} \text{ inches (or Min. 6")}$$

$$d50 = (.02)(Q)^{(4/3)} / (Tw * Do) = \mathbf{3.00} \text{ inches (or Min. 3")}$$

### Rock Riprap Gradation

% of weight smaller than the given size.

Size of stone (inches)

100	
85	
50	
15	

(See Last Page of Calculations  
for 25-Year Flows)

4.50	-	6.00
3.90	-	5.40
3.00	-	4.50
0.90	-	1.50

**RIPRAP OUTLET PROTECTION**

Location: FES #6 - (Ci01) Curb Inlet 01

Design Flow =	Q =	0.6	cfs
Tailwater =	Tw =	0.666667	feet
Pipe Dia.=	Do =	1	feet

$La = \text{Length} = 3Q/Do^{(3/2)} + 7Do = 9 \text{ feet}$

$W = \text{Width} = 3Do + (0.4)(La) = 7 \text{ feet (or Width of Channel)}$   
 $W_2 = \text{Width} = 3Do = 3 \text{ feet}$

$D = \text{Depth} = (1.5)(1.5d50) = 7 \text{ inches (or Min. 6")}$

$d50 = (.02)(Q)^{(4/3)} / (Tw * Do) = 3.00 \text{ inches (or Min. 3")}$

**Rock Riprap Gradation**

% of weight smaller than the given size.

Size of stone (inches)

100  
 85  
 50  
 15

(See Last Page of Calculations  
 for 25-Year Flows)

4.50 - 6.00  
 3.90 - 5.40  
 3.00 - 4.50  
 0.90 - 1.50

**RIPRAP OUTLET PROTECTION**

Location: FES #7 - (Ci02) Curb Inlet 02

Design Flow =	Q =	0.6	cfs
Tailwater =	Tw =	0.666667	feet
Pipe Dia.=	Do =	1	feet

$La = \text{Length} = 3Q/Do^{(3/2)} + 7Do = 9 \text{ feet}$

$W = \text{Width} = 3Do + (0.4)(La) = 7 \text{ feet (or Width of Channel)}$   
 $W_2 = \text{Width} = 3Do = 3 \text{ feet}$

$D = \text{Depth} = (1.5)(1.5d50) = 7 \text{ inches (or Min. 6")}$

$d50 = (.02)(Q)^{(4/3)} / (Tw * Do) = 3.00 \text{ inches (or Min. 3")}$

**Rock Riprap Gradation**

% of weight smaller than the given size.

Size of stone (inches)

100
85
50
15

(See Last Page of Calculations  
 for 25-Year Flows)

4.50	-	6.00
3.90	-	5.40
3.00	-	4.50
0.90	-	1.50



(This Page Is Intentionally Blank)

**477361-00\_PRE-&-POST\_2020-03-02**

Post Development -RIP RAP

Type III 24-hr 25-YR Rainfall=7.16"

Prepared by {enter your company name here}

Printed 3/5/2020

HydroCAD® 10.10-3a s/n 00866 © 2020 HydroCAD Software Solutions LLC

Page 1

Time span=0.00-24.00 hrs, dt=0.06 hrs, 401 points x 2  
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN  
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**Pond Ci01: CURB INLET 1** Peak Elev=26.63' Inflow=0.6 cfs 1,843 cf  
Outflow=0.6 cfs 1,843 cf

**Pond Ci02: CURB INLET 2** Peak Elev=26.62' Inflow=0.6 cfs 1,799 cf  
Outflow=0.6 cfs 1,799 cf

**Pond MH01: MH 1** Peak Elev=28.68' Inflow=0.1 cfs 6,254 cf  
UNDERDRAIN FROM R-TANKS 12.0" Round Culvert n=0.012 L=91.0' S=0.0082 '/' Outflow=0.1 cfs 6,254 cf

**Pond MH05: MH 5** Peak Elev=51.30' Inflow=0.0 cfs 0 cf  
UNDERDRAIN FROM BIORETENTION AREA 1 12.0" Round Culvert n=0.013 L=65.0' S=0.0523 '/' Outflow=0.0 cfs 0 cf

**Pond P003a: R-Tank #1 and 2** Peak Elev=34.48' Storage=4,100 cf Inflow=2.1 cfs 9,304 cf  
OVERFLOW FROM RITANKS Primary=0.1 cfs 2,868 cf Secondary=0.5 cfs 2,665 cf Outflow=0.5 cfs 5,533 cf

**Pond PP04A: Bioretention Area #2** Peak Elev=48.10' Storage=5,178 cf Inflow=4.4 cfs 18,386 cf  
Primary=2.6 cfs 17,436 cf Secondary=0.8 cfs 565 cf Outflow=3.4 cfs 18,001 cf

**Pond PP04B: Bioretention Area #3** Peak Elev=45.52' Storage=3,838 cf Inflow=2.6 cfs 9,026 cf  
Primary=1.4 cfs 5,826 cf Secondary=0.0 cfs 15 cf Outflow=1.5 cfs 5,841 cf

(This Page Is Intentionally Blank)

## APPENDIX H INLET CAPACITY CALCULATIONS

(This Page Is Intentionally Blank)

Assumes Steady Flow

K	Constant for Imperial Units (unitless)	1.49
K <sub>u</sub>	Constant Gutter	0.09
n	Coefficient of Roughness	0.016 For Asphalt
W	Width of Gutter (ft)	2
L	Length of Gutter (ft)	Given
S	Longitudinal Slope (ft/ft)	Given
S <sub>x</sub>	Cross Slope (ft/ft)	Given
S <sub>w</sub>	Cross Slope in Depression (ft/ft)	$S_w = a/W + S_x$
A	Area (sf)	$A = 1/2 T y$
A <sub>2</sub>	Area Based on Gutter (sf)	$A_2 = 0.5 T^2 S_x + 0.5 a W$
P	Wetted Perimeter	$P = (y/SIN\Phi) + y$
R	Hydraulic Radius (ft)	$R = A/P$
R <sub>f</sub>	Frontal Grate Efficiency	if $V < V_o$ then $R_f = 1$
R <sub>s</sub>	The ratio of side flow interc. total side flow (cfs)	$R_s = 1/[1 + (K_u V^{1.8}) / (S_x L^{2.3})]$
V	Velocity (fps)	$V = K/n R^{2/3} S^{1/2}$
V <sub>o</sub>	Splash Over Velocity (fps) (Rectilinear)	$V_o = 0.03 + 2.278L - 0.179L^2 + 0.01L^3$
y	Depth of Flow (ft)	$y = ((2QnS_x(S_x + 2)^{2/3}) / (K * D 31^{1/2}))^{3/8}$
T	Width of Flow (ft)	$T = y/S_x$
Q <sub>10</sub>	10 year, 24 hr storm Flow (cfs)	Given
Q <sub>s</sub>	Flow capacity at Gutter Section Above the Dep.(cfs)	$Q_s = K_u/n S_x^{1.67} S^{1/2} T_s^{2.67}$ <span style="margin-left: 20px;"><math>K_u = 0.56</math> (Constant for Imperial Units)</span>
Q <sub>w</sub>	Flow at Depression (cfs)	$Q_w = Q - Q_s$
Q <sub>g</sub>	Flow at Gutter (cfs)	$Q_g = Q_s / (1 - E_o)$
Q <sub>i</sub>	Flow at Gutter (cfs)	$Q_i = Q[R_f E_o + R_s (1 - E_o)]$
E <sub>o</sub>	Ratio of Flow in A Chosed Width to Gutter Flow	$E_o = 1/[1 + ((S_w/S_x)/(1 + (S_w/S_x)/(T/W - 1)))^{2.67} - 1)]$
a	Inet Depression (2 inches)	0.167 (Given)

	Q <sub>10</sub> (CFS)	L (ft)	S (ft/ft)	S <sub>x</sub> (ft/ft)	S <sub>w</sub> (ft/ft)	y (ft)	Φ of Slope	T (ft)	A (ft <sup>2</sup> )	P (ft)	R (ft)	V (fps)	A <sub>2</sub> (ft <sup>2</sup> )	V <sub>G</sub> (fps)	V <sub>O</sub> (fps)	R <sub>f</sub>	R <sub>s</sub>	E <sub>f</sub>	Q <sub>i</sub> (CFS)	R <sub>s</sub>	S <sub>w</sub> (ft/ft) (4-6)b	E <sub>o</sub> (4-4)	T <sub>s</sub> (ft)	Q <sub>s</sub> (cfs) (4-2)
CB-01	0.8	2.00	0.06	0.02	0.10	0.10	0.02	5.07	0.26	5.2	0.0497	3.0854	0.4246	1.8843	3.9500	1.000	0.080	0.758	0.6067	0.1735	0.10	0.91	3.07	0.25
CB-02	0.7	2.00	0.06	0.02	0.10	0.10	0.02	4.83	0.23	4.9	0.0473	2.9841	0.2330	3.0041	3.9500	1.000	0.084	0.084	0.0588	0.0831	0.10	0.92	2.83	0.20
CB-03	1.0	2.00	0.06	0.02	0.10	0.11	0.02	5.52	0.30	5.6	0.0541	3.2624	0.3045	3.2843	3.9500	1.000	0.072	0.072	0.0725	0.0717	0.10	0.88	3.52	0.36
CB-04	1.2	2.00	0.06	0.02	0.10	0.12	0.02	5.91	0.35	6.0	0.0579	3.4145	0.3491	3.4375	3.9500	1.000	0.067	0.067	0.0806	0.0664	0.10	0.86	3.91	0.47
CB-05	0.4	2.00	0.00	0.02	0.10	0.17	0.02	8.43	0.71	8.6	0.0827	0.5588	0.7111	0.5625	3.9500	1.000	0.652	0.652	0.2607	0.649	0.10	0.70	6.43	0.23
CB-06	0.4	2.00	0.00	0.02	0.10	0.17	0.02	8.43	0.71	8.6	0.0827	0.5588	0.7111	0.5625	3.9500	1.000	0.652	0.652	0.2607	0.649	0.10	0.70	6.43	0.23
CB-07	3.0	4.00	0.04	0.02	0.10	0.18	0.02	9.22	0.85	9.4	0.0903	3.5078	0.8495	3.5314	6.9180	1.000	0.252	0.252	0.7575	0.2502	0.10	0.65	7.22	1.86
CB-08	1.6	4.00	0.04	0.02	0.10	0.15	0.02	7.28	0.53	7.4	0.0714	2.9977	0.5302	3.0178	6.9180	1.000	0.309	0.309	0.4952	0.3069	0.10	0.77	5.28	0.81

All CB Gutter Velocity is below Jump Velocity, therefore double grate not required  
 CB -07 Flow is greater than the allowable 2 cfs, therefore, calling for double grate catchbasin for this and CB-8

(This Page Is Intentionally Blank)

**APPENDIX I**  
**NRCS WEB SOILS SURVEY**



(This Page Is Intentionally Blank)

# Custom Soil Resource Report for Rockingham County, New Hampshire

Banfield - Portsmouth, NH



# Preface

---

Soil surveys contain information that affects land use planning in survey areas. They highlight soil limitations that affect various land uses and provide information about the properties of the soils in the survey areas. Soil surveys are designed for many different users, including farmers, ranchers, foresters, agronomists, urban planners, community officials, engineers, developers, builders, and home buyers. Also, conservationists, teachers, students, and specialists in recreation, waste disposal, and pollution control can use the surveys to help them understand, protect, or enhance the environment.

Various land use regulations of Federal, State, and local governments may impose special restrictions on land use or land treatment. Soil surveys identify soil properties that are used in making various land use or land treatment decisions. The information is intended to help the land users identify and reduce the effects of soil limitations on various land uses. The landowner or user is responsible for identifying and complying with existing laws and regulations.

Although soil survey information can be used for general farm, local, and wider area planning, onsite investigation is needed to supplement this information in some cases. Examples include soil quality assessments (<http://www.nrcs.usda.gov/wps/portal/nrcs/main/soils/health/>) and certain conservation and engineering applications. For more detailed information, contact your local USDA Service Center (<https://offices.sc.egov.usda.gov/locator/app?agency=nrcs>) or your NRCS State Soil Scientist ([http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/contactus/?cid=nrcs142p2\\_053951](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/contactus/?cid=nrcs142p2_053951)).

Great differences in soil properties can occur within short distances. Some soils are seasonally wet or subject to flooding. Some are too unstable to be used as a foundation for buildings or roads. Clayey or wet soils are poorly suited to use as septic tank absorption fields. A high water table makes a soil poorly suited to basements or underground installations.

The National Cooperative Soil Survey is a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local agencies. The Natural Resources Conservation Service (NRCS) has leadership for the Federal part of the National Cooperative Soil Survey.

Information about soils is updated periodically. Updated information is available through the NRCS Web Soil Survey, the site for official soil survey information.

The U.S. Department of Agriculture (USDA) prohibits discrimination in all its programs and activities on the basis of race, color, national origin, age, disability, and where applicable, sex, marital status, familial status, parental status, religion, sexual orientation, genetic information, political beliefs, reprisal, or because all or a part of an individual's income is derived from any public assistance program. (Not all prohibited bases apply to all programs.) Persons with disabilities who require

alternative means for communication of program information (Braille, large print, audiotape, etc.) should contact USDA's TARGET Center at (202) 720-2600 (voice and TDD). To file a complaint of discrimination, write to USDA, Director, Office of Civil Rights, 1400 Independence Avenue, S.W., Washington, D.C. 20250-9410 or call (800) 795-3272 (voice) or (202) 720-6382 (TDD). USDA is an equal opportunity provider and employer.

# Contents

---

<b>Preface</b> .....	2
<b>How Soil Surveys Are Made</b> .....	5
<b>Soil Map</b> .....	8
Soil Map.....	9
Legend.....	10
Map Unit Legend.....	11
Map Unit Descriptions.....	11
Rockingham County, New Hampshire.....	13
38B—Eldridge fine sandy loam, 3 to 8 percent slopes.....	13
134—Maybid silt loam.....	14
140B—Chatfield-Hollis-Canton complex, 0 to 8 percent slopes, rocky.....	15
140C—Chatfield-Hollis-Canton complex, 8 to 15 percent slopes, rocky.....	18
538A—Squamscott fine sandy loam, 0 to 5 percent slopes.....	21
<b>References</b> .....	23

# How Soil Surveys Are Made

---

Soil surveys are made to provide information about the soils and miscellaneous areas in a specific area. They include a description of the soils and miscellaneous areas and their location on the landscape and tables that show soil properties and limitations affecting various uses. Soil scientists observed the steepness, length, and shape of the slopes; the general pattern of drainage; the kinds of crops and native plants; and the kinds of bedrock. They observed and described many soil profiles. A soil profile is the sequence of natural layers, or horizons, in a soil. The profile extends from the surface down into the unconsolidated material in which the soil formed or from the surface down to bedrock. The unconsolidated material is devoid of roots and other living organisms and has not been changed by other biological activity.

Currently, soils are mapped according to the boundaries of major land resource areas (MLRAs). MLRAs are geographically associated land resource units that share common characteristics related to physiography, geology, climate, water resources, soils, biological resources, and land uses (USDA, 2006). Soil survey areas typically consist of parts of one or more MLRA.

The soils and miscellaneous areas in a survey area occur in an orderly pattern that is related to the geology, landforms, relief, climate, and natural vegetation of the area. Each kind of soil and miscellaneous area is associated with a particular kind of landform or with a segment of the landform. By observing the soils and miscellaneous areas in the survey area and relating their position to specific segments of the landform, a soil scientist develops a concept, or model, of how they were formed. Thus, during mapping, this model enables the soil scientist to predict with a considerable degree of accuracy the kind of soil or miscellaneous area at a specific location on the landscape.

Commonly, individual soils on the landscape merge into one another as their characteristics gradually change. To construct an accurate soil map, however, soil scientists must determine the boundaries between the soils. They can observe only a limited number of soil profiles. Nevertheless, these observations, supplemented by an understanding of the soil-vegetation-landscape relationship, are sufficient to verify predictions of the kinds of soil in an area and to determine the boundaries.

Soil scientists recorded the characteristics of the soil profiles that they studied. They noted soil color, texture, size and shape of soil aggregates, kind and amount of rock fragments, distribution of plant roots, reaction, and other features that enable them to identify soils. After describing the soils in the survey area and determining their properties, the soil scientists assigned the soils to taxonomic classes (units). Taxonomic classes are concepts. Each taxonomic class has a set of soil characteristics with precisely defined limits. The classes are used as a basis for comparison to classify soils systematically. Soil taxonomy, the system of taxonomic classification used in the United States, is based mainly on the kind and character of soil properties and the arrangement of horizons within the profile. After the soil

scientists classified and named the soils in the survey area, they compared the individual soils with similar soils in the same taxonomic class in other areas so that they could confirm data and assemble additional data based on experience and research.

The objective of soil mapping is not to delineate pure map unit components; the objective is to separate the landscape into landforms or landform segments that have similar use and management requirements. Each map unit is defined by a unique combination of soil components and/or miscellaneous areas in predictable proportions. Some components may be highly contrasting to the other components of the map unit. The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The delineation of such landforms and landform segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, onsite investigation is needed to define and locate the soils and miscellaneous areas.

Soil scientists make many field observations in the process of producing a soil map. The frequency of observation is dependent upon several factors, including scale of mapping, intensity of mapping, design of map units, complexity of the landscape, and experience of the soil scientist. Observations are made to test and refine the soil-landscape model and predictions and to verify the classification of the soils at specific locations. Once the soil-landscape model is refined, a significantly smaller number of measurements of individual soil properties are made and recorded. These measurements may include field measurements, such as those for color, depth to bedrock, and texture, and laboratory measurements, such as those for content of sand, silt, clay, salt, and other components. Properties of each soil typically vary from one point to another across the landscape.

Observations for map unit components are aggregated to develop ranges of characteristics for the components. The aggregated values are presented. Direct measurements do not exist for every property presented for every map unit component. Values for some properties are estimated from combinations of other properties.

While a soil survey is in progress, samples of some of the soils in the area generally are collected for laboratory analyses and for engineering tests. Soil scientists interpret the data from these analyses and tests as well as the field-observed characteristics and the soil properties to determine the expected behavior of the soils under different uses. Interpretations for all of the soils are field tested through observation of the soils in different uses and under different levels of management. Some interpretations are modified to fit local conditions, and some new interpretations are developed to meet local needs. Data are assembled from other sources, such as research information, production records, and field experience of specialists. For example, data on crop yields under defined levels of management are assembled from farm records and from field or plot experiments on the same kinds of soil.

Predictions about soil behavior are based not only on soil properties but also on such variables as climate and biological activity. Soil conditions are predictable over long periods of time, but they are not predictable from year to year. For example, soil scientists can predict with a fairly high degree of accuracy that a given soil will have a high water table within certain depths in most years, but they cannot predict that a high water table will always be at a specific level in the soil on a specific date.

After soil scientists located and identified the significant natural bodies of soil in the survey area, they drew the boundaries of these bodies on aerial photographs and

## Custom Soil Resource Report

identified each as a specific map unit. Aerial photographs show trees, buildings, fields, roads, and rivers, all of which help in locating boundaries accurately.




# Soil Map

---

The soil map section includes the soil map for the defined area of interest, a list of soil map units on the map and extent of each map unit, and cartographic symbols displayed on the map. Also presented are various metadata about data used to produce the map, and a description of each soil map unit.

# Custom Soil Resource Report Soil Map



Soil Map may not be valid at this scale.

Map Scale: 1:4,710 if printed on A portrait (8.5" x 11") sheet.


0 50 100 200 300 Meters

0 200 400 800 1200 Feet


Map projection: Web Mercator Corner coordinates: WGS84 Edge tics: UTM Zone 19N WGS84


### MAP LEGEND

**Area of Interest (AOI)**

 Area of Interest (AOI)

**Soils**

 Soil Map Unit Polygons

 Soil Map Unit Lines


 Soil Map Unit Points

**Special Point Features**






-  Blowout
-  Borrow Pit
-  Clay Spot
-  Closed Depression
-  Gravel Pit
-  Gravelly Spot
-  Landfill
-  Lava Flow
-  Marsh or swamp
-  Mine or Quarry
-  Miscellaneous Water
-  Perennial Water
-  Rock Outcrop
-  Saline Spot
-  Sandy Spot
-  Severely Eroded Spot
-  Sinkhole
-  Slide or Slip
-  Sodic Spot

-  Spoil Area
-  Stony Spot
-  Very Stony Spot
-  Wet Spot
-  Other
-  Special Line Features


**Water Features**

 Streams and Canals

**Transportation**

-  Rails
-  Interstate Highways
-  US Routes
-  Major Roads
-  Local Roads

**Background**

 Aerial Photography

### MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service  
 Web Soil Survey URL:  
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Rockingham County, New Hampshire  
 Survey Area Data: Version 20, Sep 7, 2018

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Dec 31, 2009—Jun 14, 2017

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

## Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
38B	Eldridge fine sandy loam, 3 to 8 percent slopes	0.3	0.7%
134	Maybid silt loam	4.5	10.0%
140B	Chatfield-Hollis-Canton complex, 0 to 8 percent slopes, rocky	22.1	48.5%
140C	Chatfield-Hollis-Canton complex, 8 to 15 percent slopes, rocky	2.5	5.5%
538A	Squamscott fine sandy loam, 0 to 5 percent slopes	16.1	35.4%
<b>Totals for Area of Interest</b>		<b>45.5</b>	<b>100.0%</b>

## Map Unit Descriptions

The map units delineated on the detailed soil maps in a soil survey represent the soils or miscellaneous areas in the survey area. The map unit descriptions, along with the maps, can be used to determine the composition and properties of a unit.

A map unit delineation on a soil map represents an area dominated by one or more major kinds of soil or miscellaneous areas. A map unit is identified and named according to the taxonomic classification of the dominant soils. Within a taxonomic class there are precisely defined limits for the properties of the soils. On the landscape, however, the soils are natural phenomena, and they have the characteristic variability of all natural phenomena. Thus, the range of some observed properties may extend beyond the limits defined for a taxonomic class. Areas of soils of a single taxonomic class rarely, if ever, can be mapped without including areas of other taxonomic classes. Consequently, every map unit is made up of the soils or miscellaneous areas for which it is named and some minor components that belong to taxonomic classes other than those of the major soils.

Most minor soils have properties similar to those of the dominant soil or soils in the map unit, and thus they do not affect use and management. These are called noncontrasting, or similar, components. They may or may not be mentioned in a particular map unit description. Other minor components, however, have properties and behavioral characteristics divergent enough to affect use or to require different management. These are called contrasting, or dissimilar, components. They generally are in small areas and could not be mapped separately because of the scale used. Some small areas of strongly contrasting soils or miscellaneous areas are identified by a special symbol on the maps. If included in the database for a given area, the contrasting minor components are identified in the map unit descriptions along with some characteristics of each. A few areas of minor components may not have been observed, and consequently they are not mentioned in the descriptions, especially where the pattern was so complex that it

was impractical to make enough observations to identify all the soils and miscellaneous areas on the landscape.

The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The objective of mapping is not to delineate pure taxonomic classes but rather to separate the landscape into landforms or landform segments that have similar use and management requirements. The delineation of such segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, however, onsite investigation is needed to define and locate the soils and miscellaneous areas.

An identifying symbol precedes the map unit name in the map unit descriptions. Each description includes general facts about the unit and gives important soil properties and qualities.

Soils that have profiles that are almost alike make up a *soil series*. Except for differences in texture of the surface layer, all the soils of a series have major horizons that are similar in composition, thickness, and arrangement.

Soils of one series can differ in texture of the surface layer, slope, stoniness, salinity, degree of erosion, and other characteristics that affect their use. On the basis of such differences, a soil series is divided into *soil phases*. Most of the areas shown on the detailed soil maps are phases of soil series. The name of a soil phase commonly indicates a feature that affects use or management. For example, Alpha silt loam, 0 to 2 percent slopes, is a phase of the Alpha series.

Some map units are made up of two or more major soils or miscellaneous areas. These map units are complexes, associations, or undifferentiated groups.

A *complex* consists of two or more soils or miscellaneous areas in such an intricate pattern or in such small areas that they cannot be shown separately on the maps. The pattern and proportion of the soils or miscellaneous areas are somewhat similar in all areas. Alpha-Beta complex, 0 to 6 percent slopes, is an example.

An *association* is made up of two or more geographically associated soils or miscellaneous areas that are shown as one unit on the maps. Because of present or anticipated uses of the map units in the survey area, it was not considered practical or necessary to map the soils or miscellaneous areas separately. The pattern and relative proportion of the soils or miscellaneous areas are somewhat similar. Alpha-Beta association, 0 to 2 percent slopes, is an example.

An *undifferentiated group* is made up of two or more soils or miscellaneous areas that could be mapped individually but are mapped as one unit because similar interpretations can be made for use and management. The pattern and proportion of the soils or miscellaneous areas in a mapped area are not uniform. An area can be made up of only one of the major soils or miscellaneous areas, or it can be made up of all of them. Alpha and Beta soils, 0 to 2 percent slopes, is an example.

Some surveys include *miscellaneous areas*. Such areas have little or no soil material and support little or no vegetation. Rock outcrop is an example.

## Rockingham County, New Hampshire

### 38B—Eldridge fine sandy loam, 3 to 8 percent slopes

#### Map Unit Setting

*National map unit symbol:* 9cnc  
*Elevation:* 90 to 1,000 feet  
*Mean annual precipitation:* 30 to 55 inches  
*Mean annual air temperature:* 45 to 54 degrees F  
*Frost-free period:* 120 to 180 days  
*Farmland classification:* All areas are prime farmland

#### Map Unit Composition

*Eldridge and similar soils:* 80 percent  
*Minor components:* 20 percent  
*Estimates are based on observations, descriptions, and transects of the mapunit.*

#### Description of Eldridge

##### Setting

*Parent material:* Outwash over glaciolacustrine

##### Typical profile

*H1 - 0 to 8 inches:* fine sandy loam  
*H2 - 8 to 23 inches:* loamy fine sand  
*H3 - 23 to 62 inches:* loamy very fine sand

##### Properties and qualities

*Slope:* 3 to 8 percent  
*Depth to restrictive feature:* More than 80 inches  
*Natural drainage class:* Moderately well drained  
*Runoff class:* Medium  
*Capacity of the most limiting layer to transmit water (Ksat):* Moderately low to moderately high (0.06 to 0.60 in/hr)  
*Depth to water table:* About 12 to 24 inches  
*Frequency of flooding:* None  
*Frequency of ponding:* None  
*Available water storage in profile:* High (about 9.9 inches)

##### Interpretive groups

*Land capability classification (irrigated):* None specified  
*Land capability classification (nonirrigated):* 2w  
*Hydrologic Soil Group:* C/D  
*Hydric soil rating:* No

#### Minor Components

##### Squamscott

*Percent of map unit:* 5 percent  
*Landform:* Marine terraces  
*Hydric soil rating:* Yes

##### Boxford

*Percent of map unit:* 5 percent  
*Hydric soil rating:* No

**Well drained inclusion**

*Percent of map unit:* 5 percent  
*Hydric soil rating:* No

**Scitico**

*Percent of map unit:* 5 percent  
*Landform:* Marine terraces  
*Hydric soil rating:* Yes

**134—Maybid silt loam**

**Map Unit Composition**

*Maybid and similar soils:* 75 percent  
*Minor components:* 25 percent  
*Estimates are based on observations, descriptions, and transects of the mapunit.*

**Description of Maybid**

**Setting**

*Landform:* Marine terraces  
*Parent material:* Silty and clayey marine deposits

**Typical profile**

*H1 - 0 to 9 inches:* silt loam  
*H2 - 9 to 26 inches:* silty clay loam  
*H3 - 26 to 63 inches:* silty clay

**Properties and qualities**

*Slope:* 0 to 2 percent  
*Depth to restrictive feature:* More than 80 inches  
*Natural drainage class:* Very poorly drained  
*Runoff class:* High  
*Capacity of the most limiting layer to transmit water (Ksat):* Very low to moderately high (0.00 to 0.20 in/hr)  
*Depth to water table:* About 0 to 6 inches  
*Frequency of flooding:* None  
*Frequency of ponding:* Frequent  
*Available water storage in profile:* Moderate (about 8.8 inches)

**Interpretive groups**

*Land capability classification (irrigated):* None specified  
*Land capability classification (nonirrigated):* 6w  
*Hydrologic Soil Group:* C/D  
*Hydric soil rating:* Yes

**Minor Components**

**Ossipee**

*Percent of map unit:* 10 percent  
*Landform:* Swamps  
*Hydric soil rating:* Yes

**Scitico**

*Percent of map unit:* 10 percent  
*Landform:* Marine terraces  
*Hydric soil rating:* Yes

**Not named wet**

*Percent of map unit:* 5 percent  
*Landform:* Marine terraces  
*Hydric soil rating:* Yes

**140B—Chatfield-Hollis-Canton complex, 0 to 8 percent slopes, rocky**

**Map Unit Setting**

*National map unit symbol:* 2w82m  
*Elevation:* 380 to 1,070 feet  
*Mean annual precipitation:* 36 to 71 inches  
*Mean annual air temperature:* 39 to 55 degrees F  
*Frost-free period:* 145 to 240 days  
*Farmland classification:* Not prime farmland

**Map Unit Composition**

*Chatfield, very stony, and similar soils:* 35 percent  
*Hollis, very stony, and similar soils:* 25 percent  
*Canton, very stony, and similar soils:* 25 percent  
*Minor components:* 15 percent  
*Estimates are based on observations, descriptions, and transects of the mapunit.*

**Description of Chatfield, Very Stony**

**Setting**

*Landform:* Ridges, hills  
*Landform position (two-dimensional):* Backslope, shoulder, summit  
*Landform position (three-dimensional):* Crest, side slope, nose slope  
*Down-slope shape:* Convex  
*Across-slope shape:* Linear, convex  
*Parent material:* Coarse-loamy melt-out till derived from granite, gneiss, and/or schist

**Typical profile**

*O<sub>i</sub> - 0 to 1 inches:* slightly decomposed plant material  
*A - 1 to 2 inches:* fine sandy loam  
*B<sub>w</sub> - 2 to 30 inches:* gravelly fine sandy loam  
*2R - 30 to 40 inches:* bedrock

**Properties and qualities**

*Slope:* 0 to 8 percent  
*Percent of area covered with surface fragments:* 1.6 percent  
*Depth to restrictive feature:* 20 to 41 inches to lithic bedrock  
*Natural drainage class:* Well drained  
*Runoff class:* High  
*Capacity of the most limiting layer to transmit water (K<sub>sat</sub>):* Very low (0.00 to 0.00 in/hr)



## Custom Soil Resource Report

*Depth to water table:* More than 80 inches  
*Frequency of flooding:* None  
*Frequency of ponding:* None  
*Salinity, maximum in profile:* Nonsaline (0.0 to 1.9 mmhos/cm)  
*Available water storage in profile:* Low (about 4.3 inches)

### Interpretive groups

*Land capability classification (irrigated):* None specified  
*Land capability classification (nonirrigated):* 6s  
*Hydrologic Soil Group:* B  
*Hydric soil rating:* No

### Description of Canton, Very Stony

#### Setting

*Landform:* Hills, moraines, ridges  
*Landform position (two-dimensional):* Summit, shoulder, backslope  
*Landform position (three-dimensional):* Side slope, crest, nose slope  
*Down-slope shape:* Linear, convex  
*Across-slope shape:* Convex  
*Parent material:* Coarse-loamy over sandy melt-out till derived from gneiss, granite, and/or schist

#### Typical profile

*O<sub>i</sub> - 0 to 2 inches:* slightly decomposed plant material  
*A - 2 to 5 inches:* fine sandy loam  
*Bw<sub>1</sub> - 5 to 16 inches:* fine sandy loam  
*Bw<sub>2</sub> - 16 to 22 inches:* gravelly fine sandy loam  
*2C - 22 to 67 inches:* gravelly loamy sand

#### Properties and qualities

*Slope:* 0 to 8 percent  
*Percent of area covered with surface fragments:* 1.6 percent  
*Depth to restrictive feature:* 19 to 39 inches to strongly contrasting textural stratification  
*Natural drainage class:* Well drained  
*Runoff class:* Low  
*Capacity of the most limiting layer to transmit water (K<sub>sat</sub>):* Moderately low to high (0.14 to 14.17 in/hr)  
*Depth to water table:* More than 80 inches  
*Frequency of flooding:* None  
*Frequency of ponding:* None  
*Salinity, maximum in profile:* Nonsaline (0.0 to 1.9 mmhos/cm)  
*Available water storage in profile:* Low (about 3.4 inches)

### Interpretive groups

*Land capability classification (irrigated):* None specified  
*Land capability classification (nonirrigated):* 6s  
*Hydrologic Soil Group:* B  
*Hydric soil rating:* No

### Description of Hollis, Very Stony

#### Setting

*Landform:* Hills, ridges  
*Landform position (two-dimensional):* Backslope, shoulder, summit  
*Landform position (three-dimensional):* Crest, side slope, nose slope

## Custom Soil Resource Report

*Down-slope shape:* Convex

*Across-slope shape:* Linear, convex

*Parent material:* Coarse-loamy melt-out till derived from granite, gneiss, and/or schist

### Typical profile

*O<sub>i</sub> - 0 to 2 inches:* slightly decomposed plant material

*A - 2 to 7 inches:* gravelly fine sandy loam

*B<sub>w</sub> - 7 to 16 inches:* gravelly fine sandy loam

*2R - 16 to 26 inches:* bedrock

### Properties and qualities

*Slope:* 0 to 8 percent

*Percent of area covered with surface fragments:* 1.6 percent

*Depth to restrictive feature:* 8 to 23 inches to lithic bedrock

*Natural drainage class:* Somewhat excessively drained

*Runoff class:* Very high

*Capacity of the most limiting layer to transmit water (K<sub>sat</sub>):* Very low (0.00 to 0.00 in/hr)

*Depth to water table:* More than 80 inches

*Frequency of flooding:* None

*Frequency of ponding:* None

*Salinity, maximum in profile:* Nonsaline (0.0 to 1.9 mmhos/cm)

*Available water storage in profile:* Very low (about 2.7 inches)

### Interpretive groups

*Land capability classification (irrigated):* None specified

*Land capability classification (nonirrigated):* 6s

*Hydrologic Soil Group:* D

*Hydric soil rating:* No

### Minor Components

#### Newfields, very stony

*Percent of map unit:* 5 percent

*Landform:* Moraines, hills, ground moraines

*Landform position (two-dimensional):* Footslope

*Landform position (three-dimensional):* Base slope

*Down-slope shape:* Linear

*Across-slope shape:* Concave

*Hydric soil rating:* No

#### Freetown

*Percent of map unit:* 5 percent

*Landform:* Depressions, marshes, swamps, kettles, bogs

*Down-slope shape:* Concave

*Across-slope shape:* Concave

*Hydric soil rating:* Yes

#### Walpole, very stony

*Percent of map unit:* 3 percent

*Landform:* Depressions, outwash plains, depressions, deltas, outwash terraces

*Landform position (three-dimensional):* Tread

*Down-slope shape:* Concave

*Across-slope shape:* Concave

*Hydric soil rating:* Yes

**Rock outcrop**

*Percent of map unit:* 2 percent  
*Landform:* Hills, ridges  
*Hydric soil rating:* Unranked

**140C—Chatfield-Hollis-Canton complex, 8 to 15 percent slopes, rocky**

**Map Unit Setting**

*National map unit symbol:* 2w82s  
*Elevation:* 0 to 980 feet  
*Mean annual precipitation:* 36 to 71 inches  
*Mean annual air temperature:* 39 to 55 degrees F  
*Frost-free period:* 145 to 240 days  
*Farmland classification:* Not prime farmland

**Map Unit Composition**

*Chatfield, very stony, and similar soils:* 35 percent  
*Canton, very stony, and similar soils:* 25 percent  
*Hollis, very stony, and similar soils:* 25 percent  
*Minor components:* 15 percent  
*Estimates are based on observations, descriptions, and transects of the mapunit.*

**Description of Chatfield, Very Stony**

**Setting**

*Landform:* Ridges, hills  
*Landform position (two-dimensional):* Backslope, shoulder, summit  
*Landform position (three-dimensional):* Crest, side slope, nose slope  
*Down-slope shape:* Convex  
*Across-slope shape:* Linear, convex  
*Parent material:* Coarse-loamy melt-out till derived from granite, gneiss, and/or schist

**Typical profile**

*O<sub>i</sub> - 0 to 1 inches:* slightly decomposed plant material  
*A - 1 to 2 inches:* fine sandy loam  
*B<sub>w</sub> - 2 to 30 inches:* gravelly fine sandy loam  
*2R - 30 to 40 inches:* bedrock

**Properties and qualities**

*Slope:* 8 to 15 percent  
*Percent of area covered with surface fragments:* 1.6 percent  
*Depth to restrictive feature:* 20 to 41 inches to lithic bedrock  
*Natural drainage class:* Well drained  
*Runoff class:* High  
*Capacity of the most limiting layer to transmit water (K<sub>sat</sub>):* Very low (0.00 to 0.00 in/hr)

## Custom Soil Resource Report

*Depth to water table:* More than 80 inches  
*Frequency of flooding:* None  
*Frequency of ponding:* None  
*Salinity, maximum in profile:* Nonsaline (0.0 to 1.9 mmhos/cm)  
*Available water storage in profile:* Low (about 4.3 inches)

### Interpretive groups

*Land capability classification (irrigated):* None specified  
*Land capability classification (nonirrigated):* 6s  
*Hydrologic Soil Group:* B  
*Hydric soil rating:* No

### Description of Hollis, Very Stony

#### Setting

*Landform:* Hills, ridges  
*Landform position (two-dimensional):* Backslope, shoulder, summit  
*Landform position (three-dimensional):* Crest, side slope, nose slope  
*Down-slope shape:* Convex  
*Across-slope shape:* Linear, convex  
*Parent material:* Coarse-loamy melt-out till derived from granite, gneiss, and/or schist

#### Typical profile

*O<sub>i</sub> - 0 to 2 inches:* slightly decomposed plant material  
*A - 2 to 7 inches:* gravelly fine sandy loam  
*B<sub>w</sub> - 7 to 16 inches:* gravelly fine sandy loam  
*2R - 16 to 26 inches:* bedrock

#### Properties and qualities

*Slope:* 8 to 15 percent  
*Percent of area covered with surface fragments:* 1.6 percent  
*Depth to restrictive feature:* 8 to 23 inches to lithic bedrock  
*Natural drainage class:* Somewhat excessively drained  
*Runoff class:* Very high  
*Capacity of the most limiting layer to transmit water (K<sub>sat</sub>):* Very low (0.00 to 0.00 in/hr)  
*Depth to water table:* More than 80 inches  
*Frequency of flooding:* None  
*Frequency of ponding:* None  
*Salinity, maximum in profile:* Nonsaline (0.0 to 1.9 mmhos/cm)  
*Available water storage in profile:* Very low (about 2.7 inches)

### Interpretive groups

*Land capability classification (irrigated):* None specified  
*Land capability classification (nonirrigated):* 6s  
*Hydrologic Soil Group:* D  
*Hydric soil rating:* No

### Description of Canton, Very Stony

#### Setting

*Landform:* Hills, moraines, ridges  
*Landform position (two-dimensional):* Backslope, summit, shoulder  
*Landform position (three-dimensional):* Side slope, crest, nose slope  
*Down-slope shape:* Linear, convex  
*Across-slope shape:* Convex

## Custom Soil Resource Report

*Parent material:* Coarse-loamy over sandy melt-out till derived from gneiss, granite, and/or schist

### Typical profile

*Oi - 0 to 2 inches:* slightly decomposed plant material  
*A - 2 to 5 inches:* fine sandy loam  
*Bw1 - 5 to 16 inches:* fine sandy loam  
*Bw2 - 16 to 22 inches:* gravelly fine sandy loam  
*2C - 22 to 67 inches:* gravelly loamy sand

### Properties and qualities

*Slope:* 8 to 15 percent  
*Percent of area covered with surface fragments:* 1.6 percent  
*Depth to restrictive feature:* 19 to 39 inches to strongly contrasting textural stratification  
*Natural drainage class:* Well drained  
*Runoff class:* Low  
*Capacity of the most limiting layer to transmit water (Ksat):* Moderately low to high (0.14 to 14.17 in/hr)  
*Depth to water table:* More than 80 inches  
*Frequency of flooding:* None  
*Frequency of ponding:* None  
*Salinity, maximum in profile:* Nonsaline (0.0 to 1.9 mmhos/cm)  
*Available water storage in profile:* Low (about 3.4 inches)

### Interpretive groups

*Land capability classification (irrigated):* None specified  
*Land capability classification (nonirrigated):* 6s  
*Hydrologic Soil Group:* B  
*Hydric soil rating:* No

### Minor Components

#### Freetown

*Percent of map unit:* 5 percent  
*Landform:* Marshes, swamps, kettles, bogs, depressions  
*Down-slope shape:* Concave  
*Across-slope shape:* Concave  
*Hydric soil rating:* Yes

#### Newfields, very stony

*Percent of map unit:* 5 percent  
*Landform:* Ground moraines, moraines, hills  
*Landform position (two-dimensional):* Footslope  
*Landform position (three-dimensional):* Base slope  
*Down-slope shape:* Linear  
*Across-slope shape:* Concave  
*Hydric soil rating:* No

#### Scarboro, very stony

*Percent of map unit:* 3 percent  
*Landform:* Outwash deltas, drainageways, outwash terraces, depressions  
*Landform position (three-dimensional):* Tread  
*Down-slope shape:* Concave  
*Across-slope shape:* Concave, linear  
*Hydric soil rating:* Yes

**Rock outcrop**

*Percent of map unit:* 2 percent  
*Landform:* Hills, ridges  
*Hydric soil rating:* Unranked

**538A—Squamscott fine sandy loam, 0 to 5 percent slopes**

**Map Unit Setting**

*National map unit symbol:* 9cp9  
*Elevation:* 90 to 1,000 feet  
*Mean annual precipitation:* 30 to 55 inches  
*Mean annual air temperature:* 45 to 54 degrees F  
*Frost-free period:* 120 to 180 days  
*Farmland classification:* Farmland of local importance

**Map Unit Composition**

*Squamscott and similar soils:* 85 percent  
*Minor components:* 15 percent  
*Estimates are based on observations, descriptions, and transects of the mapunit.*

**Description of Squamscott**

**Setting**

*Landform:* Marine terraces

**Typical profile**

*H1 - 0 to 4 inches:* fine sandy loam  
*H2 - 4 to 12 inches:* loamy sand  
*H3 - 12 to 19 inches:* fine sand  
*H4 - 19 to 65 inches:* silt loam

**Properties and qualities**

*Slope:* 0 to 5 percent  
*Depth to restrictive feature:* More than 80 inches  
*Natural drainage class:* Poorly drained  
*Runoff class:* Medium  
*Capacity of the most limiting layer to transmit water (Ksat):* Moderately low to moderately high (0.06 to 0.60 in/hr)  
*Depth to water table:* About 0 to 12 inches  
*Frequency of flooding:* None  
*Frequency of ponding:* None  
*Available water storage in profile:* High (about 9.6 inches)

**Interpretive groups**

*Land capability classification (irrigated):* None specified  
*Land capability classification (nonirrigated):* 4w  
*Hydrologic Soil Group:* C/D  
*Hydric soil rating:* Yes

**Minor Components**

**Maybid**

*Percent of map unit: 5 percent*

*Landform: Marine terraces*

*Hydric soil rating: Yes*

**Scitico**

*Percent of map unit: 5 percent*

*Landform: Marine terraces*

*Hydric soil rating: Yes*

**Eldridge**

*Percent of map unit: 5 percent*

*Hydric soil rating: No*

# References

---

- American Association of State Highway and Transportation Officials (AASHTO). 2004. Standard specifications for transportation materials and methods of sampling and testing. 24th edition.
- American Society for Testing and Materials (ASTM). 2005. Standard classification of soils for engineering purposes. ASTM Standard D2487-00.
- Cowardin, L.M., V. Carter, F.C. Golet, and E.T. LaRoe. 1979. Classification of wetlands and deep-water habitats of the United States. U.S. Fish and Wildlife Service FWS/OBS-79/31.
- Federal Register. July 13, 1994. Changes in hydric soils of the United States.
- Federal Register. September 18, 2002. Hydric soils of the United States.
- Hurt, G.W., and L.M. Vasilas, editors. Version 6.0, 2006. Field indicators of hydric soils in the United States.
- National Research Council. 1995. Wetlands: Characteristics and boundaries.
- Soil Survey Division Staff. 1993. Soil survey manual. Soil Conservation Service. U.S. Department of Agriculture Handbook 18. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2\\_054262](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_054262)
- Soil Survey Staff. 1999. Soil taxonomy: A basic system of soil classification for making and interpreting soil surveys. 2nd edition. Natural Resources Conservation Service, U.S. Department of Agriculture Handbook 436. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2\\_053577](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053577)
- Soil Survey Staff. 2010. Keys to soil taxonomy. 11th edition. U.S. Department of Agriculture, Natural Resources Conservation Service. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2\\_053580](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053580)
- Tiner, R.W., Jr. 1985. Wetlands of Delaware. U.S. Fish and Wildlife Service and Delaware Department of Natural Resources and Environmental Control, Wetlands Section.
- United States Army Corps of Engineers, Environmental Laboratory. 1987. Corps of Engineers wetlands delineation manual. Waterways Experiment Station Technical Report Y-87-1.
- United States Department of Agriculture, Natural Resources Conservation Service. National forestry manual. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/home/?cid=nrcs142p2\\_053374](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/home/?cid=nrcs142p2_053374)
- United States Department of Agriculture, Natural Resources Conservation Service. National range and pasture handbook. <http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/landuse/rangepasture/?cid=stelprdb1043084>




## Custom Soil Resource Report

United States Department of Agriculture, Natural Resources Conservation Service. National soil survey handbook, title 430-VI. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/scientists/?cid=nrcs142p2\\_054242](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/scientists/?cid=nrcs142p2_054242)


United States Department of Agriculture, Natural Resources Conservation Service. 2006. Land resource regions and major land resource areas of the United States, the Caribbean, and the Pacific Basin. U.S. Department of Agriculture Handbook 296. [http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2\\_053624](http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053624)

United States Department of Agriculture, Soil Conservation Service. 1961. Land capability classification. U.S. Department of Agriculture Handbook 210. [http://www.nrcs.usda.gov/Internet/FSE\\_DOCUMENTS/nrcs142p2\\_052290.pdf](http://www.nrcs.usda.gov/Internet/FSE_DOCUMENTS/nrcs142p2_052290.pdf)

Hydrologic Soil Group—Rockingham County, New Hampshire  
(BANFIELD - HSG)



Map Scale: 1:4,680 if printed on B landscape (17" x 11") sheet.



Map projection: Web Mercator Corner coordinates: WGS84 Edge tics: UTM Zone 19N WGS84



Natural Resources  
Conservation Service

Web Soil Survey  
National Cooperative Soil Survey

(This Page Is Intentionally Blank)

## MAP LEGEND

### Area of Interest (AOI)









 Area of Interest (AOI)

### Soils

#### Soil Rating Polygons





 A  
 A/D  
 B  
 B/D  
 C  
 C/D  
 D  
 Not rated or not available

#### Soil Rating Lines


 A  
 A/D  
 B  
 B/D  
 C  
 C/D  
 D  
 Not rated or not available

#### Soil Rating Points






 A  
 A/D  
 B  
 B/D

 C  
 C/D  
 D  
 Not rated or not available

### Water Features

 Streams and Canals

### Transportation

 Rails  
 Interstate Highways  
 US Routes  
 Major Roads  
 Local Roads

### Background

 Aerial Photography

## MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service  
 Web Soil Survey URL:  
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Rockingham County, New Hampshire  
 Survey Area Data: Version 21, Sep 16, 2019

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Dec 31, 2009—Jun 14, 2017

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

(This Page Is Intentionally Blank)

## Hydrologic Soil Group

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
33A	Scitico silt loam, 0 to 5 percent slopes	C/D	6.7	5.2%
38B	Eldridge fine sandy loam, 3 to 8 percent slopes	C/D	1.7	1.3%
134	Maybid silt loam	C/D	7.6	5.9%
140B	Chatfield-Hollis-Canton complex, 0 to 8 percent slopes, rocky	B	68.4	53.3%
140C	Chatfield-Hollis-Canton complex, 8 to 15 percent slopes, rocky	B	15.9	12.4%
495	Natchaug mucky peat, 0 to 2 percent slopes	B/D	1.3	1.0%
538A	Squamscott fine sandy loam, 0 to 5 percent slopes	C/D	26.8	20.9%
<b>Totals for Area of Interest</b>			<b>128.5</b>	<b>100.0%</b>

## Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

## Rating Options

*Aggregation Method:* Dominant Condition

*Component Percent Cutoff:* None Specified

*Tie-break Rule:* Higher

**APPENDIX J**  
**TEST PIT LOGS**



(This Page Is Intentionally Blank)



SITE-SPECIFIC SOIL SURVEY REPORT  
THE VILLAGES AT BANFIELD ROAD  
PORTSMOUTH, NH  
GES # 2017071

1. MAPPING STANDARDS

*Site-Specific Soil Mapping Standards for New Hampshire and Vermont*. SSSNNE Special Publication No. 3, Version 5.0, December 2017. This map product is within the technical standards of the National Cooperative Soil Survey. It is a special product, intended for the submission to NH DES Alteration of Terrain. It was produced by a professional soil scientist and is not a product of the USDA Natural Resource Conservation Service.

2. DATE SOIL MAP PRODUCED

December 19, 2019

3. GEOGRAPHIC LOCATION AND SIZE OF SITE

Approximately 23 acres of the 44.8 acre lot was soil mapped. Tax map 256, Lot 2. The site is located in the City of Portsmouth, NH.

4. PURPOSE OF THE SOIL MAP

The preparation of this map was requested by TFM. The purpose was to meet the requirements of NH Alteration of Terrain.

5. SOIL IDENTIFICATION LEGEND

SSSS SYM.	SSSS MAP NAME	HYDROLOGIC SOIL GRP.
41	Chatfield-Hollis-Rock Outcrop Complex	B
135	Chatfield Variant-Newfields Complex	C
538	Squamscott fine sandy loam	C
656	Ridgebury fine sandy loam	C

SLOPE PHASE:

0-8%	B	8-15%	C	15-25%	D
25%+	E				

## 6. SOIL MAP UNIT DESCRIPTIONS

41 – Chatfield-Hollis-Rock Outcrop Complex is located in bedrock-controlled landscapes. A soil complex is a mix of soil types that are too interwoven to be able to separate at the scale of the soil map. Chatfield is the largest component of the complex at 50%. Hollis is the next component at 30%. The last component is Rock Outcrop at 20%. Chatfield is a loamy glacial till soil that is 20 to 40 inches deep to bedrock. The Hollis has a depth of 10 to 20 inches to bedrock. Rock Outcrop is exposed ledge. The hydrologic group for Chatfield is B. The hydrologic group for Hollis is C/D. There is no hydrologic group for Rock Outcrop, as it is impervious surface. The hydrologic group for this complex was assigned as B, as that represents the largest component of the complex.

135 – Chatfield Variant-Newfields Complex is located in bedrock-controlled landscapes. This is a case where the state-wide soil legend is not adequate to classify the soil types that are intermixed in the soil complex. While Newfields is present in the soil complex map unit, it is not one of the major components. Woodbridge is more dominant than Newfields. Newfields is a moderately well drained loose glacial till soil that has a hydrologic group of B. Woodbridge is a moderately well drained soil on dense glacial till and has a hydrologic group of C. Numerous test pits were conducted on site. At the end of the investigations, 37 Woodbridge soils, 32 Chatfield soil, and 6 Newfields were recorded on the site. So, Woodbridge is the largest component of this soil complex. The Chatfield Variant is a moderately well drained soil that is 20 to 40 inches deep. In this case, there were Chatfield Variant soils that had a dense till layer above the bedrock, which would make the hydrologic soil group for these pits more appropriately identified as C. Based upon the major component of this soil complex and based upon the Chatfield Variant soil profiles, this soil complex map unit was assigned a hydrologic group of C.

538 – Squamscott fine sandy loam is a poorly drained sand over marine silts soil that is commonly found along the Seacoast of New Hampshire. In this case, this soil represents the largest wetland on site. Inclusions would be Scitico silt loam and Ridgebury fine sandy loam.

656 – Ridgebury fine sandy loam is a poorly drained loamy soil that developed on dense glacial tills. These areas commonly have a perched water table. Inclusions would be Walpole fine sandy loam.

## 7. RESPONSIBLE SOIL SCIENTIST

James P. Gove, C.S.S. #004



8. OTHER DISTINGUISHING FEATURES OF SITE


This site has numerous rock outcrops at the higher elevations.

9. MAXIMUM SIZE OF LIMITING INCLUSIONS

15%

10. SPECIAL FEATURE SYMBOLS

None used.



(This Page Is Intentionally Blank)



(This Page Is Intentionally Blank)

Test Pit Log  
Banfield Rd, Portsmouth  
Logged By: Brenden Walden & James Gove  
Date: 8/29 & 8/30, 2019

Test Pit #1:

0-8 INCHES, 10YR 3/3, FINE SANDY LOAM, GRANULAR, FRIABLE  
8-30 INCHES, 10YR 4/6, FINE SANDY LOAM, GRANULAR, FRIABLE  
ESHWT: 30 INCHES                      REFUSAL: 30 INCHES                      OBSERVED WATER: N/A

Test Pit #2:

0-9 INCHES, 10YR 3/3, FINE SANDY LOAM, GRANULAR, FRIABLE  
9-28 INCHES, 10YR 4/6, FINE SANDY LOAM, GRANULAR, FRIABLE  
ESHWT: 28 INCHES                      REFUSAL: 28 INCHES                      OBSERVED WATER: N/A

Test Pit #3:

0-10 INCHES, 10YR 3/3, FINE SANDY LOAM, GRANULAR, FRIABLE  
10-30 INCHES, 10YR 4/6, FINE SANDY LOAM, GRANULAR, FRIABLE  
30-57 INCHES, 2.5Y 5/3, FINE SANDY LOAM, GRANULAR, FRIABLE, WITH 20% REDOX CONCENTRATIONS  
ESHWT: 30 INCHES                      REFUSAL: 57 INCHES                      OBSERVED WATER: N/A

Test Pit #4:

0-8 INCHES, 10YR 3/3, FINE SANDY LOAM, GRANULAR, FRIABLE  
8-24 INCHES, 10YR 4/6, FINE SANDY LOAM GRANULAR, FRIABLE  
ESHWT: 24 INCHES                      REFUSAL: 44 INCHES                      OBSERVED WATER: N/A

Test Pit #5:

0-6 INCHES, 10YR 3/3, FINE SANDY LOAM, GRANULAR, FRIABLE  
6-25 INCHES, 10YR 4/6, FINE SANDY LOAM, GRANULAR, FRIABLE  
25-51 INCHES, 2.5Y 5/3, FINE SANDY LOAM, PLATY, FIRM, WITH 10% REDOX, CONCENTRATIONS  
ESHWT: 25 INCHES                      REFUSAL: 51 INCHES                      OBSERVED WATER: N/A

Test Pit #6:

0-8 INCHES, 10YR 3/3, FINE SANDY LOAM, GRANULAR, FRIABLE  
8-28 INCHES, 10YR 4/6, FINE SANDY LOAM, GRANULAR, FRIABLE  
28-60 INCHES, 2.5Y 5/3, FINE SANDY LOAM, PLATY, FIRM, WITH 20% REDOX CONCENTRATIONS  
ESHWT: 28 INCHES                      REFUSAL: N/A                      OBSERVED WATER: N/A

Test Pit #7:

0-10 INCHES, 10YR 3/3, FINE SANDY LOAM, GRANULAR, FRIABLE  
10- 41 INCHES, 10YR 4/6, FINE SANDY LOAM, GRANULAR, FRIABLE  
41-64 INCHES, 2.5Y 5/3, FINE SANDY LOAM, PLATY, FIRM, WITH 10% REDOX CONCENTRATIONS  
ESHWT:41 INCHES                      REFUSAL: N/A                      OBSERVED WATER: N/A



Test Pit #8:

0-7 INCHES, 10YR 3/3, FINE SANDY LOAM, GRANULAR, FRIABLE  
7-28 INCHES, 10YR 4/6, FINE SANDY LOAM, GRANULAR, FRIABLE  
28-53 INCHES, 2.5Y 5/3, FINE SANDY LOAM, PLATY, FIRM, WITH 20% REDOX CONCENTRATIONS  
ESHWT: 28 INCHES                      REFUSAL: 53 INCHES                      OBSERVED WATER: N/A

Test Pit #10:

0-8 INCHES, 10YR 3/3, FINE SANDY LOAM, GRANULAR, FRIABLE  
8-36 INCHES, 10YR 4/6, FINE SANDY LOAM, GRANULAR, FRIABLE  
36-68 INCHES, 2.5Y 5/3, FINE SANDY LOAM, MASSIVE, FRIABLE, WITH 20% REDOX CONCENTRATIONS  
ESHWT: 36 INCHES                      REFUSAL: N/A                      OBSERVED WATER: N/A

Test Pit #11:

0-8 INCHES, 10YR 3/3, FINE SANDY LOAM, GRANULAR, FRIABLE  
8-28 INCHES, 10YR 4/6, FINE SANDY LOAM, GRANULAR, FRIABLE  
28-64 INCHES, 2.5Y 5/3, FINE SANDY LOAM, PLATY, FIRM, WITH 10% REDOX CONCENTRATIONS  
ESHWT: 28 INCHES                      REFUSAL: 64 INCHES                      OBSERVED WATER: N/A

Test Pit #13:

0-10 INCHES, 10YR 3/3, FINE SANDY LOAM, GRANULAR, FRIABLE  
10-32 INCHES, 10YR 4/6, FINE SANDY LOAM, GRANULAR, FRIABLE  
32-61 INCHES, 2.5Y 5/3, FINE SANDY LOAM, PLATY, FIRM, WITH 10% REDOX CONCENTRATIONS  
ESHWT: 32 INCHES                      REFUSAL: 61 INCHES                      OBSERVED WATER: N/A

Test Pit #14A:

0-10 INCHES, 10YR 3/3, FINE SANDY LOAM, GRANULAR, FRIABLE  
10-23 INCHES, 10YR 4/6, FINE SANDY LOAM, GRANULAR, FRIABLE  
23-44 INCHES, 2.5Y 5/3, FINE SANDY LOAM, PLATY, FIRM, WITH 20% REDOX CONCENTRATIONS  
ESHWT: 23 INCHES                      REFUSAL: 44 INCHES                      OBSERVED WATER: N/A

Test Pit #14B:

0-6 INCHES, 10YR 3/3, FINE SANDY LOAM, GRANULAR, FRIABLE  
6-32 INCHES, 10YR 4/6, FINE SANDY LOAM, GRANULAR, FRIABLE  
32-57 INCHES, 2.5Y 5/3, FINE SANDY LOAM, PLATY, FIRM, WITH 10 % REDOX CONCENTRATIONS  
ESHWT: 32 INCHES                      REFUSAL: 57 INCHES                      OBSERVED WATER: N/A

Test Pit #15:

0-14 INCHES, 10YR 3/3, FINE SANDY LOAM, GRANULAR, FRIABLE  
14-28 INCHES, 10YR 4/6, FINE SANDY LOAM, GRANULAR, FRIABLE  
28-60 INCHES, 2.5Y 5/3, FINE SANDY LOAM, MASSIVE, FIRM, WITH 40% REDOX CONCENTRATIONS  
ESHWT: 28 INCHES                      REFUSAL: 60 INCHES                      OBSERVED WATER: N/A

Test pit #16:

0-5 INCHES, 10YR 3/3, FINE SANDY LOAM, GRANULAR, FRIABLE

5-24 INCHES, 10YR 4/4, FINE SANDY LOAM, GRANULAR, FRIABLE

ESHWT: 24 INCHES      REFUSAL: 24 INCHES      OBSERVED WATER: N/A

Test Pit #17:

0-6 INCHES, 10YR 3/3, FINE SANDY LOAM, GRANULAR, FRIABLE

6-34 INCHES, 10YR 4/6, FINE SANDY LOAM, GRANULAR, FRIABLE

34-60 INCHES, 2.5Y 5/3, FINE SANDY LOAM, MASSIVE, FRIABLE, WITH 10% REDOX CONCENTRATIONS

ESHWT: 34 INCHES      REFUSAL: 60 INCHES      OBSERVED WATER: N/A

Test Pit #18:

0-6 INCHES, 10YR 3/3, FINE SANDY LOAM, GRANULAR, FRIABLE

6-22 INCHES, 10YR 4/6, FINE SANDY LOAM, GRANULAR, FRIABLE

22-50 INCHES, 2.5Y 5/3, FINE SANDY LOAM, PLATY, FIRM, WITH 10% REDOX CONCENTRATIONS

ESHWT: 22 INCHES      REFUSAL: 50 INCHES      OBSERVED WATER: N/A

Test Pit #19:

0-7 INCHES, 10YR 3/3, FINE SANDY LOAM, GRANULAR, FRIABLE

7-24 INCHES, 10YR 4/6, FINE SANDY LOAM, GRANULAR, FRIABLE

ESHWT: 24 INCHES      REFUSAL: 24 INCHES      OBSERVED WATER: N/A

Test Pit #21:

0-10 INCHES, 10YR 3/3, FINE SANDY LOAM, GRANULAR, FRIABLE

10-21 INCHES, 10YR 4/6, FINE SANDY LOAM, GRANULAR, FRIABLE

21-48 INCHES, 2.5Y 5/3, FINE SANDY LOAM, PLATY, FIRM, WITH 10% REDOX CONCENTRATIONS

ESHWT: 21 INCHES      REFUSAL: 40 INCHES      OBSERVED WATER: N/A

Test Pit #22:

0-6 INCHES, 10YR 3/3, FINE SANDY LOAM, GRANULAR, FRIABLE

6-20 INCHES, 10YR 4/6, FINE SANDY LOAM, GRANULAR, FRIABLE

20-58 INCHES, 2.5Y 5/3, FINE SANDY LOAM, PLATY, FIRM, WITH 10% REDOX CONCENTRATIONS

ESHWT: 20 INCHES      REFUSAL: 58 INCHES      OBSERVED WATER: N/A

Test Pit #E1:

0-10 INCHES, 10YR 3/3, FINE SANDY LOAM, GRANULAR, FRIABLE

10-22 INCHES, 10YR 4/6, FINE SANDY LOAM, GRANULAR, FRIABLE

22-51 INCHES, 2.5Y 5/3, FINE SANDY LOAM, PLATY, FIRM, 20% REDOX CONCENTRATIONS

ESHWT: 22 INCHES      REFUSAL: 51 INCHES      OBSERVED WATER: N/A

Test Pit #E2:

0-5 INCHES, 10YR 3/3, FINE SANDY LOAM, GRANULAR, FRIABLE

5-28 INCHES, 10YR 4/6, FINE SANDY LOAM, GRANULAR, FRIABLE

ESHWT: 28 INCHES      REFUSAL: 28 INCHES      OBSERVED WATER: N/A

Test Pit #E3:

0-8 INCHES, 10YR 3/3, FINE SANDY LOAM, GRANULAR, FRIABLE  
8-32 INCHES, 10YR 4/6, FINE SANDY LOAM, GRANULAR, FRIABLE  
32-74 INCHES, 2.5Y 5/3, FINE SANDY LOAM, PLATY, FIRM, WITH 10% REDOX CONCENTRATIONS  
ESHWT:32 INCHES                      REFUSAL: 74 INCHES                      OBSERVED WATER: N/A

Test Pit #E4:

0-9 INCHES, 10YR 3/3, FINE SANDY LOAM, GRANULAR, FRIABLE  
9-28 INCHES, 10YR 4/6, FINE SANDY LOAM, GRANULAR, FRIABLE  
28-50 INCHES, 2.5Y 5/3, FINE SANDY LOAM, PLATY, FIRM, WITH 10% REDOX CONCENTRATIONS  
ESHWT: 28 INCHES                      REFUSAL: 50 INCHES                      OBSERVED WATER: N/A

Test Pit #E8:

0-8 INCHES, 10YR 3/3, FINE SANDY LOAM, GRANULAR, FRIABLE  
8-27 INCHES, 2.5Y 4/6, FINE SANDY LOAM, GRANULAR, FRIABLE  
27-62 INCHES, 2.5Y 5/3, FINE SANDY LOAM, PLATY, FIRM, WITH 10% REDOX CONCENTRATIONS  
ESHWT:27 INCHES                      REFUSAL: N/A                      OBSERVED WATER: N/A

Test Pit #100:

0-10 INCHES, 10YR 3/3, FINE SANDY LOAM, GRANULAR, FRIABLE  
10-28 INCHES, 10YR 4/6, FINE SANDY LOAM, GRANULAR, FRIABLE  
28-54 INCHES, 2.5Y 5/3, FINE SANDY LOAM, PLATY, FIRM, WITH 10% REDOX CONCENTRATIONS  
ESHWT: 28 INCHES                      REFUSAL: 54 INCHES                      OBSERVED WATER: N/A

Test Pit #600:

0-8 INCHES, 10YR 3/3, FINE SANDY LOAM, GRANULAR, FRIABLE  
8-21 INCHES, 10YR 4/6, FINE SANDY LOAM, GRANULAR, FRIABLE  
21-47 INCHES, 2.5Y 5/3, FINE SANDY LOAM, PLATY, FIRM, WITH 10% REDOX CONCENTRATIONS  
47-60 INCHES, 2.5Y 5/2, SILT LOAM, MASSIVE, FIRM, WITH 305 REDOX CONCENTRATIONS  
ESHWT: 21 INCHES                      REFUSAL: N/A                      OBSERVED WATER: N/A

Test Pit Log

Banfield Rd

Date:

Logged By: Brenden Walden, Luke Hurley & Mike Coumo

Test Pit #5027:

0-3 INCHES, 10YR 3/2, FINE SANDY LOAM, GRANULAR, FRIABLE

3-20 INCHES, 10YR 5/5, FINE SANDY LOAM, GRANULAR, FRIABLE

ESHWT: N/A                      REFUSAL: 20 INCHES                      OBSERVED WATER: N/A

Test Pit #5026:

0-2 INCHES, 10YR 3/2, FINE SANDY LOAM, GRANULAR, FRIABLE

2-6 INCHES, 10YR 3/3, FINE SANDY LOAM, GRANULAR, FRIABLE

6-22 INCHES, 10YR 5/6, FINE SANDY LOAM, GRANULAR, FRIABLE

ESHWT: N/A                      REFUSAL: 22 INCHES                      OBSERVED WATER: N/A

Test Pit #5028:

0-2 INCHES, 10YR 3/2, FINE SANDY LOAM, GRANULAR, FRIABLE

2-4 INCHES, 10YR 3/3, FINE SANDY LOAM, GRANULAR, FRIABLE

4-36 INCHES, 10YR 4/4, FINE SANDY LOAM, GRANULAR, FRIABLE

ESHWT: N/A                      REFUSAL: 36 INCHES                      OBSERVED WATER: N/A

Test Pit #5093:

0-4 INCHES, 10YR 3/2, FINE SANDY LOAM, GRANULAR, FRIABLE

4-12 INCHES, 10YR 4/3, GRAVELY FINE SANDY LOAM, GRANULAR, FRIABLE

12-22 INCHES, 10YR 5/4, GRAVELY FINE SANDY LOAM, GRANULAR, FRIABLE

22-36 INCHES, 2.5Y 6/4, GRAVELY FINE SANDY LOAM, GRANULAR, FRIABLE

ESHWT: N/A                      REFUSAL: 36 INCHES                      OBSERVED WATER: N/A

Test Pit # 5029:

0-2 INCHES, 10YR 3/2, FINE SANDY LOAM, GRANULAR, FRIABLE

2-8 INCHES, 10YR 4/3, GRAVELY FINE SANDY LOAM, GRANULAR, FRIABLE

8-24 INCHES, 10YR 5/4, GRAVELY FINE SANDY LOAM, GRANULAR, FRIABLE

24-40 INCHES, 2.5Y 6/4, GRAVELY FINE SANDY LOAM, GRANULAR, FRIABLE

40-44 INCHES, 2.5Y 6/4, GRAVELY FINE SANDY LOAM, GRANULAR FRIABLE, WITH 10% REDOX CONCENTRATIONS

ESHWT: 40 INCHES                      REFUSAL: 44 INCHES                      OBSERVED WATER: N/A

Test Pit #5094:

0-2 INCHES, 10YR 3/2, FINE SANDY LOAM, GRANULAR, FRIABLE

2-12 INCHES, 2.5Y 5/4, GRAVELY FINE SANDY LOAM, GRANULAR, FRIABLE

12-32 INCHES, 2.5Y 6/4, FINE SANDY LOAM, GRANULAR, FRIABLE

32-54 INCHES, 2.5Y 5/4, FINE SANDY LOAM, PLATY, FIRM, WITH 20% REDOX CONCENTRATIONS

ESHWT: 32 INCHES

REFUSAL: 54 INCHES

OBSERVED WATER: N/A

Test Pit #5038:

0-3 INCHES, 10YR 3/2, FINE SANDY LOAM, GRANULAR, FRIABLE

3-8 INCHES, 2.5Y 6/4, FINE SANDY LOAM, GRANULAR, FRIABLE

8-30 INCHES, 2.5Y 7/4, GRAVELY FINE SANDY LOAM, GRANULAR, FRIABLE

30-40 INCHES, 2.5Y 6/4, GRAVELY FINE SANDY LOAM, MASSIVE, FIRM, WITH 10% REDOX CONCENTRATIONS

ESHWT: 30 INCHES

REFUSAL: 40 INCHES

OBSERVED WATER: N/A

Test Pit #5095:

0-2 INCHES, 10YR 3/2, FINE SANDY LOAM, GRANULAR, FRIABLE

2-12 INCHES, 2.5Y 6/4, FINE SANDY LOAM, GRANULAR, FRIABLE

12-32 INCHES, 2.5Y 7/4, FINE SANDY LOAM, MASSIVE, FIRM WITH 10% REDOX CONCENTRATIONS

ESHWT: 12 INCHES

REFUSAL: 32 INCHES

OBSERVED WATER: N/A

Test Pit #5040/62

0-3 INCHES, 10YR 3/2, FINE SANDY LOAM, GRANULAR, FRIABLE

3-30 INCHES, 2.5Y 5/4, FINE SANDY LOAM, GRANULAR, FRIABLE

30-38 INCHES, 2.5Y 5/6, GRAVELY FINE SANDY LOAM, MASSIVE, FIRM

ESHWT: N/A

REFUSAL: 38 INCHES

OBSERVED WATER: N/A

Test Pit #5041/63:

0-3 INCHES, 10YR 3/2, FINE SANDY LOAM, GRANULAR, FRIABLE

3-20 INCHES, 10YR 4/6, FINE SANDY LOAM, GRANULAR, FRIABLE

ESHWT: N/A

REFUSAL: 20 INCHES

OBSERVED WATER: N/A

Test Pit #5039/61:

0-3 INCHES, 10YR 3/2, FINE SANDY LOAM, GRANULAR, FRIABLE

3-24 INCHES, 2.5Y 4/6, FINE SANDY LOAM, GRANULAR, FRIABLE

ESHWT: N/A

REFUSAL: 24 INCHES

OBSERVED WATER: N/A

Test Pit #5096:

0-3 INCHES, 10YR 3/2, FINE SANDY LOAM, GRANULAR, FRIABLE

3-16 INCHES, 10YR 5/6, FINE SANDY LOAM, GRANULAR, FRIABLE

16-34 INCHES, 2.5Y 6/4, FINE SANDY LOAM, GRANULAR, FRIABLE

ESHWT: N/A

REFUSAL: 34 INCHES

OBSERVED WATER: N/A

Test Pit #5038B:

0-2 INCHES, 10YR 3/2, FINE SANDY LOAM, GRANULAR, FRIABLE

2-14 INCHES, 10YR 5/6, FINE SANDY LOAM, GRANULAR, FRIABLE

14-24 INCHES, 2.5Y 6/4, GRAVELY FINE SANDY LOAM, GRANULAR, FRIABLE

24-29 INCHES, 2.5Y 6/3, FINE SANDY LOAM, MASSIVE, FIRM

29-40 INCHES, 2.5Y 6/3, FINE SANDY LOAM, MASSIVE, FIRM, WITH 10% REDOX CONCENTRATIONS

ESHWT: 29 INCHES

REFUSAL: 40 INCHES

OBSERVED WATER: N/A

Test Pit #5037/59:

0-4 INCHES, 10YR 3/2, FINE SANDY LOAM, GRANULAR, FRIABLE

4-15 INCHES, 2.5Y 5/4, FINE SANDY LOAM, GRANULAR, FRIABLE

15-34 INCHES, 2.5Y 6/4, FINE SANDY LOAM, GRANULAR, FRIABLE

34-40 INCHES, 2.5Y 6/3, FINE SANDY LOAM, MASSIVE, FIRM, WITH 10% REDOX CONCENTRATIONS

ESHWT: 34 INCHES

REFUSAL: 40 INCHES

OBSERVED WATER: N/A

Test Pit #5036/57:

0-2 INCHES, 10YR 3/3, FINE SANDY LOAM, GRANULAR, FRIABLE

2-12 INCHES, 10YR 4/4, FINE SANDY LOAM, GRANULAR, FRIABLE

12-26 INCHES, 2.5Y 5/3, GRAVELY FINE SANDY LOAM, GRANULAR, FRIABLE

26-34 INCHES, 2.5Y 5/5, GRAVELY FINE SANDY LOAM, MASSIVE, FIRM, WITH 10% REDOX CONCENTRATIONS

ESHWT: 26 INCHES

REFUSAL: 34 INCHES

OBSERVED WATER: N/A

Test Pit #5035/58:

0-3 INCHES, 10YR 2/2, FINE SANDY LOAM, GRANULAR, FRIABLE

3-23 INCHES, 2.5Y 5/4, FINE SANDY LOAM, GRANULAR, FRIABLE

23-55 INCHES, 2.5Y 5/2, FINE SANDY LOAM, MASSIVE, FIRM, WITH 25% REDOX CONCENTRATIONS

ESHWT: 23 INCHES

REFUSAL: N/A

OBSERVED WATER: N/A

Test Pit #5034/56:

0-4 INCHES, 10YR 3/2, FINE SANDY LOAM, GRANULAR, FRIABLE

4-20 INCHES, 2.5Y 5/4, FINE SANDY LOAM, GRANULAR, FRIABLE

20-36 INCHES, 2.5Y 5/4, FINE SANDY LOAM, MASSIVE, FIRM, WITH 10% REDOX CONCENTRATIONS

ESHWT: 20 INCHES

REFUSAL: 36 INCHES

OBSERVED WATER: N/A

Test Pit #5033:

0-2 INCHES, 10YR 3/3, FINE SANDY LOAM, GRANULAR, FRIABLE

2-15 INCHES, 10YR 5/6, FINE SANDY LOAM, GRANULAR, FRIABLE

15-23 INCHES, 2.5Y 6/4, FINE SANDY LOAM, GRANULAR, FRIABLE

23-52 INCHES, 2.5Y 4/3, FINE SANDY LOAM, MASSIVE, FIRM, WITH 30% REDOX CONCENTRATIONS

ESHWT: 23 INCHES

REFUSAL: N/A

OBSERVED WATER: N/A

Test Pit #5031:

0-5 INCHES, 10YR 3/2, FINE SANDY LOAM, GRANULAR, FRIABLE

5-12 INCHES, 10YR 4/4, FINE SANDY LOAM, GRANULAR, FRIABLE

12-24 INCHES, 2.5Y 5/4, FINE SANDY LOAM, GRANULAR, FRIABLE

24-40 INCHES, 2.5Y 6/4, FINE SANDY LOAM, MASSIVE, FIRM, WITH 10% REDOX CONCENTRATIONS

ESHWT: 24 INCHES

REFUSAL: 40 INCHES

OBSERVED WATER: N/A

Test Pit #5032:

0-3 INCHES, 10YR 3/2, FINE SANDY LOAM, GRANULAR, FRIABLE  
3-6 INCHES, 10YR 4/4, FINE SANDY LOAM, GRANULAR, FRIABLE  
6-14 INCHES, 2.5Y 5/4, FINE SANDY LOAM, GRANULAR, FRIABLE  
14-36 INCHES, 2.5Y 6/4, FINE SANDY LOAM, GRANULAR, FRIABLE  
ESHWT: N/A                      REFUSAL: 36 INCHES                      OBSERVED WATER: N/A

Test Pit #5084/52:

0-6 INCHES, 10YR 3/2, FINE SANDY LOAM, GRANULAR, FRIABLE  
6-24 INCHES, 2.5Y 5/6, GRAVELY FINE SANDY LOAM, GRANULAR, FRIABLE  
24-38 INCHES, 2.5Y 5/6, GRAVELY FINE SANDY LOAM, GRANULAR, FRIABLE, WITH 10% REDOX CONCENTRATIONS  
ESHWT: 24 INCHES                      REFUSAL: 38 INCHES                      OBSERVED WATER: N/A

Test Pit #5038/51:

0-4 INCHES, 10YR 3/3, FINE SANDY LOAM, GRANULAR, FRIABLE  
4-14 INCHES, 10YR 4/6, FINE SANDY LOAM, GRANULAR, FRIABLE  
14-24 INCHES, 6/4, GRAVELY FINE SANDY LOAM, MASSIVE, FIRM  
24-60 INCHES, 2.5Y 5/2, SILT LOAM, BLOCKY, FIRM, WITH 25% REDOX CONCENTRATIONS  
ESHWT: 24 INCHES                      REFUSAL: N/A                      OBSERVED WATER: N/A

Test Pit #5086/53:

0-6 INCHES, 10YR 3/3, FINE SANDY LOAM, GRANULAR, FRIABLE  
6-24 INCHES, 2.5Y 5/6, FINE SANDY LOAM, GRANULAR, FRIABLE  
24-68 INCHES, 2.5Y 5/2, FINE SANDY LOAM, MASSIVE, FIRM, WITH 50% REDOX CONCENTRATIONS  
ESHWT: 24 INCHES                      REFUSAL: N/A                      OBSERVED WATER: N/A

Test Pit #5085/54:

0-4 INCHES, 10YR 3/2, FINE SANDY LOAM, GRANULAR, FRIABLE  
4-24 INCHES, 10YR 5/6, FINE SANDY LOAM, GRANULAR, FRIABLE  
ESHWT: N/A                      REFUSAL: 24 INCHES                      OBSERVED WATER: N/A

Test Pit #5023:

0-2 INCHES, 10YR 3/3, FINE SANDY LOAM, GRANULAR, FRIABLE  
2-24 INCHES, 10YR 5/6, FINE SANDY LOAM, GRANULAR, FRIABLE  
24-36 INCHES, 2.5Y 4/4, FINE SANDY LOAM, GRANULAR, FRIABLE  
36-44 INCHES, 2.5Y 4/4, FINE SANDY LOAM, GRANULAR, FRIABLE, WITH 10% REDOX CONCENTRATIONS  
ESHWT: 36 INCHES                      REFUSAL: 44 INCHES                      OBSERVED WATER: N/A

Test Pit #5024:

0-4 INCHES, 10YR 3/2, FINE SANDY LOAM, GRANULAR, FRIABLE  
4-18 INCHES, 2.5Y 6/4, FINE SANDY LOAM, GRANULAR, FRIABLE  
18-32 INCHES, 2.5Y 5/4, FINE SANDY LOAM, GRANULAR, FRIABLE  
ESHWT: N/A                      REFUSAL: 32 INCHES                      OBSERVED WATER: N/A

Test Pit #5025:

0-3 INCHES, 10YR 3/2, FINE SANDY LOAM, GRANULAR, FRIABLE

3-7 INCHES, 10YR 3/3, FINE SANDY LOAM, GRANULAR, FRIABLE

7-32 INCHES, 10YR 4/4, FINE SANDY LOAM, GRANULAR, FRIABLE

ESHWT: N/A

REFUSAL: 32 INCHES


OBSERVED WATER: N/A

Number	ESHWT	REFUSAL	DEPTH
<b>LEDGE PROBES</b>			
5001	N/A	47	47
5002	N/A	N/A	52
5003	N/A	32	32
5004	N/A	36	36
5005	N/A	32	32
5006	N/A	36	36
5007	N/A	36	36
5008	N/A	24	24
5009	N/A	30	30
5010	N/A	34	34
5011	N/A	22	22
5012	N/A	42	42
5013	N/A	24	24
5014	N/A	30	30
5015	N/A	24	24
5016	N/A	32	32
5017	N/A	48	48
5018	N/A	N/A	46
5019	N/A	32	32
5020	N/A	46	46
5021	N/A	N/A	41
5022	N/A	N/A	66



(This Page Is Intentionally Blank)

Mar 04, 2020 - 5:15pm F:\MISC Projects\47361 - Portsmouth - Green & Co - Banfield Road\Design\Production Drawings\Pre-Post\_Drainage.dwg



LEGEND	
<span style="display:inline-block; width:20px; height:10px; background-color:yellow;"></span>	HYDROLOGIC SOIL GROUP A
<span style="display:inline-block; width:20px; height:10px; background-color:orange;"></span>	HYDROLOGIC SOIL GROUP B
<span style="display:inline-block; width:20px; height:10px; background-color:lightblue;"></span>	HYDROLOGIC SOIL GROUP C
<span style="display:inline-block; width:20px; height:10px; background-color:lightgreen;"></span>	HYDROLOGIC SOIL GROUP D


LEGEND	
	FLOW PATH (Tc LINE)
	REACH
	SOIL GROUP BREAK LINE
	EXISTING LOT LINE
	LIMITS OF SUBCATCHMENT
	PROPOSED SUBCATCHMENT NODE
	PROPOSED REACH
	PROPOSED POND AREA AND CULVERT NODE
	POINT OF INTEREST

SOIL LEGEND PER USDA NRCS WEB SOIL SURVEY		
NRCS SYMBOL	NRCS DESCRIPTION	HYDROLOGIC SOIL GROUP
38B	ELDRIDGE FINE SANDY LOAM, 8% SLOPES	C/D
140B	CHATFIELD-HOLLIS-CANTON COMPLEX, 0% - 8%	B
140C	CHATFIELD-HOLLIS-CANTON COMPLEX, 8% - 15%	B
538A	SQUAMSCOTT FINE SANDY LOAM, 0% - 5%	C/D

SOIL LEGEND PER SITE SPECIFIC SOIL SURVEY (SSS)		
SSS SYMBOL	SSS MAP NAME	HYDROLOGIC SOIL GROUP
41	CHATFIELD-HOLLIS-ROCK OUTCROP COMPLEX	B
135	CHATFIELD VARIANT-NEWFIELDS COMPLEX	C
538	SQUAMSCOTT FINE SANDY LOAM	C
656	RIDGEBURY FINE SANDY LOAM	C
SLOPE PHASE:		
0-8%	B	
8-15%	C	
15-25%	D	
25%+	E	

**SITE DEVELOPMENT PLANS**  
 TAX MAP 256 LOT 2  
**HYDROLOGIC SOIL GROUPS**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**  
 OWNED BY  
**WALTER D HETT TRUST**  
 PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**  
**1"=200' (11"X17")**  
**SCALE: 1"=100' (22"X34')** **SEPTEMBER 25, 2019**

Copyright 2019 © Thomas F. Moran, Inc.  
 48 Constitution Drive, Bedford, N.H. 03110  
 All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.  
 This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.




<b>TFM</b>	Civil Engineers	48 Constitution Drive
	Structural Engineers	Bedford, NH 03110
	Traffic Engineers	Phone (603) 472-4488
	Land Surveyors	Fax (603) 472-9747
	Landscape Architects	www.tfmoran.com
	Scientists	
FILE 47361.00	DR RCK FB	
OK JUM CADFILE	PRE-POST_DRAINAGE	D-06


Page 103 of 216

(This Page Is Intentionally Blank)

**APPENDIX K**  
**NHDES ONE STOP DATA MAPPER**

(This Page Is Intentionally Blank)

# Banfield Road - Portsmouth, NH



## Legend

- ☐ Coastal and Great Bay Regional Communities
- ☐ Designated Rivers Quarter Mile Buffer
- Public Water Supply Wells
- ☐ Groundwater Classification / GA1
- ☐ Groundwater Classification / GA2
- ☐ Water Supply Intake Protect Areas
- ☐ Wellhead Protection Areas
- ☐ Lakes with a Quarter Mile Buffer
- ☐ All Features
- ☐ All Lakes, with a Quarter Mile Buffer
- ☐ Outstanding Resource Water Watersheds
- ☐ Surface Waters with Impairment 2016 with Quarter Mile Buffer
- ☐ Watersheds with Chloride Impairments 2016
- ☐ Parcels - polygons


Map Scale  
 1: 5,000

© NH DES, <http://des.nh.gov>  
 Map Generated: 10/3/2019

Notes



(This Page Is Intentionally Blank)



## Description

Assessment Unit ID (AUID): NHRIV600031001-03

Assessment Unit Name: SAGAMORE CREEK

Beach (Y/N?): N

Impairments related to stormwater: Chloride, Escherichia coli

[Metadata](#)

## Details

- AUID  
NHRIV600031001-03 [NHRIV600031001-03](#) N/A
- FID  
387 [387](#) N/A
- Waterbodyi  
NHRIV600031001-03 [NHRIV600031001-03](#) N/A
- Waterbodyyn  
SAGAMORE CREEK [SAGAMORE CREEK](#) N/A
- Impairment  
Chloride, Escherichia coli




## Details

- FID  
8 [8](#) N/A
- OBJECTID\_1  
3282 [3282](#) N/A
- AUID  
NHRIV600031001-03 [NHRIV600031001-03](#) N/A
- Shape\_Leng  
17891.5112 [17891.5112](#) N/A
- QAQC  
Good [Good](#) N/A
- Method  
10m DEM, 24k NHHD Burned and Catchment Walled [10m DEM, 24k NHHD Burned and Catchment Walled](#) N/A
- Mod\_Date  
Apr 8, 2013 8:00 PM [Apr 8, 2013 8:00 PM](#) N/A
- CYCLE  
2014 [2014](#) N/A
- USE\_ID  
952 [952](#) N/A
- IMPAIRMENT  
138 [138](#) N/A
- IMPAIRMEN2  
Chloride [Chloride](#) N/A
- DESCATEGOR  
5-M

**APPENDIX L**  
**CURVE NUMBER MAP**

(This Page Is Intentionally Blank)



LEGEND		
	Cn FOR HSG	B C
	EXISTING WOODS	55 70
	POWERLINES	48 65
	WETLANDS	48 65
	LAWNS	61 74
	RESTORED BUFFER	58 72
	ROADS AND DRIVES	98 98
	ROOFS	98 98

LEGEND	
	FLOW PATH (Tc LINE)
	REACH
	SOIL GROUP BREAK LINE
	EXISTING LOT LINE
	LIMITS OF SUBCATCHMENT
	PROPOSED SUBCATCHMENT NODE
	PROPOSED REACH
	PROPOSED POND AREA AND CULVERT NODE
	POINT OF INTEREST

SOIL LEGEND PER USDA NRCS WEB SOIL SURVEY		
NRCS SYMBOL	NRCS DESCRIPTION	HYDROLOGIC SOIL GROUP
38B	ELDRIDGE FINE SANDY LOAM, 8% SLOPES	3% C/D
140B	CHATFIELD-HOLLIS-CANTON COMPLEX, 0% - 8%	B
140C	CHATFIELD-HOLLIS-CANTON COMPLEX, 8% - 15%	B
538A	SQUAMSCOTT FINE SANDY LOAM, 0% - 5%	C/D

SOIL LEGEND PER SITE SPECIFIC SOIL SURVEY (SSS)		
SSS SYMBOL	SSS MAP NAME	HYDROLOGIC SOIL GROUP
41	CHATFIELD-HOLLIS-ROCK OUTCROP COMPLEX	B
135	CHATFIELD VARIANT-NEWFIELDS COMPLEX	C
538	SQUAMSCOTT FINE SANDY LOAM	C
656	RIDGEBURY FINE SANDY LOAM	C
SLOPE PHASE:		
0-8%	B	
8-15%	C	
15-25%	D	
25%+	E	

**SITE DEVELOPMENT PLANS**  
 TAX MAP 256 LOT 2  
**CURVE NUMBER PLAN**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**  
 OWNED BY  
**WALTER D HETT TRUST**  
 PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**  
**1"=200' (11"X17")**  
**SCALE: 1"=100' (22"X34")**      **SEPTEMBER 25, 2019**

Copyright 2019 © Thomas F. Moran, Inc.  
 48 Constitution Drive, Bedford, N.H. 03110  
 All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.  
 This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.



FILE	47361.00	DR	RCK	FB				
OK		OK	JUM	CADFILE	PRE-POST_DRAINAGE			D-07

Civil Engineers  
 Structural Engineers  
 Traffic Engineers  
 Land Surveyors  
 Landscape Architects  
 Scientists  
 48 Constitution Drive  
 Bedford, NH 03110  
 Phone (603) 472-4488  
 Fax (603) 472-9747  
 www.tfmoran.com

Mar 04, 2020 - 6:50pm  
 F:\MISC Projects\47361 - Portsmouth\47361-00 - Green & Co - Banfield Road\Design\Production Drawings\Pre-Post\_Drainage.dwg

(This Page Is Intentionally Blank)

**APPENDIX M**  
**PRE AND POST DRAINAGE PLANS**

(This Page Is Intentionally Blank)



### LEGEND

- FLOW PATH (Tc LINE)
- REACH
- SOIL GROUP BREAK LINE
- EXISTING LOT LINE
- LIMITS OF SUBCATCHMENT
- ES4  
EXISTING SUBCATCHMENT NODE
- ER1  
EXISTING REACH
- EC1  
EXISTING POND AREA AND CULVERT NODE
- EPOi3  
POINT OF INTEREST

#### SOIL LEGEND PER USDA NRCS WEB SOIL SURVEY

NRCS SYMBOL	NRCS DESCRIPTION	HYDROLOGIC SOIL GROUP
38B	ELDRIDGE FINE SANDY LOAM, 8% SLOPES	C/D
140B	CHATFIELD-HOLLIS-CANTON COMPLEX, 0% - 8%	B
140C	CHATFIELD-HOLLIS-CANTON COMPLEX, 8% - 15%	B
538A	SQUAMSCOTT FINE SANDY LOAM, 0% - 5%	C/D

#### SOIL LEGEND PER SITE SPECIFIC SOIL SURVEY (SSS)


SSS SYMBOL	SSS MAP NAME	HYDROLOGIC SOIL GROUP
41	CHATFIELD-HOLLIS-ROCK OUTCROP COMPLEX	B
135	CHATFIELD VARIANT-NEWFIELDS COMPLEX	C
538	SQUAMSCOTT FINE SANDY LOAM	C
656	RIDGEBURY FINE SANDY LOAM	C
SLOPE PHASE:		
0-8%	B	
8-15%	C	
15-25%	D	
25%+	E	

## SITE DEVELOPMENT PLANS

TAX MAP 256 LOT 2  
**PRE-DRAINAGE PLAN OVERALL**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**  
 OWNED BY  
**WALTER D HETT TRUST**  
 PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**  
**1"=200' (11"X17")**  
**SCALE: 1"=100' (22"X34')** **SEPTEMBER 25, 2019**

Mar 05, 2020 - 10:56am F:\MISC Projects\47361 - Portsmouth\47361-00 - Green & Co - Banfield Road\Design\Production Drawings\Pre-Post\_Drainage.dwg

Copyright 2019 © Thomas F. Moran, Inc.  
 48 Constitution Drive, Bedford, N.H. 03110  
 All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.  
 This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.



FILE	47361.00	DR	RCK	FB
CHK	JJM	CADFILE	PRE-POST_DRAINAGE	D-01

Civil Engineers  
 Structural Engineers  
 Traffic Engineers  
 Land Surveyors  
 Landscape Architects  
 Scientists

48 Constitution Drive  
 Bedford, NH 03110  
 Phone (603) 472-4488  
 Fax (603) 472-9747  
 www.tfmoran.com



(This Page Is Intentionally Blank)



### LEGEND

- FLOW PATH (Tc LINE)
- REACH
- SOIL GROUP BREAK LINE
- EXISTING LOT LINE
- LIMITS OF SUBCATCHMENT
- ES4 PROPOSED SUBCATCHMENT NODE
- PR1 PROPOSED REACH
- EC1 PROPOSED POND AREA AND CULVERT NODE
- PPOi3 POINT OF INTEREST

#### SOIL LEGEND PER USDA NRCS WEB SOIL SURVEY

NRCS SYMBOL	NRCS DESCRIPTION	PERCENTAGE	HYDROLOGIC SOIL GROUP
38B	ELDRIDGE FINE SANDY LOAM, 8% SLOPES	3%	C/D
140B	CHATFIELD-HOLLIS-CANTON COMPLEX, 0% - 8%		B
140C	CHATFIELD-HOLLIS-CANTON COMPLEX, 8% - 15%		B
538A	SQUAMSCOTT FINE SANDY LOAM, 0% - 5%		C/D

#### SOIL LEGEND PER SITE SPECIFIC SOIL SURVEY (SSS)

SSS SYMBOL	SSS MAP NAME	HYDROLOGIC SOIL GROUP
41	CHATFIELD-HOLLIS-ROCK OUTCROP COMPLEX	B
135	CHATFIELD VARIANT-NEWFIELDS COMPLEX	C
538	SQUAMSCOTT FINE SANDY LOAM	C
656	RIDGEBURY FINE SANDY LOAM	C

SLOPE PHASE:	
0-8%	B
8-15%	C
15-25%	D
25%+	E


## SITE DEVELOPMENT PLANS

TAX MAP 256 LOT 2  
**POST-DRAINAGE PLAN OVERALL**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**

OWNED BY  
**WALTER D HETT TRUST**  
PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**  
**1"=200' (11"X17")**  
**SCALE: 1"=100' (22"X34")** **SEPTEMBER 25, 2019**

Mar 05, 2020 - 10:56am F:\MISC Projects\47361 - Portsmouth\47361-00 - Green & Co - Banfield Road\Design\Production Drawings\Pre-Post\_Drainage.dwg

Copyright 2019 © Thomas F. Moran, Inc.  
48 Constitution Drive, Bedford, N.H. 03110  
All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.  
This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.





<b>TFM</b>	Civil Engineers	48 Constitution Drive Bedford, NH 03110 Phone (603) 472-4488 Fax (603) 472-9747 www.tfmoran.com	
	Structural Engineers Traffic Engineers Land Surveyors Landscape Architects Scientists		
FILE 47361.00	DR RCK FB CK JIM CADFILE	PRE-POST_DRAINAGE	D-02

Page 200 of 216

(This Page Is Intentionally Blank)

Mar 05, 2020 - 10:56am F:\MISC Projects\47361 - Portsmouth\47361-00 - Banfield Road\Design\Production Drawings\Pre-Post\_Drainage.dwg



### LEGEND

- FLOW PATH (Tc LINE)
- REACH
- SOIL GROUP BREAK LINE
- EXISTING LOT LINE
- LIMITS OF SUBCATCHMENT
- PROPOSED SUBCATCHMENT NODE
- PROPOSED REACH
- PROPOSED POND AREA AND CULVERT NODE
- POINT OF INTEREST

#### SOIL LEGEND PER USDA NRCS WEB SOIL SURVEY

NRCS SYMBOL	NRCS DESCRIPTION	PERCENTAGE	HYDROLOGIC SOIL GROUP
38B	ELDRIDGE FINE SANDY LOAM, 8% SLOPES	3%	C/D
140B	CHATFIELD-HOLLIS-CANTON COMPLEX, 0% - 8%		B
140C	CHATFIELD-HOLLIS-CANTON COMPLEX, 8% - 15%		B
538A	SQUAMSCOTT FINE SANDY LOAM, 0% - 5%		C/D

#### SOIL LEGEND PER SITE SPECIFIC SOIL SURVEY (SSS)

SSS SYMBOL	SSS MAP NAME	HYDROLOGIC SOIL GROUP
41	CHATFIELD-HOLLIS-ROCK OUTCROP COMPLEX	B
135	CHATFIELD VARIANT-NEWFIELDS COMPLEX	C
538	SQUAMSCOTT FINE SANDY LOAM	C
656	RIDGEBURY FINE SANDY LOAM	C

SLOPE PHASE:	
0-8%	B
8-15%	C
15-25%	D
25%+	E

## SITE DEVELOPMENT PLANS


TAX MAP 256 LOT 2  
**POST DRAINAGE PLAN**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**

OWNED BY  
**WALTER D HETT TRUST**  
PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**  
**1"=60' (11"X17')**  
**SCALE: 1"=30' (22"X34')** **SEPTEMBER 25, 2019**

Copyright 2019 © Thomas F. Moran, Inc.  
48 Constitution Drive, Bedford, N.H. 03110

All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.

This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.



NO.	DATE	DESCRIPTION	BY	CHK
1	12/23/19	REVISED PER REGULATORY COMMENTS	RCK	JJM

Civil Engineers  
Structural Engineers  
Traffic Engineers  
Land Surveyors  
Landscape Architects  
Scientists


48 Constitution Drive  
Bedford, NH 03110  
Phone (603) 472-4488  
Fax (603) 472-9747  
www.tfmoran.com

47361.00	DR	RCK	FB	-	D-03
	CK	JJM	CADFILE	PRE-POST_DRAINAGE	

Page 211 of 216

(This Page Is Intentionally Blank)

Mar 05, 2020 - 10:57am F:\MISC Projects\47361 - Portsmouth\47361-00 - Banfield Road\Design\Production Drawings\Pre-Post\_Drainage.dwg



### LEGEND

- FLOW PATH (Tc LINE)
- REACH
- SOIL GROUP BREAK LINE
- EXISTING LOT LINE
- LIMITS OF SUBCATCHMENT
- PROPOSED SUBCATCHMENT NODE
- PROPOSED REACH
- PROPOSED POND AREA AND CULVERT NODE
- POINT OF INTEREST

#### SOIL LEGEND PER USDA NRCS WEB SOIL SURVEY

NRCS SYMBOL	NRCS DESCRIPTION	HYDROLOGIC SOIL GROUP
38B	ELDRIDGE FINE SANDY LOAM, - 8% SLOPES 3%	C/D
140B	CHATFIELD-HOLLIS-CANTON COMPLEX, 0% - 8%	B
140C	CHATFIELD-HOLLIS-CANTON COMPLEX, 8% - 15%	B
538A	SQUAMSCOTT FINE SANDY LOAM, 0% - 5%	C/D

#### SOIL LEGEND PER SITE SPECIFIC SOIL SURVEY (SSS):

SSS SYMBOL	SSS MAP NAME	HYDROLOGIC SOIL GROUP
41	CHATFIELD-HOLLIS-ROCK OUTCROP COMPLEX	B
135	CHATFIELD VARIANT-NEWFIELDS COMPLEX	C
538	SQUAMSCOTT FINE SANDY LOAM	C
656	RIDGEBURY FINE SANDY LOAM	C

SLOPE PHASE:		
0-8%	B	
8-15%	C	
15-25%	D	
25%+	E	

## SITE DEVELOPMENT PLANS


TAX MAP 256 LOT 2  
**POST DRAINAGE PLAN**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**

OWNED BY  
**WALTER D HETT TRUST**  
 PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**  
**1"=60' (11"X17')**  
**SCALE: 1"=30' (22"X34')** **SEPTEMBER 25, 2019**

Copyright 2019 © Thomas F. Moran, Inc.  
 48 Constitution Drive, Bedford, N.H. 03110

All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.

This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.



REV	DATE	DESCRIPTION	BY	CHK
1	12/23/19	REVISED PER REGULATORY COMMENTS	RCK	JUM


Civil Engineers  
Structural Engineers  
Traffic Engineers  
Land Surveyors  
Landscape Architects  
Scientists

48 Constitution Drive  
Bedford, NH 03110  
Phone (603) 472-4488  
Fax (603) 472-9747  
www.tfmoran.com

FILE # 47361.00	DR CK	RCK JUM	FB CADFILE	PRE-POST_DRAINAGE	D-04
-----------------	-------	---------	------------	-------------------	------

Page 213 of 216

(This Page Is Intentionally Blank)



### LEGEND

- FLOW PATH (Tc LINE)
- REACH
- SOIL GROUP BREAK LINE
- EXISTING LOT LINE
- LIMITS OF SUBCATCHMENT
- PROPOSED SUBCATCHMENT NODE
- PROPOSED REACH
- PROPOSED POND AREA AND CULVERT NODE
- POINT OF INTEREST

#### SOIL LEGEND PER USDA NRCS WEB SOIL SURVEY

NRCS SYMBOL	NRCS DESCRIPTION	HYDROLOGIC SOIL GROUP
38B	ELDRIDGE FINE SANDY LOAM, - 8% SLOPES	3% C/D
140B	CHATFIELD-HOLLIS-CANTON COMPLEX, 0% - 8%	B
140C	CHATFIELD-HOLLIS-CANTON COMPLEX, 8% - 15%	B
538A	SQUAMSCOTT FINE SANDY LOAM, 0% - 5%	C/D

#### SOIL LEGEND PER SITE SPECIFIC SOIL SURVEY (SSS)

SSS SYMBOL	SSS MAP NAME	HYDROLOGIC SOIL GROUP
41	CHATFIELD-HOLLIS-ROCK OUTCROP COMPLEX	B
135	CHATFIELD VARIANT-NEWFIELDS COMPLEX	C
538	SQUAMSCOTT FINE SANDY LOAM	C
656	RIDGEBURY FINE SANDY LOAM	C

SLOPE PHASE:	
0-8%	B
8-15%	C
15-25%	D
25%+	E

## SITE DEVELOPMENT PLANS

TAX MAP 256 LOT 2  
**POST DRAINAGE PLAN**  
**THE VILLAGE AT BANFIELD WOODS**  
**PORTSMOUTH, NH**


OWNED BY  
**WALTER D HETT TRUST**  
 PREPARED FOR  
**GREEN & COMPANY REAL ESTATE**  
**1"=60' (11"X17')**  
**SCALE: 1"=30' (22"X34')** **SEPTEMBER 25, 2019**

Mar 05, 2020 - 10:57am F:\MISC Projects\47361 - Portsmouth\47361-00 - Banfield Road\Design\Production Drawings\Pre-Post\_Drainage.dwg

Copyright 2019 © Thomas F. Moran, Inc.  
 48 Constitution Drive, Bedford, N.H. 03110

All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.

This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.



1	12/23/19	REVISED PER REGULATORY COMMENTS	RCK	JUM					

Civil Engineers  
Structural Engineers  
Traffic Engineers  
Land Surveyors  
Landscape Architects  
Scientists

48 Constitution Drive  
Bedford, NH 03110  
Phone (603) 472-4488  
Fax (603) 472-9747  
www.tfmoran.com

FILE: 47361.00

DR: RCK  
CK: JUM

FB: -  
CADFILE: PRE-POST\_DRAINAGE

D-05



(This Page Is Intentionally Blank)