

C0960-006
January 27, 2021

Ms. Barbara McMillan, Chair
City of Portsmouth Conservation Commission
1 Junkins Avenue
Portsmouth, New Hampshire 03801

**Re: Wetland Conditional Use Permit Application
Proposed Multi-Family Development, 105 Bartlett Street, Portsmouth, NH**

Dear Chair McMillan:

On behalf of Iron Horse Properties, LLC, we are pleased to submit eleven (11) sets of hard copies and one (1) set of digital copies (.pdf) of the following supplemental information to support a request for a Wetland Conditional Use Permit for the above referenced project:

- Site Plan Set (full size) last revised January 20, 2021
- Drainage Analysis last revised January 20, 2021
- Constraints Exhibit last revised January 20, 2021
- Public Open Space Exhibit dated January 20, 2021
- Buffer Impact Exhibit last revised January 20, 2021
- Site Plan Comparison Exhibit dated January 27, 2021
- Wetland Delineation and Functions & Values Report last revised January 27, 2021
- Photograph Log of Existing Buffer Vegetation & Invasive Species dated January 19, 2021
- Environmental Summary Memorandum dated November 4, 2020
- Grade Plane Exhibit last revised January 20, 2021
- Fire Truck Turning Exhibit last revised January 20, 2021
- Trip Generation Memorandum last revised December 23, 2020

The applicant is pleased to provide the enclosed supplemental information which has been prepared in response to comments and feedback received over the past 16 months from the Planning Board, Technical Advisory Committee (TAC), Conservation Commission and public comment during local land-use permitting process. Most recently the applicant met with the Conservation Commission on November 4, 2020 for a regular meeting and December 7, 2020 for a site walk and the enclosed includes responses to comments received at those meetings.

PROJECT SUMMARY

To recap the project and describe additional improvements made to the enclosed information, the following narrative is provided:

Existing Conditions

The project is located at 105 Bartlett Street consisting of properties identified as Map 157 Lots 1 & 2, Map 164 Lots 1 & 4-2, and a private roadway lot. The properties are bound by Bartlett Street, the railroad and the North Mill Pond. The properties include 2,000+/- linear feet of tidal wetlands and buffers along the North Mill Pond. The limited functions and values of these areas are described in the enclosed Wetland Delineation Assessment and Functions and Values Report and the existing vegetation and invasive species of these areas are located in the enclosed Photograph Log.



The urban site has history of railroad and industrial use. The front portions of the site closest to Bartlett Street currently include the Ricci Supply buildings with paved parking areas and a private roadway that extend up the top of bank along the North Mill Pond. The stormwater for these paved areas either sheet flow directly into the North Mill Pond with no treatment or is collected in an old combined sewer overflow (CSO) system contributing burden to the City's sewer collection and treatment systems during rainfall events.

The rear portion of the site, which includes the proposed development area, consists of an industrial building converted to a brewery & dog daycare and a vacant machine shop with paving, compacted gravel and building areas that are located in close proximity to the top of the North Mill Pond bank. The rear of the site also includes derelict railroad structures that pose a safety hazard. The 100-foot tidal wetland buffer is almost entirely previously disturbed urban upland which has been neglected, fallen into disrepair, and overgrown with invasive species. The existing condition in the rear of the site has long been an attractive nuisance with a history of debris, homeless encampments, and crime.

The properties in question include a significant portion of the City of Portsmouth's long planned improvements to the shoreline of the North Mill Pond, the concept of which has been a focus of the City's planning for years. It was included in the Portsmouth Bicycle and Pedestrian Plan in 2014 and the North End Vision Plan in 2015. Many of the stated goals set forth in the City's Master Plan in 2016 called for its creation. The Final Report on the North Mill Pond Greenway and Community Park was issued in 2019.

The Final Plan calls for "a linear greenway and community park along the North Mill Pond which will create a new north-south pedestrian and bicycle connection from Bartlett Street to Market Street. This multi-use public path with civic amenities in envisioned to be constructed along the southeast shoreline of the pond, will include wetland restoration and pond edge stabilization and is anticipated and constructed through a series of public-private partnerships with private landowners."

The City's Zoning Ordinance was amended in 2016 to create an overlay district specifically allowing the construction of taller buildings in the area as incentive for real estate developers to join in these important public private partnerships.

Proposed Redevelopment

Amended Subdivision

In 2018, a proposed subdivision was granted for the subject parcels and included a private road lot with cul-de-sac. The proposed project will modify the prior approved lot lines by relocating the cul-de-sac closer to Bartlett Street in a location that is currently an existing parking area for the brewery/dog daycare building. The amended subdivision will result in a 4.72-acre property where the existing brewery/dog day care building and vacant machine shop currently are located. This 4.72-acre property will be the location of the proposed multi-family redevelopment and, along the shore of North Mill Pond, will be the construction of the long planned public bicycle and pedestrian path as well as valuable new accessible open space along the water's edge.

Commercial Area

The front portion of the site will continue to be an existing commercial area that consists of the Ricci Supply buildings with associated parking improvements and a private road. This portion of the site will be improved by pulling the private road further away from the top of North Mill Pond bank, implementing traffic and pedestrian improvements to the private road and adding landscape areas to reduce impervious surface. In addition, new stormwater management improvements will be constructed on this portion of the site. New stormwater collection systems will include deep sump catch basins with oil separator hoods and



stormwater treatment units. The new systems will eliminate the existing CSO which has long been an initiative of the Department of Public Works across the City and will provide stormwater treatment where none is provided in the existing condition.

Multi-family Development Area

The proposed development area consists of three (3) multi-family apartment buildings depicted as Building A, B and C on the Site Plan. The three (3) buildings will include a total of 152 dwelling units with basement level parking below Building A and B. The project includes associated site improvements that consist of the private road cul-de-sac adjacent to Building C, surface parking, pedestrian access, utilities, lighting, landscaping and stormwater management systems that provide treatment for runoff.

The proposed development area has unique site conditions that include close proximity to the North Mill Pond; no build view corridors required by zoning that extend from perpendicular City streets located across the railroad; 15-foot side yard setback due to the adjacent railroad where none is typically required in the CD-4W district; and a 25-foot municipal sewer easement for a large sewer pipe that conveys wastewater flow for the City's west end to the Deer Street pump station. These unique conditions put constraints on the applicant's ability to locate buildings within the developable upland area. As shown in the enclosed Constraints Exhibit, the applicant has located the three (3) proposed buildings within the site constraints. The buildings are located in a manner that still pulls the building footprints further back from existing condition, locates surface parking away from the pond along the railroad and creates expansive public open space in an urban setting along the North Mill Pond.

The existing condition of the development property does not provide any stormwater treatment. The proposed development will provide stormwater management improvements which are described in further detail in the enclosed Drainage Analysis. The following is a summary:

- Proposed treatment to runoff from the new buildings and surface parking will be provided via stormwater treatment units. In addition, an underground detention system has been incorporated into the design to address concerns raised by the Conservation Commission regarding temperature of the runoff from the surface parking area. The underground detention system will detain and slowly release runoff for a 24-hour draw down time in order regulate temperature of runoff before discharging it to the North Mill Pond. An additional benefit of the underground detention system is that it will also reduce peak rates of runoff to the North Mill Pond even though peak rate reduction is not required for direct discharges to tidal waters.
- Stormwater treatment measures have been implemented in the rear of the buildings where the public park and trail will be located. Yard drains in the open space between building B & C and along portions of the trail will capture runoff and put them thru a treatment unit. Runoff from the public park area had been designed to flow to a rain garden. The rain garden will not only serve as stormwater treatment but also will be planted as an aesthetically pleasing central feature in the public park and will provide pollinator habitat.
- The Conservation Commission and City staff have repeatedly requested the use of porous asphalt for the path in the rear of the building. An "Optional" porous asphalt design has been incorporated into the stormwater design and is further described under the Conditional Use Section below.

Open Space & Buffer Enhancement

The project is located in the West End incentive district. The applicant will be providing 47,703 SF of Greenway Community Space which will be located from the North Mill Pond mean high

water line to the 50-foot wetland buffer setback. Providing this community space will contribute towards the City realizing a goal of the Master Plan to create public access along the North Mill pond with a multi-use trail. This Greenway Community Space is 23.2% of the development parcel, exceeding the 20% required by the Zoning Ordinance. In addition to the community space, the applicant is also proposing a 23,552 SF public park adjacent the Greenway Community Space. The total public open space the project will create is 71,255 SF which is 35% of the development parcel area as shown in the enclosed Public Open Space Exhibit. Overall, the project will be providing 58.1% open space on the development lot where only 15% is required by zoning.

The project is providing buffer enhancement with the removal of invasive species and proposed plantings. The 100-foot tidal buffer zone currently consists of the existing buildings, paved roadway and parking areas, large compacted gravel areas, two small second growth wooded areas, and a 25-foot vegetated buffer zone. Much of the existing vegetation on the site consists of invasive species including Norway Maples, Buckthorn, Autumn Olive, Multiflora Rose and some Bittersweet. With the exception of the Norway Maples, which provide valuable canopy cover and screening, invasive species in the areas of construction and within the 25-foot vegetated buffer will be removed. Disturbed areas will be planted with either a native fescue grass mix (Areas shown as lawn on the Landscape Plan) or a New England Wildlife Conservation Seed Mix (Areas within the 25-foot vegetated buffer). The proposed development area will be planted with a mixed buffer of native trees, and drifts of a mix of native and ornamental (not native) shrubs and groundcovers. The majority of the proposed buffer plantings that are within the 100-foot buffer are native. In addition, a centrally located rain garden provides additional pollinator habitat with 90% of its plantings being native.

The project will provide an overall improvement in the 100-foot tidal wetland buffer by pulling parking and building further away from the North Mill Pond and by reducing overall impervious surface as summarized in Table 1 below. In addition to the summary in Table 1 below, detailed calculations of buffer impacts for the existing and proposed condition are depicted in the enclosed Buffer Impact Exhibit by both individual lot and overall project.

Table 1 - 100-Foot Tidal Buffer Impacts

Overall Buffer Impact Area		
Wetland Buffer Setback	Existing Impact	Proposed Impact
0 - 25 FT	12,788 SF	6,788 SF
25 - 50 FT	30,479 SF	22,089 SF
50 - 100 FT	66,844 SF	52,443 SF
Total Impact	110,111 SF	81,320 SF
NET BUFFER IMPROVEMENT		28,792 SF

Section 10.1017.24 of the Zoning Ordinance which indicates "Where feasible, the application shall include removal of impervious surfaces at least equal in area to the area of impervious surface impact. The intent of this provision is that the project will not result in a net loss of pervious surface within a jurisdictional wetland buffer." As shown in Table 1, the proposed project far exceeds this requirement by providing a 0.66-acre reduction in impervious surface.



Conditional Use Permit

Permitting Timeline

At the next regularly scheduled meeting in February 2020, the applicant is seeking a recommendation for approval from the Conservation Commission to the Planning Board for a Wetland Conditional Use Permit. At that time, the applicant will have met with the Conservation Commission on five (5) separate occasions:

1. September 11, 2019 – Work Session
2. May 13, 2020 – Regular Meeting
3. November 4, 2020 – Regular Meeting
4. December 7, 2020 – Site Walk
5. February 10, 2020 - Regular Meeting (seeking recommendation for approval)

Through the course of the land use permitting process, the applicant has continued to be responsive to comments regarding buffer impact and concerns with density. The applicant has submitted five (5) versions of the Site Plan to the Conservation Commission for review from the Conceptual Site Plan reviewed at the September 2019 Work Session up through the enclosed submission package. The following summarizes the different iterations of the Site Plan as it relates to improvement in the buffer and reduction in density.

Table 2 – Overall Project Buffer Impact Reduction

Submission Date	Existing Condition Buffer Impact (SF)	Overall Project Buffer Impact (SF)	Net Buffer Impact (SF)	Density (# of dwelling units)
09/11/2019	119,808	146,157	26,349	272
04/29/2020	110,110	95,121	(14,989)	174
05/27/2020	110,110	97,739	(12,371)	174
10/28/2020	110,110	89,170	(20,940)	170
01/27/2021	110,110	81,319	(28,792)	152

As depicted in Table 2, the applicant has continued to make a good faith effort to be responsive to comments from the Conservation Commission and public by conceding allowed density and further improving buffer impact for the overall project that far exceeds the net zero requirements of Section 10.1017.24.

Response to Comments

The following is a summary of further improvements in the enclosed materials since the Conservation Commission regular meeting on November 4, 2020 meeting and site walk on December 7, 2020.

- Reduced density from 170 dwelling units to 152 dwelling units.

- Eliminated the two (2) story portion of Building A from the CD4-L1 district, further reducing buffer impact. In doing so, a view corridor for Salem Street has essentially been created, though not required by zoning.
- Revised the shape and reduced the footprint for Building C. The prior footprint mirrored the existing brewery/dog daycare building. This revision eliminates footprint in the buffer and creates an open space courtyard between Building B and C.
- Reduced surface parking from 103 to 95 spaces. This further reduces buffer impact and avoids disturbance to the wooded area located in the vicinity of the Cabot Street view corridor.
- Re-aligned the path around the building by pulling it away from the North Mill Pond and into public park further reducing buffer impact. The path has been designed in a manner that minimizes asphalt to the extent feasible while still addressing fire department comments to provide safe emergency access.
- Identified locations and types of invasive species in the plan set and incorporated bank stabilization measures where disturbance will occur for the invasive species removal and construction of the stormwater outfalls.
- An “optional” porous asphalt design has been incorporated into the stormwater design for the path around the building. As previously stated, the applicant’s team does not think porous asphalt is needed in this location given the implementation of treatment measures already incorporated into the design that provide higher removal efficiencies. The applicant’s team has also previously stated that it doesn’t believe this treatment practice is the most appropriate for this location given the high ground water table and restrictive soil layers below urban fill. The implementation of this practice will also create unneeded operation and maintenance over the life of the path particularly given the other stormwater practices already will achieve higher removal efficiencies when maintained properly. That all being said, the applicant has incorporated an “optional” porous pavement detail into the Site Plan package for the path along the rear of the buildings in response to the repeated requests for porous asphalt. The applicant will defer to City staff and the land-use boards to determine if the path should be porous asphalt.
- An updated Trip Generation Memorandum prepared by Pernaw, Inc. dated December 23, 2020 was submitted to the City for peer review for the latest 152-unit program. The memorandum included a comparison of the trip generation for the program included in the 2018 Subdivision Approval and the current Site Plan. The memorandum demonstrates that the current development proposal will generate approximately -39 (AM) and -52 (PM) fewer vehicle-trips during the peak hour periods than the program studied as part of the 2018 Subdivision Approval. The City’s peer reviewer concurred with these results in a January 12, 2021 peer review letter and City staff has noted they have no further comments.

Conditional Use Permit Criteria

Based on the above described and enclosed materials, the following addresses how the proposed project warrants the granting of a Wetland Conditional Use Permit by satisfying the following six (6) criteria for approval in Section 10.1017.50 of the Zoning Ordinance:

(1) The land is reasonably suited to the use, activity or alteration.

The subject properties are within the CD4-W and CD4-L1 Zoning Districts (Character Districts). The proposed development parcel meets the requirements of the Zoning Ordinance and does not require any relief. The urban site is largely previously disturbed in the 100-foot tidal wetland buffer. The existing condition of the development includes large amounts of debris, a great deal of invasive species and derelict structures that pose

a safety hazard. This area of the site has long been an attractive nuisance with a history of homeless encampments and crime. The proposed project will result in impervious surface reduction in the buffer, buffer enhancement, and will provide public access along North Mill Pond which is a goal of the City's Master Plan.

(2) *There is no alternative location outside the wetland buffer that is feasible and reasonable for the proposed use, activity or alteration.*

The proposed development area has unique site conditions that include close proximity to the North Mill Pond; no build view corridors required by zoning that extend from perpendicular City streets located across the railroad; 15-foot side yard setback due to the adjacent railroad where none is required in the CD-4W district; and a 25-foot municipal sewer easement for large sewer pipe that conveys wastewater flow for the City's west end to the Deer Street pump station. These unique conditions put constraints on the applicant's ability to locate buildings within the developable upland area. The redevelopment is located within a feasible and reasonable manner that pulls the building footprints further back from existing condition, locates surface parking away from the pond along the railroad and creates expansive public open space in an urban setting along the North Mill Pond. As described in the Comment Response section above, the applicant has made even further effort to reduce buffer impact and density since the last meeting with the Conservation Commission.

(3) *There will be no adverse impact on the wetland functional values of the site or surrounding properties.*

There will be no adverse impact to surrounding properties as this property has long been an urban site with a history of railroad, industrial and commercial uses. The project has been designed in a manner that conforms with the requirements of the Zoning Ordinance. The project will reduce traffic from the original 2018 Subdivision approval. The project will provide public access to the North Mill Pond for the surrounding properties where none currently exists which is a goal of the City's Master Plan.

There will be no adverse impact on the wetland functional values of the site as the existing condition is largely previously disturbed upland riddled with debris and derelict structures that pose a safety hazard. The existing condition includes impervious surfaces near or at the top of North Mill Pond bank throughout much of the 100-foot tidal buffer. The proposed project will reduce buffer impact, remove invasive species in the 25-foot buffer and construction areas, and provide added value by creating public open space for recreation along the North Mill Pond.

(4) *Alteration of the natural vegetative state or managed woodland will occur only to the extent necessary to achieve construction goals.*

The proposed project is only altering the natural vegetated state to the extent necessary. The project will be removing invasive species in the locations of construction and in the 25-foot vegetated except for the Norway Maple, which provide valuable canopy cover and screening. As described above, the enclosed supplemental information identifies the location of these invasive species and includes stabilization practices for their removal and for the construction of the stormwater outfalls.

(5) *The proposal is the alternative with the least adverse impact to areas and environments under the jurisdiction of this Section.*

The applicant has continuously worked to reduce 100-foot tidal wetland buffer impacts in response to feedback received throughout the permitting process. The project will reduce buffer impact by conceding allowed density and by pulling footprints away from the North Mill Pond to the extent feasible given the site constraints. The project includes

underground parking and creates 1.63-acres of public open space area along the North Mill Pond which contribute toward a 0.66-acre net reduction in impervious surface within the buffer. Also, the applicant has conducted environmental studies on the property which are summarized in the enclosed Environmental Summary Memorandum previously submitted to and reviewed with the Conservation Commission. The applicant will remediate all identified recognized environmental conditions in accordance with applicable law.

(6) Any area within the vegetated buffer strip will be returned to a natural state to the extent feasible.

The project is providing buffer enhancement with the removal of invasive species and installation of plantings around the buildings and within the 100-foot tidal wetland buffer. The only other disturbance within the 0ft to 25ft buffer setback is for the construction of the three (3) stormwater outfalls. These outfalls will discharge treated stormwater to the North Mill Pond where none currently exists. Stabilization practices have been included in the enclosed plans for of removal invasive species and construction of the outfalls.

Conclusion

We trust the above described and enclosed materials address the criteria to grant a Wetland Conditional Use Permit for the proposed project. The proposed project meets requirements of the Zoning Ordinance. The proposed project achieves the goals of City's Master Plan to provide public access along the North Mill Pond with a Greenway Community Space and to provide buffer enhancement. In addition, the proposed buildings have been located in a manner within the unique site constraints to provide additional public benefit with an urban public park located along the Community Space Greenway in the rear of Building A and B.

In the past 16 months, the applicant has in good faith, continued to respond to feedback from the community and local land-use boards. As shown in the enclosed information, the latest proposal will further reduce density, further reduce buffer area impacts, improve stormwater management, enhance the North Mill Pond tidal wetland buffer and provide public benefit in the form of open space along the North Mill Pond. Based on this, the applicant respectfully requests a recommendation for approval to the Planning Board at the February 10, 2020 Conservation Commission regular meeting.

We respectfully request to be placed on the Conservation Committee regular meeting agenda for February 10, 2020. If you have any questions or need any additional information, please contact Patrick Crimmins by phone at (603) 988-8066 or by email at pmcrimmins@tighebond.com.

Sincerely,
TIGHE & BOND, INC.



Patrick M. Crimmins, PE
Senior Project Manager

Enclosures

Copy: Clipper Traders, LLC (via E-mail)
Iron Horse Properties, LLC (via E-mail)
Portsmouth Lumber & Hardware, LLC (via E-mail)



PROPOSED MULTI-FAMILY DEVELOPMENT

105 BARTLETT STREET
PORTSMOUTH, NEW HAMPSHIRE

JANUARY 2, 2020

LAST REVISED: JANUARY 20, 2021

LIST OF DRAWINGS		
SHEET NO.	SHEET TITLE	LAST REVISED
	COVER SHEET	01/20/2021
1 OF 5	LOT LINE RELOCATION PLAN	01/19/2021
2 OF 5	LOT LINE RELOCATION PLAN	01/19/2021
3 OF 5	LOT LINE RELOCATION PLAN	01/19/2021
4 OF 5	LOT LINE RELOCATION PLAN	01/19/2021
5 OF 5	LOT LINE RELOCATION PLAN	01/19/2021
C-101	OVERALL EXISTING CONDITIONS AND DEMOLITION PLAN	01/20/2021
C-101.1	EXISTING CONDITIONS AND DEMOLITION PLAN	01/20/2021
C-101.2	EXISTING CONDITIONS AND DEMOLITION PLAN	01/20/2021
C-102	OVERALL SITE PLAN	01/20/2021
C-102.1	SITE PLAN	01/20/2021
C-102.2	SITE PLAN	01/20/2021
C-102.3	BASEMENT LEVEL SITE PLAN	01/20/2021
C-103.1	GRADING, DRAINAGE, AND EROSION CONTROL PLAN	01/20/2021
C-103.2	GRADING, DRAINAGE, AND EROSION CONTROL PLAN	01/20/2021
C-104.1	UTILITIES PLAN	01/20/2021
C-104.2	UTILITIES PLAN	01/20/2021
C-105	PHOTOMETRIC PLAN	01/20/2021
C-201.1	ROADWAY PLAN & PROFILE	01/20/2021
C-201.2	ROADWAY PLAN & PROFILE	01/20/2021
C-301.1	UTILITY EASEMENT PLAN	01/20/2021
C-301.2	UTILITY EASEMENT PLAN	01/20/2021
C-302	ACCESS EASEMENT PLAN	01/20/2021
C-501	EROSION CONTROL NOTES AND DETAILS SHEET	01/20/2021
C-502	DETAILS SHEET	01/20/2021
C-503	DETAILS SHEET	01/20/2021
C-504	DETAILS SHEET	01/20/2021
C-505	DETAILS SHEET	01/20/2021
C-506	DETAILS SHEET	01/20/2021
C-507	DETAILS SHEET	01/20/2021
C-508	DETAILS SHEET	01/20/2021
C-509	DETAILS SHEET	01/20/2021
L-1	SITE LANDSCAPE PLAN	01/20/2021
L-2	FOUNDATION PLANTING PLAN	01/20/2021
1 OF 3	BUILDING ELEVATION PLAN	01/19/2021
2 OF 3	BUILDING ELEVATION PLAN	01/19/2021
3 OF 3	BUILDING ELEVATION PLAN	01/19/2021



LOCATION MAP
SCALE: 1" = 2000'

PREPARED BY:

Tighe & Bond

177 CORPORATE DRIVE
PORTSMOUTH, NEW HAMPSHIRE 03801
603-433-8818

APPLICANT:

IRON HORSE PROPERTIES, LLC
105 BARTLETT STREET
PORTSMOUTH, NEW HAMPSHIRE 03801

OWNERS:

TAX MAP 157, LOT 1
CLIPPER TRADERS, LLC
105 BARTLETT STREET
PORTSMOUTH, NEW HAMPSHIRE 03801

TAX MAP 164, LOT 4-2
IRON HORSE PROPERTIES, LLC
105 BARTLETT STREET
PORTSMOUTH, NH 03801

TAX MAP 157 LOT 2
TAX MAP 164, LOT 1
PORTSMOUTH HARDWARE & LUMBER, LLC
105 BARTLETT STREET
PORTSMOUTH, NH 03801


SURVEYOR:

AMBIT ENGINEERING, INC.
200 GRIFFIN ROAD - UNIT 3
PORTSMOUTH, NEW HAMPSHIRE 03801

LIST OF PERMITS		
LOCAL	STATUS	DATE
SITE PLAN REVIEW PERMIT	PENDING	
LOT LINE REVISION PERMIT	PENDING	
CONDITIONAL USE PERMIT - SHARED PARKING	PENDING	
CONDITIONAL USE PERMIT - WETLAND BUFFER	PENDING	
STATE		
NHDES - ALTERATION OF TERRAIN PERMIT	PENDING	
NHDES - WETLAND PERMIT	PENDING	
NHDES - SHORELAND PERMIT	PENDING	
NHDES - SEWER CONNECTION PERMIT	PENDING	
FEDERAL		
EPA - NPDES CGP	PENDING	



**TAC RESUBMISSION
COMPLETE SET 37 SHEETS**



AMBIT ENGINEERING, INC.

Civil Engineers & Land Surveyors

200 Griffin Road - Unit 3
Portsmouth, N.H. 03801-7114
Tel (603) 430-9282
Fax (603) 436-2315

NOTES:

1) PARCELS ARE SHOWN ON THE CITY OF PORTSMOUTH ASSESSOR'S MAP 157 LOTS 1 & 2, MAP 164 AS LOTS 1 & 4-2, AND A RIGHT-OF-WAY WITH NO ASSESSOR'S MAP DESIGNATION.

2) OWNERS OF RECORD:
MAP 157 LOT 1
CLIPPER TRADERS, LLC
105 BARTLETT STREET
PORTSMOUTH, NH 03801
5598/2725 & 5970/1701

MAP 157 LOT 2 & MAP 164 LOT 1
PORTSMOUTH LUMBER & HARDWARE, LLC
105 BARTLETT STREET
PORTSMOUTH, NH 03801
5372/2606, 5808/1379, 5540/2567, & 5970/1693

MAP 164 LOT 4-2
IRON HORSE PROPERTIES, LLC
105 BARTLETT STREET
PORTSMOUTH, NH 03801
5970/1686 & 6012/2502

RIGHT-OF-WAY
CLIPPER TRADERS, LLC, PORTSMOUTH LUMBER & HARDWARE, LLC, & IRON HORSE PROPERTIES, LLC
5970/1708

3) PORTIONS OF THE SUBJECT PARCELS ARE IN A SPECIAL FLOOD HAZARD AREA ZONE AE (EL.9) AS SHOWN ON FIRM PANEL 33015C0259E. EFFECTIVE DATE MAY 17, 2005.

4) PARCELS ARE LOCATED IN CHARACTER DISTRICT 4W (CD4-W), CHARACTER DISTRICT 4-L1 (CD4-L1), AND OFFICE RESEARCH (OR) ZONING DISTRICTS.

5) THE PURPOSE OF THIS PLAN IS TO SHOW A LOT LINE RELOCATION BETWEEN THE SUBJECT PARCELS IN THE CITY OF PORTSMOUTH.

6) VERTICAL DATUM IS MEAN SEA LEVEL NAVD88. BASIS OF VERTICAL DATUM IS REDUNDANT RTN GPS OBSERVATIONS (±0.3").

7) HORIZONTAL DATUM AND BASIS OF BEARINGS IS THE NH STATE PLANE COORDINATE SYSTEM NAD 83 (2011). BASIS OF HORIZONTAL DATUM IS REDUNDANT RTN GPS OBSERVATIONS.

NO.	DESCRIPTION	DATE
1	REVISE PROPOSED LOT LINE	1/19/21
0	ISSUED FOR COMMENT	6/22/20
REVISIONS		

**LOT LINE RELOCATION PLAN
TAX MAP 157 - LOTS 1 & 2
TAX MAP 164 - LOTS 1 & 4-2**

TAX MAP 157 LOT 1:
CLIPPER TRADERS, LLC
OWNER OF RECORD



TAX MAP 157 LOT 2 & TAX MAP 164 LOT 1:
PORTSMOUTH LUMBER & HARDWARE, LLC
OWNER OF RECORD

TAX MAP 164 LOT 4-2:
IRON HORSE PROPERTIES, LLC
OWNER OF RECORD

RIGHT-OF-WAY (NO TAX MAP DESIGNATION):
**IRON HORSE PROPERTIES, LLC,
PORTSMOUTH LUMBER & HARDWARE, LLC,
& CLIPPER TRADERS, LLC**

PROPERTY LOCATED BETWEEN:
**BARTLETT STREET & MAPLEWOOD AVENUE
CITY OF PORTSMOUTH
COUNTY OF ROCKINGHAM
STATE OF NEW HAMPSHIRE**

SCALE AS NOTED SHEET 1 OF 5 JUNE 2020



EXISTING & PROPOSED LOT AREAS:

MAP 157 LOT 1
EXISTING 61,781± S.F.
1.4183± ACRES
PROPOSED 205,804± S.F.
4.7246± ACRES

MAP 157 LOT 2
EXISTING 102,003 S.F.
2.3417 ACRES
PROPOSED 81,645 S.F.
1.8743 ACRES

MAP 164 LOT 1
EXISTING 51,952 S.F.
1.1927 ACRES
PROPOSED 52,289 S.F.
1.2004 ACRES

MAP 164 LOT 4-2
EXISTING 249,771± S.F.
5.7340± ACRES
PROPOSED 119,519± S.F.
2.7454± ACRES

RIGHT-OF-WAY
EXISTING 69,624± S.F.
1.5980± ACRES
PROPOSED 75,792± S.F.
1.7399± ACRES

ZONING DISTRICT DIMENSIONAL REQUIREMENTS:

OFFICE RESEARCH (OR)*:
*PARCELS ARE SUBJECT TO EXCEPTIONS TO DIMENSIONAL STANDARDS AS OUTLINED IN CITY OF PORTSMOUTH ZONING ORDINANCE SECTION 10.532.10 & 10.532.20, MODIFIED DIMENSIONS LISTED BELOW

MIN. LOT AREA: 2 ACRES
FRONTAGE: 200 FEET
SETBACKS: FRONT 70 FEET, SIDE 50 FEET, REAR 50 FEET
MAXIMUM STRUCTURE HEIGHT: 70 FEET
(45 FEET WITHIN 200 FEET OF NORTH MILL POND)
MAXIMUM STRUCTURE COVERAGE: 50%
MINIMUM OPEN SPACE: 20%

CHARACTER DISTRICT CD4-L1:
MIN. LOT AREA: 3,000 S.F.
FRONTAGE: NO REQUIREMENT
SETBACKS: FRONT (MAX.) 15 FEET (PRIMARY), FRONT (MAX.) 12 FEET (SECONDARY), SIDE 5-20 FEET, REAR 5 FEET
MAXIMUM STRUCTURE HEIGHT: 20-30 FEET
MAXIMUM STRUCTURE COVERAGE: 60%
MAXIMUM BUILDING FOOTPRINT: 2,500-3,500 S.F.
MINIMUM OPEN SPACE: 25%
MAXIMUM BLOCK LENGTH: 80-100 FEET
BUILDING SEPARATION: 15-30 FEET
VIEW CORRIDORS: SEE ZONING ORDINANCE

CHARACTER DISTRICT CD4-W:
MIN. LOT AREA: 5,000 S.F.
FRONTAGE: NO REQUIREMENT
SETBACKS: FRONT (MAX.) 10 FEET (PRIMARY), FRONT (MAX.) 15 FEET (SECONDARY), SIDE NO REQUIREMENT, REAR 5 FEET
MAXIMUM STRUCTURE HEIGHT: 45 FEET
MAXIMUM STRUCTURE COVERAGE: 60%
MAXIMUM BUILDING FOOTPRINT: 15,000-20,000 S.F.
MINIMUM OPEN SPACE: 15%
MINIMUM FRONT LOT LINE BUILDOUT: 50%

TRANSPORTATION CORRIDOR (TC):
NO DIMENSIONAL OR USE REQUIREMENTS DEFINED IN ORDINANCE


PLAN REFERENCES:

- 1) LAND IN PORTSMOUTH, N.H. BOSTON AND MAINE RAILROAD TO ERMINIO A.RICCI, SCALE : 1" = 40', APRIL 1960 RCRD 1595/091.
- 2) LAND IN PORTSMOUTH, N.H. BOSTON AND MAINE RAILROAD TO ERMINIO A.RICCI, SCALE : 1" = 40', MAY 1957 RCRD 02612.
- 3) EASEMENT OF LAND IN PORTSMOUTH, N.H. BOSTON AND MAINE RAILROAD TO UNITED STATES OF AMERICA, SCALE 1" = 20', MAY 1957, RCRD 02633.
- 4) LAND IN PORTSMOUTH, N.H. VITO P. MASSARO TO PORT CITY BEVERAGE CO, SCALE 1" = 40', APRIL 1949, RCRD 01448.
- 5) LAND IN PORTSMOUTH, N.H. MARY E. MORAN TO BOSTON AND MAINE RAILROAD, SCALE 1" = 40', MARCH 1920, RCRD 00540.
- 6) PLAN OF LAND OF MARY E. MORAN ON BARTLETT AND ISLINGTON STREETS PORTSMOUTH, N.H., PREPARED BY JOHN W. DURGIN, SCALE 1" = 20', MAY 1920, RCRD 08.
- 7) DRAINAGE EASEMENT GEORGE E. FRISBEE TO THE CITY OF PORTSMOUTH, N.H., PREPARED BY RICHARD P. MILLETTE AND ASSOCIATES, SCALE : 1" = 20', JUNE 1981, RCRD B-10456.
- 8) LAND IN PORTSMOUTH, N.H. BOSTON AND MAINE RAILROAD TO PORTSMOUTH FACTORY BUILDING ASSOCIATION, SCALE 1" = 20' OCTOBER 1923, RCRD 00356.
- 9) NH ELECTRIC CO. PLAN SHOWING AREA RESERVED FOR TRANSFORMER SUBSTATION ON PROPERTY OF CONTINENTAL SHOE CORP. PORTSMOUTH, N.H., SCALE 1" = 30', 11-27-53, RCRD 1303/378.
- 10) BOSTON AND MAINE RAILROAD PLAN TO ACCOMPANY AGREEMENT BETWEEN BOSTON AND MAINE RAILROAD AND CONCORD AND PORTSMOUTH RAILROAD COVERING RELOCATION OF TRACKS OF CONCORD AND PORTSMOUTH RAILROAD IN PORTSMOUTH, N.H. OCCASIONED BY CONSTRUCTION OF NEW HIGHWAY AND BRIDGE BY MAINE - NEW HAMPSHIRE INTERSTATE BRIDGE AUTHORITY, SCALE 1" = 500', DECEMBER 1936, RCRD 0934.
- 11) LAND IN PORTSMOUTH, N.H. BOSTON AND MAINE RAILROAD TO CITY CONCRETE CO., INC., SCALE 1" = 80', JANUARY 1955, RCRD 02897.
- 12) LAND IN PORTSMOUTH, N.H. BOSTON AND MAINE RAILROAD TO ALL STATE REALTY CORPORATION, SCALE 1" = 50', FEBRUARY 1961, RCRD 160.
- 13) LAND IN PORTSMOUTH, N.H. BOSTON AND MAINE RAILROAD TO VITO P. MASSARO, SCALE 1" = 40', APRIL 1949, RCRD 01450.
- 14) DRAINAGE EASEMENT STUART AND PAULA BOXER AND ARANOSIAN OIL COMPANY TO THE CITY OF PORTSMOUTH, N.H., PREPARED BY RICHARD P. MILLETTE AND ASSOCIATES, SCALE: 1" = 20', JUNE 1981, RCRD B-10455.
- 15) CONDOMINIUM PLAN ISLINGTON PLACE PREPARED FOR ANCHOR BUILDING ASSOCIATES, PREPARED BY KIMBALL CHASE COMPANY, INC., SCALE 1" = 20', 12-10-86, RCRD D-15826.
- 16) PLAN OF LOT 565-581 ISLINGTON STREET PORTSMOUTH, N.H., PREPARED BY JOHN W. DURGIN CIVIL ENGINEERS, SCALE 1" = 10', DECEMBER 1949 REVISED JANUARY 1963, RCRD B28.
- 17) SUBDIVISION OF LAND PORTSMOUTH, N.H. FOR GEORGE AND PAULINE J. FRISBEE, PREPARED BY JOHN W. DURGIN CIVIL ENGINEERS PROFESSIONAL ASSOCIATION, SCALE" 1" = 30', DECEMBER 1976, RCRD C-6587.
- 18) RIGHT OF WAY AND TRACK MAP BOSTON AND MAINE R.R. OPERATED BY THE BOSTON AND MAINE R.R. STATION 2966+20 TO STATION 3019+0, SCALE 1" = 100', JUNE 30, 1914, VAL V3NH 55.
- 19) PLAN OF LAND FOR DEER STREET ASSOCIATES DEER AND BRIDGE STREETS AND MAPLEWOOD AVENUE PORTSMOUTH, N.H. COUNTY OF ROCKINGHAM, PREPARED BY AMBIT SURVEY, SCALE: 1" = 30', SEPTEMBER 1993.
- 20) PROPOSED EASEMENTS- BARTLETT STREET BARTLETT SEWER SEPERATION PROJECT OVER LAND OF PAN AM RAILWAYS PORTSMOUTH, NEW HAMPSHIRE FOR CITY OF PORTSMOUTH, PREPARED BY JAMES VERRA AND ASSOCIATES, INC., SCALE : 1" = 20', DATED 10-01-2007 RCRD D-35477.

- 21) SEWER AND STORM DRAIN EASEMENT PLAN 105 BARTLETT STREET PORTSMOUTH, NEW HAMPSHIRE ASSESSOR'S PARCEL 164-001 & 164-003 EASEMENT OWNER CITY OF PORTSMOUTH, PREPARED BY JAMES VERRA AND ASSOCIATES, INC., SCALE 1" = 20', DATED 01/05/2012, RCRD D-37763.
- 22) EASEMENT PLAN TAX MAP 164 - LOT 4 BOSTON & MAINE CORPORATION TO THE CITY OF PORTSMOUTH OFF BREWSTER STREET CITY OF PORTSMOUTH COUNTY OF ROCKINGHAM STATE OF NEW HAMPSHIRE, PREPARED BY AMBIT ENGINEERING, INC. SCALE: 1" = 30', DATED SEPTEMBER 2012, RCRD D-37720.
- 23) STANDARD BOUNDARY SURVEY TAX MAP 157 - LOTS 7,8,10,11,12,13,14 AND 15 WASHBURN REALTY, INC. AND WASHBURN PLUMBING AND HEATING SUPPLY COMPANY, INC. FOR JAY McSHARRY 449 & 459 ISLINGTON STREET AND 18, 30, 40, & 46 DOVER STREET AND 268 & 280 MCDONOUGH STREET CITY OF PORTSMOUTH, COUNTY OF ROCKINGHAM STATE OF NEW HAMPSHIRE, PREPARED BY AMBIT ENGINEERING, INC., SCALE 1" = 20', DATED JANUARY 2012, NOT RECORDED.
- 24) SITE REDEVELOPMENT NED & BILL PROPERTIES 621-627 ISLINGTON STREET PORTSMOUTH, N.H., PREPARED BY AMBIT ENGINEERING, INC., SCALE 1" = 10', DATED MARCH 2006, NOT RECORDED.
- 25) PLAN OF LAND FOR SAGAMORE ENTERPRISES 653 ISLINGTON STREET COUNTY OF ROCKINGHAM PORTSMOUTH N.H., PREPARED BY RICHARD P. MILLETTE AND ASSOCIATES, SCALE 1" = 10', DATED SEPTEMBER 21, 1988, RCRD D-18742.
- 26) STATION MAP - LANDS BOSTON AND MAINE R.R. OPERATED BY THE BOSTON AND MAINE R.R. STATION 2966+20 TO STATION 3019+0, OFFICE OF VALUATION ENGINEER. BOSTON, MASS, SCALE 1" = 100', JUNE 30, 1914 VAL V3NH SL55.
- 27) STATION MAP - LANDS CONCORD AND PORTSMOUTH R.R. OPERATED BY THE BOSTON AND MAINE R.R. STATION 0+0 TO STATION 33+0, OFFICE OF VALUATION ENGINEER. BOSTON, MASS, SCALE 1" = 100', JUNE 30, 1914 VAL V3NH SL55A.
- 28) SUBDIVISION PLAN TAX MAP 157 - LOTS 1 & 2 TAX MAP 164 - LOTS 1, 2, 3, & 4 OWNER OF RECORD TAX MAP 157, LOT 2 & TAX MAP 164, LOTS 1, 2, & 3: PORTSMOUTH LUMBER AND HARDWARE, LLC OWNER OF RECORD TAX MAP 157, LOT 1: CLIPPER TRADERS, LLC OWNER OF RECORD TAX MAP 164, LOT 4: BOSTON AND MAINE CORPORATION PROPERTY LOCATED AT: 105 BARTLETT STREET, CITY OF PORTSMOUTH, COUNTY OF ROCKINGHAM, STATE OF NEW HAMPSHIRE. PREPARED BY AMBIT ENGINEERING, INC. DATED FEBRUARY 2018, FINAL REVISION DATE DECEMBER 14, 2018. R.C.R.D. PLAN D-41241.
- 29) LAND TRANSFER PLAN TAX MAP 164 - LOT 4 LAND OF: BOSTON AND MAINE CORPORATION TO BE CONVEYED TO: PORTSMOUTH LUMBER AND HARDWARE, LLC & CLIPPER TRADERS, LLC PROPERTY LOCATED AT 105 BARTLETT STREET, CITY OF PORTSMOUTH, COUNTY OF ROCKINGHAM, STATE OF NEW HAMPSHIRE. PREPARED BY AMBIT ENGINEERING, INC. DATED DECEMBER 2018, FINAL REVISION DATE DECEMBER 13, 2018. R.C.R.D. PLAN D-41242.
- 30) WATERLINE EASEMENT PLAN OVER TAX MAP 164 - LOT 4 LAND OF BOSTON AND MAINE CORPORATION FOR BENEFIT OF PORTSMOUTH LUMBER AND HARDWARE, LLC & CLIPPER TRADERS, LLC. OFF MCDONOUGH STREET, CITY OF PORTSMOUTH, COUNTY OF ROCKINGHAM, STATE OF NEW HAMPSHIRE. PREPARED BY AMBIT ENGINEERING, INC. DATED DECEMBER 2018, FINAL REVISION DATE DECEMBER 19, 2018. R.C.R.D. PLAN B-41243.
- 31) LOT LINE RELOCATION PLAN TAX MAP 164 - LOTS 4 & 4-2 OWNERS OF RECORD TAX MAP 164 LOT 4: BOSTON AND MAINE CORPORATION, OWNER OF RECORD TAX MAP 164 LOT 4-2: IRON HORSE PROPERTIES, LLC, PROPERTY LOCATED BETWEEN BARTLETT STREET & MAPLEWOOD AVENUE, CITY OF PORTSMOUTH, COUNTY OF ROCKINGHAM, STATE OF NEW HAMPSHIRE. PREPARED BY AMBIT ENGINEERING, INC. DATED APRIL 2019, FINAL REVISION DATE MAY 30, 2019. R.C.R.D. PLAN D-41570.
- 32) PROPOSED EASEMENT PLAN TAX MAP 164 - LOT 4 OWNER OF RECORD BOSTON AND MAINE CORPORATION TO BENEFIT IRON HORSE PROPERTIES, LLC, PROPERTY LOCATED BETWEEN BARTLETT STREET & MAPLEWOOD AVENUE, CITY OF PORTSMOUTH, COUNTY OF ROCKINGHAM, STATE OF NEW HAMPSHIRE. PREPARED BY AMBIT ENGINEERING, INC. DATED JUNE 2019, FINAL REVISION DATE JUNE 27, 2019. R.C.R.D. PLAN D-41578.


APPROVED BY THE PORTSMOUTH PLANNING BOARD

CHAIRMAN _____ DATE _____



"I CERTIFY THAT THIS PLAN WAS PREPARED UNDER MY DIRECT SUPERVISION, THAT IT IS THE RESULT OF A FIELD SURVEY BY THIS OFFICE AND HAS AN ACCURACY OF THE CLOSED TRAVERSE THAT EXCEEDS THE PRECISION OF 1:15,000."

PAUL A. DOBBERSTEIN, LL.S. 1/20/2021 DATE



LOCATION MAP SCALE 1"=1,000'

LENGTH TABLE

LINE	BEARING	DISTANCE
L3	N59°39'51"E	2'±



CURVE TABLE

CURVE	RADIUS	ARC LENGTH	CHORD LENGTH	CHORD BEARING	DELTA ANGLE
C5	150.00'	38.24'	38.14'	S39°30'52"W	14°36'24"
C6	200.00'	42.87'	42.79'	S38°21'07"W	12°16'55"
C7	25.00'	31.80'	29.70'	S19°56'09"W	72°52'42"
C8	288.61'	48.94'	48.88'	N21°21'40"W	9°42'56"
C10	288.61'	80.91'	80.65'	N08°28'19"W	16°03'46"

LEGEND:

- N/F NOW OR FORMERLY
- RP RECORD OF PROBATE
- RCRD ROCKINGHAM COUNTY
- REGISTRY OF DEEDS
- (11/21) MAP 11/LOT 21
- IR FND IRON ROD FOUND
- IP FND IRON PIPE FOUND
- IR SET IRON ROD SET
- DH FND DRILL HOLE FOUND
- DH SET DRILL HOLE SET
- △ MN FND MAG NAIL FOUND
- ▲ MN SET MAG NAIL SET
- BND w/DH BOUND WITH DRILL HOLE
- PROPERTY LINE
- - - PROPERTY LINE TO BE ABANDONED
- · - · - PROPOSED PROPERTY LINE
- - - MEAN HIGH WATER LINE

N/F
 M & B PROPERTIES, LLC
 54 BARTLETT STREET
 PORTSMOUTH, NH 03801
 5794/996



MATCHLINE - SEE SHEET 3

NOTES:

- 1) PARCELS ARE SHOWN ON THE CITY OF PORTSMOUTH ASSESSOR'S MAP 157 LOTS 1 & 2, MAP 164 AS LOTS 1 & 4-2, AND A RIGHT-OF-WAY WITH NO ASSESSOR'S MAP DESIGNATION.
- 2) OWNERS OF RECORD:
 MAP 157 LOT 1
 CLIPPER TRADERS, LLC
 105 BARTLETT STREET
 PORTSMOUTH, NH 03801
 5598/2725 & 5970/1701

 MAP 157 LOT 2 & MAP 164 LOT 1
 PORTSMOUTH LUMBER & HARDWARE, LLC
 105 BARTLETT STREET
 PORTSMOUTH, NH 03801
 5372/2606, 5808/1379, 5540/2567, & 5970/1693

 MAP 164 LOT 4-2
 IRON HORSE PROPERTIES, LLC
 105 BARTLETT STREET
 PORTSMOUTH, NH 03801
 5970/1686 & 6012/2502

 RIGHT-OF-WAY
 CLIPPER TRADERS, LLC, PORTSMOUTH LUMBER & HARDWARE, LLC, & IRON HORSE PROPERTIES, LLC
 5970/1708
- 3) PORTIONS OF THE SUBJECT PARCELS ARE IN A SPECIAL FLOOD HAZARD AREA ZONE AE (EL.9) AS SHOWN ON FIRM PANEL 33015C0259E. EFFECTIVE DATE MAY 17, 2005.
- 4) PARCELS ARE LOCATED IN CHARACTER DISTRICT 4W (CD4-W), CHARACTER DISTRICT 4-L1 (CD4-L1), AND OFFICE RESEARCH (OR) ZONING DISTRICTS.
- 5) THE PURPOSE OF THIS PLAN IS TO SHOW A LOT LINE RELOCATION BETWEEN THE SUBJECT PARCELS IN THE CITY OF PORTSMOUTH.
- 6) VERTICAL DATUM IS MEAN SEA LEVEL NAVD88. BASIS OF VERTICAL DATUM IS REDUNDANT RTN GPS OBSERVATIONS (±0.3').
- 7) HORIZONTAL DATUM AND BASIS OF BEARINGS IS THE NH STATE PLANE COORDINATE SYSTEM NAD 83 (2011). BASIS OF HORIZONTAL DATUM IS REDUNDANT RTN GPS OBSERVATIONS.
- 8) SEE SHEET 1 OF 5 FOR OVERALL PROPERTY VIEW, EXISTING AND PROPOSED LOT AREAS, PLAN REFERENCES, AND DIMENSIONAL REQUIREMENTS.

NO.	DESCRIPTION	DATE
1	REVISE PROPOSED LOT LINE	1/19/21
0	ISSUED FOR COMMENT	6/22/20

LOT LINE RELOCATION PLAN
 TAX MAP 157 - LOTS 1 & 2
 TAX MAP 164 - LOTS 1 & 4-2

TAX MAP 157 LOT 1:
CLIPPER TRADERS, LLC
 OWNER OF RECORD



 TAX MAP 157 LOT 2 & TAX MAP 164 LOT 1:
PORTSMOUTH LUMBER & HARDWARE, LLC
 OWNER OF RECORD

 TAX MAP 164 LOT 4-2:
IRON HORSE PROPERTIES, LLC
 OWNER OF RECORD

RIGHT-OF-WAY (NO TAX MAP DESIGNATION):
IRON HORSE PROPERTIES, LLC,
PORTSMOUTH LUMBER & HARDWARE, LLC,
& CLIPPER TRADERS, LLC
 PROPERTY LOCATED BETWEEN:
BARTLETT STREET & MAPLEWOOD AVENUE
 CITY OF PORTSMOUTH
 COUNTY OF ROCKINGHAM
 STATE OF NEW HAMPSHIRE

APPROVED BY THE PORTSMOUTH PLANNING BOARD

CHAIRMAN _____ DATE _____




"I CERTIFY THAT THIS PLAN WAS PREPARED UNDER MY DIRECT SUPERVISION, THAT IT IS THE RESULT OF A FIELD SURVEY BY THIS OFFICE AND HAS AN ACCURACY OF THE CLOSED TRAVERSE THAT EXCEEDS THE PRECISION OF 1:15,000."


PAUL A. DOBBERSTEIN, LLS DATE 1/20/2021

LEGEND:

- N/F NOW OR FORMERLY
- RP RECORD OF PROBATE
- RCRD ROCKINGHAM COUNTY
- REGISTRY OF DEEDS
- MAP 11/LOT 21
- IR FND IRON ROD FOUND
- IP FND IRON PIPE FOUND
- IR SET IRON ROD SET
- DH FND DRILL HOLE FOUND
- DH SET DRILL HOLE SET
- MN SET MAG NAIL SET
- BND w/DH BOUND WITH DRILL HOLE
- PROPERTY LINE
- PROPERTY LINE TO BE ABANDONED
- PROPOSED PROPERTY LINE
- MEAN HIGH WATER LINE



NORTH MILL POND (TIDAL)



AMBIT ENGINEERING, INC.
 Civil Engineers & Land Surveyors
 200 Griffin Road - Unit 3
 Portsmouth, N.H. 03801-7114
 Tel (603) 430-9282
 Fax (603) 436-2815

- NOTES:**
- 1) PARCELS ARE SHOWN ON THE CITY OF PORTSMOUTH ASSESSOR'S MAP 157 LOTS 1 & 2, MAP 164 AS LOTS 1 & 4-2, AND A RIGHT-OF-WAY WITH NO ASSESSOR'S MAP DESIGNATION.
 - 2) OWNERS OF RECORD:
 MAP 157 LOT 1
 CLIPPER TRADERS, LLC
 105 BARTLETT STREET
 PORTSMOUTH, NH 03801
 5598/2725 & 5970/1701

 MAP 157 LOT 2 & MAP 164 LOT 1
 PORTSMOUTH LUMBER & HARDWARE, LLC
 105 BARTLETT STREET
 PORTSMOUTH, NH 03801
 5372/2606, 5808/1379, 5540/2567, & 5970/1693

 MAP 164 LOT 4-2
 IRON HORSE PROPERTIES, LLC
 105 BARTLETT STREET
 PORTSMOUTH, NH 03801
 5970/1686 & 6012/2502

 RIGHT-OF-WAY
 CLIPPER TRADERS, LLC, PORTSMOUTH LUMBER & HARDWARE, LLC, & IRON HORSE PROPERTIES, LLC
 5970/1708
 - 3) PORTIONS OF THE SUBJECT PARCELS ARE IN A SPECIAL FLOOD HAZARD AREA ZONE AE (EL.9) AS SHOWN ON FIRM PANEL 33015C0259E. EFFECTIVE DATE MAY 17, 2005.
 - 4) PARCELS ARE LOCATED IN CHARACTER DISTRICT 4W (CD4-W), CHARACTER DISTRICT 4-L1 (CD4-L1), AND OFFICE RESEARCH (OR) ZONING DISTRICTS.
 - 5) THE PURPOSE OF THIS PLAN IS TO SHOW A LOT LINE RELOCATION BETWEEN THE SUBJECT PARCELS IN THE CITY OF PORTSMOUTH.
 - 6) VERTICAL DATUM IS MEAN SEA LEVEL NAVD88. BASIS OF VERTICAL DATUM IS REDUNDANT RTN GPS OBSERVATIONS (±0.3').
 - 7) HORIZONTAL DATUM AND BASIS OF BEARINGS IS THE NH STATE PLANE COORDINATE SYSTEM NAD 83 (2011). BASIS OF HORIZONTAL DATUM IS REDUNDANT RTN GPS OBSERVATIONS.
 - 8) SEE SHEET 1 OF 5 FOR OVERALL PROPERTY VIEW, EXISTING AND PROPOSED LOT AREAS, PLAN REFERENCES, AND DIMENSIONAL REQUIREMENTS.

NO.	DESCRIPTION	DATE
1	REVISE PROPOSED LOT LINE	1/19/21
0	ISSUED FOR COMMENT	6/22/20

**LOT LINE RELOCATION PLAN
 TAX MAP 157 - LOTS 1 & 2
 TAX MAP 164 - LOTS 1 & 4-2**

TAX MAP 157 LOT 1:
CLIPPER TRADERS, LLC
 OWNER OF RECORD

TAX MAP 157 LOT 2 & TAX MAP 164 LOT 1:
PORTSMOUTH LUMBER & HARDWARE, LLC
 OWNER OF RECORD

TAX MAP 164 LOT 4-2:
IRON HORSE PROPERTIES, LLC
 OWNER OF RECORD

RIGHT-OF-WAY (NO TAX MAP DESIGNATION):
**IRON HORSE PROPERTIES, LLC,
 PORTSMOUTH LUMBER & HARDWARE, LLC,
 & CLIPPER TRADERS, LLC**


PROPERTY LOCATED BETWEEN:
 BARTLETT STREET & MAPLEWOOD AVENUE
 CITY OF PORTSMOUTH
 COUNTY OF ROCKINGHAM
 STATE OF NEW HAMPSHIRE

LENGTH TABLE

LINE	BEARING	DISTANCE
L1	S46°54'17"E	11.80'
L2	S46°49'43"E	11.20'
L3	N59°39'51"E	2'±
L4	S30°20'37"W	18.60'


CURVE TABLE

CURVE	RADIUS	ARC LENGTH	CHORD LENGTH	CHORD BEARING	DELTA ANGLE
C1	60.00'	266.77'	95.37'	S05°48'40"E	254°44'33"
C2	60.00'	185.84'	119.97'	S44°26'53"E	177°28'07"
C3	60.00'	80.92'	74.93'	S82°55'23"W	77°16'26"



APPROVED BY THE PORTSMOUTH PLANNING BOARD

CHAIRMAN _____ DATE _____




"I CERTIFY THAT THIS PLAN WAS PREPARED UNDER MY DIRECT SUPERVISION, THAT IT IS THE RESULT OF A FIELD SURVEY BY THIS OFFICE AND HAS AN ACCURACY OF THE CLOSED TRAVERSE THAT EXCEEDS THE PRECISION OF 1:15,000."

PAUL A. DOBBERSTEIN, LLS
 DATE 1/20/2021

LEGEND:

- | | |
|------|--|
| N/F | NOW OR FORMERLY |
| RP | RECORD OF PROBATE |
| RCRD | ROCKINGHAM COUNTY
REGISTRY OF DEEDS |
| | MAP 11/LOT 21 |
| | IRON ROD FOUND |
| | IRON PIPE FOUND |
| | IRON ROD SET |
| | DRILL HOLE FOUND |
| | DRILL HOLE SET |
| | MAG NAIL FOUND |
| | MAG NAIL SET |
| | BOUND WITH DRILL HOLE |
| | PROPERTY LINE |
| | PROPERTY LINE TO BE ABANDONED |
| | PROPOSED PROPERTY LINE |
| | MEAN HIGH WATER LINE |



NOTES:


- 1) PARCELS ARE SHOWN ON THE CITY OF PORTSMOUTH ASSESSOR'S MAP 157 LOTS 1 & 2, MAP 164 AS LOTS 1 & 4-2, AND A RIGHT-OF-WAY WITH NO ASSESSOR'S MAP DESIGNATION.
- 2) OWNERS OF RECORD:
 MAP 157 LOT 1
 CLIPPER TRADERS, LLC
 105 BARTLETT STREET
 PORTSMOUTH, NH 03801
 5598/2725 & 5970/1701

 MAP 157 LOT 2 & MAP 164 LOT 1
 PORTSMOUTH LUMBER & HARDWARE, LLC
 105 BARTLETT STREET
 PORTSMOUTH, NH 03801
 5372/2606, 5808/1379, 5540/2567, & 5970/1693

 MAP 164 LOT 4-2
 IRON HORSE PROPERTIES, LLC
 105 BARTLETT STREET
 PORTSMOUTH, NH 03801
 5970/1686 & 6012/2502

 RIGHT-OF-WAY
 CLIPPER TRADERS, LLC, PORTSMOUTH LUMBER & HARDWARE, LLC, & IRON HORSE PROPERTIES, LLC
 5970/1708
- 3) PORTIONS OF THE SUBJECT PARCELS ARE IN A SPECIAL FLOOD HAZARD AREA ZONE AE (EL.9) AS SHOWN ON FIRM PANEL 33015C0259E. EFFECTIVE DATE MAY 17, 2005.
- 4) PARCELS ARE LOCATED IN CHARACTER DISTRICT 4W (CD4-W), CHARACTER DISTRICT 4-L1 (CD4-L1), AND OFFICE RESEARCH (OR) ZONING DISTRICTS.
- 5) THE PURPOSE OF THIS PLAN IS TO SHOW A LOT LINE RELOCATION BETWEEN THE SUBJECT PARCELS IN THE CITY OF PORTSMOUTH.
- 6) VERTICAL DATUM IS MEAN SEA LEVEL NAVD88. BASIS OF VERTICAL DATUM IS REDUNDANT RTN GPS OBSERVATIONS (±0.3').
- 7) HORIZONTAL DATUM AND BASIS OF BEARINGS IS THE NH STATE PLANE COORDINATE SYSTEM NAD 83 (2011). BASIS OF HORIZONTAL DATUM IS REDUNDANT RTN GPS OBSERVATIONS.
- 8) SEE SHEET 1 OF 5 FOR OVERALL PROPERTY VIEW, EXISTING AND PROPOSED LOT AREAS, PLAN REFERENCES, AND DIMENSIONAL REQUIREMENTS.

**NORTH MILL POND
(TIDAL)**





NO.	DESCRIPTION	DATE
1	REVISE PROPOSED LOT LINE	1/19/21
0	ISSUED FOR COMMENT	6/22/20

LOT LINE RELOCATION PLAN
TAX MAP 157 - LOTS 1 & 2
TAX MAP 164 - LOTS 1 & 4-2
 TAX MAP 157 LOT 1:
CLIPPER TRADERS, LLC
 OWNER OF RECORD
 TAX MAP 157 LOT 2 & TAX MAP 164 LOT 1:
PORTSMOUTH LUMBER & HARDWARE, LLC
 OWNER OF RECORD
 TAX MAP 164 LOT 4-2:
IRON HORSE PROPERTIES, LLC
 OWNER OF RECORD
 RIGHT-OF-WAY (NO TAX MAP DESIGNATION):
IRON HORSE PROPERTIES, LLC,
PORTSMOUTH LUMBER & HARDWARE, LLC,
& CLIPPER TRADERS, LLC
 PROPERTY LOCATED BETWEEN:
BARTLETT STREET & MAPLEWOOD AVENUE
 CITY OF PORTSMOUTH
 COUNTY OF ROCKINGHAM
 STATE OF NEW HAMPSHIRE

APPROVED BY THE PORTSMOUTH PLANNING BOARD

CHAIRMAN _____ DATE _____



"I CERTIFY THAT THIS PLAN WAS PREPARED UNDER MY DIRECT SUPERVISION, THAT IT IS THE RESULT OF A FIELD SURVEY BY THIS OFFICE AND HAS AN ACCURACY OF THE CLOSED TRAVERSE THAT EXCEEDS THE PRECISION OF 1:15,000."

PAUL A. DOBBERSTEIN, LLS DATE 1/20/2021

NOTES:

- 1) PARCELS ARE SHOWN ON THE CITY OF PORTSMOUTH ASSESSOR'S MAP 157 LOTS 1 & 2, MAP 164 AS LOTS 1 & 4-2, AND A RIGHT-OF-WAY WITH NO ASSESSOR'S MAP DESIGNATION.
- 2) OWNERS OF RECORD:
 MAP 157 LOT 1
 CLIPPER TRADERS, LLC
 105 BARTLETT STREET
 PORTSMOUTH, NH 03801
 5598/2725 & 5970/1701

 MAP 157 LOT 2 & MAP 164 LOT 1
 PORTSMOUTH LUMBER & HARDWARE, LLC
 105 BARTLETT STREET
 PORTSMOUTH, NH 03801
 5372/2606, 5808/1379, 5540/2567, & 5970/1693

 MAP 164 LOT 4-2
 IRON HORSE PROPERTIES, LLC
 105 BARTLETT STREET
 PORTSMOUTH, NH 03801
 5970/1686 & 6012/2502


 RIGHT-OF-WAY
 CLIPPER TRADERS, LLC, PORTSMOUTH LUMBER & HARDWARE, LLC, & IRON HORSE PROPERTIES, LLC
 5970/1708
- 3) PORTIONS OF THE SUBJECT PARCELS ARE IN A SPECIAL FLOOD HAZARD AREA ZONE AE (EL.9) AS SHOWN ON FIRM PANEL 33015C0259E. EFFECTIVE DATE MAY 17, 2005.
- 4) PARCELS ARE LOCATED IN CHARACTER DISTRICT 4W (CD4-W), CHARACTER DISTRICT 4-L1 (CD4-L1), AND OFFICE RESEARCH (OR) ZONING DISTRICTS.
- 5) THE PURPOSE OF THIS PLAN IS TO SHOW A LOT LINE RELOCATION BETWEEN THE SUBJECT PARCELS IN THE CITY OF PORTSMOUTH.
- 6) VERTICAL DATUM IS MEAN SEA LEVEL NAVD88. BASIS OF VERTICAL DATUM IS REDUNDANT RTN GPS OBSERVATIONS (±0.3').
- 7) HORIZONTAL DATUM AND BASIS OF BEARINGS IS THE NH STATE PLANE COORDINATE SYSTEM NAD 83 (2011). BASIS OF HORIZONTAL DATUM IS REDUNDANT RTN GPS OBSERVATIONS.
- 8) SEE SHEET 1 OF 5 FOR OVERALL PROPERTY VIEW, EXISTING AND PROPOSED LOT AREAS, PLAN REFERENCES, AND DIMENSIONAL REQUIREMENTS.

NO.	DESCRIPTION	DATE
1	REVISE PROPOSED LOT LINE	1/19/21
0	ISSUED FOR COMMENT	6/22/20

LOT LINE RELOCATION PLAN
TAX MAP 157 - LOTS 1 & 2
TAX MAP 164 - LOTS 1 & 4-2
 TAX MAP 157 LOT 1:
CLIPPER TRADERS, LLC
 OWNER OF RECORD
 TAX MAP 157 LOT 2 & TAX MAP 164 LOT 1:
PORTSMOUTH LUMBER & HARDWARE, LLC
 OWNER OF RECORD
 TAX MAP 164 LOT 4-2:
IRON HORSE PROPERTIES, LLC
 OWNER OF RECORD
 RIGHT-OF-WAY (NO TAX MAP DESIGNATION):
IRON HORSE PROPERTIES, LLC,
PORTSMOUTH LUMBER & HARDWARE, LLC,
& CLIPPER TRADERS, LLC
 PROPERTY LOCATED BETWEEN:
BARTLETT STREET & MAPLEWOOD AVENUE
CITY OF PORTSMOUTH
COUNTY OF ROCKINGHAM
STATE OF NEW HAMPSHIRE

LEGEND:


- | | | | |
|------------|-----------------------|-----|-------------------------------|
| N/F | NOW OR FORMERLY | --- | PROPERTY LINE |
| RP | RECORD OF PROBATE | --- | PROPERTY LINE TO BE ABANDONED |
| RCD | ROCKINGHAM COUNTY | --- | PROPOSED PROPERTY LINE |
| | REGISTRY OF DEEDS | --- | MEAN HIGH WATER LINE |
| (11/21) | MAP 11/LOT 21 | | |
| ○ IR FND | IRON ROD FOUND | | |
| ○ IP FND | IRON PIPE FOUND | | |
| ● IR SET | IRON ROD SET | | |
| ⊙ DH FND | DRILL HOLE FOUND | | |
| ⊙ DH SET | DRILL HOLE SET | | |
| ▲ MN FND | MAG NAIL FOUND | | |
| ▲ MN SET | MAG NAIL SET | | |
| □ BND w/DH | BOUND WITH DRILL HOLE | | |



NORTH MILL POND (TIDAL)



LENGTH TABLE

LINE	BEARING	DISTANCE
L5	S46°57'07"E	20.00'




APPROVED BY THE PORTSMOUTH PLANNING BOARD

CHAIRMAN _____ DATE _____






I CERTIFY THAT THIS PLAN WAS PREPARED UNDER MY DIRECT SUPERVISION, THAT IT IS THE RESULT OF A FIELD SURVEY BY THIS OFFICE AND HAS AN ACCURACY OF THE CLOSED TRAVERSE THAT EXCEEDS THE PRECISION OF 1:15,000."
 PAUL A DOBBERSTEIN, LLS
 DATE 1/20/2021



LEGEND

- BUILDING
- BUILDING OVERHANG
- BUILDING HATCH/TEXT
- CURB
- EDGE OF PAVEMENT
- RETAINING WALL
- STONE WALL
- CHAIN LINK FENCE
- FENCE LINE
- TREELINE
- PAVEMENT MARKING
- TRAFFIC SIGN
- MAJOR CONTOURS
- MINOR CONTOURS
- STORM DRAIN LINE
- SANITARY SEWER LINE
- WATER LINE
- UNDERGROUND ELECTRIC LINE
- OVERHEAD ELECTRIC LINE
- UNDERGROUND GAS LINE
- DRAIN MANHOLE
- CATCH BASIN
- SEWER MANHOLE
- HYDRANT
- WATER GATE VALVE
- UTILITY POLE
- TELEPHONE STRUCTURE
- GAS GATE VALVE
- BOLLARD
- GAS SHUTOFF
- WATER SHUTOFF

- EXISTING CONDITIONS PLAN NOTES:**
1. EXISTING CONDITIONS ARE BASED ON A FIELD SURVEY BY AMBIT ENGINEERING, INC., DATED 3/5/2018.
 2. WETLAND DELINEATION BY STEVEN D. RIKER, CWS, ON 8/8/2017, AND FIELD LOCATED BY AMBIT ENGINEERING, INC. ON 8/9/2017
 3. FLOOD HAZARD ZONES: "AE ELEV. 9" (SPECIAL FLOOD HAZARD AREA) AND "X" (NOT A SPECIAL FLOOD HAZARD AREA), PER FIRM MAP # 33015C0259E, DATED 5/17/05.
- REFERENCE PLANS:**
1. "PROPOSED SUBDIVISION PLANS, CLIPPER TRADERS, LLC" PREPARED BY AMBIT ENGINEERING, INC., DATED DECEMBER 14, 2018.



Proposed Multi-Family Development

Iron Horse Properties, LLC

105 Bartlett Street
Portsmouth,
New Hampshire


MARK	DATE	DESCRIPTION
H	1/20/2021	TAC Resubmission
G	11/18/2020	TAC Resubmission
F	10/28/2020	Wetland CUP Resubmission
E	5/20/2020	TAC Resubmission
D	4/29/2020	Wetland CUP Submission
C	4/20/2020	TAC Submission
B	2/6/2020	Design Review Submission
A	1/2/2020	ZBA Submission

PROJECT NO:	C-0960-006
DATE:	April 20, 2020
FILE:	C-0960-006_C-SITE.DWG
DRAWN BY:	NAH
CHECKED:	PMC
APPROVED:	BML

OVERALL EXISTING CONDITIONS PLAN

SCALE: AS SHOWN



Last Saved: 1/19/2021 11:19:05 AM
 Plotted On: Jan 19, 2021 5:05:09 PM
 By: Mahanien
 Tighe & Bond: J:\C\0960-006_105 Bartlett Street\Drawings - Figures\AutoCAD\Sheet\C-0960-006_C-SITE.dwg





DEMOLITION NOTES:

1. THE LOCATIONS OF UNDERGROUND UTILITIES ARE APPROXIMATE AND THE LOCATIONS ARE NOT GUARANTEED BY THE OWNER OR THE ENGINEER. IT IS THE CONTRACTOR'S RESPONSIBILITY TO LOCATE ALL UTILITIES, ANTICIPATE CONFLICTS, REPAIR EXISTING UTILITIES AND RELOCATE EXISTING UTILITIES REQUIRED TO COMPLETE THE WORK.
2. THE CONTRACTOR SHALL VERIFY LOCATION OF ALL EXISTING UTILITIES. CALL DIG SAFE AT LEAST 72 HOURS PRIOR TO THE COMMENCEMENT OF ANY DEMOLITION/CONSTRUCTION ACTIVITIES.
3. ALL MATERIALS SCHEDULED TO BE REMOVED SHALL BECOME THE PROPERTY OF THE CONTRACTOR UNLESS OTHERWISE SPECIFIED. THE CONTRACTOR SHALL DISPOSE OF ALL MATERIALS OFF-SITE IN ACCORDANCE WITH ALL FEDERAL, STATE, AND LOCAL REGULATIONS, ORDINANCES AND CODES.
4. COORDINATE REMOVAL, RELOCATION, DISPOSAL OR SALVAGE OF UTILITIES WITH THE OWNER AND APPROPRIATE UTILITY COMPANY.
5. ANY EXISTING WORK OR PROPERTY DAMAGED OR DISRUPTED BY CONSTRUCTION/ DEMOLITION ACTIVITIES SHALL BE REPLACED OR REPAIRED TO MATCH ORIGINAL EXISTING CONDITIONS BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE OWNER.
6. SAW CUT AND REMOVE PAVEMENT ONE (1) FOOT OFF PROPOSED EDGE OF PAVEMENT OR EXISTING CURB LINE IN ALL AREAS WHERE PAVEMENT TO BE REMOVED ABUTS EXISTING PAVEMENT OR CONCRETE TO REMAIN.
7. IT IS THE CONTRACTOR'S RESPONSIBILITY TO FAMILIARIZE THEMSELVES WITH THE CONDITIONS OF ALL OF THE PERMIT APPROVALS.
8. THE CONTRACTOR SHALL OBTAIN AND PAY FOR ADDITIONAL PERMITS, NOTICES AND FEES NECESSARY TO COMPLETE THE WORK AND ARRANGE FOR AND PAY FOR NECESSARY INSPECTIONS AND APPROVALS FROM THE AUTHORITIES HAVING JURISDICTION.
9. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL DEMOLITION AND OFF-SITE DISPOSAL OF MATERIALS REQUIRED TO COMPLETE THE WORK, EXCEPT FOR WORK NOTED TO BE COMPLETED BY OTHERS.
10. UTILITIES SHALL BE TERMINATED AT THE MAIN LINE PER UTILITY COMPANY STANDARDS. THE CONTRACTOR SHALL REMOVE ALL ABANDONED UTILITIES LOCATED WITHIN THE LIMITS OF WORK.
11. CONTRACTOR SHALL VERIFY ORIGIN OF ALL DRAINS AND UTILITIES PRIOR TO REMOVAL/TERMINATION TO DETERMINE IF DRAINS OR UTILITY IS ACTIVE, AND SERVICES ANY ON OR OFF-SITE STRUCTURE TO REMAIN. THE CONTRACTOR SHALL NOTIFY ENGINEER IMMEDIATELY OF ANY SUCH UTILITY FOUND AND SHALL MAINTAIN THESE UTILITIES UNTIL PERMANENT SOLUTION IS IN PLACE.
12. PAVEMENT REMOVAL LIMITS ARE SHOWN FOR CONTRACTOR'S CONVENIENCE. ADDITIONAL PAVEMENT REMOVAL MAY BE REQUIRED DEPENDING ON THE CONTRACTOR'S OPERATION. CONTRACTOR TO VERIFY FULL LIMITS OF PAVEMENT REMOVAL PRIOR TO BID.
13. ALL ITEMS WITHIN THE LIMIT OF WORK ARE TO REMAIN UNLESS SPECIFICALLY IDENTIFIED TO BE REMOVED OR OTHERWISE ALTERED BY THE CONTRACTOR. ITEMS TO BE REMOVED INCLUDE, BUT ARE NOT LIMITED TO: CONCRETE, PAVEMENT, MANHOLES, CATCH BASINS, UNDERGROUND PIPING & UTILITIES, POLES, STAIRS, STRUCTURES, FENCES, RAMPS, BUILDING FOUNDATIONS, TREES, AND LANDSCAPING. THE CONTRACTOR SHALL CONFIRM WITH THE ENGINEER IF THE TREATMENT OF CERTAIN ITEMS IS UNCLEAR.
14. COORDINATE ALL WORK WITHIN THE PUBLIC RIGHT OF WAYS WITH THE CITY OF PORTSMOUTH.
15. REMOVE TREES AND BRUSH AS REQUIRED FOR COMPLETION OF WORK. CONTRACTOR SHALL GRUB AND REMOVE ALL STUMPS WITHIN LIMITS OF WORK AND DISPOSE OF OFF SITE IN ACCORDANCE WITH FEDERAL, STATE, AND LOCAL LAWS AND REGULATIONS.
16. CONTRACTOR SHALL PROTECT ALL PROPERTY MONUMENTATION THROUGHOUT DEMOLITION AND CONSTRUCTION OPERATIONS. SHOULD ANY MONUMENTATION BE DISTURBED BY THE CONTRACTOR, THE CONTRACTOR SHALL EMPLOY A NEW HAMPSHIRE LICENSED SURVEYOR TO REPLACE DISTURBED MONUMENTS.
17. PROVIDE INLET PROTECTION BARRIERS AT ALL CATCH BASINS/CURB INLETS WITHIN CONSTRUCTION LIMITS AS WELL AS CATCH BASINS/CURB INLETS THAT RECEIVE RUNOFF FROM CONSTRUCTION ACTIVITIES. INLET PROTECTION BARRIERS SHALL BE MAINTAINED FOR THE DURATION OF THE PROJECT. INLET PROTECTION BARRIERS SHALL BE "HIGH FLOW SILT SACK" BY ACF ENVIRONMENTAL OR EQUAL. INSPECT BARRIERS WEEKLY AND AFTER EACH RAIN EVENT OF 0.25 INCHES OR GREATER. CONTRACTOR SHALL COMPLETE A MAINTENANCE INSPECTION REPORT AFTER EACH INSPECTION. SEDIMENT DEPOSITS SHALL BE REMOVED AFTER EACH STORM EVENT OR MORE OFTEN IF THE FABRIC BECOMES CLOGGED OR SEDIMENT HAS ACCUMULATED TO 1/3 THE DESIGN DEPTH OF THE BARRIER.
18. THE CONTRACTOR SHALL PHASE DEMOLITION AND CONSTRUCTION AS REQUIRED TO PROVIDE CONTINUOUS SERVICE TO EXISTING BUSINESSES AND HOMES THROUGHOUT THE CONSTRUCTION PERIOD. EXISTING BUSINESS AND HOME SERVICES INCLUDE, BUT ARE NOT LIMITED TO ELECTRICAL, COMMUNICATION, FIRE PROTECTION, DOMESTIC WATER AND SEWER SERVICES. TEMPORARY SERVICES, IF REQUIRED, SHALL COMPLY WITH ALL FEDERAL, STATE, LOCAL AND UTILITY COMPANY STANDARDS. CONTRACTOR SHALL PROVIDE DETAILED CONSTRUCTION SCHEDULE TO OWNER PRIOR TO ANY DEMOLITION/CONSTRUCTION ACTIVITIES AND SHALL COORDINATE TEMPORARY SERVICES TO ABUTERS WITH THE UTILITY COMPANY AND AFFECTED ABUTER.
19. EROSION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO THE START OF ANY CLEARING OR DEMOLITION ACTIVITIES.
20. THE CONTRACTOR SHALL PAY ALL COSTS NECESSARY FOR TEMPORARY PARTITIONING, BARRICADING, FENCING, SECURITY AND SAFETY DEVICES REQUIRED FOR THE MAINTENANCE OF A CLEAN AND SAFE CONSTRUCTION SITE.
21. SAW CUT AND REMOVE PAVEMENT AND CONSTRUCT PAVEMENT TRENCH PATCH FOR ALL UTILITIES TO BE REMOVED AND PROPOSED UTILITIES LOCATED IN EXISTING PAVEMENT AREAS TO REMAIN.
22. ALL CONDITIONS ON THIS PLAN SHALL REMAIN IN EFFECT IN PERPETUITY PURSUANT TO THE REQUIREMENTS OF THE SITE PLAN REVIEW REGULATIONS.
23. WITH THE EXCEPTION OF THE NORWAY MAPLES IN THE 25' VEGETATED BUFFER, WHICH ARE TO REMAIN, INVASIVE SPECIES WITHIN THE 100' SHORELAND SETBACK WILL BE REMOVED. INVASIVE SPECIES WITHIN THE 25' VEGETATED BUFFER WILL BE FLAGGED IN FIELD BY THE LANDSCAPE ARCHITECT OR CERTIFIED ARBORIST TO BE REMOVED. INVASIVE SHRUBS WITHIN THE 25' VEGETATED BUFFER WITH CALIPER MEASURING GREATER THAN 3" SUCH AS BUCKTHORN AND AUTUMN OLIVE WILL BE FLUSH CUT REPEATEDLY TO KILL THE PLANT, LEAVING THE STUMPS IN PLACE. WOODY INVASIVES SMALLER THAN 3" CALIPER SHALL BE REMOVED WITH HAND TOOLS. AREAS OF SOIL DISTURBANCE FROM SUCH REMOVALS WILL BE LIMITED TO THE IMMEDIATE ROOT AREA SURROUNDING EACH PLANT, DRESSED WITH LOAM, REPLANTED WITH NEW ENGLAND WILDLIFE AND CONSERVATION SEED MIX AND STABILIZED WITH JUTE MESH STAKED IN PLACE. ALL OTHER AREAS DISTURBED BY HEADWALLS AND CULVERTS SHALL BE LOAMED, SEEDED WITH NEW ENGLAND WILDLIFE AND CONSERVATION SEED MIX AND STABILIZED WITH JUTE MESH.

LEGEND



MATCH LINE SHEET 1
MATCH LINE SHEET 2



Proposed Multi-Family Development

Iron Horse Properties, LLC

105 Bartlett Street
Portsmouth,
New Hampshire

H	1/20/2021	TAC Resubmission
G	11/18/2020	TAC Resubmission
F	10/28/2020	Wetland CUP Resubmission
E	5/20/2020	TAC Resubmission
D	4/29/2020	Wetland CUP Submission
C	4/20/2020	TAC Submission
B	2/6/2020	Design Review Submission
A	1/2/2020	ZBA Submission


PROJECT NO:	C-0960-006
DATE:	April 20, 2020
FILE:	C-0960-006_C-SITE.DWG
DRAWN BY:	NAH
CHECKED:	PMC
APPROVED:	BML

EXISTING CONDITIONS AND DEMOLITION PLAN

SCALE: AS SHOWN

C-101.1

Last Saved: 1/19/2021
Plotted On: Jan 20, 2021 1:10:23am By: Mahansen
Tighe & Bond: P:\CUB960-006 105 Bartlett Street Drawings - Figures\AutoCAD\Sheet\C-0960-006_C-SITE.dwg



LEGEND




- APPROXIMATE LIMIT OF PROPOSED SAW CUT
- LIMIT OF WORK
- PROPOSED SILT SOCK
- APPROXIMATE LIMIT OF PAVEMENT TO BE REMOVED
- AREA OF INVASIVE SPECIES TO BE REMOVED
- PROPOSED CONSTRUCTION EXIT
- BUILDING / FOUNDATION TO BE REMOVED
- LOCATION OF PROPOSED BUILDING
- INLET PROTECTION SILT SACK
- TBR TO BE REMOVED
- BLDG BUILDING
- TYP TYPICAL
- COORD COORDINATE

DEMOLITION NOTES:

- THE LOCATIONS OF UNDERGROUND UTILITIES ARE APPROXIMATE AND THE LOCATIONS ARE NOT GUARANTEED BY THE OWNER OR THE CONTRACTOR. IT IS THE CONTRACTOR'S RESPONSIBILITY TO LOCATE ALL UTILITIES, ANTICIPATE CONFLICTS, REPAIR EXISTING UTILITIES AND RELOCATE EXISTING UTILITIES REQUIRED TO COMPLETE THE WORK.
- THE CONTRACTOR SHALL VERIFY LOCATION OF ALL EXISTING UTILITIES. CALL DIG SAFE AT LEAST 72 HOURS PRIOR TO THE COMMENCEMENT OF ANY DEMOLITION/CONSTRUCTION ACTIVITIES.
- ALL MATERIALS SCHEDULED TO BE REMOVED SHALL BECOME THE PROPERTY OF THE CONTRACTOR UNLESS OTHERWISE SPECIFIED. THE CONTRACTOR SHALL DISPOSE OF ALL MATERIALS OFF-SITE IN ACCORDANCE WITH ALL FEDERAL, STATE, AND LOCAL REGULATIONS, ORDINANCES AND CODES.
- COORDINATE REMOVAL, RELOCATION, DISPOSAL OR SALVAGE OF UTILITIES WITH THE OWNER AND APPROPRIATE UTILITY COMPANY.
- ANY EXISTING WORK OR PROPERTY DAMAGED OR DISRUPTED BY CONSTRUCTION/ DEMOLITION ACTIVITIES SHALL BE REPLACED OR REPAIRED TO MATCH ORIGINAL EXISTING CONDITIONS BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE OWNER.
- SAW CUT AND REMOVE PAVEMENT ONE (1) FOOT OFF PROPOSED EDGE OF PAVEMENT OR EXISTING CURB LINE IN ALL AREAS WHERE PAVEMENT TO BE REMOVED ADJUTS EXISTING PAVEMENT OR CONCRETE TO REMAIN.
- IT IS THE CONTRACTOR'S RESPONSIBILITY TO FAMILIARIZE THEMSELVES WITH THE CONDITIONS OF ALL OF THE PERMIT APPROVALS.
- THE CONTRACTOR SHALL OBTAIN AND PAY FOR ADDITIONAL PERMITS, NOTICES AND FEES NECESSARY TO COMPLETE THE WORK AND ARRANGE FOR AND PAY FOR NECESSARY INSPECTIONS AND APPROVALS FROM THE AUTHORITIES HAVING JURISDICTION.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL DEMOLITION AND OFF-SITE DISPOSAL OF MATERIALS REQUIRED TO COMPLETE THE WORK, EXCEPT FOR WORK NOTED TO BE COMPLETED BY OTHERS.
- UTILITIES SHALL BE TERMINATED AT THE MAIN LINE PER UTILITY COMPANY STANDARDS. THE CONTRACTOR SHALL REMOVE ALL ABANDONED UTILITIES LOCATED WITHIN THE LIMITS OF WORK.
- CONTRACTOR SHALL VERIFY ORIGIN OF ALL DRAINS AND UTILITIES PRIOR TO REMOVAL/TERMINATION TO DETERMINE IF DRAINS OR UTILITY IS ACTIVE, AND SERVICES ANY ON OR OFF-SITE STRUCTURE TO REMAIN. THE CONTRACTOR SHALL NOTIFY ENGINEER IMMEDIATELY OF ANY SUCH UTILITY FOUND AND SHALL MAINTAIN THESE UTILITIES UNTIL PERMANENT SOLUTION IS IN PLACE.
- PAVEMENT REMOVAL LIMITS ARE SHOWN FOR CONTRACTOR'S CONVENIENCE. ADDITIONAL PAVEMENT REMOVAL MAY BE REQUIRED DEPENDING ON THE CONTRACTOR'S OPERATION. CONTRACTOR TO VERIFY FULL LIMITS OF PAVEMENT REMOVAL PRIOR TO BID.

- ALL ITEMS WITHIN THE LIMIT OF WORK ARE TO REMAIN UNLESS SPECIFICALLY IDENTIFIED TO BE REMOVED OR OTHERWISE ALTERED BY THE CONTRACTOR. ITEMS TO BE REMOVED INCLUDE: CONCRETE, PAVEMENT, MANHOLES, CATCH BASINS, UNDERGROUND PIPING & UTILITIES, POLES, STAIRS, STRUCTURES, FENCES, RAMPS, BUILDING FOUNDATIONS, TREES, AND LANDSCAPING. THE CONTRACTOR SHALL CONFIRM WITH THE ENGINEER IF THE TREATMENT OF CERTAIN ITEMS IS UNCLEAR.
- COORDINATE ALL WORK WITHIN THE PUBLIC RIGHT OF WAYS WITH THE CITY OF PORTSMOUTH.
- REMOVE TREES AND BRUSH AS REQUIRED FOR COMPLETION OF WORK. CONTRACTOR SHALL GRUB AND REMOVE ALL STUMPS WITHIN LIMITS OF WORK AND DISPOSE OF OFF SITE IN ACCORDANCE WITH FEDERAL, STATE, AND LOCAL LAWS AND REGULATIONS.
- CONTRACTOR SHALL PROTECT ALL PROPERTY MONUMENTATION THROUGHOUT DEMOLITION AND CONSTRUCTION OPERATIONS. SHOULD ANY MONUMENTATION BE DISTURBED BY THE CONTRACTOR, THE CONTRACTOR SHALL EMPLOY A NEW HAMPSHIRE LICENSED SURVEYOR TO REPLACE DISTURBED MONUMENTS.
- PROVIDE INLET PROTECTION BARRIERS AT ALL CATCH BASINS/CURB INLETS WITHIN CONSTRUCTION LIMITS AS WELL AS CATCH BASINS/CURB INLETS THAT RECEIVE RUNOFF FROM CONSTRUCTION ACTIVITIES. INLET PROTECTION BARRIERS SHALL BE MAINTAINED FOR THE DURATION OF THE PROJECT. INLET PROTECTION BARRIERS SHALL BE "HIGH FLOW SILT SACK" BY ACF ENVIRONMENTAL OR EQUAL. INSPECT BARRIERS WEEKLY AND AFTER EACH RAIN EVENT OF 0.25 INCHES OR GREATER. CONTRACTOR SHALL COMPLETE A MAINTENANCE INSPECTION REPORT AFTER EACH INSPECTION. SEDIMENT DEPOSITS SHALL BE REMOVED AFTER EACH STORM EVENT OR MORE OFTEN IF THE FABRIC BECOMES CLOGGED OR SEDIMENT HAS ACCUMULATED TO 1/3 THE DESIGN DEPTH OF THE BARRIER.
- THE CONTRACTOR SHALL PHASE DEMOLITION AND CONSTRUCTION AS REQUIRED TO PROVIDE CONTINUOUS SERVICE TO EXISTING BUSINESSES AND HOMES THROUGHOUT THE CONSTRUCTION PERIOD. EXISTING BUSINESS AND HOME SERVICES INCLUDE, BUT ARE NOT LIMITED TO ELECTRICAL, COMMUNICATION, FIRE PROTECTION, DOMESTIC WATER AND SEWER SERVICES. TEMPORARY SERVICES, IF REQUIRED, SHALL COMPLY WITH ALL FEDERAL, STATE, LOCAL AND UTILITY COMPANY STANDARDS. CONTRACTOR SHALL PROVIDE DETAILED CONSTRUCTION SCHEDULE TO OWNER PRIOR TO ANY DEMOLITION/CONSTRUCTION ACTIVITIES AND SHALL COORDINATE TEMPORARY SERVICES TO AFFECTED PARTIES WITH THE UTILITY COMPANY AND AFFECTED ABUTTER.
- EROSION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO THE START OF ANY CLEARING OR DEMOLITION ACTIVITIES.
- THE CONTRACTOR SHALL PAY ALL COSTS NECESSARY FOR TEMPORARY PARTITIONING, BARRICADING, FENCING, SECURITY AND SAFETY DEVICES REQUIRED FOR THE MAINTENANCE OF A CLEAN AND SAFE CONSTRUCTION SITE.
- SAW CUT AND REMOVE PAVEMENT AND CONSTRUCT PAVEMENT TRENCH PATCH FOR ALL UTILITIES TO BE REMOVED AND PROPOSED UTILITIES LOCATED IN EXISTING PAVEMENT AREAS TO REMAIN.
- ALL CONDITIONS ON THIS PLAN SHALL REMAIN IN EFFECT IN PERPETUITY PURSUANT TO THE REQUIREMENTS OF THE SITE PLAN REVIEW REGULATIONS.
- WITH THE EXCEPTION OF THE NORWAY MAPLES IN THE 25' VEGETATED BUFFER, WHICH ARE TO REMAIN, INVASIVE SPECIES WITHIN THE 100' SHORELAND SETBACK WILL BE REMOVED. INVASIVE SPECIES WITHIN THE 25' VEGETATED BUFFER WILL BE FLAGGED IN FIELD BY THE LANDSCAPE ARCHITECT OR CERTIFIED ARBORIST TO BE REMOVED. INVASIVE SHRUBS WITHIN THE 25' VEGETATED BUFFER WITH CALIPER MEASURING GREATER THAN 3" SUCH AS BUCKTHORN AND AUTUMN OLIVE WILL BE FLUSH CUT REPEATEDLY TO KILL THE PLANT, LEAVING THE STUMPS IN PLACE. WOODY INVASIVES SMALLER THAN 3" CALIPER SHALL BE REMOVED WITH HAND TOOLS. AREAS OF SOIL DISTURBANCE FROM SUCH REMOVALS WILL BE LIMITED TO THE IMMEDIATE ROOT AREA SURROUNDING EACH PLANT, DRESSED WITH LOAM, REPLANTED WITH NEW ENGLAND WILDLIFE AND CONSERVATION SEED MIX AND STABILIZED WITH JUTE MESH STAKED IN PLACE. ALL OTHER AREAS DISTURBED BY HEADWALLS AND CURBS CUTTERS SHALL BE LOAMED, SEEDED WITH NEW ENGLAND WILDLIFE AND CONSERVATION SEED MIX AND STABILIZED WITH JUTE MESH.

NORTH MILL POND (TIDAL)



Proposed Multi-Family Development

Iron Horse Properties, LLC

105 Bartlett Street
Portsmouth,
New Hampshire

MARK	DATE	DESCRIPTION
H	1/20/2021	TAC Resubmission
G	11/18/2020	TAC Resubmission
F	10/28/2020	Wetland CUP Resubmission
E	5/20/2020	TAC Resubmission
D	4/29/2020	Wetland CUP Submission
C	4/20/2020	TAC Submission
B	2/6/2020	Design Review Submission
A	1/2/2020	ZBA Submission


PROJECT NO: C-0960-006
DATE: April 20, 2020
FILE: C-0960-006_C-SITE.DWG
DRAWN BY: NAH
CHECKED: PMC
APPROVED: BML

EXISTING CONDITIONS AND DEMOLITION PLAN

SCALE: AS SHOWN

C-101.2

Last Saved: 1/19/2021 11:19:05 AM
 Plotted On: Jan 19, 2021 11:19:05 AM
 Tighe & Bond: 11/19/2021 11:19:05 AM
 Figures: AutoCAD Sheet: C-0960-006_C-SITE.dwg



SITE DATA:
 PROJECT LOCATION: TAX MAP 157, LOT 1
 TAX MAP 157, LOT 2
 TAX MAP 164, LOT 1
 TAX MAP 164, LOT 4-2

SITE ZONING DISTRICT: 105 BARTLETT STREET
 PORTSMOUTH, NEW HAMPSHIRE
 CHARACTER DISTRICT 4 (CD4-W)
 CHARACTER DISTRICT 4 (CD4-L1)
 WEST END INCENTIVE OVERLAY DISTRICT

ALLOWED USE ON SITE: PROFESSIONAL OFFICE, BUSINESS OFFICE, MULTIFAMILY DWELLING

PROPOSED GROUND FLOOR USES:
 BUILDING A & B: RESIDENTIAL
 BUILDING C: RESIDENTIAL & AMENITY SPACE

DEVELOPMENT STANDARDS

BUILDING PLACEMENT (PRINCIPAL BUILDING):	REQUIRED (CD4-W)	PROPOSED (CD4-W)
MAX PRINCIPAL FRONT YARD:	10 FT	0 FT
MINIMUM SIDE YARD:	15 FT ⁽¹⁾	<6 FT ⁽²⁾
MINIMUM REAR YARD:	5 FT	214.54 FT
FRONT LOT LINE BUILDOUT:	50% MIN	54%

BUILDING AND LOT OCCUPATION:	REQUIRED (CD4-W)	PROPOSED (CD4-W)
MAXIMUM BUILDING BLOCK LENGTH:	200 FT	185 FT
MAXIMUM FAÇADE MODULATION LENGTH:	80 FT	<80 FT
MAXIMUM ENTRANCE SPACING:	50 FT	<50 FT
MAXIMUM BUILDING COVERAGE:	80% ⁽³⁾	±20.9%
MAXIMUM BUILDING FOOTPRINT:	20,000 SF ⁽⁴⁾	19,214 SF
MINIMUM LOT AREA:	5,000 SF	205,804 SF
MINIMUM LOT AREA PER DWELLING UNIT:	NR ⁽⁵⁾	58.1%
MINIMUM OPEN SPACE:	15%	15%
MAXIMUM GROUND FLOOR GFA PER USE:	15,000 SF	14,300 SF

- (1) - PER 10.516.20, MINIMUM SIDE YARD SETBACK ADJOINING A RAILROAD RIGHT OF WAY SHALL BE 15FT
- (2) - VARIANCE GRANTED BY ZONING BOARD OF ADJUSTMENT ON JANUARY 22, 2020
- (3) - MAXIMUM BUILDING COVERAGE ALLOWED IN THE WEST END INCENTIVE OVERLAY DISTRICT FOR PROVIDING AT LEAST 20% OF THE SITE TO BE ASSIGNED AS COMMUNITY SPACE.
- (4) - ADDITIONAL 5,000 SF OF GFA (INCREASED FROM 15,000 SF) ALLOWED FOR PROVIDING AT LEAST 20% OF THE SITE TO BE ASSIGNED AS COMMUNITY SPACE.
- (5) - NO MINIMUM LOT AREA PER DWELLING UNIT REQUIRED IN THE WEST END INCENTIVE OVERLAY DISTRICT FOR PROVIDING AT LEAST 20% OF THE SITE TO BE ASSIGNED AS COMMUNITY SPACE.

BUILDING FORM (PRINCIPAL BUILDING):

REQUIRED (CD4-W)	PROPOSED (CD4-W)	
BUILDING HEIGHT:	4 STORIES ⁽¹⁾ 50' MAX ⁽²⁾	4 STORIES, 49'-2"
MAXIMUM FINISHED FLOOR SURFACE OF GROUND FLOOR ABOVE SIDEWALK GRADE:	36 IN	<36 IN
MINIMUM GROUND STORY HEIGHT:	9 FT ⁽³⁾	12 FT
MINIMUM SECOND STORY HEIGHT:	N/A	
FAÇADE GLAZING:		
SHOPFRONT FAÇADE:	70% MIN	>70%
OTHER FAÇADE TYPES:	20% TO 50%	
ALLOWED ROOF TYPES:	FLAT, GABLE, HIP, GAMBREL, OR MANSARD	FLAT
ROOF PITCH, IF ANY:		
GABLE:	6:12 - 12:12	
HIP:	3:12 MIN	
MANSARD/GAMBREL:	6:12 - 30:12	
ALLOWED BUILDING TYPES:	APARTMENT BUILDING	APARTMENT BUILDING

- (1) - ADDITIONAL 1 STORY (INCREASED FROM 1 AND 3 RESPECTIVELY) ALLOWED FOR PROVIDING AT LEAST 20% OF THE SITE TO BE ASSIGNED AS COMMUNITY SPACE.
- (2) - ADDITIONAL 10' OF BUILDING HEIGHT (INCREASED FROM 20' AND 40' RESPECTIVELY) ALLOWED FOR PROVIDING AT LEAST 20% OF THE SITE TO BE ASSIGNED AS COMMUNITY SPACE.
- (3) - MINIMUM GROUND STORY HEIGHT ALLOWED IN WEST END INCENTIVE OVERLAY DISTRICT FOR PROVIDING AT LEAST 20% OF THE SITE TO BE ASSIGNED AS COMMUNITY SPACE.

COMMUNITY SPACE:

44,154 SF	47,703 SF
20%	23%

ZONING VARIANCES:

REQUIREMENT:	SECTION:	GRANTED:
(1) - MINIMUM SIDE YARD SETBACK FROM RAILROAD:	10.516.20	1/22/2020

OFF-STREET PARKING REQUIREMENTS:

PARKING SPACES REQUIRED:

DWELLING UNITS: 500 SF TO 750 SF 1.0 SPACES PER UNIT	BUILDING A, 16 UNITS BUILDING B, 31 UNITS BUILDING C, 17 UNITS	16 SPACES 31 SPACES 17 SPACES
TOTAL MINIMUM PARKING SPACES REQUIRED =		64 SPACES
OVER 750 SF 1.3 SPACES PER UNIT	BUILDING A, 20 UNITS BUILDING B, 39 UNITS BUILDING C, 29 UNITS	26.0 SPACES 50.7 SPACES 37.7 SPACES
TOTAL MINIMUM PARKING SPACES REQUIRED =		114.4 SPACES
VISITORS: 1 SPACE FOR EVERY 5 DWELLING UNITS	152 UNITS	31 SPACES
TOTAL MINIMUM PARKING SPACES REQUIRED =		210 SPACES

TOTAL PARKING SPACES PROVIDED:

TOTAL PARKING SPACES PROVIDED = 95 SPACES (SURFACE PARKING)
 53 SPACES (BUILDING A, UNDERGROUND)
 42 SPACES (BUILDING B, UNDERGROUND)
 20 SPACES (PRIVATE ROADWAY)⁽¹⁾
 210 SPACES

ADA SPACES REQUIRED= 7 SPACES (FOR 201-300 FACILITY TOTAL)
 ADA SPACES PROVIDED= 7 SPACES (5 SPACES INCLUDED IN SURFACE PARKING COUNT OF 95, 2 SPACES INCLUDED IN PRIVATE ROADWAY COUNT OF 20)

(1) - CONDITIONAL USE PERMIT REQUIRED FOR SHARED PARKING ON SEPARATE LOT

PARKING STALL LAYOUT:


REQUIRED	PROPOSED
8.5' X 19'	8.5' X 19'
24 FT	24 FT

BIKE SPACES REQUIRED:
 1 BIKE SPACE / 5 DWELLING UNITS, MAXIMUM OF 30 SPACES
 30 SPACES 30 SPACES*

*INDOOR BIKE STORAGE WILL BE PROVIDED THAT MEETS OR EXCEEDS THE REQUIREMENT.

LEGEND

	PROPERTY LINE
	PROPOSED PROPERTY LINE
	PROPOSED EDGE OF PAVEMENT
	PROPOSED CURB
	PROPOSED BUILDING
	PROPOSED PAVEMENT SECTION
	PROPOSED POROUS PAVEMENT SECTION
	PROPOSED CONCRETE SIDEWALK
	PROPOSED BOLLARD
	BUILDING
	TYPICAL
	COORDINATE
	30'R
	VGC
	SGC
	MVGC



Proposed Multi-Family Development

Iron Horse Properties, LLC

105 Bartlett Street
 Portsmouth,
 New Hampshire


H	1/20/2021	TAC Resubmission
G	11/18/2020	TAC Resubmission
F	10/28/2020	Wetland CUP Resubmission
E	5/20/2020	TAC Resubmission
D	4/29/2020	Wetland CUP Submission
C	4/20/2020	TAC Submission
B	2/6/2020	Design Review Submission
A	1/2/2020	ZBA Submission
MARK	DATE	DESCRIPTION

PROJECT NO:	C-0960-006
DATE:	April 20, 2020
FILE:	C-0960-006_C-SITE.DWG
DRAWN BY:	NAH
CHECKED:	PMC
APPROVED:	BML


OVERALL SITE PLAN

SCALE: AS SHOWN

C-102






Last Saved: 1/19/2021 11:19:09 AM By: Mahanien
 Plotted On: Jan 19, 2021 5:05:09 PM
 Tighe & Bond: E:\Projects\CAD\Drawings - Figures\AutoCAD\Sheet\C-0960-006_C-SITE.dwg



- SITE NOTES:**
1. STRIPE PARKING AREAS AS SHOWN, INCLUDING PARKING SPACES, STOP BARS, ADA SYMBOLS, PAINTED ISLANDS, CROSS WALKS, ARROWS, LEGENDS AND CENTERLINES SHALL BE THERMOPLASTIC MATERIAL. THERMOPLASTIC MATERIAL SHALL MEET THE REQUIREMENTS OF AASHTO AASHTO M249. (ALL MARKINGS EXCEPT CENTERLINE AND MEDIAN ISLANDS TO BE CONSTRUCTED USING WHITE TRAFFIC PAINT. CENTERLINE AND MEDIAN ISLANDS TO BE CONSTRUCTED USING YELLOW TRAFFIC PAINT. ALL TRAFFIC PAINT SHALL MEET THE REQUIREMENTS OF AASHTO M248 TYPE "F").
 2. ALL PAVEMENT MARKINGS AND SIGNS TO CONFORM TO "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES", "STANDARD ALPHABETS FOR HIGHWAY SIGNS AND PAVEMENT MARKINGS", AND THE AMERICANS WITH DISABILITIES ACT REQUIREMENTS, LATEST EDITIONS.
 3. SEE DETAILS FOR PARKING STALL MARKINGS, ADA SYMBOLS, SIGNS AND SIGN POSTS.
 4. CENTERLINES SHALL BE FOUR (4) INCH WIDE YELLOW LINES. STOP BARS SHALL BE EIGHTEEN (18) INCHES WIDE.
 5. PAINTED ISLANDS SHALL BE FOUR (4) INCH WIDE DIAGONAL LINES AT 3'-0" O.C. BORDERED BY FOUR (4) INCH WIDE LINES.
 6. THE CONTRACTOR SHALL EMPLOY A NEW HAMPSHIRE LICENSED LAND SURVEYOR TO DETERMINE ALL LINES AND GRADES.
 7. CLEAN AND COAT VERTICAL FACE OF EXISTING PAVEMENT AT SAW CUT LINE WITH RS-1 EMULSION IMMEDIATELY PRIOR TO PLACING NEW BITUMINOUS CONCRETE.
 8. ALL MATERIALS AND CONSTRUCTION SHALL CONFORM WITH APPLICABLE FEDERAL, STATE, AND LOCAL CODES & SPECIFICATIONS.
 9. COORDINATE ALL WORK WITHIN PUBLIC RIGHT OF WAY WITH THE CITY OF PORTSMOUTH.
 10. CONTRACTOR TO SUBMIT AS-BUILT PLANS IN DIGITAL FORMAT (.DWG AND .PDF FILES) ON DISK TO THE OWNER AND ENGINEER UPON COMPLETION OF THE PROJECT. AS-BUILTS SHALL BE PREPARED AND CERTIFIED BY A NEW HAMPSHIRE LICENSED LAND SURVEYOR.
 11. SEE BUILDING DRAWINGS FOR ALL CONCRETE PADS & SIDEWALKS ADJACENT TO BUILDING.
 12. ALL WORK SHALL CONFORM TO THE CITY OF PORTSMOUTH DEPARTMENT OF PUBLIC WORKS, STANDARD SPECIFICATIONS.
 13. CONTRACTOR TO PROVIDE BACKFILL AND COMPACTION AT CURB LINE AFTER CONCRETE FORMS FOR SIDEWALKS AND PADS HAVE BEEN STRIPPED. COORDINATE WITH BUILDING CONTRACTOR.
 14. COORDINATE ALL WORK ADJACENT TO BUILDING WITH BUILDING CONTRACTOR.
 15. THE PROPERTY MANAGER WILL BE RESPONSIBLE FOR TIMELY SNOW REMOVAL FROM ALL PRIVATE SIDEWALKS, DRIVEWAYS, AND PARKING AREAS. SNOW REMOVAL WILL BE HAULED OFF-SITE AND LEGALLY DISPOSED OF WHEN SNOW BANKS EXCEED 3 FEET IN HEIGHT.
 16. ALL DIMENSIONS ARE TO THE FACE OF CURB UNLESS OTHERWISE NOTED.
 17. ALL CONDITIONS ON THIS PLAN SHALL REMAIN IN EFFECT IN PERPETUITY PURSUANT TO THE REQUIREMENTS OF THE SITE PLAN REVIEW REGULATIONS.
 18. THIS SITE PLAN SHALL BE RECORDED IN THE ROCKINGHAM COUNTY REGISTRY OF DEEDS. ALL IMPROVEMENTS SHOWN ON THIS SITE PLAN SHALL BE CONSTRUCTED AND MAINTAINED IN ACCORDANCE WITH THE PLAN BY THE PROPERTY OWNER AND ALL FUTURE PROPERTY OWNERS. NO CHANGES SHALL BE MADE TO THIS SITE PLAN WITHOUT THE EXPRESS APPROVAL OF THE PORTSMOUTH PLANNING DIRECTOR.
 19. THE APPLICANT SHALL HAVE A SITE SURVEY CONDUCTED BY A RADIO COMMUNICATIONS CARRIER APPROVED BY THE CITY'S COMMUNICATIONS DIVISION. THE RADIO COMMUNICATIONS CARRIER MUST BE FAMILIAR AND CONVERSANT WITH THE POLICE AND RADIO CONFIGURATION. IF THE SITE SURVEY INDICATES THAT IT IS NECESSARY TO INSTALL A SIGNAL REPEATER EITHER ON OR NEAR THE PROPOSED PROJECT, THOSE COSTS SHALL BE THE RESPONSIBILITY OF THE PROPERTY OWNER. THE OWNER SHALL COORDINATE WITH THE SUPERVISOR OF RADIO COMMUNICATIONS FOR THE CITY.
 20. ALL TREES TO BE PLANTED ARE TO BE INSTALLED UNDER THE SUPERVISION OF THE CITY OF PORTSMOUTH DPW USING STANDARD INSTALLATION METHODS.
 21. THE APPLICATION SHALL PREPARE A CONSTRUCTION MITIGATION AND MANAGEMENT PLAN (CMMP) FOR REVIEW AND APPROVAL BY THE CITY'S LEGAL AND PLANNING DEPARTMENTS.

- LEGEND**
- PROPERTY LINE
 - PROPOSED PROPERTY LINE
 - PROPOSED EDGE OF PAVEMENT
 - PROPOSED CURB
 - ▭ PROPOSED BUILDING
 - ▭ PROPOSED PAVEMENT SECTION
 - ▭ PROPOSED POROUS PAVEMENT SECTION
 - ▭ PROPOSED CONCRETE SIDEWALK
 - PROPOSED BOLLARD
 - BLDG BUILDING
 - TYP TYPICAL
 - COORD COORDINATE
 - 30'R PROPOSED CURB RADIUS
 - VGC PROPOSED VERTICAL GRANITE CURB
 - SGC PROPOSED SLOPED GRANITE CURB
 - MVGC PROPOSED MOUNTABLE VERTICAL GRANITE CURB



Proposed Multi-Family Development

Iron Horse Properties, LLC

105 Bartlett Street
Portsmouth,
New Hampshire


MARK	DATE	DESCRIPTION
H	1/20/2021	TAC Resubmission
G	11/18/2020	TAC Resubmission
F	10/28/2020	Wetland CUP Resubmission
E	5/20/2020	TAC Resubmission
D	4/29/2020	Wetland CUP Submission
C	4/20/2020	TAC Submission
B	2/6/2020	Design Review Submission
A	1/2/2020	ZBA Submission

PROJECT NO:	C-0960-006
DATE:	April 20, 2020
FILE:	C-0960-006_C-SITE.DWG
DRAWN BY:	NAH
CHECKED:	PMC
APPROVED:	BML

SITE PLAN

SCALE: AS SHOWN

C-102.1






LEGEND

- PROPERTY LINE
- - - PROPOSED PROPERTY LINE
- ==== PROPOSED EDGE OF PAVEMENT
- ===== PROPOSED CURB
- [] PROPOSED BUILDING
- [] PROPOSED PAVEMENT SECTION
- [] PROPOSED POROUS PAVEMENT SECTION
- [] PROPOSED CONCRETE SIDEWALK
- BLDG
- TYP
- COORD
- 30'R
- VGC
- SGC
- MVGC
- PROPOSED BOLLARD
- BUILDING
- TYPICAL
- COORDINATE
- PROPOSED CURB RADIUS
- PROPOSED VERTICAL GRANITE CURB
- PROPOSED SLOPED GRANITE CURB
- PROPOSED MOUNTABLE VERTICAL GRANITE CURB

SITE NOTES

1. STRIPE PARKING AREAS AS SHOWN, INCLUDING PARKING SPACES, STOP BARS, ADA SYMBOLS, PAINTED ISLANDS, CROSS WALKS, ARROWS, LEGENDS AND CENTERLINES SHALL BE THERMOPLASTIC MATERIAL. THERMOPLASTIC MATERIAL SHALL MEET THE REQUIREMENTS OF AASHTO M249. (ALL MARKINGS EXCEPT CENTERLINE AND MEDIAN ISLANDS TO BE CONSTRUCTED USING WHITE TRAFFIC PAINT. CENTERLINE AND MEDIAN ISLANDS TO BE CONSTRUCTED USING YELLOW TRAFFIC PAINT. ALL TRAFFIC PAINT SHALL MEET THE REQUIREMENTS OF AASHTO M248 TYPE "F").
2. ALL PAVEMENT MARKINGS AND SIGNS TO CONFORM TO "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES", "STANDARD ALPHABETS FOR HIGHWAY SIGNS AND PAVEMENT MARKINGS", AND THE AMERICANS WITH DISABILITIES ACT REQUIREMENTS, LATEST EDITIONS.
3. SEE DETAILS FOR PARKING STALL MARKINGS, ADA SYMBOLS, SIGNS AND SIGN POSTS.
4. CENTERLINES SHALL BE FOUR (4) INCH WIDE YELLOW LINES. STOP BARS SHALL BE EIGHTEEN (18) INCHES WIDE.
5. PAINTED ISLANDS SHALL BE FOUR (4) INCH WIDE DIAGONAL LINES AT 3'-0" O.C. BORDERED BY FOUR (4) INCH WIDE LINES.
6. THE CONTRACTOR SHALL EMPLOY A NEW HAMPSHIRE LICENSED LAND SURVEYOR TO DETERMINE ALL LINES AND GRADES.
7. CLEAN AND COAT VERTICAL FACE OF EXISTING PAVEMENT AT SAW CUT LINE WITH RS-1 EMULSION IMMEDIATELY PRIOR TO PLACING NEW BITUMINOUS CONCRETE.
8. ALL MATERIALS AND CONSTRUCTION SHALL CONFORM WITH APPLICABLE FEDERAL, STATE, AND LOCAL CODES & SPECIFICATIONS.
9. COORDINATE ALL WORK WITHIN PUBLIC RIGHT OF WAY WITH THE CITY OF PORTSMOUTH.
10. CONTRACTOR TO SUBMIT AS-BUILT PLANS IN DIGITAL FORMAT (.DWG AND .PDF FILES) ON DISK TO THE OWNER AND ENGINEER UPON COMPLETION OF THE PROJECT. AS-BUILTS SHALL BE PREPARED AND CERTIFIED BY A NEW HAMPSHIRE LICENSED LAND SURVEYOR.
11. SEE BUILDING DRAWINGS FOR ALL CONCRETE PADS & SIDEWALKS ADJACENT TO BUILDING.
12. ALL WORK SHALL CONFORM TO THE CITY OF PORTSMOUTH DEPARTMENT OF PUBLIC WORKS, STANDARD SPECIFICATIONS.
13. CONTRACTOR TO PROVIDE BACKFILL AND COMPACTION AT CURB LINE AFTER CONCRETE FORMS FOR SIDEWALKS AND PADS HAVE BEEN STRIPPED. COORDINATE WITH BUILDING CONTRACTOR.
14. COORDINATE ALL WORK ADJACENT TO BUILDING WITH BUILDING CONTRACTOR.
15. THE PROPERTY MANAGER WILL BE RESPONSIBLE FOR TIMELY SNOW REMOVAL FROM ALL PRIVATE SIDEWALKS, DRIVEWAYS, AND PARKING AREAS. SNOW REMOVAL WILL BE HAULED OFF-SITE AND LEGALLY DISPOSED OF WHEN SNOW BANKS EXCEED 3 FEET IN HEIGHT.
16. ALL DIMENSIONS ARE TO THE FACE OF CURB UNLESS OTHERWISE NOTED.
17. ALL CONDITIONS ON THIS PLAN SHALL REMAIN IN EFFECT IN PERPETUITY PURSUANT TO THE REQUIREMENTS OF THE SITE PLAN REVIEW REGULATIONS.
18. THIS SITE PLAN SHALL BE RECORDED IN THE ROCKINGHAM COUNTY REGISTRY OF DEEDS. ALL IMPROVEMENTS SHOWN ON THIS SITE PLAN SHALL BE CONSTRUCTED AND MAINTAINED IN ACCORDANCE WITH THE PLAN BY THE PROPERTY OWNER AND ALL FUTURE PROPERTY OWNERS. NO CHANGES SHALL BE MADE TO THIS SITE PLAN WITHOUT THE EXPRESS APPROVAL OF THE PORTSMOUTH PLANNING DIRECTOR.
19. THE APPLICANT SHALL HAVE A SITE SURVEY CONDUCTED BY A RADIO COMMUNICATIONS CARRIER APPROVED BY THE CITY'S COMMUNICATIONS DIVISION. THE RADIO COMMUNICATIONS CARRIER MUST BE FAMILIAR AND CONVERSANT WITH THE POLICE AND RADIO CONFIGURATION. IF THE SITE SURVEY INDICATES THAT IT IS NECESSARY TO INSTALL A SIGNAL REPEATER EITHER ON OR NEAR THE PROPOSED PROJECT, THOSE COSTS SHALL BE THE RESPONSIBILITY OF THE PROPERTY OWNER. THE OWNER SHALL COORDINATE WITH THE SUPERVISOR OF RADIO COMMUNICATIONS FOR THE CITY.
20. ALL TREES TO BE PLANTED ARE TO BE INSTALLED UNDER THE SUPERVISION OF THE CITY OF PORTSMOUTH DPW USING STANDARD INSTALLATION METHODS.
21. THE APPLICATION SHALL PREPARE A CONSTRUCTION MITIGATION AND MANAGEMENT PLAN (CMMP) FOR REVIEW AND APPROVAL BY THE CITY'S LEGAL AND PLANNING DEPARTMENTS.

NORTH MILL POND (TIDAL)



Proposed Multi-Family Development

Iron Horse Properties, LLC

105 Bartlett Street
Portsmouth,
New Hampshire

MARK	DATE	DESCRIPTION
H	1/20/2021	TAC Resubmission
G	11/18/2020	TAC Resubmission
F	10/28/2020	Wetland CUP Resubmission
E	5/20/2020	TAC Resubmission
D	4/29/2020	Wetland CUP Submission
C	4/20/2020	TAC Submission
B	2/6/2020	Design Review Submission
A	1/2/2020	ZBA Submission


PROJECT NO:	C-0960-006
DATE:	April 20, 2020
FILE:	C-0960-006_C-SITE.DWG
DRAWN BY:	NAH
CHECKED:	PMC
APPROVED:	BML

SITE PLAN

SCALE: AS SHOWN

C-102.2

Last Saved: 1/19/2021
 Plotted On: Jan 19, 2021 5:06pm By: Mahliansen
 Tighe & Bond: P:\CUB950\Cambridge\C-0960-006_105 Bartlett Street\Drawings - Figures\AutoCAD\Sheet\C-0960-006_C-SITE.dwg







LEGEND

- PROPERTY LINE
- - - PROPOSED PROPERTY LINE
- ==== PROPOSED EDGE OF PAVEMENT
- ===== PROPOSED CURB
- [Hatched Box] PROPOSED BUILDING
- [Hatched Box] PROPOSED PAVEMENT SECTION
- [Hatched Box] PROPOSED POROUS PAVEMENT SECTION
- [Hatched Box] PROPOSED CONCRETE SIDEWALK
- PROPOSED BOLLARD
- BLDG TYP BUILDING TYPICAL
- COORD 30'R COORDINATE
- VGC PROPOSED VERTICAL GRANITE CURB
- SGC PROPOSED SLOPED GRANITE CURB
- MVGC PROPOSED MOUNTABLE VERTICAL GRANITE CURB

SITE NOTES:

1. STRIPE PARKING AREAS AS SHOWN, INCLUDING PARKING SPACES, STOP BARS, ADA SYMBOLS, PAINTED ISLANDS, CROSS WALKS, ARROWS, LEGENDS AND CENTERLINES SHALL BE THERMOPLASTIC MATERIAL. THERMOPLASTIC MATERIAL SHALL MEET THE REQUIREMENTS OF AASHTO AASHTO M249. (ALL MARKINGS EXCEPT CENTERLINE AND MEDIAN ISLANDS TO BE CONSTRUCTED USING WHITE TRAFFIC PAINT. CENTERLINE AND MEDIAN ISLANDS TO BE CONSTRUCTED USING YELLOW TRAFFIC PAINT. ALL TRAFFIC PAINT SHALL MEET THE REQUIREMENTS OF AASHTO M248 TYPE "F").
2. ALL PAVEMENT MARKINGS AND SIGNS TO CONFORM TO "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES", "STANDARD ALPHABETS FOR HIGHWAY SIGNS AND PAVEMENT MARKINGS", AND THE AMERICANS WITH DISABILITIES ACT REQUIREMENTS, LATEST EDITIONS.
3. SEE DETAILS FOR PARKING STALL MARKINGS, ADA SYMBOLS, SIGNS AND SIGN POSTS.
4. CENTERLINES SHALL BE FOUR (4) INCH WIDE YELLOW LINES. STOP BARS SHALL BE EIGHTEEN (18) INCHES WIDE.
5. PAINTED ISLANDS SHALL BE FOUR (4) INCH WIDE DIAGONAL LINES AT 3'-0" O.C. BORDERED BY FOUR (4) INCH WIDE LINES.
6. THE CONTRACTOR SHALL EMPLOY A NEW HAMPSHIRE LICENSED LAND SURVEYOR TO DETERMINE ALL LINES AND GRADES.
7. CLEAN AND COAT VERTICAL FACE OF EXISTING PAVEMENT AT SAW CUT LINE WITH RS-1 EMULSION IMMEDIATELY PRIOR TO PLACING NEW BITUMINOUS CONCRETE.
8. ALL MATERIALS AND CONSTRUCTION SHALL CONFORM WITH APPLICABLE FEDERAL, STATE, AND LOCAL CODES & SPECIFICATIONS.
9. COORDINATE ALL WORK WITHIN PUBLIC RIGHT OF WAY WITH THE CITY OF PORTSMOUTH.
10. CONTRACTOR TO SUBMIT AS-BUILT PLANS IN DIGITAL FORMAT (.DWG AND .PDF FILES) ON DISK TO THE OWNER AND ENGINEER UPON COMPLETION OF THE PROJECT. AS-BUILTS SHALL BE PREPARED AND CERTIFIED BY A NEW HAMPSHIRE LICENSED LAND SURVEYOR.
11. SEE BUILDING DRAWINGS FOR ALL CONCRETE PADS & SIDEWALKS ADJACENT TO BUILDING.
12. ALL WORK SHALL CONFORM TO THE CITY OF PORTSMOUTH DEPARTMENT OF PUBLIC WORKS, STANDARD SPECIFICATIONS.
13. CONTRACTOR TO PROVIDE BACKFILL AND COMPACTION AT CURB LINE AFTER CONCRETE FORMS FOR SIDEWALKS AND PADS HAVE BEEN STRIPPED. COORDINATE WITH BUILDING CONTRACTOR.
14. COORDINATE ALL WORK ADJACENT TO BUILDING WITH BUILDING CONTRACTOR.
15. THE PROPERTY MANAGER WILL BE RESPONSIBLE FOR TIMELY SNOW REMOVAL FROM ALL PRIVATE SIDEWALKS, DRIVEWAYS, AND PARKING AREAS. SNOW REMOVAL WILL BE HAULED OFF-SITE AND LEGALLY DISPOSED OF WHEN SNOW BANKS EXCEED 3 FEET IN HEIGHT.
16. ALL DIMENSIONS ARE TO THE FACE OF CURB UNLESS OTHERWISE NOTED.
17. ALL CONDITIONS ON THIS PLAN SHALL REMAIN IN EFFECT IN PERPETUITY PURSUANT TO THE REQUIREMENTS OF THE SITE PLAN REVIEW REGULATIONS.
18. THIS SITE PLAN SHALL BE RECORDED IN THE ROCKINGHAM COUNTY REGISTRY OF DEEDS. ALL IMPROVEMENTS SHOWN ON THIS SITE PLAN SHALL BE CONSTRUCTED AND MAINTAINED IN ACCORDANCE WITH THE PLAN BY THE PROPERTY OWNER AND ALL FUTURE PROPERTY OWNERS. NO CHANGES SHALL BE MADE TO THIS SITE PLAN WITHOUT THE EXPRESS APPROVAL OF THE PORTSMOUTH PLANNING DIRECTOR.
19. THE APPLICANT SHALL HAVE A SITE SURVEY CONDUCTED BY A RADIO COMMUNICATIONS CARRIER APPROVED BY THE CITY'S COMMUNICATIONS DIVISION. THE RADIO COMMUNICATIONS CARRIER MUST BE FAMILIAR AND CONVERSANT WITH THE POLICE AND RADIO CONFIGURATION. IF THE SITE SURVEY INDICATES THAT IT IS NECESSARY TO INSTALL A SIGNAL REPEATER EITHER ON OR NEAR THE PROPOSED PROJECT, THESE COSTS SHALL BE THE RESPONSIBILITY OF THE PROPERTY OWNER. THE OWNER SHALL COORDINATE WITH THE SUPERVISOR OF RADIO COMMUNICATIONS FOR THE CITY.
20. ALL TREES TO BE PLANTED ARE TO BE INSTALLED UNDER THE SUPERVISION OF THE CITY OF PORTSMOUTH DPW USING STANDARD INSTALLATION METHODS.
21. THE APPLICATION SHALL PREPARE A CONSTRUCTION MITIGATION AND MANAGEMENT PLAN (CMMP) FOR REVIEW AND APPROVAL BY THE CITY'S LEGAL AND PLANNING DEPARTMENTS.

NORTH MILL POND (TIDAL)



Proposed Multi-Family Development

Iron Horse Properties, LLC

105 Bartlett Street
Portsmouth,
New Hampshire

MARK	DATE	DESCRIPTION
H	1/20/2021	TAC Resubmission
G	11/18/2020	TAC Resubmission
F	10/28/2020	Wetland CUP Resubmission
E	5/20/2020	TAC Resubmission
D	4/29/2020	Wetland CUP Submission
C	4/20/2020	TAC Submission
B	2/6/2020	Design Review Submission
A	1/2/2020	ZBA Submission


PROJECT NO:	C-0960-006
DATE:	April 20, 2020
FILE:	C-0960-006_C-SITE.DWG
DRAWN BY:	NAH
CHECKED:	PMC
APPROVED:	BML

BASEMENT LEVEL SITE PLAN

SCALE: AS SHOWN

C-102.3

Last Saved: 1/19/2021 11:19:06 AM By: MAHansen
 Plotted On: Jan 19, 2021 5:06 PM By: MAHansen
 Tighe & Bond: P:\C\0960-006_105 Bartlett Street Drawings - Figures\AutoCAD\Sheet\C-0960-006_C-SITE.dwg



GRADING AND DRAINAGE NOTES:

1. COMPACTION REQUIREMENTS:
BELOW PAVED OR CONCRETE AREAS 95%
TRENCH BEDDING MATERIAL AND SAND BLANKET BACKFILL 95%
BELOW LOAM AND SEED AREAS 90%
* ALL PERCENTAGES OF COMPACTION SHALL BE OF THE MAXIMUM DRY DENSITY AT THE OPTIMUM MOISTURE CONTENT AS DETERMINED AND CONTROLLED IN ACCORDANCE WITH ASTM D-1557, METHOD C FIELD DENSITY TESTS SHALL BE MADE IN ACCORDANCE WITH ASTM D-1556 OR ASTM-2922.
2. ALL STORM DRAINAGE PIPES SHALL BE HIGH DENSITY POLYETHYLENE (HANCOR HI-Q, ADS N-12 OR EQUAL), UNLESS OTHERWISE SPECIFIED.
3. SEE UTILITY PLAN FOR ALL SITE UTILITY INFORMATION.
4. ADJUST ALL MANHOLES, CATCH BASINS, CURB BOXES, ETC. WITHIN LIMITS OF WORK TO FINISH GRADE.
5. CONTRACTOR SHALL PROVIDE A FINISH PAVEMENT SURFACE AND LAWN AREAS FREE OF LOW SPOTS AND PONDING AREAS. CRITICAL AREAS INCLUDE BUILDING ENTRANCES, EXITS, RAMPS AND LOADING DOCK AREAS ADJACENT TO THE BUILDING.
6. CONTRACTOR SHALL THOROUGHLY CLEAN ALL CATCH BASINS AND DRAIN LINES, WITHIN THE LIMIT OF WORK, OF SEDIMENT IMMEDIATELY UPON COMPLETION OF CONSTRUCTION.
7. ALL MATERIALS AND CONSTRUCTION SHALL CONFORM WITH APPLICABLE FEDERAL, STATE AND LOCAL CODES.
8. ALL DISTURBED AREAS NOT TO BE PAVED OR OTHERWISE TREATED SHALL RECEIVE 6" LOAM, SEED FERTILIZER AND MULCH.
9. ALL STORM DRAIN CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE NHDOT STANDARD SPECIFICATIONS FOR HIGHWAYS AND BRIDGES, LATEST EDITION.
10. ALL PROPOSED CATCH BASINS SHALL BE EQUIPPED WITH OIL/GAS SEPARATOR HOODS AND 4' SUMPS.
11. ALL WORK SHALL CONFORM TO THE CITY OF PORTSMOUTH DEPARTMENT OF PUBLIC WORKS, STANDARD SPECIFICATIONS AND WITH THE STATE OF NEW HAMPSHIRE DEPARTMENT OF TRANSPORTATION, "STANDARD SPECIFICATIONS OF ROAD AND BRIDGE CONSTRUCTION", CURRENT EDITION.
12. CONTRACTOR TO SUBMIT AS-BUILT PLANS IN DIGITAL FORMAT (.DWG AND .PDF FILES) ON DISK TO THE OWNER AND ENGINEER UPON COMPLETION OF THE PROJECT. AS-BUILTS SHALL BE PREPARED AND CERTIFIED BY A NEW HAMPSHIRE LICENSED LAND SURVEYOR.
13. SEE EXISTING CONDITIONS PLAN FOR BENCH MARK INFORMATION.
14. AREAS DISTURBED WITHIN THE 25' VEGETATED BUFFER BY HEADWALLS AND CULVERT CONSTRUCTION SHALL BE LOAMED, SEEDED WITH NEW ENGLAND WILDLIFE AND CONSERVATION SEED MIX AND STABILIZED WITH JUTE MESH.

LEGEND


- PROPOSED MAJOR CONTOUR LINE
- PROPOSED MINOR CONTOUR LINE
- PROPOSED DRAIN LINE (TYP)
- PROPOSED UNDERDRAIN
- PROPOSED SILT SOCK
- INLET PROTECTION SILT SACK
- PROPOSED CATCHBASIN
- PROPOSED DOUBLE GRATE CATCHBASIN
- PROPOSED DRAIN MANHOLE
- PROPOSED YARD DRAIN
- BUILDING
- TYPICAL COORDINATE
- TOP OF CURB
- BOTTOM OF CURB
- HEADWALL

DRAINAGE STRUCTURE TABLE


CB1242 RIM=9.30 INV.OUT=5.80 SW	PCB3 RIM=8.40 INV.OUT=5.50 NW	PCB9 RIM=12.65 INV.OUT=8.65 NW	PDMH3 RIM=10.65 INV.IN=4.30 SE INV.OUT=4.20 NE	PDMH9 RIM=14.05 INV.IN=4.60 SE INV.OUT=4.60 NW	PDMH15 RIM=10.00 INV.IN=6.45 NE INV.OUT=6.35 SW	PDMH21 RIM=11.90 INV.OUT=8.88 N
CB1243 RIM=9.55 INV.IN=6.65 NW INV.OUT=6.55 SE	PCB4 RIM=8.55 INV.OUT=6.10 NW	PCB10 RIM=12.15 INV.OUT=8.60 NW	PDMH4 RIM=11.70 INV.IN=3.45 SW INV.OUT=4.30 NE	PDMH10 RIM=13.95 INV.IN=6.50 SW INV.OUT=6.40 NW	PDMH16 RIM=13.50 INV.IN=10.50 SW INV.IN=10.50 NW INV.OUT=10.40 NE	POS1 RIM=10.50 INV.OUT=7.15 E
CB1244 RIM=10.00 INV.OUT=6.85 SW	PCB5 RIM=9.60 INV.OUT=6.10 NW	PCB11 RIM=8.60 INV.OUT=5.80 NE	PDMH5 RIM=11.30 INV.IN=5.05 NE INV.OUT=4.95 SW	PDMH11 RIM=12.00 INV.IN=4.60 SE INV.OUT=4.50 W	PDMH17 RIM=9.70 INV.IN=5.60 NE INV.OUT=5.50 NW	PVD1 RIM=12.50 INV.OUT=7.70 N
CB1264 RIM=9.50 INV.OUT=6.50 NE	PCB6 RIM=9.80 INV.OUT=6.30 SW	PCB12 RIM=8.60 INV.OUT=5.45 S	PDMH6 RIM=9.85 INV.IN=6.00 NE INV.IN=5.20 S INV.OUT=5.10 NE	PDMH12 RIM=13.00 INV.IN=4.00 E INV.IN=5.00 W INV.IN=3.80 SE INV.OUT=3.70 N	PDMH18 RIM=15.50 INV.IN=10.10 SW INV.IN=11.50 NE INV.OUT=10.00 NW	PVD2 RIM=12.30 INV.IN=7.50 S INV.OUT=7.40 NE
PCB1 RIM=8.50 INV.OUT=5.30 E	PCB7 RIM=10.00 INV.OUT=7.00 NE	PDMH1 RIM=8.75 INV.IN=5.20 W INV.IN=5.20 S INV.OUT=5.20 SE	PDMH7 RIM=12.27 INV.IN=6.60 NW INV.IN=5.00 SE INV.OUT=6.50 SE	PDMH13 RIM=8.75 INV.IN=5.35 SW INV.IN=5.35 N INV.OUT=5.35 NE	PDMH19 RIM=16.30 INV.IN=9.00 SE INV.IN=6.00 SW INV.OUT=5.80 NW	PVD3 RIM=11.00 INV.IN=7.10 SW INV.IN=8.00 NW INV.OUT=7.00 NE
PCB2 RIM=8.45 INV.OUT=5.30 N	PCB8 RIM=10.75 INV.OUT=7.50 NW	PDMH2 RIM=9.90 INV.IN=5.00 SW INV.IN=6.60 SW INV.OUT=4.90 NE	PDMH8 RIM=11.35 INV.IN=6.25 NW INV.IN=6.25 SE INV.IN=6.10 SW INV.OUT=6.00 NE	PDMH14 RIM=9.60 INV.IN=5.40 SE INV.IN=5.40 NE INV.IN=4.70 SW INV.OUT=4.65 NW	PDMH20 RIM=11.80 INV.OUT=8.88 SE	PVD4 RIM=13.00 INV.OUT=10.70 SE
						PVD5 RIM=11.50 INV.IN=7.00 W INV.IN=7.15 S INV.OUT=7.05 E

EROSION CONTROL NOTES:

1. INSTALL EROSION CONTROL BARRIERS AS SHOWN AS FIRST ORDER OF WORK.
2. SEE GENERAL EROSION CONTROL NOTES ON "EROSION CONTROL NOTES & DETAILS SHEET".
3. PROVIDE INLET PROTECTION AROUND ALL EXISTING AND PROPOSED CATCH BASIN INLETS WITHIN THE WORK LIMITS AS WELL AS CATCH BASINS/CURB INLETS THAT RECEIVE RUNOFF FROM CONSTRUCTION ACTIVITIES. MAINTAIN FOR THE DURATION OF THE PROJECT.
4. INSTALL STABILIZED CONSTRUCTION EXIT(S).
5. INSPECT INLET PROTECTION AND PERIMETER EROSION CONTROL MEASURES DAILY AND AFTER EACH RAIN STORM OF 0.25 INCH OR GREATER. REPAIR/MODIFY PROTECTION AS NECESSARY TO MAXIMIZE EFFICIENCY OF FILTER. REPLACE ALL FILTERS WHEN SEDIMENT IS 1/3 THE FILTER HEIGHT.
6. ALL DISTURBED AREAS NOT TO BE PAVED OR OTHERWISE TREATED SHALL RECEIVE 6" LOAM, SEED, FERTILIZER AND MULCH.
7. CONSTRUCT EROSION CONTROL BLANKET ON ALL SLOPES STEEPER THAN 3:1.
8. PRIOR TO ANY WORK OR SOIL DISTURBANCE COMMENCING ON THE SUBJECT PROPERTY, INCLUDING MOVING OF EARTH, THE APPLICANT SHALL INSTALL ALL EROSION AND SILTATION MITIGATION AND CONTROL MEASURES AS REQUIRED BY STATE AND LOCAL PERMITS AND APPROVALS.
9. CONTRACTOR SHALL BE RESPONSIBLE TO CONTROL DUST AND WIND EROSION THROUGHOUT THE CONSTRUCTION PERIOD. DUST CONTROL MEASURES SHALL INCLUDE, BUT ARE NOT LIMITED TO, SPRINKLING WATER ON UNSTABLE SOILS SUBJECT TO ARID CONDITIONS.
10. THE CONTRACTOR SHALL REMOVE AND PROPERLY DISPOSE OF ALL TEMPORARY EROSION CONTROL DEVICES UPON COMPLETION OF CONSTRUCTION.
11. ALL CATCH BASIN SUMPS AND PIPING SHALL BE THOROUGHLY CLEANED TO REMOVE ALL SEDIMENT AND DEBRIS AFTER THE PROJECT HAS BEEN FULLY PAVED.
12. TEMPORARY SOIL STOCKPILE SHALL BE SURROUNDED WITH PERIMETER CONTROLS AND SHALL BE STABILIZED BY TEMPORARY EROSION CONTROL SEEDING. STOCKPILE AREAS TO BE LOCATED AS FAR AS POSSIBLE FROM THE DELINEATED EDGE OF WETLANDS.
13. SAFETY FENCING SHALL BE PROVIDED AROUND STOCKPILES OVER 10 FT.
14. CONCRETE TRUCKS WILL BE REQUIRED TO WASH OUT (IF NECESSARY) SHOOTS ONLY WITHIN AREAS WHERE CONCRETE HAS BEEN PLACED. NO OTHER WASH OUT WILL BE ALLOWED.
15. ALL CONDITIONS ON THIS PLAN SHALL REMAIN IN EFFECT IN PERPETUITY PURSUANT TO THE REQUIREMENTS OF THE SITE PLAN REVIEW REGULATIONS.



MATCH LINE SHEET 2



Proposed Multi-Family Development

Iron Horse Properties, LLC

105 Bartlett Street
Portsmouth,
New Hampshire

H	1/20/2021	TAC Resubmission
G	11/18/2020	TAC Resubmission
F	10/28/2020	Wetland CUP Resubmission
E	5/20/2020	TAC Resubmission
D	4/29/2020	Wetland CUP Submission
C	4/20/2020	TAC Submission
B	2/6/2020	Design Review Submission
A	1/2/2020	ZBA Submission

MARK	DATE	DESCRIPTION
PROJECT NO:	C-0960-006	
DATE:	April 20, 2020	
FILE:	C-0960-006_C-SITE.DWG	
DRAWN BY:	NAH	
CHECKED:	PMC	
APPROVED:	BML	

GRADING, DRAINAGE, AND EROSION CONTROL PLAN

SCALE: AS SHOWN

C-103.1

LEGEND

- PROPOSED MAJOR CONTOUR LINE
- PROPOSED MINOR CONTOUR LINE
- PROPOSED DRAIN LINE (TYP)
- PROPOSED UNDERDRAIN
- PROPOSED SILT SOCK
- INLET PROTECTION SILT SACK
- PROPOSED CATCHBASIN
- PROPOSED DOUBLE GRATE CATCHBASIN
- PROPOSED DRAIN MANHOLE
- PROPOSED YARD DRAIN
- BLDG
- TYP
- COORD
- TC
- BC
- HW

DRAINAGE STRUCTURE TABLE

CB1242 RIM=9.30 INV.OUT=5.80 SW	PCB3 RIM=8.40 INV.OUT=5.50 NW	PCB9 RIM=12.65 INV.OUT=8.65 NW	PDMH3 RIM=10.65 INV.IN=4.30 SE INV.IN=4.30 SW INV.OUT=4.20 NE	PDMH9 RIM=14.05 INV.IN=4.60 SE INV.OUT=4.60 NW INV.OUT=7.00 NE	PDMH15 RIM=10.00 INV.IN=6.45 NE INV.OUT=6.35 SW	PDMH21 RIM=11.90 INV.OUT=8.88 N
CB1243 RIM=9.55 INV.IN=6.65 NW INV.OUT=6.55 SE	PCB4 RIM=8.55 INV.OUT=5.10 NW	PCB10 RIM=12.15 INV.OUT=8.60 NW	PDMH4 RIM=11.70 INV.IN=3.45 SW INV.IN=4.30 NE INV.OUT=3.35 NW	PDMH10 RIM=13.95 INV.IN=6.50 SW INV.OUT=6.40 NW INV.OUT=10.40 NE	PDMH16 RIM=13.50 INV.IN=10.50 SW INV.IN=10.50 NW INV.OUT=10.40 NE	POS1 RIM=10.50 INV.OUT=7.15 E
CB1244 RIM=10.00 INV.OUT=6.85 SW	PCB5 RIM=9.60 INV.OUT=6.10 NW	PCB11 RIM=8.60 INV.OUT=5.80 NE	PDMH11 RIM=12.00 INV.IN=4.60 SE INV.OUT=4.50 W	PDMH17 RIM=9.70 INV.IN=5.60 NE INV.OUT=5.50 NW	PYD1 RIM=12.50 INV.OUT=7.70 N	
CB1264 RIM=9.50 INV.OUT=6.50 NE	PCB6 RIM=9.80 INV.OUT=6.30 SW	PCB12 RIM=8.60 INV.IN=5.05 S	PDMH5 RIM=11.30 INV.IN=5.05 NE INV.OUT=4.95 SW	PDMH12 RIM=13.00 INV.IN=4.00 E INV.IN=5.00 W INV.IN=3.80 SE INV.OUT=3.70 N	PYD2 RIM=12.30 INV.IN=7.50 S INV.OUT=7.40 NE	
PCB1 RIM=8.50 INV.OUT=5.30 E	PCB7 RIM=10.00 INV.OUT=7.00 NE	PDMH1 RIM=8.75 INV.IN=5.20 W INV.IN=5.20 S INV.IN=5.20 SE INV.OUT=5.10 NE	PDMH6 RIM=9.85 INV.IN=6.00 NE INV.IN=6.00 SE INV.OUT=5.90 SW	PDMH13 RIM=13.00 INV.IN=5.35 SW INV.IN=5.35 N INV.OUT=5.35 NE	PYD3 RIM=11.00 INV.IN=7.10 SW INV.IN=8.00 NW INV.OUT=7.00 NE	
PCB2 RIM=8.45 INV.OUT=5.30 N	PCB8 RIM=10.75 INV.OUT=7.50 NW	PDMH2 RIM=8.90 INV.IN=5.00 SW INV.IN=5.00 SE INV.OUT=4.90 NE	PDMH7 RIM=12.27 INV.IN=6.60 NW INV.IN=6.60 SW INV.OUT=6.50 SE	PDMH14 RIM=9.60 INV.IN=5.40 SE INV.IN=5.40 NE INV.IN=4.70 SW INV.OUT=4.65 NW	PYD4 RIM=13.00 INV.OUT=10.70 SE	
		PDMH8 RIM=11.35 INV.IN=6.25 NW INV.IN=6.25 SE INV.IN=6.10 SW INV.OUT=6.00 NE	PDMH14 RIM=9.60 INV.IN=5.40 SE INV.IN=5.40 NE INV.IN=4.70 SW INV.OUT=4.65 NW	PDMH20 RIM=11.80 INV.OUT=8.88 SE	PYD5 RIM=11.50 INV.IN=7.00 W INV.IN=7.15 S INV.OUT=7.05 E	


GRADING AND DRAINAGE NOTES:

1. COMPACTION REQUIREMENTS:
BELOW PAVED OR CONCRETE AREAS 95%
TRENCH BEDDING MATERIAL AND SAND BLANKET BACKFILL 90%
BELOW LOAM AND SEED AREAS 90%
* ALL PERCENTAGES OF COMPACTION SHALL BE OF THE MAXIMUM DRY DENSITY AT THE OPTIMUM MOISTURE CONTENT AS DETERMINED AND CONTROLLED IN ACCORDANCE WITH ASTM D-1557, METHOD C FIELD DENSITY TESTS SHALL BE MADE IN ACCORDANCE WITH ASTM D-1556 OR ASTM-2922.
2. ALL STORM DRAINAGE PIPES SHALL BE HIGH DENSITY POLYETHYLENE (HANCOR HI-Q, ADS N-12 OR EQUAL), UNLESS OTHERWISE SPECIFIED.
3. SEE UTILITY PLAN FOR ALL SITE UTILITY INFORMATION.
4. ADJUST ALL MANHOLES, CATCH BASINS, CURB BOXES, ETC. WITHIN LIMITS OF WORK TO FINISH GRADE.
5. CONTRACTOR SHALL PROVIDE A FINISH PAVEMENT SURFACE AND LAWN AREAS FREE OF LOW SPOTS AND PONDING AREAS. CRITICAL AREAS INCLUDE BUILDING ENTRANCES, EXITS, RAMPS AND LOADING DOCK AREAS ADJACENT TO THE BUILDING.
6. CONTRACTOR SHALL THOROUGHLY CLEAN ALL CATCH BASINS AND DRAIN LINES, WITHIN THE LIMIT OF WORK, OF SEDIMENT IMMEDIATELY UPON COMPLETION OF CONSTRUCTION.
7. ALL MATERIALS AND CONSTRUCTION SHALL CONFORM WITH APPLICABLE FEDERAL, STATE AND LOCAL CODES.
8. ALL DISTURBED AREAS NOT TO BE PAVED OR OTHERWISE TREATED SHALL RECEIVE 6" LOAM, SEED FERTILIZER AND MULCH.
9. ALL STORM DRAIN CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE NHDOT STANDARD SPECIFICATIONS FOR HIGHWAYS AND BRIDGES, LATEST EDITION.
10. ALL PROPOSED CATCH BASINS SHALL BE EQUIPPED WITH OIL/GAS SEPARATOR HOODS AND 4" SUMPS.
11. ALL WORK SHALL CONFORM TO THE CITY OF PORTSMOUTH DEPARTMENT OF PUBLIC WORKS, STANDARD SPECIFICATIONS AND WITH THE STATE OF NEW HAMPSHIRE DEPARTMENT OF TRANSPORTATION, "STANDARD SPECIFICATIONS OF ROAD AND BRIDGE CONSTRUCTION", CURRENT EDITION.
12. CONTRACTOR TO SUBMIT AS-BUILT PLANS IN DIGITAL FORMAT (.DWG AND .PDF FILES) ON DISK TO THE OWNER AND ENGINEER UPON COMPLETION OF THE PROJECT. AS-BUILTS SHALL BE PREPARED AND CERTIFIED BY A NEW HAMPSHIRE LICENSED LAND SURVEYOR.
13. SEE EXISTING CONDITIONS PLAN FOR BENCH MARK INFORMATION.
14. AREAS DISTURBED WITHIN THE 25' VEGETATED BUFFER BY HEADWALLS AND CULVERT CONSTRUCTION SHALL BE LOAMED, SEEDDED WITH NEW ENGLAND WILDLIFE AND CONSERVATION SEED MIX AND STABILIZED WITH JUTE MESH.

EROSION CONTROL NOTES:

1. INSTALL EROSION CONTROL BARRIERS AS SHOWN AS FIRST ORDER OF WORK.
2. SEE GENERAL EROSION CONTROL NOTES ON "EROSION CONTROL NOTES & DETAILS SHEET".
3. PROVIDE INLET PROTECTION AROUND ALL EXISTING AND PROPOSED CATCH BASIN INLETS WITHIN THE WORK LIMITS AS WELL AS CATCH BASINS/CURB INLETS THAT RECEIVE RUNOFF FROM CONSTRUCTION ACTIVITIES. MAINTAIN FOR THE DURATION OF THE PROJECT.
4. INSTALL STABILIZED CONSTRUCTION EXIT(S).
5. INSPECT INLET PROTECTION AND PERIMETER EROSION CONTROL MEASURES DAILY AND AFTER EACH RAIN STORM OF 0.25 INCH OR GREATER. REPAIR/MODIFY PROTECTION AS NECESSARY TO MAXIMIZE EFFICIENCY OF FILTER. REPLACE ALL FILTERS WHEN SEDIMENT IS 1/3 THE FILTER HEIGHT.
6. ALL DISTURBED AREAS NOT TO BE PAVED OR OTHERWISE TREATED SHALL RECEIVE 6" LOAM, SEED, FERTILIZER AND MULCH.
7. CONSTRUCT EROSION CONTROL BLANKET ON ALL SLOPES STEEPER THAN 3:1.
8. PRIOR TO ANY WORK OR SOIL DISTURBANCE COMMENCING ON THE SUBJECT PROPERTY, INCLUDING MOVING OF EARTH, THE APPLICANT SHALL INSTALL ALL EROSION AND SILTATION MITIGATION AND CONTROL MEASURES AS REQUIRED BY STATE AND LOCAL PERMITS AND APPROVALS.
9. CONTRACTOR SHALL BE RESPONSIBLE TO CONTROL DUST AND WIND EROSION THROUGHOUT THE CONSTRUCTION PERIOD. DUST CONTROL MEASURES SHALL INCLUDE, BUT ARE NOT LIMITED TO, SPRINKLING WATER ON UNSTABLE SOILS SUBJECT TO ARID CONDITIONS.
10. THE CONTRACTOR SHALL REMOVE AND PROPERLY DISPOSE OF ALL TEMPORARY EROSION CONTROL DEVICES UPON COMPLETION OF CONSTRUCTION.
11. ALL CATCH BASIN SUMPS AND PIPING SHALL BE THOROUGHLY CLEANED TO REMOVE ALL SEDIMENT AND DEBRIS AFTER THE PROJECT HAS BEEN FULLY PAVED.
12. TEMPORARY SOIL STOCKPILE SHALL BE SURROUNDED WITH PERIMETER CONTROLS AND SHALL BE STABILIZED BY TEMPORARY EROSION CONTROL SEEDING. STOCKPILE AREAS TO BE LOCATED AS FAR AS POSSIBLE FROM THE DELINEATED EDGE OF WETLANDS.
13. SAFETY FENCING SHALL BE PROVIDED AROUND STOCKPILES OVER 10 FT.
14. CONCRETE TRUCKS WILL BE REQUIRED TO WASH OUT (IF NECESSARY) SHOOTS ONLY WITHIN AREAS WHERE CONCRETE HAS BEEN PLACED. NO OTHER WASH OUT WILL BE ALLOWED.
15. ALL CONDITIONS ON THIS PLAN SHALL REMAIN IN EFFECT IN PERPETUITY PURSUANT TO THE REQUIREMENTS OF THE SITE PLAN REVIEW REGULATIONS.

NORTH MILL POND (TIDAL)



BRADLEE MEZOUTA
No. 08830
LICENSED PROFESSIONAL ENGINEER
STATE OF NEW HAMPSHIRE
1-20-21

PATRICK R. CUMMINGS
No. 12378
LICENSED PROFESSIONAL ENGINEER
STATE OF NEW HAMPSHIRE
1-20-21

0 40' 80'
GRAPHIC SCALE

Proposed Multi-Family Development

Iron Horse Properties, LLC

105 Bartlett Street
Portsmouth,
New Hampshire


MARK	DATE	DESCRIPTION
H	1/20/2021	TAC Resubmission
G	11/18/2020	TAC Resubmission
F	10/28/2020	Wetland CUP Resubmission
E	5/20/2020	TAC Resubmission
D	4/29/2020	Wetland CUP Submission
C	4/20/2020	TAC Submission
B	2/6/2020	Design Review Submission
A	1/2/2020	ZBA Submission

PROJECT NO: C-0960-006
DATE: April 20, 2020
FILE: C-0960-006_C-SITE.DWG
DRAWN BY: NAH
CHECKED BY: PMC
APPROVED BY: BML

GRADING, DRAINAGE, AND EROSION CONTROL PLAN

SCALE: AS SHOWN

Last Saved: 1/19/2021
 Plotted On: Jan 19, 2021 5:07pm By: WAHansen
 Tighe & Bond P:\C\0960-006 105 Bartlett Street Drawings - Figures\AutoCAD\Sheet\C-0960-006_C-SITE.dwg




UTILITY NOTES:



- THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE APPROXIMATE AND THE LOCATIONS ARE NOT GUARANTEED BY THE OWNER OR ENGINEER. IT IS THE CONTRACTOR'S RESPONSIBILITY TO LOCATE ALL UTILITIES, ANTICIPATE CONFLICTS, REPAIR EXISTING UTILITIES, AND RELOCATE EXISTING UTILITIES REQUIRED TO COMPLETE THE WORK AT NO ADDITIONAL COST TO THE OWNER.
- COORDINATE ALL UTILITY WORK WITH APPROPRIATE UTILITY COMPANY.
 - NATURAL GAS - UNITIL
 - WATER/SEWER - CITY OF PORTSMOUTH
 - ELECTRIC - EVERSOURCE
 - COMMUNICATIONS - CONSOLIDATED COMMUNICATIONS & COMCAST
- SEE EXISTING CONDITIONS PLAN FOR BENCHMARK INFORMATION.
- SEE GRADING, DRAINAGE & EROSION CONTROL PLAN FOR PROPOSED GRADING AND EROSION CONTROL MEASURES.
- THE APPLICANT SHALL COORDINATE WITH THE CITY'S CONSULTANT TO COMPLETE A WATER CAPACITY ANALYSIS USING THE CITY'S CAPACITY MODELING AND SHALL MODIFY THE WATER SERVICE DESIGN AS REQUIRED. THE PRIVATE WATER LINE THAT CURRENTLY FEEDS THE DEVELOPMENT LOT SHALL BE EITHER REPLACED OR ABANDONED DEPENDING ON THE OUTCOME OF THE STUDY. ALL MODIFICATIONS SHALL BE REVIEWED AND APPROVED BY THE DPW AND THE FIRE DEPARTMENT.
- PROPOSED WATER MAIN WILL REMAIN PRIVATE AND A PRIVATE WATER MAIN MAINTENANCE AGREEMENT WITH THE CITY IS REQUIRED.
- ALL WATER MAIN INSTALLATIONS SHALL BE CLASS 52, CEMENT LINED DUCTILE IRON PIPE.
- ALL WATER MAIN INSTALLATIONS SHALL BE PRESSURE TESTED AND CHLORINATED AFTER CONSTRUCTION PRIOR TO ACTIVATING THE SYSTEM. CONTRACTOR SHALL COORDINATE CHLORINATION AND TESTING WITH THE CITY OF PORTSMOUTH WATER DEPARTMENT.
- ALL SEWER PIPE SHALL BE PVC SDR 35 UNLESS OTHERWISE STATED.
- COORDINATE ALL WORK WITHIN PUBLIC RIGHT OF WAYS WITH THE CITY OF PORTSMOUTH.
- CONTRACTOR SHALL MAINTAIN UTILITY SERVICES TO ABUTTING PROPERTIES THROUGHOUT CONSTRUCTION.
- CONNECTION TO EXISTING WATER MAIN SHALL BE CONSTRUCTED TO CITY OF PORTSMOUTH STANDARDS.
- EXISTING UTILITIES TO BE REMOVED SHALL BE CAPPED AT THE MAIN AND MEET THE DEPARTMENT OF PUBLIC WORKS STANDARDS FOR CAPPING OF WATER AND SEWER SERVICES.
- ALL ELECTRICAL MATERIAL WORKMANSHIP SHALL CONFORM TO THE NATIONAL ELECTRIC CODE, LATEST EDITION, AND ALL APPLICABLE STATE AND LOCAL CODES.
- THE EXACT LOCATION OF NEW UTILITY SERVICES AND CONNECTIONS SHALL BE COORDINATED WITH THE BUILDING DRAWINGS AND THE APPLICABLE UTILITY COMPANIES.
- ADJUST ALL MANHOLES, CATCH BASINS, CURB BOXES, ETC. WITHIN LIMITS OF WORK TO FINISH GRADE.
- ALL UNDERGROUND CONDUITS SHALL HAVE NYLON PULL ROPES TO FACILITATE PULLING CABLES.
- THE CONTRACTOR SHALL OBTAIN, PAY FOR, AND COMPLY WITH ALL REQUIRED PERMITS, ARRANGE FOR ALL INSPECTIONS, AND SUBMIT COPIES OF ACCEPTANCE CERTIFICATES TO THE OWNER PRIOR TO THE COMPLETION OF THIS PROJECT.
- THE CONTRACTOR SHALL PROVIDE AND INSTALL ALL MANHOLES, BOXES, FITTINGS, CONNECTORS, COVER PLATES, AND OTHER MISCELLANEOUS ITEMS NOT NECESSARILY DETAILED ON THESE DRAWINGS TO RENDER INSTALLATION OF UTILITIES COMPLETE AND OPERATIONAL.
- CONTRACTOR SHALL PROVIDE EXCAVATION, BEDDING, BACKFILL AND COMPACTION FOR NATURAL GAS SERVICES.
- A 10-FOOT MINIMUM EDGE TO EDGE HORIZONTAL SEPARATION SHALL BE PROVIDED BETWEEN ALL WATER AND SANITARY SEWER LINES. AN 18-INCH MINIMUM OUTSIDE TO OUTSIDE VERTICAL SEPARATION SHALL BE PROVIDED AT ALL WATER/SANITARY SEWER CROSSINGS.
- THE CONTRACTOR SHALL CONTACT "DIG-SAFE" 72 HOURS PRIOR TO COMMENCING CONSTRUCTION. THE CONTRACTOR SHALL HAVE THE "DIG-SAFE" NUMBER ON SITE AT ALL TIMES.
- CONTRACTOR TO SUBMIT AS-BUILT PLANS ON REPRODUCIBLE MYLARS AND IN DIGITAL FORMAT (.DWG FILES) TO THE OWNER AND ENGINEER UPON COMPLETION OF THE PROJECT. AS-BUILTS SHALL BE PREPARED AND CERTIFIED BY A NEW HAMPSHIRE LICENSED LAND SURVEYOR OR PROFESSIONAL ENGINEER.
- SAW CUT AND REMOVE PAVEMENT AND CONSTRUCT PAVEMENT TRENCH PATCH FOR ALL PROPOSED UTILITIES LOCATED IN EXISTING PAVEMENT AREAS TO REMAIN
- HYDRANTS, GATE VALVES, FITTINGS, ETC. SHALL MEET THE REQUIREMENTS OF THE CITY OF PORTSMOUTH.
- COORDINATE TESTING OF SEWER CONSTRUCTION WITH THE CITY OF PORTSMOUTH.
- ALL SEWER PIPE WITH LESS THAN 6' OF COVER IN PAVED AREAS OR LESS THAN 4' OF COVER IN UNPAVED AREAS SHALL BE INSULATED.
- CONTRACTOR SHALL COORDINATE ALL ELECTRIC WORK INCLUDING BUT NOT LIMITED TO: CONDUIT CONSTRUCTION, MANHOLE CONSTRUCTION, UTILITY POLE CONSTRUCTION, OVERHEAD WIRE RELOCATION, AND TRANSFORMER CONSTRUCTION WITH POWER COMPANY.
- CONTRACTOR SHALL PHASE UTILITY CONSTRUCTION, PARTICULARLY WATER MAIN AND GAS MAIN CONSTRUCTION AS TO MAINTAIN CONTINUOUS SERVICE TO ABUTTING PROPERTIES. CONTRACTOR SHALL COORDINATE TEMPORARY SERVICES TO ABUTTERS WITH THE UTILITY COMPANY AND AFFECTED ABUTTER.
- SITE LIGHTING SPECIFICATIONS, CONDUIT LAYOUT AND CIRCUITRY FOR PROPOSED SITE LIGHTING AND SIGN ILLUMINATION SHALL BE PROVIDED BY THE PROJECT ELECTRICAL ENGINEER.
- CONTRACTOR SHALL CONSTRUCT ALL UTILITIES AND DRAINS TO WITHIN 10' OF THE FOUNDATION WALLS AND CONNECT THESE TO SERVICE STUDS FROM THE BUILDING.
- ALL CONDITIONS ON THIS PLAN SHALL REMAIN IN EFFECT IN PERPETUITY PURSUANT TO THE REQUIREMENTS OF THE SITE PLAN REVIEW REGULATIONS.

LEGEND

- EXISTING STORM DRAIN
- EXISTING SANITARY SEWER
- EXISTING WATER
- EXISTING GAS
- EXISTING UNDERGROUND ELECTRIC
- EXISTING OVERHEAD UTILITY
- PROPOSED STORM DRAIN
- PROPOSED SANITARY SEWER
- PROPOSED WATER
- PROPOSED GAS
- PROPOSED UNDERGROUND ELECTRIC
- PROPOSED UNDERGROUND TELECOMMUNICATION
- EXISTING CATCHBASIN
- EXISTING DRAIN MANHOLE
- EXISTING SEWER MANHOLE
- EXISTING HYDRANT
- EXISTING WATER VALVE
- EXISTING WATER SHUT OFF
- EXISTING GAS VALVE
- EXISTING GAS SHUT OFF
- EXISTING UTILITY POLE
- EXISTING ELECTRIC MANHOLE
- EXISTING TELEPHONE MANHOLE
- PROPOSED CATCHBASIN
- PROPOSED DRAIN MANHOLE
- PROPOSED SEWER MANHOLE
- PROPOSED WATER VALVE
- PROPOSED HYDRANT
- PROPOSED GAS VALVE
- PROPOSED LIGHT POLE BASE
- BLDG
- TYP
- COORD
- VIF



MATCH LINE SHEET 2
MATCH LINE SHEET 1



Proposed Multi-Family Development

Iron Horse Properties, LLC

105 Bartlett Street
Portsmouth,
New Hampshire

MARK	DATE	DESCRIPTION
H	1/20/2021	TAC Resubmission
G	11/18/2020	TAC Resubmission
F	10/28/2020	Wetland CUP Resubmission
E	5/20/2020	TAC Resubmission
D	4/29/2020	Wetland CUP Submission
C	4/20/2020	TAC Submission
B	2/6/2020	Design Review Submission
A	1/2/2020	ZBA Submission

PROJECT NO:	C-0960-006
DATE:	April 20, 2020
FILE:	C-0960-006_C-SITE.DWG
DRAWN BY:	NAH
CHECKED:	PMC
APPROVED:	BML

UTILITIES PLAN

SCALE: AS SHOWN

C-104.1


Last Saved: 1/19/2021
Plotted On: Jan 19, 2021 5:07pm By: Mahanien
Tighe & Bond: JAC (C:\960-006_105 Bartlett Street\Drawings - Figures\AutoCAD\Sheet\C-0960-006_C-SITE.dwg)

LEGEND



- | | |
|-------|--|
| —D— | EXISTING STORM DRAIN |
| —S— | EXISTING SANITARY SEWER |
| —W— | EXISTING WATER |
| —G— | EXISTING GAS |
| —E— | EXISTING UNDERGROUND ELECTRIC |
| —OE— | EXISTING OVERHEAD UTILITY |
| —SS— | PROPOSED STORM DRAIN |
| —PW— | PROPOSED WATER |
| —G— | PROPOSED GAS |
| —E— | PROPOSED UNDERGROUND ELECTRIC |
| —COM— | PROPOSED UNDERGROUND TELECOMMUNICATION |
| ⊙ | EXISTING CATCHBASIN |
| ⊙ | EXISTING DRAIN MANHOLE |
| ⊙ | EXISTING SEWER MANHOLE |
| ⊙ | EXISTING HYDRANT |
| ⊙ | EXISTING WATER VALVE |
| ⊙ | EXISTING WATER SHUT OFF |
| ⊙ | EXISTING GAS VALVE |
| ⊙ | EXISTING GAS SHUT OFF |
| ⊙ | EXISTING UTILITY POLE |
| ⊙ | EXISTING ELECTRIC MANHOLE |
| ⊙ | EXISTING TELEPHONE MANHOLE |
| ⊙ | PROPOSED CATCHBASIN |
| ⊙ | PROPOSED DRAIN MANHOLE |
| ⊙ | PROPOSED SEWER MANHOLE |
| ⊙ | PROPOSED WATER VALVE |
| ⊙ | PROPOSED HYDRANT |
| ⊙ | PROPOSED GAS VALVE |
| ⊙ | PROPOSED LIGHT POLE BASE |
| ⊙ | BLDG TYP |
| ⊙ | COORD |
| ⊙ | VIF |

UTILITY NOTES:

- THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE APPROXIMATE AND THE LOCATIONS ARE NOT GUARANTEED BY THE OWNER OR ENGINEER. IT IS THE CONTRACTOR'S RESPONSIBILITY TO LOCATE ALL UTILITIES, ANTICIPATE CONFLICTS, REPAIR EXISTING UTILITIES, AND RELOCATE EXISTING UTILITIES REQUIRED TO COMPLETE THE WORK AT NO ADDITIONAL COST TO THE OWNER.
- COORDINATE ALL UTILITY WORK WITH APPROPRIATE UTILITY COMPANY.
 - NATURAL GAS - UNITIL
 - WATER/SEWER - CITY OF PORTSMOUTH
 - ELECTRIC - EVERSOURCE
 - COMMUNICATIONS - CONSOLIDATED COMMUNICATIONS & COMCAST
- SEE EXISTING CONDITIONS PLAN FOR BENCHMARK INFORMATION.
- SEE GRADING, DRAINAGE & EROSION CONTROL PLAN FOR PROPOSED GRADING AND EROSION CONTROL MEASURES.
- THE APPLICANT SHALL COORDINATE WITH THE CITY'S CONSULTANT TO COMPLETE A WATER CAPACITY ANALYSIS USING THE CITY'S CAPACITY MODELING AND SHALL MODIFY THE WATER SERVICE DESIGN AS REQUIRED. THE PRIVATE WATER LINE THAT CURRENTLY FEEDS THE DEVELOPMENT LOT SHALL BE EITHER REPLACED OR ABANDONED DEPENDING ON THE OUTCOME OF THE STUDY. ALL MODIFICATIONS SHALL BE REVIEWED AND APPROVED BY THE DPW AND THE FIRE DEPARTMENT.
- PROPOSED WATER MAIN WILL REMAIN PRIVATE AND A PRIVATE WATER MAIN MAINTENANCE AGREEMENT WITH THE CITY IS REQUIRED.
- ALL WATER MAIN INSTALLATIONS SHALL BE CLASS 52, CEMENT LINED DUCTILE IRON PIPE.
- ALL WATER MAIN INSTALLATIONS SHALL BE PRESSURE TESTED AND CHLORINATED AFTER CONSTRUCTION PRIOR TO ACTIVATING THE SYSTEM. CONTRACTOR SHALL COORDINATE CHLORINATION AND TESTING WITH THE CITY OF PORTSMOUTH WATER DEPARTMENT.
- ALL SEWER PIPE SHALL BE PVC SDR 35 UNLESS OTHERWISE STATED.
- COORDINATE ALL WORK WITHIN PUBLIC RIGHT OF WAYS WITH THE CITY OF PORTSMOUTH.
- CONTRACTOR SHALL MAINTAIN UTILITY SERVICES TO ABUTTING PROPERTIES THROUGHOUT CONSTRUCTION.
- CONNECTION TO EXISTING WATER MAIN SHALL BE CONSTRUCTED TO CITY OF PORTSMOUTH STANDARDS.
- EXISTING UTILITIES TO BE REMOVED SHALL BE CAPPED AT THE MAIN AND MEET THE DEPARTMENT OF PUBLIC WORKS STANDARDS FOR CAPPING OF WATER AND SEWER SERVICES.
- ALL ELECTRICAL MATERIAL WORKMANSHIP SHALL CONFORM TO THE NATIONAL ELECTRIC CODE, LATEST EDITION, AND ALL APPLICABLE STATE AND LOCAL CODES.
- THE EXACT LOCATION OF NEW UTILITY SERVICES AND CONNECTIONS SHALL BE COORDINATED WITH THE BUILDING DRAWINGS AND THE APPLICABLE UTILITY COMPANIES.
- ADJUST ALL MANHOLES, CATCH BASINS, CURB BOXES, ETC. WITHIN LIMITS OF WORK TO FINISH GRADE.
- ALL UNDERGROUND CONDUITS SHALL HAVE NYLON PULL ROPES TO FACILITATE PULLING CABLES.
- THE CONTRACTOR SHALL OBTAIN, PAY FOR, AND COMPLY WITH ALL REQUIRED PERMITS, ARRANGE FOR ALL INSPECTIONS, AND SUBMIT COPIES OF ACCEPTANCE CERTIFICATES TO THE OWNER PRIOR TO THE COMPLETION OF THIS PROJECT.
- THE CONTRACTOR SHALL PROVIDE AND INSTALL ALL MANHOLES, BOXES, FITTINGS, CONNECTORS, COVER PLATES, AND OTHER MISCELLANEOUS ITEMS NOT NECESSARILY DETAILED ON THESE DRAWINGS TO RENDER INSTALLATION OF UTILITIES COMPLETE AND OPERATIONAL.
- CONTRACTOR SHALL PROVIDE EXCAVATION, BEDDING, BACKFILL AND COMPACTION FOR NATURAL GAS SERVICES.
- A 10-FOOT MINIMUM EDGE TO EDGE HORIZONTAL SEPARATION SHALL BE PROVIDED BETWEEN ALL WATER AND SANITARY SEWER LINES. AN 18-INCH MINIMUM OUTSIDE TO OUTSIDE VERTICAL SEPARATION SHALL BE PROVIDED AT ALL WATER/SANITARY SEWER CROSSINGS.
- THE CONTRACTOR SHALL CONTACT "DIG-SAFE" 72 HOURS PRIOR TO COMMENCING CONSTRUCTION. THE CONTRACTOR SHALL HAVE THE "DIG-SAFE" NUMBER ON SITE AT ALL TIMES.
- CONTRACTOR TO SUBMIT AS-BUILT PLANS ON REPRODUCIBLE MYLARS AND IN DIGITAL FORMAT (.DWG FILES) TO THE OWNER AND ENGINEER UPON COMPLETION OF THE PROJECT. AS-BUILTS SHALL BE PREPARED AND CERTIFIED BY A NEW HAMPSHIRE LICENSED LAND SURVEYOR OR PROFESSIONAL ENGINEER.
- SAW CUT AND REMOVE PAVEMENT AND CONSTRUCT PAVEMENT TRENCH PATCH FOR ALL PROPOSED UTILITIES LOCATED IN EXISTING PAVEMENT AREAS TO REMAIN.
- HYDRANTS, GATE VALVES, FITTINGS, ETC. SHALL MEET THE REQUIREMENTS OF THE CITY OF PORTSMOUTH.
- COORDINATE TESTING OF SEWER CONSTRUCTION WITH THE CITY OF PORTSMOUTH.
- ALL SEWER PIPE WITH LESS THAN 6' OF COVER IN PAVED AREAS OR LESS THAN 4' OF COVER IN UNPAVED AREAS SHALL BE INSULATED.
- CONTRACTOR SHALL COORDINATE ALL ELECTRIC WORK INCLUDING BUT NOT LIMITED TO: CONDUIT CONSTRUCTION, MANHOLE CONSTRUCTION, UTILITY POLE CONSTRUCTION, OVERHEAD WIRE RELOCATION, AND TRANSFORMER CONSTRUCTION WITH POWER COMPANY.
- CONTRACTOR SHALL PHASE UTILITY CONSTRUCTION, PARTICULARLY WATER MAIN AND GAS MAIN CONSTRUCTION AS TO MAINTAIN CONTINUOUS SERVICE TO ABUTTING PROPERTIES. CONTRACTOR SHALL COORDINATE TEMPORARY SERVICES TO ABUTTERS WITH THE UTILITY COMPANY AND AFFECTED ABUTTER.
- SITE LIGHTING SPECIFICATIONS, CONDUIT LAYOUT AND CIRCUITRY FOR PROPOSED SITE LIGHTING AND SIGN ILLUMINATION SHALL BE PROVIDED BY THE PROJECT ELECTRICAL ENGINEER.
- CONTRACTOR SHALL CONSTRUCT ALL UTILITIES AND DRAINS TO WITHIN 10' OF THE FOUNDATION WALLS AND CONNECT THESE TO SERVICE STUBS FROM THE BUILDING.
- ALL CONDITIONS ON THIS PLAN SHALL REMAIN IN EFFECT IN PERPETUITY PURSUANT TO THE REQUIREMENTS OF THE SITE PLAN REVIEW REGULATIONS.



NORTH MILL POND (TIDAL)



Proposed Multi-Family Development

Iron Horse Properties, LLC

105 Bartlett Street
Portsmouth,
New Hampshire

MARK	DATE	DESCRIPTION
H	1/20/2021	TAC Resubmission
G	11/18/2020	TAC Resubmission
F	10/28/2020	Wetland CUP Resubmission
E	5/20/2020	TAC Resubmission
D	4/29/2020	Wetland CUP Submission
C	4/20/2020	TAC Submission
B	2/6/2020	Design Review Submission
A	1/2/2020	ZBA Submission

PROJECT NO:	C-0960-006
DATE:	April 20, 2020
FILE:	C-0960-006_C-SITE.DWG
DRAWN BY:	NAH
CHECKED:	PMC
APPROVED:	BML

UTILITIES PLAN


SCALE: AS SHOWN

C-104.2



Last Saved: 1/19/2021
 Plotted On: Jan 19, 2021 - 5:07pm By: WAHansen
 Tighe & Bond; P:\CUBSD\Cadman\06_C-0960-006_105 Bartlett Street\Drawings_Figures\AutoCAD\Sheet\C-0960-006_C-SITE.dwg

StatArea 1
 LARGE, MAIN PARKING LOT AREA ONLY
 Illuminance (Fc)
 Average = 0.65
 Maximum = 3.4
 Minimum = 0.0
 Avg/Min Ratio = N.A.
 Max/Min Ratio = N.A.

Symbol	Qty	Label	Arrangement	Description	CRI	Lum. Lumens	[MANUFAC]
○	10	B	SINGLE	CAV414-LT-WA-20W3K-U-5-N-BK	80	1775	Pemco Lighting Products Inc.
●	13	P3	SINGLE	SOUTH-NL-40W3K-U-3-N-BK/ POLE STYLE TBD	85	4126	PEMCO
●	2	P5	SINGLE	SOUTH-NL-40W3K-U-5-N-BK/ POLE STYLE TBD	85	4209	PEMCO
○	15	W	SINGLE	CMPRD-E-C3-2X20-U-CXX / WALL MTD 15' AFG	80	4518	PEMCO



**NORTH MILL POND
(TIDAL)**



**Proposed
Multi-Family
Development**

Iron Horse
Properties, LLC

105 Bartlett Street
Portsmouth,
New Hampshire





MARK	DATE	DESCRIPTION
H	1/20/2021	TAC Resubmission
G	11/18/2020	TAC Resubmission
F	10/28/2020	Wetland CUP Resubmission
E	5/20/2020	TAC Resubmission
D	4/29/2020	Wetland CUP Submission
C	4/20/2020	TAC Submission
B	2/6/2020	Design Review Submission
A	1/2/2020	ZBA Submission

PROJECT NO:	C-0960-006
DATE:	April 20, 2020
FILE:	C-0960-006_C-SITE.DWG
DRAWN BY:	NAH
CHECKED:	PMC
APPROVED:	BML

PHOTOMETRIC PLAN

SCALE: AS SHOWN

Last Saved: 1/20/2021
 Plotted On: Jan 20, 2021 10:40am By: NAHansen
 Tighe & Bond: E:\CUBSD\Calhoun\C-0960-006_105 Bartlett Street\Drawings - Figures\AutoCAD\Sheet\C-0960-006_C-SITE.dwg



Proposed Multi-Family Development

Iron Horse Properties, LLC

105 Bartlett Street
Portsmouth,
New Hampshire

MARK	DATE	DESCRIPTION
H	1/20/2021	TAC Resubmission
G	11/18/2020	TAC Resubmission
F	10/28/2020	Wetland CUP Resubmission
E	5/20/2020	TAC Resubmission
D	4/29/2020	Wetland CUP Submission
C	4/20/2020	TAC Submission
B	2/6/2020	Design Review Submission
A	1/2/2020	ZBA Submission





PROJECT NO:	C-0960-006
DATE:	April 20, 2020
FILE:	C-0960-006_C-SITE.DWG
DRAWN BY:	NAH
CHECKED:	PMC
APPROVED:	BML

ROADWAY PLAN & PROFILE

SCALE: AS SHOWN

C-201.1

Last Saved: 1/19/2021
 Plotted On: Jan 19, 2021 5:08pm By: Mahlansen
 Tighe & Bond: P:\C\0960-006_105 Bartlett Street\Drawings - Figures\AutoCAD\Sheet\C-0960-006_C-SITE.dwg



Proposed Multi-Family Development

Iron Horse Properties, LLC

105 Bartlett Street
Portsmouth,
New Hampshire

MARK	DATE	DESCRIPTION
H	1/20/2021	TAC Resubmission
G	11/18/2020	TAC Resubmission
F	10/28/2020	Wetland CUP Resubmission
E	5/20/2020	TAC Resubmission
D	4/29/2020	Wetland CUP Submission
C	4/20/2020	TAC Submission
B	2/6/2020	Design Review Submission
A	1/2/2020	ZBA Submission


PROJECT NO:	C-0960-006
DATE:	April 20, 2020
FILE:	C-0960-006_C-SITE.DWG
DRAWN BY:	NAH
CHECKED:	PMC
APPROVED:	BML

ROADWAY PLAN & PROFILE

SCALE: AS SHOWN

C-201.2


Last Saved: 1/19/2021
 Plotted On: Jan 19, 2021 5:09pm
 By: MAHansen
 Tighe & Bond: P:\C\0960-006 105 Bartlett Street\Drawings - Figures\AutoCAD\Sheet\C-0960-006_C-SITE.dwg




LEGEND

- PROPOSED SEWER EASEMENT
- PROPOSED DRAINAGE EASEMENT
- PROPOSED PARKING EASEMENT
- PROPOSED WATER EASEMENT
- PROPOSED COMMUNITY SPACE EASEMENT

EASEMENTS SHOWN HEREIN ARE FOR PERMITTING PURPOSES ONLY. FINAL EASEMENT PLAN SHALL BE PREPARED BY THE PROJECT SURVEYOR AND RECORDED AT THE ROCKINGHAM COUNTY REGISTRY OF DEED PRIOR TO ISSUING BUILDING PERMITS.



MATCH LINE SHEET 2
MATCH LINE SHEET 1



Proposed Multi-Family Development

Iron Horse Properties, LLC

105 Bartlett Street
Portsmouth,
New Hampshire

MARK	DATE	DESCRIPTION
H	1/20/2021	TAC Resubmission
G	11/18/2020	TAC Resubmission
F	10/28/2020	Wetland CUP Resubmission
E	5/20/2020	TAC Resubmission
D	4/29/2020	Wetland CUP Submission
C	4/20/2020	TAC Submission
B	2/6/2020	Design Review Submission
A	1/2/2020	ZBA Submission


PROJECT NO:	C-0960-006
DATE:	April 20, 2020
FILE:	C-0960-006_C-SITE.DWG
DRAWN BY:	NAH
CHECKED:	PMC
APPROVED:	BML

UTILITY EASEMENT PLAN






SCALE: AS SHOWN

C-301.1


Last Saved: 1/19/2021
Plotted On: Jan 19, 2021 5:09pm By: MAHansen
Tighe & Bond: J:\C:\Users\MAHansen\CAD\Drawings - Figures\AutoCAD\Sheet\C-0960-006_C-SITE.dwg



LEGEND

-  PROPOSED SEWER EASEMENT
-  PROPOSED DRAINAGE EASEMENT
-  PROPOSED PARKING EASEMENT
-  PROPOSED WATER EASEMENT
-  PROPOSED COMMUNITY SPACE EASEMENT

EASEMENTS SHOWN HEREIN ARE FOR PERMITTING PURPOSES ONLY. FINAL EASEMENT PLAN SHALL BE PREPARED BY THE PROJECT SURVEYOR AND RECORDED AT THE ROCKINGHAM COUNTY REGISTRY OF DEED PRIOR TO ISSUING BUILDING PERMITS.



Proposed Multi-Family Development

Iron Horse Properties, LLC

105 Bartlett Street
Portsmouth,
New Hampshire


MARK	DATE	DESCRIPTION
H	1/20/2021	TAC Resubmission
G	11/18/2020	TAC Resubmission
F	10/28/2020	Wetland CUP Resubmission
E	5/20/2020	TAC Resubmission
D	4/29/2020	Wetland CUP Submission
C	4/20/2020	TAC Submission
B	2/6/2020	Design Review Submission
A	1/2/2020	ZBA Submission

PROJECT NO:	C-0960-006
DATE:	April 20, 2020
FILE:	C-0960-006_C-SITE.DWG
DRAWN BY:	NAH
CHECKED:	PMC
APPROVED:	BML


UTILITY EASEMENT PLAN

SCALE: AS SHOWN



C-301.2







Last Saved: 1/19/2021
 Plotted On: Jan 19, 2021 5:09pm By: Mahlansen
 Tighe & Bond: P:\CUB960-Camaries\C-0960-006 105 Bartlett Street Drawings - Figures\AutoCAD\Sheet\C-0960-006_C-SITE.dwg



LEGEND

-  PROPOSED ACCESS EASEMENT TO BENEFIT MAP 164 LOT 4-2
-  PROPOSED ACCESS EASEMENT TO BENEFIT THE CITY OF PORTSMOUTH

EASEMENTS SHOWN HEREIN ARE FOR PERMITTING PURPOSES ONLY. FINAL EASEMENT PLAN SHALL BE PREPARED BY THE PROJECT SURVEYOR AND RECORDED AT THE ROCKINGHAM COUNTY REGISTRY OF DEED PRIOR TO ISSUING BUILDING PERMITS.



Proposed Multi-Family Development

Iron Horse Properties, LLC

105 Bartlett Street
Portsmouth,
New Hampshire

MARK	DATE	DESCRIPTION
H	1/20/2021	TAC Resubmission
G	11/18/2020	TAC Resubmission
F	10/28/2020	Wetland CUP Resubmission
E	5/20/2020	TAC Resubmission
D	4/29/2020	Wetland CUP Submission
C	4/20/2020	TAC Submission
B	2/6/2020	Design Review Submission
A	1/2/2020	ZBA Submission


PROJECT NO:	C-0960-006
DATE:	April 20, 2020
FILE:	C-0960-006_C-SITE.DWG
DRAWN BY:	NAH
CHECKED:	PMC
APPROVED:	BML

ACCESS EASEMENT PLAN


SCALE: AS SHOWN

C-302


Last Saved: 1/19/2021 11:50:09am By: Mahlansen
 Plotted On: Jan 19, 2021 5:09pm By: Tighe & Bond
 Figures/AutoCAD/Drawings - Figures/AutoCAD/Sheet/C-0960-006_C-SITE.dwg




**PRIVATE ROAD TYPICAL CROSS SECTION
STA 0+50 TO STA 2+85**
NO SCALE




**PRIVATE ROAD TYPICAL CROSS SECTION
STA 2+85 TO STA 3+75**
NO SCALE




**PRIVATE ROAD TYPICAL CROSS SECTION
STA 3+75 TO STA 5+35**
NO SCALE



**PRIVATE ROAD TYPICAL CROSS SECTION
STA 5+35 TO STA 6+50**
NO SCALE




**PRIVATE ROAD TYPICAL CROSS SECTION
STA 6+50 TO 8+00**
NO SCALE




- NOTES:**
- COORDINATE FINAL DESIGN SECTION WITH GEOTECHNICAL ENGINEER.
 - SEE SITE PLAN FOR PAVEMENT WIDTH AND LOCATION.
 - SEE GRADING, DRAINAGE AND EROSION CONTROL PLAN FOR PAVEMENT SLOPE AND CROSS-SLOPE.
 - A TACK COAT SHALL BE PLACED ON TOP OF BINDER COURSE PAVEMENT PRIOR TO PLACING WEARING COURSE.
 - REFER TO CITY SPECIFICATIONS FOR ASPHALT MIX DESIGN.

PARKING LOT PAVEMENT SECTION
NO SCALE




- NOTES:**
- COORDINATE FINAL DESIGN SECTION WITH GEOTECHNICAL ENGINEER.
 - SEE SITE PLAN FOR PAVEMENT WIDTH AND LOCATION.
 - SEE GRADING, DRAINAGE AND EROSION CONTROL PLAN FOR PAVEMENT SLOPE AND CROSS-SLOPE.
 - A TACK COAT SHALL BE PLACED ON TOP OF BINDER COURSE PAVEMENT PRIOR TO PLACING WEARING COURSE.
 - REFER TO CITY SPECIFICATIONS FOR ASPHALT MIX DESIGN.

ROADWAY PAVEMENT SECTION
NO SCALE




ROUNDAABOUT CENTER PLAN VIEW



ROUNDAABOUT CENTER SECTION

- NOTES:**
- BEDDING MATERIAL SHALL BE A SAND/CEMENT MIX THAT IS 3 PARTS SAND AND 1 PART CEMENT. SAND SHALL CONFORM WITH ASTM C33 AND CEMENT SHALL BE PORTLAND CEMENT TYPE I/TYPE II.

ROUNDAABOUT CENTER
NO SCALE



Proposed Multi-Family Development

Iron Horse Properties, LLC

105 Bartlett Street
Portsmouth,
New Hampshire

MARK	DATE	DESCRIPTION
H	1/20/2021	TAC Resubmission
G	11/18/2020	TAC Resubmission
F	10/28/2020	Wetland CUP Resubmission
E	5/20/2020	TAC Resubmission
D	4/29/2020	Wetland CUP Submission
C	4/20/2020	TAC Submission
B	2/6/2020	Design Review Submission
A	1/2/2020	ZBA Submission


PROJECT NO:	C-0960-006
DATE:	April 20, 2020
FILE:	C-0960-006_C-DTLS.DWG
DRAWN BY:	NAH
CHECKED:	PMC
APPROVED:	BML

DETAILS SHEET

SCALE: AS SHOWN


C-502

Last Saved: 1/20/2021 11:03:33am By: MAHANSEN
 Plotted On: Jan 20, 2021 1:10:33pm By: MAHANSEN
 Tighe & Bond: F:\C:\Users\cabinare\CAD\Drawings - Figures\AutoCAD\Sheet\C-0960-006_C-DTLS.dwg




VERTICAL GRANITE CURB
NO SCALE

- NOTES:
- SEE SITE PLAN(S) FOR LIMITS OF VERTICAL GRANITE CURB (VGC).
 - ADJOINING STONES SHALL HAVE THE SAME OR APPROXIMATELY THE SAME LENGTH.
 - MINIMUM LENGTH OF STRAIGHT CURB STONES = 3'
 - MAXIMUM LENGTH OF STRAIGHT CURB STONES = 10'
 - MAXIMUM LENGTH OF STRAIGHT CURB STONES LAID ON CURVES (SEE TABLE).
 - ALL RADII 20 FEET AND SMALLER SHALL BE CONSTRUCTED USING CURVED SECTIONS.
 - JOINTS BETWEEN STONES SHALL HAVE A MAXIMUM SPACING OF 1/2" AND SHALL BE MORTARED.





SLOPED GRANITE CURB
NO SCALE

- NOTES:
- SEE SITE PLAN(S) FOR LIMITS OF SLOPED GRANITE CURB (SGC).
 - ADJOINING STONES SHALL HAVE THE SAME OR APPROXIMATELY THE SAME LENGTH.
 - MINIMUM LENGTH OF STRAIGHT CURB STONES = 18"
 - MAXIMUM LENGTH OF STRAIGHT CURB STONES = 8'
 - MAXIMUM LENGTH OF STRAIGHT CURB STONES LAID ON CURVES (SEE TABLE).
 - JOINTS BETWEEN STONES SHALL HAVE A MAXIMUM SPACING OF 1/2" AND SHALL BE MORTARED.




DUMPSTER PAD
NO SCALE

- NOTES:
- CONCRETE TO BE 4500 PSI, 7% AIR ENTRAINED
 - STANDARD BROOM FINISH.




MOUNTABLE VERTICAL GRANITE CURB
NO SCALE

- NOTES:
- SEE SITE PLAN(S) FOR LIMITS OF MOUNTABLE VERTICAL GRANITE CURB (MVGC).
 - ADJOINING STONES SHALL HAVE THE SAME OR APPROXIMATELY THE SAME LENGTH.
 - MINIMUM LENGTH OF STRAIGHT CURB STONES = 3'
 - MAXIMUM LENGTH OF STRAIGHT CURB STONES = 10'
 - MAXIMUM LENGTH OF STRAIGHT CURB STONES LAID ON CURVES (SEE TABLE).
 - ALL RADII 20 FEET AND SMALLER SHALL BE CONSTRUCTED USING CURVED SECTIONS.
 - JOINTS BETWEEN STONES SHALL HAVE A MAXIMUM SPACING OF 1/2" AND SHALL BE MORTARED.



CURB TRANSITION
NO SCALE

- NOTES:
- THE INTENT OF THIS ITEM IS TO PROVIDE A SMOOTH TRANSITION BETWEEN VERTICAL GRANITE CURB AND MOUNTABLE VERTICAL GRANITE CURB WITHOUT REQUIRING FIELD CHIPPING DURING INSTALLATION. THE MOUNTABLE VERTICAL GRANITE CURB MAY REQUIRE ADJUSTMENTS TO MEET THE TRANSITION PIECE HEIGHT. TRANSITION SLOPE CURB TO STANDARD REVEAL AS QUICKLY AS POSSIBLE TO PROVIDE FOR THIS SMOOTH TRANSITION.




CONCRETE SIDEWALK
NO SCALE

- NOTES:
- SEE SITE PLAN FOR SIDEWALK WIDTH AND LOCATIONS.
 - SEE GRADING, DRAINAGE & EROSION CONTROL PLAN FOR WALK AND SIDE SLOPE GRADES.

NHDOT ITEM No. 304.3 (CRUSHED GRAVEL)	
SIEVE SIZE	% PASSING
3"	100
2"	95-100
1"	55-85
#4	27-52
#200	0-12

NHDOT ITEM No. 304.2 (GRAVEL)	
SIEVE SIZE	% PASSING
6"	100
#4	25-70
#200	0-12




RADIUS TYPE CAST IRON DETECTABLE WARNING SURFACE
NO SCALE

- NOTES:
- DETECTABLE WARNING SURFACE SHALL BE INSTALLED PER MANUFACTURER'S RECOMMENDATIONS.

- NOTES:
- CONTAINMENT MUST BE STRUCTURALLY SOUND AND LEAK FREE AND CONTAIN ALL LIQUID WASTES.
 - CONTAINMENT DEVICES MUST BE OF SUFFICIENT QUANTITY OR VOLUME TO COMPLETELY CONTAIN THE LIQUID WASTES GENERATED.
 - WASHOUT MUST BE CLEANED OR NEW FACILITIES CONSTRUCTED AND READY TO USE ONCE WASHOUT IS 75% FULL.
 - WASHOUT AREA(S) SHALL BE INSTALLED IN A LOCATION EASILY ACCESSIBLE BY CONCRETE TRUCKS.
 - ONE OR MORE AREAS MAY BE INSTALLED ON THE CONSTRUCTION SITE AND MAY BE RELOCATED AS CONSTRUCTION PROGRESSES.
 - AT LEAST WEEKLY REMOVE ACCUMULATION OF SAND AND AGGREGATE AND DISPOSE OF PROPERLY.

CONCRETE WASHOUT AREA
NO SCALE



Last Saved: 1/20/2021 10:33am By: Mahansen Plotted On: Jan 20, 2021 1:10:33pm File: C:\Users\mahansen\OneDrive\Documents\Drawings - Figures\AutoCAD\Sheet\C-0960-006_C-DTLS.dwg

Proposed Multi-Family Development

Iron Horse Properties, LLC

105 Bartlett Street
Portsmouth,
New Hampshire




MARK	DATE	DESCRIPTION
H	1/20/2021	TAC Resubmission
G	11/18/2020	TAC Resubmission
F	10/28/2020	Wetland CUP Resubmission
E	5/20/2020	TAC Resubmission
D	4/29/2020	Wetland CUP Submission
C	4/20/2020	TAC Submission
B	2/6/2020	Design Review Submission
A	1/2/2020	ZBA Submission

PROJECT NO: C-0960-006
DATE: April 20, 2020
FILE: C-0960-006_C-DTLS.DWG
DRAWN BY: NAH
CHECKED BY: PMC
APPROVED BY: BML

DETAILS SHEET


SCALE: AS SHOWN

C-503



SIGN LEGEND & SIGN POST
NO SCALE

BOLLARD MOUNTED SIGN DETAIL
NO SCALE



AASHTO #57 STONE (CHOKER COURSE)		MODIFIED NHDOT 304.1		AASHTO #8 STONE (PEA GRAVEL)		AASHTO #3 STONE (RESERVOIR COURSE)	
SIZE	% PASSING	SIZE	% PASSING	SIZE	% PASSING	SIZE	% PASSING
1 1/2"	100	6"	100	1/2"	100	2 1/2"	100
1"	95-100	#4	70-100	3/8"	85-100	2"	90-100
3/4"	25-60	#200	0-6*	#4	10-30	1 1/2"	35-70
#4	0-10			#8	0-10	1"	0-15
#8	0-5			#16	0-5	3/4"	0-5






*PREFERABLY <4%

- NOTES:**
- SEE GRADING, DRAINAGE, UTILITIES AND EROSION CONTROL PLAN FOR PAVEMENT SLOPE AND CROSS-SLOPE.
 - POROUS ASPHALT SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE LATEST SPECIFICATIONS FROM THE UNH STORMWATER CENTER FOR POROUS ASPHALT.
 - FILTER COURSE TO BE INCREASED AS NECESSARY TO MEET PROPOSED GRADES.
 - INSTALL FILTER COURSE AGGREGATE IN 8-INCH MAXIMUM LIFTS TO A MAXIMUM OF 95% STANDARD PROCTOR COMPACTION (ASTM D698 / AASHTO T99). INSTALL AGGREGATE TO GRADES INDICATED ON THE DRAWINGS.
 - INSTALL CHOKER, GRAVEL, AND STONE BASE COURSE AGGREGATE TO A MAXIMUM OF 95% COMPACTION STANDARD PROCTOR (ASTM D698 / AASHTO T99). CHOKER SHOULD BE PLACED EVENLY OVER SURFACE OF FILTER COURSE BED, SUFFICIENT TO ALLOW PLACEMENT OF PAVEMENT, AND NOTIFY ENGINEER FOR APPROVAL. CHOKER BASE COURSE THICKNESS SHALL BE SUFFICIENT TO ALLOW FOR EVEN PLACEMENT OF THE POROUS ASPHALT BUT NO LESS THAN 6-INCHES IN DEPTH.
 - THE DENSITY OF SUBBASE COURSES SHALL BE DETERMINED BY AASHTO T 191 (SAND-CONE METHOD), AASHTO T 204 (DRIVE CYLINDER METHOD), OR AASHTO T 238 (NUCLEAR METHODS), OR OTHER APPROVED METHODS AT THE DISCRETION OF THE SUPERVISING ENGINEER.

POROUS ASPHALT SECTION
NO SCALE

- NOTES:**
- RAMPS SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE AMERICANS WITH DISABILITIES ACT AND LOCAL AND STATE REQUIREMENTS.
 - A 6" COMPACTED CRUSHED GRAVEL BASE (NHDOT ITEM No. 304.3) SHALL BE PROVIDED BENEATH RAMPS.
 - DETECTABLE WARNING PANEL SHALL BE CAST IRON SET IN CONCRETE (SEE DETAIL.)
 - PROVIDE DETECTABLE WARNING SURFACES ANYTIME THAT A CURB RAMP, BLENDED TRANSITION, OR LANDING CONNECTS TO A STREET.
 - LOCATE THE DETECTABLE WARNING SURFACES AT THE BACK OF THE CURB ALONG THE EDGE OF THE LANDING.
 - THE MAXIMUM RUNNING SLOPE OF ANY SIDEWALK CURB RAMP IS 12:1; THE MAXIMUM CROSS SLOPE IS 2%; THE SLOPE OF THE LANDING SHALL NOT EXCEED 2% IN ANY DIRECTION.
 - TRANSITIONS SHALL BE FLUSH AND FREE OF ABRUPT CHANGES. ROADWAY SHOULDER SLOPES ADJOINING SIDEWALK CURB RAMPS SHALL BE A MAXIMUM OF 5% (FULL WIDTH) FOR A DISTANCE OF 2 FT. FROM THE ROADWAY CURBLINE.
 - THE BOTTOM OF THE SIDEWALK CURB RAMP OR LANDING, EXCLUSIVE OF THE FLARED SIDES, SHALL BE WHOLLY CONTAINED WITHIN THE CROSSWALK MARKINGS.
 - DETECTABLE WARNING PANELS SHALL BE A MINIMUM OF 2 FEET IN DEPTH. THE ROWS OF TRUNCATED DOMES SHALL BE ALIGNED PERPENDICULAR TO THE GRADE BREAK BETWEEN THE RAMP, BLENDED TRANSITION, OR LANDING AND THE STREET.
 - THE TEXTURE OF THE DETECTABLE WARNING FEATURE MUST CONTRAST VISUALLY WITH THE SURROUNDING SURFACES (EITHER LIGHT-ON-DARK OR DARK-ON-LIGHT).

NHDOT ITEM No. 304.3 (CRUSHED GRAVEL)	
SI-EVE SIZE	% PASSING
3"	100
2"	95-100
1"	55-85
#4	27-52
#200	0-12



CONCRETE WHEELCHAIR ACCESSIBLE RAMP
NO SCALE


SECTION A-A

SECTION B-B


SECTION C-C

PLAN A

PLAN VIEW




DRAIN CLEAN-OUT
NO SCALE




- NOTES:**
- PAVEMENT MARKINGS TO BE INSTALLED IN LOCATIONS AS SHOWN ON SITE PLAN.
 - ALL PAINT SHALL BE FAST DRYING TRAFFIC PAINT, MEETING THE REQUIREMENTS OF AASHTO M248-TYPE F. PAINT SHALL BE APPLIED AS SPECIFIED BY MANUFACTURER.

"SHARROW" SHARED LANE MARKING
NO SCALE




- NOTE:**
- PAVEMENT MARKINGS TO BE INSTALLED IN LOCATIONS AS SHOWN ON SITE PLAN.
 - STRIPING SHALL BE CONSTRUCTED USING WHITE THERMO PLASTIC, REFLECTORIZED PAVEMENT MARKING MATERIAL MEETING THE REQUIREMENTS OF ASTM D 4505

STOP BAR AND LEGEND
NO SCALE




- NOTE:**
- STRIPING SHALL BE CONSTRUCTED USING WHITE THERMO PLASTIC, REFLECTORIZED PAVEMENT MARKING MATERIAL MEETING THE REQUIREMENTS OF ASTM D 4505

CROSSWALK STRIPING
NO SCALE




- NOTES:**
- ALL PAINT SHALL BE FAST DRYING TRAFFIC PAINT, MEETING THE REQUIREMENTS OF AASHTO M248-TYPE F. PAINT SHALL BE APPLIED AS SPECIFIED BY MANUFACTURER.
 - SYMBOLS & PARKING STALLS SHALL CONFORM TO THE REQUIREMENTS OF THE AMERICAN W/DISABILITIES ACT.

ACCESSIBLE PARKING STALL
NO SCALE



- NOTES:**
- SYMBOL SHALL BE CONSTRUCTED IN ALL ACCESSIBLE SPACES USING WHITE THERMOPLASTIC, REFLECTORIZED PAVEMENT MARKING MATERIAL MEETING THE REQUIREMENTS OF ASTM D 4505.
 - SYMBOL SHALL BE CONSTRUCTED TO THE LATEST ADA, STATE AND LOCAL REQUIREMENTS.

ACCESSIBLE SYMBOL
NO SCALE



- NOTES:**
- THE WORDS "NO PARKING FIRE LANE" SHALL BE PAINTED ON THE PAVEMENT IN 30" HIGH LETTERS A (SEE PLAN FOR LOCATIONS).

FIRE LANE STRIPING
NO SCALE

Proposed Multi-Family Development

Iron Horse Properties, LLC

105 Bartlett Street
Portsmouth,
New Hampshire

MARK	DATE	DESCRIPTION
H	1/20/2021	TAC Resubmission
G	11/18/2020	TAC Resubmission
F	10/28/2020	Wetland CUP Resubmission
E	5/20/2020	TAC Resubmission
D	4/29/2020	Wetland CUP Submission
C	4/20/2020	TAC Submission
B	2/6/2020	Design Review Submission
A	1/2/2020	ZBA Submission


PROJECT NO:	C-0960-006
DATE:	April 20, 2020
FILE:	C-0960-006_C-DTLS.DWG
DRAWN BY:	NAH
CHECKED:	PMC
APPROVED:	BML

DETAILS SHEET



SCALE: AS SHOWN

C-504



Last Saved: 1/20/2021 10:33am By: Mahansen
Plotted On: Jan 20, 2021 10:33am By: Mahansen
Tighe & Bond: E:\Cadd\006-105-Bartlett-Street\Drawings - Figures\AutoCAD\Sheet\C-0960-006_C-DTLS.dwg



- NOTE:**
1. GRATE TO BE CAST IRON (NHDOT TYPE B)
 2. FRAME AND GRATE TO BE MANUFACTURED IN THE USA




CATCH BASIN FRAME & GRATE
NO SCALE




- NOTES:**
1. MANHOLE FRAME AND COVER SHALL BE 32\"/>
 - 2. ALL DIMENSIONS ARE NOMINAL.
 - 3. FRAMES USING NARROWER DIMENSIONS FOR THICKNESS ARE ALLOWED PROVIDED:
 - A. THE FRAMES MEET OR EXCEED THE SPECIFIED LOAD RATING.
 - B. THE INTERIOR PERIMETER (SEAT AREA) DIMENSIONS OF THE FRAMES REMAIN THE SAME TO ALLOW CONTINUED USE OF EXISTING GRATES/COVERS AS THE EXISTING FRAMES ALLOW, WITHOUT SHIMS OR OTHER MODIFICATIONS OR ACCOMMODATIONS.
 - C. ALL OTHER PERTINENT REQUIREMENTS OF THE SPECIFICATIONS ARE MET.
 - 4. LABEL TYPE OF MANHOLE WITH 3\"/>

DRAIN MANHOLE FRAME & COVER
NO SCALE



- NOTES:**
1. HORIZONTAL JOINTS BETWEEN THE SECTIONS OF PRECAST CONCRETE BARRELS SHALL BE PER CITY OF PORTSMOUTH DPW STANDARD AND SHALL BE SEALED FOR WATERTIGHTNESS USING A DOUBLE ROW ELASTOMERIC OR MASTIC-LIKE GASKET.
 2. PIPE TO MANHOLE JOINTS SHALL BE PER CITY OF PORTSMOUTH STANDARD.
 3. FOR BITUMASTIC TYPE JOINTS THE AMOUNT OF SEALANT SHALL BE SUFFICIENT TO FILL AT LEAST 75% OF THE JOINT CAVITY.
 4. ALL GASKETS, SEALANTS, MORTAR, ETC. SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURERS' WRITTEN INSTRUCTIONS.

MANHOLE JOINTS
NO SCALE




- NOTES:**
1. ALL CATCH BASIN OUTLETS TO HAVE "ELIMINATOR" OIL AND FLOATING DEBRIS TRAP MANUFACTURED BY KLEANSTREAM (NO EQUAL)
 2. INSTALL DEBRIS TRAP TIGHT TO INSIDE OF STRUCTURE.
 3. 1/4\"/>

"ELIMINATOR" OIL FLOATING DEBRIS TRAP
NO SCALE




NOMINAL PIPE SIZE I.D.*	OVERALL LENGTH**		NUMBER OF CLAMPS	CUFF DEPTH		BACK PRESSURE RATING	
	Inches	Millimeters		Inches	Millimeters	Feet	Meters
12	300	23	584	1	2	51	40
18	450	31	787	1	4	102	20
24	600	47.5	1207	2	8	203	20

Mounting Styles and Configurations




Flange shape and bolt pattern can be customized. Flangeless thimble inserts are available.

TYPICAL BACK FLOW PREVENTER
NO SCALE



- NOTES:**
1. POLYETHYLENE LINER (ITEM 604.0007) SHALL BE FABRICATED AT THE SHOP. DOWNSPOUT SHALL BE EXTRUSION FILLET WELDED TO THE POLYETHYLENE SHEET.
 2. PLACE A CONTINUOUS BEAD OF AN APPROVED SILICONE SEALANT (SUBSIDIARY TO ITEM 604.0007) BETWEEN FRAME AND POLYETHYLENE SHEET.
 3. PLACE CLASS AA CONCRETE TO 2\"/>
 - 4. USE ON DRAINAGE STRUCTURES 4\"/>
 - 5. TRIM POLYETHYLENE SHEET A MAXIMUM OF 4\"/>
 - 6. THE CENTER OF THE GRATE & FRAME MAY BE SHIFTED A MAXIMUM OF 6\"/>
 - 7. PLACED ONLY IN DRAINAGE STRUCTURES IN PAVEMENT.
 - 8. SEE NHDOT DR-04, "DI-DB, UNDERDRAIN FLUSHING BASIN AND POLYETHYLENE LINER DETAILS", FOR ADDITIONAL INFORMATION.
 - 9. CATCHBASINS WITHIN CITY RIGHT OF WAY SHALL HAVE A POLYETHYLENE LINER


POLYETHYLENE LINER
NO SCALE



- NOTES:**
1. ALL SECTIONS SHALL BE CONCRETE CLASS AA(4000 psi).
 2. CIRCUMFERENTIAL REINFORCEMENT SHALL BE 0.12 SQ.IN. PER LINEAR FT. IN ALL SECTIONS AND SHALL BE PLACED IN THE CENTER THIRD OF THE WALL.
 3. THE TONGUE AND GROOVE OF THE JOINT SHALL CONTAIN ONE LINE OF CIRCUMFERENTIAL REINFORCEMENT EQUAL TO 0.12 SQ. IN. PER LINEAR FT.
 4. RISERS OF 1', 2', 3' & 4' CAN BE USED TO REACH DESIRED DEPTH.
 5. THE STRUCTURES SHALL BE DESIGNED FOR H2O LOADING.
 6. FITTING FRAME TO GRADE MAY BE DONE WITH PREFABRICATED ADJUSTMENT RINGS OR CLAY BRICKS (2 COURSES MAX.).
 7. CONE SECTIONS MAY BE EITHER CONCENTRIC OR ECCENTRIC, OR FLAT SLAB TOPS MAY BE USED WHERE PIPE WOULD OTHERWISE ENTER INTO THE CONE SECTION OF THE STRUCTURE AND WHERE PERMITTED.
 8. PIPE ELEVATIONS SHOWN ON PLANS SHALL BE FIELD VERIFIED PRIOR TO PRECASTING.
 9. OUTSIDE EDGES OF PIPES SHALL PROJECT NO MORE THAN 3\"/>
 - 10. PRECAST SECTIONS SHALL HAVE A TONGUE AND GROOVE JOINT 4\"/>
 - 11. THE TONGUE AND GROOVE JOINT SHALL BE SEALED WITH ONE STRIP OF BUTYL RUBBER SEALANT.
 - 12. "ELIMINATOR" OIL/WATER SEPARATOR SHALL BE INSTALLED TIGHT TO INSIDE OF CATCHBASIN.

4\"/>

NHDOT ITEM No. 304.4 (CRUSHED STONE - FINE)	
SIIEVE SIZE	% PASSING
2"	100
1-1/2"	85-100
3/4"	45-75
#4	10-45
#200	0-5



- NOTES:**
1. ALL SECTIONS SHALL BE 4,000 PSI CONCRETE.
 2. CIRCUMFERENTIAL REINFORCEMENT SHALL BE 0.12 SQUARE INCHES PER LINEAR FOOT IN ALL SECTIONS AND SHALL BE PLACED IN THE CENTER THIRD OF THE WALL.
 3. THE TONGUE AND THE GROOVE OF THE JOINT SHALL CONTAIN ONE LINE OF CIRCUMFERENTIAL REINFORCEMENT EQUAL TO 0.12 SQUARE INCHES PER LINEAR FOOT.
 4. THE STRUCTURES SHALL BE DESIGNED FOR H2O LOADING.
 5. CONSTRUCT CRUSHED STONE BEDDING AND BACKFILL UNDER (6\"/>
 - 6. THE TONGUE AND GROOVE JOINT SHALL BE SEALED WITH ONE STRIP OF BUTYL RUBBER SEALANT.
 - 7. PIPE ELEVATIONS SHOWN ON PLANS SHALL BE FIELD VERIFIED PRIOR TO PRECASTING.
 - 8. OUTSIDE EDGES OF PIPES SHALL PROJECT NO MORE THAN 3\"/>
 - 9. PRECAST SECTIONS SHALL HAVE A TONGUE AND GROOVE JOINT 4\"/>
 - 10. ALL STRUCTURES WITH MULTIPLE PIPES SHALL HAVE A MINIMUM OF 12\"/>

4\"/>

Proposed Multi-Family Development

Iron Horse Properties, LLC

105 Bartlett Street
Portsmouth,
New Hampshire

MARK	DATE	DESCRIPTION
H	1/20/2021	TAC Resubmission
G	11/18/2020	TAC Resubmission
F	10/28/2020	Wetland CUP Resubmission
E	5/20/2020	TAC Resubmission
D	4/29/2020	Wetland CUP Submission
C	4/20/2020	TAC Submission
B	2/6/2020	Design Review Submission
A	1/2/2020	ZBA Submission

PROJECT NO:	C-0960-006
DATE:	April 20, 2020
FILE:	C-0960-006_C-DTLS.DWG
DRAWN BY:	NAH
CHECKED BY:	PMC
APPROVED:	BML

DETAILS SHEET

SCALE: AS SHOWN

C-505

Last Saved: 1/20/2021 1:10:33am By: Mahansen
 Plotted On: Jan 20, 2021 1:10:33am By: Mahansen
 Tighe & Bond: C:\Users\mahansen\OneDrive\Documents\C-0960-006_C-DTLS.dwg

JELLYFISH JFPD0808 - DESIGN NOTES

JELLYFISH TREATMENT CAPACITY IS A FUNCTION OF THE CARTRIDGE LENGTH AND THE NUMBER OF CARTRIDGES. THE STANDARD PEAK DIVERSION STYLE WITH PRECAST TOP SLAB IS SHOWN. ALTERNATE OFFLINE VAULT AND/OR SHALLOW ORIENTATIONS ARE AVAILABLE. PEAK CONVEYANCE CAPACITY TO BE DETERMINED BY ENGINEER OF RECORD

CARTRIDGE SELECTION	54"	40"	27"	15"
CARTRIDGE LENGTH	54"	40"	27"	15"
OUTLET INVERT TO STRUCTURE INVERT (A)	6'-6"	5'-4"	4'-3"	3'-3"
FLOW RATE HI-FLO / DRAINDOWN (CFS) (PER CART)	0.178 / 0.089	0.133 / 0.067	0.089 / 0.045	0.049 / 0.025
MAX. TREATMENT (CFS)	2.94	2.21	1.47	0.81
DECK TO INSIDE TOP (MIN) (B)	5.00	4.00	4.00	4.00

JELLYFISH JFPD0806 - DESIGN NOTES

JELLYFISH TREATMENT CAPACITY IS A FUNCTION OF THE CARTRIDGE LENGTH AND THE NUMBER OF CARTRIDGES. THE STANDARD PEAK DIVERSION STYLE WITH PRECAST TOP SLAB IS SHOWN. ALTERNATE OFFLINE VAULT AND/OR SHALLOW ORIENTATIONS ARE AVAILABLE. PEAK CONVEYANCE CAPACITY TO BE DETERMINED BY ENGINEER OF RECORD

CARTRIDGE SELECTION	54"	40"	27"	15"
CARTRIDGE LENGTH	54"	40"	27"	15"
OUTLET INVERT TO STRUCTURE INVERT (A)	6'-6"	5'-4"	4'-3"	3'-3"
FLOW RATE HI-FLO / DRAINDOWN (CFS) (PER CART)	0.178 / 0.089	0.133 / 0.067	0.089 / 0.045	0.049 / 0.025
MAX. TREATMENT (CFS)	1.96	1.47	0.98	0.54
DECK TO INSIDE TOP (MIN) (B)	5.00	4.00	4.00	4.00




SITE SPECIFIC DATA REQUIREMENTS

STRUCTURE ID	JF-1	JF-2	JF-3	JF-4
MODEL SIZE	JFPD0808	JFPD0806	JFPD0806	JFPD0806
WATER QUALITY FLOW RATE (cfs)	2.853	0.617	0.992	1.021
PEAK FLOW RATE (cfs)	26.54	5.07	8.82	4.48
RETURN PERIOD OF PEAK FLOW (yrs)	25	25	25	25
# OF CARTRIDGES REQUIRED (HF / DD)	15/3	5/1	5/2	7/2
CARTRIDGE SIZE	54"	40"	54"	54"


- GENERAL NOTES:**
- CONTECH TO PROVIDE ALL MATERIALS UNLESS NOTED OTHERWISE.
 - FOR SITE SPECIFIC DRAWINGS WITH DETAILED STRUCTURE DIMENSIONS AND WEIGHT, PLEASE CONTACT YOUR CONTECH ENGINEERED SOLUTIONS REPRESENTATIVE. www.contechES.com
 - JELLYFISH WATER QUALITY STRUCTURE SHALL BE IN ACCORDANCE WITH ALL DESIGN DATA AND INFORMATION CONTAINED IN THIS DRAWING. CONTRACTOR TO CONFIRM STRUCTURE MEETS REQUIREMENTS OF PROJECT.
 - STRUCTURE SHALL MEET AASHTO H5-20 OR PER APPROVING JURISDICTION REQUIREMENTS, WHICHEVER IS MORE STRINGENT, ASSUMING EARTH COVER OR 0' - 3' AND GROUNDWATER ELEVATION AT, OR BELOW, THE OUTLET PIPE INVERT ELEVATION. ENGINEER OF RECORD TO CONFIRM ACTUAL GROUNDWATER ELEVATION. CASTINGS SHALL MEET AASHTO M86 LOAD RATING AND BE CAST WITH THE CONTECH LOGO.
 - STRUCTURE SHALL BE PRECAST CONCRETE CONFORMING TO ASTM C-478 AND AASHTO LOAD FACTOR DESIGN METHOD.
 - OUTLET PIPE INVERT IS EQUAL TO THE CARTRIDGE DECK ELEVATION.
 - THE OUTLET PIPE DIAMETER FOR NEW INSTALLATIONS IS TO BE ONE PIPE SIZE LARGER THAN THE INLET PIPE AT EQUAL OR GREATER SLOPE.
 - NO PRODUCT SUBSTITUTIONS SHALL BE ACCEPTED UNLESS SUBMITTED 10 DAYS PRIOR TO PROJECT BID DATE, OR AS DIRECTED BY THE ENGINEER OF RECORD.

- INSTALLATION NOTES**
- ANY SUB-BASE BACKFILL DEPTH, AND/OR ANTI-FLOTATION PROVISIONS ARE SITE-SPECIFIC DESIGN CONSIDERATIONS AND SHALL BE SPECIFIED BY ENGINEER OF RECORD.
 - CONTRACTOR TO PROVIDE EQUIPMENT WITH SUFFICIENT LIFTING AND REACH CAPACITY TO LIFT AND SET THE STRUCTURE (LIFTING CLUTCHES PROVIDED).
 - CONTRACTOR WILL INSTALL AND LEVEL THE STRUCTURE, SEALING THE JOINTS, LINE ENTRY AND EXIT POINTS (NON-SHRINK GROUT WITH APPROVED WATERSTOP OR FLEXIBLE BOOT).
 - CONTRACTOR TO TAKE APPROPRIATE MEASURES TO PROTECT CARTRIDGES FROM CONSTRUCTION-RELATED EROSION RUNOFF.
 - CARTRIDGE INSTALLATION BY CONTECH SHALL OCCUR ONLY AFTER SITE HAS BEEN STABILIZED AND THE JELLYFISH UNIT IS CLEAN AND FREE OF DEBRIS. CONTACT CONTECH TO COORDINATE CARTRIDGE INSTALLATION WITH SITE STABILIZATION AT (866) 740-3318.

Jellyfish Filter
 www.contechES.com
 9025 Centre Pointe Dr., Suite 400, West Chester, OH 45399
 800-338-1122 513-645-7000 513-645-7993 FAX




ELEVATION VIEW JELLYFISH JFPD0806
ELEVATION VIEW JELLYFISH JFPD0808
CONTECH JELLYFISH STORMWATER FILTER
 NO SCALE



- NOTES:**
- GRATES/SOLID COVER SHALL BE DUCTILE IRON PER ASTM A536 GRADE 70-50-05.
 - FRAMES SHALL BE DUCTILE IRON PER ASTM A536 GRADE 70-50-05
 - SEE GRADING, DRAINAGE, AND EROSION CONTROL PLAN FOR LOCATIONS.

YARD DRAIN
NO SCALE




- NOTES:**
- RAIN GARDENS SHALL NOT BE PLACED INTO SERVICE UNTIL THE PRACTICE HAS BEEN PLANTED AND ITS CONTRIBUTING AREAS HAVE BEEN FULLY STABILIZED. DO NOT TRAFFIC EXPOSED SOIL SURFACES WITH CONSTRUCTION EQUIPMENT. CONTRACTOR SHALL KEEP ALL EXCAVATION EQUIPMENT OUTSIDE OF THE LIMIT OF THE RAIN GARDEN.
 - SEE GRADING, DRAINAGE & EROSION CONTROL PLAN FOR LOCATIONS, LAYOUTS, AND ELEVATIONS.
 - THE SAND PORTION OF THE FILTER MEDIA SHALL MEET THE FOLLOWING GRADATION (ASTM C-33):

FILTER MEDIA COMPOSITION:


COMPONENT MATERIAL	PERCENT OF MIXTURE BY VOLUME	GRADATION OF MATERIAL
ASTM C-33 CONCRETE SAND	50-55	SEE NOTE #5
LOAMY SAND TOPSOIL	20-30	15-25
MODERATELY FINE SHREDDED BARK OR WOOD FIBER MULCH	20-30	5 MAX

AASHTO #8 STONE (#8 to 3/8")		AASHTO #57 STONE (#4 to 1")	
SIEVE SIZE	% PASSING	SIEVE SIZE	% PASSING
1/2"	100	1-1/2"	100
3/8"	85-100	1"	95-100
#4	10-30	1/2"	25-60
#8	0-10	#4	0-10
#16	0-5	#8	0-5

RAIN GARDEN
NO SCALE



OUTLET STRUCTURE (POS1) DETAIL
NO SCALE



PDMH9 (5' DIA)
NO SCALE

- NOTE:**
- ALL JOINTS ON THE OUTLET STRUCTURE SHALL BE WATERTIGHT.

Proposed Multi-Family Development

Iron Horse Properties, LLC

105 Bartlett Street
Portsmouth,
New Hampshire


MARK	DATE	DESCRIPTION
H	1/20/2021	TAC Resubmission
G	11/18/2020	TAC Resubmission
F	10/28/2020	Wetland CUP Resubmission
E	5/20/2020	TAC Resubmission
D	4/29/2020	Wetland CUP Submission
C	4/20/2020	TAC Submission
B	2/6/2020	Design Review Submission
A	1/2/2020	ZBA Submission

PROJECT NO: C-0960-006
 DATE: April 20, 2020
 FILE: C-0960-006_C-DTLS.DWG
 DRAWN BY: NAH
 CHECKED BY: PMC
 APPROVED: BML

DETAILS SHEET

SCALE: AS SHOWN

C-506




Proposed Multi-Family Development
Iron Horse Properties, LLC

105 Bartlett Street
Portsmouth,
New Hampshire

MARK	DATE	DESCRIPTION
H	1/20/2021	TAC Resubmission
G	11/18/2020	TAC Resubmission
F	10/28/2020	Wetland CUP Resubmission
E	5/20/2020	TAC Resubmission
D	4/29/2020	Wetland CUP Submission
C	4/20/2020	TAC Submission
B	2/6/2020	Design Review Submission
A	1/2/2020	ZBA Submission

PROJECT NO:	C-0960-006
DATE:	April 20, 2020
FILE:	C-0960-006_C-DTLS.DWG
DRAWN BY:	NAH
CHECKED:	PMC
APPROVED:	BML

DETAILS SHEET
SCALE: AS SHOWN
C-507



PIPE DIA.	MIN. TRENCH WIDTH
12"	30"
15"	34"
18"	39"
24"	48"
30"	56"
36"	64"
42"	72"
48"	80"
60"	96"

PIPE DIA.	SURFACE LIVE LOADING CONDITION	
	H-25	HEAVY CONSTRUCTION (75T AXLE LOAD) *
12" - 48"	12"	48"
60"	24"	60"


TABLE 2, MINIMUM RECOMMENDED COVER BASED ON VEHICLE LOADING CONDITION * VEHICLES IN EXCESS OF 75T MAY REQUIRE ADDITIONAL COVER

PIPE DIA.	CLASS I	CLASS II	CLASS III	CLASS IV			
					95% COMPACTED	95% 90% 85% 95%	90% 95%
12"	41'	28'	21'	16'	20'	16'	16'
15"	42'	29'	21'	16'	21'	16'	16'
18"	44'	30'	21'	16'	22'	17'	16'
24"	37'	26'	18'	14'	19'	14'	14'

TABLE 3, MAXIMUM COVER FOR ADS HP STORM PIPE
FILL HEIGHT TABLE GENERATED USING AASHTO SECTION 12, LOAD RESISTANCE FACTOR DESIGN (LRFD) PROCEDURE WITH THE FOLLOWING ASSUMPTIONS:
NO HYDROSTATIC PRESSURE
UNIT WEIGHT OF SOIL (γs) = 120 PCF


- NOTES:
- ALL PIPE SYSTEMS SHALL BE INSTALLED IN ACCORDANCE WITH ASTM D2321, "STANDARD PRACTICE FOR UNDERGROUND INSTALLATION OF THERMOPLASTIC PIPE FOR SEWERS AND OTHER GRAVITY FLOW APPLICATIONS", LATEST ADDITION, WITH THE EXCEPTION THAT THE INITIAL BACKFILL MAY EXTEND TO THE CROWN OF THE PIPE. SOIL CLASSIFICATIONS ARE PER THE LATEST VERSION OF ASTM D2321. CLASS I/IV MATERIALS (MH, CH) AS DEFINED IN PREVIOUS VERSIONS OF ASTM D2321 ARE NOT APPROPRIATE BACKFILL MATERIALS.
 - MEASURES SHOULD BE TAKEN TO PREVENT MIGRATION OF NATIVE FINES INTO BACKFILL MATERIAL, WHEN REQUIRED.
 - FOUNDATION: WHERE THE TRENCH BOTTOM IS UNSTABLE AS JUDGED BY THE ENGINEER, THE CONTRACTOR SHALL EXCAVATE TO A DEPTH REQUIRED BY THE ENGINEER AND REPLACE WITH SUITABLE MATERIAL AS SPECIFIED BY THE ENGINEER. AS AN ALTERNATIVE AND AT THE DISCRETION OF THE DESIGN ENGINEER, THE TRENCH BOTTOM MAY BE STABILIZED USING A GEOTEXTILE MATERIAL. REFER TO SPECIFICATION 310000 EARTHWORK - SITE.
 - BEDDING: SUITABLE MATERIAL SHALL BE CLASS I, II, III, OR IV. THE CONTRACTOR SHALL PROVIDE DOCUMENTATION FOR MATERIAL SPECIFICATION TO ENGINEER. COMPACTION SHALL BE SPECIFIED BY THE ENGINEER IN ACCORDANCE WITH TABLE 3 FOR THE APPLICABLE FILL HEIGHTS LISTED. UNLESS OTHERWISE NOTED BY THE ENGINEER, MINIMUM BEDDING THICKNESS SHALL BE 4" (100mm) FOR 12"-24" (300mm-600mm) DIAMETER PIPE; 6" (150mm) FOR 30"-60" (750mm-1500mm) DIAMETER PIPE. THE MIDDLE 1/3 BENEATH THE PIPE INVERT SHALL BE LOOSELY PLACED. PLEASE NOTE, CLASS IV MATERIAL HAS LIMITED APPLICATION AND CAN BE DIFFICULT TO PLACE AND COMPACT; USE ONLY WITH THE APPROVAL OF THE GEOTECHNICAL ENGINEER.
 - INITIAL BACKFILL: SUITABLE MATERIAL SHALL BE CLASS I, II, III, OR IV IN THE PIPE ZONE EXTENDING TO THE CROWN OF THE PIPE. THE CONTRACTOR SHALL PROVIDE DOCUMENTATION FOR MATERIAL SPECIFICATION TO ENGINEER. MATERIAL SHALL BE INSTALLED AS REQUIRED IN ASTM D2321, LATEST EDITION. COMPACTION SHALL BE SPECIFIED BY THE ENGINEER IN ACCORDANCE WITH TABLE 3 FOR THE APPLICABLE FILL HEIGHTS LISTED. PLEASE NOTE, CLASS IV MATERIAL HAS LIMITED APPLICATION AND CAN BE DIFFICULT TO PLACE AND COMPACT; USE ONLY WITH THE APPROVAL OF THE GEOTECHNICAL ENGINEER.
 - MINIMUM COVER: FOR TRAFFIC APPLICATIONS, MINIMUM COVER, H, IS 12" (300mm) UP TO 48" (1200mm) DIAMETER PIPE AND 24" (600mm) OF COVER FOR 60" (1500mm) DIAMETER PIPE, MEASURED FROM TOP OF PIPE TO BOTTOM OF FLEXIBLE PAVEMENT OR TO TOP OF RIGID PAVEMENT.
 - FOR ADDITIONAL INFORMATION SEE TECHNICAL NOTE 2.04.

HP STORM TRENCH INSTALLATION DETAIL
NO SCALE



- NOTES:
- UNDERGROUND DETENTION SYSTEM TO BE 60" HDPE PIPE DESIGNED FOR H-20 LOADING. CONTRACTOR TO SUBMIT PIPE SPECIFICATIONS AND FINAL MANUFACTURERS DESIGN TO ENGINEER FOR APPROVAL.
 - MANUFACTURER TO SUBMIT PLANS STAMPED BY A PROFESSIONAL ENGINEER LICENSED IN THE STATE OF NEW HAMPSHIRE.
 - THE DESIGN ENGINEER SHALL PROVIDE SUFFICIENT INSPECTION TO CERTIFY THAT THE SYSTEM HAS BEEN INSTALLED PER THE APPROVED DESIGN PLAN.
 - REFER TO STANDARD DUTY PAVEMENT SECTION DETAIL FOR PAVEMENT SECTION.

UNDERGROUND DETENTION SYSTEM DETAIL
NO SCALE



DIMENSIONS AND QUANTITIES FOR ONE WING TYPE ENDWALL



D	B	C	G	H	K	L	P	Q	R	W	WOL
IN.	FT-IN	FT-IN	FT-IN	FT-IN	FT-IN	FT-IN	FT-IN	FT-IN	FT-IN	FT-IN	CY
24	1'-6"	2'-0"	3'-3"	6'-9"	9'-1 1/2"	7'-3 3/4"	1'-4 1/2"	0'-9 3/4"	3'-4 1/2"	5'-5 1/2"	5.87
36	1'-6"	2'-0"	3'-3"	6'-8"	9'-1 1/4"	7'-3 3/4"	1'-4 1/2"	0'-9 3/4"	3'-4 1/2"	5'-5 1/2"	5.87
42	1'-6"	2'-0"	3'-3"	7'-2"	9'-10 1/4"	7'-9 3/4"	1'-6 1/2"	0'-9 3/4"	3'-10 1/4"	6'-7 1/2"	6.67

* FOR D < 36" USE DIMENSIONS LISTED FOR D = 36"

HEADWALL WITH WINGWALLS
NO SCALE


OUTLET PLUNGE POOL SIZING

	Do	S	W	L	D50	D
HW1	24"	1.0'	4.0'	6.0'	8"	1.5'
HW2	18"	0.75'	3.0'	5.0'	6"	1.13'
HW3	24"	1.0'	4.0'	6.0'	6"	1.13'



ELECTRICAL AND COMMUNICATION CONDUIT
NO SCALE

- NOTES:
- NUMBER, MATERIAL, AND SIZE OF UTILITY CONDUITS TO BE DETERMINED BY LOCAL UTILITY OR AS SHOWN ON ELECTRICAL DRAWINGS. CONTRACTOR TO PROVIDE ONE SPARE CONDUIT FOR EACH UTILITY TO BUILDING.
 - DIMENSIONS SHOWN REPRESENT OWNERS MINIMUM REQUIREMENTS. ACTUAL DIMENSIONS MAY BE GREATER BASED ON UTILITY COMPANY STANDARDS, BUT SHALL NOT BE LESS THAN THOSE SHOWN.
 - NO CONDUIT RUN SHALL EXCEED 360 DEGREES IN TOTAL BENDS.
 - A SUITABLE PULLING STRING, CAPABLE OF 200 POUNDS OF PULL, MUST BE INSTALLED IN THE CONDUIT BEFORE UTILITY COMPANY IS NOTIFIED TO INSTALL CABLE. THE STRING SHOULD BE BLOWN INTO THE CONDUIT AFTER THE RUN IS ASSEMBLED TO AVOID BONDING THE STRING TO THE CONDUIT.
 - UTILITY COMPANY MUST BE GIVEN THE OPPORTUNITY TO INSPECT THE CONDUIT PRIOR TO BACKFILL. THE CONTRACTOR IS RESPONSIBLE FOR ALL REPAIRS SHOULD THE UTILITY COMPANY BE UNABLE TO INSTALL ITS CABLE IN A SUITABLE MANNER.
 - ALL CONDUIT INSTALLATIONS MUST CONFORM TO THE CURRENT EDITION OF THE NATIONAL ELECTRIC SAFETY CODE, STATE AND LOCAL CODES AND ORDINANCES, AND, WHERE APPLICABLE, THE NATIONAL ELECTRIC CODE. ALL 90° SWEEPS WILL BE MADE USING RIGID GALVANIZED STEEL SWEEPS WITH A 36 TO 48 INCH RADIUS.
 - SAND BEDDING TO BE REPLACED WITH CONCRETE ENCASEMENT WHERE COVER IS LESS THAN 3 FEET, WHEN LOCATED BELOW PAVEMENT, OR WHERE SHOWN ON THE UTILITIES PLAN.




GAS TRENCH
NO SCALE

WATER TRENCH
NO SCALE

- NOTE:
- SAND BEDDING AND BACKFILL FOR FULL WIDTH OF THE TRENCH FROM 6" BELOW PIPE IN EARTH AND 12" BELOW PIPE IN ROCK UP TO 12" ABOVE TOP OF PIPE.
 - GAS SHALL BE INSTALLED PER UNTIL STANDARDS. COORDINATE ALL INSTALLATIONS WITH THE CITY OF PORTSMOUTH.


- NOTES:
- SAND BEDDING AND BACKFILL FOR FULL WIDTH OF THE TRENCH FROM 6" BELOW PIPE IN EARTH AND 12" BELOW PIPE IN ROCK UP TO 12" ABOVE TOP OF PIPE.
 - WATER MAIN SHALL BE INSTALLED PER CITY OF PORTSMOUTH STANDARDS. COORDINATE ALL INSTALLATIONS WITH THE CITY OF PORTSMOUTH.
 - WATER MAIN TO BE PLACED IN A PROTECTIVE POLYWRAP AND INSTALLED WITH 3 CONTINUITY WEDGES PER JOINT.

Last Saved: 1/20/2021 11:03:33am By: Mahansen
Plotted On: Jan 20, 2021 1:10:33pm
Tighe & Bond, P.C. 105 Bartlett Street, Portsmouth, NH 03801
Figures AutoCAD Sheet: C-0960-006_C-DTLS.dwg



YARD DRAIN 1
NO SCALE

- NOTES:
1. CONCRETE SHALL BE 4,000 PSI (TYPE II CEMENT)
 2. SEE SITE, GRADING, DRAINAGE, EROSION CONTROL & UTILITIES PLAN FOR LOCATIONS.
 3. THE STRUCTURES SHALL BE DESIGNED FOR H2O LOADING.
 4. ALL JOINTS ON THE STRUCTURE AND PIPING SHALL BE WATERTIGHT.




THRUST BLOCKING DETAIL
NO SCALE

REACTION TYPE	PIPE SIZE				
	4"	6"	8"	10"	12"
A 90°	0.89	2.19	3.82	11.14	17.24
B 180°	0.65	1.55	2.78	8.38	12.00
C 45°	0.48	1.19	2.12	6.02	9.32
D 22-1/2°	0.25	0.60	1.06	3.08	4.74
E 11-1/4°	0.13	0.30	0.54	1.54	2.38


TEST PRESSURE = 200psi

- NOTES:
1. POUR THRUST BLOCKS AGAINST UNDISTURBED MATERIAL, WHERE TRENCH WALL HAS BEEN DISTURBED, EXCAVATE LOOSE MATERIAL AND EXTEND THRUST BLOCK TO UNDISTURBED MATERIAL. NO JOINTS SHALL BE COVERED WITH CONCRETE.
 2. ON BENDS AND TEES, EXTEND THRUST BLOCKS FULL LENGTH OF FITTING.
 3. PLACE BOARD IN FRONT OF ALL PLUGS BEFORE POURING THRUST BLOCKS.
 4. WHERE M.J. PIPE IS USED, M.J. PLUG WITH RETAINER GLAND MAY BE SUBSTITUTED FOR END BLOCKINGS.
 5. INSTALLATION AND STANDARD DIMENSIONAL REQUIREMENTS SHALL BE WITH CITY OF PORTSMOUTH WATER DEPARTMENT STANDARDS.



- NOTE:
1. HYDRANT TO BE KENNEDY TYPE K-81, RIGHT OPEN (NO EQUAL). COORDINATE WITH CITY OF PORTSMOUTH WATER DEPARTMENT AND CITY OF PORTSMOUTH FIRE DEPARTMENT.
 2. PAINT HYDRANT IN ACCORDANCE WITH CITY STANDARD SPECIFICATIONS AFTER INSTALLATION AND TESTING.


FIRE HYDRANT
NO SCALE



TRENCH DRAIN PROFILE


- NOTES:
1. TRENCH DRAIN FRAME AND GRATE SHALL BE MULTIDRAIN ECONODRAIN SERIES #12 OR EQUAL.

TRENCH DRAIN DETAIL
NO SCALE




ROADWAY TRENCH PATCH
NO SCALE

- NOTE:
- COORDINATE AND OBTAIN APPROVAL FOR ALL TRENCHING AND PATCHING WITHIN CITY RIGHT OF WAY WITH CITY OF PORTSMOUTH DPW PRIOR TO COMMENCING WORK.




- NOTES:
1. INVERT AND SHELF TO BE PLACED AFTER EACH LEAKAGE TEST.
 2. CARE SHALL BE TAKEN TO INSURE THAT THE BRICK INVERT IS A SMOOTH CONTINUATION OF THE SEWER INVERT.
 3. INVERT BRICKS SHALL BE LAID ON EDGE.
 4. BITUMINOUS WATERPROOF COATING TO BE APPLIED TO ENTIRE EXTERIOR OF MANHOLE.
 5. FRAMES AND COVERS: MANHOLE FRAMES AND COVERS WITHIN CITY RIGHT OF WAY SHALL BE CITY STANDARD HINGE COVERS MANUFACTURED BY E.J. FRAMES AND COVERS WILL BE PURCHASED FROM THE CITY OF PORTSMOUTH DEPARTMENT OF PUBLIC WORKS. ALL OTHER MANHOLE FRAMES AND COVERS SHALL BE OF HEAVY DUTY DESIGN AND PROVIDE A 30-INCH CLEAR OPENING. A 3-INCH (MINIMUM HEIGHT) WORD "SEWER" SHALL BE PLAINLY CAST INTO THE CENTER OF EACH COVER.
 6. HORIZONTAL JOINTS SHALL BE SEALED FOR WATER TIGHTNESS USING A DOUBLE ROW OF ELASTOMERIC OR MASTIC-LIKE SEALANT.
 7. BARREL AND CONE SECTIONS SHALL BE PRECAST REINFORCED CONCRETE DESIGNED FOR H2O LOADING, AND CONFORMING TO ASTM C478-06.

SEWER MANHOLE
NO SCALE





STANDARD SERVICE LATERAL CONNECTION
NO SCALE



- NOTE:
1. CRUSHED STONE BEDDING FOR FULL WIDTH OF THE TRENCH FROM 6" BELOW PIPE IN EARTH AND 12" BELOW PIPE IN ROCK. CRUSHED STONE SHALL ALSO COMPLETELY ENCASE THE PIPE AND COVER THE PIPE TO A GRADE 6" OVER THE TOP OF THE PIPE FOR THE ENTIRE WIDTH OF THE TRENCH.
 2. COORDINATE ALL INSTALLATIONS WITH THE CITY OF PORTSMOUTH.

SEWER SERVICE TRENCH
NO SCALE



- NOTES:
1. SEAL ENDS OF SLEEVE TO PREVENT MIGRATION OF MATERIAL AND WATER THROUGH ANNULAR SPACE BETWEEN CASING PIPE AND CARRIER PIPE
 2. STEEL CASING PIPE SHALL MEET COOPERS E-80 RAILROAD LOADING WITH A MINIMUM YIELD STRENGTH OF 35,000 PSI AND SHALL CONFORM TO THE LATEST REVISIONS OF THE REQUIREMENTS OF A.W.A. STANDARDS FOR FABRICATING ELECTRICALLY WELDED STEEL WATER PIPES OR ITS EQUIVALENT.
 3. STEEL CASING PIPE JOINTS SHALL BE FULLY WELDED AROUND THE COMPLETE CIRCUMFERENCE OF THE PIPE.
 4. CONTRACTOR SHALL COORDINATE ALL UTILITY AND CARRIER PIPE WORK WITHIN THE RAIL ROAD RIGHT OF WAY WITH PAN-AM & THE CITY PORTSMOUTH DPW PRIOR TO CONSTRUCTION.

WATER PIPELINE SLEEVE DETAIL (CARRIER PIPE)
NO SCALE



Proposed Multi-Family Development

Iron Horse Properties, LLC

105 Bartlett Street
Portsmouth,
New Hampshire



MARK	DATE	DESCRIPTION
H	1/20/2021	TAC Resubmission
G	11/18/2020	TAC Resubmission
F	10/28/2020	Wetland CUP Resubmission
E	5/20/2020	TAC Resubmission
D	4/29/2020	Wetland CUP Submission
C	4/20/2020	TAC Submission
B	2/6/2020	Design Review Submission
A	1/2/2020	ZBA Submission

DETAILS SHEET

SCALE: AS SHOWN


C-508

Last Saved: 1/20/2021 10:33am By: Mahansen
 Plotted On: Jan 20, 2021 1:10:33pm
 Tighe & Bond: E:\C:\Users\mahansen\OneDrive\Documents\CAD\Drawings - Figures\AutoCAD\Sheet\C-0960-006_C-DTLS.dwg




3-PHASE TRANSFORMER PAD
NO SCALE

- NOTES:**
1. DIMENSIONS SHOWN REPRESENT TYPICAL REQUIREMENTS. MANHOLE LOCATIONS AND REQUIREMENTS SHALL BE COORDINATED WITH EVERSOURCE PRIOR TO CONSTRUCTION
 2. CONCRETE MINIMUM STRENGTH - 4,000 PSI @ 28 DAYS
 3. STEEL REINFORCEMENT - ASTM A615, GRADE 60
 4. PAD MEETS OR EXCEEDS EVERSOURCE SPECIFICATIONS



- NOTES:**
- THE GROUND GRID SHALL BE SUPPLIED AND INSTALLED BY THE CONTRACTOR AND IS TO BE BURIED AT LEAST 12 INCHES BELOW GRADE. EIGHT FEET OF EXTRA WIRE FOR EACH GROUND GRID LEG SHALL BE LEFT EXPOSED IN THE CABLE COMPARTMENT TO ALLOW FOR THE CONNECTION TO THE TRANSFORMER. THE TWO 8-FOOT GROUND RODS MAY BE EITHER GALVANIZED STEEL OR COPPERWELD AND THEY SHALL BE CONNECTED TO THE GRID WITH NEC APPROVED CONNECTORS.

PAD-MOUNTED EQUIPMENT GROUNDING GRID DETAIL
NO SCALE



Proposed Multi-Family Development

Iron Horse Properties, LLC

105 Bartlett Street
Portsmouth,
New Hampshire

MARK	DATE	DESCRIPTION
H	1/20/2021	TAC Resubmission
G	11/18/2020	TAC Resubmission
F	10/28/2020	Wetland CUP Resubmission
E	5/20/2020	TAC Resubmission
D	4/29/2020	Wetland CUP Submission
C	4/20/2020	TAC Submission
B	2/6/2020	Design Review Submission
A	1/2/2020	ZBA Submission

PROJECT NO:	C-0960-006
DATE:	April 20, 2020
FILE:	C-0960-006_C-DTLS.DWG
DRAWN BY:	NAH
CHECKED:	PMC
APPROVED:	BML

DETAILS SHEET


SCALE: AS SHOWN

C-509

Plant List

Symbol	Botanical Name	Common Name	Quantity	Size	Comments
Am	<i>Amelanchier canadensis</i>	Shadbowl Serviceberry	2	2.5-3" Cal	B&B
Ar	<i>Acer rubrum</i> 'October Glory'	October Glory Red Maple	1	2.5-3" Cal	B&B
As	<i>Acer saccharum</i> 'Green Mountain'	Green Mountain Sugar Maple	1	2.5-3" Cal	B&B
Bn	<i>Betula nigra</i> 'Heritage'	Heritage River Birch	8	8-10" Ht	Multi-stem, B&B
Cb	<i>Carpinus carolinianum</i>	American Hornbeam	2	2.5-3" Cal	B&B
Gt	<i>Ginkgo biloba</i> 'Autumn Gold'	Autumn Gold Ginkgo	4	2.5-3" Cal	B&B
Gl	<i>Gleditsia triacanthos</i> 'Inermis	Halka Thornless Honeylocust	2	2.5-3" Cal	B&B
Ham	<i>Hamamelis x intermedia</i> 'Arnold promise'	Arnold Promise Witchhazel	1	8-10" Ht	Multi-stem, B&B
Ls	<i>Liquidambar styraciflua</i>	American Sweetgum	5	2.5-3" Cal	B&B
Lt	<i>Liriodendron tulipifera</i>	Tuliptree	5	2.5-3" Cal	B&B
Mal	<i>Malus</i> 'Sugar Tyme'	Sugartyme White Crabapple	6	1.5-2" Cal	B&B
Ns	<i>Nyssa sylvatica</i>	Black Tupelo	1	4" Cal	B&B
Qp	<i>Quercus palustris</i> 'Green Pillar'	Green Pillar Pin Oak	7	2.5-3" Cal	B&B
Th	<i>Thuja plicata</i> 'Green Giant'	Green Giant Arborvitae	3	2.5-3" Cal	B&B
Ua	<i>Ulmus americana</i> 'Princeton'	Princeton American Elm	6	2.5-3" Cal	B&B

Lawn Penninton Smartseed Tall Fescue Blend
Seed Mix 1 New England Wetland Plants, Inc. New England Conservation/Wildlife Mix



General Landscape Notes


- Design is based on drawings by Tighe & Bond dated January 14, 2020 and may require adjustment due to actual field conditions.
- The contractor shall follow best management practices during construction and shall take all means necessary to stabilize and protect the site from erosion.
- Erosion Control shall be in place prior to construction.
- The Contractor shall verify layout and grades and inform the Landscape Architect or Client's Representative of any discrepancies or changes in layout and/or grade relationships prior to construction.
- It is the contractor's responsibility to verify drawings provided are to the correct scale prior to any bid, estimate or installation. A graphic scale bar has been provided on each sheet for this purpose. If it is determined that the scale of the drawing is incorrect, the landscape architect will provide a set of drawings at the correct scale, at the request of the contractor.
- Trees to Remain within the construction zone shall be protected from damage for the duration of the project by snow fence or other suitable means of protection to be approved by Landscape Architect or Client's Representative. Snow fence shall be located at the drip line at a minimum and shall include any and all surface roots. Do not fill or mulch on the trunk flare. Do not disturb roots. In order to protect the integrity of the roots, trunk and bark of the tree(s) no vehicles or construction equipment shall drive or park in or on the area within the drip line(s) of the tree(s). Do not store any refuse or construction materials or portalets within the tree protection area.
- This plan is for review purposes only, NOT for Construction. Construction Documents will be provided upon request.
- Location, support, protection, and restoration of all existing utilities and appurtenances shall be the responsibility of the Contractor.
- The Contractor shall verify exact location and elevation of all utilities with the respective utility owners prior to construction. Call DIGSAFE at 1-888-344-7233.
- The Contractor shall procure any required permits prior to construction.
- Prior to any landscape construction activities Contractor shall test all existing loam and loam from off-site intended to be used for lawns and plant beds using a thorough sampling throughout the supply. Soil testing shall indicate levels of pH, nitrates, macro and micro nutrients, texture, soluble salts, and organic matter. Contractor shall provide Landscape Architect with test results and recommendations from the testing facility along with soil amendment plans as necessary for the proposed plantings to thrive. All loam to be used on site shall be amended as approved by the Landscape Architect prior to placement.
- Contractor shall notify landscape architect or owner's representative immediately if at any point during demolition or construction a site condition is discovered which may negatively impact the completed project. This includes, but is not limited to, unforeseen drainage problems, unknown subsurface conditions, and discrepancies between the plan and the site. If a contractor is aware of a potential issue, and does not bring it to the attention of the landscape architect or owner's representative immediately, they may be responsible for the labor and materials associated with correcting the problem.
- The Contractor shall furnish and plant all plants shown on the drawings and listed thereon. All plants shall be nursery-grown under climatic conditions similar to those in the locality of the project. Plants shall conform to the botanical names and standards of size, culture, and quality for the highest grades and standards as adopted by the American Association of Nurserymen, Inc. in the American Standard of Nursery Stock, American Standards Institute, Inc. 230 Southern Building, Washington, D.C. 20005.
- A complete list of plants, including a schedule of sizes, quantities, and other requirements is shown on the drawings. In the event that quantity discrepancies or material omissions occur in the plant materials list, the planting plans shall govern.
- All plants shall be legibly tagged with proper botanical name.
- The Contractor shall guarantee all plants for not less than one year from time of acceptance.
- Owner or Owner's Representative will inspect plants upon delivery for conformity to Specification requirements. Such approval shall not affect the right of inspection and rejection during or after the progress of the work. The Owner reserves the right to inspect and/or select all trees at the place of growth and reserves the right to approve a representative sample of each type of shrub, herbaceous perennial, annual, and ground cover at the place of growth. Such sample will serve as a minimum standard for all plants of the same species used in this work.
- No substitutions of plants may be made without prior approval of the Owner or the Owner's Representative for any reason.
- All landscaping shall be provided with the following:
 - Outside hose attachments spaced a maximum of 150 feet apart, and
 - An underground irrigation system, or
 - A temporary irrigation system designed for a two-year period of plant establishment.
- If an automatic irrigation system is installed, all irrigation valve boxes shall be located within planting bed areas.
- The contractor is responsible for all plant material from the time their work commences until final acceptance. This includes but is not limited to maintaining all plants in good condition, the security of the plant material once delivered to the site, and watering of plants. Plants shall be appropriately watered prior to, during and after planting. It is the contractor's responsibility to provide clean water suitable for plant health from off site, should it not be available on site.
- All disturbed areas will be dressed with 6" of topsoil and planted as noted on the plans or seeded except plant beds. Plant beds shall be prepared to a depth of 12" with 75% loam and 25% compost.
- Trees, ground cover, and shrub beds shall be mulched to a depth of 2" with one-year-old, well-composted, shredded native bark not longer than 4" in length and 1/2" in width, free of woodchips and sawdust. Mulch for ferns and herbaceous perennials shall be no longer than 1" in length. Trees in lawn areas shall be mulched in a 5' diameter min. saucer. Color of mulch shall be black.
- In no case shall mulch touch the stem of a plant nor shall mulch ever be more than 3" thick total (including previously applied mulch) over the root ball of any plant.
- Secondary lateral branches of deciduous trees overhanging vehicular and pedestrian travel ways shall be pruned up to a height of 6' to allow clear and safe passage of vehicles and pedestrians under tree canopy. Within the sight distance triangles at vehicle intersections the canopies shall be raised to 8' min.
- Snow shall be stored a minimum of 5' from shrubs and trunks of trees.
- Landscape Architect is not responsible for the means and methods of the contractor.

City of Portsmouth Landscape Notes

- The property owner and all future property owners shall be responsible for the maintenance, repair and replacement of all required screening and landscape materials.
- All required plant materials shall be tended and maintained in a healthy growing condition, replaced when necessary, and kept free of refuse and debris. All required fences and walls shall be maintained in good repair.
- The property owner shall be responsible to remove and replace dead or diseased plant materials immediately with the same type, size and quantity of plant materials as originally installed, unless alternative plantings are requested, justified and approved by the Planning Board or Planning Director.

INVASIVES REMOVAL AND DISTURBANCES WITHIN THE BUFFER ZONE

With the exception of the Norway Maples in the 25' vegetated buffer, which are to remain, invasive species within the 100' shoreland setback will be removed. Invasive species within the 25' vegetated buffer will be flagged in field by the landscape architect or certified arborist to be removed. Invasive shrubs within the 25' vegetated buffer with caliper measuring greater than 3" such as Buckthorn and Autumn Olive will be flush cut repeatedly to kill the plant, leaving the stumps in place. Woody invasives smaller than 3" caliper shall be removed with hand tools. Areas of soil disturbance from such removals will be limited to the immediate root area surrounding each plant, dressed with loam, replanted with New England Wildlife and Conservation Seed Mix and stabilized with jute mesh staked in place. All other areas disturbed by headwalls and culverts shall be loamed, seeded with New England Wildlife and Conservation Seed Mix and stabilized with jute mesh.




City of Portsmouth Tree Planting Detail

PART 1 - GENERAL

1.1 THE BASIS OF THE CITY OF PORTSMOUTH TREE PLANTING REQUIREMENTS IS THE ANSI A300 PART 6 STANDARD PRACTICES FOR PLANTING AND TRANSPLANTING. ANSI A300 PART 6 LAYS OUT TERMS AND BASIC STANDARDS AS SET FORTH BY INDUSTRY BUT IT IS NOT THE "END ALL" FOR THE CITY OF PORTSMOUTH. THE FOLLOWING ARE THE CITY OF PORTSMOUTH, NH TREE PLANTING REQUIREMENTS THAT ARE IN ADDITION TO OR THAT GO BEYOND THE ANSI A300 PART 6.

PART 2 - EXECUTION

- ALL PLANTING HOLES SHALL BE DUG BY HAND - NO MACHINES. THE ONLY EXCEPTIONS ARE NEW CONSTRUCTION WHERE NEW PLANTING PITS, PLANTING BEDS WITH GRANITE CURBING, AND PLANTING SITES WITH SILVA CELLS ARE BEING CREATED. IF A MACHINE IS USED TO DIG IN ANY OF THESE SITUATIONS AND PLANTING DEPTH NEEDS TO BE RAISED THE MATERIAL IN THE BOTTOM OF THE PLANTING HOLE MUST BE FIRMED WITH MACHINE TO PREVENT SINKING OF THE ROOT BALL.
- ALL WIRE AND BURLAP SHALL BE REMOVED FROM THE ROOT BALL AND PLANTING HOLE.
- THE ROOT BALL OF THE TREE SHALL BE WORKED SO THAT THE ROOT COLLAR OF THE TREE IS VISIBLE AND NO GRIDLING ROOTS ARE PRESENT.
- THE ROOT COLLAR OF THE TREE SHALL BE 2"-3" ABOVE GRADE OF PLANTING HOLE FOR FINISHING DEPTH.
- ALL PLANTINGS SHALL BE BACKFILLED WITH SOIL FROM THE SITE AND AMENDED NO MORE THAN 20% WITH ORGANIC COMPOST. THE ONLY EXCEPTIONS ARE NEW CONSTRUCTION WHERE ENGINEERED SOIL IS BEING USED IN CONJUNCTION WITH SILVA CELLS AND WHERE NEW PLANTING BEDS ARE BEING CREATED.
- ALL PLANTINGS SHALL BE BACKFILLED IN THREE LIFTS AND ALL LIFTS SHALL BE WATERED SO THE PLANTING WILL BE SET AND FREE OF AIR POKETS - NO EXCEPTIONS.
- AN EARTH BEEM SHALL BE PLACED AROUND THE PERIMETER OF THE PLANTING HOLE EXCEPT WHERE CURBED PLANTING BEDS OR PITS ARE BEING USED.
- 2"-3" OF MULCH SHALL BE PLACED OVER THE PLANTING AREA.
- AT THE TIME OF PLANTING IS COMPLETE THE PLANTING SHALL RECEIVE ADDITIONAL WATER TO ENSURE COMPLETE HYDRATION OF THE ROOTS, BACKFILL MATERIAL AND MULCH LAYER.
- STAKES AND GUY'S SHALL BE USED WHERE APPROPRIATE AND/OR NECESSARY. GUY MATERIAL SHALL BE NON-DAMAGING TO THE TREE.
- ALL PLANTING STOCK SHALL BE SPECIMEN QUALITY, FREE OF DEFECTS, AND DISEASE OR INJURY. THE CITY OF PORTSMOUTH, NH RESERVES THE RIGHT TO REFUSE/REJECT ANY PLANT MATERIAL OR PLANTING ACTION THAT FAILS TO MEET THE STANDARDS SET FORTH IN THE ANSI A300 PART 6 STANDARD PRACTICES FOR PLANTING AND TRANSPLANTATION AND/OR THE CITY OF PORTSMOUTH, NH PLANTING REQUIREMENTS.



Proposed Multi-Family Development
FOUNDATION PLANTING PLAN
 105 Bartlett Street Portsmouth, New Hampshire

Drawn By: VM
 Checked By: RW
 Scale: 1" = 20' - 0"
 Date: November 4, 2020
 Revisions:
 November 18, 2020
 January 20, 2021


NOTE: For tree planting plan, see L-1

SHRUBS

Symbol	Botanical Name	Common Name	Quantity	Size	Comments
Bth	<i>Buxus 'Tide Hill'</i>	Tide Hill Boxwood	40	2' Ht	B&B
Bud	<i>Buddleia 'Lo and Behold'</i>	Lo and Behold Butterflybush	30	3 gal	
Bwg	<i>Buxus 'Winter Gem'</i>	Winter Gem Boxwood	31	2' Ht	B&B
Cle	<i>Clethra alnifolia 'Hummingbird'</i>	Hummingbird Summersweet	28	5 gal	
For	<i>Forsythia 'Gold Tide'</i>	Gold Tide Forsythia	177	3 gal	
Foth	<i>Fothergilla gardenii</i>	Dwarf Fothergilla	16	5 gal	
HyB	<i>Hydrangea paniculata 'Bobo'</i>	Bobo Hydrangea	36	3 gal	
HyE	<i>Hydrangea macrophylla 'Endless Summer'</i>	Endless Summer Hydrangea	14	5 gal	
HyI	<i>Hydrangea arborescens 'Incrediball'</i>	Incrediball Hydrangea	4	5 gal	
HyL	<i>Hydrangea paniculata 'Little Lime'</i>	Little Lime Hydrangea	42	3 gal	
Ig	<i>Ilex glabra 'Shamrock'</i>	Shamrock Inkberry	125	5 gal	full to ground
Iv	<i>Ilex verticillata 'Red Sprite'</i>	Red Sprite Winterberry	9	3 gal	
Jc	<i>Juniperus chinensis 'Sargentii'</i>	Sargent Juniper	107	5 gal	
Jv	<i>Juniperus virginiana 'Emerald Sentinel'</i>	Emerald Sentinel Red Cedar	6	7-8' Ht	B&B
Mp	<i>Myrica pensylvanica</i>	Northern Bayberry	12	5 gal	
Po	<i>Picea orientalis 'Gowdy'</i>	Gowdy Oriental Spruce	1	8-10' Ht	B&B
Rh	<i>Rhus aromatica 'Grow-Low'</i>	Grow Low Sumac	387	3 gal	
Ros	<i>Rosa 'Blush Knockout'</i>	Blush Knockout Rose	76	3 gal	
Sy	<i>Syringa meyeri 'Palibin'</i>	Dwarf Korean Lilac	28	3-4' Ht	B&B
Tax	<i>Taxus media 'Ever-Low'</i>	Ever-Low Yew	32	3 gal	
Th	<i>Thuja occidentalis 'Smaragd'</i>	Emerald Green Arborvitae	2	7-8' Ht	B&B

PERENNIALS, GROUNDCOVERS, VINES and ANNUALS

Symbol	Botanical Name	Common Name	Quantity	Size
Bap	<i>Baptisia australis</i>	False Blue Indigo	12	1 gal
Cal	<i>Calamagrostis acutifolia 'Karl Foerster'</i>	Feather Reed Grass	22	1 gal
Day	<i>Helianthus 'Big Time Happy'</i>	Big Time Happy Daylily	20	1 gal
Ir	<i>Iris versicolor</i>	Blue Flag Iris	46	1 gal
Pan	<i>Panicum virgatum 'Heavy Metal'</i>	Heavy Metal Switch Grass	48	1 gal
Rud	<i>Rubbeckia fulgida 'Goldsturm'</i>	Black-Eyed Susan	63	1 gal
Vm	<i>Vinca minor 'Bowles'</i>	Bowles Periwinkle	1500	2.5" pots





1 SOUTH ELEVATION - RAILROAD TRACKS




2 EAST ELEVATION - BUILDING A




3 EAST ELEVATION - BUILDING B



4 EAST ELEVATION - BUILDING C



KEY PLAN






1 NORTH ELEVATION - NORTH MILL POND




2 WEST ELEVATION - BUILDING C




3 WEST ELEVATION - BUILDING B



4 WEST ELEVATION - BUILDING A



KEY PLAN







1 SOUTH ELEVATION - BUILDING B - RAILROAD TRACKS




2 WEST ELEVATION - BUILDING A



KEY PLAN





Tighe & Bond

Proposed Multi-Family Development
105 Bartlett Street
Portsmouth, NH

Drainage Analysis

Prepared For:

Iron Horse Properties LLC

April 20, 2020

Last Revised: January 21, 2021

Section 1

Project Description

The Bartlett Street property is comprised of a five (5) parcels that are bounded by Bartlett Street to the west and south, North Mill Pond to the north, and the Boston and Maine (B&M) railroad to the east. The existing parcels are listed below.

Tax Map/Lot No.	Area (ac)
157 / 1	1.42
157 / 2	2.34
164 / 1	1.19
164 / 4-2	5.73
R.O.W.	1.60

Lot 157-1 is currently occupied by a 20,000-square-foot, 2-story, concrete block/steel frame building and associated parking lot. Lot 157-2 contains another 20,000-square foot wood frame structure with a variety of outbuildings, such as sheds, to support an impervious lumber yard. Lot 164-1 also contains an approximately 20,000-square foot wood frame structure that hosts a variety of smaller businesses and associated parking. Lot 164-4-2 is currently occupied by a former B&M railroad turntable, a dilapidated former brick roundhouse, and an approximately 3,600-square-foot machine shop. Several shipping containers are also present throughout the lot. The northern end of the lot is comprised mostly of abandoned rail lines that run down the shoreline between North Mill Pond and the active railroad past the northern limits of the project site

The proposed project includes the demolition and relocation of the structures on Lots 157-1, 157-2, and 164-4-2 and construction of two (2) multi-family apartment buildings with basement level parking, as well as one (1) mixed used building with first floor office spaces, amenity space, and upper story apartments. In order to accommodate the footprints of the new structure and site improvements, the listed lots are proposed to be revised into five (5) new lots. The project will include associated site improvements that consist of a private road with cul-de-sac, parking, utilities, stormwater management and treatment, landscaping, lighting, and a greenway park. Additionally, the land from North Mill Pond’s mean high water (MHW) line to the 50ft buffer will be deeded to the City of Portsmouth and designated as community space for the City’s North Mill Pond Trail project. The City will be responsible for the future design and permitting of the North Mill Pond Trail project and any of its associated work within the 50ft buffer.

The pre-development and post-development watershed areas have been analyzed at two points of analysis. While the points of analysis remained unchanged, their contributing sub-catchment areas varied between pre-development and post-development conditions. These adjustments were made to reflect the differences in drainage patterns between the existing and proposed conditions. The overall area analyzed as part of this drainage

analysis was held constant. For reference, PA-1 assesses flows that discharge directly to North Mill Pond via overland flow or various outlets, and PA-2 assesses flows that discharge to the 36" brick sewer which runs through the development area. In the post-development condition, however, all stormwater flows have been separated from the brick sewer and are discharged to North Mill Pond after being treated. PA-2 would have no stormwater flows in the post-development condition, therefore removing the need to assess it.

Furthermore, since North Mill Pond is a tidal water, NHDES does not require peak runoff control requirements to be met (Env-Wq 1507.06(d)). For this reason, a comparison of peak runoff rates for the various storm events has not been provided. A detention system is included on the development site for the purpose of mitigating temperature differences between the stormwater runoff and the North Mill Pond.

1.1 Calculation Methods

The design storms analyzed in this study are the 2-year, 10-year, 25-year and 50-year 24-hour duration storm events. The stormwater modeling system, HydroCAD 10.0 was utilized to predict the peak runoff rates from these storm events. The peak discharge rates were determined by analyzing Type III 24-hour storm events. The rainfall data for these storm events was obtained from the data published by the Northeast Regional Climate Center at Cornell University, with an additional 15% added factor of safety as required by Env-Wq 1503.08(l).

The time of concentration was computed using the TR-55 Method, which provides a means of determining the time for an entire watershed to contribute runoff to a specific location via sheet flows, shallow concentrated flow and channel flow. Runoff curve numbers were calculated by estimating the coverage areas and then summing the curve number for the coverage area as a percent of the entire watershed.

References:

1. HydroCAD Stormwater Modeling System, by HydroCAD Software Solutions LLC, Chocorua, New Hampshire.
2. New Hampshire Stormwater Management Manual, Volume 2, Post-Construction Best Management Practices Selection and Design, December 2008.
3. "Extreme Precipitation in New York & New England." Extreme Precipitation in New York & New England by Northeast Regional Climate Center (NRCC), 26 June 2012.

Section 2

Pre-Development Conditions

In order to analyze the pre-development condition, the site has been divided into two (2) watershed areas modeled at two (2) points of analysis. These points of analysis and watersheds are depicted on the plans entitled "Pre-Development Watershed Plan", Sheets C-801.1 and C-801.2.

Each of the points of analysis and their contributing watershed areas are described below:

Point of Analysis (PA-1)



Pre-development Watershed 1.0 (PRE 1.0) is comprised of mostly impervious surfaces from paved parking and structures, as well as some disturbed forested areas to the northeast that surround a dilapidated roundhouse, former railroad turntable, and a machine shop. Banks along the shoreline of North Mill Pond consist of lawn, various species associated with disturbed sites, and rubble. Runoff from this watershed area travels via overland flow or underground drainage system to discharge into North Mill Pond. The runoff is currently untreated before discharge.

Point of Analysis (PA-2)



Pre-development Watershed 2.0 (PRE-2.0) is comprised mostly of impervious surfaces in the form of paved parking, roadway, and structures. Additional runoff comes from a grassy wooded strip that slopes down from the railroad to the east of the watershed. Runoff from this watershed drains to various catch basins that tie into an existing brick sewer.

2.2.1 Pre-Development Calculations



2.2.2 Pre-Development Watershed Plans



NORTH MILL POND



COMBINED SYSTEM
TO SEWER



C0960-006 PRE

Prepared by Tighe & Bond

HydroCAD® 10.00-20 s/n 03436 © 2017 HydroCAD Software Solutions LLC

Printed 1/18/2021

Page 2

Area Listing (all nodes)

Area (acres)	CN	Description (subcatchment-numbers)
0.507	39	>75% Grass cover, Good, HSG A (PRE-1.0)
0.419	61	>75% Grass cover, Good, HSG B (PRE-1.0, PRE-2.0)
0.922	74	>75% Grass cover, Good, HSG C (PRE-1.0, PRE-2.0)
0.071	80	>75% Grass cover, Good, HSG D (PRE-1.0)
1.173	96	Gravel surface, HSG C (PRE-1.0, PRE-2.0)
3.596	98	Paved parking, HSG C (PRE-1.0, PRE-2.0)
1.695	98	Roofs, HSG C (PRE-1.0, PRE-2.0)
0.496	30	Woods, Good, HSG A (PRE-1.0)
0.292	55	Woods, Good, HSG B (PRE-1.0, PRE-2.0)
1.378	70	Woods, Good, HSG C (PRE-1.0, PRE-2.0)
0.306	77	Woods, Good, HSG D (PRE-1.0)
10.853	83	TOTAL AREA

C0960-006 PRE

Prepared by Tighe & Bond

HydroCAD® 10.00-20 s/n 03436 © 2017 HydroCAD Software Solutions LLC

Printed 1/18/2021

Page 3

Soil Listing (all nodes)

Area (acres)	Soil Group	Subcatchment Numbers
1.003	HSG A	PRE-1.0
0.711	HSG B	PRE-1.0, PRE-2.0
8.763	HSG C	PRE-1.0, PRE-2.0
0.376	HSG D	PRE-1.0
0.000	Other	
10.853		TOTAL AREA

C0960-006 PRE

Type III 24-hr 2-YR Rainfall=3.69"

Prepared by Tighe & Bond

Printed 1/18/2021

HydroCAD® 10.00-20 s/n 03436 © 2017 HydroCAD Software Solutions LLC

Page 4

Time span=0.00-24.00 hrs, dt=0.05 hrs, 481 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment PRE-1.0: Runoff Area=280,495 sf 37.67% Impervious Runoff Depth>1.71"
Flow Length=461' Tc=12.7 min CN=79 Runoff=10.22 cfs 0.918 af

Subcatchment PRE-2.0: Runoff Area=192,280 sf 64.91% Impervious Runoff Depth>2.62"
Flow Length=248' Tc=5.0 min CN=90 Runoff=13.43 cfs 0.965 af

Link PA-1: NORTH MILL POND Inflow=10.22 cfs 0.918 af
Primary=10.22 cfs 0.918 af

Link PA-2: COMBINED SYSTEM TO SEWER Inflow=13.43 cfs 0.965 af
Primary=13.43 cfs 0.965 af

Total Runoff Area = 10.853 ac Runoff Volume = 1.883 af Average Runoff Depth = 2.08"
51.25% Pervious = 5.563 ac 48.75% Impervious = 5.291 ac

C0960-006 PRE

Type III 24-hr 10-YR Rainfall=5.60"

Prepared by Tighe & Bond

Printed 1/18/2021

HydroCAD® 10.00-20 s/n 03436 © 2017 HydroCAD Software Solutions LLC

Page 5

Time span=0.00-24.00 hrs, dt=0.05 hrs, 481 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment PRE-1.0: Runoff Area=280,495 sf 37.67% Impervious Runoff Depth>3.32"
Flow Length=461' Tc=12.7 min CN=79 Runoff=19.96 cfs 1.780 af

Subcatchment PRE-2.0: Runoff Area=192,280 sf 64.91% Impervious Runoff Depth>4.45"
Flow Length=248' Tc=5.0 min CN=90 Runoff=22.22 cfs 1.639 af

Link PA-1: NORTH MILL POND Inflow=19.96 cfs 1.780 af
Primary=19.96 cfs 1.780 af

Link PA-2: COMBINED SYSTEM TO SEWER Inflow=22.22 cfs 1.639 af
Primary=22.22 cfs 1.639 af

Total Runoff Area = 10.853 ac Runoff Volume = 3.419 af Average Runoff Depth = 3.78"
51.25% Pervious = 5.563 ac 48.75% Impervious = 5.291 ac

Summary for Subcatchment PRE-1.0:

Runoff = 19.96 cfs @ 12.18 hrs, Volume= 1.780 af, Depth> 3.32"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 10-YR Rainfall=5.60"

Area (sf)	CN	Description
22,079	39	>75% Grass cover, Good, HSG A
21,626	30	Woods, Good, HSG A
15,637	61	>75% Grass cover, Good, HSG B
9,580	55	Woods, Good, HSG B
43,774	98	Roofs, HSG C
13,394	74	>75% Grass cover, Good, HSG C
61,882	98	Paved parking, HSG C
33,912	70	Woods, Good, HSG C
42,224	96	Gravel surface, HSG C
3,074	80	>75% Grass cover, Good, HSG D
13,313	77	Woods, Good, HSG D
280,495	79	Weighted Average
174,839		62.33% Pervious Area
105,656		37.67% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.9	100	0.0400	0.24		Sheet Flow, Grass: Short n= 0.150 P2= 3.69"
5.8	361	0.0219	1.04		Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps
12.7	461	Total			

Summary for Subcatchment PRE-2.0:

[49] Hint: Tc<2dt may require smaller dt

Runoff = 22.22 cfs @ 12.07 hrs, Volume= 1.639 af, Depth> 4.45"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 10-YR Rainfall=5.60"

Area (sf)	CN	Description
2,616	61	>75% Grass cover, Good, HSG B
3,131	55	Woods, Good, HSG B
30,043	98	Roofs, HSG C
26,755	74	>75% Grass cover, Good, HSG C
94,757	98	Paved parking, HSG C
26,114	70	Woods, Good, HSG C
8,864	96	Gravel surface, HSG C
192,280	90	Weighted Average
67,480		35.09% Pervious Area
124,800		64.91% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
2.1	48	0.1875	0.39		Sheet Flow, Grass: Short n= 0.150 P2= 3.69"
1.6	200	0.0100	2.03		Shallow Concentrated Flow, Paved Kv= 20.3 fps
3.7	248	Total, Increased to minimum Tc = 5.0 min			

Summary for Link PA-1: NORTH MILL POND

Inflow Area = 6.439 ac, 37.67% Impervious, Inflow Depth > 3.32" for 10-YR event
 Inflow = 19.96 cfs @ 12.18 hrs, Volume= 1.780 af
 Primary = 19.96 cfs @ 12.18 hrs, Volume= 1.780 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Summary for Link PA-2: COMBINED SYSTEM TO SEWER

Inflow Area = 4.414 ac, 64.91% Impervious, Inflow Depth > 4.45" for 10-YR event
 Inflow = 22.22 cfs @ 12.07 hrs, Volume= 1.639 af
 Primary = 22.22 cfs @ 12.07 hrs, Volume= 1.639 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

C0960-006 PRE

Type III 24-hr 25-YR Rainfall=7.10"

Prepared by Tighe & Bond

Printed 1/18/2021

HydroCAD® 10.00-20 s/n 03436 © 2017 HydroCAD Software Solutions LLC

Page 8

Time span=0.00-24.00 hrs, dt=0.05 hrs, 481 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment PRE-1.0: Runoff Area=280,495 sf 37.67% Impervious Runoff Depth>4.67"
Flow Length=461' Tc=12.7 min CN=79 Runoff=28.08 cfs 2.504 af

Subcatchment PRE-2.0: Runoff Area=192,280 sf 64.91% Impervious Runoff Depth>5.92"
Flow Length=248' Tc=5.0 min CN=90 Runoff=29.06 cfs 2.177 af

Link PA-1: NORTH MILL POND Inflow=28.08 cfs 2.504 af
Primary=28.08 cfs 2.504 af

Link PA-2: COMBINED SYSTEM TO SEWER Inflow=29.06 cfs 2.177 af
Primary=29.06 cfs 2.177 af

Total Runoff Area = 10.853 ac Runoff Volume = 4.681 af Average Runoff Depth = 5.18"
51.25% Pervious = 5.563 ac 48.75% Impervious = 5.291 ac

C0960-006 PRE

Type III 24-hr 50-YR Rainfall=8.50"

Prepared by Tighe & Bond

Printed 1/18/2021

HydroCAD® 10.00-20 s/n 03436 © 2017 HydroCAD Software Solutions LLC

Page 9

Time span=0.00-24.00 hrs, dt=0.05 hrs, 481 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method


Subcatchment PRE-1.0: Runoff Area=280,495 sf 37.67% Impervious Runoff Depth>5.96"
Flow Length=461' Tc=12.7 min CN=79 Runoff=35.62 cfs 3.200 af

Subcatchment PRE-2.0: Runoff Area=192,280 sf 64.91% Impervious Runoff Depth>7.29"
Flow Length=248' Tc=5.0 min CN=90 Runoff=35.39 cfs 2.683 af





Link PA-1: NORTH MILL POND Inflow=35.62 cfs 3.200 af
Primary=35.62 cfs 3.200 af



Link PA-2: COMBINED SYSTEM TO SEWER Inflow=35.39 cfs 2.683 af
Primary=35.39 cfs 2.683 af

Total Runoff Area = 10.853 ac Runoff Volume = 5.883 af Average Runoff Depth = 6.50"
51.25% Pervious = 5.563 ac 48.75% Impervious = 5.291 ac



LEGEND

-  PRE-DEVELOPMENT WATERSHED BOUNDARY
-  LONGEST FLOW PATH
-  PRE DEVELOPMENT WATERSHED AREA DESIGNATION
-  POINT OF ANALYSIS



Proposed Multi-Family Development

Iron Horse Properties, LLC

105 Bartlett Street
Portsmouth,
New Hampshire


MARK	DATE	DESCRIPTION
H	1/20/2021	TAC Resubmission
G	11/18/2020	TAC Resubmission
F	10/28/2020	Wetland CUP Resubmission
E	5/20/2020	TAC Resubmission
D	4/29/2020	Wetland CUP Submission
C	4/20/2020	TAC Submission
B	2/6/2020	Design Review Submission
A	1/2/2020	ZBA Submission

PROJECT NO:	C-0960-006
DATE:	April 20, 2020
FILE:	C-0960-006_C-SITE.DWG
DRAWN BY:	NAH
CHECKED:	PMC
APPROVED:	BML





PRE-DEVELOPMENT WATERSHED PLAN


SCALE: AS SHOWN

C-801.1



LEGEND

-  PRE-DEVELOPMENT WATERSHED BOUNDARY
-  LONGEST FLOW PATH
-  PRE DEVELOPMENT WATERSHED AREA DESIGNATION
-  POINT OF ANALYSIS



Proposed Multi-Family Development

Iron Horse Properties, LLC

105 Bartlett Street
Portsmouth,
New Hampshire

MARK	DATE	DESCRIPTION
H	1/20/2021	TAC Resubmission
G	11/18/2020	TAC Resubmission
F	10/28/2020	Wetland CUP Resubmission
E	5/20/2020	TAC Resubmission
D	4/29/2020	Wetland CUP Submission
C	4/20/2020	TAC Submission
B	2/6/2020	Design Review Submission
A	1/2/2020	ZBA Submission

PROJECT NO:	C-0960-006
DATE:	April 20, 2020
FILE:	C-0960-006_C-SITE.DWG
DRAWN BY:	NAH
CHECKED:	PMC
APPROVED:	BML

PRE-DEVELOPMENT WATERSHED PLAN

SCALE: AS SHOWN

C-801.2



Last Saved: 1/18/2021 11:03am By: Mahanzen
 Plotted On: Jan 16, 2021 11:03am By: Mahanzen
 Tighe & Bond: F:\C\0960-006_105 Bartlett Street\Drawings_Figures\AutoCAD\Sheet\C-0960-006_C-SITE.dwg

MATCH LINE SHEET 2
 MATCH LINE SHEET 1

Section 3

Post-Development Conditions

The post-development condition was analyzed by dividing the watersheds into nine (9) watershed areas. Stormwater runoff from these sub-catchment areas flow via subsurface drainage systems prior to discharging to North Mill Pond. Unlike in the pre-development condition, flows from these sub-catchment areas are modeled at only one point of analysis at North Mill Pond (PA-1). As previously described, a large portion of the site has been designed to reroute runoff to North Mill Pond instead of the existing brick sewer. This increases the watershed area flowing to PA-1 compared to the pre-development condition but eliminates the site's contribution to a combined sewer system. As per Env-Wq 1507.06(d), the resulting increased peak flows from a larger effective watershed area are not of concern since North Mill Pond is a tidal water and the peak runoff control requirements do not apply. For this reason, a comparison of peak runoff rates for the various storm events has not been provided.

A detention system is included on the development site for the purpose of mitigating temperature differences between the stormwater runoff and the North Mill Pond. The detention system and outlet structure have been sized to detain the WQV with a drain down time of 24 hours, prior to discharging to the treatment unit. Flows greater than the 2-year storm event are designed to bypass the treatment unit.

The point of analysis (PA-1) and its sub-catchment areas are depicted on the plans entitled "Post-Development Watershed Plan," Sheets C-802.1 and C-802.2. Each of the points of analysis and their contributing watershed areas are described below:

Point of Analysis (PA-1)

Post-development Watershed 1.0 (POST-1.0) is comprised of mostly existing impervious areas on the south end of the site behind some of the existing structures. Runoff from this watershed area travels via overland flow to the modified subsurface drainage system, where it is pretreated by deep-sump catch basins and treated by a Contech Jellyfish Stormwater Filter (JF-1). The Jellyfish units proposed are Contech's Peak Diversion model, which include an internal bypass that route flows greater than the design Water Quality Flow past the internal treatment system. Flows exiting the Jellyfish Filter discharge to a manhole structure outfitted with a backflow preventer within the outlet invert to protect the drainage system from tidal backflow and flooding. Flows then directly discharge to North Mill Pond (PA-1), through an outfall protected by a concrete winged headwall and plunge pool.

Post-development Watershed 1.1 (POST-1.1) collects the runoff from the modified roadway and parking areas at the entrance of the site. Runoff from this watershed area travels via overland flow to deep-sump catch basins that tie into a structure (PDMH3) just upstream of the Jellyfish Filter described in POST 1.0 (JF-1). Runoff is treated and discharged through manhole structure equipped with a backflow preventer before exiting to North Mill Pond (PA-1). A concrete winged headwall and plunge pool provide erosion control and bank stability to the outfall.

Post-development Watershed 2.0 (POST-2.0) is comprised mostly of asphalt roadway and concrete sidewalks in the center of the site. Runoff from this watershed area travels via

overland flow to deep-sump catch basins and a Contech Jellyfish Stormwater Filter (JF-2). Flows exiting the Jellyfish Filter tie into a manhole structure that combines the flows with those of POST-1.0 before similarly exiting to North Mill Pond.

Post-development Watershed 3.0 (POST-3.0) primarily collects the roof runoff from two (2) of the proposed buildings, as well as some additional impervious cover below. Runoff from this watershed area travels via roof leaders or yard drains to a Contech Jellyfish Stormwater Filter (JF-3). Flows exiting the Jellyfish Filter discharge to North Mill Pond (PA-1). Similar to Post-Development Watershed 1.0 (POST-1.0), the pipe network is protected by a backflow preventer within the outlet invert of a manhole structure at the most downstream location. A concrete winged headwall and plunge pool provide erosion control and bank stability to the outfall.

Post-development Watershed 4.0 (POST-4.0) collects the roof runoff from the third proposed building, paved parking, and some forested grassy slopes parallel to the existing railroad. Runoff from this watershed area travels via overland flow or roof leader to deep sump catch basins and an underground detention system. The detention system and outlet structure have been sized to detain the WQV with a drain down time of 24 hours, prior to discharging to the treatment unit, a Contech Jellyfish Stormwater Filter (JF-4). Flows greater than the 2-year storm event are designed to bypass the treatment unit. Flows exiting the Jellyfish Filter discharge to North Mill Pond (PA-1). Similar to Post-Development Watershed 1.0 (POST-1.0), the pipe network is protected by a backflow preventer within the outlet invert of a manhole structure at the most downstream location. A concrete winged headwall and plunge pool provide erosion control and bank stability to the outfall.

Post-development Watershed 5.0 (POST-5.0) is comprised mostly of porous pavement multi use path located between the proposed development and the North Mill Pond. Runoff from the watershed infiltrates through the filter media section under the porous pavement and discharges to an underdrain. The underdrain connects to the closed drainage system on site, ultimately discharging to the North Mill Pond.

Post-development Watershed 5.1 (POST-5.1) is comprised of porous pavement multi use path and landscaped park area located between the proposed development and the North Mill Pond. Runoff from the watershed infiltrates through the filter media section under the porous pavement and discharges to an underdrain. The underdrain connects to the closed drainage system on site, ultimately discharging to the North Mill Pond.

Post-development Watershed 6.0 (POST-6.0) is comprised mostly of grassy and slightly forested areas along the shoreline of North Mill Pond. Runoff from this watershed simply sheets toward and discharges into North Mill Pond, as in the existing condition. There are no proposed impervious surfaces that are within this watershed area that would require treatment.




Post-development Watershed 7.0 (POST-7.0) collects the runoff from the small area of the proposed greenway park area behind the proposed buildings. A circular rain garden (RG-1), paired with an outlet control structure, has been designed to provide treatment for the runoff from this area. The outlet control structure directs flows to a manhole structure downstream that combines flows with those of POST-4.0 before exiting to North Mill Pond.

Point of Analysis (PA-2)

All runoff previously draining to the existing brick sewer (PA-2) is proposed to be diverted to underground drainage that flows to North Mill Pond, effectively eliminating all flows to this point of analysis from this site.

3.3.1 Post-Development Calculations

3.3.2 Post-Development Watershed Plans



Routing Diagram for C0960-006 POST
 Prepared by Tighe & Bond, Printed 1/18/2021
 HydroCAD® 10.00-20 s/n 03436 © 2017 HydroCAD Software Solutions LLC

C0960-006 POST

Prepared by Tighe & Bond

HydroCAD® 10.00-20 s/n 03436 © 2017 HydroCAD Software Solutions LLC

Printed 1/18/2021

Page 11

Area Listing (all nodes)

Area (acres)	CN	Description (subcatchment-numbers)
0.480	39	>75% Grass cover, Good, HSG A (POST-3.0, POST-5.0, POST-6.0)
0.417	61	>75% Grass cover, Good, HSG B (POST-4.0, POST-6.0)
1.752	74	>75% Grass cover, Good, HSG C (POST-1.0, POST-1.1, POST-2.0, POST-3.0, POST-4.0, POST-5.0, POST-5.1, POST-6.0, POST-7.0)
0.077	80	>75% Grass cover, Good, HSG D (POST-5.1, POST-6.0)
0.421	89	Gravel roads, HSG C (POST-1.0)
0.055	98	Paved parking, HSG A (POST-1.1, POST-3.0, POST-5.0)
0.209	98	Paved parking, HSG B (POST-4.0)
3.919	98	Paved parking, HSG C (POST-1.0, POST-1.1, POST-2.0, POST-3.0, POST-4.0, POST-5.0, POST-5.1)
1.921	98	Roofs, HSG C (POST-1.0, POST-1.1, POST-2.0, POST-3.0, POST-4.0)
0.028	98	Roofs, HSG D (POST-3.0)
0.469	30	Woods, Good, HSG A (POST-6.0)
0.085	55	Woods, Good, HSG B (POST-4.0, POST-6.0)
0.752	70	Woods, Good, HSG C (POST-1.0, POST-4.0, POST-6.0)
0.270	83	Woods, Poor, HSG D (POST-6.0)
10.853	84	TOTAL AREA

C0960-006 POST

Prepared by Tighe & Bond

HydroCAD® 10.00-20 s/n 03436 © 2017 HydroCAD Software Solutions LLC

Printed 1/18/2021

Page 12

Soil Listing (all nodes)

Area (acres)	Soil Group	Subcatchment Numbers
1.003	HSG A	POST-1.1, POST-3.0, POST-5.0, POST-6.0
0.711	HSG B	POST-4.0, POST-6.0
8.763	HSG C	POST-1.0, POST-1.1, POST-2.0, POST-3.0, POST-4.0, POST-5.0, POST-5.1, POST-6.0, POST-7.0
0.376	HSG D	POST-3.0, POST-5.1, POST-6.0
0.000	Other	
10.853		TOTAL AREA

C0960-006 POST

Type III 24-hr 2-YR Rainfall=3.69"

Prepared by Tighe & Bond

Printed 1/18/2021

HydroCAD® 10.00-20 s/n 03436 © 2017 HydroCAD Software Solutions LLC

Page 13

Time span=0.00-24.00 hrs, dt=0.05 hrs, 481 points
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
 Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment POST-1.0:	Runoff Area=129,041 sf 66.78% Impervious Runoff Depth>2.72" Tc=5.0 min CN=91 Runoff=9.28 cfs 0.671 af
Subcatchment POST-1.1:	Runoff Area=42,709 sf 91.75% Impervious Runoff Depth>3.23" Tc=5.0 min CN=96 Runoff=3.45 cfs 0.264 af
Subcatchment POST-2.0:	Runoff Area=32,330 sf 86.24% Impervious Runoff Depth>3.12" Tc=5.0 min CN=95 Runoff=2.56 cfs 0.193 af
Subcatchment POST-3.0:	Runoff Area=50,366 sf 70.02% Impervious Runoff Depth>2.53" Tc=5.0 min CN=89 Runoff=3.41 cfs 0.244 af
Subcatchment POST-4.0:	Runoff Area=96,700 sf 66.72% Impervious Runoff Depth>2.35" Tc=5.0 min CN=87 Runoff=6.09 cfs 0.435 af
Subcatchment POST-5.0:	Runoff Area=5,912 sf 65.31% Impervious Runoff Depth>2.18" Tc=5.0 min CN=85 Runoff=0.35 cfs 0.025 af
Subcatchment POST-5.1:	Runoff Area=26,210 sf 38.86% Impervious Runoff Depth>2.02" Tc=5.0 min CN=83 Runoff=1.43 cfs 0.101 af
Subcatchment POST-6.0:	Runoff Area=85,650 sf 0.00% Impervious Runoff Depth>0.49" Tc=5.0 min CN=57 Runoff=0.70 cfs 0.080 af
Subcatchment POST-7.0:	Runoff Area=3,857 sf 0.00% Impervious Runoff Depth>1.37" Tc=5.0 min CN=74 Runoff=0.14 cfs 0.010 af
Pond JF-1:	Peak Elev=6.30' Inflow=12.73 cfs 0.935 af 24.0" Round Culvert n=0.013 L=4.0' S=0.0125 '/' Outflow=12.73 cfs 0.935 af
Pond JF-2:	Peak Elev=6.29' Inflow=2.56 cfs 0.193 af 15.0" Round Culvert n=0.013 L=50.0' S=0.0040 '/' Outflow=2.56 cfs 0.193 af
Pond JF-3:	Peak Elev=4.32' Inflow=3.41 cfs 0.251 af 18.0" Round Culvert n=0.013 L=5.0' S=0.0200 '/' Outflow=3.41 cfs 0.251 af
Pond JF-4:	Peak Elev=5.00' Inflow=2.85 cfs 0.312 af 15.0" Round Culvert n=0.013 L=55.0' S=0.0055 '/' Outflow=2.85 cfs 0.312 af
Pond PDMH13:	Peak Elev=4.45' Inflow=2.97 cfs 0.377 af 24.0" Round Culvert n=0.013 L=37.0' S=0.0054 '/' Outflow=2.97 cfs 0.377 af
Pond PDMH4:	Peak Elev=5.70' Inflow=15.29 cfs 1.129 af 24.0" Round Culvert n=0.013 L=11.0' S=0.0045 '/' Outflow=15.29 cfs 1.129 af
Pond POND 4.0: UNDERGROUND DETENTION	Peak Elev=6.96' Storage=7,035 cf Inflow=6.09 cfs 0.435 af Primary=2.85 cfs 0.312 af Secondary=0.00 cfs 0.000 af Outflow=2.85 cfs 0.312 af

C0960-006 POST

Prepared by Tighe & Bond

HydroCAD® 10.00-20 s/n 03436 © 2017 HydroCAD Software Solutions LLC

Type III 24-hr 2-YR Rainfall=3.69"

Printed 1/18/2021

Page 14

Pond POND-5.0: POROUS PAVEMENT

Peak Elev=8.95' Storage=803 cf Inflow=0.35 cfs 0.025 af
Outflow=0.01 cfs 0.007 af

Pond POND-5.1: POROUS PAVEMENT

Peak Elev=9.19' Storage=2,186 cf Inflow=1.43 cfs 0.101 af
Outflow=0.24 cfs 0.065 af

Pond RG-1: RAIN GARDEN

Peak Elev=8.45' Storage=441 cf Inflow=0.14 cfs 0.010 af
Outflow=0.00 cfs 0.000 af

Link PA-1:

Inflow=19.59 cfs 1.837 af
Primary=19.59 cfs 1.837 af

Total Runoff Area = 10.853 ac Runoff Volume = 2.024 af Average Runoff Depth = 2.24"
43.51% Pervious = 4.722 ac 56.49% Impervious = 6.131 ac

C0960-006 POST

Prepared by Tighe & Bond

HydroCAD® 10.00-20 s/n 03436 © 2017 HydroCAD Software Solutions LLC

Type III 24-hr 10-YR Rainfall=5.60"

Printed 1/18/2021

Page 15

Time span=0.00-24.00 hrs, dt=0.05 hrs, 481 points
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
 Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment POST-1.0:	Runoff Area=129,041 sf 66.78% Impervious Runoff Depth>4.56" Tc=5.0 min CN=91 Runoff=15.16 cfs 1.127 af
Subcatchment POST-1.1:	Runoff Area=42,709 sf 91.75% Impervious Runoff Depth>5.13" Tc=5.0 min CN=96 Runoff=5.34 cfs 0.419 af
Subcatchment POST-2.0:	Runoff Area=32,330 sf 86.24% Impervious Runoff Depth>5.01" Tc=5.0 min CN=95 Runoff=4.00 cfs 0.310 af
Subcatchment POST-3.0:	Runoff Area=50,366 sf 70.02% Impervious Runoff Depth>4.35" Tc=5.0 min CN=89 Runoff=5.72 cfs 0.419 af
Subcatchment POST-4.0:	Runoff Area=96,700 sf 66.72% Impervious Runoff Depth>4.13" Tc=5.0 min CN=87 Runoff=10.56 cfs 0.765 af
Subcatchment POST-5.0:	Runoff Area=5,912 sf 65.31% Impervious Runoff Depth>3.92" Tc=5.0 min CN=85 Runoff=0.62 cfs 0.044 af
Subcatchment POST-5.1:	Runoff Area=26,210 sf 38.86% Impervious Runoff Depth>3.72" Tc=5.0 min CN=83 Runoff=2.62 cfs 0.186 af
Subcatchment POST-6.0:	Runoff Area=85,650 sf 0.00% Impervious Runoff Depth>1.44" Tc=5.0 min CN=57 Runoff=2.99 cfs 0.235 af
Subcatchment POST-7.0:	Runoff Area=3,857 sf 0.00% Impervious Runoff Depth>2.85" Tc=5.0 min CN=74 Runoff=0.30 cfs 0.021 af
Pond JF-1:	Peak Elev=8.44' Inflow=20.50 cfs 1.546 af 24.0" Round Culvert n=0.013 L=4.0' S=0.0125 ' /' Outflow=20.50 cfs 1.546 af
Pond JF-2:	Peak Elev=7.21' Inflow=4.00 cfs 0.310 af 15.0" Round Culvert n=0.013 L=50.0' S=0.0040 ' /' Outflow=4.00 cfs 0.310 af
Pond JF-3:	Peak Elev=4.71' Inflow=5.72 cfs 0.445 af 18.0" Round Culvert n=0.013 L=5.0' S=0.0200 ' /' Outflow=5.72 cfs 0.445 af
Pond JF-4:	Peak Elev=5.49' Inflow=4.43 cfs 0.599 af 15.0" Round Culvert n=0.013 L=55.0' S=0.0055 ' /' Outflow=4.43 cfs 0.599 af
Pond PDMH13:	Peak Elev=4.94' Inflow=6.61 cfs 0.795 af 24.0" Round Culvert n=0.013 L=37.0' S=0.0054 ' /' Outflow=6.61 cfs 0.795 af
Pond PDMH4:	Peak Elev=6.85' Inflow=24.50 cfs 1.856 af 24.0" Round Culvert n=0.013 L=11.0' S=0.0045 ' /' Outflow=24.50 cfs 1.856 af
Pond POND 4.0: UNDERGROUND	Peak Elev=7.59' Storage=9,931 cf Inflow=10.56 cfs 0.765 af Primary=4.43 cfs 0.599 af Secondary=1.58 cfs 0.039 af Outflow=5.96 cfs 0.639 af

C0960-006 POST

Prepared by Tighe & Bond

HydroCAD® 10.00-20 s/n 03436 © 2017 HydroCAD Software Solutions LLC

Type III 24-hr 10-YR Rainfall=5.60"

Printed 1/18/2021

Page 16

Pond POND-5.0: POROUS PAVEMENT Peak Elev=9.10' Storage=1,021 cf Inflow=0.62 cfs 0.044 af
Outflow=0.13 cfs 0.027 af

Pond POND-5.1: POROUS PAVEMENT Peak Elev=9.71' Storage=3,586 cf Inflow=2.62 cfs 0.186 af
Outflow=0.72 cfs 0.149 af

Pond RG-1: RAIN GARDEN Peak Elev=10.00' Storage=597 cf Inflow=0.30 cfs 0.021 af
Outflow=0.03 cfs 0.007 af

Link PA-1: Inflow=38.25 cfs 3.331 af
Primary=38.25 cfs 3.331 af

Total Runoff Area = 10.853 ac Runoff Volume = 3.526 af Average Runoff Depth = 3.90"
43.51% Pervious = 4.722 ac 56.49% Impervious = 6.131 ac

C0960-006 POST

Prepared by Tighe & Bond

HydroCAD® 10.00-20 s/n 03436 © 2017 HydroCAD Software Solutions LLC

Type III 24-hr 10-YR Rainfall=5.60"

Printed 1/18/2021

Page 17

Summary for Subcatchment POST-1.0:

[49] Hint: Tc<2dt may require smaller dt

Runoff = 15.16 cfs @ 12.07 hrs, Volume= 1.127 af, Depth> 4.56"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 10-YR Rainfall=5.60"

Area (sf)	CN	Description
27,484	98	Roofs, HSG C
576	74	>75% Grass cover, Good, HSG C
58,692	98	Paved parking, HSG C
23,967	70	Woods, Good, HSG C
18,322	89	Gravel roads, HSG C
129,041	91	Weighted Average
42,865		33.22% Pervious Area
86,176		66.78% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Summary for Subcatchment POST-1.1:

[49] Hint: Tc<2dt may require smaller dt

Runoff = 5.34 cfs @ 12.07 hrs, Volume= 0.419 af, Depth> 5.13"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 10-YR Rainfall=5.60"

Area (sf)	CN	Description
5	98	Paved parking, HSG A
5,020	98	Roofs, HSG C
3,525	74	>75% Grass cover, Good, HSG C
34,159	98	Paved parking, HSG C
42,709	96	Weighted Average
3,525		8.25% Pervious Area
39,184		91.75% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

C0960-006 POST

Prepared by Tighe & Bond

HydroCAD® 10.00-20 s/n 03436 © 2017 HydroCAD Software Solutions LLC

Type III 24-hr 10-YR Rainfall=5.60"

Printed 1/18/2021

Page 18

Summary for Subcatchment POST-2.0:

[49] Hint: Tc<2dt may require smaller dt

Runoff = 4.00 cfs @ 12.07 hrs, Volume= 0.310 af, Depth> 5.01"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 10-YR Rainfall=5.60"

Area (sf)	CN	Description
6,843	98	Roofs, HSG C
4,447	74	>75% Grass cover, Good, HSG C
21,040	98	Paved parking, HSG C
32,330	95	Weighted Average
4,447		13.76% Pervious Area
27,883		86.24% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Summary for Subcatchment POST-3.0:

[49] Hint: Tc<2dt may require smaller dt

Runoff = 5.72 cfs @ 12.07 hrs, Volume= 0.419 af, Depth> 4.35"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 10-YR Rainfall=5.60"

Area (sf)	CN	Description
1,942	39	>75% Grass cover, Good, HSG A
69	98	Paved parking, HSG A
32,010	98	Roofs, HSG C
13,159	74	>75% Grass cover, Good, HSG C
1,949	98	Paved parking, HSG C
1,237	98	Roofs, HSG D
50,366	89	Weighted Average
15,101		29.98% Pervious Area
35,265		70.02% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

C0960-006 POST

Prepared by Tighe & Bond

HydroCAD® 10.00-20 s/n 03436 © 2017 HydroCAD Software Solutions LLC

Type III 24-hr 10-YR Rainfall=5.60"

Printed 1/18/2021

Page 19

Summary for Subcatchment POST-4.0:

[49] Hint: Tc<2dt may require smaller dt

Runoff = 10.56 cfs @ 12.07 hrs, Volume= 0.765 af, Depth> 4.13"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 10-YR Rainfall=5.60"

Area (sf)	CN	Description
15,366	61	>75% Grass cover, Good, HSG B
9,099	98	Paved parking, HSG B
3,314	55	Woods, Good, HSG B
12,311	98	Roofs, HSG C
11,567	74	>75% Grass cover, Good, HSG C
43,113	98	Paved parking, HSG C
1,930	70	Woods, Good, HSG C
96,700	87	Weighted Average
32,177		33.28% Pervious Area
64,523		66.72% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Summary for Subcatchment POST-5.0:

[49] Hint: Tc<2dt may require smaller dt

Runoff = 0.62 cfs @ 12.07 hrs, Volume= 0.044 af, Depth> 3.92"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 10-YR Rainfall=5.60"

Area (sf)	CN	Description
763	39	>75% Grass cover, Good, HSG A
2,310	98	Paved parking, HSG A
1,288	74	>75% Grass cover, Good, HSG C
1,551	98	Paved parking, HSG C
5,912	85	Weighted Average
2,051		34.69% Pervious Area
3,861		65.31% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

C0960-006 POST

Prepared by Tighe & Bond

HydroCAD® 10.00-20 s/n 03436 © 2017 HydroCAD Software Solutions LLC

Type III 24-hr 10-YR Rainfall=5.60"

Printed 1/18/2021

Page 20

Summary for Subcatchment POST-5.1:

[49] Hint: Tc<2dt may require smaller dt

Runoff = 2.62 cfs @ 12.07 hrs, Volume= 0.186 af, Depth> 3.72"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 10-YR Rainfall=5.60"

Area (sf)	CN	Description
15,734	74	>75% Grass cover, Good, HSG C
10,186	98	Paved parking, HSG C
290	80	>75% Grass cover, Good, HSG D
26,210	83	Weighted Average
16,024		61.14% Pervious Area
10,186		38.86% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Summary for Subcatchment POST-6.0:

[49] Hint: Tc<2dt may require smaller dt

Runoff = 2.99 cfs @ 12.09 hrs, Volume= 0.235 af, Depth> 1.44"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 10-YR Rainfall=5.60"

Area (sf)	CN	Description
18,189	39	>75% Grass cover, Good, HSG A
20,427	30	Woods, Good, HSG A
2,779	61	>75% Grass cover, Good, HSG B
406	55	Woods, Good, HSG B
22,150	74	>75% Grass cover, Good, HSG C
6,839	70	Woods, Good, HSG C
3,085	80	>75% Grass cover, Good, HSG D
11,775	83	Woods, Poor, HSG D
85,650	57	Weighted Average
85,650		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

C0960-006 POST

Type III 24-hr 10-YR Rainfall=5.60"

Prepared by Tighe & Bond

Printed 1/18/2021

HydroCAD® 10.00-20 s/n 03436 © 2017 HydroCAD Software Solutions LLC

Page 21

Summary for Subcatchment POST-7.0:

[49] Hint: Tc<2dt may require smaller dt

Runoff = 0.30 cfs @ 12.08 hrs, Volume= 0.021 af, Depth> 2.85"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 10-YR Rainfall=5.60"

Area (sf)	CN	Description
3,857	74	>75% Grass cover, Good, HSG C
3,857		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Summary for Pond JF-1:

Inflow Area = 3.943 ac, 72.99% Impervious, Inflow Depth > 4.70" for 10-YR event
 Inflow = 20.50 cfs @ 12.07 hrs, Volume= 1.546 af
 Outflow = 20.50 cfs @ 12.07 hrs, Volume= 1.546 af, Atten= 0%, Lag= 0.0 min
 Primary = 20.50 cfs @ 12.07 hrs, Volume= 1.546 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 8.44' @ 12.10 hrs
 Flood Elev= 10.80'

Device	Routing	Invert	Outlet Devices
#1	Primary	3.45'	24.0" Round Culvert L= 4.0' Ke= 0.500 Inlet / Outlet Invert= 3.45' / 3.40' S= 0.0125 '/' Cc= 0.900 n= 0.013, Flow Area= 3.14 sf

Primary OutFlow Max=17.25 cfs @ 12.07 hrs HW=8.03' TW=6.73' (Dynamic Tailwater)
 ↑**1=Culvert** (Inlet Controls 17.25 cfs @ 5.49 fps)

Summary for Pond JF-2:

Inflow Area = 0.742 ac, 86.24% Impervious, Inflow Depth > 5.01" for 10-YR event
 Inflow = 4.00 cfs @ 12.07 hrs, Volume= 0.310 af
 Outflow = 4.00 cfs @ 12.07 hrs, Volume= 0.310 af, Atten= 0%, Lag= 0.0 min
 Primary = 4.00 cfs @ 12.07 hrs, Volume= 0.310 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 7.21' @ 12.11 hrs
 Flood Elev= 10.25'

Device	Routing	Invert	Outlet Devices
#1	Primary	5.30'	15.0" Round Culvert L= 50.0' Ke= 0.500 Inlet / Outlet Invert= 5.30' / 5.10' S= 0.0040 '/' Cc= 0.900

C0960-006 POST

Prepared by Tighe & Bond

HydroCAD® 10.00-20 s/n 03436 © 2017 HydroCAD Software Solutions LLC

Type III 24-hr 10-YR Rainfall=5.60"

Printed 1/18/2021

Page 22

n= 0.013, Flow Area= 1.23 sf

Primary OutFlow Max=2.03 cfs @ 12.07 hrs HW=6.85' TW=6.74' (Dynamic Tailwater)↑**1=Culvert** (Inlet Controls 2.03 cfs @ 1.66 fps)**Summary for Pond JF-3:**

Inflow Area = 1.292 ac, 69.52% Impervious, Inflow Depth > 4.14" for 10-YR event
 Inflow = 5.72 cfs @ 12.07 hrs, Volume= 0.445 af
 Outflow = 5.72 cfs @ 12.07 hrs, Volume= 0.445 af, Atten= 0%, Lag= 0.0 min
 Primary = 5.72 cfs @ 12.07 hrs, Volume= 0.445 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Peak Elev= 4.71' @ 12.07 hrs

Flood Elev= 13.00'

Device	Routing	Invert	Outlet Devices
#1	Primary	3.30'	18.0" Round Culvert L= 5.0' Ke= 0.500 Inlet / Outlet Invert= 3.30' / 3.20' S= 0.0200 '/ Cc= 0.900 n= 0.013, Flow Area= 1.77 sf

Primary OutFlow Max=5.51 cfs @ 12.07 hrs HW=4.67' TW=0.00' (Dynamic Tailwater)↑**1=Culvert** (Barrel Controls 5.51 cfs @ 4.26 fps)**Summary for Pond JF-4:**

Inflow Area = 2.220 ac, 66.72% Impervious, Inflow Depth > 3.24" for 10-YR event
 Inflow = 4.43 cfs @ 12.15 hrs, Volume= 0.599 af
 Outflow = 4.43 cfs @ 12.15 hrs, Volume= 0.599 af, Atten= 0%, Lag= 0.0 min
 Primary = 4.43 cfs @ 12.15 hrs, Volume= 0.599 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Peak Elev= 5.49' @ 12.22 hrs

Flood Elev= 13.25'

Device	Routing	Invert	Outlet Devices
#1	Primary	4.00'	15.0" Round Culvert L= 55.0' Ke= 0.500 Inlet / Outlet Invert= 4.00' / 3.70' S= 0.0055 '/ Cc= 0.900 n= 0.013, Flow Area= 1.23 sf

Primary OutFlow Max=4.11 cfs @ 12.15 hrs HW=5.44' TW=4.93' (Dynamic Tailwater)↑**1=Culvert** (Outlet Controls 4.11 cfs @ 3.65 fps)**Summary for Pond PDMH13:**

Inflow Area = 2.910 ac, 58.93% Impervious, Inflow Depth > 3.28" for 10-YR event
 Inflow = 6.61 cfs @ 12.19 hrs, Volume= 0.795 af
 Outflow = 6.61 cfs @ 12.19 hrs, Volume= 0.795 af, Atten= 0%, Lag= 0.0 min
 Primary = 6.61 cfs @ 12.19 hrs, Volume= 0.795 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

C0960-006 POST

Type III 24-hr 10-YR Rainfall=5.60"

Prepared by Tighe & Bond

Printed 1/18/2021

HydroCAD® 10.00-20 s/n 03436 © 2017 HydroCAD Software Solutions LLC

Page 23

Peak Elev= 4.94' @ 12.19 hrs

Flood Elev= 10.90'

Device	Routing	Invert	Outlet Devices
#1	Primary	3.60'	24.0" Round Culvert L= 37.0' Ke= 0.500 Inlet / Outlet Invert= 3.60' / 3.40' S= 0.0054 '/ Cc= 0.900 n= 0.013, Flow Area= 3.14 sf

Primary OutFlow Max=6.59 cfs @ 12.19 hrs HW=4.93' TW=0.00' (Dynamic Tailwater)

↑1=Culvert (Barrel Controls 6.59 cfs @ 4.19 fps)

Summary for Pond PDMH4:

[80] Warning: Exceeded Pond JF-2 by 0.17' @ 12.05 hrs (2.44 cfs 0.010 af)

Inflow Area = 4.685 ac, 75.09% Impervious, Inflow Depth > 4.75" for 10-YR event
 Inflow = 24.50 cfs @ 12.07 hrs, Volume= 1.856 af
 Outflow = 24.50 cfs @ 12.07 hrs, Volume= 1.856 af, Atten= 0%, Lag= 0.0 min
 Primary = 24.50 cfs @ 12.07 hrs, Volume= 1.856 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Peak Elev= 6.85' @ 12.07 hrs

Flood Elev= 10.50'

Device	Routing	Invert	Outlet Devices
#1	Primary	3.30'	24.0" Round Culvert L= 11.0' Ke= 0.500 Inlet / Outlet Invert= 3.30' / 3.25' S= 0.0045 '/ Cc= 0.900 n= 0.013, Flow Area= 3.14 sf

Primary OutFlow Max=23.60 cfs @ 12.07 hrs HW=6.73' TW=0.00' (Dynamic Tailwater)

↑1=Culvert (Inlet Controls 23.60 cfs @ 7.51 fps)

Summary for Pond POND 4.0: UNDERGROUND DETENTION

Inflow Area = 2.220 ac, 66.72% Impervious, Inflow Depth > 4.13" for 10-YR event
 Inflow = 10.56 cfs @ 12.07 hrs, Volume= 0.765 af
 Outflow = 5.96 cfs @ 12.18 hrs, Volume= 0.639 af, Atten= 44%, Lag= 6.7 min
 Primary = 4.43 cfs @ 12.15 hrs, Volume= 0.599 af
 Secondary = 1.58 cfs @ 12.20 hrs, Volume= 0.039 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Peak Elev= 7.59' @ 12.20 hrs Surf.Area= 7,279 sf Storage= 9,931 cf

Flood Elev= 9.60' Surf.Area= 7,279 sf Storage= 17,683 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow)

Center-of-Mass det. time= 41.7 min (837.5 - 795.8)

C0960-006 POST

Type III 24-hr 10-YR Rainfall=5.60"

Prepared by Tighe & Bond

Printed 1/18/2021

HydroCAD® 10.00-20 s/n 03436 © 2017 HydroCAD Software Solutions LLC

Page 24

Volume	Invert	Avail.Storage	Storage Description
#1A	4.10'	0 cf	31.09'W x 234.17'L x 6.58'H Field A 47,925 cf Overall - 21,458 cf Embedded = 26,467 cf x 0.0% Voids
#2A	4.60'	18,068 cf	ADS N-12 60" x 44 Inside #1 Inside= 59.5"W x 59.5"H => 19.30 sf x 20.00'L = 386.0 cf Outside= 67.0"W x 67.0"H => 22.91 sf x 20.00'L = 458.2 cf 4 Rows of 11 Chambers 28.09' Header x 19.30 sf x 2 = 1,084.1 cf Inside
		18,068 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	4.60'	12.0" Round Culvert L= 20.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 4.60' / 4.50' S= 0.0050 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#2	Device 1	4.60'	1.5" Vert. Orifice/Grate C= 0.600
#3	Device 1	6.60'	4.0' long x 5.00' rise Sharp-Crested Rectangular Weir 2 End Contraction(s)
#4	Secondary	7.00'	24.0" Round Culvert L= 10.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 7.00' / 6.50' S= 0.0500 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 3.14 sf

Primary OutFlow Max=4.35 cfs @ 12.15 hrs HW=7.56' TW=5.44' (Dynamic Tailwater)

↑1=Culvert (Inlet Controls 4.35 cfs @ 5.54 fps)

↑2=Orifice/Grate (Passes < 0.09 cfs potential flow)

↑3=Sharp-Crested Rectangular Weir (Passes < 11.80 cfs potential flow)

Secondary OutFlow Max=1.57 cfs @ 12.20 hrs HW=7.58' TW=4.94' (Dynamic Tailwater)

↑4=Culvert (Inlet Controls 1.57 cfs @ 2.05 fps)

Summary for Pond POND-5.0: POROUS PAVEMENT

Inflow Area = 0.136 ac, 65.31% Impervious, Inflow Depth > 3.92" for 10-YR event
 Inflow = 0.62 cfs @ 12.07 hrs, Volume= 0.044 af
 Outflow = 0.13 cfs @ 12.49 hrs, Volume= 0.027 af, Atten= 78%, Lag= 25.0 min
 Primary = 0.13 cfs @ 12.49 hrs, Volume= 0.027 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Peak Elev= 9.10' @ 12.49 hrs Surf.Area= 3,540 sf Storage= 1,021 cf

Flood Elev= 11.80' Surf.Area= 3,540 sf Storage= 3,108 cf

Plug-Flow detention time= 218.7 min calculated for 0.027 af (60% of inflow)

Center-of-Mass det. time= 115.4 min (917.3 - 801.9)

Volume	Invert	Avail.Storage	Storage Description
#1	8.38'	3,108 cf	Custom Stage Data (Prismatic) Listed below (Recalc)

C0960-006 POST

Type III 24-hr 10-YR Rainfall=5.60"

Prepared by Tighe & Bond

Printed 1/18/2021

HydroCAD® 10.00-20 s/n 03436 © 2017 HydroCAD Software Solutions LLC

Page 25

Elevation (feet)	Surf.Area (sq-ft)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
8.38	3,540	0.0	0	0
9.95	3,540	40.0	2,223	2,223
10.95	3,540	10.0	354	2,577
11.45	3,540	30.0	531	3,108
11.80	3,540	0.0	0	3,108

Device	Routing	Invert	Outlet Devices
#1	Primary	8.88'	6.0" Round Culvert L= 9.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 8.88' / 8.00' S= 0.0978 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.20 sf
#2	Device 1	8.88'	6.0" Vert. Underdrain C= 0.600
#3	Device 2	8.38'	10.000 in/hr Filter Media Infiltration over Surface area

Primary OutFlow Max=0.13 cfs @ 12.49 hrs HW=9.10' TW=3.88' (Dynamic Tailwater)

↑ **1=Culvert** (Controls 0.13 cfs)

↑ **2=Underdrain** (Orifice Controls 0.13 cfs @ 1.60 fps)

↑ **3=Filter Media Infiltration** (Passes 0.13 cfs of 0.82 cfs potential flow)

Summary for Pond POND-5.1: POROUS PAVEMENT

Inflow Area = 0.602 ac, 38.86% Impervious, Inflow Depth > 3.72" for 10-YR event
 Inflow = 2.62 cfs @ 12.07 hrs, Volume= 0.186 af
 Outflow = 0.72 cfs @ 12.43 hrs, Volume= 0.149 af, Atten= 73%, Lag= 21.5 min
 Primary = 0.72 cfs @ 12.43 hrs, Volume= 0.149 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 9.71' @ 12.43 hrs Surf.Area= 6,754 sf Storage= 3,586 cf
 Flood Elev= 11.80' Surf.Area= 6,754 sf Storage= 5,930 cf

Plug-Flow detention time= 152.3 min calculated for 0.149 af (80% of inflow)
 Center-of-Mass det. time= 76.6 min (884.2 - 807.6)

Volume	Invert	Avail.Storage	Storage Description
#1	8.38'	5,930 cf	Custom Stage Data (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
8.38	6,754	0.0	0	0
9.95	6,754	40.0	4,242	4,242
10.95	6,754	10.0	675	4,917
11.45	6,754	30.0	1,013	5,930
11.80	6,754	0.0	0	5,930

Device	Routing	Invert	Outlet Devices
#1	Primary	8.88'	6.0" Round Culvert L= 47.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 8.88' / 8.00' S= 0.0187 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.20 sf
#2	Device 1	8.88'	6.0" Vert. Underdrain C= 0.600

C0960-006 POST

Type III 24-hr 10-YR Rainfall=5.60"

Prepared by Tighe & Bond

Printed 1/18/2021

HydroCAD® 10.00-20 s/n 03436 © 2017 HydroCAD Software Solutions LLC

Page 26

#3 Device 2 8.38' **10.000 in/hr Filter Media Infiltration over Surface area****Primary OutFlow** Max=0.72 cfs @ 12.43 hrs HW=9.71' TW=4.79' (Dynamic Tailwater)↑ **1=Culvert** (Controls 0.72 cfs)↑ **2=Underdrain** (Orifice Controls 0.72 cfs @ 3.66 fps)↑ **3=Filter Media Infiltration** (Passes 0.72 cfs of 1.56 cfs potential flow)**Summary for Pond RG-1: RAIN GARDEN**

[87] Warning: Oscillations may require smaller dt or Finer Routing (severity=102)

Inflow Area = 0.089 ac, 0.00% Impervious, Inflow Depth > 2.85" for 10-YR event
 Inflow = 0.30 cfs @ 12.08 hrs, Volume= 0.021 af
 Outflow = 0.03 cfs @ 13.50 hrs, Volume= 0.007 af, Atten= 91%, Lag= 85.3 min
 Primary = 0.03 cfs @ 13.50 hrs, Volume= 0.007 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 10.00' @ 13.50 hrs Surf.Area= 919 sf Storage= 597 cf
 Flood Elev= 11.80' Surf.Area= 1,590 sf Storage= 2,835 cf

Plug-Flow detention time= 322.2 min calculated for 0.007 af (35% of inflow)
 Center-of-Mass det. time= 195.3 min (1,026.0 - 830.6)

Volume	Invert	Avail.Storage	Storage Description	
#1	7.25'	2,835 cf	Custom Stage Data (Prismatic) Listed below (Recalc)	
Elevation (feet)	Surf.Area (sq-ft)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
7.25	919	0.0	0	0
8.50	919	40.0	460	460
10.00	919	100.0	138	597
11.00	1,269	100.0	1,094	1,691
11.80	1,590	100.0	1,144	2,835

Device	Routing	Invert	Outlet Devices
#1	Primary	7.15'	12.0" Round Culvert L= 238.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 7.15' / 5.00' S= 0.0090 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#2	Device 1	10.50'	16.4" x 16.4" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#3	Device 1	7.25'	6.0" Vert. UD C= 0.600
#4	Device 3	10.00'	0.26 cfs Exfiltration when above 10.00'

Primary OutFlow Max=0.00 cfs @ 13.50 hrs HW=10.00' TW=4.12' (Dynamic Tailwater)↑ **1=Culvert** (Passes 0.00 cfs of 4.21 cfs potential flow)↑ **2=Orifice/Grate** (Controls 0.00 cfs)↑ **3=UD** (Passes 0.00 cfs of 1.49 cfs potential flow)↑ **4=Exfiltration** (Controls 0.00 cfs)

Summary for Link PA-1:

Inflow Area = 10.853 ac, 56.49% Impervious, Inflow Depth > 3.68" for 10-YR event
Inflow = 38.25 cfs @ 12.08 hrs, Volume= 3.331 af
Primary = 38.25 cfs @ 12.08 hrs, Volume= 3.331 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

C0960-006 POST

Prepared by Tighe & Bond

HydroCAD® 10.00-20 s/n 03436 © 2017 HydroCAD Software Solutions LLC

Type III 24-hr 25-YR Rainfall=7.10"

Printed 1/18/2021

Page 28

Time span=0.00-24.00 hrs, dt=0.05 hrs, 481 points
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
 Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment POST-1.0:	Runoff Area=129,041 sf 66.78% Impervious Runoff Depth>6.03" Tc=5.0 min CN=91 Runoff=19.73 cfs 1.490 af
Subcatchment POST-1.1:	Runoff Area=42,709 sf 91.75% Impervious Runoff Depth>6.62" Tc=5.0 min CN=96 Runoff=6.81 cfs 0.541 af
Subcatchment POST-2.0:	Runoff Area=32,330 sf 86.24% Impervious Runoff Depth>6.50" Tc=5.0 min CN=95 Runoff=5.13 cfs 0.402 af
Subcatchment POST-3.0:	Runoff Area=50,366 sf 70.02% Impervious Runoff Depth>5.80" Tc=5.0 min CN=89 Runoff=7.52 cfs 0.559 af
Subcatchment POST-4.0:	Runoff Area=96,700 sf 66.72% Impervious Runoff Depth>5.57" Tc=5.0 min CN=87 Runoff=14.03 cfs 1.031 af
Subcatchment POST-5.0:	Runoff Area=5,912 sf 65.31% Impervious Runoff Depth>5.35" Tc=5.0 min CN=85 Runoff=0.83 cfs 0.060 af
Subcatchment POST-5.1:	Runoff Area=26,210 sf 38.86% Impervious Runoff Depth>5.12" Tc=5.0 min CN=83 Runoff=3.56 cfs 0.257 af
Subcatchment POST-6.0:	Runoff Area=85,650 sf 0.00% Impervious Runoff Depth>2.38" Tc=5.0 min CN=57 Runoff=5.27 cfs 0.390 af
Subcatchment POST-7.0:	Runoff Area=3,857 sf 0.00% Impervious Runoff Depth>4.13" Tc=5.0 min CN=74 Runoff=0.43 cfs 0.030 af
Pond JF-1:	Peak Elev=11.23' Inflow=26.54 cfs 2.030 af 24.0" Round Culvert n=0.013 L=4.0' S=0.0125 '/' Outflow=26.54 cfs 2.030 af
Pond JF-2:	Peak Elev=9.23' Inflow=5.13 cfs 0.402 af 15.0" Round Culvert n=0.013 L=50.0' S=0.0040 '/' Outflow=5.13 cfs 0.402 af
Pond JF-3:	Peak Elev=5.03' Inflow=7.62 cfs 0.602 af 18.0" Round Culvert n=0.013 L=5.0' S=0.0200 '/' Outflow=7.62 cfs 0.602 af
Pond JF-4:	Peak Elev=5.81' Inflow=4.66 cfs 0.791 af 15.0" Round Culvert n=0.013 L=55.0' S=0.0055 '/' Outflow=4.66 cfs 0.791 af
Pond PDMH13:	Peak Elev=5.26' Inflow=9.39 cfs 1.139 af 24.0" Round Culvert n=0.013 L=37.0' S=0.0054 '/' Outflow=9.39 cfs 1.139 af
Pond PDMH4:	Peak Elev=8.63' Inflow=31.67 cfs 2.433 af 24.0" Round Culvert n=0.013 L=11.0' S=0.0045 '/' Outflow=31.67 cfs 2.433 af
Pond POND 4.0: UNDERGROUND	Peak Elev=7.96' Storage=11,628 cf Inflow=14.03 cfs 1.031 af Primary=4.66 cfs 0.791 af Secondary=3.89 cfs 0.113 af Outflow=8.53 cfs 0.904 af

C0960-006 POST

Prepared by Tighe & Bond

HydroCAD® 10.00-20 s/n 03436 © 2017 HydroCAD Software Solutions LLC

Type III 24-hr 25-YR Rainfall=7.10"

Printed 1/18/2021

Page 29

Pond POND-5.0: POROUS PAVEMENT Peak Elev=9.24' Storage=1,216 cf Inflow=0.83 cfs 0.060 af
Outflow=0.31 cfs 0.042 af

Pond POND-5.1: POROUS PAVEMENT Peak Elev=10.73' Storage=4,768 cf Inflow=3.56 cfs 0.257 af
Outflow=1.03 cfs 0.219 af

Pond RG-1: RAIN GARDEN Peak Elev=10.01' Storage=605 cf Inflow=0.43 cfs 0.030 af
Outflow=0.27 cfs 0.017 af

Link PA-1: Inflow=51.65 cfs 4.563 af
Primary=51.65 cfs 4.563 af

Total Runoff Area = 10.853 ac Runoff Volume = 4.760 af Average Runoff Depth = 5.26"
43.51% Pervious = 4.722 ac 56.49% Impervious = 6.131 ac

C0960-006 POST

Prepared by Tighe & Bond

HydroCAD® 10.00-20 s/n 03436 © 2017 HydroCAD Software Solutions LLC

Type III 24-hr 50-YR Rainfall=8.50"

Printed 1/18/2021

Page 30

Time span=0.00-24.00 hrs, dt=0.05 hrs, 481 points
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
 Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment POST-1.0:	Runoff Area=129,041 sf 66.78% Impervious Runoff Depth>7.41" Tc=5.0 min CN=91 Runoff=23.96 cfs 1.830 af
Subcatchment POST-1.1:	Runoff Area=42,709 sf 91.75% Impervious Runoff Depth>8.02" Tc=5.0 min CN=96 Runoff=8.19 cfs 0.655 af
Subcatchment POST-2.0:	Runoff Area=32,330 sf 86.24% Impervious Runoff Depth>7.90" Tc=5.0 min CN=95 Runoff=6.17 cfs 0.488 af
Subcatchment POST-3.0:	Runoff Area=50,366 sf 70.02% Impervious Runoff Depth>7.17" Tc=5.0 min CN=89 Runoff=9.18 cfs 0.691 af
Subcatchment POST-4.0:	Runoff Area=96,700 sf 66.72% Impervious Runoff Depth>6.93" Tc=5.0 min CN=87 Runoff=17.25 cfs 1.283 af
Subcatchment POST-5.0:	Runoff Area=5,912 sf 65.31% Impervious Runoff Depth>6.69" Tc=5.0 min CN=85 Runoff=1.03 cfs 0.076 af
Subcatchment POST-5.1:	Runoff Area=26,210 sf 38.86% Impervious Runoff Depth>6.45" Tc=5.0 min CN=83 Runoff=4.44 cfs 0.324 af
Subcatchment POST-6.0:	Runoff Area=85,650 sf 0.00% Impervious Runoff Depth>3.36" Tc=5.0 min CN=57 Runoff=7.62 cfs 0.551 af
Subcatchment POST-7.0:	Runoff Area=3,857 sf 0.00% Impervious Runoff Depth>5.37" Tc=5.0 min CN=74 Runoff=0.56 cfs 0.040 af
Pond JF-1:	Peak Elev=14.45' Inflow=32.14 cfs 2.485 af 24.0" Round Culvert n=0.013 L=4.0' S=0.0125 '/' Outflow=32.14 cfs 2.485 af
Pond JF-2:	Peak Elev=11.52' Inflow=6.17 cfs 0.488 af 15.0" Round Culvert n=0.013 L=50.0' S=0.0040 '/' Outflow=6.17 cfs 0.488 af
Pond JF-3:	Peak Elev=5.43' Inflow=9.48 cfs 0.749 af 18.0" Round Culvert n=0.013 L=5.0' S=0.0200 '/' Outflow=9.48 cfs 0.749 af
Pond JF-4:	Peak Elev=6.15' Inflow=4.82 cfs 0.957 af 15.0" Round Culvert n=0.013 L=55.0' S=0.0055 '/' Outflow=4.82 cfs 0.957 af
Pond PDMH13:	Peak Elev=5.60' Inflow=12.45 cfs 1.465 af 24.0" Round Culvert n=0.013 L=37.0' S=0.0054 '/' Outflow=12.45 cfs 1.465 af
Pond PDMH4:	Peak Elev=10.65' Inflow=38.31 cfs 2.974 af 24.0" Round Culvert n=0.013 L=11.0' S=0.0045 '/' Outflow=38.31 cfs 2.974 af
Pond POND 4.0: UNDERGROUND	Peak Elev=8.28' Storage=13,067 cf Inflow=17.25 cfs 1.283 af Primary=4.82 cfs 0.957 af Secondary=6.46 cfs 0.198 af Outflow=11.07 cfs 1.155 af

C0960-006 POST

Prepared by Tighe & Bond

HydroCAD® 10.00-20 s/n 03436 © 2017 HydroCAD Software Solutions LLC

Type III 24-hr 50-YR Rainfall=8.50"

Printed 1/18/2021

Page 31


Pond POND-5.0: POROUS PAVEMENT Peak Elev=9.37' Storage=1,396 cf Inflow=1.03 cfs 0.076 af
Outflow=0.46 cfs 0.058 af

Pond POND-5.1: POROUS PAVEMENT Peak Elev=11.41' Storage=5,851 cf Inflow=4.44 cfs 0.324 af
Outflow=1.18 cfs 0.285 af






Pond RG-1: RAIN GARDEN Peak Elev=10.06' Storage=656 cf Inflow=0.56 cfs 0.040 af
Outflow=0.26 cfs 0.026 af



Link PA-1: Inflow=65.00 cfs 5.738 af
Primary=65.00 cfs 5.738 af

Total Runoff Area = 10.853 ac Runoff Volume = 5.937 af Average Runoff Depth = 6.56"
43.51% Pervious = 4.722 ac 56.49% Impervious = 6.131 ac



LEGEND

-  POST-DEVELOPMENT WATERSHED BOUNDARY
-  LONGEST FLOW PATH
-  PRE DEVELOPMENT WATERSHED AREA DESIGNATION
-  POST-DEVELOPMENT POND DESIGNATION
-  POINT OF ANALYSIS



Proposed Multi-Family Development

Iron Horse Properties, LLC

105 Bartlett Street
Portsmouth,
New Hampshire


MARK	DATE	DESCRIPTION
H	1/20/2021	TAC Resubmission
G	11/18/2020	TAC Resubmission
F	10/28/2020	Wetland CUP Resubmission
E	5/20/2020	TAC Resubmission
D	4/29/2020	Wetland CUP Submission
C	4/20/2020	TAC Submission
B	2/6/2020	Design Review Submission
A	1/2/2020	ZBA Submission

PROJECT NO:	C-0960-006
DATE:	April 20, 2020
FILE:	C-0960-006_C-SITE.DWG
DRAWN BY:	NAH
CHECKED BY:	PMC
APPROVED:	BML






POST-DEVELOPMENT WATERSHED PLAN



SCALE: AS SHOWN

C-802.1



LEGEND

-  POST-DEVELOPMENT WATERSHED BOUNDARY
-  LONGEST FLOW PATH
-  POST 1.0
PRE DEVELOPMENT WATERSHED AREA DESIGNATION
-  POST POND 1
POST-DEVELOPMENT POND DESIGNATION
-  PA-1
POINT OF ANALYSIS



Proposed Multi-Family Development

Iron Horse Properties, LLC

105 Bartlett Street
Portsmouth,
New Hampshire

MARK	DATE	DESCRIPTION
H	1/20/2021	TAC Resubmission
G	11/18/2020	TAC Resubmission
F	10/28/2020	Wetland CUP Resubmission
E	5/20/2020	TAC Resubmission
D	4/29/2020	Wetland CUP Submission
C	4/20/2020	TAC Submission
B	2/6/2020	Design Review Submission
A	1/2/2020	ZBA Submission

PROJECT NO:	C-0960-006
DATE:	April 20, 2020
FILE:	C-0960-006_C-SITE.DWG
DRAWN BY:	NAH
CHECKED:	PMC
APPROVED:	BML

POST-DEVELOPMENT WATERSHED PLAN

SCALE: AS SHOWN

C-802.2

Last Saved: 1/19/2021
 Plotted On: Jan 20, 2021 4:04pm By: MWhitman
 Tighe & Bond: C:\Users\mwhitman\OneDrive\Documents\CAD\Drawings - Figures\AutoCAD\Sheet\C-0960-006_C-SITE.dwg

Section 4

Stormwater Treatment

The stormwater management system has been designed to provide stormwater treatment as required by the City of Portsmouth Site Review Regulations and NHDES AoT Regulations (Env-Wq 1500).

4.4.1 Pre-Treatment Methods for Protecting Water Quality

Pre-treatment for the stormwater filtration systems consist of deep sump catch basins.

4.4.2 Treatment Methods for Protecting Water Quality.

The runoff from existing and proposed impervious areas will be treated by various Contech Jellyfish stormwater filtration systems. These Jellyfish systems are sized to treat the Water Quality Flows of their respective subcatchment areas. Each system is outfitted with an internal bypass that diverts peak flows away from treatment. The BMP worksheet for these treatment practices have been included in Section 5 of this report.

A rain garden within the proposed greenway park is included to treat runoff from the surrounding area. The rain garden has been designed and sized to contain the 50-year storm without overtopping, as well as treat a volume of runoff greater than the WQV. Due to poor infiltration rates of the surrounding soils, the bottom of the rain garden is proposed to be lined and outfitted with underdrains to convey treated runoff to the system's outlet structure. The BMP worksheet for this treatment practice has been included in Section 5 of this report, as well.

The multiuse path along the North Mill Pond and through the greenway park will be constructed as lined porous pavement with and underdrain. The underdrain will discharge to the onsite closed drainage system prior to discharging to the Pond.

BMP	Total Suspended Solids	Total Nitrogen	Total Phosphorus
Jellyfish Filter w/Pretreatment ¹	91%	53%	61%
Raingarden ²	90%	65%	65%
Porous Pavement w/Underdrain ²	90%	10%	45%

1. Pollutant removal calculations for Jellyfish Filter with deep sump catchbasin pretreatment shown in Table 4.2.
2. Pollutant removal efficiencies from NH Stormwater Manual Volume 2, Appendix B.

Table 4.2 – Pollutant Removal Calculations				
Contech Jellyfish Filter				
BMP	TSS Removal Rate	Starting TSS Load	TSS Removed	Remaining TSS Load
Deep Sump Catchbasin w/Hood ¹	0.15	1.00	0.15	0.85
Jellyfish Filter ²	0.89	0.85	0.76	0.09
Total Suspended Solids Removed:				91%
	TN Removal Rate	Starting TN Load	TN Removed	Remaining TN Load
Deep Sump Catchbasin w/Hood ¹	0.05	1.00	0.05	0.95
Jellyfish Filter ²	0.51	0.95	0.48	0.47
Total Nitrogen Removed:				53%
	TP Removal Rate	Starting TP Load	TP Removed	Remaining TP Load
Deep Sump Catchbasin w/Hood ¹	0.05	1.00	0.05	0.95
Jellyfish Filter ²	0.59	0.95	0.56	0.39
Total Phosphorus Removed:				61%

1. Pollutant removal efficiencies from NH Stormwater Manual Volume 2, Appendix E.
2. Pollutant removal efficiencies from Contech Engineered Solutions, Jellyfish Filter Stormwater Treatment performance testing results.

Section 5

BMP Worksheets and Sizing Memos



General Calculations - WQV and WQF (optional worksheet)

This worksheet may be useful when designing a BMP that does not fit into one of the specific worksheets already provided (i.e. for a technology which is not a stormwater wetland, infiltration practice, etc.)

Water Quality Volume (WQV)

3.94 ac	A = Area draining to the practice
2.88 ac	A_I = Impervious area draining to the practice
0.73 decimal	I = percent impervious area draining to the practice, in decimal form
0.71 unitless	R_v = Runoff coefficient = $0.05 + (0.9 \times I)$
2.79 ac-in	$WQV = 1'' \times R_v \times A$
10,118 cf	WQV conversion (ac-in x 43,560 sf/ac x 1ft/12")

Water Quality Flow (WQF)

1 inches	P = amount of rainfall. For WQF in NH, P = 1".
0.71 inches	Q = water quality depth. $Q = WQV/A$
97 unitless	CN = unit peak discharge curve number. $CN = 1000 / (10 + 5P + 10Q - 10 * [Q^2 + 1.25 * Q * P]^{0.5})$
0.3 inches	S = potential maximum retention. $S = (1000/CN) - 10$
0.061 inches	Ia = initial abstraction. $I_a = 0.2S$
5.0 minutes	T_c = Time of Concentration
655.0 cfs/mi ² /in	q_u is the unit peak discharge. Obtain this value from TR-55 exhibits 4-II and 4-III
2.853 cfs	$WQF = q_u \times WQV$. Conversion: to convert "cfs/mi ² /in * ac-in" to "cfs" multiply by 1mi ² /640ac

Designer's Notes: POST 1.0 & 1.1 combined

JF-1

PEAK FLOW = 26.54 CFS



CONTECH Stormwater Solutions Inc. Engineer:
Date Prepared:

DRA
11/13/2020

Site Information

Project Name	105 Bartlett Street JF1
Project State	NH
Project City	Portsmouth
Total Drainage Area, Ad	3.94 ac
Post Development Impervious Area, Ai	2.88 ac
Pervious Area, Ap	1.06 ac
% Impervious	73%
Runoff Coefficient, Rc	0.71

Mass Loading Calculations

Mean Annual Rainfall, P	50 in
Agency Required % Removal	80%
Percent Runoff Capture	90%
Mean Annual Runoff, Vt	455583 ft ³
Event Mean Concentration of Pollutant, EMC	70 mg/l
Annual Mass Load, M total	1989.70 lbs

Filter System

Filtration Brand	Jelly Fish
Cartridge Length	54 in

Jelly Fish Sizing

Mass to be Captured by System	1591.76 lbs
Water Quality Flow	2.85 cfs

Method to Use

FLOW BASED

Summary

Flow	Treatment Flow Rate	2.94 cfs
	Required Size	JFPD0808-15-3



General Calculations - WQV and WQF (optional worksheet)

This worksheet may be useful when designing a BMP that does not fit into one of the specific worksheets already provided (i.e. for a technology which is not a stormwater wetland, infiltration practice, etc.)

Water Quality Volume (WQV)

0.74	ac	A = Area draining to the practice
0.64	ac	A _I = Impervious area draining to the practice
0.86	decimal	I = percent impervious area draining to the practice, in decimal form
0.83	unitless	Rv = Runoff coefficient = 0.05 + (0.9 x I)
0.61	ac-in	WQV = 1" x Rv x A
2,222	cf	WQV conversion (ac-in x 43,560 sf/ac x 1ft/12")

Water Quality Flow (WQF)

1	inches	P = amount of rainfall. For WQF in NH, P = 1".
0.83	inches	Q = water quality depth. Q = WQV/A
98	unitless	CN = unit peak discharge curve number. CN = 1000 / (10 + 5P + 10Q - 10 * [Q ² + 1.25 * Q * P] ^{0.5})
0.2	inches	S = potential maximum retention. S = (1000 / CN) - 10
0.033	inches	Ia = initial abstraction. Ia = 0.2S
5.0	minutes	T _c = Time of Concentration
655.0	cfs/mi ² /in	qu is the unit peak discharge. Obtain this value from TR-55 exhibits 4-II and 4-III
0.627	cfs	WQF = q _u x WQV. Conversion: to convert "cfs/mi ² /in * ac-in" to "cfs" multiply by 1mi ² /640ac

Designer's Notes: JF-2

PEAK FLOW = 5.13 CFS



CONTECH Stormwater Solutions Inc. Engineer:
Date Prepared:

DRA
11/13/2020

Site Information

Project Name	105 Bartlett Street JF2
Project State	NH
Project City	Portsmouth
Total Drainage Area, Ad	0.74 ac
Post Development Impervious Area, Ai	0.64 ac
Pervious Area, Ap	0.10 ac
% Impervious	86%
Runoff Coefficient, Rc	0.83

Mass Loading Calculations

Mean Annual Rainfall, P	50 in
Agency Required % Removal	80%
Percent Runoff Capture	90%
Mean Annual Runoff, Vt	98663 ft ³
Event Mean Concentration of Pollutant, EMC	70 mg/l
Annual Mass Load, M total	430.90 lbs

Filter System

Filtration Brand	Jelly Fish
Cartridge Length	40 in

Jelly Fish Sizing

Mass to be Captured by System	344.72 lbs
Water Quality Flow	0.63 cfs

Method to Use

FLOW BASED

Summary

Flow	Treatment Flow Rate	0.73 cfs
	Required Size	JFPD0806-5-1



General Calculations - WQV and WQF (optional worksheet)

This worksheet may be useful when designing a BMP that does not fit into one of the specific worksheets already provided (i.e. for a technology which is not a stormwater wetland, infiltration practice, etc.)

Water Quality Volume (WQV)

1.29	ac	A = Area draining to the practice
0.90	ac	A_I = Impervious area draining to the practice
0.70	decimal	I = percent impervious area draining to the practice, in decimal form
0.68	unitless	R_v = Runoff coefficient = $0.05 + (0.9 \times I)$
0.87	ac-in	$WQV = 1'' \times R_v \times A$
3,168	cf	WQV conversion (ac-in x 43,560 sf/ac x 1ft/12")

Water Quality Flow (WQF)

1	inches	P = amount of rainfall. For WQF in NH, P = 1".
0.68	inches	Q = water quality depth. $Q = WQV/A$
97	unitless	CN = unit peak discharge curve number. $CN = 1000 / (10 + 5P + 10Q - 10 * [Q^2 + 1.25 * Q * P]^{0.5})$
0.4	inches	S = potential maximum retention. $S = (1000/CN) - 10$
0.070	inches	I_a = initial abstraction. $I_a = 0.2S$
5.0	minutes	T_c = Time of Concentration
655.0	cfs/mi ² /in	q_u is the unit peak discharge. Obtain this value from TR-55 exhibits 4-II and 4-III
0.893	cfs	$WQF = q_u \times WQV$. Conversion: to convert "cfs/mi ² /in * ac-in" to "cfs" multiply by $1 \text{ mi}^2 / 640 \text{ ac}$

Designer's Notes: JF-3

PEAK FLOW = 7.62 CFS



CONTECH Stormwater Solutions Inc. Engineer:
Date Prepared:

DRA
11/13/2020

Site Information

Project Name	105 Bartlett Street JF3
Project State	NH
Project City	Portsmouth
Total Drainage Area, Ad	1.29 ac
Post Development Impervious Area, Ai	0.90 ac
Pervious Area, Ap	0.39 ac
% Impervious	70%
Runoff Coefficient, Rc	0.68

Mass Loading Calculations

Mean Annual Rainfall, P	50 in
Agency Required % Removal	80%
Percent Runoff Capture	90%
Mean Annual Runoff, Vt	158450 ft ³
Event Mean Concentration of Pollutant, EMC	70 mg/l
Annual Mass Load, M total	692.01 lbs

Filter System

Filtration Brand	Jelly Fish
Cartridge Length	54 in

Jelly Fish Sizing

Mass to be Captured by System	553.60 lbs
Water Quality Flow	0.89 cfs

Method to Use

FLOW BASED

Summary

Flow	Treatment Flow Rate	1.07 cfs
	Required Size	JFPD0806-5-2



General Calculations - WQV and WQF (optional worksheet)

This worksheet may be useful when designing a BMP that does not fit into one of the specific worksheets already provided (i.e. for a technology which is not a stormwater wetland, infiltration practice, etc.)

Water Quality Volume (WQV)

2.22 ac	A = Area draining to the practice
1.48 ac	A_I = Impervious area draining to the practice
0.67 decimal	I = percent impervious area draining to the practice, in decimal form
0.65 unitless	R_v = Runoff coefficient = $0.05 + (0.9 \times I)$
1.44 ac-in	$WQV = 1'' \times R_v \times A$
5,241 cf	WQV conversion (ac-in x 43,560 sf/ac x 1ft/12")

Water Quality Flow (WQF)

1 inches	P = amount of rainfall. For WQF in NH, P = 1".
0.65 inches	Q = water quality depth. $Q = WQV/A$
96 unitless	CN = unit peak discharge curve number. $CN = 1000 / (10 + 5P + 10Q - 10 * [Q^2 + 1.25 * Q * P]^{0.5})$
0.4 inches	S = potential maximum retention. $S = (1000 / CN) - 10$
0.077 inches	I_a = initial abstraction. $I_a = 0.2S$
5.0 minutes	T_c = Time of Concentration
655.0 cfs/mi ² /in	q_u is the unit peak discharge. Obtain this value from TR-55 exhibits 4-II and 4-III
1.478 cfs	$WQF = q_u \times WQV$. Conversion: to convert "cfs/mi ² /in * ac-in" to "cfs" multiply by 1mi ² /640ac

Designer's Notes: JF-4

PEAK FLOW = 4.66 CFS



CONTECH Stormwater Solutions Inc. Engineer:
Date Prepared:

DRA
11/13/2020

Site Information

Project Name **105 Bartlett Street JF4**
Project State **NH**
Project City **Portsmouth**

Total Drainage Area, Ad **2.22** ac
Post Development Impervious Area, Ai **1.48** ac
Pervious Area, Ap **0.74** ac
% Impervious **67%**
Runoff Coefficient, Rc **0.65**

Mass Loading Calculations

Mean Annual Rainfall, P **50** in
Agency Required % Removal **80%**
Percent Runoff Capture **90%**
Mean Annual Runoff, Vt **262422** ft³
Event Mean Concentration of Pollutant, EMC **70** mg/l
Annual Mass Load, M total **1146.09** lbs

Filter System

Filtration Brand **Jelly Fish**
Cartridge Length **54** in

Jelly Fish Sizing

Mass to be Captured by System **916.87** lbs

Summary		
Mass	Treatment Mass	1001.00 lbs
	Required Size	JFPD0806-7-2



FILTRATION PRACTICE DESIGN CRITERIA (Env-Wq 1508.07)

Type/Node Name: _____

RG-1

Enter the type of filtration practice (e.g., bioretention system) and the node name in the drainage analysis, if applicable

Yes		Have you reviewed the restrictions on unlined systems outlined in Env-Wq 1508.07(a)?	
0.09	ac	A = Area draining to the practice	
-	ac	A _I = Impervious area draining to the practice	
-	decimal	I = percent impervious area draining to the practice, in decimal form	
0.05	unitless	R _v = Runoff coefficient = 0.05 + (0.9 x I)	
0.00	ac-in	WQV = 1" x R _v x A	
16	cf	WQV conversion (ac-in x 43,560 sf/ac x 1ft/12")	
4	cf	25% x WQV (check calc for sediment forebay volume)	
12	cf	75% x WQV (check calc for surface sand filter volume)	
Clean		Method of Pretreatment? (not required for clean or roof runoff)	
cf		V _{SED} = sediment forebay volume, if used for pretreatment	← ≥ 25%WQV
919	sf	A _{SA} = surface area of the practice	
-	iph	K _{sat} DESIGN = design infiltration rate ¹	
Yes	Yes/No	If K _{sat} (prior to factor of safety) is < 0.50 iph, has an underdrain been provided?	
-	hours	T _{DRAIN} = drain time = V / (A _{SA} * I _{DESIGN})	← ≤ 72-hrs
8.50	feet	E _{FC} = elevation of the bottom of the filter course material ²	
7.25	feet	E _{UD} = invert elevation of the underdrain (UD), if applicable	
	feet	E _{SHWT} = elevation of SHWT (if none found, enter the lowest elevation of the test pit)	
	feet	E _{ROCK} = elevation of bedrock (if none found, enter the lowest elevation of the test pit)	
1.25	feet	D _{FC to UD} = depth to UD from the bottom of the filter course	← ≥ 1'
8.50	feet	D _{FC to ROCK} = depth to bedrock from the bottom of the filter course	← ≥ 1'
8.50	feet	D _{FC to SHWT} = depth to SHWT from the bottom of the filter course	← ≥ 1'
10.06	ft	Peak elevation of the 50-year storm event (infiltration can be used in analysis)	
11.80	ft	Elevation of the top of the practice	
YES		50 peak elevation ≤ Elevation of the top of the practice	← yes

If a surface sand filter or underground sand filter is proposed:

YES	ac	Drainage Area check.	← < 10 ac
	cf	V = volume of storage ³ (attach a stage-storage table)	← ≥ 75%WQV
	inches	D _{FC} = filter course thickness	← 18", or 24" if within GPA
Sheet		Note what sheet in the plan set contains the filter course specification	
Yes/No		Access grate provided?	← yes

If a bioretention area is proposed:

YES	ac	Drainage Area no larger than 5 ac?	← yes
641	cf	V = volume of storage ³ (attach a stage-storage table)	← ≥ WQV
18.0	inches	D _{FC} = filter course thickness	← 18", or 24" if within GPA
Sheet	C-506	Note what sheet in the plan set contains the filter course specification	
3.0	:1	Pond side slopes	← ≥3:1
Sheet		Note what sheet in the plan set contains the planting plans and surface cover	

If porous pavement is proposed:

		Type of pavement proposed (concrete? Asphalt? Pavers? Etc)	
	acres	A _{SA} = surface area of the pervious pavement	
	:1	ratio of the contributing area to the pervious surface area	← ≤ 5:1
	inches	D _{FC} = filter course thickness	← 12", or 18" if within GPA
Sheet		Note what sheet in the plan set contains the filter course spec.	← 304.1 sand

1. Rate of the limiting layer (either the filter course or the underlying soil). $K_{sat_{design}}$ includes factor of safety. See Env-Wq 1504.14 for guidance on determining the infiltration rate.
2. See lines 34, 40 and 48 for required depths of filter media.
3. Volume without depending on infiltration. The volume includes the storage above the filter (but below the invert of the outlet structure, if any), the filter media voids, and the pretreatment area. The storage above the filter media shall not include the volume above the outlet structure, if any.

Designer's Notes:

C0960-006 POST

Prepared by Tighe & Bond

HydroCAD® 10.00-20 s/n 03436 © 2017 HydroCAD Software Solutions LLC

Type III 24-hr 50-YR Rainfall=8.50"

Printed 1/18/2021

Stage-Area-Storage for Pond RG-1: RAIN GARDEN

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
7.25	919	0	9.85	919	584
7.30	919	18	9.90	919	588
7.35	919	37	9.95	919	593
7.40	919	55	10.00	919	597
7.45	919	74	10.05	937	644
7.50	919	92	10.10	954	691
7.55	919	110	10.15	972	739
7.60	919	129	10.20	989	788
7.65	919	147	10.25	1,007	838
7.70	919	165	10.30	1,024	889
7.75	919	184	10.35	1,041	940
7.80	919	202	10.40	1,059	993
7.85	919	221	10.45	1,076	1,046
7.90	919	239	10.50	1,094	1,101
7.95	919	257	10.55	1,112	1,156
8.00	919	276	10.60	1,129	1,212
8.05	919	294	10.65	1,147	1,269
8.10	919	312	10.70	1,164	1,326
8.15	919	331	10.75	1,182	1,385
8.20	919	349	10.80	1,199	1,445
8.25	919	368	10.85	1,216	1,505
8.30	919	386	10.90	1,234	1,566
8.35	919	404	10.95	1,251	1,628
8.40	919	423	11.00	1,269	1,691
8.45	919	441	11.05	1,289	1,755
8.50	919	460	11.10	1,309	1,820
8.55	919	464	11.15	1,329	1,886
8.60	919	469	11.20	1,349	1,953
8.65	919	473	11.25	1,369	2,021
8.70	919	478	11.30	1,389	2,090
8.75	919	482	11.35	1,409	2,160
8.80	919	487	11.40	1,430	2,231
8.85	919	492	11.45	1,450	2,303
8.90	919	496	11.50	1,470	2,376
8.95	919	501	11.55	1,490	2,450
9.00	919	505	11.60	1,510	2,525
9.05	919	510	11.65	1,530	2,601
9.10	919	515	11.70	1,550	2,678
9.15	919	519	11.75	1,570	2,756
9.20	919	524	11.80	1,590	2,835
9.25	919	528			
9.30	919	533			
9.35	919	538			
9.40	919	542			
9.45	919	547			
9.50	919	551			
9.55	919	556			
9.60	919	561			
9.65	919	565			
9.70	919	570			
9.75	919	574			
9.80	919	579			



FILTRATION PRACTICE DESIGN CRITERIA (Env-Wq 1508.07)

Type/Node Name: _____

PP-1

Enter the type of filtration practice (e.g., bioretention system) and the node name in the drainage analysis, if applicable

Yes		Have you reviewed the restrictions on unlined systems outlined in Env-Wq 1508.07(a)?	
0.14	ac	A = Area draining to the practice	
0.09	ac	A _I = Impervious area draining to the practice	
0.65	decimal	I = percent impervious area draining to the practice, in decimal form	
0.64	unitless	R _v = Runoff coefficient = 0.05 + (0.9 x I)	
0.09	ac-in	WQV = 1" x R _v x A	
315	cf	WQV conversion (ac-in x 43,560 sf/ac x 1ft/12")	
79	cf	25% x WQV (check calc for sediment forebay volume)	
237	cf	75% x WQV (check calc for surface sand filter volume)	
		Method of Pretreatment? (not required for clean or roof runoff)	
	cf	V _{SED} = sediment forebay volume, if used for pretreatment	← ≥ 25%WQV
3,540	sf	A _{SA} = surface area of the practice	
-	iph	K _{sat} DESIGN = design infiltration rate ¹	
Yes	Yes/No	If K _{sat} (prior to factor of safety) is < 0.50 iph, has an underdrain been provided?	
-	hours	T _{DRAIN} = drain time = V / (A _{SA} * I _{DESIGN})	← ≤ 72-hrs
9.95	feet	E _{FC} = elevation of the bottom of the filter course material ²	
8.88	feet	E _{UD} = invert elevation of the underdrain (UD), if applicable	
	feet	E _{SHWT} = elevation of SHWT (if none found, enter the lowest elevation of the test pit)	
	feet	E _{ROCK} = elevation of bedrock (if none found, enter the lowest elevation of the test pit)	
1.07	feet	D _{FC to UD} = depth to UD from the bottom of the filter course	← ≥ 1'
9.95	feet	D _{FC to ROCK} = depth to bedrock from the bottom of the filter course	← ≥ 1'
9.95	feet	D _{FC to SHWT} = depth to SHWT from the bottom of the filter course	← ≥ 1'
9.37	ft	Peak elevation of the 50-year storm event (infiltration can be used in analysis)	
11.80	ft	Elevation of the top of the practice	
YES		50 peak elevation ≤ Elevation of the top of the practice	← yes

If a surface sand filter or underground sand filter is proposed:

YES	ac	Drainage Area check.	← < 10 ac
	cf	V = volume of storage ³ (attach a stage-storage table)	← ≥ 75%WQV
	inches	D _{FC} = filter course thickness	← 18", or 24" if within GPA
Sheet		Note what sheet in the plan set contains the filter course specification	
	Yes/No	Access grate provided?	← yes

If a bioretention area is proposed:

YES	ac	Drainage Area no larger than 5 ac?	← yes
	cf	V = volume of storage ³ (attach a stage-storage table)	← ≥ WQV
	inches	D _{FC} = filter course thickness	← 18", or 24" if within GPA
Sheet		Note what sheet in the plan set contains the filter course specification	
	:1	Pond side slopes	← ≥3:1
Sheet		Note what sheet in the plan set contains the planting plans and surface cover	

If porous pavement is proposed:

	Asphalt	Type of pavement proposed (concrete? Asphalt? Pavers? Etc)	
	0.1 acres	A _{SA} = surface area of the pervious pavement	
1.7	:1	ratio of the contributing area to the pervious surface area	← ≤ 5:1
12.0	inches	D _{FC} = filter course thickness	← 12", or 18" if within GPA
Sheet	C-504	Note what sheet in the plan set contains the filter course spec.	← 304.1 sand

1. Rate of the limiting layer (either the filter course or the underlying soil). $K_{sat_{design}}$ includes factor of safety. See Env-Wq 1504.14 for guidance on determining the infiltration rate.
2. See lines 34, 40 and 48 for required depths of filter media.
3. Volume without depending on infiltration. The volume includes the storage above the filter (but below the invert of the outlet structure, if any), the filter media voids, and the pretreatment area. The storage above the filter media shall not include the volume above the outlet structure, if any.

Designer's Notes:

C0960-006 POST

Prepared by Tighe & Bond

HydroCAD® 10.00-20 s/n 03436 © 2017 HydroCAD Software Solutions LLC

Type III 24-hr 25-YR Rainfall=7.10"

Printed 1/18/2021

Stage-Area-Storage for Pond POND-5.0: POROUS PAVEMENT

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
8.38	3,540	0	10.98	3,540	2,609
8.43	3,540	71	11.03	3,540	2,662
8.48	3,540	142	11.08	3,540	2,715
8.53	3,540	212	11.13	3,540	2,768
8.58	3,540	283	11.18	3,540	2,821
8.63	3,540	354	11.23	3,540	2,874
8.68	3,540	425	11.28	3,540	2,928
8.73	3,540	496	11.33	3,540	2,981
8.78	3,540	566	11.38	3,540	3,034
8.83	3,540	637	11.43	3,540	3,087
8.88	3,540	708	11.48	3,540	3,108
8.93	3,540	779	11.53	3,540	3,108
8.98	3,540	850	11.58	3,540	3,108
9.03	3,540	920	11.63	3,540	3,108
9.08	3,540	991	11.68	3,540	3,108
9.13	3,540	1,062	11.73	3,540	3,108
9.18	3,540	1,133	11.78	3,540	3,108
9.23	3,540	1,204			
9.28	3,540	1,274			
9.33	3,540	1,345			
9.38	3,540	1,416			
9.43	3,540	1,487			
9.48	3,540	1,558			
9.53	3,540	1,628			
9.58	3,540	1,699			
9.63	3,540	1,770			
9.68	3,540	1,841			
9.73	3,540	1,912			
9.78	3,540	1,982			
9.83	3,540	2,053			
9.88	3,540	2,124			
9.93	3,540	2,195			
9.98	3,540	2,234			
10.03	3,540	2,251			
10.08	3,540	2,269			
10.13	3,540	2,287			
10.18	3,540	2,305			
10.23	3,540	2,322			
10.28	3,540	2,340			
10.33	3,540	2,358			
10.38	3,540	2,375			
10.43	3,540	2,393			
10.48	3,540	2,411			
10.53	3,540	2,428			
10.58	3,540	2,446			
10.63	3,540	2,464			
10.68	3,540	2,482			
10.73	3,540	2,499			
10.78	3,540	2,517			
10.83	3,540	2,535			
10.88	3,540	2,552			
10.93	3,540	2,570			



FILTRATION PRACTICE DESIGN CRITERIA (Env-Wq 1508.07)

Type/Node Name: _____

PP-2

Enter the type of filtration practice (e.g., bioretention system) and the node name in the drainage analysis, if applicable

Yes		Have you reviewed the restrictions on unlined systems outlined in Env-Wq 1508.07(a)?	
0.60	ac	A = Area draining to the practice	
0.23	ac	A _I = Impervious area draining to the practice	
0.39	decimal	I = percent impervious area draining to the practice, in decimal form	
0.40	unitless	R _v = Runoff coefficient = 0.05 + (0.9 x I)	
0.24	ac-in	WQV = 1" x R _v x A	
874	cf	WQV conversion (ac-in x 43,560 sf/ac x 1ft/12")	
218	cf	25% x WQV (check calc for sediment forebay volume)	
655	cf	75% x WQV (check calc for surface sand filter volume)	
		Method of Pretreatment? (not required for clean or roof runoff)	
	cf	V _{SED} = sediment forebay volume, if used for pretreatment	← ≥ 25%WQV
6,754	sf	A _{SA} = surface area of the practice	
-	iph	K _{sat} DESIGN = design infiltration rate ¹	
Yes	Yes/No	If K _{sat} (prior to factor of safety) is < 0.50 iph, has an underdrain been provided?	
-	hours	T _{DRAIN} = drain time = V / (A _{SA} * I _{DESIGN})	← ≤ 72-hrs
9.95	feet	E _{FC} = elevation of the bottom of the filter course material ²	
8.88	feet	E _{UD} = invert elevation of the underdrain (UD), if applicable	
	feet	E _{SHWT} = elevation of SHWT (if none found, enter the lowest elevation of the test pit)	
	feet	E _{ROCK} = elevation of bedrock (if none found, enter the lowest elevation of the test pit)	
1.07	feet	D _{FC to UD} = depth to UD from the bottom of the filter course	← ≥ 1'
9.95	feet	D _{FC to ROCK} = depth to bedrock from the bottom of the filter course	← ≥ 1'
9.95	feet	D _{FC to SHWT} = depth to SHWT from the bottom of the filter course	← ≥ 1'
11.41	ft	Peak elevation of the 50-year storm event (infiltration can be used in analysis)	
11.80	ft	Elevation of the top of the practice	
YES		50 peak elevation ≤ Elevation of the top of the practice	← yes

If a surface sand filter or underground sand filter is proposed:

YES	ac	Drainage Area check.	← < 10 ac
	cf	V = volume of storage ³ (attach a stage-storage table)	← ≥ 75%WQV
	inches	D _{FC} = filter course thickness	← 18", or 24" if within GPA
Sheet		Note what sheet in the plan set contains the filter course specification	
	Yes/No	Access grate provided?	← yes

If a bioretention area is proposed:

YES	ac	Drainage Area no larger than 5 ac?	← yes
	cf	V = volume of storage ³ (attach a stage-storage table)	← ≥ WQV
	inches	D _{FC} = filter course thickness	← 18", or 24" if within GPA
Sheet		Note what sheet in the plan set contains the filter course specification	
	:1	Pond side slopes	← ≥3:1
Sheet		Note what sheet in the plan set contains the planting plans and surface cover	

If porous pavement is proposed:

Asphalt		Type of pavement proposed (concrete? Asphalt? Pavers? Etc)	
0.2	acres	A _{SA} = surface area of the pervious pavement	
3.9	:1	ratio of the contributing area to the pervious surface area	← ≤ 5:1
12.0	inches	D _{FC} = filter course thickness	← 12", or 18" if within GPA
Sheet	C-504	Note what sheet in the plan set contains the filter course spec.	← 304.1 sand

1. Rate of the limiting layer (either the filter course or the underlying soil). $K_{sat_{design}}$ includes factor of safety. See Env-Wq 1504.14 for guidance on determining the infiltration rate.
2. See lines 34, 40 and 48 for required depths of filter media.
3. Volume without depending on infiltration. The volume includes the storage above the filter (but below the invert of the outlet structure, if any), the filter media voids, and the pretreatment area. The storage above the filter media shall not include the volume above the outlet structure, if any.

Designer's Notes:

C0960-006 POST

Prepared by Tighe & Bond

HydroCAD® 10.00-20 s/n 03436 © 2017 HydroCAD Software Solutions LLC

Type III 24-hr 25-YR Rainfall=7.10"

Printed 1/18/2021

Stage-Area-Storage for Pond POND-5.1: POROUS PAVEMENT

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
8.38	6,754	0	10.98	6,754	4,978
8.43	6,754	135	11.03	6,754	5,079
8.48	6,754	270	11.08	6,754	5,180
8.53	6,754	405	11.13	6,754	5,282
8.58	6,754	540	11.18	6,754	5,383
8.63	6,754	675	11.23	6,754	5,484
8.68	6,754	810	11.28	6,754	5,586
8.73	6,754	946	11.33	6,754	5,687
8.78	6,754	1,081	11.38	6,754	5,788
8.83	6,754	1,216	11.43	6,754	5,889
8.88	6,754	1,351	11.48	6,754	5,930
8.93	6,754	1,486	11.53	6,754	5,930
8.98	6,754	1,621	11.58	6,754	5,930
9.03	6,754	1,756	11.63	6,754	5,930
9.08	6,754	1,891	11.68	6,754	5,930
9.13	6,754	2,026	11.73	6,754	5,930
9.18	6,754	2,161	11.78	6,754	5,930
9.23	6,754	2,296			
9.28	6,754	2,431			
9.33	6,754	2,567			
9.38	6,754	2,702			
9.43	6,754	2,837			
9.48	6,754	2,972			
9.53	6,754	3,107			
9.58	6,754	3,242			
9.63	6,754	3,377			
9.68	6,754	3,512			
9.73	6,754	3,647			
9.78	6,754	3,782			
9.83	6,754	3,917			
9.88	6,754	4,052			
9.93	6,754	4,187			
9.98	6,754	4,262			
10.03	6,754	4,296			
10.08	6,754	4,329			
10.13	6,754	4,363			
10.18	6,754	4,397			
10.23	6,754	4,431			
10.28	6,754	4,464			
10.33	6,754	4,498			
10.38	6,754	4,532			
10.43	6,754	4,566			
10.48	6,754	4,599			
10.53	6,754	4,633			
10.58	6,754	4,667			
10.63	6,754	4,701			
10.68	6,754	4,735			
10.73	6,754	4,768			
10.78	6,754	4,802			
10.83	6,754	4,836			
10.88	6,754	4,870			
10.93	6,754	4,903			

Section 6 Long-Term Operation & Maintenance Plan

It is the intent of this Operation and Maintenance Plan to identify the areas of this site that need special attention and consideration, as well as implementing a plan to assure routine maintenance. By identifying the areas of concern as well as implementing a frequent and routine maintenance schedule the site will maintain a high-quality stormwater runoff.

6.1 Contact/Responsible Party

Tax Map & Lot	Contact/Responsible Party
Tax Map 157, Lot 1	Iron Horse Properties, LLC 105 Bartlett Street Portsmouth, NH 03801
Private Roadway	Iron Horse Properties, LLC 105 Bartlett Street Portsmouth, NH 03801
Map 157, Lot 2	Portsmouth Lumber & Hardware, LLC 105 Bartlett Street Portsmouth, NH 03801
Map 164, Lot 1	Portsmouth Lumber & Hardware, LLC 105 Bartlett Street Portsmouth, NH 03801

(Note: The contact information for the Contact/Responsible Party shall be kept current. If ownership changes, the Operation and Maintenance Plan must be transferred to the new party.)

6.2 Maintenance Items

Maintenance of the following items shall be recorded:

- *Litter/Debris Removal*
- *Landscaping*
- *Catchbasin Cleaning*
- *Pavement Sweeping*
- *Contech Jellyfish Filtration System*
- *Porous Pavement*
- *Rain Garden*

The following maintenance items and schedule represent the minimum action required. Periodic site inspections shall be conducted, and all measures must be maintained in effective operating condition. The following items shall be observed during site inspection and maintenance:

- Inspect vegetated areas, particularly slopes and embankments for areas of erosion. Replant and restore as necessary
- Inspect catch basins for sediment buildup
- Inspect site for trash and debris

6.3 Overall Site Operation & Maintenance Schedule

Maintenance Item	Frequency of Maintenance	Location
Litter/Debris Removal	Weekly	Tax Map 157, Lot 1 Private Roadway Map 157, Lot 2 Map 164, Lot 1
Pavement Sweeping - Sweep impervious areas to remove sand and litter.	Annually	Tax Map 157, Lot 1 Private Roadway Map 157, Lot 2 Map 164, Lot 1
Landscaping - Landscaped islands to be maintained and mulched.	Maintained as required and mulched each Spring	Tax Map 157, Lot 1 Private Roadway Map 157, Lot 2 Map 164, Lot 1
Catch Basin (CB) Cleaning - CB to be cleaned of solids and oils.	Annually	Tax Map 157, Lot 1 Private Roadway Map 157, Lot 2 Map 164, Lot 1
Rain Garden - Trash and debris to be removed. - Any required maintenance shall be addressed.	Two (2) times annually and after any rainfall event exceeding 2.5" in a 24-hr period	Tax Map 157, Lot 1
Plunge Pools - Trash and debris to be removed. - Any required maintenance shall be addressed.	Annually	Tax Map 157, Lot 1 Private Roadway
Jelly Fish Units	In accordance with Manufacturer's Recommendations	Tax Map 157, Lot 1 Private Roadway
Underground Detention Basin - Visual observation of sediment levels within system	Annually	Tax Map 157, Lot 1
Porous Pavement - Clean using a vacuum sweeper	Bi-Annually	Tax Map 157, Lot 1

Rain Garden Inspection/Maintenance Requirements		
Inspection/ Maintenance	Frequency	Action
Monitor to ensure that Rain Gardens function effectively after storms	Two (2) times annually and after any rainfall event exceeding 2.5" in a 24-hr period	<ul style="list-style-type: none"> - Trash and debris to be removed - Any required maintenance shall be addressed
Inspect Vegetation	Annually	<ul style="list-style-type: none"> - Inspect the condition of all Rain Garden vegetation - Prune back overgrowth - Replace dead vegetation - Remove any invasive species
Inspect Drawdown Time - The system shall drawdown within 48-hours following a rainfall event.	Annually	<ul style="list-style-type: none"> - Assess the condition of the facility to determine measures required to restore the filtration function, including but not limited to removal of accumulated sediments or reconstruction of the filter.

Contech Jellyfish Filter System Inspection/Maintenance Requirements		
Inspection/ Maintenance	Frequency	Action
Inspect vault for sediment build up, static water, plugged media and bypass condition	One (1) time annually and after any rainfall event exceeding 2.5" in a 24-hr period	Maintenance required for any of the following: <ul style="list-style-type: none"> - >4" of sediment on the vault floor - >1/4" of sediment on top of the cartridge - .4" of static water above the cartridge bottom more than 24 hours after a rain event - If pore space between media is absent. - If vault is in bypass condition during an average rainfall event.
Replace Cartridges	As required by inspection, 1-5 years.	<ul style="list-style-type: none"> - Remove filter cartridges per manufacturer methods. - Vacuum sediment from vault. - Install new cartridges per manufacturer methods

6.3.1 Disposal Requirements

Disposal of debris, trash, sediment and other waste material should be done at suitable disposal/recycling sites and in compliance with all applicable local, state and federal waste regulations.

6.3.2 Snow & Ice Management for Standard Asphalt and Walkways

Snow storage areas shall be located such that no direct untreated discharges are possible to receiving waters from the storage site (snow storage areas have been shown on the Site Plan). The property manager will be responsible for timely snow removal from all private sidewalks, driveways, and parking areas. Snow removal will be hauled off-site and legally disposed of when snowbanks exceed 6 feet in height. Salt storage areas shall be covered or located such that no direct untreated discharges are possible to receiving waters from the storage site. Salt and sand shall be used to the minimum extent practical (refer to the attached for de-icing application rate guideline from the New Hampshire Stormwater Management Manual, Volume 2,).

6.4 Chloride Management Plan

Winter Operational Guidelines

The following Chloride Management Plan is for the 105 Bartlett Street, Multi-Family, Mixed Use Development in Portsmouth, New Hampshire. The Plan includes operational guidelines including winter operator certification requirements, weather monitoring, equipment calibration requirements, mechanical removal, and salt usage evaluation and monitoring. Due to the evolving nature of chloride management efforts, the Chlorides Management Plan will be reviewed annually, in advance of the winter season, to reflect the current management standards.

6.4.1 Background Information

The 105 Bartlett Street, Multi-Family Development is located along the North Mill Pond in Portsmouth, New Hampshire.

6.4.2 Operational Guidelines – Chloride Management

All private contractors engaged at the development site for the purposes of winter operational snow removal and surface maintenance, are responsible for assisting in meeting compliance for the following protocols. Private contractors are expected to minimize the effects of the use of de-icing, anti-icing and pretreatment materials by adhering to the strict guidelines outlined below.

The winter operational de-icing, anti-icing and pretreatment materials will adhere to the following protocols:

6.4.2.1 Winter Operator Certification Requirements

All private contractors engaged at the premises for the purpose of winter operational snow removal and surface maintenance must be current UNHT2 Green SnowPro Certified operators or equivalent and will use only pre-approved

methods for spreading abrasives on private roadways and parking lots. All private contractors engaged at the premises for the purpose of winter operational snow removal and surface maintenance shall provide to the property management two copies of the annual UNHT2 Green SnowPro certificate or equivalent for each operator utilized on the premises. The annual UNHT2 Green SnowPro certificate or equivalent for each operator will be available on file in the Facilities Management office and be present in the vehicle/carrier at all times.

6.4.2.2 Improved Weather Monitoring

The property manager will coordinate weather information for use by winter maintenance contractors. This information in conjunction with site specific air/ground surface temperature monitoring will ensure that private contractors engaged at the premises for the purpose of winter operational snow removal and surface maintenance will make more informed decisions as to when and to what extent de-icing, anti-icing and pretreatment materials are applied to private roadways, sidewalks, and parking lots.

6.4.2.3 Equipment Calibration Requirements

All equipment utilized on the premises for the purpose of winter operational snow removal and surface maintenance will conform to the following calibration requirements.

6.4.2.3.1 Annual Calibration Requirements

All private contractors engaged at the premises for the purpose of winter operational snow removal and surface maintenance shall provide two copies of the annual calibration report for each piece of equipment utilized on the premises. Each calibration report shall include the vehicle/carrier VIN number and the serial numbers for each component including, but not limited to, spreader control units, salt aggregate spreader equipment, brining/pre-wetting equipment, ground speed orientation unit, and air/ground surface temperature monitor. Annual calibration reports will be available on file in the Facilities Management office and be present in the vehicle/carrier at all times.

Prior to each use, each vehicle/carrier operator will perform a systems check to verify that unit settings remain within the guidelines established by the Management Team in order to accurately dispense material. All private contractors engaged at the premises for the purpose of winter operational snow removal and surface maintenance will be subject to spot inspections by members of the Property Management Team to ensure that each vehicle/carrier is operating in a manner consistent with the guidelines set herein or State and Municipal regulations. All units will be recalibrated, and the updated calibration reports will be provided each time repairs or maintenance procedures affect the hydraulic system of the vehicle/carrier.

6.4.2.4 Increased Mechanical Removal Capabilities

All private contractors engaged at the premises will endeavor to use mechanical removal means on a more frequent basis for roadways, parking lots and sidewalks. Dedicating more manpower and equipment to increase snow removal frequencies prevents the buildup of snow and the corresponding need for de-icing, anti-icing and pretreatment materials. Shortened maintenance routes, with shorter service intervals, will be used to stay ahead of snowfall. Minimized snow and ice packing will reduce the need for abrasives, salt aggregates, and/or brining solution to restore surfaces back to bare surface states after winter precipitation events.

After storm events the management team will be responsible for having the streets swept to recapture un-melted de-icing materials, when practical.

6.4.3 Salt Usage Evaluation and Monitoring

All private contractors engaged at the premises for the purpose of winter operational snow removal and surface maintenance shall provide two copies of a storm report, which includes detailed information regarding treatment areas and the use of de-icing, anti-icing and pretreatment materials applied for the removal of snow and surface maintenance on the premises. The property manager will maintain copies of Summary Documents, including copies of the Storm Reports, operator certifications, equipment used for roadway and sidewalk winter maintenance, calibration reports and amount of de-icing materials used.

6.4.4 Summary

The above-described methodologies are incorporated into the Operational Manual and are to be used to qualify and retain all private contractors engaged at the 105 Bartlett Street premises for the purpose of winter operational snow removal and surface maintenance. This section of the Manual is intended to be an adaptive management document that is modified as required based on experience gained from past practices and technological advancements that reflect chloride BMP standards. All employees directly involved with winter operational activities are required to review this document and the current standard Best Management Practices published by the UNH Technology Transfer (T2) program annually. All employees directly involved with winter operational activities, and all private contractors engaged at the premises for the purposes of winter operational snow removal and surface maintenance, must be current UNHT2 Green SnowPro Certified operators or equivalent and undergo the necessary requirements to maintain this certification annually.

Deicing Application Rate Guidelines

24' of pavement (typical two-lane road)

These rates are not fixed values, but rather the middle of a range to be selected and adjusted by an agency according to its local conditions and experience.

Pavement Temp. (°F) and Trend (↑↓)	Weather Condition	Maintenance Actions	Pounds per two-lane mile			
			Salt Prewetted / Pretreated with Salt Brine	Salt Prewetted / Pretreated with Other Blends	Dry Salt*	Winter Sand (abrasives)
> 30° ↑	Snow	Plow, treat intersections only	80	70	100*	Not recommended
	Freezing Rain	Apply Chemical	80 - 160	70 - 140	100 - 200*	Not recommended
30° ↓	Snow	Plow and apply chemical	80 - 160	70 - 140	100 - 200*	Not recommended
	Freezing Rain	Apply Chemical	150 - 200	130 - 180	180 - 240*	Not recommended
25° - 30° ↑	Snow	Plow and apply chemical	120 - 160	100 - 140	150 - 200*	Not recommended
	Freezing Rain	Apply Chemical	150 - 200	130 - 180	180 - 240*	Not recommended
25° - 30° ↓	Snow	Plow and apply chemical	120 - 160	100 - 140	150 - 200*	Not recommended
	Freezing Rain	Apply Chemical	160 - 240	140 - 210	200 - 300*	400
20° - 25° ↑	Snow or Freezing Rain	Plow and apply chemical	160 - 240	140 - 210	200 - 300*	400
20° - 25° ↓	Snow	Plow and apply chemical	200 - 280	175 - 250	250 - 350*	Not recommended
	Freezing Rain	Apply Chemical	240 - 320	210 - 280	300 - 400*	400
15° - 20° ↑	Snow	Plow and apply chemical	200 - 280	175 - 250	250 - 350*	Not recommended
	Freezing Rain	Apply Chemical	240 - 320	210 - 280	300 - 400*	400
15° - 20° ↓	Snow or Freezing Rain	Plow and apply chemical	240 - 320	210 - 280	300 - 400*	500 for freezing rain
0° - 15° ↑↓	Snow	Plow, treat with blends, sand hazardous areas	Not recommended	300 - 400	Not recommended	500 - 750 spot treatment as needed
< 0°	Snow	Plow, treat with blends, sand hazardous areas	Not recommended	400 - 600**	Not recommended	500 - 750 spot treatment as needed

* Dry salt is not recommended. It is likely to blow off the road before it melts ice.

** A blend of 6 - 8 gal/ton MgCl₂ or CaCl₂ added to NaCl can melt ice as low as -10°.

Anti-icing Route Data Form				
Truck Station:				
Date:				
Air Temperature	Pavement Temperature	Relative Humidity	Dew Point	Sky
Reason for applying:				
Route:				
Chemical:				
Application Time:				
Application Amount:				
Observation (first day):				
Observation (after event):				
Observation (before next application):				
Name:				

6.5 Invasive Species

With respect to a particular ecosystem, any species, including its seeds, eggs, spores, or other biological material capable of propagating that species, that is not native to that ecosystem is classified as an invasive species. Refer to the following fact sheet prepared by the University of New Hampshire Cooperative Extension entitled Methods for Disposing Non-Native Invasive Plants for recommended methods to dispose of invasive plant species.

6.6 Annual Updates and Log Requirements

The Owner and/or Contact/Responsible Party shall review this Operation and Maintenance Plan once per year for its effectiveness and adjust the plan and deed as necessary.

A log of all preventative and corrective measures for the stormwater system shall be kept on-site and be made available upon request by any public entity with administrative, health environmental or safety authority over the site including NHDES.

Copies of the Stormwater Maintenance report shall be submitted to the City of Portsmouth on an annual basis.

Stormwater Management Report						
Multi Family Development		105 Bartlett Street – Map 157, Lot 1 & Private Roadway				
BMP Description	Date of Inspection	Inspector	BMP Installed and Operating Properly?	Cleaning / Corrective Action Needed	Date of Cleaning / Repair	Performed By
Deep Sump CB's			<input type="checkbox"/> Yes <input type="checkbox"/> No			
Underground Detention			<input type="checkbox"/> Yes <input type="checkbox"/> No			
Jellyfish Filter 1			<input type="checkbox"/> Yes <input type="checkbox"/> No			
Jellyfish Filter 2			<input type="checkbox"/> Yes <input type="checkbox"/> No			
Jellyfish Filter 3			<input type="checkbox"/> Yes <input type="checkbox"/> No			
Jellyfish Filter 4			<input type="checkbox"/> Yes <input type="checkbox"/> No			
Porous Pavement			<input type="checkbox"/> Yes <input type="checkbox"/> No			
Rain Garden			<input type="checkbox"/> Yes <input type="checkbox"/> No			

Stormwater Management Report						
Ricci Lumber		105 Bartlett Street – Map 157, Lot 2 & Map 164, Lot 1				
BMP Description	Date of Inspection	Inspector	BMP Installed and Operating Properly?	Cleaning / Corrective Action Needed	Date of Cleaning / Repair	Performed By
Deep Sump CB's			<input type="checkbox"/> Yes <input type="checkbox"/> No			
			<input type="checkbox"/> Yes <input type="checkbox"/> No			
			<input type="checkbox"/> Yes <input type="checkbox"/> No			
			<input type="checkbox"/> Yes <input type="checkbox"/> No			

J:\C\C0960 Cathartes\C-0960-006 105 Bartlett Street\Report_Evaluation\Applications\City of Portsmouth\20200420_TAC Submission\C-0960-006_Drainage Report.docx


LEGEND

- EXISTING BUILDING
- EXISTING BUILDING TO BE RENOVATED OR REMOVED
- APPROXIMATE LOCATION OF HISTORIC ROUND HOUSE
- PROPOSED BUILDING
- ZONING LINE
- PROPERTY LINE

PROPOSED DEVELOPMENT
105 BARTLETT STREET
PORTSMOUTH, NH

CONSTRAINTS PLAN

BUILDING CONSTRAINTS	AREA
 PROPOSED DEVELOPMENT LOT	205,804 SF
 APPROXIMATE LOCATION OF CITY UTILITIES	15,547 SF
 NORTH MILL POND COMMUNITY SPACE AREA	47,703 SF
 VIEW CORRIDOR	14,413 SF
 15' MINIMUM RAILROAD SETBACK	8,727 SF



C-0960-006_C-CONSTRAINTS_CLR.dwg Date Plotted: Jan 19, 2021 - 10:46am Plotted By: NAHANSEN


PROPOSED MULTI-FAMILY DEVELOPMENT PORTSMOUTH, NEW HAMPSHIRE

PUBLIC OPEN SPACE EXHIBIT





PUBLIC OPEN SPACE:		PROVIDED	% OF LOT AREA
	GREENWAY COMMUNITY SPACE	47,703 SF	23.2%
	PUBLIC PARK	23,552 SF	11.4%
		71,255 SF 1.64 ACRES	34.6%

Last Save Date: January 19, 2021, 4:50 PM By: WAHANSEN
 Plot Date: Tuesday, January 19, 2021, Plotted By: Neil A. Hansen
 TSS File Location: J:\C0960\06\006_105\Bantick Street\Drawings\Figures\AutoCAD Sheet\C-0960-006_C-SITE.dwg Layout Tab: COMMUNITY



Tighe&Bond

January 20, 2021
C-0960-006-C-SITE.dwg





EXISTING WETLAND BUFFER IMPACTS

Wetland Buffer Setback	Buffer Impact Area for Project Parcels							
	Map 157 Lot 1		Roadway Lot		Map 157 Lot 2		Map 164 Lot 1	
	Existing Impact	Proposed Impact	Existing Impact	Proposed Impact	Existing Impact	Proposed Impact	Existing Impact	Proposed Impact
0 - 25 FT	3,094 SF (1)	0 SF	9,694 SF	6,788 SF	0 SF	0 SF	0 SF	0 SF
25 - 50 FT	7,537 SF (2)	3,138 SF	21,656 SF	17,692 SF	422 SF	422 SF	863 SF	837 SF
50 - 100 FT	20,407 SF (3)	11,889 SF	14,253 SF	11,809 SF	13,345 SF	12,610 SF	18,839 SF	16,135 SF
Total Lot Impact	31,038 SF	15,027 SF	45,603 SF	36,289 SF	13,767 SF	13,032 SF	19,702 SF	16,971 SF
Net Buffer Improvement on Parcels	16,011 SF		9,314 SF		735 SF		2,731 SF	
Overall Project Improvement	28,792 SF							

Notes:
 (1) Includes 147 SF of impact in 0 - 25 ft buffer from the existing railroad turntable structure.
 (2) Includes 1,806 SF of impact in 25 - 50 ft buffer from the existing railroad turntable structure.
 (3) Includes 2,397 SF of impact in 50 - 100 ft buffer from the existing railroad turntable structure.

Overall Buffer Impact Area		
Wetland Buffer Setback	Existing Impact	Proposed Impact
0 - 25 FT	12,788 SF	6,788 SF
25 - 50 FT	30,479 SF	22,089 SF
50 - 100 FT	66,844 SF	52,443 SF
Total Impact	110,111 SF	81,320 SF
NET BUFFER IMPROVEMENT		28,792 SF



PROPOSED WETLAND BUFFER IMPACTS

Proposed Multi-Family Development

Iron Horse Properties, LLC


105 Bartlett Street
Portsmouth,
New Hampshire

MARK	DATE	DESCRIPTION
H	1/20/2021	TAC Resubmission
G	11/18/2020	TAC Resubmission
F	10/28/2020	Wetland CUP Resubmission
E	5/20/2020	TAC Resubmission
D	4/29/2020	Wetland CUP Submission
C	4/20/2020	TAC Submission
B	2/6/2020	Design Review Submission
A	1/2/2020	ZBA Submission


PROJECT NO:	C-0960-006
DATE:	April 20, 2020
FILE:	C-0960-006_C-SITE.DWG
DRAWN BY:	NAH
CHECKED:	PMC
APPROVED:	BML

OVERALL WETLAND BUFFER IMPACTS EXHIBIT



SCALE: AS SHOWN



EXISTING WETLAND BUFFER IMPACTS
= 31,038 SF



WETLAND BUFFER IMPACTS - NOVEMBER 18, 2020 TAC SUBMISSION
= 23,240 SF (7,798 SF IMPROVEMENT)



PROPOSED WETLAND BUFFER IMPACTS
= 15,027 SF (16,011 SF IMPROVEMENT)

Development Lot Buffer Impact Area			
Wetland Buffer Setback	Existing Impact	11/18/2020 TAC Submission Impact	Proposed Impact
0 - 25 FT	3,094 SF	0 SF	0 SF
25 - 50 FT	7,537 SF	8,542 SF	3,138 SF
50 - 100 FT	20,407 SF	14,698 SF	11,889 SF
Total Impact	31,038 SF	23,240 SF	15,027 SF
NET BUFFER IMPROVEMENT		7,798 SF	16,011 SF

Proposed Multi-Family Development

Iron Horse Properties, LLC

105 Bartlett Street
Portsmouth,
New Hampshire

MARK	DATE	DESCRIPTION
H	1/20/2021	TAC Resubmission
G	11/18/2020	TAC Resubmission
F	10/28/2020	Wetland CUP Resubmission
E	5/20/2020	TAC Resubmission
D	4/29/2020	Wetland CUP Submission
C	4/20/2020	TAC Submission
B	2/6/2020	Design Review Submission
A	1/2/2020	ZBA Submission

PROJECT NO:	C-0960-006
DATE:	April 20, 2020
FILE:	C-0960-006_C-SITE.DWG
DRAWN BY:	NAH
CHECKED:	PMC
APPROVED:	BML

DEVELOPMENT LOT WETLAND BUFFER IMPACTS EXHIBIT

SCALE: AS SHOWN



EXISTING PLAN





REZONING PLAN ACREAGE: 5.73 **NUMBER OF UNITS: 120**

DATE : AUGUST 2018





ACREAGE: 7.07 **NUMBER OF UNITS: 272**

DATE : SEPTEMBER 2019





ACREAGE: 5.07 **NUMBER OF UNITS: 174**

DATE : MAY 2020





ACREAGE: 4.71 **NUMBER OF UNITS: 170**

DATE : OCTOBER 2020





ACREAGE: 4.72 **NUMBER OF UNITS: 152**

DATE : JANUARY 2021






Cathartes
105 Bartlett Street Project
Portsmouth, NH

WETLAND DELINEATION AND ASSESSMENT OF FUNCTIONS AND VALUES

April 2020
Last Revised: January 2021



Tighe&Bond
Engineers | Environmental Specialists

1.0	Introduction	1
2.0	Methods.....	1
3.0	North Mill Pond	1
3.1	Ecological Integrity.....	2
3.2	Wildlife, Finfish, and Shellfish Habitat	2
3.3	Recreational and Commercial Potential.....	2
3.4	Aesthetic Quality	2
3.5	Educational Potential	3
3.6	Noteworthiness	3
4.0	North Mill Pond Tidal Buffer	3
4.1	Commercial Area Buffer	3
4.2	Disturbed Forest Buffer	4
4.3	Shrub Thicket Buffer.....	4
4.4	Buffer Impacts and Mitigation	4
5.0	Excavated Palustrine Forested Wetland	4
6.0	Summary	5

1.0 Introduction

The purpose of this report is to characterize wetlands and buffers in the vicinity of a proposed multi-family development at 105 Bartlett Street in Portsmouth, NH. The site is long and narrow and is located between an active railroad and North Mill Pond. It includes commercial buildings with paved and gravel parking areas, abandoned railroad structures, disturbed forest, and a dense shrub thicket. The area is highly disturbed, being originally filled by the railroad in the late 1800s.

2.0 Methods

On October 29 and December 2, 2019, Tighe & Bond reviewed and assessed 2,000+/- linear feet of tidal wetlands and buffers along the North Mill Pond. The review was limited to the vicinity of a proposed multi-family development, extending from Bartlett Street to an area opposite Cornwall Street, which runs roughly perpendicular to the parcel.

The wetland delineation review was based on criteria specified in the *Corps of Engineers Wetlands Delineation Manual, Technical Report Y-87-1* (January 1987), and the *Regional Supplement to the Corps of Engineers Wetland Delineation Manual: Northcentral and Northeast Region* (January 2012). The Highest Observable Tide Line was reviewed based on the definition found in NH Department of Environmental Services Wetland Rules, Env-Wt 101.49/Env-Wt 602.23. Wetlands were classified based on *Classification of Wetlands and Deepwater Habitats of the United States* (Cowardin et al., 1979).

The Highest Observable Tide Line (HOTL) had been previously delineated by another consulting firm in 2017. This line was reviewed by exporting the 2017 surveyed line into ArcGIS to overlay on an aerial photographic base map. This base map was then uploaded to an iPad and paired with a Trimble R1 submeter GPS for in-field verification. Using the iPad and GPS as a guide, the line was then evaluated in the field. The HOTL was deemed accurate and the previous 2017 delineation was accepted by Tighe & Bond. A previously unidentified freshwater wetland was also found within a six-foot +/- deep abandoned railroad turntable. Tighe & Bond delineated this area with sequentially numbered flagging and located the wetland boundary using the GPS technology described above.

Functions and values were assessed in the vicinity of the proposed project. Assessment methodologies were adapted from the *Maine Citizens Guide to Evaluating, Restoring, and Managing Tidal Marshes* (Bryan et al., 1997) and *The Highway Methodology Workbook Supplement—Wetland Functions and Values: A Descriptive Approach*, NAEPP-360-1-30a, US Army Corps of Engineers, New England Division, September 1999.

Photographs of the wetlands and buffers are provided in Appendix A.

3.0 North Mill Pond

North Mill Pond is a 79+/- acre tidal pond at the outlet of Hodgson Brook. It receives tidal flows under Maplewood Avenue at the northeast end of the pond. The pond consists predominantly of exposed mudflats at low tide, and is classified as Estuarine, Intertidal, Unconsolidated Shore, Mud, Regularly Flooded (E2US3N). A narrow band of salt marsh reaching up to 35+/- feet wide was identified between the mudflats and upland (Photo 1). The marsh is dominated by smooth cordgrass (*Spartina alterniflora*), with species such as

saltmeadow cordgrass (*Spartina patens*), sea lavender (*Limonium carolinianum*), and seaside goldenrod (*Solidago sempervirens*) more dominant toward the upland edge. This marsh area was classified as Estuarine, Intertidal, Emergent, Persistent, Regularly Flooded (E2EM1N).

North Mill Pond provides several important wetland functions and values, though many have been degraded by development and human activity. The following functions and values were assessed for the wetland in the vicinity of the proposed project.

3.1 Ecological Integrity

Ecological Integrity relates to how much the wetland has retained its native biotic and abiotic features and how these may have been degraded by human influences.

The Ecological Integrity of North Mill Pond has been compromised due to the presence of a tidal restriction, development of the upland buffer, water quality degradation, and filling along the project site. Efforts have been made in recent years to improve water quality entering the pond, improve tidal flushing, and restore some of the salt marshes. The peripheral salt marsh appears to be healthy and is comprised of native species along the project area.

3.2 Wildlife, Finfish, and Shellfish Habitat

The Wildlife, Finfish, and Shellfish Habitat function is the suitability of the habitat to support wildlife.

North Mill Pond contains extensive mudflats and a healthy but narrow peripheral salt marsh that contribute to wildlife habitat value. However, this value has been compromised by all the factors affecting Ecological Integrity described above. The area is likely to support a variety of wildlife, including migratory birds, finfish, and shellfish. Wildlife Action Plan mapping (Appendix B) depicts several small areas of the highest ranked wildlife value habitat around the pond. These high value habitats include two salt marsh areas in the vicinity of the proposed project; one directly across from the project and another just to the northeast of it.

3.3 Recreational and Commercial Potential

Recreational and Commercial Potential is the suitability of the wetland to support activities such as hiking, boating, hunting, bird watching, and shellfish harvesting.

North Mill Pond has the potential for use by small boats during high tide, though access appears to be limited to a boat launch on Marsh Lane, north of Maplewood Avenue. Shellfish harvesting is not allowed within the mudflats. Bird watching is a potential activity but public access is limited. There is an informal trail that runs through the proposed project area between Bartlett Street and Maplewood Avenue across private property that could be used for bird watching, but public access is not currently guaranteed. There is no visitor center, formally maintained trails, or access for disabled persons that would make this a more valuable area for recreation.

3.4 Aesthetic Quality

Aesthetic Quality refers to the ability of the wetland to provide interesting views and natural vistas.

The areas surrounding North Mill Pond are highly developed commercial and residential areas. There are few public viewing areas, but in locations where the pond can be seen it generally offers wide vistas and aesthetically pleasing views.

3.5 Educational Potential

Educational Potential consists of the ability of the wetland to serve as an outdoor classroom.

There is no safe public access to North Mill Pond near the project site. In addition to being private property, the project site has dangerous construction debris and steep banks to the pond, further diminishing the educational potential of this wetland.

3.6 Noteworthiness

Noteworthiness includes important qualities of the wetland not identified in previous functions, such as historic sites or unique natural features.

This area of North Mill Pond is noteworthy as it contains a salt marsh in a developed setting, which adds to its importance aesthetically and as part of the character of the area. In addition, the adjacent uplands have been proposed as part of the North Mill Pond Greenways project, which was presented to stakeholders in January 2019. (<https://www.cityofportsmouth.com/planportsmouth/north-mill-pond-trail-and-greenway>).

The wetland itself is not known for having any important historical features in the vicinity of the project area, though there have been historic structures and activities along its banks. The project area has some significance as the site of an old railroad yard with a turntable and roundhouse.

4.0 North Mill Pond Tidal Buffer

The North Mill Pond 100-foot tidal buffer can be divided into three zones within the project area: 1) a commercial area, including the Ricci Supply and Ace Hardware complex, the Great Rhythm Brewery building, a former railroad machine shop, and all the paved and unpaved impervious surfaces associated with those buildings; 2) the disturbed forest directly northeast and northwest of Great Rhythm Brewery, including the area around the old railroad turntable and roundhouse remains; and 3) the shrub thicket extending along the narrow portion of the parcel to the northeast. These areas all include historic filling 2-16 feet deep associated with railroad activities. The fill includes coal, coal ash, and possible slag.

4.1 Commercial Area Buffer

The commercial area (Photos 1-3) is comprised almost completely of impervious surfaces. These include buildings, paved and compact gravel parking lots, and a narrow strip of vegetation 10-20 feet wide extending down a steep bank to the tidal wetland. The vegetation includes lawn and species associated with disturbed sites such as staghorn sumac (*Rhus typhina*), autumn olive (*Elaeagnus umbellata*), black cherry (*Prunus serotina*), and Asiatic bittersweet (*Celastrus orbiculatus*). This area has little to offer in the way of functions and values other than contributing to stabilization of steep eroding

banks along the wetland. Runoff from this area likely contributes to the degraded water quality in North Mill Pond.

4.2 Disturbed Forest Buffer

The disturbed forested area northeast and southwest of Great Rhythm Brewery (Photos 4-6) is dominated by Norway Maple (*Acer platanoides*), black cherry, and staghorn sumac. The area includes significant rubble and debris as well as the railroad turntable and roundhouse remains. This area provides some screening for wildlife using the North Mill Pond and provides cover and food for small mammals and birds. However, it is dominated by invasive vegetation, and is highly disturbed by human activity.

4.3 Shrub Thicket Buffer

The shrub thicket northeast of the commercial area (Photos 7-8) is dominated by autumn olive with lesser amounts of staghorn sumac and other shrub species. This area provides wildlife habitat for small mammals and birds as well as screening for wildlife using North Mill Pond. Though invasive, the autumn olive provides prolific fruits utilized by birds and other frugivores. Bedding, clothing, campfire remains, trash, and other evidence suggests that this densely vegetated area has been used as camp sites by homeless individuals.

4.4 Buffer Impacts and Mitigation

The proposed project will not include any work within the 25-foot buffer to North Mill Pond. In addition, a 50-foot easement from the mean high water will be granted to the City of Portsmouth by the developer to build the North Mill Pond Trail and Greenway, which will provide improvements to the buffer, including invasive species management and revegetation with native species. Installation of the trail and greenway would result in improved functions and values of the wetland and buffer including: Ecological Integrity, Recreation Potential, Aesthetic Quality, and possibly Educational Potential. Existing impacts to the 100-foot buffer will be reduced from the trail and greenway improvements through the removal and restoration of impervious surfaces.

Table 4.1

105 Bartlett Street Multi-Family Development Buffer Impact Reductions

Overall Buffer Impact Area		
Wetland Buffer Setback	Existing Impact	Proposed Impact
0 - 25 FT	12,788 SF	6,788 SF
25 - 50 FT	30,479 SF	22,089 SF
50 - 100 FT	66,844 SF	52,443 SF
Total Impact	110,111 SF	81,320 SF
NET BUFFER IMPROVEMENT		28,792 SF

5.0 Excavated Palustrine Forested Wetland

A small wetland was delineated by Tighe & Bond within the base of the six-foot +/- deep, concrete walled railroad roundtable (Photos 9-10) within the disturbed forested area. The soils in this wetland are poorly drained marine silts and clays. The vegetation is dominated

by Norway maple and red osier dogwood (*Cornus sericea*). Nearby test pits identified approximately two to four feet of fill in the vicinity of the structure. Therefore, it is likely this wetland was at least partly excavated into native marine sediments during construction of the turntable. It is unclear if this area was originally a wetland or if the wetland was created by the excavation. This wetland was classified as Palustrine, Forested, Deciduous, Saturated (PFO1B). The small size of the wetland and its location within a man-made structure in a highly disturbed landscape has resulted in this system providing negligible wetland functions and values.

6.0 Summary

Two wetlands were delineated and evaluated on the site:

North Mill Pond is a 79+/- acre tidal wetland with expansive mud flats (E2US3N) and a narrow fringe of salt marsh (E2EM1N). Wetland functions and values are primarily Wildlife, Finfish, and Shellfish Habitat, as well as Aesthetic Quality and Noteworthiness. It is noteworthy as an important aesthetic component of the area and as an important potential site for a greenways trail project. It also has compromised but improving Ecological Integrity and some Recreation Potential. Upland buffers to the wetland have been compromised by development and invasive species, but limited vegetation does provide some screening for wildlife in the wetland.

A small excavated forested wetland (PFO1B) was identified within the old railroad turntable, approximately six feet below existing grade within a concrete wall. The small size of the wetland and its location within a man-made structure in a highly disturbed landscape has resulted in this system providing negligible wetland functions and values.

Tighe&Bond

APPENDIX A

Appendix A- Photographic Log

Client: Cathartes

Job Number: C-0960006

Site: 105 Bartlett St., Portsmouth, NH

Photograph No.: 1	Date: 10/29/19	Direction Taken: Northeast
Description: Salt marsh fringe along North Mill Pond at low tide opposite a commercial area in southwest portion of the site.		


Photograph No.: 2	Date: 10/29/19	Direction Taken: Northeast
Description: Paved buffer and eroding banks along North Mill Pond at low tide along the commercial area in southwest portion of the site.		


Appendix A- Photographic Log

Client: Cathartes

Job Number: C-0960006

Site: 105 Bartlett St., Portsmouth, NH

Photograph No.: 3	Date: 10/29/19	Direction Taken: Northeast
Description: Compact gravel drive and old railroad repair shop at the northern end of the commercial area with impervious surfaces.		
		

Photograph No.: 4	Date: 10/29/19	Direction Taken: Northeast
Description: Buffer fill slope with rubble adjacent to a narrow salt marsh along the disturbed forest just northwest of the Great Rhythm Brewing Company.		
		

Appendix A- Photographic Log

Client: Cathartes

Job Number: C-0960006

Site: 105 Bartlett St., Portsmouth, NH

Photograph No.: 5	Date: 10/29/19	Direction Taken: Southwest
--------------------------	-----------------------	-----------------------------------

Description: Lawn and disturbed forest buffer northwest of the Great Rhythm Brewing Company.



Photograph No.: 6	Date: 10/29/19	Direction Taken: East
--------------------------	-----------------------	------------------------------

Description: Remains of the railroad roundhouse and disturbed forest buffer northeast of the Great Rhythm Brewing Company.



Appendix A- Photographic Log

Client: Cathartes

Job Number: C-0960006

Site: 105 Bartlett St., Portsmouth, NH

Photograph No.: 7	Date: 10/29/19	Direction Taken: Northeast
--------------------------	-----------------------	-----------------------------------

Description: Shrub thicket and existing informal trail at the northeast end of the proposed project area.



Photograph No.: 8	Date: 10/29/19	Direction Taken: Northeast
--------------------------	-----------------------	-----------------------------------

Description: Evidence of use as camp sites by homeless individuals within the shrub thicket at the northeast end of the project area.



Appendix A- Photographic Log

Client: Cathartes

Job Number: C-0960006

Site: 105 Bartlett St., Portsmouth, NH

Photograph No.: 9	Date: 12/2/19	Direction Taken: South
--------------------------	----------------------	-------------------------------

Description: Wetland dominated by Norway maple and red osier dogwood within the old railroad turntable approximately six feet below grade.



Photograph No.: 10	Date: 12/2/19	Direction Taken: n/a
---------------------------	----------------------	-----------------------------

Description: Poorly drained marine silts and clays observed in the bottom of the old railroad turntable.



Tighe&Bond

APPENDIX B

2015 HIGHEST RANKED WILDLIFE HABITAT BY ECOLOGICAL CONDITION


 Highest Ranked Habitat in New Hampshire

 Highest Ranked Habitat in the Biological Region

Biological region = TNC ecoregional subsection for terrestrial habitats or Aquatic Resource Mitigation region for wetlands and floodplain forest.

 Supporting Landscapes

 Conservation or public




Base map data provided by NH GRANIT at UNH September 2019. Intended for planning use only.




0 1 2 Kilometers


0 1 2 Miles







Existing vegetation within the 100' Buffer on the 105 Bartlett property consists of many invasive species along with native second growth trees and shrubs. Invasive species within the 100' buffer zone, include Buckthorn, Autumn Olive, Honeysuckle, Bittersweet, Norway Maple. With the exception of the Norway Maples in the 25' vegetated buffer, invasive species within the 100' shoreland setback will be removed. Invasive species within the 25' vegetated buffer will be flagged in field by the landscape architect or certified arborist to be removed. Invasive shrubs within the 25' vegetated buffer with caliper measuring greater than 3" such as Buckthorn and Autumn Olive will be flush cut repeatedly to kill the plant, leaving the stumps in place. Woody invasives smaller than 3" caliper shall be removed with hand tools. Areas of soil disturbance from such removals will be limited to the immediate root area surrounding each plant, dressed with loam, replanted with New England Wildlife and Conservation Seed Mix and stabilized with jute mesh staked in place. All other areas disturbed by headwalls and culverts shall be loamed, seeded with New England Wildlife and Conservation Seed Mix and stabilized with jute mesh.



1 Ash



2

Multiflora Rose




3

Bittersweet



4 Eastern Red Cedar

105 Bartlett – Existing Vegetation & Invasive Species in 100’ Buffer - Photos



Sumac & Ash
5



6


Ash and Buckthorn



7 Ash and Buckthorn



8 Buckthorn



Multiflora rose,
Crabapple,
Dogwood,
Buckthorn

9



Norway Maple, Rhus aromatica

10



Norway Maple, Buckthorn,
Cottonwoods

11



Norway
Maple

12



Norway Maples
Red Oak
13



Buckthorn, Crabapple,
Norway Maples,
Cottonwoods, Autumn Olive
14



Cottonwoods



15
16
105 Bartlett – Existing Vegetation & Invasive Species in 100' Buffer - Photos



Cherry, Norway
Maple, Buckthorn

17



18 Cottonwood, Norway
Maple, Buckthorn



19



20



21



Norway Maple, Sumac
 Red Oak 22

Ash, Cottonwood

23
105 Bartlett – Existing Vegetation & Invasive Species in 100’ Buffer - Photos



Gravel, Scrub, Norway Maples, Cottonwood beyond

24



Cottonwood & Birch

25



Open Gravel

26

105 Bartlett – Existing Vegetation & Invasive Species in 100’ Buffer - Photos

C-0960-006
November 4, 2020

Mr. Jeff Johnston, Principal
Cathartes
100 Summer Street, Suite 1600
Boston, MA 02110

Re: **Environmental Summary**
105 Bartlett Street
Portsmouth, New Hampshire

Dear Mr. Johnston:

Tighe & Bond conducted an environmental assessment in 2019 for the 105 Bartlett Street, New Hampshire property (herein referred to as the "Site") on behalf of Cathartes. Tighe & Bond conducted a limited subsurface exploration program to help assess the subsurface conditions potentially impacted by historical operations and to better understand potential environmental risks associated with property acquisition and redevelopment.

Below is a summary of potential environmental concerns associated with the Site identified during this limited environmental assessment:

- Tighe & Bond completed an Environmental Site Assessment which included visual field observations of soil and the collection and chemical analysis of both soil and ground water samples across the Site.
 - A total of ten(10) environmental soil samples were collected across the Site and submitted for a comprehensive chemical analysis of volatile organic compounds (VOCs), semi-volatile organic compounds (SVOCs), total petroleum hydrocarbons (TPH), polychlorinated biphenyl (PCBs), RCRA 8 Metals and reactivity.
 - A total of four(4) groundwater samples were collected across the Site and submitted for a comprehensive chemical analysis of VOCs, SVOCs and dissolved RCRA 8 metals.
- Tighe & Bond concluded that in general, portions of the site are underlain with a layer of anthropogenic fill material at varying thickness which is attributed to the historic site use. The anthropogenic fil material is generally consistent with typical urban sites with similar commercial/industrial historical site uses.
- Portions of the Site were formerly utilized for B&M railroad operations and a foundry. The presence of coal tar was not observed in test pits, and/or the soil and groundwater data collected at the site to date.
- Analytical data from soil samples collected during the 2019 subsurface investigations indicate concentrations of contaminants are typical for similar urban sites are considered background conditions from the anthropogenic fill material at the Site and do not constitute a NHDES reporting condition.

105 Bartlett Street
Portsmouth, New Hampshire

November 2020

Analytical data obtained from the 2019 groundwater sampling at the Site indicate no exceedances of the NHDES groundwater standards were observed.

- A 20,000 gallon tank was removed from the site in 1992. The soil in this area has limited petroleum contaminants in soil. This area will be remediated under a soil management plan and in accordance with NHDES regulations during redevelopment.

If you have any questions pertaining to this limited subsurface investigation, please feel free to contact the undersigned.

Very truly yours,

TIGHE & BOND, INC.



Bryan Gammons
Senior Environmental Scientist


\\Tighebond.com\data\Data\Projects\C\C0960 Cathartes\C-0960-006 105 Bartlett Street\Environmental\Reports\Environmental Memo - November 2020\2020-1104-105 Bartlett Street - Environmental Memo-Final.doc

BUILDING C GRADE PLANE ELEVATIONS

POINT #	ELEV	POINT #	ELEV	POINT #	ELEV	POINT #	ELEV	POINT #	ELEV	POINT #	ELEV	POINT #	ELEV	AVERAGE GRADE PLANE
1	12.70	18	13.10	35	14.30	52	14.30	69	11.45	86	13.10	103	14.35	13.28
2	12.55	19	13.30	36	14.30	53	14.30	70	11.50	87	13.20	104	14.35	
3	12.40	20	13.50	37	14.30	54	14.30	71	11.55	88	13.30	105	14.30	
4	12.30	21	13.70	38	14.30	55	14.20	72	11.60	89	13.40	106	14.15	
5	12.20	22	13.95	39	14.30	56	14.05	73	11.75	90	13.50	107	14.00	
6	12.10	23	14.10	40	14.30	57	13.95	74	11.95	91	13.55	108	13.85	
7	12.05	24	14.30	41	14.30	58	13.50	75	12.05	92	13.65	109	13.75	
8	12.00	25	14.30	42	14.30	59	13.10	76	12.10	93	13.75	110	13.60	
9	12.00	26	14.30	43	14.30	60	13.00	77	12.20	94	13.80	111	13.45	
10	12.00	27	14.30	44	14.30	61	12.50	78	12.35	95	13.85	112	13.30	
11	12.00	28	14.30	45	14.30	62	12.10	79	12.50	96	13.95	113	13.15	
12	12.00	29	14.30	46	14.30	63	12.00	80	12.60	97	13.95	114	13.00	
13	12.00	30	14.30	47	14.30	64	11.80	81	12.70	98	14.00	115	12.95	
14	12.00	31	14.30	48	14.30	65	11.70	82	12.85	99	14.10	116	12.90	
15	12.00	32	14.30	49	14.30	66	11.60	83	12.95	100	14.15	117	12.80	
16	12.10	33	14.30	50	14.30	67	11.60	84	13.00	101	14.20	118	12.75	
17	12.70	34	14.30	51	14.30	68	11.50	85	13.05	102	14.30	119	12.73	

BUILDING A & B GRADE PLANE ELEVATIONS

POINT #	ELEV	POINT #	ELEV	POINT #	ELEV	POINT #	ELEV	POINT #	ELEV	POINT #	ELEV	POINT #	ELEV	POINT #	ELEV	POINT #	ELEV	POINT #	ELEV	POINT #	ELEV	POINT #	ELEV	POINT #	ELEV	POINT #	ELEV	POINT #	ELEV	POINT #	ELEV	POINT #	ELEV	POINT #	ELEV	POINT #	ELEV	AVERAGE GRADE PLANE
200	17.50	217	17.50	234	17.50	251	12.60	268	16.20	285	16.40	302	17.50	319	16.90	336	17.50	353	17.50	370	16.15	387	17.50	404	17.50	421	14.00	16.39										
201	17.50	218	17.50	235	17.50	252	12.95	269	16.60	286	16.00	303	17.50	320	16.90	337	17.50	354	17.50	371	16.20	388	17.50	405	17.50	422	14.20											
202	17.50	219	17.50	236	17.50	253	13.10	270	17.00	287	15.80	304	17.50	321	16.70	338	17.50	355	17.50	372	16.35	389	17.50	406	17.50	423	14.50											
203	17.50	220	17.50	237	17.50	254	13.25	271	17.40	288	15.80	305	17.50	322	16.50	339	17.50	356	17.50	373	17.00	390	17.50	407	17.50	424	14.75											
204	17.50	221	17.50	238	17.50	255	13.40	272	17.50	289	17.50	306	17.50	323	16.20	340	17.50	357	17.50	374	17.50	391	17.50	408	17.50	425	14.90											
205	17.50	222	17.50	239	17.50	256	13.60	273	17.50	290	17.50	307	17.50	324	16.05	341	17.50	358	17.50	375	17.50	392	17.50	409	17.50	426	15.00											
206	17.50	223	17.50	240	17.50	257	13.75	274	17.50	291	17.50	308	17.50	325	16.00	342	17.50	359	17.50	376	17.50	393	17.50	410	17.50	427	15.10											
207	14.50	224	17.50	241	7.90	258	13.85	275	17.50	292	17.50	309	17.50	326	15.00	343	17.50	360	17.50	377	17.50	394	17.50	411	17.50	428	15.20											
208	14.50	225	17.50	242	7.90	259	13.95	276	15.50	293	17.50	310	17.50	327	14.50	344	17.50	361	17.00	378	17.50	395	17.50	412	17.50	429	15.15											
209	15.00	226	17.50	243	7.95	260	14.00	277	15.50	294	17.50	311	17.50	328	13.80	345	17.50	362	16.80	379	17.50	396	17.50	413	17.50	430	15.10											
210	17.00	227	17.50	244	7.95	261	14.10	278	15.50	295	17.50	312	17.50	329	13.70	346	17.50	363	16.10	380	17.50	397	17.50	414	17.50	431	15.00											
211	17.50	228	17.50	245	12.70	262	14.40	279	15.50	296	17.50	313	17.50	330	13.60	347	17.50	364	16.05	381	17.50	398	17.50	415	17.50	432	15.00											
212	17.50	229	17.50	246	12.65	263	14.90	280	17.50	297	17.50	314	16.20	331	13.55	348	17.50	365	16.10	382	17.50	399	17.50	416	17.50	433	15.00											
213	17.50	230	17.50	247	12.60	264	15.20	281	17.50	298	17.50	315	16.25	332	13.50	349	17.50	366	16.10	383	17.50	400	17.50	417	17.50	434	15.90											
214	17.50	231	17.50	248	12.55	265	15.30	282	17.50	299	17.50	316	16.85	333	13.60	350	17.50	367	16.10	384	17.50	401	17.50	418	15.00	AVERAGE GRADE PLANE	16.39											
215	17.50	232	17.50	249	12.50	266	15.40	283	17.20	300	17.50	317	16.90	334	13.70	351	17.50	368	16.10	385	17.50	402	17.50	419	13.90													
216	17.50	233	17.50	250	12.55	267	15.80	284	16.80	301	17.50	318	16.90	335	13.90	352	17.50	369	16.15	386	17.50	403	17.50	420	14.00													



BUILDING ELEVATIONS AND HEIGHTS

	GRADE PLANE ELEVATION	BUILDING ELEVATION		BUILDING HEIGHT	
		ALLOWED	PROPOSED	ALLOWED	PROPOSED
BUILDING A	16.39'	66.39'	65.50'	50.00'	49.11'
BUILDING B	16.39'	66.39'	65.50'	50.00'	49.11'
BUILDING C	13.28'	63.28'	62.50'	50.00'	49.22'

Last Saved: 1/19/2021
Plotted On: Jan 19, 2021 12:36pm By: MAHansen
Tighe & Bond P:\Cadd\Projects\105 Bartlett Street Drawings - Figures\AutoCAD\Sheet\C-0960-006_C-SITE.dwg

Proposed Multi-Family Development


Iron Horse Properties, LLC

105 Bartlett Street
Portsmouth,
New Hampshire


MARK	DATE	DESCRIPTION
H	1/20/2021	TAC Resubmission
G	11/18/2020	TAC Resubmission
F	10/28/2020	Wetland CUP Resubmission
E	5/20/2020	TAC Resubmission
D	4/29/2020	Wetland CUP Submission
C	4/20/2020	TAC Submission
B	2/6/2020	Design Review Submission
A	1/2/2020	ZBA Submission

GRADE PLANE EXHIBIT


SCALE: AS SHOWN



WB-67 ENTERING



WB-67 - Interstate Semi-Trailer
 Overall Length 73.501ft
 Overall Width 8.500ft
 Overall Body Height 13.500ft
 Min Body Ground Clearance 1.334ft
 Max Track Width 8.500ft
 Lock-to-lock time 6.00s
 Max Steering Angle (Virtual) 28.40°



WB-67 EXITING

Proposed Multi-Family Development

Iron Horse Properties, LLC


105 Bartlett Street
 Portsmouth,
 New Hampshire



MARK	DATE	DESCRIPTION
H	1/20/2021	TAC Resubmission
G	11/18/2020	TAC Resubmission
F	10/28/2020	Wetland CUP Resubmission
E	5/20/2020	TAC Resubmission
D	4/29/2020	Wetland CUP Submission
C	4/20/2020	TAC Submission
B	2/6/2020	Design Review Submission
A	1/2/2020	ZBA Submission

PROJECT NO:	C-0960-006
DATE:	April 20, 2020
FILE:	C-0960-006_C-SITE.DWG
DRAWN BY:	NAH
CHECKED:	PMC
APPROVED:	BML


TRUCK TURNING EXHIBIT

SCALE: AS SHOWN








FIRE TRUCK CUL-DE-SAC




FIRE TRUCK TURN AROUND



FIRE TRUCK - REAR BUILDING ACCESS



Portsmouth Fire Truck
 Overall Length 47.830ft
 Overall Width 8.500ft
 Overall Body Height 10.432ft
 Min Body Ground Clearance 0.862ft
 Track Width 8.000ft
 Lock-to-lock time 6.00s
 Max Steering Angle (Virtual) 38.00°



Proposed Multi-Family Development

Iron Horse Properties, LLC

105 Bartlett Street
Portsmouth,
New Hampshire

MARK	DATE	DESCRIPTION
H	1/20/2021	TAC Resubmission
G	11/18/2020	TAC Resubmission
F	10/28/2020	Wetland CUP Resubmission
E	5/20/2020	TAC Resubmission
D	4/29/2020	Wetland CUP Submission
C	4/20/2020	TAC Submission
B	2/6/2020	Design Review Submission
A	1/2/2020	ZBA Submission

PROJECT NO:	C-0960-006
DATE:	April 20, 2020
FILE:	C-0960-006_C-SITE.DWG
DRAWN BY:	NAH
CHECKED:	PMC
APPROVED:	BML

TRUCK TURNING EXHIBIT

SCALE: AS SHOWN

Last Saved: 1/19/2021 11:09am By: MAHansen
 Plotted On: Jan 19, 2021 11:11am
 Tighe & Bond: P:\CUBSD\Camaron\C-0960-006_105 Bartlett Street\Drawings - Figures\AutoCAD\Sheet\C-0960-006_C-SITE.dwg

MEMORANDUM

Ref: 1955A

To: Jeff Johnston
Cathartes

From: Stephen G. Pernaw, P.E., PTOE

Subject: Trip Generation Update

Date: February 21, 2020 (Updated December 23, 2020)

As you know, our office prepared the “*Traffic Impact & Site Access Study – Proposed Residential Subdivision*” report dated June 18, 2019 for the 120-unit multi-family low/mid-rise residential development located on the south side of North Mill Pond in Portsmouth, New Hampshire. The development proposal has changed and it now involves: 1) acquiring the property associated with Great Rhythm Brewing Company and the Play All Day Doggy Daycare facility and razing these buildings, 2) increasing the development area by +1.72 acres, and 3) increasing the number of dwellings to 152 units (see Attachment 1). Similar to our previous traffic report, all site vehicles will travel to/from the development via Bartlett Street. The purpose of this memorandum is to compare the trip generating characteristics of the former and current development proposals. The following tabulation compares these development proposals.

	Original Development Proposal	Current Development Proposal	Change
1. Apartments (units)	120	152	+32 units
2. Great Rhythm Brew ing Co	remains	razed	} - 68 AM & -85 PM trips
3. Play All Day dog care	remains	razed	
4. Access/Egress	Via Bartlett St. Only	Via Bartlett St. Only	No change
5. Development area	2.99 Acres	4.71 Acres	+58% increase

Table 1A summarizes the updated trip generation analyses and shows that the proposed residences will generate a total of approximately 52 (AM) and 66 (PM) vehicle-trips during the peak hour periods (see Attachment 2). Driveway counts conducted at the brewery/dog daycare parking lot in October 2018 revealed that these two uses generated 68 (AM) and 85 (PM) vehicle-trips on a typical weekday (see Attachment 3).

The current development proposal will generate approximately -57 (AM) and -72 (PM) fewer vehicle-trips during the peak hour periods than the previous development proposal. Accordingly, the traffic projections contained in the previous traffic study are now considered to be quite conservative on the “high side.”

Table 1A **Trip Generation Summary**
Current Development Proposal (12/23/20)


	Current Development Proposal			Original Development Proposal ³
	Apartments ¹ (152 units)	Less Brewery & Dog Daycare ²	Net Trips Generated	
Weekday AM Peak Hour				
Entering	14 veh	-34 veh	-20 veh	+11 veh
Exiting	<u>38 veh</u>	<u>-34 veh</u>	<u>4 veh</u>	<u>+30 veh</u>
Total	52 trips	-68 trips	-16 trips	+41 trips
Weekday PM Peak Hour				
Entering	40 veh	-43 veh	-3 veh	+32 veh
Exiting	<u>26 veh</u>	<u>-42 veh</u>	<u>-16 veh</u>	<u>+21 veh</u>
Total	66 trips	-85 trips	-19 trips	+53 trips

¹ITE Land Use Code 221- Multifamily Housing (Mid-Rise) - Equation Method - See Attachment 2

²October 2018 Driveway Counts - See Attachment 3

³See Attachments 4 & 5

Attachments



Trip Generation Summary

Alternative: Alternative 1
 Phase:
 Project: 1955A Gen 122220
 Open Date: 12/22/2020
 Analysis Date: 12/22/2020

ITE	Land Use	Weekday Average Daily Trips			Weekday AM Peak Hour of Adjacent Street Traffic			Weekday PM Peak Hour of Adjacent Street Traffic		
		* Enter	Exit	Total	* Enter	Exit	Total	* Enter	Exit	Total
221	MID-RISE 1 <i>EQUATION METHOD</i> 152 Dwelling Units	414	413	827	14	38	52	40	26	66
	Unadjusted Volume	414	413	827	14	38	52	40	26	66
	Internal Capture Trips	0	0	0	0	0	0	0	0	0
	Pass-By Trips	0	0	0	0	0	0	0	0	0
	Volume Added to Adjacent Streets	414	413	827	14	38	52	40	26	66

Total Weekday Average Daily Trips Internal Capture = 0 Percent
 Total Weekday AM Peak Hour of Adjacent Street Traffic Internal Capture = 0 Percent
 Total Weekday PM Peak Hour of Adjacent Street Traffic Internal Capture = 0 Percent

* - Custom rate used for selected time period.

MEMORANDUM

Ref: 1821A

To: Juliet T. H. Walker, AICP
 Planning Director
 City of Portsmouth Planning Department

From: Stephen G. Pernaw, P.E., PTOE

Subject: Clipper Traders – Supplemental Traffic Counts
 Portsmouth, New Hampshire

Date: October 9, 2018

On October 2, 2018 the Technical Advisory Committee requested that traffic counts be conducted at the Great Rhythm Brewing Company & Play All Day dog day care center parking lot to determine when the busiest traffic periods occur. These traffic counts were conducted on Thursday, October 4, 2018 during the morning and evening commuter periods:

<u>Hourly Volumes</u>			
	<u>Arrivals</u>	<u>Departures</u>	<u>Trips</u>
7:00 - 8:00	32	29	61
8:00 - 9:00	<u>35</u>	<u>33</u>	<u>68</u>
2-Hour Total	67	62	129
3:00 - 4:00	22	14	36
4:00 - 5:00	34	37	71
5:00 - 6:00	<u>38</u>	<u>41</u>	<u>79</u>
3-Hour Total	94	92	186
<u>AM Peak Hour Volumes</u>			
7:30 - 8:30	34	34	68
8:00 - 9:00	35	33	68
<u>PM Peak Hour Volumes</u>			
4:15 - 5:15	43	42	85

The highest hourly traffic volume that was generated by this parking lot occurred from 4:15 to 5:15 PM with 43 arrivals and 42 departures (85 vehicle-trips).

cc: John Chagnon, P.E. – Ambit Engineering, Inc.
 Doug Pinciario, Clipper Traders, LLC
 Ed Hayes, Ricci Lumber
 Eric Eby, P.E. – City of Portsmouth
 Elizabeth Oltman, P.E. – The Engineering Corporation

TRIP GENERATION

To estimate the quantity of vehicle trips that will be produced by the proposed residential development, Pernaw & Company, Inc. considered the standardized trip-generation rates and equations published by the Institute of Transportation Engineers (ITE)¹. Based upon ITE Land Use Code LUC 221 – Multi-Family Housing (Mid-Rise) the overall development is expected to generate approximately 41 vehicle-trips during the weekday AM peak hour and 53 vehicle-trips during the weekday PM peak hour, on an average weekday basis. These results are based upon consideration of both the trip “rate” and “equation” method, and 120 dwelling units as the independent variable. The following table summarizes the anticipated trip-generating characteristics of the proposed residential development.

Table 1		Trip Generation Summary - Clipper Traders	
		120 Dwelling Units ¹	
Weekday Total ²			
Entering		326 veh	
Exiting		<u>326 veh</u>	
Total		652 trips	
Weekday AM Peak Hour ²			
Entering		11 veh	
Exiting		<u>30 veh</u>	
Total		41 trips	
Weekday PM Peak Hour ²			
Entering		32 veh	
Exiting		<u>21 veh</u>	
Total		53 trips	

¹ ITE LUC 221 Multi-Family Housing (Mid-Rise)

² Trip Equation Method

³ Trip Rate Method

All vehicle-trips associated with the proposed residential development will be “primary” trips, or new trips to the area. Appendix F contains the trip generation computations for the proposed residential development, along with a diagram that summarizes the distribution of the primary trips at the various study area intersections.

¹ Institute of Transportation Engineers, *Trip Generation*, tenth edition (Washington, D.C., 2017).

Trip Generation Summary

Alternative: Previous Development Proposal

Phase:

Project: 1955A

Open Date: 6/25/2020

Analysis Date: 6/25/2020

ITE	Land Use	Weekday Average Daily Trips			Weekday AM Peak Hour of Adjacent Street Traffic			Weekday PM Peak Hour of Adjacent Street Traffic		
		* Enter	Exit	Total	* Enter	Exit	Total	* Enter	Exit	Total
221	MID-RISE 2	327	326	653	11	30	41	32	21	53
	120 Dwelling Units									
	Unadjusted Volume	327	326	653	11	30	41	32	21	53
	Internal Capture Trips	0	0	0	0	0	0	0	0	0
	Pass-By Trips	0	0	0	0	0	0	0	0	0
	Volume Added to Adjacent Streets	327	326	653	11	30	41	32	21	53

Total Weekday Average Daily Trips Internal Capture = 0 Percent

Total Weekday AM Peak Hour of Adjacent Street Traffic Internal Capture = 0 Percent

Total Weekday PM Peak Hour of Adjacent Street Traffic Internal Capture = 0 Percent

* - Custom rate used for selected time period.