

Findings of Fact | Site Plan Review

City of Portsmouth Planning Board

Date: April 16, 2026

Property Address: 1151 Sagamore Ave.

Application #: LU-25-178

Decision: Approve Deny Approve with Conditions

Findings of Fact:

Per RSA 676:3, I: The local land use board shall issue a final written decision which either approves or disapproves an application for a local permit and make a copy of the decision available to the applicant. **The decision shall include specific written findings of fact that support the decision. Failure of the board to make specific written findings of fact supporting a disapproval shall be grounds for automatic reversal and remand by the superior court upon appeal, in accordance with the time periods set forth in RSA 677:5 or RSA 677:15, unless the court determines that there are other factors warranting the disapproval.** If the application is not approved, the board shall provide the applicant with written reasons for the disapproval. If the application is approved with conditions, the board shall include in the written decision a detailed description of the all conditions necessary to obtain final approval.

Site Plan Regulations Section 2.9 Evaluation Criteria - in order to grant site plan review approval, the TAC and the Planning Board shall find that the application satisfies evaluation criteria pursuant to NH State Law and listed herein. In making a finding, the TAC and the Planning Board shall consider all standards provided in Articles 3 through 11 of these regulations.

	Site Plan Review Regulations Section 2.9 Evaluation Criteria	Finding (Meets Standard/Criteria)	Supporting Information
1	Compliance with all City Ordinances and Codes and these regulations. <u>Applicable standards:</u>	Meets Does Not Meet	<u>Applicable standards:</u> No Variances Required. Project complies with all Ordinance requirements including parking, setbacks, open space, building coverage, lot area per dwelling unit, height, and frontage.
2	Provision for the safe development, change or expansion of use of the site.	Meets Does Not Meet	TAC reviewed the site layout, and recommended approval. Plans show all utility connections and drainage infrastructure needed. Driveway exists.

	Site Plan Review Regulations Section 2.9 Evaluation Criteria	Finding (Meets Standard/Criteria)	Supporting Information
3	Adequate erosion control and stormwater management practices and other mitigative measures, if needed, to prevent adverse effects on downstream water quality and flooding of the property or that of another.	Meets Does Not Meet	Rain Garden and subsurface infiltration systems to minimize storm water peak discharge and provide stormwater treatment. Erosion controls during construction as necessary. Long Term Maintenance Plan provided.
4	Adequate protection for the quality of groundwater.	Meets Does Not Meet	No groundwater withdrawal (water supply is city). No nearby production wells. Rain Garden and infiltration systems provide treatment.
5	Adequate and reliable water supply sources.	Meets Does Not Meet	Water supply is Public -City. Supply confirmed by TAC review. All plumbing fixtures will be low / water conserving.
6	Adequate and reliable sewage disposal facilities, lines, and connections.	Meets Does Not Meet	Sewer connection is Public - City. Property has existing force main stub to be connected to. Stub size and capacity to serve development verified by TAC.
7	Absence of undesirable and preventable elements of pollution such as smoke, soot, particulates, odor, wastewater, stormwater, sedimentation or any other discharge into the environment which might prove harmful to persons, structures, or adjacent properties.	Meets Does Not Meet	Property will not have any fuel consuming devices. No Natural Gas, No Home Heating Oil. All appliances will be Energy Star certified. Air or Geo-thermal heat pump proposed. All air exchange via energy recovery ventilators. Filtered dryer vents are the only other exhaust points.
8	Adequate provision for fire safety, prevention and control.	Meets Does Not Meet	Full NFPA 13 wet sprinkler system construction. Adequate FD access – reviewed during TAC.
9	Adequate protection of natural features such as, but not limited to, wetlands.	Meets Does Not Meet	No wetlands or other protected natural resources on or adjacent to site.
10	Adequate protection of historical features on the site.	Meets Does Not Meet	Site is vacant – no existing historical features are present. Existing single family residence was removed in 2025 under separate demolition permit.
11	Adequate management of the volume and flow of traffic on the site and adequate	Meets	The residential use is a low volume trip generator.

	Site Plan Review Regulations Section 2.9 Evaluation Criteria	Finding (Meets Standard/Criteria)	Supporting Information
	traffic controls to protect public safety and prevent traffic congestion.	Does Not Meet	
12	Adequate traffic controls and traffic management measures to prevent an unacceptable increase in safety hazards and traffic congestion off-site.	Meets Does Not Meet	Application was submitted to NHDOT in early 2026 and comments addressed. Final NHDOT submission to be made simultaneously to city approval.
13	Adequate insulation from external noise sources.	Meets Does Not Meet	No adjacent high noise generators are present.
14	Existing municipal solid waste disposal, police, emergency medical, and other municipal services and facilities adequate to handle any new demands on infrastructure or services created by the project.	Meets Does Not Meet	Trash collection will be city curbside, as allowed. TAC Review included Fire and Police Departments. All concerns addressed in design.
15	Provision of usable and functional open spaces of adequate proportions, including needed recreational facilities that can reasonably be provided on the site	Meets Does Not Meet	Site conforms to setbacks and open space requirements.
16	Adequate layout and coordination of on-site accessways and sidewalks in relationship to off-site existing or planned streets, accessways, bicycle paths, and sidewalks.	Meets Does Not Meet	Site driveway connects to existing sidewalk along property's frontage.
17	Demonstration that the land indicated on plans submitted with the application shall be of such character that it can be used for building purposes without danger to health.	Meets Does Not Meet	Land is suitable for the intended purpose, Existing Lot. Previously used for one single family residence. Plans follow ordinance and guidelines; see TAC approval.
18	Adequate quantities, type or arrangement of landscaping and open space for the provision of visual, noise and air pollution buffers.	Meets Does Not Meet	Professionally prepared landscape design provided.

	Site Plan Review Regulations Section 2.9 Evaluation Criteria	Finding (Meets Standard/Criteria)	Supporting Information
19	Compliance with applicable City approved design standards.	<p style="text-align: center;">Meets</p> <p style="text-align: center;">Does Not Meet</p>	Approved by the Technical Advisory Committee
	Other Board Findings:		

DRAFT



HALEY WARD®

APPLICATION FOR SITE PLAN REVIEW

**TO THE CITY OF PORTSMOUTH
FOR 1151 SAGAMORE AVENUE**

Map 224, Lot 19 | Portsmouth, NH

APPLICANT:

1151 Sagamore Avenue CBC LLC

76 State Street, Newburyport, ME 01950

March 25, 2026
JN: 5010314.002

REPORT PREPARED BY:

Haley Ward, Inc.

200 Griffin Road, Unit 14 | Portsmouth, NH 03801

March 25, 2026

Rick Chellman, Planning Board Chair
City of Portsmouth
1 Junkins Avenue
Portsmouth, New Hampshire 03801

Re: Site Plan Application at 1151 Sagamore Avenue, Tax Map 224, Lot 19

Dear Chairman Chellman and Planning Board Members:

On behalf of 1151 Sagamore Avenue CBC LLC, we are pleased to submit the attached plan set for **Site Plan Approval** for the above-mentioned project and request that we be placed on the agenda for your **April 16, 2026** Planning Board Meeting. The project includes the proposed new construction of four (4) standalone, single family residential dwelling units and the associated and required site improvements. The property was previously occupied by a one single family home, which was demolished under a City Demolition permit in late 2025.

The application conforms to all of the required Density and Development Standards of the MRO Zoning District; no variances are necessary.

This applicant seeks Planning Board approval for the project. A drawing set has been included with this application which depicts the existing site conditions and the proposed improvements. Also included in this submission are the following additional exhibits:

- Portsmouth Tax and Zoning Maps
- Preliminary Traffic Assessment
- Wastewater Pump Design Report
- Green Building Statement
- Drainage Analysis
- Building Plans
- Engineer's Cost Estimate

The project received a positive recommendation from the Technical Advisory Committee on March 5, 2026. We look forward to the Planning Boards review of this submission, and we will be in attendance at the meeting to answer any questions the Board may have on the proposed design.

Sincerely,
Haley Ward, Inc.



Drew Olehowski, PE
Project Manager

DJO-cba



City of Portsmouth, New Hampshire

Site Plan Application Checklist

This site plan application checklist is a tool designed to assist the applicant in the planning process and for preparing the application for Planning Board review. The checklist is required to be completed and uploaded to the Site Plan application in the City's online permitting system. A pre-application conference with a member of the planning department is strongly encouraged as additional project information may be required depending on the size and scope. The applicant is cautioned that this checklist is only a guide and is not intended to be a complete list of all site plan review requirements. Please refer to the Site Plan review regulations for full details.

Applicant Responsibilities (Section 2.5.2): Applicable fees are due upon application submittal along with required attachments. The application shall be complete as submitted and provide adequate information for evaluation of the proposed site development. Waiver requests must be submitted in writing with appropriate justification.

Name of Applicant: 1151 Sagamore Ave CBC, LLC Date Submitted: 12/12/2025

Application # (in City's online permitting): LU-25-178

Site Address: 1151 Sagamore Avenue Portsmouth, NH 03801 Map: 224 Lot: 19

Application Requirements			
<input checked="" type="checkbox"/>	Required Items for Submittal	Item Location (e.g. Page or Plan Sheet/Note #)	Waiver Requested
<input type="checkbox"/>	Complete application form submitted via the City's web-based permitting program (2.5.2.1(2.5.2.3A))	Online	N/A
<input type="checkbox"/>	All application documents, plans, supporting documentation and other materials uploaded to the application form in viewpoint in digital Portable Document Format (PDF). One hard copy of all plans and materials shall be submitted to the Planning Department by the published deadline. (2.5.2.8)	Online and Delivered	N/A

Site Plan Review Application Required Information			
<input checked="" type="checkbox"/>	Required Items for Submittal	Item Location (e.g. Page/line or Plan Sheet/Note #)	Waiver Requested
<input type="checkbox"/>	Statement that lists and describes "green" building components and systems. (2.5.3.1B)	TBD	
<input type="checkbox"/>	Existing and proposed gross floor area and dimensions of all buildings and statement of uses and floor area for each floor. (2.5.3.1C)	Architects Plans	N/A
<input type="checkbox"/>	Tax map and lot number, and current zoning of all parcels under Site Plan Review. (2.5.3.1D)	Proposed Site Plan	N/A

Site Plan Review Application Required Information			
<input checked="" type="checkbox"/>	Required Items for Submittal	Item Location (e.g. Page/line or Plan Sheet/Note #)	Waiver Requested
<input type="checkbox"/>	Owner's name, address, telephone number, and signature. Name, address, and telephone number of applicant if different from owner. (2.5.3.1E)	Cover Page	N/A
<input type="checkbox"/>	Names and addresses (including Tax Map and Lot number and zoning districts) of all direct abutting property owners (including properties located across abutting streets) and holders of existing conservation, preservation or agricultural preservation restrictions affecting the subject property. (2.5.3.1F)	Proposed Site Plan	N/A
<input type="checkbox"/>	Names, addresses and telephone numbers of all professionals involved in the site plan design. (2.5.3.1G)	Cover Page	N/A
<input type="checkbox"/>	List of reference plans. (2.5.3.1H)	Cover Page	N/A
<input type="checkbox"/>	List of names and contact information of all public or private utilities servicing the site. (2.5.3.1I)	Cover Page	N/A

Site Plan Specifications			
<input checked="" type="checkbox"/>	Required Items for Submittal	Item Location (e.g. Page/line or Plan Sheet/Note #)	Waiver Requested
<input type="checkbox"/>	Full size plans shall not be larger than 22 inches by 34 inches with match lines as required, unless approved by the Planning Director.. (2.5.4.1A)	Required on all plan sheets	N/A
<input type="checkbox"/>	Scale: Not less than 1 inch = 60 feet and a graphic bar scale shall be included on all plans. (2.5.4.1B)	Required on all plan sheets	N/A
<input type="checkbox"/>	GIS data should be referenced to the coordinate system New Hampshire State Plane, NAD83 (1996), with units in feet. (2.5.4.1C)	Complies	N/A
<input type="checkbox"/>	Plans shall be drawn to scale and stamped by a NH licensed civil engineer. (2.5.4.1D)	Required on all plan sheets	N/A
<input type="checkbox"/>	Wetlands shall be delineated by a NH certified wetlands scientist and so stamped. (2.5.4.1E)	N/A	N/A
<input type="checkbox"/>	Title (name of development project), north point, scale, legend. (2.5.4.2A)	All Pages	N/A
<input type="checkbox"/>	Date plans first submitted, date and explanation of revisions. (2.5.4.2B)	All Pages	N/A
<input type="checkbox"/>	Individual plan sheet title that clearly describes the information that is displayed. (2.5.4.2C)	Required on all plan sheets	N/A
<input type="checkbox"/>	Source and date of data displayed on the plan. (2.5.4.2D)	On Site Survey	N/A

Site Plan Specifications – Required Exhibits and Data

<input checked="" type="checkbox"/>	Required Items for Submittal	Item Location (e.g. Page/line or Plan Sheet/Note #)	Waiver Requested
<input type="checkbox"/>	<p>1. Existing Conditions: (2.5.4.3A)</p> <ul style="list-style-type: none"> • Surveyed plan of site showing existing natural and built features; • Existing building footprints and gross floor area; • Existing parking areas and number of parking spaces provided; • Zoning district boundaries; • Existing, required, and proposed dimensional zoning requirements including building and open space coverage, yards and/or setbacks, and dwelling units per acre; • Existing impervious and disturbed areas; • Limits and type of existing vegetation; • Wetland delineation, wetland function and value assessment (including vernal pools); • SFHA, 100-year flood elevation line and BFE data, as required. 	Existing Conditions Plan	
<input type="checkbox"/>	<p>2. Buildings and Structures: (2.5.4.3B)</p> <ul style="list-style-type: none"> • Plan view: Use, size, dimensions, footings, overhangs, 1st fl. elevation; • Elevations: Height, massing, placement, materials, lighting, façade treatments; • Total Floor Area; • Number of Usable Floors; • Gross floor area by floor and use. 	Architects Plans	
<input type="checkbox"/>	<p>3. Access and Circulation: (2.5.4.3C)</p> <ul style="list-style-type: none"> • Location/width of access ways within site; • Location of curbing, right of ways, edge of pavement and sidewalks; • Location, type, size and design of traffic signing (pavement markings); • Names/layout of existing abutting streets; • Driveway curb cuts for abutting prop. and public roads; • If subdivision; Names of all roads, right of way lines and easements noted; • AASHTO truck turning templates, description of minimum vehicle allowed being a WB-50 (unless otherwise approved by TAC). 	Proposed Site Plan	
<input type="checkbox"/>	<p>4. Parking and Loading: (2.5.4.3D)</p> <ul style="list-style-type: none"> • Location of off street parking/loading areas, landscaped areas/buffers; • Parking Calculations (# required and the # provided). 	Proposed Site Plan	
<input type="checkbox"/>	<p>5. Water Infrastructure: (2.5.4.3E)</p> <ul style="list-style-type: none"> • Size, type and location of water mains, shut-offs, hydrants & Engineering data; • Location of wells and monitoring wells (include protective radii). 	Utility Plan	
<input type="checkbox"/>	<p>6. Sewer Infrastructure: (2.5.4.3F)</p> <ul style="list-style-type: none"> • Size, type and location of sanitary sewage facilities & Engineering data, including any onsite temporary facilities during construction period. 	Utility Plan	


<input type="checkbox"/>	7. Utilities: (2.5.4.3G) <ul style="list-style-type: none"> The size, type and location of all above & below ground utilities; Size type and location of generator pads, transformers and other fixtures. 	Utility Plan	
<input type="checkbox"/>	8. Solid Waste Facilities: (2.5.4.3H) <ul style="list-style-type: none"> The size, type and location of solid waste facilities. 		
		City Pick Up General Notes Sheet	
<input type="checkbox"/>	9. Storm water Management: (2.5.4.3I) <ul style="list-style-type: none"> The location, elevation and layout of all storm-water drainage. The location of onsite snow storage areas and/or proposed off-site snow removal provisions. Location and containment measures for any salt storage facilities Location of proposed temporary and permanent material storage locations and distance from wetlands, water bodies, and stormwater structures. 	Grading & Drainage Plan C6	
<input type="checkbox"/>	10. Outdoor Lighting: (2.5.4.3J) <ul style="list-style-type: none"> Type and placement of all lighting (exterior of building, parking lot and any other areas of the site) and photometric plan. 	No Exterior Lighting	
<input type="checkbox"/>	11. Indicate where dark sky friendly lighting measures have been implemented. (10.1)	N/A	
<input type="checkbox"/>	12. Landscaping: (2.5.4.3K) <ul style="list-style-type: none"> Identify all undisturbed area, existing vegetation and that which is to be retained; Location of any irrigation system and water source. 	Landscape Plan	
<input type="checkbox"/>	13. Contours and Elevation: (2.5.4.3L) <ul style="list-style-type: none"> Existing/Proposed contours (2 foot minimum) and finished grade elevations. 	Grading Plan	
<input type="checkbox"/>	14. Open Space: (2.5.4.3M) <ul style="list-style-type: none"> Type, extent and location of all existing/proposed open space. 	Proposed Site Plan	
<input type="checkbox"/>	15. All easements, deed restrictions and non-public rights of ways. (2.5.4.3N)	N/A	
<input type="checkbox"/>	16. Character/Civic District (All following information shall be included): (2.5.4.3P) <ul style="list-style-type: none"> Applicable Building Height (10.5A21.20 & 10.5A43.30); Applicable Special Requirements (10.5A21.30); Proposed building form/type (10.5A43); Proposed community space (10.5A46). 	N/A	
<input type="checkbox"/>	17. Special Flood Hazard Areas (2.5.4.3Q) <ul style="list-style-type: none"> The proposed development is consistent with the need to minimize flood damage; All public utilities and facilities are located and construction to minimize or eliminate flood damage; Adequate drainage is provided so as to reduce exposure to flood hazards. 	N/A	

Other Required Information			
<input checked="" type="checkbox"/>	Required Items for Submittal	Item Location (e.g. Page/line or Plan Sheet/Note #)	Waiver Requested
<input type="checkbox"/>	Traffic Impact Study or Trip Generation Report, as required. (3.2.1-2)	Online	
<input type="checkbox"/>	Indicate where Low Impact Development Design practices have been incorporated. (7.1)	Drainage Analysis	
<input type="checkbox"/>	Indicate whether the proposed development is located in a wellhead protection or aquifer protection area. Such determination shall be approved by the Director of the Dept. of Public Works. (7.3.1)	N/A	
<input type="checkbox"/>	Stormwater Management and Erosion Control Plan. (7.4)	General Notes Sheet	
<input type="checkbox"/>	Inspection and Maintenance Plan (7.6.5)	Drainage Analysis	

Final Site Plan Approval Required Information			
<input checked="" type="checkbox"/>	Required Items for Submittal	Item Location (e.g. Page/line or Plan Sheet/Note #)	Waiver Requested
<input type="checkbox"/>	All local approvals, permits, easements and licenses required, including but not limited to: <ul style="list-style-type: none"> • Waivers; • Driveway permits; • Special exceptions; • Variances granted; • Easements; • Licenses. (2.5.3.2A)	Cover Sheet	
<input type="checkbox"/>	Exhibits, data, reports or studies that may have been required as part of the approval process, including but not limited to: <ul style="list-style-type: none"> • Calculations relating to stormwater runoff; • Information on composition and quantity of water demand and wastewater generated; • Information on air, water or land pollutants to be discharged, including standards, quantity, treatment and/or controls; • Estimates of traffic generation and counts pre- and post-construction; • Estimates of noise generation; • A Stormwater Management and Erosion Control Plan; • Endangered species and archaeological / historical studies; • Wetland and water body (coastal and inland) delineations; • Environmental impact studies. (2.5.3.2B)	Online	
<input type="checkbox"/>	A document from each of the required private utility service providers indicating approval of the proposed site plan and indicating an ability to provide all required private utilities to the site. (2.5.3.2D)	TBD	

Final Site Plan Approval Required Information

<input checked="" type="checkbox"/>	Required Items for Submittal	Item Location (e.g. Page/line or Plan Sheet/Note #)	Waiver Requested
<input type="checkbox"/>	A list of any required state and federal permit applications required for the project and the status of same. (2.5.3.2E)	Cover Sheet	
<input type="checkbox"/>	A note shall be provided on the Site Plan stating: "All conditions on this Plan shall remain in effect in perpetuity pursuant to the requirements of the Site Plan Review Regulations." (2.5.4.2E)	Proposed Site Plan	N/A
<input type="checkbox"/>	For site plans that involve land designated as "Special Flood Hazard Areas" (SFHA) by the National Flood Insurance Program (NFIP) confirmation that all necessary permits have been received from those governmental agencies from which approval is required by Federal or State law, including Section 404 of the Federal Water Pollution Control Act Amendments of 1972, 33 U.S.C. 1334. (2.5.4.2F)	N/A	
<input type="checkbox"/>	Plan sheets submitted for recording shall include the following notes: a. "This Site Plan shall be recorded in the Rockingham County Registry of Deeds." b. "All improvements shown on this Site Plan shall be constructed and maintained in accordance with the Plan by the property owner and all future property owners. No changes shall be made to this Site Plan without the express approval of the Portsmouth Planning Director." (2.13.3)	Proposed Site Plan	N/A

Applicant's Signature:  Date: 12/22/2025

August 22, 2025

To Whom It May Concern:

Please be advised that Haley Ward, Inc. is hereby authorized to act on behalf of 1151 Sagamore Avenue CBC, LLC, regarding the proposed residential development at 1151 Sagamore Avenue in Portsmouth, NH.

David Kennedy, its manager

Printed Name and Title

David Kennedy

Signature

8/22/2025

Date



CITY OF PORTSMOUTH

Planning & Sustainability
Department
1 Junkins Avenue
Portsmouth, New
Hampshire 03801
(603) 610-7216

TECHNICAL ADVISORY COMMITTEE

March 5, 2026

Sagamore Avenue CBC, LLC
76 State Street
Newburyport, Massachusetts 01950

RE: Site Plan Review approval for property located at 1151 Sagamore Avenue, Portsmouth, NH 03801 (LU-24-178)

Dear Property Owner:

The Technical Advisory Committee, at its regularly scheduled meeting of Tuesday, March 3, 2026, considered your application for Site Plan Review approval for the demolition of the existing structure and construction of four (4) standalone condominium single family structures with associated site improvements. Said property is shown on Assessor Map 224 Lot 19 and lies within the Mixed Residential Office (MRO) District. As a result of said consideration, the Committee voted to recommend approval to the Planning Board as presented.

This matter will be placed on the agenda for the Planning Board meeting scheduled for **Thursday, April 16, 2026**. One (1) hard copy of all plans and supporting reports and exhibits as well as an updated electronic file (in a PDF format) must be filed in the Planning & Sustainability Department and uploaded to the online permit system no later than **Wednesday, March 25, 2026**.

Per Section 2.5 of the Site Plan Regulations, a site plan review application to the Planning Board must include all applicable information and supporting materials including but not limited to the following items:

- *Full updated plan set*
- *Draft Easements*
- *Drainage Analysis*
- *Traffic Studies*
- *Etc.*

All comments, corrections, and conditions identified as "Items to be addressed before Planning Board submittal" must be resolved/corrected for the Planning Board application submittal to be deemed complete.

The minutes and audio recording of this meeting are available by contacting the Planning & Sustainability Department.

Very truly yours,

A handwritten signature in blue ink, appearing to read "Peter Britz", with a horizontal line extending to the right.

Peter Britz,
Planning and Sustainability Director

cc:



Property Information

Property ID 0224-0019-0000
Location 1151 SAGAMORE AVE
Owner 1151 SAGAMORE AVENUE CBC LLC




**MAP FOR REFERENCE ONLY
NOT A LEGAL DOCUMENT**

City of Portsmouth, NH makes no claims and no warranties, expressed or implied, concerning the validity or accuracy of the GIS data presented on this map.

Geometry updated 10/23/2025

Print map scale is approximate. Critical layout or measurement activities should not be done using this resource.



Property Information

Property ID 0224-0019-0000
Location 1151 SAGAMORE AVE
Owner 1151 SAGAMORE AVENUE CBC LLC



**MAP FOR REFERENCE ONLY
NOT A LEGAL DOCUMENT**

City of Portsmouth, NH makes no claims and no warranties, expressed or implied, concerning the validity or accuracy of the GIS data presented on this map.








Geometry updated 10/23/2025

Print map scale is approximate. Critical layout or measurement activities should not be done using this resource.

Map Theme Legends

Zoning

Residential Districts

	R	Rural
	SRA	Single Residence A
	SRB	Single Residence B
	GRA	General Residence A
	GRB	General Residence B
	GRC	General Residence C
	GA/MH	Garden Apartment/Mobile Home Park




Mixed Residential Districts

	MRO	Mixed Residential Office
	MRB	Mixed Residential Business
	G1	Gateway Corridor
	G2	Gateway Center





Business Districts

	GB	General Business
	B	Business
	WB	Waterfront Business



Industrial Districts

	OR	Office Research
	I	Industrial
	WI	Waterfront Industrial






Airport Districts

	AIR	Airport
	AI	Airport Industrial
	PI	Pease Industrial
	ABC	Airport Business Commercial


Conservation Districts

	M	Municipal
	NRP	Natural Resource Protection


Character Districts

	CD5	Character District 5
	CD4	Character District 4
	CD4W	Character District 4-W
	CD4-L1	Character District 4-L1
	CD4-L2	Character District 4-L2




Civic District

	Civic District
---	----------------

Municipal District

	Municipal District
---	--------------------

Overlay Districts

	OLOD	Osprey Landing Overlay District
	Downtown Overlay District	
	Historic District	

City of Portsmouth



**1151 Sagamore Ave, Portsmouth NH
Traffic Analysis**

Introduction

The Applicant, 1151 Sagamore Avenue CBC LLC, is proposing to develop a 4-unit residential development, consisting of 4 single-family units under a condominium agreement. This project was historically occupied by one single family dwelling, which was demolished in October 2025. This property is currently accessed from an existing driveway entrance on Sagamore Avenue. Because the development will alter the location and use of the driveway, a Driveway Permit from the NHDOT is required. In support of Applicant's application for a Site Plan permit, the following Preliminary Traffic Analysis has been provided. Please note that the Applicant submitted a Driveway Entrance Permit application to the NHDOT on November 5, 2025 containing this analysis.

Trip Generation

Trip Generation for the site has been calculated using the Institute of Transportation Engineer's (ITE) publication, Trip Generation, 12th Edition, the most recent edition accepted by NHDOT. The proposed development will include 4 single family dwelling units. After reviewing the Land Use Codes (LUCs) providing the ITE 12th Edition, the following was selected to calculate the trip generation for the existing and proposed uses:

- LUC 210 – Single Family Detached Housing

In calculating trip generation, standard methodology includes review of both the average rate and the fitted curve equation. If $R^2 \geq 0.80$, then the fitted curve equation is typically used, and if $R^2 < 0.80$, then the average rate is typically used. For this project, the R^2 value is 0.94, so the fitted rate is used. Trip generation calculations are provided in the Appendix of this Memo.

The following Table 1 summarizes the trip generation for the proposed HVAC office/warehouse.

Table 1 – Trip Generation Proposed (LUC 210 – 4 single-family dwelling units)

Time Period	Trip Generation	
	Trip Gen Rates	Trip Generation
Weekday	9.09	36
AM Peak Hour of Adjacent Street	0.70	8
PM Peak Hour of Adjacent Street	0.93	5
AM Peak Hour Generator	0.75	12
PM Peak Hour Generator	0.97	6

Conclusion

As shown on the tables above, the number of peak hour trips for the proposed site is 12 for the AM Peak Hour Generator. Per the NHDOT's "Traffic Impact Documentation Guidance," document, because the peak hour trips generated is between 11 and 100, this project is classified as a "Major Driveway." The Applicant will continue working with the NHDOT to provide additional materials as required to support this Traffic Impact Study.

Land Use: 210

Single-Family Detached Housing

Description

A single-family detached housing site includes any single-family detached home on an individual lot. A typical site surveyed is a suburban subdivision.

Specialized Land Use

Data have been submitted for several single-family detached housing developments with homes that are commonly referred to as patio homes. A patio home is a detached housing unit that is located on a small lot with little (or no) front or back yard. In some subdivisions, communal maintenance of outside grounds is provided for the patio homes. The three patio home sites total 299 dwelling units with overall weighted average trip generation rates of 5.35 vehicle trips per dwelling unit for weekday, 0.26 for the AM adjacent street peak hour, and 0.47 for the PM adjacent street peak hour. These patio home rates, based on a small sample of sites, are lower than those for single-family detached housing (Land Use 210), lower than those for single-family attached housing (Land Use 215), and higher than those for senior adult housing—single-family (Land Use 251). (Source 1008)

Additional Data

The sites were surveyed in the 1990s, the 2000s, the 2010s, and the 2020s in Alabama, Arizona, British Columbia (CAN), California, Delaware, Illinois, Kentucky, Massachusetts, Minnesota, Montana, New Jersey, New York, North Carolina, Ontario (CAN), Oregon, Pennsylvania, South Carolina, South Dakota, Vermont, and West Virginia.

Source Numbers

356, 357, 367, 384, 387, 407, 435, 522, 550, 552, 579, 598, 601, 603, 614, 637, 711, 716, 720, 728, 735, 868, 869, 903, 925, 936, 1005, 1007, 1008, 1010, 1033, 1066, 1077, 1078, 1079, 1204, 1221, 1225, 1236, 1251, 1265, 1267

Single-Family Detached Housing (210)

Vehicle Trip Ends vs: Dwelling Units
On a: Weekday

Setting/Location: General Urban/Suburban

Number of Studies: 155


Avg. Num. of Dwelling Units: 261

Directional Distribution: 50% entering, 50% exiting

Vehicle Trip Generation per Dwelling Unit

Average Rate	Range of Rates	Standard Deviation
9.09	3.47 - 23.80	2.29

Data Plot and Equation



Single-Family Detached Housing (210)

Vehicle Trip Ends vs: Dwelling Units

On a: Weekday,

Peak Hour of Adjacent Street Traffic,
One Hour Between 7 and 9 a.m.

Setting/Location: General Urban/Suburban

Number of Studies: 153


Avg. Num. of Dwelling Units: 239

Directional Distribution: 27% entering, 73% exiting

Vehicle Trip Generation per Dwelling Unit

Average Rate	Range of Rates	Standard Deviation
0.70	0.22 - 2.27	0.26

Data Plot and Equation



Single-Family Detached Housing (210)

Vehicle Trip Ends vs: Dwelling Units

**On a: Weekday,
Peak Hour of Adjacent Street Traffic,
One Hour Between 4 and 6 p.m.**

Setting/Location: General Urban/Suburban

Number of Studies: 166


Avg. Num. of Dwelling Units: 266

Directional Distribution: 62% entering, 38% exiting

Vehicle Trip Generation per Dwelling Unit

Average Rate	Range of Rates	Standard Deviation
0.93	0.35 - 2.98	0.33

Data Plot and Equation



Single-Family Detached Housing (210)

Vehicle Trip Ends vs: Dwelling Units

On a: Weekday,
AM Peak Hour of Generator

Setting/Location: General Urban/Suburban

Number of Studies: 132


Avg. Num. of Dwelling Units: 232

Directional Distribution: 27% entering, 73% exiting

Vehicle Trip Generation per Dwelling Unit

Average Rate	Range of Rates	Standard Deviation
0.75	0.32 - 2.27	0.26

Data Plot and Equation



Single-Family Detached Housing (210)

Vehicle Trip Ends vs: Dwelling Units

On a: Weekday,
PM Peak Hour of Generator

Setting/Location: General Urban/Suburban

Number of Studies: 138


Avg. Num. of Dwelling Units: 214

Directional Distribution: 63% entering, 37% exiting

Vehicle Trip Generation per Dwelling Unit

Average Rate	Range of Rates	Standard Deviation
0.97	0.49 - 2.98	0.32

Data Plot and Equation



Single-Family Detached Housing (210)

Vehicle Trip Ends vs: Dwelling Units
On a: Saturday

Setting/Location: General Urban/Suburban

Number of Studies: 42


Avg. Num. of Dwelling Units: 159

Directional Distribution: 50% entering, 50% exiting

Vehicle Trip Generation per Dwelling Unit

Average Rate	Range of Rates	Standard Deviation
9.03	3.36 - 28.90	2.51

Data Plot and Equation



Single-Family Detached Housing (210)

Vehicle Trip Ends vs: Dwelling Units

On a: Saturday, Peak Hour of Generator

Setting/Location: General Urban/Suburban

Number of Studies: 33


Avg. Num. of Dwelling Units: 106

Directional Distribution: 53% entering, 47% exiting

Vehicle Trip Generation per Dwelling Unit

Average Rate	Range of Rates	Standard Deviation
1.00	0.41 - 2.90	0.36

Data Plot and Equation



Single-Family Detached Housing (210)


Vehicle Trip Ends vs: Dwelling Units
On a: Sunday

Setting/Location: General Urban/Suburban
Number of Studies: 38
Avg. Num. of Dwelling Units: 172
Directional Distribution: 50% entering, 50% exiting

Vehicle Trip Generation per Dwelling Unit

Average Rate	Range of Rates	Standard Deviation
8.43	2.61 - 16.44	1.73

Data Plot and Equation



Single-Family Detached Housing (210)

Vehicle Trip Ends vs: Dwelling Units

On a: Sunday, Peak Hour of Generator

Setting/Location: General Urban/Suburban

Number of Studies: 26


Avg. Num. of Dwelling Units: 130

Directional Distribution: 53% entering, 47% exiting

Vehicle Trip Generation per Dwelling Unit

Average Rate	Range of Rates	Standard Deviation
0.91	0.36 - 2.15	0.23

Data Plot and Equation



Single-Family Detached Housing (210)


Vehicle Trip Ends vs: Residents
On a: Weekday

Setting/Location: General Urban/Suburban
Number of Studies: 30
Avg. Num. of Residents: 810
Directional Distribution: 50% entering, 50% exiting

Vehicle Trip Generation per Resident

Average Rate	Range of Rates	Standard Deviation
2.65	1.56 - 5.62	0.64

Data Plot and Equation



Single-Family Detached Housing (210)

Vehicle Trip Ends vs: Residents

On a: Weekday,

Peak Hour of Adjacent Street Traffic,
One Hour Between 7 and 9 a.m.

Setting/Location: General Urban/Suburban

Number of Studies: 21


Avg. Num. of Residents: 1100

Directional Distribution: 31% entering, 69% exiting

Vehicle Trip Generation per Resident

Average Rate	Range of Rates	Standard Deviation
0.21	0.12 - 0.42	0.08

Data Plot and Equation



Single-Family Detached Housing (210)

Vehicle Trip Ends vs: Residents

On a: Weekday,

Peak Hour of Adjacent Street Traffic,
One Hour Between 4 and 6 p.m.

Setting/Location: General Urban/Suburban

Number of Studies: 21


Avg. Num. of Residents: 1083

Directional Distribution: 66% entering, 34% exiting

Vehicle Trip Generation per Resident

Average Rate	Range of Rates	Standard Deviation
0.28	0.12 - 0.60	0.08

Data Plot and Equation



Single-Family Detached Housing (210)

Vehicle Trip Ends vs: Residents

On a: Weekday,

AM Peak Hour of Generator

Setting/Location: General Urban/Suburban

Number of Studies: 22


Avg. Num. of Residents: 1073

Directional Distribution: 30% entering, 70% exiting

Vehicle Trip Generation per Resident

Average Rate	Range of Rates	Standard Deviation
0.21	0.12 - 0.42	0.08

Data Plot and Equation



Single-Family Detached Housing (210)

Vehicle Trip Ends vs: Residents

On a: Weekday,

PM Peak Hour of Generator

Setting/Location: General Urban/Suburban

Number of Studies: 21


Avg. Num. of Residents: 1083

Directional Distribution: 66% entering, 34% exiting

Vehicle Trip Generation per Resident

Average Rate	Range of Rates	Standard Deviation
0.28	0.12 - 0.60	0.08

Data Plot and Equation



Single-Family Detached Housing (210)


Vehicle Trip Ends vs: Residents
On a: Saturday

Setting/Location: General Urban/Suburban
Number of Studies: 14
Avg. Num. of Residents: 1085
Directional Distribution: 50% entering, 50% exiting

Vehicle Trip Generation per Resident

Average Rate	Range of Rates	Standard Deviation
2.48	1.43 - 3.63	0.46

Data Plot and Equation



Single-Family Detached Housing (210)

Vehicle Trip Ends vs: Residents

On a: Saturday, Peak Hour of Generator

Setting/Location: General Urban/Suburban

Number of Studies: 11


Avg. Num. of Residents: 875

Directional Distribution: 54% entering, 46% exiting

Vehicle Trip Generation per Resident

Average Rate	Range of Rates	Standard Deviation
0.27	0.19 - 0.41	0.08

Data Plot and Equation



Single-Family Detached Housing (210)

Vehicle Trip Ends vs: Residents

On a: Sunday

Setting/Location: General Urban/Suburban

Number of Studies: 14


Avg. Num. of Residents: 1085

Directional Distribution: 50% entering, 50% exiting

Vehicle Trip Generation per Resident

Average Rate	Range of Rates	Standard Deviation
2.42	1.62 - 3.16	0.43

Data Plot and Equation



Single-Family Detached Housing (210)

Vehicle Trip Ends vs: Residents

On a: Sunday, Peak Hour of Generator

Setting/Location: General Urban/Suburban

Number of Studies: 12


Avg. Num. of Residents: 870

Directional Distribution: 50% entering, 50% exiting

Vehicle Trip Generation per Resident

Average Rate	Range of Rates	Standard Deviation
0.25	0.19 - 0.35	0.05

Data Plot and Equation





Environment One Corporation

Pressure Sewer Preliminary

Cost and Design Analysis

For

1151 Sagamore Ave

Portsmouth, NH

Prepared For:

Drew Olehowski Haley Ward

120 Main St Suite 132

Saco ME 04072

Tel: 207-576-6488

Fax:

Prepared By: D.Coppola

February 11, 2026

PRELIMINARY PRESSURE SEWER - PIPE SIZING AND BRANCH ANALYSIS

Prepared By:
D.Coppola

1151 Sagamore Ave
Portsmouth, NH

February 11, 2026

Zone Number	Connects to Zone	Number of Pumps in Zone	Accum Pumps in Zone	Gals/day per Pump	Max Flow Per Pump (gpm)	Max Sim Ops	Max Flow (GPM)	Pipe Size (inches)	Max Velocity (FPS)	Length of Main this Zone	Friction Loss Factor (ft/100 ft)	Friction Loss This Zone	Accum Fric Loss (feet)	Max Main Elevation	Minimum Pump Elevation	Static Head (feet)	Total Dynamic Head (ft)
This spreadsheet was calculated using pipe diameters for: SDR11HDPE								Friction loss calculations were based on a Constant for inside roughness "C" of:								150	
1.00	1.00	4	4	200	11.00	3	33.00	1.25	7.31	274.00	14.40	39.46	39.46	32.00	28.00	4.00	43.46

Note: This analysis is valid only with the use of progressive cavity type grinder pumps as manufactured by Environment One.

PRELIMINARY PRESSURE SEWER - ACCUMULATED RETENTION TIME (HR)

Prepared By:
D.Coppola

1151 Sagamore Ave
Portsmouth, NH

February 11, 2026

Zone Number	Connects to Zone	Accumulated Total of Pumps this Zone	Pipe Size (inches)	Gallons per 100 lineal feet	Length of Zone	Capacity of Zone	Average Daily Flow	Average Fluid Changes per Day	Average Retention Time (Hr)	Accumulated Retention Time (Hr)	
This spreadsheet was calculated using pipe diameters for			SDR11HDPE							Gals per Day per Dwelling	200
1.00	1.00	4	1.25	7.52	274.00	20.61	800	38.81	0.62	0.62	

"Green" Building Statement, 1155 Sagamore Ave., Portsmouth

Location and Transportation

Walkable Destinations: 1155 Sagamore is two miles from Wentworth-By-The-Sea, two miles from downtown Portsmouth, and less than one mile to the Rye border and the Atlantic Grill.

Bicycles: This area is a frequently used bicycle traffic route to beaches, downtown amenities, other points north and south and other popular locations. Hanging bicycle storage is provided within each garage space.

Ride sharing: Although this location is not serviced directly by public transportation, it enjoys easy access and is a quickly identifiable address for cabs or shared transportation services.

Site

Stormwater: Stormwater will be collected and treated in a proposed Rain Garden before discharge from the property. This Rain Garden provides advanced stormwater treatment where no treatment is currently provided.

Reuse: This site requires demolition of an outdated and underutilized structure. The new 4-unit townhouse structure will better utilize this location with a modern design, defined parking areas, non-polluting HVAC systems, and elimination of an existing multi-unit septic disposal system.

Landscaping: A professionally produced landscaping plan includes shrubbery, grass, and a multitude of trees that currently do not exist. An irrigation system to maintain grass and plantings is included.

Zoning: This project meets requirements in the MRO zone where it is located. No variances have been requested.

Utilities and fire protection

Water: All new water-saving plumbing fixtures will be installed as per the current plumbing code. Frost-free outside water taps are included at each living unit.

Sewer: The existing septic system is being replaced by a common E-one grinder/ejector system connected to the public sewer.

Electric: Eversource has indicated they will be installing a new transformer to service this property. All connections from the pole to this transformer and transformer to the electric meter bank will be underground. The current electric service is overhead. The transformer will be partially screened with landscaping.

Fire Protection: A fire suppression system governed by requirements of NFPA 13 will be installed in each townhouse. Additionally, full foundation to ridge firewalls will be installed between living units.

Gas or heating oil: None.

Energy:

Heating and Air Conditioning: HVAC will be via either air-source or ground-source (geothermal) heat pump. No natural gas, propane gas or heating oil facilities are included in this design. No exhaust flues are required, nor greenhouse gases emitted. Further, the potential for carbon monoxide poisoning from a malfunctioning heating system is eliminated.

Insulation: The heated envelope will be insulated with spray-foam insulation to maximize insulation R-values, minimize air penetration and minimize acoustic noise from outdoors and between living units.

Lighting: LED lighting will be used throughout.

Kitchen Appliances: All kitchen appliances will be energy-star certified.

Fenestration: Very substantial windows and doors are state-of-the-art and shall have a U-value below .30, meeting or exceeding energy-star requirements.



STORMWATER MANAGEMENT AND EROSION CONTROL PLAN

**TO THE CITY OF PORTSMOUTH
FOR 1151 SAGAMORE AVENUE**
Map 224, Lot 19 | Portsmouth, NH

APPLICANT:
1151 Sagamore Avenue CBC LLC
76 State Street, Newburyport, ME 01950

February 17, 2026
JN: 5010314.002

REPORT PREPARED BY:
Haley Ward, Inc.
200 Griffin Road, Unit 14 | Portsmouth, NH 03801



EXECUTIVE SUMMARY

This drainage analysis examines the pre-development (existing) and post-development (proposed) stormwater drainage patterns for the proposed residential redevelopment project at 1151 Sagamore Avenue in Portsmouth, NH. The site is shown on the City of Portsmouth Assessor's Tax Map 224 as Lot 19. The project proposes to replace an existing building with four (4) single family condominiums. The total size of the lot is 30,191 square-feet (0.69 acres). The size of the total drainage area is 67,213 square-feet (1.53 acres).

The development will provide for the construction of four (4) standalone condominium units, with associated landscaping, utilities, and driveways. The new buildings will be serviced by public water and sewer. The development has the potential to increase stormwater runoff to adjacent properties and therefore must be designed in a manner to prevent that occurrence. This will be done primarily by capturing stormwater runoff and routing it through appropriate stormwater facilities, designed to ensure that there will be no significant increase in peak runoff from the site as a result of this project.

The hydrologic modeling utilized for this analysis uses the "Extreme Precipitation" values for rainfall from The Northeast Regional Climate Center (Cornell University), with a 15% increase to comply with local ordinance.

INTRODUCTION / PROJECT DESCRIPTION

This drainage report is designed to assist the owner, planning board, contractor, regulatory reviewer, and others in understanding the impact of the proposed development project on local surface water runoff and quality. The project site is shown on the City of Portsmouth, NH Assessor's Tax Map 224 as Lot 19. Bounding the site to north is Wentworth Road. Bounding the site to east is Sagamore Avenue. Bounding the site to south is a condominium complex. Bounding the site to the west is a City owned conservation land.

The property is situated in the Mixed Residential Office Zone. A vicinity map is included in the Appendix to this report. The proposed building replacement will demolish an existing building and associated driveway.

This report includes information about the existing site necessary to analyze stormwater runoff and to design any required mitigation. The report includes maps of pre- development and post-development watersheds, subcatchment areas and calculations of runoff. The report will provide a narrative of the stormwater runoff and describe numerically and graphically the surface water runoff patterns



for this site. Proposed stormwater management and treatment structures and methods will also be described, as well as erosion and sediment control practices. To fully understand the proposed site development the reader should also review a complete site plan set in addition to this report.

METHODOLOGY

“Extreme Precipitation” values from The Northeast Regional Climate Center (Cornell University) have been used for modeling purposes. These values have been used in this analysis, with a 15% addition to comply with local ordinances.

This report uses the US Soil Conservation Service (SCS) Method for estimating stormwater runoff. The SCS method is published in The National Engineering Handbook (NEH), Section 4 “Hydrology” and includes the Technical Release No. 20, (TR-20) “Computer Program for Project Formulation Hydrology”, and Technical Release No. 55 (TR-55) “Urban Hydrology for Small Watersheds” methods. This report uses the HydroCAD version 10.20 program, written by HydroCAD Software Solutions LLC, Chocorua, N.H., to apply these methods for the calculation of runoff and for pond modeling. Rainfall data and runoff curve numbers are taken from “The Stormwater Management and Erosion Control Handbook for Urban and Developing Areas in New Hampshire.”

Time of Concentration (T_c) is calculated by entering measured flow path data such as flow path type, length, slope and surface characteristics into the HydroCAD program. For the purposes of this report, a minimum time of concentration of 5 minutes is used.

The storm events used for the calculations in this report are the 2-year, 10-year, 25-year, and 50-year (24-hour) storms. Watershed basin boundaries have been delineated using topographic maps prepared by Haley Ward and field observations to confirm.

SITE SPECIFIC INFORMATION

Based on the United States Department of Agriculture (USDA) Natural Resources Conservation Service (NRCS), Soil Survey of Rockingham County, New Hampshire the site is made up of one soil type:

Soil Symbol	Soil Name and Slopes
140B	Chatfield-Hollis-Canton complex (0-8% slopes), rocky

Chatfield-Hollis-Canton complex is well drained with a stated depth to restrictive feature of 20-41 inches.



One test pit was dug on the site in the location of the proposed Rain Garden. A restrictive ledge layer was identified at 41-inches. The seasonal high-water table was identified at approximately 18" depth, or elevation 27-feet. The soil is described as fine, sandy loam, granular, friable, fill.

The physical characteristics of the site consist of flat (0-8%) grades that generally slope downward from the south to the north of the lot. Elevations on the site range from 30 to 35 feet above sea level. The existing site is developed and includes an existing building located in the front of the lot, with an asphalt driveway. Vegetation around the developed portion of the lot consists of established grasses, shrubs, and trees.

There are no protected natural resources on or directly adjacent to the subject property.

According to the Federal Emergency Management Agency (FEMA) Flood Insurance Rate Map (FIRM) number 33015C0286F (effective date January 29, 2021), the project site is located in Zone X and is determined to be outside of the 0.2% annual chance floodplain. A copy of the FIRM map is included in the Appendix.

CONSTRUCTION TIMING

Development of the site has been ongoing throughout 2025; completed activities include blasting/excavation to bring the site to foundation grade, and the existing home has already been demolished. Construction of the proposed development is anticipated to begin in Spring 2026, pending receipt of required land use permits. Prior to further earth moving activities, the site will be stabilized via the proposed erosion control devices as shown on the Site Plan. These devices will not be removed until the site has been stabilized via permanent vegetation, which is expected to occur in Fall/Winter 2026.

LOW-IMPACT DEVELOPMENT STATEMENT

The proposed developed utilized Low-Impact Development to the greatest extent practical. Primarily, runoff generated from the proposed driveway and building roofs is directed to a Rain Garden which has been designed per the New Hampshire Stormwater Manual. Impervious areas have been minimized by including garages within the proposed buildings, eliminating the need for additional outdoor parking spaces.



BUFFERS, SETBACKS, EXISTING FEATURES

The site will adhere to the applicable setbacks found within the City zoning ordinance. There are no setbacks related to protected natural resources. The site is not within a mapped floodplain. There are mature trees between the subject parcel and the abutting property to the south which will be protected as deemed practical. There are no known water quality concerns associated with this site.

WASTE

The majority of the site preparation, including demolition of the existing building, has already been completed at the time of this application's submission. Additional construction debris will be collected in a dumpster and will be disposed of off-site by a licensed hauler. Solid waste and wastewater generated by the proposed residential units will be handled via public systems.

PRE-DEVELOPMENT DRAINAGE

In the pre-development condition, the site has been analyzed as three (3) subcatchment watershed basins based on localized topography and discharge location. A Pre-Development Hydrology map and HydroCAD model results have been provided.

Subcatchment 1 (1S) represents the majority of the subject property area, as well as offsite area to the north, which drains towards the center of the site where runoff is detained in a local low point. Runoff in this detention area has been observed to infiltrate; no pooling of water has been documented. While the majority of runoff entering this area is discarded via infiltration, any overflow is directed to the southwest corner of the site (Summation Point 1.)

Subcatchment 2 (2S) represents the front of the subject property, as well as a portion of the abutting 1151 Sagamore Avenue property to the south. This area drains to the northeast corner of the site where it is discharged to the Sagamore Avenue Public ROW (Summation Point 2, SP2)

POST-DEVELOPMENT DRAINAGE

The proposed development has been designed to match the pre-development drainage patterns to the greatest extent feasible. In the post-development condition, the site has been analyzed as eight (8) subcatchment basins. A Post-Development Hydrology map and HydroCAD model results have been provided.

Subcatchment 1 (1S) continues to represent the area to the north of the site. This drainage area will be intercepted by an infiltration trench to be located on the



north side of the proposed buildings. This trench has been designed to detain and infiltrate runoff from the 50-year storm event. This trench is equipped with underdrain pipe and several manholes for maintenance access. In the event that this trench were to fail, runoff will be directed to the rain garden.

Subcatchment 2 (2S) continues to represent the front of the lot and the adjacent 1155 Sagamore Avenue property. Runoff in this area will continue to be directed to the northeast corner of the lot, Summation Point 2.

Subcatchment 3 (3S) represents the proposed driveway and landscaped areas. Runoff within this subcatchment will be directed as overland flow to a proposed rain garden at the rear of the site. This rain garden will release controlled flow to a subsurface detention system located beneath the proposed driveway.

Subcatchments 4,5,6, and 7 (4S, 5S, 6S, 7S) represent the roof areas of the four proposed buildings. These units will be equipped with gutters and downspouts which will direct their runoff to the proposed rain garden.

Subcatchment 8 (8S) represents a portion of the 1155 Sagamore Avenue property, as well as offsite area to the west. Runoff from this offsite area cannot be feasibly captured by the proposed onsite stormwater infrastructure and is therefore the source of the minor post-development peak runoff rate increase, as identified below.

RUNOFF COMPARISON

Table 1: Pre-Development to Post-Development Comparison

Design Point	Q2 (CFS)		Q10 (CFS)		Q25(CFS)		Q50 (CFS)		Description
	Pre	Post	Pre	Post	Pre	Post	Pre	Post	
SP1	0.00	0.05	0.00	0.16	0.00	0.27	0.00	0.38	Southwest corner of property
SP2	0.38	0.38	0.87	0.78	1.30	1.13	1.71	1.46	Sagamore Ave ROW

As shown in Table 1, post-development runoff rates are similar to those observed under pre-development conditions. The minor increases observed at Summation Point 1 are due to runoff from the offsite areas (Subcatchment 8) that cannot be feasibly detained by the proposed onsite detention features. These increases of less than one half CFS are not expected to have a significant impact on downstream properties.



OFFSITE INFRASTRUCTURE CAPACITY

There is no Town infrastructure utilized in this project in regard to storm drainage. All retention and routing to the final destination of the stormwater is done on-site, therefore no impact to city infrastructure is anticipated.

EROSION AND SEDIMENT CONTROL PRACTICES

The erosion potential for this site as it exists is moderate due to the presence of soils that are highly erodible. During construction, the major potential for erosion is wind and stormwater runoff. The contractor will be required to inspect and maintain all necessary erosion control measures, as well as installing any additional measures as required. All erosion control practices shall conform to "The Stormwater Management and Erosion Control Handbook for Urban and Developing Areas in New Hampshire." Some examples of erosion and sediment control measures to be utilized for this project during construction may include:

- Silt Soxx (or approved alternative) located at the toe of disturbed slopes
- Stabilized construction entrance at access point to the site
- Temporary mulching and seeding for disturbed areas
- Spraying water over disturbed areas to minimize wind erosion

After construction, permanent stabilization will be accomplished by permanent seeding, landscaping, and surfacing the access drives and parking areas with asphalt paving and other areas with impervious walkways.

CONCLUSION

The proposed development has been designed to match the pre-development drainage patterns to the greatest extent feasible. With the design of the rain garden, the post-development runoff rates are effectively equivalent to the pre-development runoff rates. Erosion and sediment control practices will be implemented for both the temporary condition during construction and for final stabilization after construction. Therefore, there are no negative impacts to downstream receptors or adjacent properties anticipated as a result of this project.



REFERENCES

1. Comprehensive Environmental Inc. and New Hampshire Department of Environmental Services. *New Hampshire Stormwater Manual (Volumes 1, 2 and 3)*, December 2008 (Revision 1.0).
2. Minnick, E.L. and H.T. Marshall. *Stormwater Management and Erosion and Sediment Control Handbook for Urban and Developing Areas in New Hampshire*, prepared by Rockingham County Conservation District, prepared for New Hampshire Department of Environmental Services, in cooperation with USDA Soil Conservation Service, August 1992.
3. HydroCAD Software Solution, LLC. *HydroCAD Stormwater Modeling System Version 10.20* copyright 2013.



Property Information

Property ID 0224-0019-0000
Location 1151 SAGAMORE AVE
Owner 1151 SAGAMORE AVENUE CBC LLC



**MAP FOR REFERENCE ONLY
NOT A LEGAL DOCUMENT**

City of Portsmouth, NH makes no claims and no warranties, expressed or implied, concerning the validity or accuracy of the GIS data presented on this map.

Geometry updated 10/23/2025

Print map scale is approximate. Critical layout or measurement activities should not be done using this resource.

Extreme Precipitation Tables

Northeast Regional Climate Center

Data represents point estimates calculated from partial duration series. All precipitation amounts are displayed in inches.

Metadata for Point	
Smoothing State	Yes
Location	
Latitude	43.052 degrees North
Longitude	70.748 degrees West
Elevation	10 feet
Date/Time	Fri Aug 25 2023 11:03:42 GMT-0400 (Eastern Daylight Time)

Extreme Precipitation Estimates

	5min	10min	15min	30min	60min	120min		1hr	2hr	3hr	6hr	12hr	24hr	48hr		1day	2day	4day	7day	10day	
1yr	0.26	0.40	0.50	0.65	0.82	1.04	1yr	0.70	0.98	1.21	1.56	2.03	2.67	2.94	1yr	2.36	2.82	3.24	3.96	4.57	1yr
2yr	0.32	0.50	0.62	0.82	1.03	1.30	2yr	0.89	1.18	1.52	1.94	2.49	3.22	3.58	2yr	2.85	3.45	3.95	4.70	5.35	2yr
5yr	0.37	0.58	0.73	0.98	1.25	1.61	5yr	1.08	1.47	1.89	2.44	3.15	4.08	4.60	5yr	3.61	4.42	5.07	5.96	6.73	5yr
10yr	0.41	0.65	0.82	1.12	1.46	1.90	10yr	1.26	1.73	2.24	2.91	3.76	4.88	5.55	10yr	4.32	5.34	6.12	7.14	8.01	10yr
25yr	0.48	0.77	0.97	1.34	1.78	2.35	25yr	1.54	2.15	2.79	3.65	4.76	6.19	7.13	25yr	5.48	6.85	7.85	9.07	10.09	25yr
50yr	0.54	0.87	1.11	1.55	2.09	2.78	50yr	1.80	2.54	3.31	4.35	5.69	7.42	8.62	50yr	6.56	8.29	9.48	10.87	12.02	50yr
100yr	0.60	0.98	1.26	1.79	2.44	3.28	100yr	2.10	3.00	3.93	5.19	6.80	8.88	10.42	100yr	7.86	10.02	11.46	13.03	14.33	100yr
200yr	0.68	1.11	1.44	2.07	2.85	3.87	200yr	2.46	3.54	4.66	6.17	8.12	10.65	12.60	200yr	9.42	12.11	13.85	15.63	17.08	200yr
500yr	0.81	1.33	1.73	2.51	3.52	4.81	500yr	3.03	4.42	5.82	7.76	10.28	13.53	16.20	500yr	11.97	15.58	17.81	19.89	21.57	500yr




Lower Confidence Limits

	5min	10min	15min	30min	60min	120min		1hr	2hr	3hr	6hr	12hr	24hr	48hr		1day	2day	4day	7day	10day	
1yr	0.23	0.36	0.44	0.59	0.72	0.88	1yr	0.62	0.86	0.93	1.34	1.69	2.26	2.50	1yr	2.00	2.41	2.88	3.21	3.94	1yr
2yr	0.31	0.49	0.60	0.81	1.00	1.19	2yr	0.86	1.16	1.37	1.81	2.33	3.07	3.47	2yr	2.72	3.33	3.84	4.56	5.11	2yr
5yr	0.35	0.54	0.67	0.92	1.17	1.40	5yr	1.01	1.37	1.61	2.11	2.72	3.80	4.20	5yr	3.36	4.04	4.74	5.56	6.26	5yr
10yr	0.39	0.59	0.74	1.03	1.33	1.60	10yr	1.15	1.57	1.80	2.38	3.05	4.38	4.88	10yr	3.88	4.69	5.47	6.44	7.22	10yr
25yr	0.44	0.67	0.83	1.19	1.56	1.90	25yr	1.35	1.86	2.10	2.74	3.52	4.78	5.91	25yr	4.23	5.68	6.69	7.83	8.72	25yr
50yr	0.48	0.73	0.91	1.31	1.77	2.17	50yr	1.53	2.12	2.35	3.05	3.91	5.41	6.82	50yr	4.79	6.56	7.77	9.10	10.06	50yr
100yr	0.54	0.81	1.02	1.47	2.02	2.47	100yr	1.74	2.41	2.63	3.39	4.31	6.10	7.87	100yr	5.40	7.57	9.04	10.58	11.63	100yr
200yr	0.59	0.89	1.13	1.64	2.28	2.81	200yr	1.97	2.75	2.94	3.74	4.74	6.86	9.09	200yr	6.07	8.74	10.50	12.32	13.45	200yr
500yr	0.69	1.02	1.31	1.91	2.72	3.36	500yr	2.34	3.29	3.42	4.26	5.39	8.01	10.98	500yr	7.09	10.56	12.80	15.09	16.30	500yr

Upper Confidence Limits

	5min	10min	15min	30min	60min	120min		1hr	2hr	3hr	6hr	12hr	24hr	48hr		1day	2day	4day	7day	10day	
1yr	0.29	0.44	0.54	0.72	0.89	1.09	1yr	0.77	1.06	1.26	1.74	2.20	2.98	3.18	1yr	2.64	3.06	3.59	4.38	5.05	1yr
2yr	0.34	0.52	0.64	0.87	1.07	1.27	2yr	0.92	1.24	1.48	1.96	2.52	3.43	3.72	2yr	3.03	3.58	4.11	4.86	5.64	2yr
5yr	0.40	0.62	0.77	1.05	1.34	1.63	5yr	1.16	1.59	1.89	2.54	3.26	4.36	4.98	5yr	3.85	4.79	5.40	6.40	7.18	5yr
10yr	0.47	0.72	0.89	1.25	1.62	1.99	10yr	1.39	1.94	2.29	3.11	3.97	5.36	6.23	10yr	4.74	5.99	6.85	7.87	8.79	10yr
25yr	0.58	0.88	1.10	1.57	2.06	2.59	25yr	1.78	2.53	2.97	4.08	5.18	7.75	8.38	25yr	6.86	8.05	9.20	10.38	11.45	25yr
50yr	0.68	1.03	1.28	1.84	2.48	3.15	50yr	2.14	3.08	3.61	5.02	6.36	9.69	10.50	50yr	8.57	10.10	11.51	12.78	14.01	50yr
100yr	0.80	1.20	1.51	2.18	2.99	3.84	100yr	2.58	3.76	4.40	6.19	7.83	12.11	13.16	100yr	10.71	12.65	14.40	15.76	17.15	100yr
200yr	0.93	1.41	1.78	2.58	3.60	4.70	200yr	3.10	4.59	5.37	7.63	9.63	15.17	16.51	200yr	13.43	15.87	18.04	19.43	20.98	200yr
500yr	1.16	1.73	2.22	3.23	4.59	6.11	500yr	3.96	5.97	6.97	10.10	12.71	20.46	22.28	500yr	18.11	21.43	24.31	25.62	27.41	500yr





Pre Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 2-yr Rainfall=3.70"

Printed 2/13/2026

Page 2

Time span=5.00-24.00 hrs, dt=0.05 hrs, 381 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment1S: SUBCATCHMENT1 Runoff Area=47,354 sf 10.22% Impervious Runoff Depth>0.66"
Flow Length=100' Slope=0.0800 '/' Tc=13.4 min CN=61 Runoff=0.50 cfs 0.060 af

Subcatchment2S: SUBCATCHMENT2 Runoff Area=12,579 sf 27.43% Impervious Runoff Depth>1.19"
Tc=5.0 min CN=71 Runoff=0.38 cfs 0.029 af

Reach SP1: SUMMATIONPOINT 1 Inflow=0.00 cfs 0.000 af
Outflow=0.00 cfs 0.000 af

Reach SP2: SUMMATIONPOINT 2 Inflow=0.38 cfs 0.029 af
Outflow=0.38 cfs 0.029 af

Pond 2P: Existing "detention" area Peak Elev=27.60' Storage=704 cf Inflow=0.50 cfs 0.060 af
Discarded=0.12 cfs 0.060 af Primary=0.00 cfs 0.000 af Outflow=0.12 cfs 0.060 af

Total Runoff Area = 1.376 ac Runoff Volume = 0.089 af Average Runoff Depth = 0.77"
86.16% Pervious = 1.186 ac 13.84% Impervious = 0.190 ac

Pre Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 2-yr Rainfall=3.70"

Printed 2/13/2026

Page 3

Summary for Subcatchment 1S: SUBCATCHMENT 1


Runoff = 0.50 cfs @ 12.23 hrs, Volume= 0.060 af, Depth> 0.66"

Routed to Pond 2P : Existing "detention" area

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 2-yr Rainfall=3.70"


Area (sf)	CN	Description
28,956	55	Woods, Good, HSG B
13,557	61	>75% Grass cover, Good, HSG B
* 4,841	98	IMPERVIOUS
47,354	61	Weighted Average
42,513		89.78% Pervious Area
4,841		10.22% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
13.4	100	0.0800	0.12		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 2.70"



Subcatchment 1S: SUBCATCHMENT 1

Hydrograph



Pre Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 2-yr Rainfall=3.70"

Printed 2/13/2026

Page 4

Summary for Subcatchment 2S: SUBCATCHMENT 2

Runoff = 0.38 cfs @ 12.09 hrs, Volume= 0.029 af, Depth> 1.19"
Routed to Reach SP2 : SUMMATION POINT 2


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 2-yr Rainfall=3.70"

Area (sf)	CN	Description
9,128	61	>75% Grass cover, Good, HSG B
* 3,451	98	IMPERVIOUS
12,579	71	Weighted Average
9,128		72.57% Pervious Area
3,451		27.43% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment 2S: SUBCATCHMENT 2

Hydrograph



Pre Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 2-yr Rainfall=3.70"

Printed 2/13/2026


Page 5

Summary for Reach SP1: SUMMATION POINT 1

Inflow Area = 1.087 ac, 10.22% Impervious, Inflow Depth = 0.00" for 2-yr event
Inflow = 0.00 cfs @ 5.00 hrs, Volume= 0.000 af
Outflow = 0.00 cfs @ 5.00 hrs, Volume= 0.000 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs

Reach SP1: SUMMATION POINT 1



Pre Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 2-yr Rainfall=3.70"

Printed 2/13/2026


Page 6

Summary for Reach SP2: SUMMATION POINT 2

Inflow Area = 0.289 ac, 27.43% Impervious, Inflow Depth > 1.19" for 2-yr event
Inflow = 0.38 cfs @ 12.09 hrs, Volume= 0.029 af
Outflow = 0.38 cfs @ 12.09 hrs, Volume= 0.029 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs

Reach SP2: SUMMATION POINT 2



Pre Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 2-yr Rainfall=3.70"

Printed 2/13/2026

Page 7

Summary for Pond 2P: Existing "detention" area

Inflow Area = 1.087 ac, 10.22% Impervious, Inflow Depth > 0.66" for 2-yr event
 Inflow = 0.50 cfs @ 12.23 hrs, Volume= 0.060 af
 Outflow = 0.12 cfs @ 13.07 hrs, Volume= 0.060 af, Atten= 76%, Lag= 50.3 min
 Discarded = 0.12 cfs @ 13.07 hrs, Volume= 0.060 af
 Primary = 0.00 cfs @ 5.00 hrs, Volume= 0.000 af
 Routed to Reach SP1 : SUMMATION POINT 1

Routing by Stor-Ind method, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 27.60' @ 13.07 hrs Surf.Area= 2,104 sf Storage= 704 cf


Plug-Flow detention time= 67.4 min calculated for 0.060 af (100% of inflow)
 Center-of-Mass det. time= 65.8 min (968.5 - 902.6)

Volume	Invert	Avail.Storage	Storage Description
#1	27.00'	17,225 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
27.00	250	0	0
28.00	3,350	1,800	1,800
29.00	8,000	5,675	7,475
30.00	11,500	9,750	17,225

Device	Routing	Invert	Outlet Devices
#1	Discarded	27.00'	2.400 in/hr Exfiltration over Surface area
#2	Primary	29.50'	10.0' long x 10.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.49 2.56 2.70 2.69 2.68 2.69 2.67 2.64

Discarded OutFlow Max=0.12 cfs @ 13.07 hrs HW=27.60' (Free Discharge)
 ↑1=**Exfiltration** (Exfiltration Controls 0.12 cfs)

Primary OutFlow Max=0.00 cfs @ 5.00 hrs HW=27.00' (Free Discharge)
 ↑2=**Broad-Crested Rectangular Weir**(Controls 0.00 cfs)



Pre Development

Prepared by Haley Ward


HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 2-yr Rainfall=3.70"

Printed 2/13/2026

Page 8

Pond 2P: Existing "detention" area



Pre Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 10-yr Rainfall=5.61"

Printed 2/13/2026

Page 9

Time span=5.00-24.00 hrs, dt=0.05 hrs, 381 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment1S: SUBCATCHMENT1 Runoff Area=47,354 sf 10.22% Impervious Runoff Depth>1.74"
Flow Length=100' Slope=0.0800 '/' Tc=13.4 min CN=61 Runoff=1.63 cfs 0.158 af

Subcatchment2S: SUBCATCHMENT2 Runoff Area=12,579 sf 27.43% Impervious Runoff Depth>2.59"
Tc=5.0 min CN=71 Runoff=0.87 cfs 0.062 af

Reach SP1: SUMMATIONPOINT 1 Inflow=0.00 cfs 0.000 af
Outflow=0.00 cfs 0.000 af

Reach SP2: SUMMATIONPOINT 2 Inflow=0.87 cfs 0.062 af
Outflow=0.87 cfs 0.062 af

Pond 2P: Existing "detention" area Peak Elev=28.22' Storage=2,652 cf Inflow=1.63 cfs 0.158 af
Discarded=0.24 cfs 0.155 af Primary=0.00 cfs 0.000 af Outflow=0.24 cfs 0.155 af

Total Runoff Area = 1.376 ac Runoff Volume = 0.220 af Average Runoff Depth = 1.92"
86.16% Pervious = 1.186 ac 13.84% Impervious = 0.190 ac

Pre Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 10-yr Rainfall=5.61"

Printed 2/13/2026

Page 10

Summary for Subcatchment 1S: SUBCATCHMENT 1


Runoff = 1.63 cfs @ 12.20 hrs, Volume= 0.158 af, Depth> 1.74"

Routed to Pond 2P : Existing "detention" area

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 10-yr Rainfall=5.61"


Area (sf)	CN	Description
28,956	55	Woods, Good, HSG B
13,557	61	>75% Grass cover, Good, HSG B
* 4,841	98	IMPERVIOUS
47,354	61	Weighted Average
42,513		89.78% Pervious Area
4,841		10.22% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
13.4	100	0.0800	0.12		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 2.70"



Subcatchment 1S: SUBCATCHMENT 1

Hydrograph



Pre Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 10-yr Rainfall=5.61"

Printed 2/13/2026

Page 11

Summary for Subcatchment 2S: SUBCATCHMENT 2

Runoff = 0.87 cfs @ 12.08 hrs, Volume= 0.062 af, Depth> 2.59"
 Routed to Reach SP2 : SUMMATION POINT 2


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-yr Rainfall=5.61"

Area (sf)	CN	Description
9,128	61	>75% Grass cover, Good, HSG B
* 3,451	98	IMPERVIOUS
12,579	71	Weighted Average
9,128		72.57% Pervious Area
3,451		27.43% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment 2S: SUBCATCHMENT 2

Hydrograph



Pre Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 10-yr Rainfall=5.61"

Printed 2/13/2026


Page 12

Summary for Reach SP1: SUMMATION POINT 1

Inflow Area = 1.087 ac, 10.22% Impervious, Inflow Depth = 0.00" for 10-yr event
Inflow = 0.00 cfs @ 5.00 hrs, Volume= 0.000 af
Outflow = 0.00 cfs @ 5.00 hrs, Volume= 0.000 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs

Reach SP1: SUMMATION POINT 1



Pre Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 10-yr Rainfall=5.61"

Printed 2/13/2026


Page 13

Summary for Reach SP2: SUMMATION POINT 2

Inflow Area = 0.289 ac, 27.43% Impervious, Inflow Depth > 2.59" for 10-yr event
Inflow = 0.87 cfs @ 12.08 hrs, Volume= 0.062 af
Outflow = 0.87 cfs @ 12.08 hrs, Volume= 0.062 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs

Reach SP2: SUMMATION POINT 2



Pre Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 10-yr Rainfall=5.61"

Printed 2/13/2026

Page 14

Summary for Pond 2P: Existing "detention" area

Inflow Area = 1.087 ac, 10.22% Impervious, Inflow Depth > 1.74" for 10-yr event
 Inflow = 1.63 cfs @ 12.20 hrs, Volume= 0.158 af
 Outflow = 0.24 cfs @ 13.23 hrs, Volume= 0.155 af, Atten= 85%, Lag= 61.5 min
 Discarded = 0.24 cfs @ 13.23 hrs, Volume= 0.155 af
 Primary = 0.00 cfs @ 5.00 hrs, Volume= 0.000 af
 Routed to Reach SP1 : SUMMATION POINT 1

Routing by Stor-Ind method, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 28.22' @ 13.23 hrs Surf.Area= 4,376 sf Storage= 2,652 cf


Plug-Flow detention time= 141.3 min calculated for 0.155 af (98% of inflow)
 Center-of-Mass det. time= 130.3 min (999.7 - 869.4)

Volume	Invert	Avail.Storage	Storage Description
#1	27.00'	17,225 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
27.00	250	0	0
28.00	3,350	1,800	1,800
29.00	8,000	5,675	7,475
30.00	11,500	9,750	17,225

Device	Routing	Invert	Outlet Devices
#1	Discarded	27.00'	2.400 in/hr Exfiltration over Surface area
#2	Primary	29.50'	10.0' long x 10.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.49 2.56 2.70 2.69 2.68 2.69 2.67 2.64

Discarded OutFlow Max=0.24 cfs @ 13.23 hrs HW=28.22' (Free Discharge)
 ↑1=**Exfiltration** (Exfiltration Controls 0.24 cfs)

Primary OutFlow Max=0.00 cfs @ 5.00 hrs HW=27.00' (Free Discharge)
 ↑2=**Broad-Crested Rectangular Weir**(Controls 0.00 cfs)



Pre Development

Prepared by Haley Ward


HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 10-yr Rainfall=5.61"

Printed 2/13/2026

Page 15

Pond 2P: Existing "detention" area



Pre Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 25-yr Rainfall=7.12"

Printed 2/13/2026

Page 16

Time span=5.00-24.00 hrs, dt=0.05 hrs, 381 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment1S: SUBCATCHMENT1 Runoff Area=47,354 sf 10.22% Impervious Runoff Depth>2.78"
Flow Length=100' Slope=0.0800 '/' Tc=13.4 min CN=61 Runoff=2.71 cfs 0.252 af

Subcatchment2S: SUBCATCHMENT2 Runoff Area=12,579 sf 27.43% Impervious Runoff Depth>3.82"
Tc=5.0 min CN=71 Runoff=1.30 cfs 0.092 af

Reach SP1: SUMMATIONPOINT 1 Inflow=0.00 cfs 0.000 af
Outflow=0.00 cfs 0.000 af

Reach SP2: SUMMATIONPOINT 2 Inflow=1.30 cfs 0.092 af
Outflow=1.30 cfs 0.092 af

Pond 2P: Existing "detention" area Peak Elev=28.61' Storage=4,705 cf Inflow=2.71 cfs 0.252 af
Discarded=0.34 cfs 0.239 af Primary=0.00 cfs 0.000 af Outflow=0.34 cfs 0.239 af

Total Runoff Area = 1.376 ac Runoff Volume = 0.344 af Average Runoff Depth = 3.00"
86.16% Pervious = 1.186 ac 13.84% Impervious = 0.190 ac

Pre Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 25-yr Rainfall=7.12"

Printed 2/13/2026

Page 17

Summary for Subcatchment 1S: SUBCATCHMENT 1


Runoff = 2.71 cfs @ 12.20 hrs, Volume= 0.252 af, Depth> 2.78"

Routed to Pond 2P : Existing "detention" area

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 25-yr Rainfall=7.12"


Area (sf)	CN	Description
28,956	55	Woods, Good, HSG B
13,557	61	>75% Grass cover, Good, HSG B
* 4,841	98	IMPERVIOUS
47,354	61	Weighted Average
42,513		89.78% Pervious Area
4,841		10.22% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
13.4	100	0.0800	0.12		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 2.70"



Subcatchment 1S: SUBCATCHMENT 1

Hydrograph



Pre Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 25-yr Rainfall=7.12"

Printed 2/13/2026

Page 18

Summary for Subcatchment 2S: SUBCATCHMENT 2

Runoff = 1.30 cfs @ 12.08 hrs, Volume= 0.092 af, Depth> 3.82"
Routed to Reach SP2 : SUMMATION POINT 2


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 25-yr Rainfall=7.12"

Area (sf)	CN	Description
9,128	61	>75% Grass cover, Good, HSG B
* 3,451	98	IMPERVIOUS
12,579	71	Weighted Average
9,128		72.57% Pervious Area
3,451		27.43% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment 2S: SUBCATCHMENT 2

Hydrograph



Pre Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 25-yr Rainfall=7.12"

Printed 2/13/2026


Page 19

Summary for Reach SP1: SUMMATION POINT 1

Inflow Area = 1.087 ac, 10.22% Impervious, Inflow Depth = 0.00" for 25-yr event
Inflow = 0.00 cfs @ 5.00 hrs, Volume= 0.000 af
Outflow = 0.00 cfs @ 5.00 hrs, Volume= 0.000 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs

Reach SP1: SUMMATION POINT 1



Pre Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 25-yr Rainfall=7.12"

Printed 2/13/2026


Page 20

Summary for Reach SP2: SUMMATION POINT 2

Inflow Area = 0.289 ac, 27.43% Impervious, Inflow Depth > 3.82" for 25-yr event
Inflow = 1.30 cfs @ 12.08 hrs, Volume= 0.092 af
Outflow = 1.30 cfs @ 12.08 hrs, Volume= 0.092 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs

Reach SP2: SUMMATION POINT 2



Pre Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 25-yr Rainfall=7.12"

Printed 2/13/2026

Page 21

Summary for Pond 2P: Existing "detention" area

Inflow Area = 1.087 ac, 10.22% Impervious, Inflow Depth > 2.78" for 25-yr event
 Inflow = 2.71 cfs @ 12.20 hrs, Volume= 0.252 af
 Outflow = 0.34 cfs @ 13.36 hrs, Volume= 0.239 af, Atten= 87%, Lag= 69.9 min
 Discarded = 0.34 cfs @ 13.36 hrs, Volume= 0.239 af
 Primary = 0.00 cfs @ 5.00 hrs, Volume= 0.000 af
 Routed to Reach SP1 : SUMMATION POINT 1

Routing by Stor-Ind method, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 28.61' @ 13.36 hrs Surf.Area= 6,183 sf Storage= 4,705 cf


Plug-Flow detention time= 179.9 min calculated for 0.238 af (95% of inflow)
 Center-of-Mass det. time= 152.9 min (1,008.3 - 855.3)

Volume	Invert	Avail.Storage	Storage Description
#1	27.00'	17,225 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
27.00	250	0	0
28.00	3,350	1,800	1,800
29.00	8,000	5,675	7,475
30.00	11,500	9,750	17,225

Device	Routing	Invert	Outlet Devices
#1	Discarded	27.00'	2.400 in/hr Exfiltration over Surface area
#2	Primary	29.50'	10.0' long x 10.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.49 2.56 2.70 2.69 2.68 2.69 2.67 2.64

Discarded OutFlow Max=0.34 cfs @ 13.36 hrs HW=28.61' (Free Discharge)
 ↑1=**Exfiltration** (Exfiltration Controls 0.34 cfs)

Primary OutFlow Max=0.00 cfs @ 5.00 hrs HW=27.00' (Free Discharge)
 ↑2=**Broad-Crested Rectangular Weir**(Controls 0.00 cfs)



Pre Development

Prepared by Haley Ward


HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 25-yr Rainfall=7.12"

Printed 2/13/2026

Page 22

Pond 2P: Existing "detention" area



Pre Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 50-yr Rainfall=8.53"

Printed 2/13/2026

Page 23

Time span=5.00-24.00 hrs, dt=0.05 hrs, 381 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment1S: SUBCATCHMENT1 Runoff Area=47,354 sf 10.22% Impervious Runoff Depth>3.84"
Flow Length=100' Slope=0.0800 '/' Tc=13.4 min CN=61 Runoff=3.81 cfs 0.348 af

Subcatchment2S: SUBCATCHMENT2 Runoff Area=12,579 sf 27.43% Impervious Runoff Depth>5.04"
Tc=5.0 min CN=71 Runoff=1.71 cfs 0.121 af

Reach SP1: SUMMATIONPOINT 1 Inflow=0.00 cfs 0.000 af
Outflow=0.00 cfs 0.000 af

Reach SP2: SUMMATIONPOINT 2 Inflow=1.71 cfs 0.121 af
Outflow=1.71 cfs 0.121 af

Pond 2P: Existing "detention" area Peak Elev=28.93' Storage=6,956 cf Inflow=3.81 cfs 0.348 af
Discarded=0.43 cfs 0.320 af Primary=0.00 cfs 0.000 af Outflow=0.43 cfs 0.320 af

Total Runoff Area = 1.376 ac Runoff Volume = 0.469 af Average Runoff Depth = 4.09"
86.16% Pervious = 1.186 ac 13.84% Impervious = 0.190 ac

Pre Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 50-yr Rainfall=8.53"

Printed 2/13/2026

Page 24

Summary for Subcatchment 1S: SUBCATCHMENT 1


Runoff = 3.81 cfs @ 12.19 hrs, Volume= 0.348 af, Depth> 3.84"

Routed to Pond 2P : Existing "detention" area

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 50-yr Rainfall=8.53"


Area (sf)	CN	Description
28,956	55	Woods, Good, HSG B
13,557	61	>75% Grass cover, Good, HSG B
* 4,841	98	IMPERVIOUS
47,354	61	Weighted Average
42,513		89.78% Pervious Area
4,841		10.22% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
13.4	100	0.0800	0.12		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 2.70"



Subcatchment 1S: SUBCATCHMENT 1

Hydrograph



Pre Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 50-yr Rainfall=8.53"

Printed 2/13/2026

Page 25

Summary for Subcatchment 2S: SUBCATCHMENT 2

Runoff = 1.71 cfs @ 12.08 hrs, Volume= 0.121 af, Depth> 5.04"
Routed to Reach SP2 : SUMMATION POINT 2


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 50-yr Rainfall=8.53"

Area (sf)	CN	Description
9,128	61	>75% Grass cover, Good, HSG B
* 3,451	98	IMPERVIOUS
12,579	71	Weighted Average
9,128		72.57% Pervious Area
3,451		27.43% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment 2S: SUBCATCHMENT 2

Hydrograph



Pre Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 50-yr Rainfall=8.53"

Printed 2/13/2026


Page 26

Summary for Reach SP1: SUMMATION POINT 1

Inflow Area = 1.087 ac, 10.22% Impervious, Inflow Depth = 0.00" for 50-yr event
Inflow = 0.00 cfs @ 5.00 hrs, Volume= 0.000 af
Outflow = 0.00 cfs @ 5.00 hrs, Volume= 0.000 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs

Reach SP1: SUMMATION POINT 1



Pre Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 50-yr Rainfall=8.53"

Printed 2/13/2026


Page 27

Summary for Reach SP2: SUMMATION POINT 2

Inflow Area = 0.289 ac, 27.43% Impervious, Inflow Depth > 5.04" for 50-yr event
Inflow = 1.71 cfs @ 12.08 hrs, Volume= 0.121 af
Outflow = 1.71 cfs @ 12.08 hrs, Volume= 0.121 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs

Reach SP2: SUMMATION POINT 2



Pre Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 50-yr Rainfall=8.53"

Printed 2/13/2026

Page 28

Summary for Pond 2P: Existing "detention" area

Inflow Area = 1.087 ac, 10.22% Impervious, Inflow Depth > 3.84" for 50-yr event
 Inflow = 3.81 cfs @ 12.19 hrs, Volume= 0.348 af
 Outflow = 0.43 cfs @ 13.54 hrs, Volume= 0.320 af, Atten= 89%, Lag= 80.5 min
 Discarded = 0.43 cfs @ 13.54 hrs, Volume= 0.320 af
 Primary = 0.00 cfs @ 5.00 hrs, Volume= 0.000 af
 Routed to Reach SP1 : SUMMATION POINT 1

Routing by Stor-Ind method, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 28.93' @ 13.54 hrs Surf.Area= 7,692 sf Storage= 6,956 cf


Plug-Flow detention time= 209.3 min calculated for 0.320 af (92% of inflow)
 Center-of-Mass det. time= 168.7 min (1,014.6 - 845.9)

Volume	Invert	Avail.Storage	Storage Description
#1	27.00'	17,225 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
27.00	250	0	0
28.00	3,350	1,800	1,800
29.00	8,000	5,675	7,475
30.00	11,500	9,750	17,225

Device	Routing	Invert	Outlet Devices
#1	Discarded	27.00'	2.400 in/hr Exfiltration over Surface area
#2	Primary	29.50'	10.0' long x 10.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.49 2.56 2.70 2.69 2.68 2.69 2.67 2.64

Discarded OutFlow Max=0.43 cfs @ 13.54 hrs HW=28.93' (Free Discharge)
 ↑1=**Exfiltration** (Exfiltration Controls 0.43 cfs)

Primary OutFlow Max=0.00 cfs @ 5.00 hrs HW=27.00' (Free Discharge)
 ↑2=**Broad-Crested Rectangular Weir**(Controls 0.00 cfs)



Pre Development

Prepared by Haley Ward


HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC


Type III 24-hr 50-yr Rainfall=8.53"

Printed 2/13/2026

Page 29

Pond 2P: Existing "detention" area





Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 2-yr Rainfall=3.70"

Printed 2/13/2026

Page 2

Time span=5.00-24.00 hrs, dt=0.05 hrs, 381 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment1S: SUBCATCHMENT1 Runoff Area=26,883 sf 8.11% Impervious Runoff Depth>0.61"
Flow Length=490' Tc=34.4 min CN=60 Runoff=0.18 cfs 0.032 af

Subcatchment2S: SUBCATCHMENT2 Runoff Area=9,849 sf 37.64% Impervious Runoff Depth>1.44"
Tc=5.0 min CN=75 Runoff=0.38 cfs 0.027 af

Subcatchment3S: SUBCATCHMENT3 Runoff Area=10,559 sf 56.44% Impervious Runoff Depth>1.95"
Tc=0.0 min CN=82 Runoff=0.64 cfs 0.039 af

Subcatchment4S: SUBCATCHMENT4 Runoff Area=2,050 sf 100.00% Impervious Runoff Depth>3.39"
Tc=5.0 min CN=98 Runoff=0.17 cfs 0.013 af

Subcatchment5S: SUBCATCHMENT5 Runoff Area=2,050 sf 100.00% Impervious Runoff Depth>3.39"
Tc=5.0 min CN=98 Runoff=0.17 cfs 0.013 af

Subcatchment6S: SUBCATCHMENT6 Runoff Area=2,050 sf 100.00% Impervious Runoff Depth>3.39"
Tc=5.0 min CN=98 Runoff=0.17 cfs 0.013 af

Subcatchment7S: SUBCATCHMENT7 Runoff Area=2,050 sf 100.00% Impervious Runoff Depth>3.39"
Tc=5.0 min CN=98 Runoff=0.17 cfs 0.013 af

Subcatchment8S: SUBCATCHMENT 8 Runoff Area=4,442 sf 0.00% Impervious Runoff Depth>0.62"
Tc=10.0 min CN=60 Runoff=0.05 cfs 0.005 af

Reach SP1: SUMMATIONPOINT 1 Inflow=0.05 cfs 0.005 af
Outflow=0.05 cfs 0.005 af

Reach SP2: SUMMATIONPOINT 2 Inflow=0.38 cfs 0.027 af
Outflow=0.38 cfs 0.027 af

Pond 1P: RAIN GARDEN Peak Elev=30.96' Storage=1,298 cf Inflow=1.18 cfs 0.093 af
Discarded=0.02 cfs 0.011 af Primary=0.82 cfs 0.065 af Secondary=0.00 cfs 0.000 af Outflow=0.83 cfs 0.076 af

Pond 2P: INFILTRATION TRENCH Peak Elev=28.09' Storage=87 cf Inflow=0.18 cfs 0.032 af
Discarded=0.13 cfs 0.031 af Primary=0.00 cfs 0.000 af Outflow=0.13 cfs 0.031 af

Pond 3P: SUBSURFACE DETENTION Peak Elev=28.64' Storage=920 cf Inflow=0.82 cfs 0.065 af
Outflow=0.19 cfs 0.065 af

Total Runoff Area = 1.376 ac Runoff Volume = 0.157 af Average Runoff Depth = 1.37"
66.55% Pervious = 0.916 ac 33.45% Impervious = 0.460 ac

Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 2-yr Rainfall=3.70"

Printed 2/13/2026

Page 3

Summary for Subcatchment 1S: SUBCATCHMENT 1

Runoff = 0.18 cfs @ 12.60 hrs, Volume= 0.032 af, Depth> 0.61"

Routed to Pond 2P : INFILTRATION TRENCH

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 2-yr Rainfall=3.70"

Area (sf)	CN	Description
16,143	55	Woods, Good, HSG B
8,559	61	>75% Grass cover, Good, HSG B
* 2,181	98	IMPERVIOUS
26,883	60	Weighted Average
24,702		91.89% Pervious Area
2,181		8.11% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
17.7	100	0.0400	0.09		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 2.70"
16.5	350	0.0050	0.35		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
0.2	40	0.0800	4.24		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps
34.4	490	Total			



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC


Type III 24-hr 2-yr Rainfall=3.70"

Printed 2/13/2026

Page 4

Subcatchment 1S: SUBCATCHMENT 1

Hydrograph



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 2-yr Rainfall=3.70"

Printed 2/13/2026

Page 5

Summary for Subcatchment 2S: SUBCATCHMENT 2

Runoff = 0.38 cfs @ 12.08 hrs, Volume= 0.027 af, Depth> 1.44"
 Routed to Reach SP2 : SUMMATION POINT 2


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
 Type III 24-hr 2-yr Rainfall=3.70"

Area (sf)	CN	Description
6,142	61	>75% Grass cover, Good, HSG B
* 3,707	98	IMPERVIOUS
9,849	75	Weighted Average
6,142		62.36% Pervious Area
3,707		37.64% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment 2S: SUBCATCHMENT 2

Hydrograph



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 2-yr Rainfall=3.70"

Printed 2/13/2026

Page 6

Summary for Subcatchment 3S: SUBCATCHMENT 3


Runoff = 0.64 cfs @ 12.00 hrs, Volume= 0.039 af, Depth> 1.95"
Routed to Pond 1P : RAIN GARDEN

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 2-yr Rainfall=3.70"

Area (sf)	CN	Description
18	55	Woods, Good, HSG B
4,582	61	>75% Grass cover, Good, HSG B
* 5,959	98	IMPERVIOUS
10,559	82	Weighted Average
4,600		43.56% Pervious Area
5,959		56.44% Impervious Area

Subcatchment 3S: SUBCATCHMENT 3

Hydrograph



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 2-yr Rainfall=3.70"

Printed 2/13/2026

Page 7

Summary for Subcatchment 4S: SUBCATCHMENT 4

Runoff = 0.17 cfs @ 12.07 hrs, Volume= 0.013 af, Depth> 3.39"

Routed to Pond 1P : RAIN GARDEN


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 2-yr Rainfall=3.70"

Area (sf)	CN	Description
* 2,050	98	IMPERVIOUS
2,050		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment 4S: SUBCATCHMENT 4

Hydrograph



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 2-yr Rainfall=3.70"

Printed 2/13/2026

Page 8

Summary for Subcatchment 5S: SUBCATCHMENT 5

Runoff = 0.17 cfs @ 12.07 hrs, Volume= 0.013 af, Depth> 3.39"
Routed to Pond 1P : RAIN GARDEN


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 2-yr Rainfall=3.70"

Area (sf)	CN	Description
* 2,050	98	IMPERVIOUS
2,050		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment 5S: SUBCATCHMENT 5

Hydrograph



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 2-yr Rainfall=3.70"

Printed 2/13/2026

Page 9

Summary for Subcatchment 6S: SUBCATCHMENT 6

Runoff = 0.17 cfs @ 12.07 hrs, Volume= 0.013 af, Depth> 3.39"
Routed to Pond 1P : RAIN GARDEN


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 2-yr Rainfall=3.70"

Area (sf)	CN	Description
* 2,050	98	IMPERVIOUS
2,050		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment 6S: SUBCATCHMENT 6

Hydrograph



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 2-yr Rainfall=3.70"

Printed 2/13/2026

Page 10

Summary for Subcatchment 7S: SUBCATCHMENT 7

Runoff = 0.17 cfs @ 12.07 hrs, Volume= 0.013 af, Depth> 3.39"
Routed to Pond 1P : RAIN GARDEN


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 2-yr Rainfall=3.70"

Area (sf)	CN	Description
* 2,050	98	IMPERVIOUS
2,050		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment 7S: SUBCATCHMENT 7

Hydrograph



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 2-yr Rainfall=3.70"

Printed 2/13/2026

Page 11

Summary for Subcatchment 8S: SUBCATCHMENT 8

Runoff = 0.05 cfs @ 12.18 hrs, Volume= 0.005 af, Depth> 0.62"
Routed to Reach SP1 : SUMMATION POINT 1


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 2-yr Rainfall=3.70"

Area (sf)	CN	Description
679	55	Woods, Good, HSG B
3,763	61	>75% Grass cover, Good, HSG B
4,442	60	Weighted Average
4,442		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry,

Subcatchment 8S: SUBCATCHMENT 8

Hydrograph



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 2-yr Rainfall=3.70"

Printed 2/13/2026


Page 12

Summary for Reach SP1: SUMMATION POINT 1

Inflow Area = 0.719 ac, 6.96% Impervious, Inflow Depth > 0.09" for 2-yr event
Inflow = 0.05 cfs @ 12.18 hrs, Volume= 0.005 af
Outflow = 0.05 cfs @ 12.18 hrs, Volume= 0.005 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs

Reach SP1: SUMMATION POINT 1



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 2-yr Rainfall=3.70"

Printed 2/13/2026


Page 13

Summary for Reach SP2: SUMMATION POINT 2

Inflow Area = 0.226 ac, 37.64% Impervious, Inflow Depth > 1.44" for 2-yr event
Inflow = 0.38 cfs @ 12.08 hrs, Volume= 0.027 af
Outflow = 0.38 cfs @ 12.08 hrs, Volume= 0.027 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs

Reach SP2: SUMMATION POINT 2



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 2-yr Rainfall=3.70"

Printed 2/13/2026

Page 14

Summary for Pond 1P: RAIN GARDEN

Inflow Area = 0.431 ac, 75.48% Impervious, Inflow Depth > 2.58" for 2-yr event
 Inflow = 1.18 cfs @ 12.04 hrs, Volume= 0.093 af
 Outflow = 0.83 cfs @ 12.13 hrs, Volume= 0.076 af, Atten= 29%, Lag= 5.8 min
 Discarded = 0.02 cfs @ 12.13 hrs, Volume= 0.011 af
 Primary = 0.82 cfs @ 12.13 hrs, Volume= 0.065 af
 Routed to Pond 3P : SUBSURFACE DETENTION
 Secondary = 0.00 cfs @ 5.00 hrs, Volume= 0.000 af
 Routed to Reach SP1 : SUMMATION POINT 1

Routing by Stor-Ind method, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 30.96' @ 12.13 hrs Surf.Area= 1,488 sf Storage= 1,298 cf

Plug-Flow detention time= 131.7 min calculated for 0.076 af (82% of inflow)
 Center-of-Mass det. time= 60.8 min (850.0 - 789.2)

Volume	Invert	Avail.Storage	Storage Description
#1	30.00'	5,850 cf	Custom Stage Data (Prismatic) Listed below
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
30.00	1,200	0	0
31.00	1,500	1,350	1,350
33.50	2,100	4,500	5,850

Device	Routing	Invert	Outlet Devices
#1	Discarded	30.00'	2.400 in/hr Exfiltration over Surface area above 30.00' Excluded Surface area = 1,200 sf
#2	Primary	30.00'	12.0" Round Culvert L= 20.0' CMP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 30.00' / 29.50' S= 0.0250 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#3	Device 2	30.50'	12.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 2	32.80'	12.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Secondary	32.90'	5.0' long x 5.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.34 2.50 2.70 2.68 2.68 2.66 2.65 2.65 2.65 2.65 2.67 2.66 2.68 2.70 2.74 2.79 2.88

Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 2-yr Rainfall=3.70"

Printed 2/13/2026

Page 15

Discarded OutFlow Max=0.02 cfs @ 12.13 hrs HW=30.96' (Free Discharge)

↳ 1=Exfiltration (Exfiltration Controls 0.02 cfs)

Primary OutFlow Max=0.81 cfs @ 12.13 hrs HW=30.96' (Free Discharge)


↳ 2=Culvert (Passes 0.81 cfs of 2.04 cfs potential flow)

↳ 3=Orifice/Grate (Orifice Controls 0.81 cfs @ 2.31 fps)

↳ 4=Orifice/Grate (Controls 0.00 cfs)


Secondary OutFlow Max=0.00 cfs @ 5.00 hrs HW=30.00' (Free Discharge)

↳ 5=Broad-Crested Rectangular Weir (Controls 0.00 cfs)



Pond 1P: RAIN GARDEN

Hydrograph



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 2-yr Rainfall=3.70"

Printed 2/13/2026

Page 16

Summary for Pond 2P: INFILTRATION TRENCH

Inflow Area = 0.617 ac, 8.11% Impervious, Inflow Depth > 0.61" for 2-yr event
 Inflow = 0.18 cfs @ 12.60 hrs, Volume= 0.032 af
 Outflow = 0.13 cfs @ 12.45 hrs, Volume= 0.031 af, Atten= 29%, Lag= 0.0 min
 Discarded = 0.13 cfs @ 12.45 hrs, Volume= 0.031 af
 Primary = 0.00 cfs @ 5.00 hrs, Volume= 0.000 af
 Routed to Reach SP1 : SUMMATION POINT 1

Routing by Stor-Ind method, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 28.09' @ 12.92 hrs Surf.Area= 2,300 sf Storage= 87 cf

Plug-Flow detention time= 5.1 min calculated for 0.031 af (100% of inflow)
 Center-of-Mass det. time= 4.3 min (926.6 - 922.3)

Volume	Invert	Avail.Storage	Storage Description
#1	28.00'	2,157 cf	Custom Stage Data (Prismatic) Listed below (Recalc) 6,900 cf Overall - 1,508 cf Embedded = 5,392 cf x 40.0% Voids
#2	28.50'	754 cf	24.0" Round Pipe Storage Inside #1 L= 240.0'
#3	28.50'	754 cf	24.0" Round Pipe Storage Inside #1 L= 240.0'
		3,665 cf	Total Available Storage

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
28.00	2,300	0	0
31.00	2,300	6,900	6,900

Device	Routing	Invert	Outlet Devices
#1	Discarded	28.00'	2.400 in/hr Exfiltration over Surface area
#2	Primary	31.00'	320.0' long x 5.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.34 2.50 2.70 2.68 2.68 2.66 2.65 2.65 2.65 2.65 2.67 2.66 2.68 2.70 2.74 2.79 2.88

Discarded OutFlow Max=0.13 cfs @ 12.45 hrs HW=28.03' (Free Discharge)
 ↑1=Exfiltration (Exfiltration Controls 0.13 cfs)

Primary OutFlow Max=0.00 cfs @ 5.00 hrs HW=28.00' (Free Discharge)
 ↑2=Broad-Crested Rectangular Weir(Controls 0.00 cfs)



Post Development

Prepared by Haley Ward


HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 2-yr Rainfall=3.70"

Printed 2/13/2026

Page 17

Pond 2P: INFILTRATION TRENCH



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 2-yr Rainfall=3.70"

Printed 2/13/2026

Page 18

Summary for Pond 3P: SUBSURFACE DETENTION

Inflow Area = 0.431 ac, 75.48% Impervious, Inflow Depth > 1.80" for 2-yr event
 Inflow = 0.82 cfs @ 12.13 hrs, Volume= 0.065 af
 Outflow = 0.19 cfs @ 11.95 hrs, Volume= 0.065 af, Atten= 76%, Lag= 0.0 min
 Discarded = 0.19 cfs @ 11.95 hrs, Volume= 0.065 af

Routing by Stor-Ind method, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 28.64' @ 12.78 hrs Surf.Area= 3,500 sf Storage= 920 cf

Plug-Flow detention time= 38.2 min calculated for 0.065 af (100% of inflow)
 Center-of-Mass det. time= 38.0 min (861.9 - 824.0)

Volume	Invert	Avail.Storage	Storage Description
#1	28.00'	3,748 cf	Custom Stage Data (Prismatic) Listed below (Recalc) 10,500 cf Overall - 1,131 cf Embedded = 9,369 cf x 40.0% Voids
#2	28.50'	377 cf	24.0" Round Pipe Storage Inside #1 L= 120.0'
#3	28.50'	377 cf	24.0" Round Pipe Storage Inside #1 L= 120.0'
#4	28.50'	377 cf	24.0" Round Pipe Storage Inside #1 L= 120.0'
		4,879 cf	Total Available Storage

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
28.00	3,500	0	0
31.00	3,500	10,500	10,500

Device	Routing	Invert	Outlet Devices
#1	Discarded	28.00'	2.400 in/hr Exfiltration over Surface area

Discarded OutFlow Max=0.19 cfs @ 11.95 hrs HW=28.03' (Free Discharge)
 ↑1=Exfiltration (Exfiltration Controls 0.19 cfs)

Pond 3P: SUBSURFACE DETENTION

Exfiltration

Post Development

Prepared by Haley Ward


HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 2-yr Rainfall=3.70"

Printed 2/13/2026

Page 19

Pond 3P: SUBSURFACE DETENTION



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 10-yr Rainfall=5.61"

Printed 2/13/2026

Page 20

Time span=5.00-24.00 hrs, dt=0.05 hrs, 381 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment1S: SUBCATCHMENT1 Runoff Area=26,883 sf 8.11% Impervious Runoff Depth>1.66"
Flow Length=490' Tc=34.4 min CN=60 Runoff=0.59 cfs 0.085 af

Subcatchment2S: SUBCATCHMENT2 Runoff Area=9,849 sf 37.64% Impervious Runoff Depth>2.95"
Tc=5.0 min CN=75 Runoff=0.78 cfs 0.056 af

Subcatchment3S: SUBCATCHMENT3 Runoff Area=10,559 sf 56.44% Impervious Runoff Depth>3.63"
Tc=0.0 min CN=82 Runoff=1.18 cfs 0.073 af

Subcatchment4S: SUBCATCHMENT4 Runoff Area=2,050 sf 100.00% Impervious Runoff Depth>5.22"
Tc=5.0 min CN=98 Runoff=0.26 cfs 0.020 af

Subcatchment5S: SUBCATCHMENT5 Runoff Area=2,050 sf 100.00% Impervious Runoff Depth>5.22"
Tc=5.0 min CN=98 Runoff=0.26 cfs 0.020 af

Subcatchment6S: SUBCATCHMENT6 Runoff Area=2,050 sf 100.00% Impervious Runoff Depth>5.22"
Tc=5.0 min CN=98 Runoff=0.26 cfs 0.020 af

Subcatchment7S: SUBCATCHMENT7 Runoff Area=2,050 sf 100.00% Impervious Runoff Depth>5.22"
Tc=5.0 min CN=98 Runoff=0.26 cfs 0.020 af

Subcatchment8S: SUBCATCHMENT 8 Runoff Area=4,442 sf 0.00% Impervious Runoff Depth>1.67"
Tc=10.0 min CN=60 Runoff=0.16 cfs 0.014 af

Reach SP1: SUMMATIONPOINT 1 Inflow=0.16 cfs 0.014 af
Outflow=0.16 cfs 0.014 af

Reach SP2: SUMMATIONPOINT 2 Inflow=0.78 cfs 0.056 af
Outflow=0.78 cfs 0.056 af

Pond 1P: RAIN GARDEN Peak Elev=31.14' Storage=1,603 cf Inflow=1.97 cfs 0.155 af
Discarded=0.02 cfs 0.013 af Primary=1.45 cfs 0.125 af Secondary=0.00 cfs 0.000 af Outflow=1.47 cfs 0.138 af

Pond 2P: INFILTRATION TRENCH Peak Elev=29.07' Storage=1,200 cf Inflow=0.59 cfs 0.085 af
Discarded=0.13 cfs 0.085 af Primary=0.00 cfs 0.000 af Outflow=0.13 cfs 0.085 af

Pond 3P: SUBSURFACE DETENTION Peak Elev=29.43' Storage=2,312 cf Inflow=1.45 cfs 0.125 af
Outflow=0.19 cfs 0.125 af

Total Runoff Area = 1.376 ac Runoff Volume = 0.310 af Average Runoff Depth = 2.70"
66.55% Pervious = 0.916 ac 33.45% Impervious = 0.460 ac

Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 10-yr Rainfall=5.61"

Printed 2/13/2026

Page 21

Summary for Subcatchment 1S: SUBCATCHMENT 1

Runoff = 0.59 cfs @ 12.53 hrs, Volume= 0.085 af, Depth> 1.66"
 Routed to Pond 2P : INFILTRATION TRENCH

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-yr Rainfall=5.61"

Area (sf)	CN	Description
16,143	55	Woods, Good, HSG B
8,559	61	>75% Grass cover, Good, HSG B
* 2,181	98	IMPERVIOUS
26,883	60	Weighted Average
24,702		91.89% Pervious Area
2,181		8.11% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
17.7	100	0.0400	0.09		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 2.70"
16.5	350	0.0050	0.35		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
0.2	40	0.0800	4.24		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps
34.4	490	Total			



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC


Type III 24-hr 10-yr Rainfall=5.61"

Printed 2/13/2026

Page 22

Subcatchment 1S: SUBCATCHMENT 1

Hydrograph



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 10-yr Rainfall=5.61"

Printed 2/13/2026

Page 23

Summary for Subcatchment 2S: SUBCATCHMENT 2

Runoff = 0.78 cfs @ 12.08 hrs, Volume= 0.056 af, Depth> 2.95"
 Routed to Reach SP2 : SUMMATION POINT 2


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-yr Rainfall=5.61"

Area (sf)	CN	Description
6,142	61	>75% Grass cover, Good, HSG B
* 3,707	98	IMPERVIOUS
9,849	75	Weighted Average
6,142		62.36% Pervious Area
3,707		37.64% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment 2S: SUBCATCHMENT 2

Hydrograph



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 10-yr Rainfall=5.61"

Printed 2/13/2026

Page 24

Summary for Subcatchment 3S: SUBCATCHMNT 3

Runoff = 1.18 cfs @ 12.00 hrs, Volume= 0.073 af, Depth> 3.63"


Routed to Pond 1P : RAIN GARDEN

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 10-yr Rainfall=5.61"

Area (sf)	CN	Description
18	55	Woods, Good, HSG B
4,582	61	>75% Grass cover, Good, HSG B
* 5,959	98	IMPERVIOUS
10,559	82	Weighted Average
4,600		43.56% Pervious Area
5,959		56.44% Impervious Area

Subcatchment 3S: SUBCATCHMNT 3

Hydrograph



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 10-yr Rainfall=5.61"

Printed 2/13/2026

Page 25

Summary for Subcatchment 4S: SUBCATCHMENT 4

Runoff = 0.26 cfs @ 12.07 hrs, Volume= 0.020 af, Depth> 5.22"

Routed to Pond 1P : RAIN GARDEN


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 10-yr Rainfall=5.61"

Area (sf)	CN	Description
* 2,050	98	IMPERVIOUS
2,050		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment 4S: SUBCATCHMENT 4

Hydrograph



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 10-yr Rainfall=5.61"

Printed 2/13/2026

Page 26

Summary for Subcatchment 5S: SUBCATCHMENT 5

Runoff = 0.26 cfs @ 12.07 hrs, Volume= 0.020 af, Depth> 5.22"
Routed to Pond 1P : RAIN GARDEN


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 10-yr Rainfall=5.61"

Area (sf)	CN	Description
* 2,050	98	IMPERVIOUS
2,050		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment 5S: SUBCATCHMENT 5

Hydrograph



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 10-yr Rainfall=5.61"

Printed 2/13/2026

Page 27

Summary for Subcatchment 6S: SUBCATCHMENT 6

Runoff = 0.26 cfs @ 12.07 hrs, Volume= 0.020 af, Depth> 5.22"
Routed to Pond 1P : RAIN GARDEN


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 10-yr Rainfall=5.61"

Area (sf)	CN	Description
* 2,050	98	IMPERVIOUS
2,050		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment 6S: SUBCATCHMENT 6

Hydrograph



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 10-yr Rainfall=5.61"

Printed 2/13/2026

Page 28

Summary for Subcatchment 7S: SUBCATCHMENT 7

Runoff = 0.26 cfs @ 12.07 hrs, Volume= 0.020 af, Depth> 5.22"
 Routed to Pond 1P : RAIN GARDEN


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-yr Rainfall=5.61"

Area (sf)	CN	Description
* 2,050	98	IMPERVIOUS
2,050		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment 7S: SUBCATCHMENT 7

Hydrograph



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 10-yr Rainfall=5.61"

Printed 2/13/2026

Page 29

Summary for Subcatchment 8S: SUBCATCHMENT 8

Runoff = 0.16 cfs @ 12.16 hrs, Volume= 0.014 af, Depth> 1.67"
 Routed to Reach SP1 : SUMMATION POINT 1


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-yr Rainfall=5.61"

Area (sf)	CN	Description
679	55	Woods, Good, HSG B
3,763	61	>75% Grass cover, Good, HSG B
4,442	60	Weighted Average
4,442		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry,

Subcatchment 8S: SUBCATCHMENT 8

Hydrograph



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 10-yr Rainfall=5.61"

Printed 2/13/2026


Page 30

Summary for Reach SP1: SUMMATION POINT 1

Inflow Area = 0.719 ac, 6.96% Impervious, Inflow Depth > 0.24" for 10-yr event
Inflow = 0.16 cfs @ 12.16 hrs, Volume= 0.014 af
Outflow = 0.16 cfs @ 12.16 hrs, Volume= 0.014 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs

Reach SP1: SUMMATION POINT 1



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 10-yr Rainfall=5.61"

Printed 2/13/2026


Page 31

Summary for Reach SP2: SUMMATION POINT 2

Inflow Area = 0.226 ac, 37.64% Impervious, Inflow Depth > 2.95" for 10-yr event
Inflow = 0.78 cfs @ 12.08 hrs, Volume= 0.056 af
Outflow = 0.78 cfs @ 12.08 hrs, Volume= 0.056 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs

Reach SP2: SUMMATION POINT 2



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 10-yr Rainfall=5.61"

Printed 2/13/2026

Page 32

Summary for Pond 1P: RAIN GARDEN

Inflow Area = 0.431 ac, 75.48% Impervious, Inflow Depth > 4.32" for 10-yr event
 Inflow = 1.97 cfs @ 12.03 hrs, Volume= 0.155 af
 Outflow = 1.47 cfs @ 12.12 hrs, Volume= 0.138 af, Atten= 26%, Lag= 5.3 min
 Discarded = 0.02 cfs @ 12.12 hrs, Volume= 0.013 af
 Primary = 1.45 cfs @ 12.12 hrs, Volume= 0.125 af
 Routed to Pond 3P : SUBSURFACE DETENTION
 Secondary = 0.00 cfs @ 5.00 hrs, Volume= 0.000 af
 Routed to Reach SP1 : SUMMATION POINT 1

Routing by Stor-Ind method, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 31.14' @ 12.12 hrs Surf.Area= 1,534 sf Storage= 1,603 cf

Plug-Flow detention time= 97.0 min calculated for 0.138 af (89% of inflow)
 Center-of-Mass det. time= 45.4 min (827.5 - 782.1)

Volume	Invert	Avail.Storage	Storage Description
#1	30.00'	5,850 cf	Custom Stage Data (Prismatic) Listed below
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
30.00	1,200	0	0
31.00	1,500	1,350	1,350
33.50	2,100	4,500	5,850

Device	Routing	Invert	Outlet Devices
#1	Discarded	30.00'	2.400 in/hr Exfiltration over Surface area above 30.00' Excluded Surface area = 1,200 sf
#2	Primary	30.00'	12.0" Round Culvert L= 20.0' CMP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 30.00' / 29.50' S= 0.0250 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#3	Device 2	30.50'	12.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 2	32.80'	12.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Secondary	32.90'	5.0' long x 5.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.34 2.50 2.70 2.68 2.68 2.66 2.65 2.65 2.65 2.65 2.67 2.66 2.68 2.70 2.74 2.79 2.88

Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 10-yr Rainfall=5.61"

Printed 2/13/2026

Page 33

Discarded OutFlow Max=0.02 cfs @ 12.12 hrs HW=31.14' (Free Discharge)

↑1=Exfiltration (Exfiltration Controls 0.02 cfs)

Primary OutFlow Max=1.43 cfs @ 12.12 hrs HW=31.14' (Free Discharge)


↑2=Culvert (Passes 1.43 cfs of 2.38 cfs potential flow)

↑3=Orifice/Grate (Orifice Controls 1.43 cfs @ 2.71 fps)


↑4=Orifice/Grate (Controls 0.00 cfs)

Secondary OutFlow Max=0.00 cfs @ 5.00 hrs HW=30.00' (Free Discharge)

↑5=Broad-Crested Rectangular Weir (Controls 0.00 cfs)



Pond 1P: RAIN GARDEN



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 10-yr Rainfall=5.61"

Printed 2/13/2026

Page 34

Summary for Pond 2P: INFILTRATION TRENCH

Inflow Area = 0.617 ac, 8.11% Impervious, Inflow Depth > 1.66" for 10-yr event
 Inflow = 0.59 cfs @ 12.53 hrs, Volume= 0.085 af
 Outflow = 0.13 cfs @ 12.15 hrs, Volume= 0.085 af, Atten= 79%, Lag= 0.0 min
 Discarded = 0.13 cfs @ 12.15 hrs, Volume= 0.085 af
 Primary = 0.00 cfs @ 5.00 hrs, Volume= 0.000 af
 Routed to Reach SP1 : SUMMATION POINT 1

Routing by Stor-Ind method, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 29.07' @ 13.80 hrs Surf.Area= 2,300 sf Storage= 1,200 cf

Plug-Flow detention time= 84.8 min calculated for 0.085 af (100% of inflow)
 Center-of-Mass det. time= 84.0 min (972.1 - 888.2)

Volume	Invert	Avail.Storage	Storage Description
#1	28.00'	2,157 cf	Custom Stage Data (Prismatic) Listed below (Recalc) 6,900 cf Overall - 1,508 cf Embedded = 5,392 cf x 40.0% Voids
#2	28.50'	754 cf	24.0" Round Pipe Storage Inside #1 L= 240.0'
#3	28.50'	754 cf	24.0" Round Pipe Storage Inside #1 L= 240.0'
		3,665 cf	Total Available Storage

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
28.00	2,300	0	0
31.00	2,300	6,900	6,900

Device	Routing	Invert	Outlet Devices
#1	Discarded	28.00'	2.400 in/hr Exfiltration over Surface area
#2	Primary	31.00'	320.0' long x 5.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.34 2.50 2.70 2.68 2.68 2.66 2.65 2.65 2.65 2.65 2.67 2.66 2.68 2.70 2.74 2.79 2.88

Discarded OutFlow Max=0.13 cfs @ 12.15 hrs HW=28.04' (Free Discharge)
 ↑1=Exfiltration (Exfiltration Controls 0.13 cfs)

Primary OutFlow Max=0.00 cfs @ 5.00 hrs HW=28.00' (Free Discharge)
 ↑2=Broad-Crested Rectangular Weir(Controls 0.00 cfs)



Post Development

Prepared by Haley Ward


HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 10-yr Rainfall=5.61"

Printed 2/13/2026

Page 35

Pond 2P: INFILTRATION TRENCH



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 10-yr Rainfall=5.61"

Printed 2/13/2026

Page 36

Summary for Pond 3P: SUBSURFACE DETENTION

Inflow Area = 0.431 ac, 75.48% Impervious, Inflow Depth > 3.49" for 10-yr event
 Inflow = 1.45 cfs @ 12.12 hrs, Volume= 0.125 af
 Outflow = 0.19 cfs @ 11.70 hrs, Volume= 0.125 af, Atten= 87%, Lag= 0.0 min
 Discarded = 0.19 cfs @ 11.70 hrs, Volume= 0.125 af

Routing by Stor-Ind method, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 29.43' @ 13.09 hrs Surf.Area= 3,500 sf Storage= 2,312 cf

Plug-Flow detention time= 104.7 min calculated for 0.125 af (100% of inflow)
 Center-of-Mass det. time= 104.1 min (917.4 - 813.3)

Volume	Invert	Avail.Storage	Storage Description
#1	28.00'	3,748 cf	Custom Stage Data (Prismatic) Listed below (Recalc) 10,500 cf Overall - 1,131 cf Embedded = 9,369 cf x 40.0% Voids
#2	28.50'	377 cf	24.0" Round Pipe Storage Inside #1 L= 120.0'
#3	28.50'	377 cf	24.0" Round Pipe Storage Inside #1 L= 120.0'
#4	28.50'	377 cf	24.0" Round Pipe Storage Inside #1 L= 120.0'
		4,879 cf	Total Available Storage

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
28.00	3,500	0	0
31.00	3,500	10,500	10,500

Device	Routing	Invert	Outlet Devices
#1	Discarded	28.00'	2.400 in/hr Exfiltration over Surface area

Discarded OutFlow Max=0.19 cfs @ 11.70 hrs HW=28.04' (Free Discharge)
 ↑1=Exfiltration (Exfiltration Controls 0.19 cfs)



Post Development

Prepared by Haley Ward


HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 10-yr Rainfall=5.61"

Printed 2/13/2026

Page 37

Pond 3P: SUBSURFACE DETENTION



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 25-yr Rainfall=7.12"

Printed 2/13/2026

Page 38

Time span=5.00-24.00 hrs, dt=0.05 hrs, 381 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment1S: SUBCATCHMENT1 Runoff Area=26,883 sf 8.11% Impervious Runoff Depth>2.67"
Flow Length=490' Tc=34.4 min CN=60 Runoff=1.00 cfs 0.137 af

Subcatchment2S: SUBCATCHMENT2 Runoff Area=9,849 sf 37.64% Impervious Runoff Depth>4.25"
Tc=5.0 min CN=75 Runoff=1.13 cfs 0.080 af

Subcatchment3S: SUBCATCHMENT3 Runoff Area=10,559 sf 56.44% Impervious Runoff Depth>5.03"
Tc=0.0 min CN=82 Runoff=1.61 cfs 0.102 af

Subcatchment4S: SUBCATCHMENT4 Runoff Area=2,050 sf 100.00% Impervious Runoff Depth>6.65"
Tc=5.0 min CN=98 Runoff=0.33 cfs 0.026 af

Subcatchment5S: SUBCATCHMENT5 Runoff Area=2,050 sf 100.00% Impervious Runoff Depth>6.65"
Tc=5.0 min CN=98 Runoff=0.33 cfs 0.026 af

Subcatchment6S: SUBCATCHMENT6 Runoff Area=2,050 sf 100.00% Impervious Runoff Depth>6.65"
Tc=5.0 min CN=98 Runoff=0.33 cfs 0.026 af

Subcatchment7S: SUBCATCHMENT7 Runoff Area=2,050 sf 100.00% Impervious Runoff Depth>6.65"
Tc=5.0 min CN=98 Runoff=0.33 cfs 0.026 af

Subcatchment8S: SUBCATCHMENT 8 Runoff Area=4,442 sf 0.00% Impervious Runoff Depth>2.68"
Tc=10.0 min CN=60 Runoff=0.27 cfs 0.023 af

Reach SP1: SUMMATIONPOINT 1 Inflow=0.27 cfs 0.023 af
Outflow=0.27 cfs 0.023 af

Reach SP2: SUMMATIONPOINT 2 Inflow=1.13 cfs 0.080 af
Outflow=1.13 cfs 0.080 af

Pond 1P: RAIN GARDEN Peak Elev=31.27' Storage=1,829 cf Inflow=2.63 cfs 0.206 af
Discarded=0.02 cfs 0.014 af Primary=1.92 cfs 0.175 af Secondary=0.00 cfs 0.000 af Outflow=1.94 cfs 0.189 af

Pond 2P: INFILTRATION TRENCH Peak Elev=30.04' Storage=2,629 cf Inflow=1.00 cfs 0.137 af
Discarded=0.13 cfs 0.131 af Primary=0.00 cfs 0.000 af Outflow=0.13 cfs 0.131 af

Pond 3P: SUBSURFACE DETENTION Peak Elev=30.07' Storage=3,474 cf Inflow=1.92 cfs 0.175 af
Outflow=0.19 cfs 0.175 af

Total Runoff Area = 1.376 ac Runoff Volume = 0.446 af Average Runoff Depth = 3.89"
66.55% Pervious = 0.916 ac 33.45% Impervious = 0.460 ac

Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 25-yr Rainfall=7.12"

Printed 2/13/2026

Page 39

Summary for Subcatchment 1S: SUBCATCHMENT 1

Runoff = 1.00 cfs @ 12.51 hrs, Volume= 0.137 af, Depth> 2.67"
 Routed to Pond 2P : INFILTRATION TRENCH

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
 Type III 24-hr 25-yr Rainfall=7.12"

Area (sf)	CN	Description
16,143	55	Woods, Good, HSG B
8,559	61	>75% Grass cover, Good, HSG B
* 2,181	98	IMPERVIOUS
26,883	60	Weighted Average
24,702		91.89% Pervious Area
2,181		8.11% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
17.7	100	0.0400	0.09		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 2.70"
16.5	350	0.0050	0.35		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
0.2	40	0.0800	4.24		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps
34.4	490	Total			



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC


Type III 24-hr 25-yr Rainfall=7.12"

Printed 2/13/2026

Page 40

Subcatchment 1S: SUBCATCHMENT 1

Hydrograph



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 25-yr Rainfall=7.12"

Printed 2/13/2026

Page 41

Summary for Subcatchment 2S: SUBCATCHMENT 2

Runoff = 1.13 cfs @ 12.08 hrs, Volume= 0.080 af, Depth> 4.25"
 Routed to Reach SP2 : SUMMATION POINT 2


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
 Type III 24-hr 25-yr Rainfall=7.12"

Area (sf)	CN	Description
6,142	61	>75% Grass cover, Good, HSG B
* 3,707	98	IMPERVIOUS
9,849	75	Weighted Average
6,142		62.36% Pervious Area
3,707		37.64% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment 2S: SUBCATCHMENT 2

Hydrograph



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 25-yr Rainfall=7.12"

Printed 2/13/2026

Page 42

Summary for Subcatchment 3S: SUBCATCHMNT 3


Runoff = 1.61 cfs @ 12.00 hrs, Volume= 0.102 af, Depth> 5.03"
Routed to Pond 1P : RAIN GARDEN

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 25-yr Rainfall=7.12"

Area (sf)	CN	Description
18	55	Woods, Good, HSG B
4,582	61	>75% Grass cover, Good, HSG B
* 5,959	98	IMPERVIOUS
10,559	82	Weighted Average
4,600		43.56% Pervious Area
5,959		56.44% Impervious Area

Subcatchment 3S: SUBCATCHMNT 3

Hydrograph



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 25-yr Rainfall=7.12"

Printed 2/13/2026

Page 43

Summary for Subcatchment 4S: SUBCATCHMENT 4

Runoff = 0.33 cfs @ 12.07 hrs, Volume= 0.026 af, Depth> 6.65"
Routed to Pond 1P : RAIN GARDEN


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 25-yr Rainfall=7.12"

Area (sf)	CN	Description
* 2,050	98	IMPERVIOUS
2,050		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment 4S: SUBCATCHMENT 4

Hydrograph



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 25-yr Rainfall=7.12"

Printed 2/13/2026

Page 44

Summary for Subcatchment 5S: SUBCATCHMENT 5

Runoff = 0.33 cfs @ 12.07 hrs, Volume= 0.026 af, Depth> 6.65"

Routed to Pond 1P : RAIN GARDEN


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 25-yr Rainfall=7.12"

Area (sf)	CN	Description
* 2,050	98	IMPERVIOUS
2,050		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment 5S: SUBCATCHMENT 5

Hydrograph



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 25-yr Rainfall=7.12"

Printed 2/13/2026

Page 45

Summary for Subcatchment 6S: SUBCATCHMENT 6

Runoff = 0.33 cfs @ 12.07 hrs, Volume= 0.026 af, Depth> 6.65"
Routed to Pond 1P : RAIN GARDEN


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 25-yr Rainfall=7.12"

Area (sf)	CN	Description
* 2,050	98	IMPERVIOUS
2,050		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment 6S: SUBCATCHMENT 6

Hydrograph



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 25-yr Rainfall=7.12"

Printed 2/13/2026

Page 46

Summary for Subcatchment 7S: SUBCATCHMENT 7

Runoff = 0.33 cfs @ 12.07 hrs, Volume= 0.026 af, Depth> 6.65"
Routed to Pond 1P : RAIN GARDEN


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 25-yr Rainfall=7.12"

Area (sf)	CN	Description
* 2,050	98	IMPERVIOUS
2,050		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment 7S: SUBCATCHMENT 7

Hydrograph



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 25-yr Rainfall=7.12"

Printed 2/13/2026

Page 47

Summary for Subcatchment 8S: SUBCATCHMENT 8

Runoff = 0.27 cfs @ 12.15 hrs, Volume= 0.023 af, Depth> 2.68"
Routed to Reach SP1 : SUMMATION POINT 1


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 25-yr Rainfall=7.12"

Area (sf)	CN	Description
679	55	Woods, Good, HSG B
3,763	61	>75% Grass cover, Good, HSG B
4,442	60	Weighted Average
4,442		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry,

Subcatchment 8S: SUBCATCHMENT 8

Hydrograph



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 25-yr Rainfall=7.12"

Printed 2/13/2026


Page 48

Summary for Reach SP1: SUMMATION POINT 1

Inflow Area = 0.719 ac, 6.96% Impervious, Inflow Depth > 0.38" for 25-yr event
Inflow = 0.27 cfs @ 12.15 hrs, Volume= 0.023 af
Outflow = 0.27 cfs @ 12.15 hrs, Volume= 0.023 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs

Reach SP1: SUMMATION POINT 1



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 25-yr Rainfall=7.12"

Printed 2/13/2026


Page 49

Summary for Reach SP2: SUMMATION POINT 2

Inflow Area = 0.226 ac, 37.64% Impervious, Inflow Depth > 4.25" for 25-yr event
Inflow = 1.13 cfs @ 12.08 hrs, Volume= 0.080 af
Outflow = 1.13 cfs @ 12.08 hrs, Volume= 0.080 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs

Reach SP2: SUMMATION POINT 2



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 25-yr Rainfall=7.12"

Printed 2/13/2026

Page 50

Summary for Pond 1P: RAIN GARDEN

Inflow Area = 0.431 ac, 75.48% Impervious, Inflow Depth > 5.74" for 25-yr event
 Inflow = 2.63 cfs @ 12.02 hrs, Volume= 0.206 af
 Outflow = 1.94 cfs @ 12.11 hrs, Volume= 0.189 af, Atten= 26%, Lag= 5.3 min
 Discarded = 0.02 cfs @ 12.11 hrs, Volume= 0.014 af
 Primary = 1.92 cfs @ 12.11 hrs, Volume= 0.175 af
 Routed to Pond 3P : SUBSURFACE DETENTION
 Secondary = 0.00 cfs @ 5.00 hrs, Volume= 0.000 af
 Routed to Reach SP1 : SUMMATION POINT 1

Routing by Stor-Ind method, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 31.27' @ 12.11 hrs Surf.Area= 1,564 sf Storage= 1,829 cf

Plug-Flow detention time= 81.7 min calculated for 0.188 af (91% of inflow)
 Center-of-Mass det. time= 39.1 min (817.0 - 777.9)

Volume	Invert	Avail.Storage	Storage Description
#1	30.00'	5,850 cf	Custom Stage Data (Prismatic) Listed below

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
30.00	1,200	0	0
31.00	1,500	1,350	1,350
33.50	2,100	4,500	5,850

Device	Routing	Invert	Outlet Devices
#1	Discarded	30.00'	2.400 in/hr Exfiltration over Surface area above 30.00' Excluded Surface area = 1,200 sf
#2	Primary	30.00'	12.0" Round Culvert L= 20.0' CMP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 30.00' / 29.50' S= 0.0250 ' / Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#3	Device 2	30.50'	12.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 2	32.80'	12.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Secondary	32.90'	5.0' long x 5.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.34 2.50 2.70 2.68 2.68 2.66 2.65 2.65 2.65 2.65 2.67 2.66 2.68 2.70 2.74 2.79 2.88

Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 25-yr Rainfall=7.12"

Printed 2/13/2026

Page 51

Discarded OutFlow Max=0.02 cfs @ 12.11 hrs HW=31.26' (Free Discharge)

↳ 1=Exfiltration (Exfiltration Controls 0.02 cfs)

Primary OutFlow Max=1.90 cfs @ 12.11 hrs HW=31.26' (Free Discharge)


↳ 2=Culvert (Passes 1.90 cfs of 2.60 cfs potential flow)

↳ 3=Orifice/Grate (Orifice Controls 1.90 cfs @ 2.97 fps)

↳ 4=Orifice/Grate (Controls 0.00 cfs)


Secondary OutFlow Max=0.00 cfs @ 5.00 hrs HW=30.00' (Free Discharge)

↳ 5=Broad-Crested Rectangular Weir (Controls 0.00 cfs)



Pond 1P: RAIN GARDEN

Hydrograph



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 25-yr Rainfall=7.12"

Printed 2/13/2026

Page 52

Summary for Pond 2P: INFILTRATION TRENCH

Inflow Area = 0.617 ac, 8.11% Impervious, Inflow Depth > 2.67" for 25-yr event
 Inflow = 1.00 cfs @ 12.51 hrs, Volume= 0.137 af
 Outflow = 0.13 cfs @ 12.00 hrs, Volume= 0.131 af, Atten= 87%, Lag= 0.0 min
 Discarded = 0.13 cfs @ 12.00 hrs, Volume= 0.131 af
 Primary = 0.00 cfs @ 5.00 hrs, Volume= 0.000 af
 Routed to Reach SP1 : SUMMATION POINT 1

Routing by Stor-Ind method, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 30.04' @ 14.94 hrs Surf.Area= 2,300 sf Storage= 2,629 cf

Plug-Flow detention time= 216.4 min calculated for 0.131 af (96% of inflow)
 Center-of-Mass det. time= 194.2 min (1,068.1 - 873.9)

Volume	Invert	Avail.Storage	Storage Description
#1	28.00'	2,157 cf	Custom Stage Data (Prismatic) Listed below (Recalc) 6,900 cf Overall - 1,508 cf Embedded = 5,392 cf x 40.0% Voids
#2	28.50'	754 cf	24.0" Round Pipe Storage Inside #1 L= 240.0'
#3	28.50'	754 cf	24.0" Round Pipe Storage Inside #1 L= 240.0'
		3,665 cf	Total Available Storage

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
28.00	2,300	0	0
31.00	2,300	6,900	6,900

Device	Routing	Invert	Outlet Devices
#1	Discarded	28.00'	2.400 in/hr Exfiltration over Surface area
#2	Primary	31.00'	320.0' long x 5.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.34 2.50 2.70 2.68 2.68 2.66 2.65 2.65 2.65 2.65 2.67 2.66 2.68 2.70 2.74 2.79 2.88

Discarded OutFlow Max=0.13 cfs @ 12.00 hrs HW=28.04' (Free Discharge)
 ↑1=**Exfiltration** (Exfiltration Controls 0.13 cfs)

Primary OutFlow Max=0.00 cfs @ 5.00 hrs HW=28.00' (Free Discharge)
 ↑2=**Broad-Crested Rectangular Weir**(Controls 0.00 cfs)



Post Development

Prepared by Haley Ward


HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 25-yr Rainfall=7.12"

Printed 2/13/2026

Page 53

Pond 2P: INFILTRATION TRENCH



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 25-yr Rainfall=7.12"

Printed 2/13/2026

Page 54

Summary for Pond 3P: SUBSURFACE DETENTION

Inflow Area = 0.431 ac, 75.48% Impervious, Inflow Depth > 4.87" for 25-yr event
 Inflow = 1.92 cfs @ 12.11 hrs, Volume= 0.175 af
 Outflow = 0.19 cfs @ 11.45 hrs, Volume= 0.175 af, Atten= 90%, Lag= 0.0 min
 Discarded = 0.19 cfs @ 11.45 hrs, Volume= 0.175 af

Routing by Stor-Ind method, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 30.07' @ 13.44 hrs Surf.Area= 3,500 sf Storage= 3,474 cf

Plug-Flow detention time= 160.8 min calculated for 0.175 af (100% of inflow)
 Center-of-Mass det. time= 160.5 min (967.2 - 806.7)

Volume	Invert	Avail.Storage	Storage Description
#1	28.00'	3,748 cf	Custom Stage Data (Prismatic) Listed below (Recalc) 10,500 cf Overall - 1,131 cf Embedded = 9,369 cf x 40.0% Voids
#2	28.50'	377 cf	24.0" Round Pipe Storage Inside #1 L= 120.0'
#3	28.50'	377 cf	24.0" Round Pipe Storage Inside #1 L= 120.0'
#4	28.50'	377 cf	24.0" Round Pipe Storage Inside #1 L= 120.0'
		4,879 cf	Total Available Storage

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
28.00	3,500	0	0
31.00	3,500	10,500	10,500

Device	Routing	Invert	Outlet Devices
#1	Discarded	28.00'	2.400 in/hr Exfiltration over Surface area

Discarded OutFlow Max=0.19 cfs @ 11.45 hrs HW=28.03' (Free Discharge)
 ↑1=Exfiltration (Exfiltration Controls 0.19 cfs)



Post Development

Prepared by Haley Ward


HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 25-yr Rainfall=7.12"

Printed 2/13/2026

Page 55

Pond 3P: SUBSURFACE DETENTION



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 50-yr Rainfall=8.53"

Printed 2/13/2026

Page 56

Time span=5.00-24.00 hrs, dt=0.05 hrs, 381 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment1S: SUBCATCHMENT1 Runoff Area=26,883 sf 8.11% Impervious Runoff Depth>3.71"
Flow Length=490' Tc=34.4 min CN=60 Runoff=1.41 cfs 0.191 af

Subcatchment2S: SUBCATCHMENT2 Runoff Area=9,849 sf 37.64% Impervious Runoff Depth>5.52"
Tc=5.0 min CN=75 Runoff=1.46 cfs 0.104 af

Subcatchment3S: SUBCATCHMENT3 Runoff Area=10,559 sf 56.44% Impervious Runoff Depth>6.36"
Tc=0.0 min CN=82 Runoff=2.02 cfs 0.129 af

Subcatchment4S: SUBCATCHMENT4 Runoff Area=2,050 sf 100.00% Impervious Runoff Depth>7.99"
Tc=5.0 min CN=98 Runoff=0.40 cfs 0.031 af

Subcatchment5S: SUBCATCHMENT5 Runoff Area=2,050 sf 100.00% Impervious Runoff Depth>7.99"
Tc=5.0 min CN=98 Runoff=0.40 cfs 0.031 af

Subcatchment6S: SUBCATCHMENT6 Runoff Area=2,050 sf 100.00% Impervious Runoff Depth>7.99"
Tc=5.0 min CN=98 Runoff=0.40 cfs 0.031 af

Subcatchment7S: SUBCATCHMENT7 Runoff Area=2,050 sf 100.00% Impervious Runoff Depth>7.99"
Tc=5.0 min CN=98 Runoff=0.40 cfs 0.031 af

Subcatchment8S: SUBCATCHMENT 8 Runoff Area=4,442 sf 0.00% Impervious Runoff Depth>3.73"
Tc=10.0 min CN=60 Runoff=0.38 cfs 0.032 af

Reach SP1: SUMMATIONPOINT 1 Inflow=0.38 cfs 0.046 af
Outflow=0.38 cfs 0.046 af

Reach SP2: SUMMATIONPOINT 2 Inflow=1.46 cfs 0.104 af
Outflow=1.46 cfs 0.104 af

Pond 1P: RAIN GARDEN Peak Elev=31.38' Storage=2,042 cf Inflow=3.23 cfs 0.254 af
Discarded=0.02 cfs 0.015 af Primary=2.35 cfs 0.222 af Secondary=0.00 cfs 0.000 af Outflow=2.37 cfs 0.236 af

Pond 2P: INFILTRATION TRENCH Peak Elev=31.00' Storage=3,665 cf Inflow=1.41 cfs 0.191 af
Discarded=0.13 cfs 0.136 af Primary=0.31 cfs 0.015 af Outflow=0.44 cfs 0.150 af

Pond 3P: SUBSURFACE DETENTION Peak Elev=30.85' Storage=4,672 cf Inflow=2.35 cfs 0.222 af
Outflow=0.19 cfs 0.221 af

Total Runoff Area = 1.376 ac Runoff Volume = 0.580 af Average Runoff Depth = 5.06"
66.55% Pervious = 0.916 ac 33.45% Impervious = 0.460 ac

Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 50-yr Rainfall=8.53"

Printed 2/13/2026

Page 57

Summary for Subcatchment 1S: SUBCATCHMENT 1

Runoff = 1.41 cfs @ 12.50 hrs, Volume= 0.191 af, Depth> 3.71"
 Routed to Pond 2P : INFILTRATION TRENCH

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
 Type III 24-hr 50-yr Rainfall=8.53"

Area (sf)	CN	Description
16,143	55	Woods, Good, HSG B
8,559	61	>75% Grass cover, Good, HSG B
* 2,181	98	IMPERVIOUS
26,883	60	Weighted Average
24,702		91.89% Pervious Area
2,181		8.11% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
17.7	100	0.0400	0.09		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 2.70"
16.5	350	0.0050	0.35		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
0.2	40	0.0800	4.24		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps
34.4	490	Total			



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC


Type III 24-hr 50-yr Rainfall=8.53"

Printed 2/13/2026

Page 58

Subcatchment 1S: SUBCATCHMENT 1

Hydrograph



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 50-yr Rainfall=8.53"

Printed 2/13/2026

Page 59

Summary for Subcatchment 2S: SUBCATCHMENT 2

Runoff = 1.46 cfs @ 12.07 hrs, Volume= 0.104 af, Depth> 5.52"
 Routed to Reach SP2 : SUMMATION POINT 2


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
 Type III 24-hr 50-yr Rainfall=8.53"

Area (sf)	CN	Description
6,142	61	>75% Grass cover, Good, HSG B
* 3,707	98	IMPERVIOUS
9,849	75	Weighted Average
6,142		62.36% Pervious Area
3,707		37.64% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment 2S: SUBCATCHMENT 2

Hydrograph



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 50-yr Rainfall=8.53"

Printed 2/13/2026

Page 60

Summary for Subcatchment 3S: SUBCATCHMNT 3


Runoff = 2.02 cfs @ 12.00 hrs, Volume= 0.129 af, Depth> 6.36"
Routed to Pond 1P : RAIN GARDEN

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 50-yr Rainfall=8.53"

Area (sf)	CN	Description
18	55	Woods, Good, HSG B
4,582	61	>75% Grass cover, Good, HSG B
* 5,959	98	IMPERVIOUS
10,559	82	Weighted Average
4,600		43.56% Pervious Area
5,959		56.44% Impervious Area

Subcatchment 3S: SUBCATCHMNT 3

Hydrograph



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 50-yr Rainfall=8.53"

Printed 2/13/2026

Page 61

Summary for Subcatchment 4S: SUBCATCHMENT 4

Runoff = 0.40 cfs @ 12.07 hrs, Volume= 0.031 af, Depth> 7.99"

Routed to Pond 1P : RAIN GARDEN


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 50-yr Rainfall=8.53"

Area (sf)	CN	Description
* 2,050	98	IMPERVIOUS
2,050		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment 4S: SUBCATCHMENT 4

Hydrograph



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 50-yr Rainfall=8.53"

Printed 2/13/2026

Page 62

Summary for Subcatchment 5S: SUBCATCHMENT 5

Runoff = 0.40 cfs @ 12.07 hrs, Volume= 0.031 af, Depth> 7.99"
Routed to Pond 1P : RAIN GARDEN


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 50-yr Rainfall=8.53"

Area (sf)	CN	Description
* 2,050	98	IMPERVIOUS
2,050		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment 5S: SUBCATCHMENT 5

Hydrograph



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 50-yr Rainfall=8.53"

Printed 2/13/2026

Page 63

Summary for Subcatchment 6S: SUBCATCHMENT 6

Runoff = 0.40 cfs @ 12.07 hrs, Volume= 0.031 af, Depth> 7.99"

Routed to Pond 1P : RAIN GARDEN


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 50-yr Rainfall=8.53"

Area (sf)	CN	Description
* 2,050	98	IMPERVIOUS
2,050		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment 6S: SUBCATCHMENT 6

Hydrograph



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 50-yr Rainfall=8.53"

Printed 2/13/2026

Page 64

Summary for Subcatchment 7S: SUBCATCHMENT 7

Runoff = 0.40 cfs @ 12.07 hrs, Volume= 0.031 af, Depth> 7.99"
Routed to Pond 1P : RAIN GARDEN


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 50-yr Rainfall=8.53"

Area (sf)	CN	Description
* 2,050	98	IMPERVIOUS
2,050		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment 7S: SUBCATCHMENT 7

Hydrograph



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 50-yr Rainfall=8.53"

Printed 2/13/2026

Page 65

Summary for Subcatchment 8S: SUBCATCHMENT 8

Runoff = 0.38 cfs @ 12.15 hrs, Volume= 0.032 af, Depth> 3.73"
Routed to Reach SP1 : SUMMATION POINT 1


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
Type III 24-hr 50-yr Rainfall=8.53"

Area (sf)	CN	Description
679	55	Woods, Good, HSG B
3,763	61	>75% Grass cover, Good, HSG B
4,442	60	Weighted Average
4,442		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry,

Subcatchment 8S: SUBCATCHMENT 8

Hydrograph



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 50-yr Rainfall=8.53"

Printed 2/13/2026


Page 66

Summary for Reach SP1: SUMMATION POINT 1

Inflow Area = 0.719 ac, 6.96% Impervious, Inflow Depth > 0.77" for 50-yr event
Inflow = 0.38 cfs @ 12.15 hrs, Volume= 0.046 af
Outflow = 0.38 cfs @ 12.15 hrs, Volume= 0.046 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs

Reach SP1: SUMMATION POINT 1



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 50-yr Rainfall=8.53"

Printed 2/13/2026


Page 67

Summary for Reach SP2: SUMMATION POINT 2

Inflow Area = 0.226 ac, 37.64% Impervious, Inflow Depth > 5.52" for 50-yr event
Inflow = 1.46 cfs @ 12.07 hrs, Volume= 0.104 af
Outflow = 1.46 cfs @ 12.07 hrs, Volume= 0.104 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs

Reach SP2: SUMMATION POINT 2



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 50-yr Rainfall=8.53"

Printed 2/13/2026

Page 68

Summary for Pond 1P: RAIN GARDEN

Inflow Area = 0.431 ac, 75.48% Impervious, Inflow Depth > 7.08" for 50-yr event
 Inflow = 3.23 cfs @ 12.02 hrs, Volume= 0.254 af
 Outflow = 2.37 cfs @ 12.11 hrs, Volume= 0.236 af, Atten= 26%, Lag= 5.4 min
 Discarded = 0.02 cfs @ 12.11 hrs, Volume= 0.015 af
 Primary = 2.35 cfs @ 12.11 hrs, Volume= 0.222 af
 Routed to Pond 3P : SUBSURFACE DETENTION
 Secondary = 0.00 cfs @ 5.00 hrs, Volume= 0.000 af
 Routed to Reach SP1 : SUMMATION POINT 1

Routing by Stor-Ind method, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 31.38' @ 12.11 hrs Surf.Area= 1,592 sf Storage= 2,042 cf

Plug-Flow detention time= 71.7 min calculated for 0.236 af (93% of inflow)
 Center-of-Mass det. time= 35.1 min (809.9 - 774.8)

Volume	Invert	Avail.Storage	Storage Description
#1	30.00'	5,850 cf	Custom Stage Data (Prismatic) Listed below

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
30.00	1,200	0	0
31.00	1,500	1,350	1,350
33.50	2,100	4,500	5,850

Device	Routing	Invert	Outlet Devices
#1	Discarded	30.00'	2.400 in/hr Exfiltration over Surface area above 30.00' Excluded Surface area = 1,200 sf
#2	Primary	30.00'	12.0" Round Culvert L= 20.0' CMP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 30.00' / 29.50' S= 0.0250 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#3	Device 2	30.50'	12.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 2	32.80'	12.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Secondary	32.90'	5.0' long x 5.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.34 2.50 2.70 2.68 2.68 2.66 2.65 2.65 2.65 2.65 2.67 2.66 2.68 2.70 2.74 2.79 2.88

Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 50-yr Rainfall=8.53"

Printed 2/13/2026

Page 69

Discarded OutFlow Max=0.02 cfs @ 12.11 hrs HW=31.38' (Free Discharge)

↳ 1=Exfiltration (Exfiltration Controls 0.02 cfs)

Primary OutFlow Max=2.33 cfs @ 12.11 hrs HW=31.38' (Free Discharge)


↳ 2=Culvert (Passes 2.33 cfs of 2.80 cfs potential flow)

↳ 3=Orifice/Grate (Orifice Controls 2.33 cfs @ 3.19 fps)


↳ 4=Orifice/Grate (Controls 0.00 cfs)

Secondary OutFlow Max=0.00 cfs @ 5.00 hrs HW=30.00' (Free Discharge)

↳ 5=Broad-Crested Rectangular Weir (Controls 0.00 cfs)



Pond 1P: RAIN GARDEN



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 50-yr Rainfall=8.53"

Printed 2/13/2026

Page 70

Summary for Pond 2P: INFILTRATION TRENCH

Inflow Area = 0.617 ac, 8.11% Impervious, Inflow Depth > 3.71" for 50-yr event
 Inflow = 1.41 cfs @ 12.50 hrs, Volume= 0.191 af
 Outflow = 0.44 cfs @ 13.45 hrs, Volume= 0.150 af, Atten= 69%, Lag= 57.0 min
 Discarded = 0.13 cfs @ 11.80 hrs, Volume= 0.136 af
 Primary = 0.31 cfs @ 13.45 hrs, Volume= 0.015 af
 Routed to Reach SP1 : SUMMATION POINT 1

Routing by Stor-Ind method, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 31.00' @ 13.45 hrs Surf.Area= 2,300 sf Storage= 3,665 cf

Plug-Flow detention time= 249.6 min calculated for 0.150 af (79% of inflow)
 Center-of-Mass det. time= 170.8 min (1,035.2 - 864.4)

Volume	Invert	Avail.Storage	Storage Description
#1	28.00'	2,157 cf	Custom Stage Data (Prismatic) Listed below (Recalc) 6,900 cf Overall - 1,508 cf Embedded = 5,392 cf x 40.0% Voids
#2	28.50'	754 cf	24.0" Round Pipe Storage Inside #1 L= 240.0'
#3	28.50'	754 cf	24.0" Round Pipe Storage Inside #1 L= 240.0'
		3,665 cf	Total Available Storage

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
28.00	2,300	0	0
31.00	2,300	6,900	6,900

Device	Routing	Invert	Outlet Devices
#1	Discarded	28.00'	2.400 in/hr Exfiltration over Surface area
#2	Primary	31.00'	320.0' long x 5.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.34 2.50 2.70 2.68 2.68 2.66 2.65 2.65 2.65 2.65 2.67 2.66 2.68 2.70 2.74 2.79 2.88

Discarded OutFlow Max=0.13 cfs @ 11.80 hrs HW=28.03' (Free Discharge)
 ↑1=**Exfiltration** (Exfiltration Controls 0.13 cfs)

Primary OutFlow Max=0.09 cfs @ 13.45 hrs HW=31.00' (Free Discharge)
 ↑2=**Broad-Crested Rectangular Weir**(Weir Controls 0.09 cfs @ 0.11 fps)



Post Development

Prepared by Haley Ward


HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 50-yr Rainfall=8.53"

Printed 2/13/2026

Page 71

Pond 2P: INFILTRATION TRENCH



Post Development

Prepared by Haley Ward

HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 50-yr Rainfall=8.53"

Printed 2/13/2026

Page 72

Summary for Pond 3P: SUBSURFACE DETENTION

Inflow Area = 0.431 ac, 75.48% Impervious, Inflow Depth > 6.17" for 50-yr event
 Inflow = 2.35 cfs @ 12.11 hrs, Volume= 0.222 af
 Outflow = 0.19 cfs @ 11.15 hrs, Volume= 0.221 af, Atten= 92%, Lag= 0.0 min
 Discarded = 0.19 cfs @ 11.15 hrs, Volume= 0.221 af

Routing by Stor-Ind method, Time Span= 5.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 30.85' @ 13.88 hrs Surf.Area= 3,500 sf Storage= 4,672 cf

Plug-Flow detention time= 219.9 min calculated for 0.221 af (100% of inflow)
 Center-of-Mass det. time= 219.5 min (1,021.2 - 801.7)

Volume	Invert	Avail.Storage	Storage Description
#1	28.00'	3,748 cf	Custom Stage Data (Prismatic) Listed below (Recalc) 10,500 cf Overall - 1,131 cf Embedded = 9,369 cf x 40.0% Voids
#2	28.50'	377 cf	24.0" Round Pipe Storage Inside #1 L= 120.0'
#3	28.50'	377 cf	24.0" Round Pipe Storage Inside #1 L= 120.0'
#4	28.50'	377 cf	24.0" Round Pipe Storage Inside #1 L= 120.0'
		4,879 cf	Total Available Storage

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
28.00	3,500	0	0
31.00	3,500	10,500	10,500

Device	Routing	Invert	Outlet Devices
#1	Discarded	28.00'	2.400 in/hr Exfiltration over Surface area

Discarded OutFlow Max=0.19 cfs @ 11.15 hrs HW=28.03' (Free Discharge)
 ↑ 1=Exfiltration (Exfiltration Controls 0.19 cfs)

Pond 3P: SUBSURFACE DETENTION

Exfiltration

Post Development

Prepared by Haley Ward


HydroCAD® 10.20-7a s/n 00641 © 2025 HydroCAD Software Solutions LLC



Type III 24-hr 50-yr Rainfall=8.53"

Printed 2/13/2026

Page 73

Pond 3P: SUBSURFACE DETENTION






LOCATION MAP: USGS QUADRANGLE: KITTERY
 MAPTECH® USGS TOPOGRAPHIC SERIES™
 SCALE: 1"=2000'
 ©MAPTECH®, INC. 978-933-3000
 WWW.MAPTECH.COM/TOPO



PRE LEGEND:

	PROPERTY LINE
	WATERSHED BOUNDARY LINE
	WATERSHED DESIGNATION
	TIME OF CONCENTRATION FLOW PATH
	FLOW PATH DESCRIPTION
	SHEET FLOW
	SHALLOW CONCENTRATED FLOW
	CHANNEL FLOW
	PIPE FLOW



FILE LOCATION: P:\NH\010114\BUILD_MERGE\2025\1151 SAGAMORE AVE - PORTSMOUTH - HYDROCAD_FILES\CAD_FILES\CAD\HYDROCAD\2025\1151 SAGAMORE AVE - PORTSMOUTH - HYDROCAD - 2025.12.22.dwg, 2025.12.16, 8:00 AM


1	2025.01.16	REVISED PER TAC REVIEW COMMENTS	PJM	DJO			
REV.	DATE	DESCRIPTION	BY	CHK.			
DRAWING ISSUE STATUS							
ISSUED FOR PERMITTING							
		HALEY WARD					
WWW.HALEYWARD.COM		200 Griffin Rd., Unit 14 Portsmouth, New Hampshire 03801 603.430.9282					
PROJECT							
1151 SAGAMORE AVENUE CBC, LLC 1151 SAGAMORE AVE., PORTSMOUTH, NH							
TITLE							
PRE-DEVELOPMENT HYDROLOGY PLAN							
		DATE	2025.12.22	SCALE	1"=30'		
		DRAWN BY	BLO/PJM	DESIGNED BY	BLO/PJM	CHECKED BY	DJO
		PROJECT No.	5010314.002			REV.	
		DRAWING No.	C701			REV.	1



LOCATION MAP: USGS QUADRANGLE: KITTERY
 MAPTECH® USGS TOPOGRAPHIC SERIES™
 SCALE: 1"=2000'
 ©MAPTECH®, INC. 978-933-3000
 WWW.MAPTECH.COM/TOPO

POST LEGEND:

	PROPERTY LINE
	WATERSHED BOUNDARY LINE
	WATERSHED DESIGNATION
	TIME OF CONCENTRATION FLOW PATH
	FLOW PATH DESCRIPTION
	SHEET FLOW
	SHALLOW CONCENTRATED FLOW
	CHANNEL FLOW
	PIPE FLOW



1	2025.01.16	REVISED PER TAC REVIEW COMMENTS	PJM	DJO
REV.	DATE	DESCRIPTION	BY	CHK.

DRAWING ISSUE STATUS

ISSUED FOR PERMITTING

200 Griffin Rd., Unit 14
 Portsmouth, New Hampshire 03801
 603.430.9282

PROJECT

1151 SAGAMORE AVENUE CBC, LLC
 1151 SAGAMORE AVE., PORTSMOUTH, NH


TITLE

POST DEVELOPMENT HYDROLOGY PLAN


DATE: 2025.12.22		SCALE: 1"=30'	
DRAWN BY: BLO/PJM	DESIGNED BY: BLO/PJM	CHECKED BY: DJO	
PROJECT No.: 5010314.002		DRAWING No.: C702	
DREW JOHN OLEHOWSKI No. 18516 LICENSED PROFESSIONAL ENGINEER 01/16/2026		1	

FILE LOCATION: P:\PROJECTS\1151 SAGAMORE AVE - PORTSMOUTH - HYDROCAD - FILED\CAD - FILED\CAD - HYDROCAD - 2025.01.16, 8:00 AM

Hydrologic Soil Group—Rockingham County, New Hampshire




Map Scale: 1:1,260 if printed on A portrait (8.5" x 11") sheet.



MAP LEGEND

Area of Interest (AOI)









 Area of Interest (AOI)

Soils

Soil Rating Polygons





 A
 A/D
 B
 B/D
 C
 C/D
 D
 Not rated or not available

Soil Rating Lines


 A
 A/D
 B
 B/D
 C
 C/D
 D
 Not rated or not available

Soil Rating Points






 A
 A/D
 B
 B/D

 C
 C/D
 D
 Not rated or not available


Water Features

 Streams and Canals

Transportation

 Rails
 Interstate Highways
 US Routes
 Major Roads
 Local Roads

Background

 Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
 Web Soil Survey URL:
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Rockingham County, New Hampshire
 Survey Area Data: Version 28, Sep 9, 2025

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Jun 19, 2020—Sep 20, 2020

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Hydrologic Soil Group

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
140B	Chatfield-Hollis-Canton complex, 0 to 8 percent slopes, rocky	B	3.5	84.8%
140D	Chatfield-Hollis-Canton complex, 15 to 35 percent slopes, rocky	B	0.2	4.9%
699	Urban land		0.4	10.3%
Totals for Area of Interest			4.2	100.0%

Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

Rating Options

Aggregation Method: Dominant Condition

Component Percent Cutoff: None Specified

Tie-break Rule: Higher

From the test pit observations taken 7/16/2025 and the Test Pit log created from this reading it is determined that the Soil Permeability Class for the Receiving Layer (0-16") to be Moderate to Moderately Rapid. This permeability Class equates to a permeability rate of 6 cm/hr. This is converted to 26 MPI.

SOIL DESCRIPTION

Soil type:		Map Unit Symbol:		File No:	
Area:		Date:		Described by:	
Location				Photo Number:	
Native Veg.				Climate:	
Parent material					
Relief				% Slope	Aspect:
Elevation		Drainage		Gr. water	

Additional notes:

	Soil Profile / Landscape Sketch

Hori- zon	Depth Inches	Color Moist	Color Redox Features	% Redox	Texture	Structure	Consistence Moist	Boun- -dary	Roots	% Frag
B	0-10"	10YR 4/4	N/A	6	Silt & loam	Friable	Ledge		Yes	
	12"-18"	10YR 4/6	N/A		Sandy loam	Friable	Firming		No	
	18"-41"	10YR 4/6	18 = Est HWT		Silt & loam	Angular Blocky	Firm		↓	
Ledge	41"	Restrictive ledge	10YR 4/6 2.5 6/2			↓ Platy				

TABLE 17A
Visual indicators of permeability: structural characteristics of soil

<i>Permeability class (Table 15)</i>	<i>Structure, type and class (Sec 73) (1)</i>	<i>Structure, grade and consistency (Secs 72 + 80) (2)</i>	<i>Relationship of horizontal and vertical axes, overlap, cleavage, and its direction (3)</i>	<i>Porosity channels and cracks (4)</i>
Very slow permeability	<p>Massive</p> <p>Irregular blocky; often assuming a columnar structure</p> <p>Structureless</p>	<p>Very strong</p> <p>Clods are very strong and cannot be broken by hand. More force is required to break the blocks vertically than horizontally. Horizontal breakage is usually along the block faces and in some instances the small irregular angular blocks can be flaked off horizontally.</p> <p>It is usually difficult to break into the mass, but once broken in, the small indurated lumps pulverize easily.</p>	<p>Where the irregular blocky structure dominates, the irregular fragments are very firmly developed with a longer horizontal than vertical axis and with sharp angles. These are meshed shingle-fashion with about 50 percent horizontal overlap. Under proper moisture conditions, the medium to coarse irregular angular blocks break along definite cleavage to fine irregular, angular blocky structure, the arrangement remaining the same regardless of size.</p>	<p>Without visible pores.</p> <p>The individual blocks have no visible pores, but some tortuous vertical channels that seem to follow block faces are discernible, usually at 2- to 5-cm intervals which seldom extend more than 5-8 cm without a horizontal jog.</p>
Slow permeability	<p>Fine to medium irregular blocky</p> <p>Usually platy, sometimes structureless</p>	<p>More force is required to break the blocks along the vertical than the horizontal axis. The broken faces tend to assume a saw-toothed appearance.</p> <p>Plates broken horizontally fracture along straight smooth lines, the laminated layers seeming to be made of small flattish "chips" that can be easily removed by tweezers.</p>	<p>The irregular angular blocks have sharp angles and the horizontal axes are longer than the vertical. The blocks are generally meshed shingle-fashion with about 40 percent horizontal overlap. Horizontal bedding can be easily detected in "chip" form, generally lying in shingle-fashion with horizontal overlap of 40-50 percent or more. Sometimes the thin, laminated layers are continuous.</p>	<p>There are very few small pores discernible. The apparent vertical cracks which follow the block surfaces seldom extend more than a few cm before jogs of 2-5 cm appear.</p> <p>Only a few very fine vertical pores are visible. Flow of water follows apparently tortuous lines around the main chips.</p>
Moderately slow permeability	<p>Medium to fine irregular blocky, fragmental</p>	<p>The blocks (clods) and fragments are less firm and stable than those of the slower permeability classes. They can be more easily broken along the vertical axes.</p>	<p>The angle of the blocks and fragments is not sharp and often very slightly rounded. The horizontal axis is only slightly longer than the vertical. The structural fragments overlap 20-25 percent. If the overlap is oblique, the size of fragments may be larger and the overlap more than 25 percent.</p>	<p>Pores are fine but moderately numerous. The oblique overlap is indicative of freer air and water movement. Root penetration is noticeable.</p>
Moderate permeability	<p>Fine to medium subangular blocky (nut-like), partially rounded, some obtuse angles</p>	<p>Cohesion of soil materials is moderate and clods are easily broken by hand, but seldom fractured unless broken individually.</p>	<p>The clods or blocks overlap only slightly and many vertical fractures are almost straight. Cleavage generally occurs along the faces of the nutforn aggregates.</p>	<p>Pores are medium to fine and numerous.</p>
Moderately rapid permeability	<p>Medium subangular blocky (nutforn) coarse granular or crumb structure</p>	<p>The structural aggregates are not firmly developed and the cohesion of soil material is moderately weak.</p>	<p>Vertical cleavage is nearly always along aggregate faces and follows approximately straight vertical or oblique lines, with only occasional slight overlap of structural aggregates.</p>	<p>Pores in the aggregate are large and numerous.</p>
Rapid permeability	<p>Crumb structure (sometimes ranging toward a single-grain condition)</p>	<p>Consistency ranges from slightly plastic when wet to friable or crumbly when dry.</p>		<p>Pore space is large.</p>
Very rapid permeability	<p>Single-grain structure</p>	<p>Consistency ranges from non-plastic when wet to incoherent when moist or dry.</p>		

TABLE 17 B
Visual Indicators of permeability: texture, physical behaviour and colour of soil

<i>Permeability class (Table 15)</i>	<i>Texture and profile</i>	<i>Physical behaviour</i>	<i>Colour and mottling</i>
Very slow permeability	Claypans, heavy clay, or in presence of very slowly permeable substratum	Soil cracks severely on drying with exception of hardpan or indurated layers which do not crack or fracture.	Generally mottled.
	Hardpan as distinguished from claypan	The hardpan layers associated with this class often consist of highly indurated layers of sand or sand and gravel. These usually give out a ringing sound when struck with a spade.	High degree of mottling.
Slow permeability	Clay or silty clay, claypans, moderately indurated layers	Shrinkage and cracking are less pronounced than in the very slowly permeable class.	Mottling is moderately strong.
	Silt, "siltpan"		Moderately strong mottling and greyish colour are indications of this type of structure.
Moderately slow permeability	Moderately fine-textured horizons, showing a small amount of granulation or a slight dispersion of particles	Shrinkage is usually not very pronounced and cracks are neither large nor numerous.	Mottling is moderate, but the colour is brighter than for the slow permeability class.
Moderate permeability	Moderately fine textures, slightly plastic when wet and moderately hard when dry		Mottling is generally slight.
Moderately rapid permeability	Moderately fine to medium-textured soils		Occasional mottling. Colour is generally moderately bright yellow.
Rapid permeability	Medium or moderately coarse-textured soils		There are no mottlings unless water-table is high. Colour is generally very bright. Organic matter content is usually moderate or low.
Very rapid permeability	Coarse-textured or gravelly soils		Colour is bright unless the water-table is high.

TABLE 15
Soil permeability classes for agriculture and conservation


Soil permeability classes	Permeability rates ¹	
	cm/hour	cm/day
Very slow	Less than 0.13	Less than 3
Slow	0.13 - 0.3	3 - 12
Moderately slow	0.5 - 2.0	12 - 48
Moderate	2.0 - 6.3	48 - 151
Moderately rapid	6.3 - 12.7	151 - 305
Rapid	12.7 - 25	305 - 600
Very rapid	More than 25	More than 600

		Conversion Table: cm/h to min/inch				
		cm/hr	min/inch		cm/hr	min/inch
60 MPI Slowest Allowable Design		1	152.40		41	3.72
		2	76.20		42	3.63
		3	50.80		43	3.54
		4	38.10		44	3.46
		5	30.48		45	3.39
		6	25.40		46	3.31
		7	21.77		47	3.24
		8	19.05		48	3.18
		9	16.93		49	3.11
		10	15.24		50	3.05
		11	13.85		51	2.99
		12	12.70		52	2.93
		13	11.72		53	2.88
		14	10.89		54	2.82
		15	10.16		55	2.77
		16	9.53		56	2.72
		17	8.96		57	2.67
		18	8.47		58	2.63
		19	8.02		59	2.58
		20	7.62		60	2.54
		21	7.26		61	2.50
		22	6.93		62	2.46
		23	6.63		63	2.42
		24	6.35		64	2.38
		25	6.10		65	2.34

National Flood Hazard Layer FIRMMette



70°45'12"W 43°3'21"N



1:6,000

70°44'35"W 43°2'54"N

Basemap Imagery Source: USGS National Map 2023

Legend

SEE FIS REPORT FOR DETAILED LEGEND AND INDEX MAP FOR FIRM PANEL LAYOUT

- | | | |
|------------------------------------|--|--|
| SPECIAL FLOOD HAZARD AREAS | | Without Base Flood Elevation (BFE)
<i>Zone A, V, A99</i> |
| | | With BFE or Depth <i>Zone AE, AO, AH, VE, AR</i> |
| | | Regulatory Floodway |
| OTHER AREAS OF FLOOD HAZARD | | 0.2% Annual Chance Flood Hazard, Areas of 1% annual chance flood with average depth less than one foot or with drainage areas of less than one square mile <i>Zone X</i> |
| | | Future Conditions 1% Annual Chance Flood Hazard <i>Zone X</i> |
| | | Area with Reduced Flood Risk due to Levee. See Notes. <i>Zone X</i> |
| | | Area with Flood Risk due to Levee <i>Zone D</i> |
| OTHER AREAS | | NO SCREEN Area of Minimal Flood Hazard <i>Zone X</i> |
| | | Effective LOMRs |
| GENERAL STRUCTURES | | Area of Undetermined Flood Hazard <i>Zone D</i> |
| | | Channel, Culvert, or Storm Sewer |
| | | Levee, Dike, or Floodwall |
| OTHER FEATURES | | 20.2 Cross Sections with 1% Annual Chance |
| | | 17.5 Water Surface Elevation |
| | | Coastal Transect |
| | | Base Flood Elevation Line (BFE) |
| | | Limit of Study |
| | | Jurisdiction Boundary |
| | | Coastal Transect Baseline |
| | | Profile Baseline |
| | | Hydrographic Feature |
| MAP PANELS | | Digital Data Available |
| | | No Digital Data Available |
| | | Unmapped |
| | | The pin displayed on the map is an approximate point selected by the user and does not represent an authoritative property location. |



This map complies with FEMA's standards for the use of digital flood maps if it is not void as described below. The basemap shown complies with FEMA's basemap accuracy standards

The flood hazard information is derived directly from the authoritative NFHL web services provided by FEMA. This map was exported on **9/27/2023 at 1:41 PM** and does not reflect changes or amendments subsequent to this date and time. The NFHL and effective information may change or become superseded by new data over time.

This map image is void if the one or more of the following map elements do not appear: basemap imagery, flood zone labels, legend, scale bar, map creation date, community identifiers, FIRM panel number, and FIRM effective date. Map images for unmapped and unmodernized areas cannot be used for regulatory purposes.



INSPECTION & LONG-TERM MAINTENANCE PLAN FOR PROPOSED RESIDENTIAL DEVELOPMENT

**1151 SAGAMORE AVENUE
PORTSMOUTH, NH**

Introduction

The intent of this plan is to provide 1151 Sagamore Avenue CBC, LLC (herein referred to as “owner”) with a list of procedures that document the inspection and maintenance requirements of the stormwater management system for this development. Specifically, the Rain Garden and associated structures on the project site (collectively referred to as the “Stormwater Management System”). The contact information for the owner shall be kept current, and if there is a change of ownership of the property this plan must be transferred to the new owner.

The following inspection and maintenance program is necessary to keep the stormwater management system functioning properly and will help in maintaining a high quality of stormwater runoff to minimize potential environmental impacts. By following the enclosed procedures, the owner will be able to maintain the functional design of the stormwater management system and maximize its ability to remove sediment and other contaminants from site generated stormwater runoff.

Annual Report

The owner shall prepare an annual Inspection & Maintenance Report. The report shall include a summary of the system’s maintenance and repair by transmission of the Inspection & Maintenance Log and other information as required. A copy of the report shall be delivered annually to the City of Portsmouth Public Works Department, as required.

Inspection & Maintenance Checklist/Log

The following pages contain the Stormwater Management System Inspection & Maintenance Requirements and a blank copy of the Stormwater Management System Inspection & Maintenance Log. These forms are provided to the owner as a guideline for performing the inspection and maintenance of the Stormwater Management System. This is a guideline and should be periodically reviewed for conformance with current practice and standards.



Stormwater Management System Components

The Stormwater Management System is designed to mitigate both the quantity and quality of site-generated stormwater runoff. As a result, the design includes the following elements:

Non-Structural BMPs

Non-Structural best management practices (BMP's) include temporary and permanent measures that typically require less labor and capital inputs and are intended to provide protection against erosion of soils. Examples of non-structural BMP's on this project include but are not limited to:

- Temporary and Permanent mulching
- Temporary and Permanent grass cover
- Trees
- Shrubs and ground covers
- Miscellaneous landscape plantings
- Dust control
- Tree protection
- Topsoiling
- Sediment barriers
- Stabilized construction entrance
- Vegetated buffer area

Structural BMPs

Structural BMPs are more labor and capital-intensive structures or installations that require more specialized personnel to install. Examples on this project include but are not limited to:

- Rain Garden
- Outlet Control Structures and Storm Drains

Inspection and Maintenance Requirements

The following summarizes the inspection and maintenance requirements for the various BMPs that may be found on this project.

- 1. Grassed areas (until established):** After each rain event of 0.5" or more during a 24-hour period, inspect grassed areas for signs of disturbance, such as erosion. If damaged areas are discovered, immediately repair the damage. Repairs may include adding new topsoil, lime, seed, fertilizer and mulch.



2. **Plantings:** Planting and landscaping (trees, shrubs) shall be monitored bi-monthly during the first year to insure viability and vigorous growth. Replace dead or dying vegetation with new stock and make adjustments to the conditions that caused the dead or dying vegetation. During dryer times of the year, provide weekly watering or irrigation during the establishment period of the first year.

Make the necessary adjustments to ensure long-term health of the vegetated covers, i.e. provide more permanent mulch or compost or other means of protection.
3. **Vegetated buffer area:** Check for scour or sediment buildup in buffer area, at least annually. Replace any vegetation removed by scour or sediment buildup with similar vegetation.
4. **Rain Garden:** After installation of the rain garden, perform the following inspections on a monthly basis:
 - a. Monitor for excessive or concentrated accumulations of debris, or excessive erosion below the various pipe inlets. Remove debris as required and replace or add inlet fabric strips or rip rap stones.
 - b. Monitor the outflow for problems with erosion. Repair as required.
 - c. After significant rainfalls, monitor rain garden surfaces for ponding of water. If water remains flooded over the surface 24 hours after a 1” rainfall, then investigate the cause, if not related to overflow blockage, then excavate and replace filter media.
 - d. Monitor vegetation on rain garden and replace dead or dying vegetation as required.
 - e. Monitor rain garden for rodent borrows and repair as required; remove persistent occupiers.
 - f. Monitor side slopes of rain garden for damage or erosion—repair, as necessary.
5. **Outlet Control Structures and Storm Drains:** Monitor accumulation of debris in outlet control structures monthly or after significant rain events. Remove sediments when they accumulate within the yard drains and outlet pipe. During construction, maintain inlet protection until the site has been stabilized. Prior to the end of construction, inspect the drains and basins for accumulations and remove and clean by jet-vacuuming.

Pollution Prevention

The following pollution prevention activities shall be undertaken to minimize potential impacts on stormwater runoff quality. The Contractor is responsible for all activities during construction. The Owner is responsible thereafter.



Spill Procedures: Any discharge of waste oil or other pollutant shall be reported immediately to the New Hampshire Department of Environmental Services (NHDES). The Contractor/Owner will be responsible for any incident of groundwater contamination resulting from the improper discharge of pollutants to the stormwater system, and may be required by NHDES to remediate incidents that may impact groundwater quality. If the property ownership is transferred, the new owner will be informed of the legal responsibilities associated with operation of the stormwater system, as indicated above.

Sanitary Facilities: Sanitary facilities shall be provided during all phases of construction.

Material Storage: No on site trash facility is provided until homes are constructed. The contractors are required to remove trash from the site. Hazardous material storage is prohibited.

Material Disposal: All waste material, trash, sediment, and debris shall be removed from the site and disposed of in accordance with applicable local, state, and federal guidelines and regulations. Removed sediments shall be if necessary dewatered prior to disposal.

Invasive Species

Monitor the Stormwater Management System for signs of invasive species growth. If caught early, their eradication is much easier. The most likely places where invasions start is in wetter, disturbed soils or detention ponds. Species such as phragmites and purple loose-strife are common invaders in these wetter areas. If they are found, the owner shall refer to the fact-sheet created by the University of New Hampshire Cooperative Extension (or other source) or contact a wetlands scientist with experience in invasive species control to implement a plan of action for eradication. Measures that do not require the application of chemical herbicides should be the first line of defense.



Figure 1: *Lythrum salicaria*, Purple Loosestrife. Photo by Liz West. Figure 2: *Phragmites australis*. Photo by Le Loup Gris

RAIN GARDEN MAINTENANCE SHEET

INSPECTION REQUIREMENTS		
ACTION TAKEN	FREQUENCY	MAINTENANCE REQUIREMENTS
<p><i>-Inspect pond surface for the occurrence of sediment, trash, debris, or structural damage.</i></p>	<p>Bi-Yearly and following major storm events</p>	<p><i>-Remove sediments, trash, and debris, as necessary.</i></p> <p><i>-Repair outlet structures and appurtenances, as necessary.</i></p>
<p><i>-Check to see if pond drains within 72 hours of rainfall.</i></p> <p><i>-Check vegetation health.</i></p>	<p>Annually</p>	<p><i>-If system does not drain within 72 hours of a rainfall event, consult a qualified professional about restoration of function of the dry well.</i></p> <p><i>-Vegetation should be maintained and pruned.</i></p> <p><i>-Dead or diseased vegetation should be removed, as well as any invasive species.</i></p>

MAINTENANCE LOG	
PROJECT NAME	
INSPECTOR NAME	INSPECTOR CONTACT INFO
DATE OF INSPECTION	REASON FOR INSPECTION <input type="checkbox"/> LARGE STORM EVENT <input type="checkbox"/> PERIODIC CHECK-IN
IS CORRECTIVE ACTION NEEDED? <input type="checkbox"/> YES <input type="checkbox"/> NO	DESCRIBE ANY PROBLEMS, NEEDED MAINTENANCE
DATE OF MAINTENANCE	PERFORMED BY
NOTES	

CLOSED DRAINAGE STRUCTURE LONG-TERM MAINTENANCE SHEET

INSPECTION REQUIREMENTS		
ACTION TAKEN	FREQUENCY	MAINTENANCE REQUIREMENTS
<ul style="list-style-type: none"> -Outlet Control Structures -Drain Manholes -Catch Basins 	Monthly for 1 year following construction, Every other Month thereafter	<i>Check for erosion or short-circuiting</i> <i>Check for sediment accumulation</i> <i>Check for floatable contaminants</i>
<ul style="list-style-type: none"> -Drainage Pipes 	Monthly for 1 year following construction, 1 time per 2 years thereafter	<i>Check for sediment accumulation/clogging, or soiled runoff.</i> <i>Check for erosion at outlets.</i>

MAINTENANCE LOG	
PROJECT NAME	
INSPECTOR NAME	INSPECTOR CONTACT INFO
DATE OF INSPECTION	REASON FOR INSPECTION <input type="checkbox"/> LARGE STORM EVENT <input type="checkbox"/> PERIODIC CHECK-IN
IS CORRECTIVE ACTION NEEDED? <input type="checkbox"/> YES <input type="checkbox"/> NO	DESCRIBE ANY PROBLEMS, NEEDED MAINTENANCE
DATE OF MAINTENANCE	PERFORMED BY
NOTES	

STABILIZED CONSTRUCTION ENTRANCE CONSTRUCTION MAINTENANCE SHEET

INSPECTION REQUIREMENTS		
ACTION TAKEN	FREQUENCY	MAINTENANCE REQUIREMENTS
ENTRANCE SURFACE <i>-Check for sediment accumulation/clogging of stone</i>	After heavy rains, as necessary	<i>-Top dress pad with new stone. -Replace stone completely if completely clogged.</i>
WASHING FACILITIES (if applicable) <i>-Monitor Sediment Accumulation</i>	As often as necessary	<i>-Remove Sediments from traps.</i>

MAINTENANCE LOG	
PROJECT NAME	
INSPECTOR NAME	INSPECTOR CONTACT INFO
DATE OF INSPECTION	REASON FOR INSPECTION <input type="checkbox"/> LARGE STORM EVENT <input type="checkbox"/> PERIODIC CHECK-IN
IS CORRECTIVE ACTION NEEDED? <input type="checkbox"/> YES <input type="checkbox"/> NO	DESCRIBE ANY PROBLEMS, NEEDED MAINTENANCE
DATE OF MAINTENANCE	PERFORMED BY
NOTES	

CONSULTANTS

**PROGRESS
PRINT**

NOT FOR CONSTRUCTION

PROJECT

**1151 SAGAMORE
AVENUE - UNIT 1**

PORTSMOUTH NH

OWNER

Owner

REVISION SCHEDULE

No.	Date	Description

Project Phase SCHEMATIC

Proj Issue Date N/A

Project No. 2511

COPYRIGHT
William Frangos Architect 2026


SHEET TITLE

Basement Plan


SHEET ISSUE DATE: 3/17/2026

A-101

SHEET 1 OF 5



1 0.0 BSMT
1/4" = 1'-0"



CONSULTANTS

**PROGRESS
PRINT**

NOT FOR CONSTRUCTION

PROJECT

**1151 SAGAMORE
AVENUE - UNIT 1**

PORTSMOUTH NH

OWNER

Owner

REVISION SCHEDULE		
No.	Date	Description

Project Phase SCHEMATIC
Proj Issue Date N/A
Project No. 2511

COPYRIGHT
William Frangos Architect 2026


SHEET TITLE

First Floor Plan

SHEET ISSUE DATE: 3/17/2026

A-102

SHEET 2 OF 5




1 1.0 FLR
1/4" = 1'-0"


OPTION: WRAP STEP, GAR SIDE &
ENTIRE FRONT (L-CONFIG)

C:\Users\William Frangos\Documents\AR REV\1151-Sagamore Av\2511 1151-SA 26.03.19 SD-ATTIC.M

3/24/2026 12:06:17 PM



① 2.0 FLR
1/4" = 1'-0"



**William Frangos
Architect**

500 Cummings Center, Suite 6500
Beverly MA 01915-6234

O: 978 927 9419
F: 978 927 9417

CONSULTANTS

**PROGRESS
PRINT**
NOT FOR CONSTRUCTION

PROJECT
**1151 SAGAMORE
AVENUE - UNIT 1**

PORTSMOUTH NH

OWNER

Owner

REVISION SCHEDULE		
No.	Date	Description

Project Phase SCHEMATIC
Proj Issue Date N/A
Project No. 2511

COPYRIGHT
William Frangos Architect 2026

SHEET TITLE
Second Floor Plan

SHEET ISSUE DATE: 3/17/2026

A-103

SHEET 3 OF 5

CONSULTANTS

**PROGRESS
PRINT**

NOT FOR CONSTRUCTION

PROJECT
**1151 SAGAMORE
AVENUE - UNIT 1**

PORTSMOUTH NH

OWNER

Owner

REVISION SCHEDULE		
No.	Date	Description

Project Phase SCHEMATIC
Proj Issue Date N/A
Project No. 2511

COPYRIGHT
William Frangos Architect 2026



SHEET TITLE

Elevations

SHEET ISSUE DATE: 3/17/2026


A-201

SHEET 4 OF 5



② NORTH
1/4" = 1'-0"

① SOUTH - FACADE
1/4" = 1'-0"



William Frangos
Architect

500 Cummings Center, Suite 6500
Beverly MA 01915-6234

O: 978 927 9419
F: 978 927 9417

CONSULTANTS

**PROGRESS
PRINT**

NOT FOR CONSTRUCTION

PROJECT

1151 SAGAMORE
AVENUE - UNIT 1

PORTSMOUTH NH

OWNER

Owner

REVISION SCHEDULE

No.	Date	Description
-----	------	-------------

Project Phase SCHEMATIC

Proj Issue Date N/A

Project No. 2511

COPYRIGHT
William Frangos Architect 2026

SHEET TITLE

Elevations

SHEET ISSUE DATE: 3/17/2026

A-202

SHEET 5 OF 5


C:\Users\William Frangos\Documents\AR REV\2511 1151-Sagamore Av\2511 1151-SA 26.03.19 SD-ATTIC.M

3/24/2026 12:09:10 PM



① EAST
1/4" = 1'-0"

② WEST
1/4" = 1'-0"



PROJECT NAME & ADDRESS:

1151 Sagamore Ave

DATE:

1.16.2026

MAP & LOT:

224/19

Description**Quantity Unit Unit Price Total****Yellow cells are the ONLY editable items***Site Preparation****\$ 17,406.20**

Clearing & Grubbing	0	AC	\$ 12,000.00	\$ -
Removal of Pipe Lines ≤ 24"		LF	\$ 18.00	\$ -
Removal of Pipe Lines > 24"		LF	\$ 36.00	\$ -
Common Excavation	500	CY	\$ 16.00	\$ 8,000.00
Unsuitable Excavation		CY	\$ 36.00	\$ -
Ledge Excavation	75	CY	\$ 125.00	\$ 9,375.00
Saw Cut Pavement	12	LF	\$ 2.60	\$ 31.20

Roads**\$ 147,264.00**

Screened Sand	420	CY	\$ 25.00	\$ 10,500.00	Utility Trench fill material
Granular/Common Fill	2200	CY	\$ 32.00	\$ 70,400.00	Fill material to leve and grade site
Gravel Backfill (304.2)	700	CY	\$ 36.00	\$ 25,200.00	See Below*
Crushed Gravel (304.3)	131	CY	\$ 36.00	\$ 4,716.00	Asphalt sub base
Crushed Stone - Fine Gradation (304.4)		CY	\$ 40.00	\$ -	
Crushed Stone - Coarse Gradation (304.5)		CY	\$ 42.00	\$ -	
Hot Bituminous Pavement - Hand Method		TON	\$ 170.00	\$ -	
Hot Bituminous Pavement - Machine Method	220	TON	\$ 150.00	\$ 33,000.00	
Pavement Prep for Top Coat if placed over 1-yr after Base Coat		SY	\$ 1.00	\$ -	
Cold Plane		SY	\$ 6.50	\$ -	
Reclaim Pavement		SY	\$ 4.00	\$ -	
Fine Grading	790	SY	\$ 3.00	\$ 2,370.00	
Concrete Sidewalk 4"		SY	\$ 62.00	\$ -	
Bituminous Sidewalk 3"		SY	\$ 44.00	\$ -	
Straight Granite Curb	250	LF	\$ 40.00	\$ 10,000.00	
Curved Granite Curb		LF	\$ 50.00	\$ -	
Reset Granite Curb		LF	\$ 21.00	\$ -	
Bituminous Curb, Type B 6" Reveal		LF	\$ 12.00	\$ -	
Traffic Sign with Post		EA	\$ 320.00	\$ -	
Lightpole Base and Fixture		EA	\$ 12,000.00	\$ -	
Cobra Head Light onto Existing Pole		EA	\$ 1,170.00	\$ -	
Conduit Duct Bank (4" SCH 80 - 2 Pipes)		LF	\$ 80.00	\$ -	
Conduit Duct Bank (4" SCH 80 - 3 Pipes)		LF	\$ 100.00	\$ -	
Conduit Duct Bank (4" SCH 80 - 4 Pipes)		LF	\$ 120.00	\$ -	
Traffic Loop Detectors		EA	\$ 1,000.00	\$ -	
Retroflective Paint Marking - 4" Line	310	LF	\$ 1.20	\$ 372.00	
Retroflective Paint Pavement Marking - Symbol or Word	6	EA	\$ 51.00	\$ 306.00	
Retroflective Thermoplastic Pavement Marking - ≤ 12" Line		LF	\$ 3.20	\$ -	
Retroflective Thermoplastic Pavement Marking - Symbol		EA	\$ 130.00	\$ -	
Obliterate Pavement Marking - ≤12" Line		LF	\$ 1.00	\$ -	
Guardrail (Steel rail and posts)	20	LF	\$ 45.00	\$ 900.00	

Structural**\$ -**

Mechanically Stabilized Earth Retaining Wall		SF	\$ 50.00	\$ -
Retaining Wall - Modular Block		SF	\$ 54.00	\$ -

Utilities**\$ 129,339.00**

Catch Basin with Frame, Grate & Hood	2	EA	\$ 4,800.00	\$ 9,600.00
Special Catch Basins (i.e. Tree Box Filters)		EA	\$ 5,600.00	\$ -
Box Culvert ≤ 36' x 60'		LF	\$ 500.00	\$ -

Box Culvert ≥ 36' x 60'		LF	\$	680.00	\$	-
Drop Inlet		EA	\$	3,200.00	\$	-
MH - 4' Dia. w/ Base and Top		VF	\$	480.00	\$	-
MH - 5' Dia. w/ Base and Top		VF	\$	520.00	\$	-
MH - 6' Dia. w/ Base and Top		VF	\$	640.00	\$	-
MH - 8' Dia. w/ Base and Top		VF	\$	940.00	\$	-
Remove and Reset CB, DI Grate and Frame		EA	\$	500.00	\$	-
Reconstruct / Adjust Drainage Manholes		EA	\$	1,000.00	\$	-
Outlet/Inlet Control Structure	1	EA	\$	6,100.00	\$	6,100.00
Riprap		CY	\$	64.00	\$	-
Perf Underdrain ≤ 6"	375	LF	\$	58.00	\$	21,750.00
Perf Underdrain > 6"		LF	\$	90.00	\$	-
12" RC Pipe - Class III		LF	\$	125.00	\$	-
15" RC Pipe - Class IV		LF	\$	140.00	\$	-
18" RC Pipe - Class IV		LF	\$	156.00	\$	-
24" RC Pipe - Class IV		LF	\$	204.00	\$	-
30" RC Pipe - Class IV		LF	\$	240.00	\$	-
36" RC Pipe - Class IV		LF	\$	285.00	\$	-
48" RC Pipe - Class V		LF	\$	400.00	\$	-
12" RCP - End Sections		EA	\$	780.00	\$	-
15" RCP - End Sections		EA	\$	880.00	\$	-
18" RCP - End Sections		EA	\$	980.00	\$	-
24" RCP - End Sections		EA	\$	1,200.00	\$	-
30" RCP - End Sections		EA	\$	1,300.00	\$	-
36" RCP - End Sections		EA	\$	1,500.00	\$	-
48" RCP - End Sections		EA	\$	1,800.00	\$	-
12" Plastic Corrugated/Smooth Pipe	250	LF	\$	85.00	\$	21,250.00
15" Plastic Corrugated/Smooth Pipe		LF	\$	98.00	\$	-
18" Plastic Corrugated/Smooth Pipe		LF	\$	120.00	\$	-
24" Plastic Corrugated/Smooth Pipe		LF	\$	180.00	\$	-
30" Plastic Corrugated/Smooth Pipe		LF	\$	200.00	\$	-
36" Plastic Corrugated/Smooth Pipe		LF	\$	260.00	\$	-
12" Plastic Flared End Sections		EA	\$	300.00	\$	-
15" Plastic Flared End Sections		EA	\$	310.00	\$	-
18" Plastic Flared End Sections		EA	\$	340.00	\$	-
24" Plastic Flared End Sections		EA	\$	400.00	\$	-
30" Plastic Flared End Sections		EA	\$	540.00	\$	-
36" Plastic Flared End Sections		EA	\$	610.00	\$	-
PVC Sewer Gravity Main ≤ 8"		LF	\$	130.00	\$	-
PVC Sewer Gravity Main > 8"		LF	\$	180.00	\$	-
PVC Sewer Service Pipe and Fittings		LF	\$	120.00	\$	-
PVC Sewer Forcemain Pipe ≤ 3"	280	LF	\$	36.00	\$	10,080.00
PVC Sewer Forcemain Pipe > 3"		LF	\$	61.00	\$	-
Reconstruct / Adjust Sewer Manholes		EA	\$	1,000.00	\$	-
Manhole Covers and Frames (Drainage and Sewer)		EA	\$	1,200.00	\$	-
6" Cement Lined Ductile Iron Water Pipe CL 52		LF	\$	150.00	\$	-
8" Cement Lined Ductile Iron Water Pipe CL 52		LF	\$	180.00	\$	-
12" Cement Lined Ductile Iron Water Pipe CL 52		LF	\$	210.00	\$	-
20" Cement Lined Ductile Iron Water Pipe CL 52		LF	\$	280.00	\$	-
3/4" Copper Water Pipe		LF	\$	65.00	\$	-
1" Copper Water Pipe	36	LF	\$	84.00	\$	3,024.00
2" Copper Water Pipe		LF	\$	120.00	\$	-
3/4" PE Water Pipe	375	LF	\$	45.00	\$	16,875.00
1" PE Water Pipe		LF	\$	81.00	\$	-
2" PE Water Pipe	375	LF	\$	100.00	\$	37,500.00
Curb Stop w/ Box & Rod	6	EA	\$	385.00	\$	2,310.00
6" Gate Valve		EA	\$	2,100.00	\$	-
8" Gate Valve		EA	\$	2,750.00	\$	-
12" Gate Valve		EA	\$	3,800.00	\$	-

1" Water Service Tap & Corporation	2	EA	\$	425.00	\$	850.00
Chlorine Injection Tap		EA	\$	1,400.00	\$	-
Hydrant		EA	\$	6,800.00	\$	-
Subdivision Electrification (Cost from Utility)	1	LS	\$	-	\$	-

Site Stabilization/Stormwater/Landscaping **\$ 186,494.50**

Silt Fence (or equal)	800	LF	\$	4.70	\$	3,760.00
Storm Water Pollution Prevention Plan (SWPPP)		EA	\$	5,400.00	\$	-
Monitor SWPPP		HR	\$	90.00	\$	-
Chain Link/Stockade Fence - 5'		LF	\$	85.00	\$	-
Permanent Dumpster Pad & Enclosure		EA	\$	2,900.00	\$	-
New Trees - Deciduous - General		EA	\$	510.00	\$	-
New Trees - Evergreen Cedar		EA	\$	510.00	\$	-
Shrubs - Large		EA	\$	150.00	\$	-
Shrubs - Small		EA	\$	80.00	\$	-
Rain Garden/Gravel Wetland (Volume of Storage)		CF	\$	15.30	\$	-
Infiltration/Detention Basin (Volume of Storage)	2100	CF	\$	8.30	\$	17,430.00
Subsurface Infiltration Chamber (Volume of Storage)	6000	CF	\$	25.00	\$	150,000.00
Loam and Seed	1611	SY	\$	9.50	\$	15,304.50
Sod		SY	\$	9.40	\$	-
Mulch		CY	\$	80.00	\$	-
Hay Bales - Temporary Erosion Control		LF	\$	22.00	\$	-

Quality Control **\$ 1,488.00**

Physical Testing Laboratory Services	0	AC	\$	3,400.00	\$	-
Officers - 4 hr min	8	HR	\$	98.00	\$	784.00
Flagger	16	HR	\$	44.00	\$	704.00

Project Documentation **\$ 5,000.00**

As-Built Drawing (\$3,000 min)	1	LS	\$	5,000.00	\$	5,000.00
Staking/Monumentation/Record Drawings Prep (\$2,500 Min)	1	LS	\$		\$	-

Site Maintenance **\$ 4,480.00**

Site Clean Up (Removal of Construction Materials/Debris)	0.7	AC	\$	6,400.00	\$	4,480.00
Clean Out Catch Basins (\$400 Min)		EA	\$	80.00	\$	-
Dumpster (10 CY - 4 Ton)		WK	\$	675.00	\$	-

Demolition **\$ -**

Specialized or Site Specific Demolition (\$1,200 Min)	1	LS	\$		\$	-
---	---	----	----	--	----	---

Specialty Requirements per N.O.D. **\$ 16,000.00**

Requirement or Other Cost not Listed Above	1	LS	\$	-	\$	-
E-One grinder pumps	4	EA	\$	4,000.00	\$	16,000.00
	1	LS	\$	-	\$	-
	1	LS	\$	-	\$	-
	1	LS	\$	-	\$	-
	1	LS	\$	-	\$	-

Mobilization/Demobilization **\$ 25,373.59**

Subtotal: \$ 532,845.29

10% Contingency: \$ 53,284.53

Performance Guarantee (10% of total cost including 10% contingency): \$ 58,612.98

Surety = 110% of the Uncompleted Work: \$ 586,129.81

*Sub grade for building foundations. Stone backfill for sewer. Under drain. Roadway

Site Plan Review Application Fee – FY25

Project:

Map/Lot:

Applicant:

All development

Base fee \$600

\$600.00

Plus \$5.00 per \$1,000 of site costs

Site costs

\$532,845

+ \$2,664.23

Plus \$10.00 per 1,000 S.F. of site development area

Site development area

30,200 S.F.

+ \$302.00

Fee \$3,566.23

Maximum fee: \$20,000.00

Fee received by: _____

Date: _____

Note: Initial application fee may be based on the applicant's estimates of site costs and site development area. Following site plan approval, the application fee will be recalculated based on the approved site plan and site engineer's corresponding site cost estimate as approved by the Department of Public Works, and any additional fee shall be paid prior to the issuance of a building permit.

1151 SAGAMORE AVENUE CBC, LLC SITE PLAN REVIEW

1151 SAGAMORE AVENUE, PORTSMOUTH, NEW HAMPSHIRE

PROJECT INFORMATION

CIVIL ENGINEER
HALEY WARD, INC.
ATTN: DREW OLEHOWSKI, PE.
200 GRIFFIN ROAD, UNIT 14
PORTSMOUTH, NEW HAMPSHIRE 03801
T: 603.430.9282

OWNER / APPLICANT
1151 SAGAMORE AVENUE CBC, LLC
76 STATE STREET
NEWBURYPORT, MASSACHUSETTS 01950

SURVEYOR
HALEY WARD, INC.
ATTN: CHARLES ADAMS, LLS, PLS
200 GRIFFIN ROAD, UNIT 14
PORTSMOUTH, NEW HAMPSHIRE 03801
T: 603.430.9282

LANDSCAPE ARCHITECT
TERRA FIRMA LANDSCAPE ARCHITECTURE
ATTN: TERENCE PARKER
163.A COURT STREET
PORTSMOUTH, NEW HAMPSHIRE 03801
T: 603.531.9109


UTILITY PROVIDERS
WATER & SEWER
CITY OF PORTSMOUTH DEPT. OF
PUBLIC WORKS
ATTN: DOUG SPARKS
680 PEVERLY HILL ROAD
PORTSMOUTH, NEW HAMPSHIRE 03801
T: 603.427.1530

ELECTRIC
EVERSOURCE
ATTN: NICHOLAS KOSKO
1700 LAFAYETTE ROAD
PORTSMOUTH, NEW HAMPSHIRE 03801
T: 603.436.7708, EXT. 3327565

CABLE
XFINITY BY COMCAST
ATTN: MIKE COLLINS
180 GREENLEAF AVENUE
PORTSMOUTH, NEW HAMPSHIRE 03801
T: 603.266.2278

COMMUNICATIONS
CONSOLIDATED COMMUNICATIONS
ATTN: BENJAMIN WILLS
1575 GREENLAND ROAD
GREENLAND, NEW HAMPSHIRE 03840
T: 603.427.5525

NATURAL GAS
UNITIL
ATTN: DAVE BEAULIEU
325 WEST ROAD
PORTSMOUTH, NEW HAMPSHIRE 03801
T: 603.294.5144



LOCATION MAP

0 2640 5280 Feet

INDEX OF DRAWINGS

C000	COVER SHEET
C001	GENERAL NOTES, LEGEND & ABBREVIATIONS
V101	EXISTING CONDITIONS
C101	SITE PLAN
C102	UTILITY PLAN
C103	GRADING PLAN
C201	PROPOSED DRIVEWAY PLAN & PROFILE
C202	SITE DISTANCE PLAN & PROFILE
C501	SITE DETAILS
C502	SITE DETAILS
C503	SITE DETAILS
C701	PRE-DEVELOPMENT HYDROLOGY PLAN
C702	POST-DEVELOPMENT HYDROLOGY PLAN
TR-1	TURNING DIAGRAM
TR-2	TURNING DIAGRAM
TR-3	TURNING DIAGRAM
TR-4	TURNING DIAGRAM
EX-1	AVERAGE GRADE PLANE EXHIBIT

PLANS BY TERRA FIRMA LANDSCAPE ARCHITECTURE:

L-1	LANDSCAPE PLAN
L-2	LANDSCAPE DETAILS

PERMITS & APPROVALS

CITY OF PORTSMOUTH - SITE PLAN REVIEW: IN PROGRESS

PLAN REFERENCE

- EXISTING CONDITIONS PLAN FOR BUILD AMERICA, PREPARED FEBRUARY 2025 BY HALEY WARD, INC.
- AS-BUILT SITE PLAN FOR BUILD AMERICA, PREPARED NOVEMBER 2025 BY AMBIT ENGINEERING, INC., A DIVISION OF HALEY WARD, INC.
- SUPPLEMENTAL LIDAR TOPOGRAPHY OBTAINED FROM THE NOAA DIGITAL COAST DATA ACCESS VIEWER.

ISSUED FOR PERMITTING
MARCH 2, 2026



HALEY WARD

www.haleyward.com

CONSTRUCTION SEQUENCE

DO NOT BEGIN CONSTRUCTION UNTIL ALL LOCAL, STATE AND FEDERAL PERMITS HAVE BEEN APPLIED FOR AND RECEIVED.

INSTALL SILT SOXX TO CONTROL EROSION AND SEDIMENTATION PRIOR TO ANY EARTH MOVING ACTIVITIES.

REMOVE EXISTING BUILDINGS AND OTHER SITE FEATURES TO BE REMOVED.

CONSTRUCT STABILIZED CONSTRUCTION ENTRANCE.

CUT AND REMOVE ALL TREES, SHRUBS, SAPLINGS, BRUSH, VINES AND OTHER DEBRIS AND RUBBISH AS REQUIRED.

STRIP AND STOCKPILE LOAM FROM SITE. STOCKPILES SHALL BE SURROUNDED WITH SILT SOXX TO CONTROL SEDIMENT RUN OFF.

ROUGH GRADE SITE AND CONSTRUCT DRAINAGE STRUCTURES, RAIN GARDEN AND SWALES. INSTALL AND MAINTAIN EROSION CONTROL DEVICES AS SHOWN ON THE PLANS. ALL PERMANENT DITCHES, AND SWALES SHALL BE STABILIZED PRIOR TO DIRECTING RUNOFF TO THEM. CONSTRUCT BUILDING FOUNDATIONS.

LOAM AND SEED DISTURBED AREAS IN ACCORDANCE WITH VEGETATIVE PRACTICE AND GENERAL CONSTRUCTION NOTES. CUT AND FILL SLOPES SHALL BE SEEDED IMMEDIATELY AFTER THEIR CONSTRUCTION.

CONSTRUCT UTILITIES, BUILDINGS AND PAVEMENT BASE COURSE.

PLANT LANDSCAPING.

CONSTRUCT PAVEMENT WEARING COURSE.

REMOVE TRAPPED SEDIMENTS FROM COLLECTION DEVICES AS APPROPRIATE, AND THEN REMOVE TEMPORARY EROSION CONTROL MEASURES.

PROJECT DESCRIPTION

THE PROJECT CONSISTS OF FOUR HOUSING UNITS WITH ASSOCIATED PARKING AND UTILITIES.

THE TOTAL AREA TO BE DISTURBED IS APPROXIMATELY 0.695 ACRES.

BASED ON THE USCS WEB SOIL SURVEY THE SOILS ON SITE CONSIST OF CHATFIELD-HOLLIS-CANTON COMPLEX WHICH IS WELL DRAINED SOILS WITH A HYDROLOGIC SOIL GROUP RATING OF B.

THE STORMWATER RUNOFF FROM THE SITE WILL BE DISCHARGED VIA OVERLAND DRAINAGE PATHWAYS WHICH ULTIMATELY FLOW TO THE SAGAMORE CREEK.

GENERAL CONSTRUCTION NOTES

THE EROSION CONTROL PROCEDURES SHALL CONFORM TO SECTION 645 OF THE "STANDARD SPECIFICATION FOR ROAD AND BRIDGE CONSTRUCTION" OF THE NHDOT, AND "STORM WATER MANAGEMENT AND EROSION AND SEDIMENT CONTROL HANDBOOK FOR URBAN AND DEVELOPING AREAS IN NEW HAMPSHIRE". THE PROJECT IS TO BE MANAGED IN A MANNER THAT MEETS THE REQUIREMENTS AND INTENT OF RSA 430:53 AND CHAPTER AGR 3800 RELATIVE TO INVASIVE SPECIES.

DURING CONSTRUCTION AND THEREAFTER, EROSION CONTROL MEASURES ARE TO BE IMPLEMENTED AS NOTED. THE SMALLEST PRACTICAL AREA OF LAND SHOULD BE EXPOSED AT ANY ONE TIME DURING DEVELOPMENT. NO DISTURBED AREA SHALL BE LEFT UNSTABILIZED FOR MORE THAN 45 DAYS.

ANY DISTURBED AREAS WHICH ARE TO BE LEFT TEMPORARILY, AND WHICH WILL BE REGRADED LATER DURING CONSTRUCTION SHALL BE MACHINE HAY MULCHED AND SEEDED WITH RYE GRASS TO PREVENT EROSION.

THE PROJECT IS TO BE MANAGED IN A MANNER THAT MEETS THE REQUIREMENTS AND INTENT OF RSA 430:53 AND CHAPTER AGR 3800 RELATIVE TO INVASIVE SPECIES.

DUST CONTROL: DUST CONTROL MEASURES SHALL INCLUDE BUT ARE NOT LIMITED TO SPRINKLING WATER ON EXPOSED AREAS, COVERING LOADED DUMP TRUCKS LEAVING THE SITE, AND TEMPORARY MULCHING. DUST CONTROL MEASURES SHALL BE UTILIZED SO AS TO PREVENT THE MIGRATION OF DUST FROM THE SITE TO ADJUTING AREAS.

IF TEMPORARY STABILIZATION PRACTICES, SUCH AS TEMPORARY VEGETATION AND MULCHING, DO NOT ADEQUATELY REDUCE DUST GENERATION, APPLICATION OF WATER OR CALCIUM CHLORIDE SHALL BE APPLIED IN ACCORDANCE WITH BEST MANAGEMENT PRACTICES.

SILT/SOXX SHALL BE PERIODICALLY INSPECTED DURING THE LIFE OF THE PROJECT AND AFTER EACH STORM. ALL DAMAGED SILT/SOXX SHALL BE REPAIRED. SEDIMENT DEPOSITS SHALL PERIODICALLY BE REMOVED AND DISPOSED IN A SECURED LOCATION.

ALL FILLS SHALL BE PLACED AND COMPACTED TO REDUCE EROSION, SLIPPAGE, SETTLEMENT, SUBSIDENCE OR OTHER RELATED PROBLEMS.

ALL NON-STRUCTURAL, SITE-FILL SHALL BE PLACED AND COMPACTED TO 90% MODIFIED PROCTOR DENSITY IN LAYERS NOT EXCEEDING 18 INCHES IN THICKNESS UNLESS OTHERWISE NOTED.

FROZEN MATERIAL OR SOFT, MUCKY OR HIGHLY COMPRESSIBLE MATERIAL, TRASH, WOODY DEBRIS, LEAVES, BRUSH OR ANY DELETERIOUS MATTER SHALL NOT BE INCORPORATED INTO FILLS.

FILL MATERIAL SHALL NOT BE PLACED ON FROZEN FOUNDATION SUBGRADE.

DURING CONSTRUCTION AND UNTIL ALL DEVELOPED AREAS ARE FULLY STABILIZED, ALL EROSION CONTROL MEASURES SHALL BE INSPECTED WEEKLY AND AFTER EACH ONE HALF INCH OF RAINFALL.

THE CONTRACTOR SHALL MODIFY OR ADD EROSION CONTROL MEASURES AS NECESSARY TO ACCOMMODATE PROJECT CONSTRUCTION.

ALL ROADWAYS AND PARKING AREAS SHALL BE STABILIZED WITHIN 72 HOURS OF ACHIEVING FINISHED GRADE. ALL CUT AND FILL SLOPES SHALL BE SEEDED/LOAMED WITHIN 72 HOURS OF ACHIEVING FINISHED GRADE.

AN AREA SHALL BE CONSIDERED STABLE IF ONE OF THE FOLLOWING HAS OCCURRED:

- BASE COURSE GRAVELS HAVE BEEN INSTALLED ON AREAS TO BE PAVED
- A MINIMUM OF 85% VEGETATED GROWTH HAS BEEN ESTABLISHED
- A MINIMUM OF 3 INCHES OF NON-EROSIVE MATERIAL SUCH AS STONE OR RIPRAP HAS BEEN INSTALLED
- EROSION CONTROL BLANKETS HAVE BEEN INSTALLED
- IN AREAS TO BE PAVED, "STABLE" MEANS THAT BASE COURSE GRAVELS MEETING THE REQUIREMENTS OF NHDOT STANDARD FOR ROAD AND BRIDGE CONSTRUCTION, ITEM, 2016, ITEM 304.2 HAVE BEEN INSTALLED.

STABILIZATION SHALL BE INITIATED ON ALL LOAM STOCKPILES, AND DISTURBED AREAS, WHERE CONSTRUCTION ACTIVITY SHALL NOT OCCUR FOR MORE THAN TWENTY-ONE (21) CALENDAR DAYS BY THE FOURTEENTH (14TH) DAY AFTER CONSTRUCTION ACTIVITY HAS PERMANENTLY OR TEMPORARILY CEASED IN THAT AREA.

STABILIZATION MEASURES TO BE USED INCLUDE:

- TEMPORARY SEEDING,
- MULCHING.

- 1. ALL AREAS SHALL BE STABILIZED WITHIN 45 DAYS OF INITIAL DISTURBANCE.
2. WHEN CONSTRUCTION ACTIVITY PERMANENTLY OR TEMPORARILY CEASES WITHIN 100 FEET OF NEARBY SURFACE WATERS OR DELINEATED WETLANDS, THE AREA SHALL BE STABILIZED WITHIN SEVEN (7) DAYS OR PRIOR TO A RAIN EVENT. ONCE CONSTRUCTION ACTIVITY CEASES PERMANENTLY IN THESE AREAS, SILT/SOXX, MULCH BERMS, HAY BALE BARRIERS AND ANY EARTHDIKES SHALL BE REMOVED ONCE PERMANENT MEASURES ARE ESTABLISHED.
3. DURING CONSTRUCTION, RUNOFF WILL BE DIVERTED AROUND THE SITE WITH EARTH DIKES, PIPING OR STABILIZED CHANNELS WHERE POSSIBLE. SHEET RUNOFF FROM THE SITE WILL BE FILTERED THROUGH SILT/SOXX, MULCH BERMS, HAY BALE BARRIERS, OR SILT SOCKS. ALL STORM DRAIN BASIN INLETS SHALL BE PROVIDED WITH FLARED END SECTIONS AND TRASH RACKS. THE SITE SHALL BE STABILIZED FOR THE WINTER BY OCTOBER 15.

MAINTENANCE AND PROTECTION

THE SILT/SOXX BARRIER SHALL BE CHECKED AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL.

SILT/SOXX SHALL BE REMOVED ONCE SITE IS STABILIZED, AND DISTURBED AREAS RESULTING FROM SILT/SOXX REMOVAL SHALL BE PERMANENTLY SEEDED.

THE CATCH BASIN INLET BASKET SHALL BE INSPECTED WITHIN 24 HOURS AFTER EACH RAINFALL OR DAILY DURING EXTENDED PERIODS OF PRECIPITATION. REPAIRS SHALL BE MADE IMMEDIATELY, AS NECESSARY, TO PREVENT PARTICLES FROM REACHING THE DRAINAGE SYSTEM AND/OR CAUSING SURFACE FLOODING. SEDIMENT DEPOSITS SHALL BE REMOVED AFTER EACH STORM EVENT, OR MORE OFTEN IF THE FABRIC BECOMES CLOGGED.

WINTER NOTES

ALL PROPOSED VEGETATED AREAS THAT DO NOT EXHIBIT A MINIMUM OF 85% VEGETATED GROWTH BY OCTOBER 15, OR WHICH ARE DISTURBED AFTER OCTOBER 15, SHALL BE STABILIZED BY SEEDING AND INSTALLING EROSION CONTROL BLANKETS ON SLOPES GREATER THAN 3:1, AND SEEDING AND PLACING 3 TO 4 TONS OF MULCH PER ACRE, SECURED WITH ANCHORED NETTING, ELSEWHERE, THE INSTALLATION OF EROSION CONTROL BLANKETS OR MULCH AND NETTING SHALL NOT OCCUR OVER ACCUMULATED SNOW OR ON FROZEN GROUND AND SHALL BE COMPLETED IN ADVANCE OF THAW OR SPRING MELT EVENTS.

ALL DITCHES OR SWALES WHICH DO NOT EXHIBIT A MINIMUM OF 85 PERCENT VEGETATIVE GROWTH BY OCTOBER 15, OR WHICH ARE DISTURBED AFTER OCTOBER 15, SHALL BE STABILIZED TEMPORARILY WITH STONE OR EROSION CONTROL BLANKETS APPROPRIATE FOR THE DESIGN FLOW CONDITIONS;

AFTER OCTOBER 15, INCOMPLETE ROAD OR PARKING SURFACES, WHERE WORK HAS STOPPED FOR THE WINTER SEASON, SHALL BE PROTECTED WITH A MINIMUM OF 3 INCHES OF CRUSHED GRAVEL PER NHDOT ITEM 304.3, OR IF CONSTRUCTION IS TO CONTINUE THROUGH THE WINTER SEASON BE CLEARED OF ANY ACCUMULATED SNOW AFTER EACH STORM EVENT;

STOCKPILES

- 1. LOCATE STOCKPILES A MINIMUM OF 50 FEET AWAY FROM CATCH BASINS, SWALES, AND CULVERTS.
2. ALL STOCKPILES SHOULD BE SURROUNDED WITH TEMPORARY EROSION CONTROL MEASURES PRIOR TO THE ONSET OF PRECIPITATION.
3. PERIMETER BARRIERS SHOULD BE MAINTAINED AT ALL TIMES, AND ADJUSTED AS NEEDED TO ACCOMMODATE THE DELIVERY AND REMOVAL OF MATERIALS FROM THE STOCKPILE. THE INTEGRITY OF THE BARRIER SHOULD BE INSPECTED AT THE END OF EACH WORKING DAY.
4. PROTECT ALL STOCKPILES FROM STORMWATER RUN-OFF USING TEMPORARY EROSION CONTROL MEASURES SUCH AS BERMS, SILT SOCK, OR OTHER APPROVED PRACTICE TO PREVENT MIGRATION OF MATERIAL BEYOND THE IMMEDIATE CONFINES OF THE STOCKPILES.

CONCRETE WASHOUT AREA

THE FOLLOWING ARE THE ONLY NON-STORMWATER DISCHARGES ALLOWED. ALL OTHER NON-STORMWATER DISCHARGES ARE PROHIBITED ON SITE.

- 1. THE CONCRETE DELIVERY TRUCKS SHALL, WHENEVER POSSIBLE, USE WASHOUT FACILITIES AT THEIR OWN PLANT OR DISPATCH FACILITY.
2. IF IT IS NECESSARY, SITE CONTRACTOR SHALL DESIGNATE SPECIFIC WASHOUT AREAS AND DESIGN FACILITIES TO HANDLE ANTICIPATED WASHOUT WATER.
3. CONTRACTOR SHALL LOCATE WASHOUT AREAS AT LEAST 150 FEET AWAY FROM STORM DRAINS, SWALES AND SURFACE WATERS OR DELINEATED WETLANDS;
4. INSPECT WASHOUT FACILITIES DAILY TO DETECT LEAKS OR TEARS AND TO IDENTIFY WHEN MATERIALS NEED TO BE REMOVED.

ALLOWABLE NON-STORMWATER DISCHARGES

- 1. FIRE-FIGHTING ACTIVITIES;
2. FIRE HYDRANT FLUSHING;
3. WATERS USED TO WASH VEHICLES WHERE DETERGENTS ARE NOT USED;
4. WATER USED TO CONTROL DUST;
5. POTABLE WATER INCLUDING UNCONTAMINATED WATER LINE FLUSHING;
6. ROUTINE EXTERNAL BUILDING WASH DOWN WHERE DETERGENTS ARE NOT USED;
7. PAVEMENT WASH WATERS WHERE DETERGENTS ARE NOT USED;
8. UNCONTAMINATED AIR CONDITIONING/COMPRESSOR CONDENSATION;
9. UNCONTAMINATED GROUND WATER OR SPRING WATER;
10. FOUNDATION OR FOOTING DRAINS WHICH ARE UNCONTAMINATED;
11. UNCONTAMINATED EXCAVATION DEWATERING;
12. LANDSCAPE IRRIGATION.

WASTE DISPOSAL

- 1. WASTE MATERIAL
- ALL WASTE MATERIALS SHALL BE COLLECTED AND STORED IN SECURELY LIDDED RECEPTACLES. ALL TRASH AND CONSTRUCTION DEBRIS FROM THE SITE SHALL BE DEPOSITED IN A DUMPSTER.
- NO CONSTRUCTION WASTE MATERIALS SHALL BE BURIED ON SITE.
- ALL PERSONNEL SHALL BE INSTRUCTED REGARDING THE CORRECT PROCEDURE FOR WASTE DISPOSAL BY THE SUPERINTENDENT.
2. HAZARDOUS WASTE
- ALL HAZARDOUS WASTE MATERIALS SHALL BE DISPOSED OF IN THE MANNER SPECIFIED BY LOCAL OR STATE REGULATION OR BY THE MANUFACTURER;
- SITE PERSONNEL SHALL BE INSTRUCTED IN THESE PRACTICES BY THE SUPERINTENDENT.
3. SANITARY WASTE
- ALL SANITARY WASTE SHALL BE COLLECTED FROM THE PORTABLE UNITS A MINIMUM OF ONCE PER WEEK BY A LICENSED SANITARY WASTE MANAGEMENT CONTRACTOR.

BLASTING NOTES

- 1. CONTRACTOR SHALL CONTACT THE NHDES AND/OR LOCAL JURISDICTION PRIOR TO COMMENCING ANY BLASTING ACTIVITIES.
2. FOR ANY PROJECT FOR WHICH BLASTING OF BEDROCK IS ANTICIPATED, THE APPLICANT SHALL SUBMIT A BLASTING PLAN THAT IDENTIFIES:
- WHERE THE BLASTING ACTIVITIES ARE ANTICIPATED TO OCCUR;
- THE ESTIMATED QUANTITY OF BLAST ROCK IN CUBIC YARDS; AND
- SITE-SPECIFIC BLASTING BEST MANAGEMENT PRACTICES.

ABBREVIATIONS

Table with 4 columns: Abbreviation, Full Name, Unit/Measure, and Description. Includes entries for ANSI, BLDG, CL, CB, CLR, CMP, CO, CPE, DI, DIA, E, EL, EFM, EPS, FM, GAL, GALV, GPH, GPM, HDPE, HP, ID, IN, INT, INV, etc.

LEGEND:

ITEMS SHOWN MAY NOT APPEAR ON PLANS

Legend table with columns: DESCRIPTION, EXISTING, PROPOSED. Lists symbols for PROPERTY LINE, BENCHMARK, SURVEY STATION, IRON PIN, DRILL HOLE, BOUND, TEST PIT, SEWER MANHOLE, GAS VALVE, UTILITY POLE, GUY ANCHOR, ELECTRICAL MANHOLE, TRANSFORMER, PULLBOX, WELL, WATER VALVE, WATER SHUTOFF, HYDRANT, AIR RELIEF VALVE, DRAINAGE MANHOLE, CATCH BASIN, CURB INLET, PARKING LIGHT, FLOOD LIGHT, SITE LIGHT, SIGN, TRASH CAN, FLAGPOLE, MONITORING WELL, EDGE OF GRAVEL, EDGE OF PAVEMENT, CURBING, MAJOR FOOT CONTOUR, MINOR FOOT CONTOUR, WATERLINE, STORM DRAIN, UNDER DRAIN, SANITARY SEWER, FORCE MAIN, OVERHEAD UTILITIES, UNDERGROUND UTILITIES, GAS LINE, CHAIN LINK FENCE, GUARDRAIL, SILT FENCE, TREE LINE, GRAVEL SURFACE, PAVED SURFACE, CONCRETE SURFACE, BUILDING FOOTPRINT, WETLANDS, RIPRAP, FILTER SURFACE.

Revision table with columns: REV, DATE, DESCRIPTION, BY, CHK. Shows three revisions from 2026-03-02 to 2026-01-16.

ISSUED FOR PERMITTING

HALEY WARD logo and contact information: 200 Griffin Rd., Unit 14, Portsmouth, New Hampshire 03801, 603.430.9282

PROJECT: 1151 SAGAMORE AVENUE CBC, LLC, 1151 SAGAMORE AVE., PORTSMOUTH, NH

GENERAL NOTES, LEGEND & ABBREVIATIONS

Professional Engineer seal for DREW JOHN OLEHOWSKI, No. 18515, dated 03/02/2026. Includes drawing title C001 and revision number 3.

PARCEL INFORMATION	
MAP - LOT:	224 - 19
LOT AREA (ACRES):	69 ACRES
ZONE OR DISTRICT:	MRO - MIXED RESIDENTIAL OFFICE
EXISTING USE:	SINGLE FAMILY RESIDENTIAL
FLOOD ZONE (PNL 33015C0286F):	N/A
WATER:	PUBLIC
SEWER:	PUBLIC
RECORD OWNER:	1151 SAGAMORE AVENUE CBC, LLC 76 STATE STREET NEWBURYPORT, MASSACHUSETTS 01950


SITE DEVELOPMENT DATA		
	PRE-CONSTRUCTION IMPERVIOUS (SF)	POST-CONSTRUCTION IMPERVIOUS (SF)
MAIN STRUCTURE	789	7124
DECKS, STAIRS, & RAMPS	287	770
WALKWAYS	36	288
PAVEMENT	1575	6649
TOTAL IMPERVIOUS:	2687	14831
LOT COVERAGE:	8.90%	49.12%

DESIGN STANDARDS - PORTSMOUTH MRO		
	REQ'D	PROVIDED
MIN. LOT AREA (SF)	7500	30191
LOT AREA PER DWELLING UNIT (SF)	7500	7548
MINIMUM ROAD FRONTAGE (FT)	100	101.35
MINIMUM SETBACK, FRONT YARD (FT)	5	49
MINIMUM SETBACK, SIDE YARDS (FT)	10	14
MINIMUM SETBACK, REAR YARDS (FT)	15	39
MINIMUM OPEN SPACE	25%	50.88%
MAXIMUM STRUCTURE COVERAGE	40%	24%
MAXIMUM BUILDING HEIGHT (FT)	30 (FLAT ROOF), 40 (SLOPED ROOF)	TO COMPLY
PARKING:	1.3 PER UNIT x 4 = 6	16 (8 DRIVEWAY, 8 GARAGE)

PROJECT INFORMATION	
APPLICANT:	1151 SAGAMORE AVENUE CBC, LLC 76 STATE STREET NEWBURYPORT, MASSACHUSETTS 01950
ENGINEER:	HALEY WARD, INC. ATTN: DREW OLEHOWSKI, PE 200 GRIFFIN ROAD PORTSMOUTH, NEW HAMPSHIRE 03801



LOCATION MAP: USGS QUADRANGLE: KITTERY
MAPTECH® USGS TOPOGRAPHIC SERIES™
©MAPTECH®, INC. 978-933-3000
WWW.MAPTECH.COM/TOPO



- NOTES:**
- VERTICAL DATUM IS NAVD88. BASIS OF VERTICAL DATUM IS REDUNDANT RTN GNSS OBSERVATIONS.
 - TRASH PICKUP TO BE CURBSIDE.

- PLAN REFERENCE:**
- EXISTING CONDITIONS PLAN FOR BUILD AMERICA, PREPARED FEBRUARY 2025 BY HALEY WARD.
 - OFF-SITE TOPOGRAPHIC CONTOURS WERE PROVIDED BY THE CITY OF PORTSMOUTH GIS DEPARTMENT.

REV.	DATE	DESCRIPTION	BY	CHK.
3	2026.03.02	REVISED PER TAC REVIEW COMMENTS	PJM	DJO
2	2026.02.13	REVISED PER TAC REVIEW COMMENTS	PJM	DJO
1	2026.01.16	REVISED PER TAC REVIEW COMMENTS	PJM	DJO


ISSUED FOR PERMITTING



1151 SAGAMORE AVENUE CBC, LLC
1151 SAGAMORE AVE., PORTSMOUTH, NH

PROPOSED SITE PLAN

DATE	2025.12.22	SCALE	1"=20'
DRAWN BY	BLQ/PJM	DESIGNED BY	BLQ/PJM
CHECKED BY	DJO	PROJECT No.	5010314.002
DRAWING No.	C101	REV.	3



- CONDITIONS OF APPROVAL:**
- ALL CONDITIONS ON THIS PLAN SHALL REMAIN IN EFFECT IN PERPETUITY PURSUANT TO THE REQUIREMENTS OF THE SITE PLAN REVIEW REGULATIONS.
 - THIS SITE PLAN SHALL BE RECORDED IN THE ROCKINGHAM COUNTY REGISTRY OF DEEDS.
 - ALL IMPROVEMENTS SHOWN ON THIS SITE PLAN SHALL BE CONSTRUCTED AND MAINTAINED IN ACCORDANCE WITH THE PLAN BY THE PROPERTY OWNER AND ALL FUTURE PROPERTY OWNERS. NO CHANGES SHALL BE MADE TO THIS SITE PLAN WITHOUT THE EXPRESS APPROVAL OF THE PORTSMOUTH PLANNING DIRECTOR.


APPROVED BY THE PORTSMOUTH PLANNING BOARD

CHAIRMAN _____ DATE _____


FILE LOCATION: P:\NEWBURYPORT\BUILD_AMERICA\1151_SAGAMORE_AVE_PORTSMOUTH_PANV25CAD_FLESCAD\10101002\CAD\DWG_2026.03.02_844.dwg

UTILITY NOTES:

- SEE EXISTING CONDITIONS PLAN FOR BENCHMARK INFORMATION.
- COORDINATE ALL UTILITY WORK WITH APPROPRIATE UTILITY.
- SEE GRADING AND DRAINAGE PLAN FOR PROPOSED GRADING AND EROSION CONTROL MEASURES.
- ALL SEWER PIPE SHALL BE PVC SDR 35 UNLESS OTHERWISE STATED.
- ALL WORK WITHIN CITY R.O.W. SHALL BE COORDINATED WITH CITY OF PORTSMOUTH.
- CONTRACTOR SHALL MAINTAIN UTILITY SERVICES TO ABUTTING PROPERTIES THROUGHOUT CONSTRUCTION.
- ANY CONNECTION TO EXISTING WATERMAIN SHALL BE CONSTRUCTED BY THE CITY OF PORTSMOUTH.
- EXISTING UTILITIES TO BE REMOVED SHALL BE CAPPED AT THE MAIN AND MEET THE DEPARTMENT OF PUBLIC WORKS STANDARDS FOR CAPPING OF WATER AND SEWER SERVICES.
- ALL ELECTRICAL MATERIAL WORKMANSHIP SHALL CONFORM TO THE NATIONAL ELECTRIC CODE, LATEST EDITION, AND ALL APPLICABLE STATE AND LOCAL CODES.
- THE EXACT LOCATION OF NEW UTILITY SERVICES AND CONNECTIONS SHALL BE COORDINATED WITH BUILDING DRAWINGS AND UTILITY COMPANIES.
- ADJUST ALL MANHOLES, CATCH BASINS, CURB BOXES, ETC. WITHIN LIMITS OF WORK TO FINISH GRADE.
- ALL UNDERGROUND CONDUITS SHALL HAVE NYLON PULL ROPES TO FACILITATE PULLING CABLES.
- THE CONTRACTOR SHALL OBTAIN, PAY FOR, AND COMPLY WITH ALL REQUIRED PERMITS, ARRANGE FOR ALL INSPECTIONS, AND SUBMIT COPIES OF ACCEPTANCE CERTIFICATED TO THE OWNER PRIOR TO THE COMPLETION OF PROJECT.
- THE CONTRACTOR SHALL PROVIDE AND INSTALL ALL MANHOLES, BOXES, FITTINGS, CONNECTORS, COVER PLATES AND OTHER MISCELLANEOUS ITEMS NOT NECESSARILY DETAILED IN THESE DRAWING TO RENDER INSTALLATION OF UTILITIES COMPLETE AND OPERATIONAL.
- CONTRACTOR SHALL PROVIDE EXCAVATION, BEDDING, BACKFILL AND COMPACTION FOR NATURAL GAS SERVICES.
- A 10-FOOT MINIMUM EDGE TO EDGE HORIZONTAL SEPARATION SHALL BE PROVIDED BETWEEN ALL WATER AND SANITARY SEWER LINES. AN 18-INCH MINIMUM OUTSIDE TO OUTSIDE VERTICAL SEPARATION SHALL BE PROVIDED AT ALL WATER/SANITARY SEWER CROSSINGS WATER ABOVE SEWER.
- SAWCUT AND REMOVE PAVEMENT AND CONSTRUCT PAVEMENT TRENCH PATCH FOR ALL PROPOSED UTILITIES LOCATED IN EXISTING PAVED AREAS.
- GATE VALVES, FITTINGS, ETC. SHALL MEET THE REQUIREMENTS OF THE CITY OF PORTSMOUTH.
- COORDINATE TESTING OF SEWER CONSTRUCTION WITH THE CITY OF PORTSMOUTH.
- ALL SEWER PIPES WITH LESS THAN 6' COVER SHALL BE INSULATED.
- CONTRACTOR SHALL COORDINATE ALL ELECTRIC WORK INCLUDING BUT NOT LIMITED TO: CONDUIT CONSTRUCTION, MANHOLE CONSTRUCTION, UTILITY POLE CONSTRUCTION, OVERHEAD WIRE RELOCATION, AND TRANSFORMER CONSTRUCTION WITH POWER COMPANY.
- SITE LIGHTING SPECIFICATIONS, CONDUIT LAYOUT AND CIRCUITRY FOR PROPOSED SITE LIGHTING AND SIGN ILLUMINATION SHALL BE PROVIDED BY THE PROJECT ELECTRICAL ENGINEER IN COORDINATION WITH THE SITE CIVIL ENGINEER.
- CONTRACTOR SHALL CONSTRUCT ALL UTILITIES AND DRAINS TO WITHIN 10' OF THE FOUNDATION WALLS AND CONNECT THESE TO SERVICE STUBS FROM THE BUILDING.
- FINAL REVIEW OF ALL UTILITIES SHALL BE MADE DURING THE REQUIRED SEWER CONNECTION PERMIT PROCESS IN COORDINATION WITH DEPARTMENT OF PUBLIC WORKS.
- ALL WORK PERFORMED IN THE PUBLIC RIGHT-OF-WAY SHALL BE BUILT TO DEPARTMENT OF PUBLIC WATER WORKS STANDARDS.
- THE CONTRACTOR SHALL NOTIFY DIG SAFE AT 1-888-DIG-SAFE (1-888-344-7233) AT LEAST 72 HOURS PRIOR TO COMMENCING ANY EXCAVATION ON PUBLIC OR PRIVATE PROPERTY WITHIN 100 FEET OF UNDERGROUND UTILITIES. THE EXCAVATOR IS RESPONSIBLE TO MAINTAIN MARKS. DIG SAFE TICKETS EXPIRE IN THIRTY DAYS.
- UNDERGROUND UTILITY LOCATIONS ARE BASED UPON BEST AVAILABLE EVIDENCE AND ARE NOT FIELD VERIFIED. LOCATING AND PROTECTING ANY ABOVEGROUND OR UNDERGROUND UTILITIES IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND/OR THE OWNER. UTILITY CONFLICTS SHOULD BE REPORTED AT ONCE TO THE DESIGN ENGINEER.
- PROVIDE STANDARD LEAK, VALVE AND METER EASEMENT DEED FOR THE PRIVATE WATER SYSTEM TO BE REVIEWED AND APPROVED BY THE CITY OF PORTSMOUTH. PAINT DOMESTIC WATER SHUTOFF BLUE AND FIRE SERVICE SHUTOFF RED.



LOCATION MAP: USGS QUADRANGLE: KITTERY
 MAPTECH® USGS TOPOGRAPHIC SERIES™
 ©MAPTECH®, INC. 978-933-3000
 WWW.MAPTECH.COM/TOPO



NOTES:

- VERTICAL DATUM IS NAVD88. BASIS OF VERTICAL DATUM IS REDUNDANT RTN GNSS OBSERVATIONS.
- TRASH PICKUP TO BE CURBSIDE.

PLAN REFERENCE:

- EXISTING CONDITIONS PLAN FOR BUILD AMERICA, PREPARED FEBRUARY 2025 BY HALEY WARD.
- OFF-SITE TOPOGRAPHIC CONTOURS WERE PROVIDED BY THE CITY OF PORTSMOUTH GIS DEPARTMENT.

REV.	DATE	DESCRIPTION	BY	CHK.
3	2026.03.02	REVISED PER TAC REVIEW COMMENTS	PJM	DJO
2	2026.02.13	REVISED PER TAC REVIEW COMMENTS	PJM	DJO
1	2026.01.16	REVISED PER TAC REVIEW COMMENTS	PJM	DJO


ISSUED FOR PERMITTING

HALEY WARD
 200 Griffin Rd., Unit 14
 Portsmouth, New Hampshire 03801
 603.430.9282
 WWW.HALEYWARD.COM

PROJECT
 1151 SAGAMORE AVENUE CBC, LLC
 1151 SAGAMORE AVE., PORTSMOUTH, NH

UTILITY PLAN


DATE	2025.12.22	SCALE	1"=20'
DRAWN BY	BLQ/PJM	DESIGNED BY	BLQ/PJM
CHECKED BY	DJO	PROJECT No.	5010314.002
DRAWING No.	C102	REV.	3



FILE LOCATION: P:\NH\01014-BUILD_AMERICA\010141151 SAGAMORE AVE. PORTSMOUTH - PAVES\CAD_FILES\CADD\010141151 SAGAMORE AVE. PORTSMOUTH - PAVES\DWG_2026.03.02_844.dwg



LOCATION MAP: USGS QUADRANGLE: KITTERY
 MAPTECH® USGS TOPOGRAPHIC SERIES™
 ©MAPTECH®, INC. 378-933-3000
 WWW.MAPTECH.COM/TOPO



NOTES:

- VERTICAL DATUM IS NAVD88. BASIS OF VERTICAL DATUM IS REDUNDANT RTN GNSS OBSERVATIONS.
- TRASH PICKUP TO BE CURBSIDE.

PLAN REFERENCE:

- EXISTING CONDITIONS PLAN FOR BUILD AMERICA, PREPARED FEBRUARY 2025 BY HALEY WARD
- OFF-SITE TOPOGRAPHIC CONTOURS WERE PROVIDED BY THE CITY OF PORTSMOUTH GIS DEPARTMENT.

REV.	DATE	DESCRIPTION	BY	CHK.
3	2026.03.02	REVISED PER TAC REVIEW COMMENTS	PJM	DJO
2	2026.02.13	REVISED PER TAC REVIEW COMMENTS	PJM	DJO
1	2026.01.16	REVISED PER TAC REVIEW COMMENTS	PJM	DJO


ISSUED FOR PERMITTING

HALEY WARD
 200 Griffin Rd., Unit 14
 Portsmouth, New Hampshire 03801
 603.430.9282
 WWW.HALEYWARD.COM


PROJECT
 1151 SAGAMORE AVENUE CBC, LLC
 1151 SAGAMORE AVE., PORTSMOUTH, NH

TITLE
 GRADING PLAN


DATE	2025.12.22	SCALE	1"=20'
DRAWN BY	BLQ/PJM	DESIGNED BY	BLQ/PJM
CHECKED BY	DJO	PROJECT No.	5010314.002
DRAWING No.	C103	REV.	3




FILE LOCATION: P:\16510314-BUILD_AMERICA\1151_SAGAMORE_AVE., PORTSMOUTH - PLAN\ISSUES\11510314-002-CB-DWG_2026.03.02.dwg, 2026.03.02, 8:44 AM



LOCATION MAP: USGS QUADRANGLE: KITTERY
 MAPTECH® USGS TOPOGRAPHIC SERIES™
 ©MAPTECH®, INC. 978-933-3000
 WWW.MAPTECH.COM/TOPO



PROFILE VIEW OF PROPOSED DRIVEWAY - STA 0+00 TO 2+65
 SCALE: H: 1"=40' / V: 1"=4'



NOTES:

- VERTICAL DATUM IS NAVD88. BASIS OF VERTICAL DATUM IS REDUNDANT RTN GNSS OBSERVATIONS.
- TRASH PICKUP TO BE CURBSIDE.

PLAN REFERENCE:

- EXISTING CONDITIONS PLAN FOR BUILD AMERICA, PREPARED FEBRUARY 2025 BY HALEY WARD.
- OFF-SITE TOPOGRAPHIC CONTOURS WERE PROVIDED BY THE CITY OF PORTSMOUTH GIS DEPARTMENT.

REV.	DATE	DESCRIPTION	BY	CHK.
3	2026.03.02	REVISED PER TAC REVIEW COMMENTS	PJM	DJO
2	2026.02.13	REVISED PER TAC REVIEW COMMENTS	PJM	DJO
1	2026.01.16	REVISED PER TAC REVIEW COMMENTS	PJM	DJO

DRAWING ISSUE STATUS

ISSUED FOR PERMITTING


PROJECT
 1151 SAGAMORE AVENUE CBC, LLC
 1151 SAGAMORE AVE., PORTSMOUTH, NH

TITLE
 PROPOSED DRIVEWAY PLAN & PROFILE

DATE	SCALE	
2025.12.22	1"=20'	
DRAWN BY	DESIGNED BY	CHECKED BY
BLQ/PJM	BLQ/PJM	DJO
PROJECT No.	5010314.002	
DRAWING No.	C201	
		3




FILE LOCATION: P:\NH\01014-BUILD_AMERICA\002\1151_SAGAMORE_AVE_PORTSMOUTH_PAVESCAD_FILES\CADD_FILES\CADD_002\CADD_002.DWG, 2026.03.02, 8:44 AM




- NOTES:**
1. ALL MATERIAL TO MEET FILTREXX SPECIFICATIONS.
 2. FILTREXX SYSTEM SHALL BE INSTALLED BY A CERTIFIED FILTREXX INSTALLER.
 3. THE CONTRACTOR SHALL MAINTAIN THE COMPOST FILTRATION SYSTEM IN A FUNCTIONAL CONDITION AT ALL TIMES. IT WILL BE ROUTINELY INSPECTED AND REPAIRED WHEN REQUIRED.
 4. SILTSOXX DEPICTED IS FOR MINIMUM SLOPES, GREATER SLOPES MAY REQUIRE ADDITIONAL PLACEMENTS.
 5. THE COMPOST FILTER MATERIAL WILL BE DISPERSED ON SITE WHEN NO LONGER REQUIRED, AS DETERMINED BY THE ENGINEER.

FILTREXX SILTSOXX DETAIL
NTS



STORM DRAIN CLEANOUT DETAIL
NTS



LENGTH TABLE

D	L	W	D50
12"	14'	17"	3"
15"	16'	20"	4"
18"	20'	25"	6"
24"	30'	36"	8"


(REFER TO NOTE 1)

- NOTES**
- 1) USE #50 AS NOTED IN TABLE UNLESS SPECIFIED OTHERWISE ON PLANS.
 - 2) UNDERLAY RIP-RAP WITH 6" OF SIZE 67 STONE FILL (N.H.D.O.T. NO. 520.2.2.3) & MIRAFI 700X OR APPROVED EQUAL GEOTEXTILE FABRIC.
 - 3) USE WIDTHS NOTED IN TABLE OR CONFORM TO NATURAL OR PROPOSED SWALE TOPOGRAPHY.

**NHDOT NO. 520.2.2.3
STANDARD STONE SIZE 67**

SIEVE SIZE	PERCENTAGE BY WEIGHT PASSING
1" (25.0mm)	100
3/4" (19.0mm)	90 - 100
3/8" (9.5mm)	20 - 25
No. 4 (4.75mm)	0 - 10
No. 8 (2.36mm)	0 - 5

CULVERT OUTLET PROTECTION
N.T.S.




- MAINTENANCE**
- 1) MUD AND SOIL PARTICLES WILL EVENTUALLY CLOG THE VOIDS IN THE GRAVEL AND THE EFFECTIVENESS OF THE GRAVEL PAD WILL NOT BE SATISFACTORY. WHEN THIS OCCURS, THE PAD SHOULD BE TOP DRESSED WITH NEW STONE. COMPLETE REPLACEMENT OF THE PAD MAY BE NECESSARY WHEN THE PAD BECOMES COMPLETELY CLOGGED.
 - 2) IF WASHING FACILITIES ARE USED, THE SEDIMENT TRAPS SHOULD BE CLEANED OUT AS OFTEN AS NECESSARY TO ASSURE THAT ADEQUATE TRAPPING EFFICIENCY AND STORAGE VOLUME IS AVAILABLE. VEGETATIVE FILTER STRIPS SHOULD BE MAINTAINED TO INSURE A VIGOROUS STAND OF VEGETATION AT ALL TIMES.

CONSTRUCTION SPECIFICATIONS

- 1) STONE FOR A STABILIZED CONSTRUCTION ENTRANCE SHALL BE 1 TO 2 INCH STONE, RECLAIMED STONE, OR RECYCLED CONCRETE EQUIVALENT.
- 2) THE LENGTH OF THE STABILIZED ENTRANCE SHALL NOT BE LESS THAN 50 FEET, EXCEPT FOR A SINGLE RESIDENTIAL LOT WHERE A 30 FOOT MINIMUM LENGTH WOULD APPLY.
- 3) THE THICKNESS OF THE STONE FOR THE STABILIZED ENTRANCE SHALL NOT BE LESS THAN 6 INCHES.
- 4) THE WIDTH OF THE ENTRANCE SHALL NOT BE LESS THAN THE FULL WIDTH OF THE ENTRANCE WHERE INGRESS OR EGRESS OCCURS OR 10 FEET, WHICHEVER IS GREATER.
- 5) GEOTEXTILE FILTER CLOTH SHALL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING THE STONE. FILTER CLOTH IS NOT REQUIRED FOR A SINGLE FAMILY RESIDENCE LOT.
- 6) ALL SURFACE WATER THAT IS FLOWING TO OR DIVERTED TOWARD THE CONSTRUCTION ENTRANCE SHALL BE PIPED BENEATH THE ENTRANCE. IF PIPING IS IMPRACTICAL, A BERM WITH 5:1 SLOPES THAT CAN BE CROSSED BY VEHICLES MAY BE SUBSTITUTED FOR THE PIPE.
- 7) THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, WASHED, OR TRACKED ONTO PUBLIC RIGHT-OF-WAY MUST BE REMOVED PROMPTLY.
- 8) WHEELS SHALL BE CLEANED TO REMOVE MUD PRIOR TO ENTRANCE ONTO PUBLIC RIGHT-OF-WAY, WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH STONE WHICH DRAINS INTO AN APPROVED SEDIMENT TRAPPING DEVICE.

STABILIZED CONSTRUCTION ENTRANCE DETAIL
NTS



EMERGENCY SPILLWAY SECTION

RAIN GARDEN MEDIA

- 1) MULCH/GROWING MEDIUM: GRASS SEED MIX A WITH LOAM
- 2) SOIL FILTER LAYER: USE UNHSC BIORETENTION SOIL SPECIFICATIONS DATED FEBRUARY, 2017. 20% - 30% MULCH BY VOLUME, MIXED THOROUGHLY WITH LOAMY, COARSE SAND (70% - 80% BY VOLUME) MEETING THE FOLLOWING GRADATION:


SIEVE NO.	% BY WEIGHT, PASSING
4	100
10	95
40	10 - 25
200	0 - 5
- 3) 0.75" - 1.5" CRUSHED STONE, WASHED.
- 4) 3/8" PEA GRAVEL

BIORETENTION MAINTENANCE


SOILS: VISUALLY INSPECT AND REPAIR EROSION MONTHLY. USE SMALL STONES TO STABILIZE EROSION ALONG DRAINAGE PATHS. CHECK THE pH ONCE OR TWICE A YEAR. APPLY AN ALKALINE PRODUCT, SUCH AS LIMESTONE, IF NEEDED.

MULCH: REMULCH ANY VOID AREAS BY HAND AS NEEDED. EVERY 6 MONTHS, IN THE SPRING AND FALL, ADD A FRESH MULCH LAYER. ONCE EVERY 2 TO 3 YEARS, IN THE SPRING, REMOVE OLD MULCH LATER BEFORE APPLYING NEW ONE.

PLANTS: IMMEDIATELY AFTER THE COMPLETION OF CELL CONSTRUCTION, WATER GRASS COVERING FOR 14 CONSECUTIVE DAYS UNLESS THERE IS SUFFICIENT NATURAL RAINFALL. ONCE A MONTH (MORE FREQUENTLY IN SUMMER), VISUALLY INSPECT VEGETATION FOR DISEASE OR PEST PROBLEMS. IF TREATMENT IS WARRANTED, USE THE LEAST TOXIC APPROACH. TWICE A YEAR, FROM MARCH 15TH TO APRIL 30TH AND OCTOBER 1ST TO NOVEMBER 30TH, REMOVE AND REPLACE ALL DEAD AND DISEASED VEGETATION CONSIDERED BEYOND TREATMENT. DURING TIMES OF EXTENDED DROUGHT, LOOK FOR PHYSICAL FEATURES OF STRESS (UNREVIVED WILTING, YELLOW, SPOTTED OR BROWN PATCHES ETC.). WATER IN THE EARLY MORNING AS NEEDED. WEED REGULARLY, IF NEEDED.




RAIN GARDEN SECTION




RAIN GARDEN PROFILE

TYPICAL RAIN GARDEN DETAILS
N.T.S.



DETENTION POND OUTLET STRUCTURE DETAIL
NTS



TYPICAL TYPE 'F' CATCH BASIN DETAIL
NTS

REV.	DATE	DESCRIPTION	BY	CHK.
3	2026-03-02	REVISED PER TAC REVIEW COMMENTS	PJM	DJO
2	2026-02-13	REVISED PER TAC REVIEW COMMENTS	PJM	DJO
1	2026-01-16	REVISED PER TAC REVIEW COMMENTS	PJM	DJO

ISSUED FOR PERMITTING





HALEY WARD
200 Griffin Rd., Unit 14
Portsmouth, New Hampshire 03801
603.430.9282

1151 SAGAMORE AVENUE CBC, LLC
1151 SAGAMORE AVE., PORTSMOUTH, NH

SITE DETAILS


STATE OF NEW HAMPSHIRE
DREW JOHN OLEHOWSKI
No. 18515
Professional Engineer

DATE: 2025.12.22 SCALE: NTS
DRAWN BY: BLQ/PJM DESIGNED BY: BLQ/PJM CHECKED BY: DJO
PROJECT No.: 5010314.002
DRAWING No.: **C501** REV: **3**



ROOF OR FOUNDATION DRAIN OUTLET DETAIL


NTS



VERTICAL GRANITE CURB DETAILS


NTS

Typical Gravity Wall Section with Freestanding Hollow Core Coping




This drawing is for reference only. Determination of the suitability and/or manner of use of any details contained in this document is the sole responsibility of the design engineer of record. Final project designs, including all construction details, shall be prepared by a licensed professional engineer using the actual conditions of the proposed site.

DRAWN BY:	NWL	TITLE:	Typical Gravity Wall Detail
APPROVED BY:	JRJ	DATE:	31MAY2018
SHEET:	1 of 1	FILE:	Typical-Gravity-Wall-with-F-HC-Section.dwg




TYPICAL ASPHALT PAVEMENT GRINDING DETAIL

NTS




TYPICAL WATER SERVICE DETAIL

NTS



TYPICAL SEWER / WATER SEPARATION DETAIL

NTS




NOTES

- SEE SHEET "REQUIREMENTS FOR PADMOUNTED TRANSFORMER SLAB DETAILS".
- ALL REINFORCING TO BE #6 BARS.
- 1" PVC CONDUIT SLEEVE FOR GROUND GRID LEADS.
- THE GROUND GRID SHALL BE SUPPLIED AND INSTALLED BY THE CUSTOMER AND IS TO BE BURIED AT LEAST 12" BELOW GRADE. EIGHT FEET OF EXTRA WIRE FOR EACH GROUND GRID LEG SHALL BE LEFT EXPOSED IN THE CABLE COMPARTMENT TO ALLOW FOR THE CONNECTION TO THE TRANSFORMER. THE TWO 8" GROUND RODS MAY BE EITHER GALVANIZED STEEL OR COPPERWELD AND THEY SHALL BE CONNECTED TO THE GRID WITH NEC APPROVED CONNECTORS.

3 PHASE TRANSFORMER PAD DETAIL

NTS



NOTES:

- ALL CONDUIT TO BE U.L. LISTED, SCH. 80 UNDER ALL TRAVEL WAYS, & SCH. 40 FOR THE REMAINDER.
- NORMAL CONDUIT SIZES FOR CMP ARE 3 INCH FOR SINGLE PHASE PRIMARY AND SECONDARY VOLTAGE CABLES, 4 INCH FOR THREE PHASE SECONDARY, AND 5 INCH FOR THREE PHASE PRIMARY.
- ALL WORK TO CONFORM TO THE NATIONAL ELECTRICAL CODE (LATEST REVISION)
- INSTALL A 200# PULL ROPE FOR EACH CONDUIT
- VERIFY ALL CONDUIT SPECIFICATIONS WITH UTILITY COMPANIES PRIOR TO ANY CONSTRUCTION.

TYPICAL UNDERGROUND UTILITY TRENCH DETAIL

NTS

REV.	DATE	DESCRIPTION	BY	CHK.
3	2026.03.02	REVISED PER TAC REVIEW COMMENTS	PJM	DJO
2	2026.02.13	REVISED PER TAC REVIEW COMMENTS	PJM	DJO
1	2026.01.16	REVISED PER TAC REVIEW COMMENTS	PJM	DJO

ISSUED FOR PERMITTING




1151 SAGAMORE AVENUE CBC, LLC
 1151 SAGAMORE AVE., PORTSMOUTH, NH

SITE DETAILS


DATE	2025.12.22	SCALE	NTS
DRAWN BY	BLQ/PJM	DESIGNED BY	BLQ/PJM
CHECKED BY	DJO		
PROJECT No.	5010314.002		
DRAWING No.	C502		
REV.	3		

NOTES:


- SERVICE CONNECTION TO BE 1.5" DIAMETER UNLESS OTHERWISE SHOWN ON THE DRAWINGS.
- EXTEND SERVICE TO CONNECTION AT EDGE OF PROPERTY.



LPS SERVICE CONNECTION DETAIL
NTS




FORCE MAIN TRENCH DETAIL
NTS



TYPICAL BASEMENT WALL BACKFILL & DRAINAGE DETAIL
NTS

**E/ONE
EXTREME
SERIES**

DH071



General Features

The model DH071 grinder pump station is a complete unit that includes: the grinder pump, check valve, HDPE (high density polyethylene) tank, controls, and alarm panel. A single DH071 is a popular choice for one, average single-family home and can also be used for up to two average single-family homes where codes allow and with consent of the factory.

- Rated for flows of 700 gpd (2650 lpd)
- 70 gallons (265 liters) of capacity
- Indoor or outdoor installation
- Standard outdoor heights range from 61 inches to 160 inches

The DH071 has a cable that connects the motor controls to the level controls through watertight penetrations.

Operational Information

Motor
1 hp, 1,725 rpm, high torque, capacitor start, thermally protected, 120/240V, 60 Hz, 1 phase

Inlet Connections
4-inch inlet grommet standard for DWV pipe. Other inlet configurations available from the factory.

Discharge Connections
Pump discharge terminates in 1.25-inch NPT female thread. Can easily be adapted to 1.25-inch PVC pipe or any other material required by local codes.

Discharge
15 gpm at 0 psig (0.95 lps at 0 m)
11 gpm at 40 psig (0.69 lps at 28 m)
7.8 gpm at 80 psig (0.49 lps at 56 m)



Accessories

E/One requires that the Uni-Lateral, E/One's own stainless steel check valve, be installed between the grinder pump station and the street main for added protection against backflow.

Alarm panels are available with a variety of options, from basic monitoring to advanced notice of service requirements.

The Remote Sentry is ideal for installations where the alarm panel may be hidden from view.

NA0050P01 Rev E



3	2026-03-02	REVISED PER TAC REVIEW COMMENTS	PJM	DJO
2	2026-02-13	REVISED PER TAC REVIEW COMMENTS	PJM	DJO
1	2026-01-16	REVISED PER TAC REVIEW COMMENTS	PJM	DJO
REV.	DATE	DESCRIPTION	BY	CHK.

ISSUED FOR PERMITTING

HALEY WARD
WWW.HALEYWARD.COM

200 Griffin Rd., Unit 14
Portsmouth, New Hampshire 03801
603.430.9262

PROJECT
1151 SAGAMORE AVENUE CBC, LLC
1151 SAGAMORE AVE., PORTSMOUTH, NH

TITLE
SITE DETAILS


DATE 2025.12.22 SCALE NTS

DRAWN BY BLQ/PJM DESIGNED BY BLQ/PJM CHECKED BY DJO

PROJECT No. 5010314.002

DRAWING No. **C503** REV. **3**

03/02/2026



PROFILE VIEW OF CROSS SECTION A - STA 0+00 TO 1+20

3	2026-03-02	REVISED PER TAC REVIEW COMMENTS	PJM	DJO
2	2026-02-13	REVISED PER TAC REVIEW COMMENTS	PJM	DJO
1	2026-01-16	REVISED PER TAC REVIEW COMMENTS	PJM	DJO
REV.	DATE	DESCRIPTION	BY	CHK.

DRAWING ISSUE STATUS

ISSUED FOR PERMITTING



HALEY WARD
200 Griffin Rd., Unit 14
Portsmouth, New Hampshire 03801
603.430.9262


PROJECT

1151 SAGAMORE AVENUE CBC, LLC
1151 SAGAMORE AVE., PORTSMOUTH, NH


TITLE

SITE DETAILS

DATE	2025.12.22	SCALE	NTS
DRAWN BY	BLQ/PJM	DESIGNED BY	BLQ/PJM
CHECKED BY	DJO	PROJECT No.	5010314.002
DRAWING No.	C504		REV.
			3




FILE LOCATION: P:\NH\5010314-BUILD_AMERICAS\1151 SAGAMORE AVE., PORTSMOUTH - PAVE\CAD_FILES\CAD_FILES\5010314.002\C504.DWG, 2026.03.02, 8:44 AM



LOCATION MAP: USGS QUADRANGLE: KITTEERY
 MAPTECH® USGS TOPOGRAPHIC SERIES™
 SCALE: 1"=2000'
 ©MAPTECH®, INC. 978-933-3000
 WWW.MAPTECH.COM/TOPO

PRE LEGEND:

	PROPERTY LINE
	WATERSHED BOUNDARY LINE
	WATERSHED DESIGNATION
	TIME OF CONCENTRATION FLOW PATH
	FLOW PATH DESCRIPTION
	SHEET FLOW
	SHALLOW CONCENTRATED FLOW
	CHANNEL FLOW
	PIPE FLOW



REV.	DATE	DESCRIPTION	BY	CHK.
3	2025.03.02	REVISED PER TAC REVIEW COMMENTS	PJM	DJO
2	2025.02.13	REVISED PER TAC REVIEW COMMENTS	PJM	DJO
1	2025.01.16	REVISED PER TAC REVIEW COMMENTS	PJM	DJO

ISSUED FOR PERMITTING

HALEY WARD
 200 Griffin Rd., Unit 14
 Portsmouth, New Hampshire 03801
 603.430.9282
 WWW.HALEYWARD.COM



PROJECT

1151 SAGAMORE AVENUE CBC, LLC
 1151 SAGAMORE AVE., PORTSMOUTH, NH


TITLE

PRE-DEVELOPMENT HYDROLOGY PLAN

DATE	2025.12.22	SCALE	1"=30'
DRAWN BY	BLQ/PJM	DESIGNED BY	BLQ/PJM
CHECKED BY	DJO		
PROJECT No.	5010314.002		
DRAWING No.	C701		REV. 3




FILE LOCATION: P:\NH\5010314-BUILD_AMERICAS\1151 SAGAMORE AVE., PORTSMOUTH - PRE-DEVELOPMENT HYDROLOGY PLAN.dwg, 2025.03.02, 8:44 AM



POST LEGEND:

	PROPERTY LINE
	WATERSHED BOUNDARY LINE
	WATERSHED DESIGNATION
	TIME OF CONCENTRATION FLOW PATH
	FLOW PATH DESCRIPTION
	SHEET FLOW
	SHALLOW CONCENTRATED FLOW
	CHANNEL FLOW
	PIPE FLOW



REV.	DATE	DESCRIPTION	BY	CHK.
3	2025.03.02	REVISED PER TAC REVIEW COMMENTS	PJM	DJO
2	2025.02.13	REVISED PER TAC REVIEW COMMENTS	PJM	DJO
1	2025.01.16	REVISED PER TAC REVIEW COMMENTS	PJM	DJO

ISSUED FOR PERMITTING

200 Griffin Rd., Unit 14
 Portsmouth, New Hampshire 03801
 603.430.7282



PROJECT

1151 SAGAMORE AVENUE CBC, LLC
 1151 SAGAMORE AVE., PORTSMOUTH, NH



TITLE

POST DEVELOPMENT HYDROLOGY PLAN

DATE	2025.12.22	SCALE	1"=30'
DRAWN BY	BLQ/PJM	DESIGNED BY	BLQ/PJM
CHECKED BY	DJO	PROJECT No.	5010314.002
DRAWING No.	C702	REV.	3



FILE LOCATION: P:\NH\5010314-BUILD_AMERICAS\1151 SAGAMORE AVE., PORTSMOUTH - PLAN\SCAD_FILES\SCAD_FILES\SCAD_Plan_2025.03.02.dwg, 2025.03.02, 8:45 AM





E-ONE Combination Unit	
Overall Length	38.250ft
Overall Width	8.333ft
Overall Body Height	11.250ft
Min Body Ground Clearance	1.393ft
Track Width	8.333ft
Lock-to-lock time	6.00s
Max Wheel Angle	45.00°

PROJECT	1151 SAGAMORE AVENUE CBC, LLC 1151 SAGAMORE AVE., PORTSMOUTH NH
TITLE	TURNING EXHIBIT LEFT TURN ENTERING COMPLEX

DWG No.	TR-1
JN	5010314.002
SCALE	1"=20'

BY	PJM
DATE	2025.12.22
REV.	
REV. DATE	





E-ONE Combination Unit	
Overall Length	38.250ft
Overall Width	8.333ft
Overall Body Height	11.250ft
Min Body Ground Clearance	1.393ft
Track Width	8.333ft
Lock-to-lock time	6.00s
Max Wheel Angle	45.00°

PROJECT
1151 SAGAMORE AVENUE CBC, LLC
 1151 SAGAMORE AVE., PORTSMOUTH NH

TITLE
TURNING EXHIBIT
RIGHT TURN ENTERING COMPLEX

DWG No.
TR-2

JN
 5010314.002
 SCALE
 1"=20'


BY
 PJM

DATE
 2025.12.22

REV.

REV. DATE







PROJECT	1151 SAGAMORE AVENUE CBC, LLC 1151 SAGAMORE AVE., PORTSMOUTH NH
TITLE	TURNING EXHIBIT RIGHT TURN EXITING COMPLEX

DWG No.	TR-3
JN	5010314.002
SCALE	1"=20'

BY	PJM
DATE	2025.12.22
REV.	
REV. DATE	





E-ONE Combination Unit	
Overall Length	38.250ft
Overall Width	8.333ft
Overall Body Height	11.250ft
Min Body Ground Clearance	1.393ft
Track Width	8.333ft
Lock-to-lock time	6.00s
Max Wheel Angle	45.00°

PROJECT **1151 SAGAMORE AVENUE CBC, LLC**
1151 SAGAMORE AVE., PORTSMOUTH NH

TITLE **TURNING EXHIBIT**
LEFT TURN EXITING COMPLEX

DWG No. **TR-4**

BY **PJM**

DATE **2025.12.22**

JN **5010314.002**

SCALE **1"=20'**

REV.

REV. DATE



Plant List - Trees and Shrubs

ID	Qty	Botanical Name	Common Name	Scheduled Size	Mature Height	Mature Width	Growth Habit	Tolerances	Requirements
ARB	5	Acer rubrum 'Bowhall'	Bowhall Maple	3" Cal.	40-60'	10-15'	Upright, Broadly Columnar	Urban, Wet Soil	Full, partial sun. Moist, well drained soils.
GTH	1	Gleditsia triacanthos inermis 'Halka'	Halka Honeylocust	2" Cal.	30-40'	30-40'	Rounded	Urban, Salt, Drought, Wind, Heat	Full sun. Moist, well drained soils.
JBD	121	Juniperus communis depressa 'Blueberry Delight'	Blueberry Delight Juniper	2 Gal.	18-24"	4-5"	Spreading	Drought, Deer, Urban, Salt	Full, partial sun. Average, well drained soil.
PGD	3	Picea glauca 'Densata'	Black Hills Spruce	7-8" Ht.	20-30'	15-20'	Pyramidal	Drought, Deer, Wind	Full sun. Moist, well drained soils.
QB	1	Quercus bicolor	Swamp White Oak	3" Cal.	40-60'	40-60'	Broad	Drought, Moist Soil, Urban	Full sun, large space. Medium to wet, acidic soil.
RGL	47	Rhus aromatica 'Grow Low'	Grow Low Sumac	18-24"	18-24"	6-8"	Spreading	Drought, Urban, Salt	Full, partial sun. Dry to average, well drained soil.
TOS	5	Thuja occidentalis 'Smaragd'	American Arborvitae	7-8" Ht.	15-20'	5-6'	Upright, Pyramidal	Urban, Moist Soil	Full, partial sun. Average, well drained soil.
VBM	5	Viburnum dentatum 'Blue Muffin®'	Blue Muffin® Viburnum	3-4" Ht.	6-8"	4-5"	Compact	Deer, Moist Soil, Drought, Salt, Urban	Full, partial sun. Average, well drained soil.

Plant List - Perennials

ID	Qty	Botanical Name	Common Name	Scheduled Size	Mature Height	Mature Width	Growth Habit	Tolerances	Requirements
BAP	14	Baptisia australis	False Indigo	1 Gal.	36"	36"	Bushy	Salt, Drought, Urban	Sun, partial shade. Average soil.
PVS	19	Panicum virgatum 'Shenandoah'	Shenandoah Switch Grass	2 Gal.	36"	30-48"	Clump	Drought, Wet soil, Urban, Salt	Sun, partial shade. Average to moist soil.



Ernst Conservation Seeds
 8884 Mercer Pike
 Meadville, PA 16335
 (800) 873-3321 Fax (814) 336-5191
www.ernstseed.com

Date: November 06, 2025

Rain Garden Grass Mix - ERNMX-180-1

Botanical Name	Common Name
40.30 % <i>Schizachyrium scoparium, Fort Indiantown Gap-PA Ecotype</i>	Little Bluestem, Fort Indiantown Gap-PA Ecotype
20.00 % <i>Elymus virginicus, Madison-NY Ecotype</i>	Virginia Wildrye, Madison-NY Ecotype
17.80 % <i>Carex vulpinoidea, PA Ecotype</i>	Fox Sedge, PA Ecotype
9.00 % <i>Panicum clandestinum, Tioga</i>	Deertongue, Tioga
6.00 % <i>Chasmodon latifolium, WV Ecotype</i>	River Oats, WV Ecotype
5.50 % <i>Panicum rigidulum, PA Ecotype</i>	Redtop Panicgrass, PA F
0.70 % <i>Juncus effusus</i>	Soft Rush
0.70 % <i>Juncus tenuis, PA Ecotype</i>	Path Rush, PA Ecotype

100.00 %
Seeding Rate: 15 lb per acre with a cover crop. For sites that drain within 24 hours of a rain event use one of the following cover crops: Oats (1 Jan to 31 Jul; 30 lbs/acre), Japanese Millet (1 May to 31 Aug; 10 lbs/acre), or grain rye (1 Aug to 31 Dec; 30 lbs/acre).

Grasses & Grass-like Species - Herbaceous Perennial; Stormwater Management

Mix formulations are subject to change without notice depending on the availability of existing and new products. While the formula may change, the guiding philosophy and function of the mix will not.



Ernst Conservation Seeds
 8884 Mercer Pike
 Meadville, PA 16335
 (800) 873-3321 Fax (814) 336-5191
www.ernstseed.com

Date: November 07, 2025



Conservation Shade Mix - ERNMX-129

Botanical Name	Common Name
30.00 % <i>Festuca rubra</i>	Creeping Red Fescue
30.00 % <i>Festuca rubra ssp. commutata</i>	Chewings Fescue
20.00 % <i>Lolium multiflorum</i>	Annual Ryegrass
10.00 % <i>Poa pratensis, 'Baron'</i>	Kentucky Bluegrass, 'Baron'
10.00 % <i>Poa trivialis</i>	Rough Bluegrass

100.00 %
Seeding Rate: 100-200 lb per acre, or 3-5 lb per 1,000 sq ft

Grasses & Grass-like Species - Herbaceous Perennial; Lawn & Turfgrass Sites

While designed for deep-shaded areas, this mix requires at least 2 hours of sunlight daily. The fescues and bluegrasses are shade tolerant and blend very well together. Mix formulations are subject to change without notice depending on the availability of existing and new products. While the formula may change, the guiding philosophy and function of the mix will not.



terra firma
 landscape architecture

165.a Court Street Portsmouth, NH 03801
 603.531.9109 | terence@terrefirmalandscape.com

Build America
 1151 Sagamore Ave.
 Portsmouth, NH



terra firma landscape architecture
 163.a Court Street
 Portsmouth, NH

REV.	DATE	DESCRIPTION
D	3/3/2026	TAC Submission
C	2/11/2026	CIVIL PLAN UPDATES
B	12/19/2025	
A	12/5/2025	Patio, Walkway, and Window Well Adjustments

NO.	DATE	ISSUE NOTE

Project Manager: _____ Drawn By: TC
 Date: November 2025 Reviewed By: TP
 Project ID: 1151 Sagamore

Sheet Title: **Landscape Plan**

Sheet No.: **L-1**

4

3

2


1

D


C

B

A




1
L-5
TREE PLANTING - 2"+ CAL.
SCALE: NTS




3
L-5
SHRUB/GROUND COVER PLANTING DETAIL
SCALE: NTS

NOTE: SHRUBS SHALL BE PLANTED A MINIMUM OF 1" & NO MORE THAN 2" ABOVE FINISH GRADE, DEPENDING UPON SITE CONDITIONS.




4
L-5
B&B SHRUB PLANTING
SCALE: NTS



5
L-5
GROUND COVER SPACING DETAIL
SCALE: NTS

NOTES:
1. PLACE PLANTS IN BED AS SHOWN, SPACING AS SPECIFIED IN PLANT SCHEDULE.
2. GROUND COVER SHALL BE TRIANGULAR SPACED IN ROWS PARALLEL TO STRAIGHT EDGES AND SHALL BE EVENLY SPACED IN ROWS PARALLEL TO CURVE EDGES.



2
L-5
PYRAMIDAL EVERGREEN TREE PLANTING
SCALE: NTS

LANDSCAPE NOTES:

1. THE CONTRACTOR SHALL LOCATE AND VERIFY THE EXISTENCE OF ALL UTILITIES PRIOR TO STARTING WORK.
2. THE CONTRACTOR SHALL SUPPLY ALL PLANT MATERIALS IN QUANTITIES SUFFICIENT TO COMPLETE THE PLANTINGS SHOWN ON THE DRAWINGS.
3. ALL MATERIAL SHALL CONFORM TO THE GUIDELINES ESTABLISHED BY THE CURRENT AMERICAN STANDARD FOR NURSERY STOCK PUBLISHED BY THE AMERICAN ASSOCIATION OF NURSERYMEN.
4. ALL PLANT SUBSTITUTIONS MUST BE APPROVED BY THE LANDSCAPE ARCHITECT.
5. ALL PLANT MATERIALS SHALL BE EXACTLY AS SPECIFIED BY THE LANDSCAPE ARCHITECT. IF PLANT SPECIES CULTIVARS ARE FOUND TO VARY FROM THAT SPECIFIED AT ANY TIME DURING THE GUARANTEE PERIOD, THE LANDSCAPE ARCHITECT RESERVES THE RIGHT TO HAVE THE CONTRACTOR REPLACE THAT PLANT MATERIAL. THE LANDSCAPE ARCHITECT RESERVES THE RIGHT TO REJECT ANY PLANT DELIVERED TO THE SITE FOR AESTHETIC REASONS BEFORE PLANTING. THE LANDSCAPE CONTRACTOR IS RESPONSIBLE FOR THE QUALITY FOR ALL THE PLANTS.
6. PLANTS SHALL BE SUBJECT TO INSPECTION AND APPROVAL AT THE PLACE OF GROWTH, UPON DELIVERY OR AT THE JOB SITE WHILE WORK IS ON-GOING TO CONFORMITY TO SPECIFIED QUALITY, SIZE AND VARIETY.
7. PLANTS FURNISHED IN CONTAINERS SHALL HAVE THE ROOTS WELL ESTABLISHED IN THE SOIL MASS AND SHALL HAVE AT LEAST ONE (1) GROWING SEASON. ROOT-BOUND PLANTS OR INADEQUATELY SIZED CONTAINERS TO SUPPORT THE PLANT MAY BE DEEMED UNACCEPTABLE.
8. NO PLANT SHALL BE PUT IN THE GROUND BEFORE GRADING HAS BEEN FINISHED AND APPROVED BY THE LANDSCAPE ARCHITECT.
9. ALL PLANTS SHALL BE INSTALLED AND DETAILED PER PROJECT SPECIFICATIONS.
10. ALL PLANTS SHALL BE WATERED THOROUGHLY TWICE DURING THE FIRST 24-HOUR PERIOD AFTER PLANTING. ALL PLANTS SHALL BE WATERED WEEKLY, OR MORE OFTEN IF NECESSARY, DURING THE FIRST GROWING SEASON.
11. ALL PLANTS SHALL BE GUARANTEED BY THE CONTRACTOR FOR NOT LESS THAN ONE FULL YEAR FROM THE TIME OF PROVISIONAL ACCEPTANCE. DURING THIS TIME, THE OWNER SHALL MAINTAIN ALL PLANT MATERIALS IN THE ABOVE MANNER. IT IS THE CONTRACTOR'S RESPONSIBILITY TO INSPECT THE PLANTS TO ENSURE PROPER CARE. IF THE CONTRACTOR IS DISSATISFIED WITH THE CARE GIVEN, HE SHALL IMMEDIATELY, AND IN SUFFICIENT TIME TO PERMIT THE CONDITION TO BE RECTIFIED, NOTIFY THE LANDSCAPE ARCHITECT IN WRITING OR OTHERWISE FORFEIT HIS CLAIM. LANDSCAPE CONTRACTOR SHALL PRUNE PLANTINGS OF DEAD LIMBS OR TWIGS DURING THE FIRST YEAR OF GROWTH.
12. FINAL ACCEPTANCE BY THE LANDSCAPE ARCHITECT WILL BE MADE UPON THE CONTRACTOR'S REQUEST AFTER ALL CORRECTIVE WORK HAS BEEN COMPLETED.
13. LANDSCAPE CONTRACTOR SHOULD REPLACE DEAD PLANTINGS IMMEDIATELY UPON OWNER DIRECTION WITHIN THE WARRANTY PERIOD AND AGAIN AT THE END OF THE GUARANTEE PERIOD, THE CONTRACTOR SHALL HAVE REPLACED ANY PLANT MATERIAL THAT IS MISSING, NOT TRUE TO SIZE AS SPECIFIED, THAT HAVE DIED, THAT HAVE LOST THEIR NATURAL SHAPE DUE TO DEAD BRANCHES, EXCESSIVE PRUNING OR INADEQUATE OR IMPROPER CARE, OR THAT ARE, IN THE OPINION OF THE LANDSCAPE ARCHITECT, IN UNHEALTHY OR UNSIGHTLY CONDITION.
14. ALL LANDSCAPE AREAS TO BE GRASS COMMON TO REGION EXCEPT FOR INTERIOR LANDSCAPED ISLANDS OR WHERE OTHER PLANT MATERIAL IS CALLED FOR.
15. ALL TREES AND SHRUBS TO BE PLANTED IN MULCH BEDS WITH DEFINED AND CUT EDGES TO SEPARATE TURF GRASS AREAS.
16. FOR ANY LANDSCAPE AREA SO DESIGNATED TO REMAIN, WHETHER ON OR OFF-SITE, REMOVE WEEDS, ROCKS, CONSTRUCTION ITEMS, ETC., THEN APPLY GRASS SEED OR PINE BARK MULCH AS DEPICTED ON PLANS.
17. LANDSCAPE CONTRACTOR SHALL FEED AND PRUNE EX. TREES, ON OR JUST OFF SITE, THAT HAVE EXPERIENCED ROOT BASE INTRUSION OR DAMAGE DURING CONSTRUCTION IMMEDIATELY AND FOR THE DURATION OF THE WARRANTY PERIOD AT THE DIRECTION OF THE LANDSCAPE ARCHITECT.
18. EXISTING TREES TO REMAIN SHALL BE PROTECTED WITH TEMPORARY SNOW FENCING AT THE EDGE OF THE EX. TREE CANOPY THE CONTRACTOR SHALL NOT STORE VEHICLES OR MATERIALS WITHIN THE LANDSCAPED AREAS. ANY DAMAGE TO EXISTING TREES, SHRUBS OR LAWN SHALL BE REPAIRED BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE OWNER.
19. ALL MULCH AREAS SHALL RECEIVE A 2" LAYER OF SHREDDED PINE BARK MULCH.
20. ALL WORK SHALL BE DONE IN STRICT ACCORDANCE WITH PROJECT SPECIFICATIONS.

PLEASE NOTE: THIS SHEET IS SCALED FOR 22 BY 34 PAPER, DO NOT REDUCE OR ENLARGE.



terra firma
landscape architecture

165.a Court Street Portsmouth, NH 03801
603.531.9109 | terrence@terrafirmalandscape.com

Build America

1151 Sagamore Ave.
Portsmouth, NH

Project Title



terra firma landscape
architecture
163.a Court Street
Portsmouth, NH

Consultant

REV.	DATE	DESCRIPTION
D	3/3/2026	TAC Submission
C	2/11/2026	CIVIL PLAN UPDATES

NO.	DATE	ISSUE NOTE
Project Manager	Drawn By	TC
Date	November 2025	Reviewed By
Project ID	1151 Sagamore	

Sheet Title

Landscape Details

Sheet No.

L-2

4

3

2

1